

FINAL

United States Department of the Interior
National Park Service

National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in National Register Bulletin, *How to Complete the National Register of Historic Places Registration Form*. If any item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional certification comments, entries, and narrative items on continuation sheets if needed (NPS Form 10-900a).

1. Name of Property

historic name Peabody Memorial Tower
other names/site number Singing Tower

2. Location

street & number 400 West 7th Street not for publication
city or town North Manchester vicinity
state Indiana code IN county Wabash code 169 zip code 46962

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended,
I hereby certify that this x nomination ___ request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60.
In my opinion, the property x meets ___ does not meet the National Register Criteria. I recommend that this property be considered significant at the following level(s) of significance:
national ~~statewide~~ x local
[Signature] 5/5/2010
Signature of certifying official Date
Indiana State Historic Preservation Officer
Title State or Federal agency/bureau or Tribal Government

In my opinion, the property ___ meets ___ does not meet the National Register criteria.

Signature of commenting official Date

Title State or Federal agency/bureau or Tribal Government

4. National Park Service Certification

I, hereby, certify that this property is:
___ entered in the National Register ___ determined eligible for the National Register
___ determined not eligible for the National Register ___ removed from the National Register
___ other (explain:)

Signature of the Keeper Date of Action

5. Classification

Ownership of Property
(Check as many boxes as apply)

- private
- public - Local
- public - State
- public - Federal

Category of Property
(Check only one box)

- building(s)
- district
- site
- structure
- object

Number of Resources within Property
(Do not include previously listed resources in the count.)

Contributing	Noncontributing	
0	0	buildings
0	0	district
0	0	site
1	0	structure
0	0	object
1	0	Total

Name of related multiple property listing
(Enter "N/A" if property is not part of a multiple property listing)

N/A

Number of contributing resources previously listed in the National Register

6. Function or Use

Historic Functions

(Enter categories from instructions)

RECREATION AND CULTURE: monument

FUNERARY: burials

Current Functions

(Enter categories from instructions)

RECREATION AND CULTURE: monument

FUNERARY: burials

7. Description

Architectural Classification

(Enter categories from instructions)

LATE 19TH AND 20TH CENTURY REVIVALS:

Tudor Revival

Modern Movement: Art Deco

Materials

(Enter categories from instructions)

foundation: STONE: Granite

walls: BRICK

STONE: Limestone

roof:

other: METAL: Bronze

Narrative Description

(Describe the historic and current physical appearance of the property. Explain contributing and noncontributing resources if necessary. Begin with a **summary paragraph** that briefly describes the general characteristics of the property, such as its location, setting, size, and significant features.)

Summary Paragraph

The Peabody Memorial Tower is an octagonal, brick and limestone carillon set on a cube-shaped limestone base that serves as a mausoleum. The total height of the tower reaches 110 feet. The tower is set in a simple, balanced, circular landscape that rises toward the structure. Symmetrically placed plantings emphasize the rise in topography and form a visual transition from the horizontal setting to the base of the tower. Stylistically, the tower combines a vaguely streamline twentieth century classicism that almost gives its base an Art Deco character with Tudor late medieval features that meld with the classicism successfully to produce a cohesive design. Sculptural details such as the bronze entrance door, relief surrounds and panels, and the sinuous grillwork in the arched openings enhance the tower's Art Deco spirit. The interior of the base that serves as a mausoleum is completely sheathed in white marble with gray veining.

Narrative Description

The tower is centrally located near the entrance to the Peabody Retirement Community campus on the west side of North Maple Street in North Manchester. The two large residential halls and the chapel of the retirement center form a balanced backdrop for the tower as one approaches from Maple Street. The asphalt-paved driveway that surrounds the tower and gives access to retirement center parking is amidst grounds that are spotted with mature trees. Contemporary street lights are widely spaced along the drive. The island on which the tower sits is landscaped with a concrete-paved wide sidewalk, a sidewalk lawn that slopes to the driveway pavement and is intermittently planted with low, ornamental trees, and extended flights of concrete steps that approach the tower from east and west. Ground cover and low shrubs surround the base of the tower while taller, shaped shrubs provide accents flanking the flights of steps.

In plan, the base of the tower is a square whose corners are cut into in a stepped arrangement. This treatment gives each elevation of the base the appearance of being composed of three superimposed wall planes all resting on the dark concrete pad that provides the foundation for the tower. The bottom of each plane is a tall cavetto base. A deep recess visually separates the cavetto from a cushion molding that runs continuously around the entire tower base. Above this cushion molding, smooth limestone blocks rise to the summit of the tower's base.

The west elevation of the tower is the primary one and is distinguished by an entrance into the structure. The primary plane of this elevation is stepped at its summit and frames a narrow panel with a dentil-like design. The entrance, which projects slightly from the primary plane and rises almost to the full height of the base, is defined by two antae with incised reliefs carved almost to their full height. The reliefs are divided in half by a thin vertical moldings that make each half of the relief the mirror image of the other half. The tops of the reliefs are stylized flower with leaf designs that trail down each side of the relief design as straight vines. This treatment almost gives each anta the appearance of being fluted while the flower design recalls the volutes of an Ionic capital. The uncarved, stepped top of each anta thereby reads as an architrave. The bronze door to the tower is centrally located between the antae and beneath a wide panel with "Peabody" incised in un-serifed letters. The antepagment flanking the door is a floral-leaf relief design similar to that on the antae.

The bronze door, designed by Julius C. Loester, is classical in spirit. The main plane of the door is recessed several inches behind a wide frame. Two thirds of that plane is solid while the upper third is grillwork. A draped, classical female figure whose head is in profile and lower body is frontal is set against this ground. The figure's left hand rests against the bronze frame while her right hand pulls back her head covering. Her exaggerated contrapposto pose causes the drapery covering her left leg to fall in straight folds and the shape of her right leg to be revealed. Her head covering also falls in a spiral of folds that help to frame the right leg. The figure's classical facial features reveal no emotion. An inscription in small lettering in the lower right corner of the door reads: "IN MEMORY OF MY MOTHER AND FATHER" above the artist's name.

The secondary plane of the west elevation echoes the primary plane by having the cavetto base and cushion molding but the top of the plane is not stepped. Instead, the top course of limestone is separated from those beneath by a deep recess. Acroteria embellish the corners of this plane and frame the bottom of the tower shaft. The tertiary plane also repeats the cavetto base and the cushion molding, but its summit is stepped as described above.

The north and south elevations of the base repeat the composition of the west elevation but replace the entrance feature with simple rectangular openings on their primary planes that are filled with grillwork. These grills repeat the grill in the upper third of the bronze entrance door.

The east elevation is approached by a series of nine steps with two landings. In general composition, this elevation repeats the arrangement of its counterpart on the west. However, on this elevation the tall cavetto base is broken and a simple louvered bronze door in a molded limestone jamb takes the place of the elaborate entrance feature on the west.

The octagonal tower rises from the base. Limestone panels at the base of each face of the tower assist the transition to the brick shaft. The tower appears to taper slightly. That impression is, in part, the result of the fact that the limestone buttresses at the junction of each face become thinner in stages as the tower rises. Also, the limestone summit of the tower is inset from the shaft. Each face of the shaft is sheathed to roughly two thirds its height in red brick laid in a Flemish bond pattern. Thin quoins projecting from each buttress provide a regular vertical pattern against the brick. The top portion of each face of the tower is comprised of a Tudor arched opening with relief panel beneath and the termination of the buttresses flanking each face. The carving in the panels beneath each Tudor arched opening is "deep relief" in contrast to that on the entrance feature. The subject matter in these panels is birds and foliage. There are four different motifs distributed so that the same design is on opposite faces of the tower. A panel above each Tudor arch contains sunbursts whose rays shine on the arches. The Tudor arched openings are enriched by elaborate bronze screens that depict sinuous sweeping vines emerging from a thicket of fronds. Smaller vines form a counterbalance and all are hung with a Spanish moss-like covering on which small birds perch. The tower is topped off by the inset octagonal limestone cap each face of which is carved in relief. The relief style and general subject matter is the same as that found beneath the arched openings.

The east and west faces of the octagonal shaft have additional ornamental enrichment. The west face of the shaft has a rectangular opening immediately above the base that is surrounded by a limestone frame and topped by a cornice supporting acroteria. A bronze door is recessed deeply within the opening which is wrapped by a low wrought iron railing. At the top of the brick veneered portion of the tower face a narrow window opening framed by limestone is suspended under a curved balconet. A quoined rectangular panel containing a stylized relief of birds is centered above the balconet. The same window-balconet-relief panel motif is found in the corresponding location on the east face of the tower. However, on this face, the opening just above the base is a narrow, unadorned window with a soldier course lintel. Similar unadorned narrow window openings but with limestone sills are located on the southwest face and northwest face at different height locations.

The interior of the base is split into two discrete spaces. The space accessed through the west entrance is the mausoleum with five Peabody family graves. The entire space including floor, walls, and ceiling vault is sheathed in white marble with soft gray veining. The rectangular openings in the north and south elevations of the base admit light into the mausoleum. The ceiling of the space is composed of four triangular planes that form a pyramid. Two columbaria containing the names and dates of the deceased are located against the north wall and two are against the south wall. A fifth burial, also with name and dates, is set against the east wall of the space in the form of a low altar-like table. The second space in the base is entered through the door on the east elevation. This space has a concrete floor, tile brick walls, and a metal staircase that winds to the top of the structure.

8. Statement of Significance

Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield, information important in prehistory or history.

Areas of Significance

(Enter categories from instructions)

Social History

Architecture

Period of Significance

1937-1960

1937

Significant Dates

Significant Person

(Complete only if Criterion B is marked above)

Cultural Affiliation

Architect/Builder

Weatherhogg, Charles R. architect

Criteria Considerations

(Mark "x" in all the boxes that apply)

Property is:

- A Owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years old or achieving significance within the past 50 years.

Period of Significance (justification)

The tower was completed and dedicated in 1937 so that date was used for the architectural period of significance. It has served as a philanthropic landmark in North Manchester to the present day but the social history period of significance was terminated fifty years ago in 1960.

Criteria Considerations (explanation, if necessary)

Statement of Significance Summary Paragraph (provide a summary paragraph that includes level of significance and applicable criteria)

The Peabody Memorial Tower is eligible for the National Register under Criterion A for its social history significance and eligible under Criterion C for its architectural significance. The tower is both a clear symbol of the Peabody family's philanthropic commitment to the community of North Manchester and an outstanding architectural monument. The Peabody Memorial Tower is on the campus of the Estelle Peabody Memorial Home, an early example of a retirement community built by James B. Peabody to honor his late wife. Designed by regionally significant architect, Charles R. Weatherhogg, the tower combines Tudor Revival and Art Deco stylistic features into a successful composition.

Narrative Statement of Significance (provide at least one paragraph for each area of significance)

Brothers Simon (1851-1933) and James B. Peabody (1859-1934) made an early reputation for the Peabody family beginning in the late 1800s when they began providing high quality lumber to northern Indiana. Later, in 1902, James partnered with J. S. Stigglemann and began the Peabody Seating Company, which manufactured school and auditorium furniture as well as wood folding chairs. Peabody bought Stigglemann's shares in the company after about three years in business and at that time the company name changed to the Peabody School Furniture Company and was managed by James and his son, Thomas. After struggling for a few years, business picked up and the Peabody School Furniture Company became known nationally and internationally. Operations for the company continued through the 1980s.

The philanthropic ethic ran throughout the Peabody family. Simon Peabody, James's brother, wintered in Daytona Beach, Florida where he golfed with the likes of John D. Rockefeller. Simon was a major benefactor there, as well as in Columbia City and North Manchester, Indiana. Philanthropic ideals continued to be followed by James and Thomas who used the Peabody School Furniture Company to help the lives of others. For example, donations of school furniture were sent to San Francisco following the earthquake of 1906. Later, in 1931-32 during the Great Depression, Thomas, who took over the management of the company when his father retired, continued running operations on a three-day work week even though there was not demand for the furniture. In order to keep the employees working the furniture was stockpiled in the hopes that one day it could be sold.

When James B. Peabody died in 1934, Thomas made a memorial bequest for his father to all employees of one year or more. Each received \$100 for each year of service up through fifteen years. A similar bequest was made by the president of the company at the time of Thomas's death.

Of course, the main example of the philanthropic efforts of James B. Peabody is the Estelle B. Peabody Memorial Home. When Mrs. Peabody (1865-1928) died, her husband sought ways to commemorate her life and set into motion a process of creating a retirement community, a relatively innovative concept at that time. He acquired the land in 1929 for the elderly care facility and then created the organization to maintain it and its residents in time beyond the Peabody family's significant philanthropy and interests. The Peabody Retirement Community, as it is now called, is a growing, certified human resources institution, nationally recognized in geriatric research and a major investment in the community of North Manchester.

Although the complex we know today is larger in geographical area, the Peabody family bought what had been the old Tri-County or North Manchester fairgrounds and horse racing track which was comprised of six city blocks in northwest North Manchester extending more or less from Sixth to Ninth Streets and from Maple to Washington Streets. This is adjacent to the old Harter Grove, a natural reserve intact throughout the history of the town from 1837 until the present. There was an attempt to improve the grove as Oak Park Addition south of Seventh Street, while north of Seventh the land reverted to private ownership in its natural state. The land had first been owned by Jonas Warvel (1870-1936) a naturalist and civic leader, then by Thomas A. Peabody (1917-1991), Thomas and Mary Makemson (1885-1966), Peabody's only heir. By a bequest of the late Thomas Peabody and then as gift of Mary K. Peabody, much of the grove is preserved by the Town of North Manchester as Warvel Park in memory of Peabody's friend Jonas Warvel.

The Peabody family became stewards of the land and aesthetic ideals which coalesced into a natural setting including the approach to the retirement community and the tree-lined allee along West Seventh Street. While the use of the land has changed with the growth of the retirement community and the evolution of its marketing strategies, the essential intent of

the family and the architect has not been lost. The Peabody Memorial Tower epitomizes the Peabody family's century-long humane impact on the surrounding area and its role in encouraging an ongoing tradition of benevolence by many families, individuals, and corporations.

The philanthropic ethic of the Peabody family was not uncommon among affluent Americans of the time period. The gifting of money to churches, and to the poor through churches, has been around for centuries. However, it was during the early 20th century that people began to use their wealth outside of church to help their communities, to further research, and to solve social problems. Well known philanthropists of the time such as Andrew Carnegie helped fund the construction of over 2500 libraries in his quest to help provide free education in growing communities. John D. Rockefeller, who wanted to "promote the well-being of mankind throughout the world", personally contributed to the construction of the Whiting Community Center for the Indiana community that was headquarters for Standard Oil of Indiana. The Peabody Memorial Tower represents the same ethical mindset benefiting the town of North Manchester.

Philanthropically and architecturally, the Peabody Memorial Tower can be compared to the Bok Singing Tower, 1927-29, in Lake Wales, Florida. The Peabody tower was inspired by the Singing Tower, a 205 foot carillon which was built for Edward W. Bok (1863-1930) as a gift of gratitude to the American people. Edward Bok came to America from the Netherlands as a boy and was a successful entrepreneur and the editor of *Ladies Home Journal*. The Singing Tower, designed by Philadelphia architect, Milton B. Medary (1874-1929), reflects the influence of both the Gothic style and Art Deco design that was popular in the late 1920s and 1930s. The gardens were designed by Frederick Law Olmstead, Jr. (1870-1959) and the entire complex has been designated a National Historic Landmark.

The Peabody Memorial Tower has been a landmark in Wabash County since its construction began in 1936 and remains so today. The editor of the local newspaper, *North Manchester News-Journal*, kept the reading public posted, almost on a week-by-week basis, of construction progress on the tower and the Peabody Home. When the scaffold was erected to the maximum height the tower was to attain, the newspaper observed on August 6, 1936, "for the first time people can get some conception of the distance into the sky that the tower will reach, and general effect it will have on the sky line, if a town the size of North Manchester can rightfully be supposed to have a sky line." Consequently, there is a skyline. The tower has a commanding presence, visible for a couple of miles outside the town, especially at night when it is dramatically lighted. It is a familiar landmark because of its proximity to areas of town where groups of people congregate.

The architect who worked with the Peabody family to design the complex was Charles R. Weatherhogg (1872-1937) of Fort Wayne. He was an English born and trained designer who came to the Chicago Columbian Exposition of 1892, like what he saw, and stayed in this country. Some architectural historians tend to regard Weatherhogg as a Fort Wayne product, although from his firm's inception until his death, he became recognized throughout northern Indiana and possibly beyond. Earlier in his career, Weatherhogg partnered with architect Alfred Grindle to design the Jasper County Courthouse in Rensselaer, Indiana. Weatherhogg's buildings are also found on the campus of Howe Military School. He designed the Columbia Theater in Columbia City, Whitley County which no longer stands.

In Fort Wayne, Weatherhogg was the architect for the Irene Byron Tuberculosis Sanitorium, North Side High School, Central High School (now the Anthis Career Center), Harrison Hill School, Fairfield Manor, and Temple Achduth Vesholom among other commissions.

Weatherhogg also did a number of commissions in North Manchester in addition to the Peabody retirement community. His work includes drawings for the former Central High School, now the site of the North Manchester Public Library which was constructed by the Mary K. Peabody Foundation in 1995. He also designed new facades for Zion Evangelical Lutheran Church (1923), and the former Oppenheim Department Store building (1923). Weatherhogg also was initially involved in the construction of the former Manchester College gymnasium (1926), although those drawings as published were altered to suit the needs of the college. His principal residential commission in North Manchester was the home of Thomas and Mary M. Peabody, a large, three-story Cotswold Tudor mansion of stone and brick at 300 West Seventh Street which was built in 1932-33.

Weatherhogg's skill as an architect is evident in the three remaining original buildings of the Estelle B. Peabody Memorial Home – the so-called South House, the original portion of the Chapel, and the Memorial Tower. The North House, a memorial to James B. Peabody, originally balanced the South House in the symmetrical complex composition but has been replaced by contemporary construction. We tend to take for granted the technologies used in the Memorial Tower, new at the time this six-story building was constructed. As the other buildings of the complex, the 110 foot tower's brickwork is laid in traditional Flemish bond. Modern building methods and materials, demonstrated by the use of

structural steel and concrete as in the other original buildings of the Home, are confirmed by a study of the architect's drawings of the tower dated March 2, 1936.

Another technology that figures in the design of the tower satisfied Thomas Peabody's interest in the transmission of electronic communications following the advent of radio in the 1920s. The tower and the chapel were wired from top to bottom to power floodlights to light the exteriors at night and to service the public address system that was connected not only to the chapel for use on special occasions, but also to the commercial radio stations of northeastern Indiana. The tower still broadcasts prerecorded religious and seasonal music at scheduled times during the day as well as the recorded Westminster chime marking each quarter hour and tolling the daylight hours.

Stylistically, Weatherhogg melded influence from the Tudor Revival popular in the early 20th century with increasingly popular Art Deco design ideas. Many Tudor Revival inspired designs at the time contained features such as half-timbering with stucco infill, chimney pots, and narrow divided light windows in groups. Advancement in veneering techniques permitted the use of brick or stone veneers of the sort used on the Peabody Memorial Tower in projects reflecting a range of budgets. The Art Deco style, popular after 1925, drew its inspiration from a variety of sources including a simplified classicism, African tribal art, as well as Aztec, Mayan, and even Egyptian art. Weatherhogg's skillful meld of these two design influences – the simplified classical, yet almost modern Deco influence in the base and the references to late Tudor medievalism in the shaft – make the tower a recognizable product of the eclectic tastes of the 1930s.

The beautiful bronze door on the west face of the memorial tower, which also reflects the simplified classical side of Art Deco, was designed by Julius C. Loester. Details of Loester's life are meager which may indicate that, at the time he executed the Peabody commission, he was an employee of the Frank Schmool Metal Products Company of Mount Vernon, New York which had the contract for the tower bronze work. The seminal idea for the door may have come from Thomas Peabody himself. In one of Peabody's scrapbooks there is a black and white cartoon from an unpublished, undated source showing a figure who is facing to the viewer's right with right hand raised to the shoulder. The eight bronze grills at the top of the tower were roughly sketched by Weatherhogg in his blueprints. Loester also designed the Wisconsin State Monument at Vicksburg Battlefield in Vicksburg, Mississippi and the Mothers Monument in Mount Vernon, New York.

The Peabody Memorial Tower is an architectural monument of subtlety and sophistication that has served as a local landmark since its completion in 1937 and a notable artifact of the architectural career of Charles R. Weatherhogg. It is also a symbol of the philanthropic largesse of the Peabody family whose gift of the Estelle Peabody Memorial Home to the people of North Manchester fits into the larger culture of philanthropy associated with America's wealthy in the early 20th century. As such, the tower has significance under Criteria A and C and should be listed in the National Register of Historic Places.

Developmental history/additional historic context information (if appropriate)

9. Major Bibliographical References

Bibliography (Cite the books, articles, and other sources used in preparing this form)

Bayer, Patricia. Art Deco Sourcebook. The Wellfleet Press, Secaucus, New Jersey, 1988.

Breihan, John. "Loyola's Collegiate Gothic Architecture". Loyola College in Maryland website:
http://www.loyola.edu/academics/alldepartments/history/Architecture_YOTC/CGA_Intro. accessed March 19, 2009.

Eager, Amy. "The Peabody Family of Wabash and Whitley Counties: "A Tradition of Philanthropy", January 2005.

Fisher, Frances. Mary K. Peabody Foundation, correspondence, January 18, 2007. Mrs. Fisher has provided access on numerous occasions to the Peabody scrapbooks.

Historic Sites Guide. "UF Builds: The Architecture of the University of Florida." website:
<http://www.uflib.ufl.edu/ufarch/collegiate.htm>. accessed March 23, 2009

Kipp, Frances. "A Brief History of the Estelle Peabody Memorial Home, 1931-1981"

Loester, Julius. phone conversation, commercial brochures from Loester studio.

"Mountain Lake Sanctuary and Singing Tower". National Historic Landmark nomination, NHL designation, April 1993.

National Gallery of Art. "Anatomy of an Exhibition: Art Nouveau, 1890-1914". website:
<http://www.nga.gov/feature/nouveau/nouveau.shtm>. accessed March 26, 2009.

North Manchester News-Journal microfilms.

Peabody Retirement Community Annual Report, 2000.

"Singing Tower" newsletter, Summer 1996, special 65th anniversary edition.

Wabash County Interim Report. Indiana Historic Sites & Structures Inventory. Indiana Department of Natural Resources, Division of Historic Preservation and Archaeology.

Charles R. Weatherhogg, blueprints for Peabody Memorial Tower, eight plates, March 2, 1936.

Previous documentation on file (NPS):

- preliminary determination of individual listing (36 CFR 67 has been Requested)
 previously listed in the National Register
 previously determined eligible by the National Register
 designated a National Historic Landmark

Primary location of additional data:

- State Historic Preservation Office
 Other State agency
 Federal agency
 Local government
 University

Peabody Memorial Tower
Name of Property

Wabash County, IN
County and State

recorded by Historic American Buildings Survey #
recorded by Historic American Engineering Record #

Other
Name of repository:

Historic Resources Survey Number (if assigned): 169-469-03006

10. Geographical Data

Acreage of Property Less than 1 acre
(Do not include previously listed resource acreage)

UTM References

(Place additional UTM references on a continuation sheet)

1	16	602550	4539000	3			
	Zone	Easting	Northing		Zone	Easting	Northing
2				4			
	Zone	Easting	Northing		Zone	Easting	Northing

Verbal Boundary Description (describe the boundaries of the property)

The boundary for the Peabody Memorial Tower includes the tower and the stairs leading to the west and east entrances and extends 10 feet beyond the stairs on the west elevation. That point is on the perimeter of a circle drawn around the resource to form the boundary for purposes of this nomination.

Boundary Justification (explain why the boundaries were selected)

The boundary includes the historic setting for the Peabody Memorial Tower and stairs and walks which were part of the architect's original design.

11. Form Prepared By

name/title Catherine R. Wright, Allan D. White
organization Indiana Landmarks date March 27, 2009
street & number 104 W. Market Street telephone 260-563-4534
city or town 104 W. Market Street state IN zip code 46992
e-mail

Additional Documentation

Submit the following items with the completed form:

- **Maps:** A **USGS map** (7.5 or 15 minute series) indicating the property's location.
A **Sketch map** for historic districts and properties having large acreage or numerous resources. Key all photographs to this map.
- **Continuation Sheets**
- **Additional items:** (Check with the SHPO or FPO for any additional items)

Photographs:

Submit clear and descriptive photographs. The size of each image must be 1600x1200 pixels at 300 ppi (pixels per inch) or larger. Key all photographs to the sketch map.

Name of Property: Peabody Memorial Tower

City or Vicinity: North Manchester

County: Wabash

State: Indiana

Photographer: Catherine R. Wright

Date Photographed: March 17, 2009

Description of Photograph(s) and number:

- 1 of 16. Peabody Retirement Community, camera facing southwest
- 2 of 16. Peabody Memorial Tower base, west façade, camera facing east
- 3 of 16. Peabody Memorial Tower base, east elevation, camera facing west
- 4 of 16. Peabody Memorial Tower base, south elevation, camera facing north
- 5 of 16. Peabody Memorial Tower, west façade, camera facing east
- 6 of 16. Peabody Memorial Tower, northwest façade, camera facing southwest
- 7 of 16. Peabody memorial Tower, east elevation, camera facing west
- 8 of 16. Peabody Memorial Tower, southwest elevation camera facing northeast
- 9 of 16. Peabody Memorial Tower, west façade, camera facing east
- 10 of 16. Peabody Memorial Tower, west façade tower detail, camera facing east

Peabody Memorial Tower
Name of Property

Wabash County, IN
County and State

13 of 16. Peabody Memorial Tower, mausoleum interior, camera facing northeast

14 of 16. Peabody Memorial Tower, mausoleum interior, camera facing southeast

15 of 16. Peabody Memorial Tower, mausoleum interior, camera facing east

16 of 16. Peabody Memorial Tower, east side interior wall detail, camera facing east

Property Owner:

(complete this item at the request of the SHPO or FPO)

name Peabody Retirement Community

street & number 400 West 7th Street

telephone 260-982-8616

city or town North Manchester

state IN

zip code 46962

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C.460 et seq.).

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Office of Planning and Performance Management, U.S. Dept. of the Interior, 1849 C. Street, NW, Washington, DC.


Peabody Memorial Tower, Wabash County, Indiana

Site & Photo Map

Not to Scale

0006, 0011

0001



0005, 0009, 0010

0007

0012

0004




0008

KEY

0000 = Photo number(s) and approximate camera location and direction

○ = Boundary Line




TEABODY MEMORIAL
TOWER
16 603650 4539000

(SERVIA)
3866 I NN

ROAD CLASSIFICATION

- Heavy-duty Light-duty
- Medium-duty Unimproved dirt
- State Route



- 10 FEET
2F 1929



QUADRANGLE LOCATION

NORTH MANCHESTER NORTH, IND.
41085-A7-TF-024

MAP ACCURACY STANDARDS
FLORADO 80225, OR RESTON, VIRGINIA 22092
SURCES, INDIANAPOLIS, INDIANA 46204
SYMBOLS IS AVAILABLE ON REQUEST

1962
MINOR REVISION 1994
DMA 3866 III SE - SERIES Y851

00
R. 6 E. URBANA 7 MI. 47°30' R. 7 E.
R. 6 E. WABASH 15 MI. 41°00'
AKRON 15 MI. 85°45'
DISKO 11 MI. 905
LUTHER 11 MI. 23 MI. TO U.S. 24
4541
4540000m-N.
905 | 85°45'