

**ADDENDUM NO. 1
TO
CONSTRUCTION DOCUMENTS**

FOR PROJECT NO. **E030283**

DESCRIPTION: **Electrical Pedestal Improvements**

LOCATION: **Potato Creek State Park**

FOR AGENCY: **Department of Natural Resources**

The information contained in this Addendum shall become a part of the basic plans and specifications the same as if originally incorporated therein. The original plans and specifications shall remain in their entirety, except as modified by this Addendum. The items herein shall supersede information in the specifications and on the plans.

ITEM #1: Specifications: SECTION 01010 GENERAL REQUIREMENTS

PART 1 – GENERAL

1.01 DESCRIPTION: Paragraph A:

Revise Subparagraph 1 to read as follows: “**The installation of new underground primary conductors, (1) new pad mount transformer with CT’s and meter socket installed, (1) new 4” dia. drop pipe at the existing CT cabinet with additional service conductor,** the installation of new underground secondary copper conductors (2) new distribution panels with breakers, and new 50 amp campsite power pedestals for (57) sites with (2) spares.”

Also please note: The notice to bidders indicated a quantity of 42 sites. The correct quantity of sites is 57.”

Remove subparagraph 1 that previously read as follows: “1. The installation of new underground copper conductors, (2) new transformers, (2) new distribution panels with breakers, and new 50 amp campsite power pedestals for (57) sites with (2) spares.”

ITEM #2: Specifications: SECTION 01010 GENERAL REQUIREMENTS

PART 1 -- GENERAL

1.03 COMMENCEMENT AND COMPLETION OF WORK:

Revise Paragraph “A” to read as follows:

- A. **The contractor shall commence work**, after the date of the execution of the Contract, **within one week after Halloween weekend; October 30, 31, and November1, 2015**. Construction dangers and work on weekends will not be allowed.

Remove paragraph “A” that read as follows:

- A. The Contractor shall commence work within 30 days after the date of the execution of the Contract not withstanding that work or interruption of the campground service as it now stands shall be coordinated with the Site Manager during the period between Memorial Day and Labor Day. Construction dangers and work on holidays and weekends will not be allowed.

ITEM #3: Specifications: SECTION 01020 ALLOWANCES:

PART 1 – GENERAL

1.01 REMEDIATION ALLOWANCE

Revise Paragraph A. to read as follows:

- A. Contractor shall include an allowance of **\$2000.00** in the Base Bid for remediation of unforeseen constraints.

1.02 PRIMARY POWER ALLOWANCE:

Revise Paragraph A to read as follows:

- A. Contractor shall include an allowance of **\$15,000.00** in the Base Bid for providing primary underground electrical service to a new transformer at the location of new Panel “B” under this contract. This allowance includes providing and installing a new 167kva transformer with provision for CT metering by the utility at the location of new Panel “B”.

Revise Paragraph B to read as follows:

- B. Indiana Michigan Power will furnish all labor, materials and equipment to complete the following utility work:
1. Purchasing and installing new 7200/120-240 volt oil cooled pad-mounted transformer **with CT metering and meter socket** for Panel “B”.
 2. **Providing** and installing **primary** cable in conduit to new transformer to be installed at Panel “B”. All primary cable will be buried a minimum of 48” below finished grade.
 3. Terminating all cables at new transformer.
 4. **Installing new service conductor to CT cabinet at existing transformer.**

Revise Paragraph C to read as follows:

- C. The contractor will be responsible for the following:
1. **Installing 4”dia. conduit for the service conductor to the existing CT cabinet.**

ITEM #4 Plans: SHEET # E-4:

Revise the “New “B” Schematic” as follows:

Remove the requirement for providing “Meter base” and “New CT Cabinet”.

Note: The utility will provide pad-mounted transformer cabinet containing CT metering and meter base at new transformer. The new [(4) 350kcmil] 1200 amp conductors will be required between the transformers and the new 1200 amp distribution panels.

END OF ADDENDUM

State Form 21208R4

DAPW-118