

DATE: 10/28/2020

ADDENDUM NO. 1
TO
CONSTRUCTION DOCUMENTS
FOR PROJECT NO. E008302

DESCRIPTION: **AML SITE 2084, FIREPIT #2**

LOCATION: **PIKE COUNTY, INDIANA**

FOR AGENCY: **DEPARTMENT OF NATURAL RESOURCES**

The information contained in this Addendum shall become a part of the basic plans and specifications the same as if originally incorporated therein. The original plans and specifications shall remain in their entirety, except as modified by this addendum. The items herein shall supersede information in the specifications and on the plans.

ITEM NO. 1: Sheet 8 of the Plans indicates the guardrail is to be removed and reset. The guardrail is not to be reset, but rather shall be removed and stockpiled.

ITEM NO. 2: Replace “130 LFT” in note for Ditch Line S on Sheet 3 with “976 LFT”.

ITEM NO. 3: Add note for outlet protection of the farthest south final pond to read “Pond A outlet protection, 32 TONS of revetment riprap on 42 SYS of geotextile”.

ITEM NO. 4: Add note for outlet protection of the middle final pond to read “Pond B outlet protection, 105 TONS of revetment riprap on 140 SYS of geotextile”.

ITEM NO. 5: Replace the note that reads “Riprap, Class I” in Detail 8 on sheet 8 with “Riprap, Class II”.

END OF ADDENDUM