

CALL ORDER : 241

CONTRACT ID : R -24947-B

LETTING DATE : 10/17/00 10:00 AM

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION, SIGNS		
1	105-01925 FIELD OFFICE, 51.1 m2	26.000	MOS
2	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
5	202-01405 CONTAMINATED SOIL, REMOVE AND DISPOSE	1,170.000	m3
6	202-02240 PAVEMENT, REMOVE	1,171.300	m2
7	202-02241 GUARDRAIL, REMOVE	123.000	m
8	202-02278 CURB, CONCRETE, REMOVE	338.000	m
9	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
11	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
12	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
13	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
14	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, UNDER 11400	1.000	EACH
19	202-05825 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, OVER 22800	1.000	EACH
20	202-52710 SIDEWALK, CONCRETE, REMOVE	3,821.000	m2
21	202-60820 SURFACE MILLING, ASPHALT	379.000	m2
22	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
23	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
24	203-02000 EXCAVATION, COMMON	38,370.000	m3
25	203-04523 DEWATERING	LUMP	LUMP
26	205-02224 TEMPORARY EROSION AND SEDIMENT CONTROL, PERIMETER PROTECTION	1,228.000	m
27	205-02229 TEMPORARY EROSION AND SEDIMENT CONTROL, STRAW BALE DITCH	77.000	m
28	205-02231 TEMPORARY EROSION AND SEDIMENT CONTROL, RIPRAP DITCH CHECK	35.000	m
29	205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE	15.000	EACH
30	205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	138.000	EACH
31	210-05839 TEMPORARY	LUMP	LUMP
32	210-05873 TESTING	LUMP	LUMP
33	211-02060 B BORROW FOR STRUCTURE BACKFILL	5,305.000	m3
34	303-52308 COMPACTED AGGREGATE FOR BASE, 0, 53	3,709.000	Mg
35	305-05204 HMA FOR PATCHING	455.000	Mg
36	401-05437 QC/QA HMA BASE 25.0 mm, MAINLINE	19,961.000	Mg
37	401-05455 QC/QA HMA INTERMEDIATE 19.0 mm, MAINLINE	8,986.000	Mg
38	401-05456 QC/QA HMA SURFACE 9.5 mm, MAINLINE	3,364.000	Mg
39	402-05470 HMA BASE C25.0 mm, MAINLINE	14,534.000	Mg
40	405-05517 ASPHALT FOR PRIME COAT	80.000	Mg
41	406-05520 ASPHALT FOR TACK COAT	53.700	Mg
42	601-01867 GUARDRAIL TRANSITION, TGB RETROFIT	2.000	EACH
43	601-06037 GUARDRAIL END TREATMENT, I	2.000	EACH
44	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	15.200	m
45	603-02736 FENCE, WOOD, REMOVE AND RESET	43.600	m
46	603-06040 FENCE, FARM FIELD, 1190 mm	545.300	m
47	603-06065 FENCE, CHAIN LINK, RESET	22.000	m

SCHEDULE OF PAY ITEMS

CALL ORDER : 241
 LETTING DATE : 10/17/00 10:00 AM

CONTRACT ID : R -24947-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION, SIGNS			
48	603-96042 FENCE GATE, FARM FIELD, 1190 mm X 7.3 m	2.000	EACH
49	604-06069 CURB RAMP, CONCRETE	994.000	m2
50	604-44251 STEPS, CONCRETE	5.200	m3
51	604-91531 SIDEWALK, CONCRETE, 100 mm	5,838.000	m2
52	605-06120 CURB, CONCRETE	81.000	m
53	605-06150 CURB AND GUTTER, C, CONCRETE	3,553.000	m
54	605-97937 CURB AND GUTTER, CONCRETE, ROLL	16.000	m
55	610-05527 HMA FOR APPROACHES	2,631.000	Mg
56	611-05330 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 150 mm	6,403.000	m2
57	615-06490 RIGHT OF WAY MARKER	157.000	EACH
58	615-06505 MONUMENT, B	4.000	EACH
59	616-02320 GEOTEXTILES	28.000	m2
60	616-06405 RIPRAP, REVETMENT	17.000	Mg
61	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
62	621-06545 FERTILIZER	3.000	Mg
63	621-06553 SEED MIXTURE, R	477.000	kg
64	621-06565 MULCHING MATERIAL	12.000	Mg
65	621-06567 WATER	393.000	kL
66	621-06574 SODDING	19,626.000	m2
67	714-93584 RETAINING WALL, STONE	3.000	m
68	715-02902 GATE VALVE, 25 mm	1.000	EACH
69	715-04857 SAFETY METAL END SECTION,	1.000	EACH
70	715-05028 PIPE, TYPE 2, CIRCULAR, 300 mm	1,748.000	m
71	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	5,029.000	m
72	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	71.000	m
73	715-05146 PIPE, TYPE 2, CIRCULAR, 150 mm	2.000	m
74	715-05148 PIPE, TYPE 2, CIRCULAR, 250 mm	1.000	m
75	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	495.000	m
76	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	727.000	m
77	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	280.000	m
78	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	808.000	m
79	715-05155 PIPE, TYPE 2, CIRCULAR, 675 mm	353.000	m
80	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	14.500	m
81	715-05325 PIPE, TYPE 2, DEFORMED, MIN. AREA 0.10 m2	43.500	m
82	715-05361 PIPE, TYPE 3, DEFORMED, MIN. AREA 0.10 m2	229.000	m
83	715-44240 CONCRETE, A, STRUCTURES	1.300	m3
84	715-46020 PIPE END SECTION, 600 mm	1.000	EACH
85	715-46045 PIPE END SECTION, MIN. AREA .11 m2	33.000	EACH
86	715-92037 PIPE, PVC, 100 mm	3.000	m
87	715-92525 WATER MAIN, 250 mm	22.000	m
88	715-93911 WATER MAIN, 100 mm	364.000	m
89	715-93912 WATER MAIN, 150 mm	523.000	m
90	715-93913 WATER MAIN, 200 mm	30.000	m
91	716-06472 BORING	15.240	m
92	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	5,000.000	m
93	718-52610 AGGREGATE FOR UNDERDRAINS	1,174.000	m3
94	718-99153 GEOTEXTILES FOR UNDERDRAIN	12,243.000	m2

SCHEDULE OF PAY ITEMS

CALL ORDER : 241
 LETTING DATE : 10/17/00 10:00 AM

CONTRACT ID : R -24947-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION, SIGNS			
95	720-45015 INLET, A8	19.000	EACH
96	720-45065 INLET, N12	1.000	EACH
97	720-45215 CATCH BASIN, A8	6.000	EACH
98	720-45235 CATCH BASIN, E7	3.000	EACH
99	720-45250 CATCH BASIN, K10	36.000	EACH
100	720-45265 PIPE CATCH BASIN, 375 mm	3.000	EACH
101	720-45410 MANHOLE, C4	53.000	EACH
102	720-45415 MANHOLE, D4	9.000	EACH
103	720-45416 MANHOLE, E4	1.000	EACH
104	720-45510 MANHOLE, C4, MODIFIED	2.000	EACH
105	720-90984 MANHOLE, C2	2.000	EACH
106	720-98174 INLET, B15	4.000	EACH
107	720-99416 CATCH BASIN, B15	37.000	EACH
108	720-99417 CATCH BASIN, C15	12.000	EACH
109	730-03475 SAFETY METAL END SECTION, 4:1, 375 mm	2.000	EACH
110	732-03063 TAPPING SLEEVE	2.000	EACH
111	732-03063 TAPPING SLEEVE	5.000	EACH
112	732-03063 TAPPING SLEEVE	2.000	EACH
113	732-03063 TAPPING SLEEVE	2.000	EACH
114	732-03063 TAPPING SLEEVE	2.000	EACH
115	732-03073 CROSS	6.000	EACH
116	732-03942 HYDRANT	8.000	EACH
117	732-03942 HYDRANT	3.000	EACH
118	732-04749 CASING	15.240	m
119	732-04836 GATE VALVE	4.000	EACH
120	732-04836 GATE VALVE	2.000	EACH
121	732-04836 GATE VALVE	1.000	EACH
122	732-04836 GATE VALVE	1.000	EACH
123	732-04836 GATE VALVE	11.000	EACH
124	732-04837 PLUG	4.000	EACH
125	732-04964 WATER MAIN	1,488.000	m
126	732-94780 WATER SERVICE CONNECTION	80.000	EACH
127	732-94780 WATER SERVICE CONNECTION	8.000	EACH
128	801-04308 ROAD CLOSURE SIGN ASSEMBLY	17.000	EACH
129	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	6,486.000	m
130	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	6,076.000	m
131	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 600 mm	26.000	m
132	801-06605 BARRICADE, I I I A	89.000	EACH
133	801-06625 DETOUR ROUTE MARKER ASSEMBLY	19.000	EACH
134	801-06640 CONSTRUCTION SIGN, A	130.000	EACH
135	801-06645 CONSTRUCTION SIGN, B	65.000	EACH
136	801-06710 FLASHING ARROW SIGN	1,000.000	DAY
137	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
138	802-02489 SIGN POST, SQUARE, REINFORCED ANCHOR BASE	335.400	m
139	802-02922 SIGN POST, SQUARE, UNREINFORCED ANCHOR BASE	66.000	m
140	802-04893 REFERENCE POST	2.000	EACH
141	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	36.500	m2

SCHEDULE OF PAY ITEMS

PAGE 4

CALL ORDER : 241

CONTRACT ID : R -24947-B

LETTING DATE : 10/17/00 10:00 AM

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION, SIGNS			
142	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	40.500	m2
143	802-93494 POST, ROUND, GALVANIZED	124.700	m
144	805-01816 SIGNAL SUPPORT FOUNDATION, 900 mm X 900 mm X 2500 mm	12.000	EACH
145	805-01842 HANDHOLE, SIGNAL	16.000	EACH
146	805-01844 CONDUIT, STEEL, GALVANIZED, 50 mm, UNDERGROUND	651.000	m
147	805-02069 SIGNAL CANTILEVER STRUCTURE, 7.6 m	2.000	EACH
148	805-02072 SIGNAL CANTILEVER STRUCTURE, 9.1 m ARM	6.000	EACH
149	805-02073 SIGNAL CANTILEVER STRUCTURE, 10.7 m ARM	2.000	EACH
150	805-02077 SIGNAL CANTILEVER STRUCTURE, 12.2 m ARM	2.000	EACH
151	805-02595 CONTROLLER, RESET TIMING	10.000	EACH
152	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
153	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000	EACH
154	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
155	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	24.000	EACH
156	805-78370 PEDESTRIAN PUSH BUTTON	12.000	EACH
157	805-78445 SIGNAL SERVICE	3.000	EACH
158	805-78452 SIGNAL CONDUIT RISER, 25 mm	3.000	EACH
159	805-78467 SIGNAL CABLE, 3C 8GA.	105.000	m
160	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,452.000	m
161	805-78480 SIGNAL CABLE, 3C 14GA.	526.000	m
162	805-78485 SIGNAL CABLE, 5C 14GA.	363.000	m
163	805-78490 SIGNAL CABLE, 7C 14GA.	1,139.000	m
164	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	942.000	m
165	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
166	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	490.000	m
167	805-78925 CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
168	805-90510 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 230 mm	24.000	EACH
169	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	5.000	EACH
170	805-94295 SIGNAL HEAD, RELOCATE	49.000	EACH
171	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	1,126.900	m
172	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	245.200	m
173	808-06716 LINE, REMOVE	210.000	m
174	808-75008 LINE, PAINT, SOLID, WHITE, 200 mm	482.300	m
175	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	5,117.000	m
176	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	51.000	m
177	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600mm	270.000	m
178	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150mm	963.000	m
179	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	7.000	EACH
180	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH
181	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	234.000	EACH
182	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	556.000	m

SCHEDULE OF PAY ITEMS

CALL ORDER : 247
 LETTING DATE : 10/17/00 10:00 AM

CONTRACT ID : R -25028-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PEDESTRIAN / BIKE FACILITIES			
1	105-06790 FIELD OFFICE, 27.9 m2	6.000	MOS
2	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
5	202-60820 SURFACE MILLING, ASPHALT	22.000	m2
6	203-02000 EXCAVATION, COMMON	1,331.000	m3
7	203-02070 BORROW	518.200	m3
8	205-02224 TEMPORARY EROSION AND SEDIMENT CONTROL, PERIMETER PROTECTION	7,182.000	m
9	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	4.000	EACH
10	205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	4.000	EACH
11	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	24.000	m3
12	210-05584 LINER	181.400	m2
13	211-02060 B BORROW FOR STRUCTURE BACKFILL	423.700	m3
14	303-04075 COMPACTED AGGREGATE FOR SURFACE, 0, 73	10.000	Mg
15	303-52308 COMPACTED AGGREGATE FOR BASE, 0, 53	13,990.000	Mg
16	303-94433 AGGREGATE, 12	330.000	m3
17	402-05468 HMA BASE 25.0 mm, MAINLINE	1,943.400	Mg
18	402-05474 HMA INTERMEDIATE 19.0 mm, MAINLINE	613.000	Mg
19	402-05477 HMA SURFACE 9.5 mm, MAINLINE	1,093.000	Mg
20	405-05517 ASPHALT FOR PRIME COAT	18.940	Mg
21	406-05520 ASPHALT FOR TACK COAT	4.600	Mg
22	601-95344 HANDRAIL, PEDESTRIAN	198.000	m
23	601-95344 HANDRAIL, PEDESTRIAN	177.000	m
24	602-97768 PARKING BARRIER, RESET	60.000	EACH
25	603-04244 GATE	1.000	EACH
26	604-06069 CURB RAMP, CONCRETE	189.000	m2
27	604-91531 SIDEWALK, CONCRETE, 100 mm	2,972.000	m2
28	605-06120 CURB, CONCRETE	828.500	m
29	605-06150 CURB AND GUTTER, C, CONCRETE	118.600	m
30	611-95023 MAILBOX ASSEMBLY, RESET	3.000	EACH
31	615-02153 TIMBER BOLLARDS	7.000	EACH
32	615-06496 PARKING BARRIER	62.000	EACH
33	616-02320 GEOTEXTILES	187.000	m2
34	616-06405 RIPRAP, REVETMENT	131.000	Mg
35	621-06559 MULCHED SEEDING, R	21,936.000	m2
36	621-06574 SODDING	100.000	m2
37	622-05748 TIMBER	153.000	m
38	701-51190 PILE, STEEL H, HP 250 X 62	54.000	m
39	701-91792 PILE TIP, STEEL H	12.000	EACH
40	702-51005 CONCRETE, A, SUBSTRUCTURE	24.000	m3
41	702-51863 FIELD DRILLED HOLE IN CONCRETE	576.000	EACH
42	702-94139 CONCRETE, A, ABOVE FOOTINGS	48.000	m3
43	703-51032 REINFORCING STEEL, EPOXY COATED	3,924.000	kg
44	708-05394 REPAIR	LUMP	LUMP
45	709-51821 SURFACE SEAL	LUMP	LUMP
46	711-05396 REPLACE	LUMP	LUMP
47	712-03812 BENCH	7.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 247
 LETTING DATE : 10/17/00 10:00 AM

CONTRACT ID : R -25028-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PEDESTRIAN / BIKE FACILITIES			
48	712-03862 PREFABRICATED BRIDGE	LUMP	LUMP
49	712-03862 PREFABRICATED BRIDGE	LUMP	LUMP
50	712-04928 TIMBER STEPS	1.000	EACH
51	714-02102 RETAINING WALL, MODULAR, CONCRETE	190.000	m2
52	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	84.900	m
53	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	116.600	m
54	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	22.800	m
55	715-46000 PIPE END SECTION, 300 mm	11.000	EACH
56	715-46005 PIPE END SECTION, 375 mm	1.000	EACH
57	720-44296 CAP INLET	1.000	EACH
58	720-45025 INLET, D6	2.000	EACH
59	720-45030 INLET, E7	2.000	EACH
60	720-45045 INLET, J10	2.000	EACH
61	720-98555 INLET, C15	2.000	EACH
62	731-93947 LEVELING PAD, CONCRETE	95.000	m
63	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
64	802-02489 SIGN POST, SQUARE, REINFORCED ANCHOR BASE	247.900	m
65	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	27.900	m2
66	805-02352 WIRE, XHHW, NO. 4 CU, IN PLASTIC DUCT, 1C 4GA.	17.000	m
67	805-02426 WIRE, THW, NO. 4 CU, IN PLASTIC DUCT, IN CONDUIT, 4 1C	170.000	m
68	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	170.000	m
69	805-86805 SERVICE POINT, I	1.000	EACH
70	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	280.000	m
71	805-86920 MULTIPLE COMPRESSION FITTING, NOT WATERPROOFED	15.000	EACH
72	805-86930 INSULATING LINK, NOT WATERPROOFED	14.000	EACH
73	805-96014 SAW CUT, FULL DEPTH	100.000	m
74	807-02820 LIGHT POLE BASE, CAST IRON, ORNAMENTAL	7.000	EACH
75	807-03950 LUMINAIRE, ORNAMENTAL	7.000	EACH
76	807-04113 CONCRETE FOUNDATION WITH GROUNDING, 500 mm DIA. X 1200 mm	7.000	EACH
77	807-86910 CONNECTOR KIT, UNFUSED	7.000	EACH
78	807-86915 CONNECTOR KIT, FUSED	7.000	EACH
79	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	13.000	EACH
80	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	3.000	EACH
81	808-75007 LINE, PAINT, SOLID, WHITE, 150 mm	1,344.000	m
82	808-75047 LINE, PAINT, SOLID, YELLOW, 150 mm	1,651.000	m
83	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600mm	13.000	m
84	808-91662 TRANSVERSE MARKINGS, PREFORMED PLASTIC, SOLID, WHITE,	632.000	m
85	808-97222 PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	11.000	EACH
86	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
87	712-03862 PREFABRICATED BRIDGE	LUMP	LUMP
88	205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE	11.000	EACH
89	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
90	801-06645 CONSTRUCTION SIGN, B	14.000	EACH
91	210-06852 BOARDWALK	215.000	m2

