

CALL ORDER : 130
 LETTING DATE :

CONTRACT ID : R -26854-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	11.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02255 TREE, 460 mm, REMOVE	18.000	EACH
10	202-02271 HEADWALL, REMOVE	3.000	EACH
11	202-03783 SIGN, PANEL, REMOVE	7.000	EACH
12	202-74035 SIGN, REMOVE	39.000	EACH
13	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
14	202-91385 INLET, REMOVE	2.000	EACH
15	202-93047 MANHOLE, REMOVE	1.000	EACH
16	202-96022 CONCRETE FOUNDATION, REMOVE	1.000	EACH
17	202-96133 PIPE, REMOVE	239.000	m
18	203-02000 EXCAVATION, COMMON	4,564.000	m3
19	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	7.000	Mg
20	205-06932 TEMPORARY CHECK DAM, STRAW BALES	345.000	m
21	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
22	205-06936 TEMPORARY SEDIMENT TRAP	35.000	Mg
23	205-06937 TEMPORARY SILT FENCE	285.000	m
24	207-08268 SUBGRADE TREATMENT, TYPE IV	6,806.000	m2
25	211-07454 STRUCTURE BACKFILL	288.000	m3
26	213-52830 FLOWABLE MORTAR	14.000	m3
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,832.000	Mg
28	303-07449 COMPACTED AGGREGATE, NO. 73	13.000	Mg
29	304-07494 WIDENING WITH HMA, TYPE C	345.000	Mg
30	306-08033 MILLING, ASPHALT, 25 mm	7,478.000	m2
31	306-08043 MILLING, TRANSITION	518.000	m2
32	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	346.000	Mg
33	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	938.000	Mg
34	401-07385 QC/QA-HMA, 3, 76, INTERMEDIATE, 12.5 mm	64.000	Mg
35	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	1,387.000	Mg
36	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 MM	1,038.000	Mg
37	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	1,122.000	Mg
38	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	416.000	Mg
39	406-05520 ASPHALT FOR TACK COAT	6.000	Mg
40	601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION	2.000	EACH
41	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
42	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	2.000	EACH
43	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	2.000	EACH
44	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	55.000	m
45	605-06120 CURB, CONCRETE	98.000	m
46	605-06150 CURB AND GUTTER, C, CONCRETE	118.000	m
47	610-07486 HMA FOR APPROACHES, TYPE A	112.000	Mg
48	610-07487 HMA FOR APPROACHES, TYPE B	39.000	Mg

CALL ORDER : 130
 LETTING DATE :

CONTRACT ID : R -26854-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
49	610-07712 PCCP FOR APPROACHES, 150 mm	83.000	m2
50	611-06497 MAILBOX ASSEMBLY, SINGLE	9.000	EACH
51	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
52	615-06490 RIGHT OF WAY MARKER	37.000	EACH
53	616-02320 GEOTEXTILES	630.000	m2
54	616-06405 RIPRAP, REVETMENT	473.000	Mg
55	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
56	621-06545 FERTILIZER	1.000	Mg
57	621-06554 SEED MIXTURE, U	165.000	kg
58	621-06565 MULCHING MATERIAL	5.000	Mg
59	621-06567 WATER	30.000	kL
60	621-06574 SODDING	1,635.000	m2
61	703-51030 REINFORCING STEEL	28.000	kg
62	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	1,523.000	m
63	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	18.000	m
64	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	32.000	m
65	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	134.000	m
66	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	208.000	m
67	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	59.000	m
68	715-05173 PIPE, TYPE 3, CIRCULAR, 600 mm	52.000	m
69	715-46005 PIPE END SECTION, 375 mm	14.000	EACH
70	715-46010 PIPE END SECTION, 450 mm	2.000	EACH
71	715-46020 PIPE END SECTION, 600 mm	11.000	EACH
72	715-91361 PIPE, PVC, 150 mm	67.000	m
73	718-06529 OUTLET PROTECTOR, 2	9.000	EACH
74	718-52610 AGGREGATE FOR UNDERDRAINS	345.000	m3
75	718-99153 GEOTEXTILES FOR UNDERDRAIN	3,046.000	m2
76	720-44000 CASTING, ADJUST TO GRADE	6.000	EACH
77	720-45030 INLET, E7	1.000	EACH
78	720-45035 INLET, F7	3.000	EACH
79	720-45045 INLET, J10	3.000	EACH
80	720-45410 MANHOLE, C4	2.000	EACH
81	720-45510 MANHOLE, C4, MODIFIED	4.000	EACH
82	720-94157 MANHOLE, C	1.000	EACH
83	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
84	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	8,352.000	m
85	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 600 mm	9.000	m
86	801-06605 BARRICADE, IIIA	8.000	EACH
87	801-06625 DETOUR ROUTE MARKER ASSEMBLY	17.000	EACH
88	801-06640 CONSTRUCTION SIGN, A	29.000	EACH
89	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
90	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
91	802-04893 REFERENCE POST	7.000	EACH
92	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	123.000	m
93	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	4.000	m
94	802-07057 SIGN, PANEL, WITH LEGEND	8.000	m2
95	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	16.000	m2
96	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	1.000	m2

CALL ORDER : 130
 LETTING DATE :

CONTRACT ID : R -26854-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
97	802-76095 STRUCTURAL STEEL, BREAKAWAY	412.000	kg
98	803-06031 SIGN FOUNDATIONS, CONCRETE	2.000	m3
99	805-01816 SIGNAL SUPPORT FOUNDATION, 900 mm X 900 mm X 2500 mm	2.000	EACH
100	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
101	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm AMBER	4.000	EACH
102	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm RED	4.000	EACH
103	805-78415 SPAN, CATENARY, AND TETHER	1.000	EACH
104	805-78420 DISCONNECT HANGER	1.000	EACH
105	805-78445 SIGNAL SERVICE	1.000	EACH
106	805-78467 SIGNAL CABLE, 3C 8GA.	15.000	m
107	805-78480 SIGNAL CABLE, 3C 14GA.	80.000	m
108	805-78485 SIGNAL CABLE, 5C 14GA.	20.000	m
109	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	2.000	EACH
110	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	2,349.000	m
111	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 200 mm	112.000	m
112	808-06716 LINE, REMOVE	6,344.000	m
113	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	1,554.000	m
114	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	28.000	m
115	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	5.000	EACH
116	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	105.000	EACH
117	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	105.000	EACH
118	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	480.000	m
119	808-99176 LINE, THERMOPLASTIC, SOLID, YELLOW, 600 mm	79.000	m

CALL ORDER : 140
 LETTING DATE :

CONTRACT ID : R -27263-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 LANDSCAPING AT REST AREA			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	24.000	MOS
3	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-01502 LIGHT STANDARD, REMOVE	30.000	EACH
11	202-02240 PAVEMENT REMOVAL	19,455.000	m2
12	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
13	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
14	202-03783 SIGN, PANEL, REMOVE	12.000	EACH
15	203-02000 EXCAVATION, COMMON	134,515.000	m3
16	203-02070 BORROW	107,880.000	m3
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	930.000	Mg
18	205-06934 TEMPORARY MULCHING	82.000	Mg
19	205-06936 TEMPORARY SEDIMENT TRAP	790.000	Mg
20	205-06937 TEMPORARY SILT FENCE	2,416.000	m
21	207-08263 SUBGRADE TREATMENT, TYPE IA	106,530.000	m2
22	210-05758 BUILDING	LUMP	LUMP
23	210-05758 BUILDING	LUMP	LUMP
24	210-05758 BUILDING	LUMP	LUMP
25	210-06902 PUMP	1.000	EACH
26	210-07724 WELL	LUMP	LUMP
27	210-08541 WASTEWATER	LUMP	LUMP
28	210-08541 WASTEWATER	LUMP	LUMP
29	210-08542 WATER	LUMP	LUMP
30	210-08542 WATER	LUMP	LUMP
31	210-97671 PICNIC TABLE	30.000	EACH
32	211-07454 STRUCTURE BACKFILL	1,890.000	m3
33	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	32,000.000	Mg
34	303-01180 COMPACTED AGGREGATE, NO. 53	12,190.000	Mg
35	304-06464 SUBBASE FOR PCCP	17,590.000	m3
36	306-08033 MILLING, ASPHALT, 25 mm	13,580.000	m2
37	307-05402 CEMENT	150.000	m2
38	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	2,260.000	Mg
39	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 MM	2,435.000	Mg
40	401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm	9,142.000	Mg
41	401-08338 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm	1,555.000	Mg
42	402-05494 HMA RUMBLE STRIPS	92.000	m
43	402-07432 HMA SURFACE, TYPE A	760.000	Mg
44	402-07440 HMA BASE, TYPE A	2,260.000	Mg
45	406-05520 ASPHALT FOR TACK COAT	23.000	Mg
46	501-06321 QC/QA-PCCP, 250 mm	12,454.000	m2
47	501-06325 QC/QA-PCCP, 350 mm	59,475.000	m2
48	503-05240 D-1 CONTRACTION JOINT	12,323.000	m

CALL ORDER : 140
 LETTING DATE :

CONTRACT ID : R -27263-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 LANDSCAPING AT REST AREA			
49	601-05657 ENERGY ABSORBING TERMINAL, CZ, LEAVE IN PLACE	1.000	EACH
50	603-04847 FENCE GATE	1.000	EACH
51	603-06040 FENCE, FARM FIELD, 1190 mm	1,017.000	m
52	603-06045 FENCE, CHAIN LINK, 1220 mm	1,200.000	m
53	603-92636 FENCE, CHAIN LINK, 1830 mm	3,136.000	m
54	604-01527 PAVERS, BRICK	832.000	m2
55	604-91404 SIDEWALK, CONCRETE, 125 mm	2,900.000	m2
56	604-91404 SIDEWALK, CONCRETE, 125 mm	1,260.000	m2
57	605-06090 CURB, INTEGRAL, CONCRETE	916.000	m
58	605-06100 CURB, INTEGRAL, C, CONCRETE	969.000	m
59	606-07484 MILLED HMA SHOULDER CORRUGATIONS	4,530.000	m
60	610-07486 HMA FOR APPROACHES, TYPE A	108.000	Mg
61	611-03668 URN	8.000	EACH
62	611-03671 TRASH RECEPTACLE	50.000	EACH
63	616-02320 GEOTEXTILES	304.000	m2
64	616-06406 RIPRAP, REVETMENT	304.000	m2
65	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
66	621-02318 SEED MIXTURE, PRAIRIE GRASS	155.000	kg
67	621-02770 EROSION CONTROL BLANKET	101,545.000	m2
68	621-04258 SEED MIXTURE	765.000	kg
69	621-04258 SEED MIXTURE	295.000	kg
70	621-06553 SEED MIXTURE, R	950.000	kg
71	621-06557 SEED MIXTURE, T	2,390.000	kg
72	621-06567 WATER	3.000	kL
73	621-06575 SODDING, NURSERY	10,276.000	m2
74	621-08538 MULCH	10.000	m3
75	621-08539 HOSE	180.000	m
76	621-08539 HOSE	360.000	m
77	621-98038 MULCH, HARDWOOD SHREDDED BARK	102.000	m3
78	622-01937 PLANT	179.000	EACH
79	622-05605 PLANT, ANNUAL	8,720.000	EACH
80	622-05617 PLANT, BROADLEAF EVERGREEN, GLOBE, DWARF, OVER 600 mm	196.000	EACH
81	622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 1800	460.000	EACH
82	622-05631 PLANT, CONIFEROUS EVERGREEN, GLOBE, DWARF, OVER 600 TO 900	24.000	EACH
83	622-05639 PLANT, DECIDUOUS SHRUB, OVER 450 TO 600 mm	431.000	EACH
84	622-05641 PLANT, DECIDUOUS SHRUB, OVER 900 TO 1200 mm	321.000	EACH
85	622-05645 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 1800 TO 2400 mm	68.000	EACH
86	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM OVER 32 TO 50 mm	24.000	EACH
87	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 50 TO 63 mm	176.000	EACH
88	622-05654 PLANT, PERENNIAL	2,715.000	EACH
89	622-52436 SIGN, DO NOT MOW OR SPRAY	200.000	EACH
90	707-99085 FLAG POLE	2.000	EACH
91	711-92184 BUILDING, REST AREA	LUMP	LUMP
92	711-92184 BUILDING, REST AREA	LUMP	LUMP
93	711-98751 BUILDING, MECHANICAL	LUMP	LUMP
94	711-98751 BUILDING, MECHANICAL	LUMP	LUMP
95	712-03812 BENCH	32.000	EACH
96	715-03025 SANITARY MANHOLE	5.000	EACH

CALL ORDER : 140
 LETTING DATE :

CONTRACT ID : R -27263-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LANDSCAPING AT REST AREA		
97	715-04618 SAFETY METAL END SECTION, 6:1, 750 mm	1.000	EACH
98	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	11,680.000	m
99	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	1,406.000	m
100	715-05087 MAINTENANCE	LUMP	LUMP
101	715-05087 MAINTENANCE	LUMP	LUMP
102	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	199.000	m
103	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	80.000	m
104	715-05125 PIPE, TYPE 1, CIRCULAR, 750 mm	115.000	m
105	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	436.000	m
106	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	362.000	m
107	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	475.000	m
108	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	92.000	m
109	715-05408 PIPE, SANITARY SEWER, 200 mm	585.000	m
110	715-05711 PIPE, SANITARY SEWER, 150 mm	140.000	m
111	715-06814 PIPE, SANITARY SEWER, 100 mm	200.000	m
112	715-07073 WATER LINE	400.000	m
113	715-08048 STORMWATER TREATMENT SYSTEM	2.000	EACH
114	715-46000 PIPE END SECTION, 300 mm	1.000	EACH
115	715-46005 PIPE END SECTION, 375 mm	12.000	EACH
116	715-46010 PIPE END SECTION, 450 mm	4.000	EACH
117	715-46020 PIPE END SECTION, 600 mm	7.000	EACH
118	715-46030 PIPE END SECTION, 750 mm	3.000	EACH
119	715-98265 WATER MAIN, DUCTILE IRON, 100 mm	200.000	m
120	716-07630 PIPE INSTALLATION, TRENCHLESS, 300 mm	120.000	m
121	718-06529 OUTLET PROTECTOR, 2	50.000	EACH
122	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	2,000.000	m
123	718-52610 AGGREGATE FOR UNDERDRAINS	2,450.000	m3
124	718-99153 GEOTEXTILES FOR UNDERDRAIN	26,065.000	m2
125	719-03975 BUILDING PLUMBING	LUMP	LUMP
126	719-03975 BUILDING PLUMBING	LUMP	LUMP
127	720-03194 MANHOLE	1.000	EACH
128	720-45265 PIPE CATCH BASIN, 375 mm	4.000	EACH
129	720-45410 MANHOLE, C4	13.000	EACH
130	720-95422 MANHOLE, J4	8.000	EACH
131	720-96554 INLET, M13, MODIFIED	14.000	EACH
132	732-03942 HYDRANT	12.000	EACH
133	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
134	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	28,586.000	m
135	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
136	801-06710 FLASHING ARROW SIGN	360.000	DAY
137	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
138	801-07118 BARRICADE, III-A	9.000	m
139	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	148.000	m
140	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	90.000	m
141	802-07137 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	10.000	EACH
142	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	14.000	EACH
143	802-76015 SIGN,PANEL,ENCAPSULATED LENS WITH LEGEND	83.000	m2
144	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	12.000	m2

CALL ORDER : 140
 LETTING DATE :

CONTRACT ID : R -27263-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 LANDSCAPING AT REST AREA			
145	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	58.000	m2
146	802-76095 STRUCTURAL STEEL, BREAKAWAY	2,203.000	kg
147	804-06725 DELINEATOR WITH POST, D1, 75 mm	203.000	EACH
148	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	250.000	m
149	807-02191 HANDHOLE, LIGHTING	4.000	EACH
150	807-03694 BUILDING ELECTRICAL	LUMP	LUMP
151	807-03694 BUILDING ELECTRICAL	LUMP	LUMP
152	807-03714 CONCRETE FOUNDATION WITH GROUNDING, 300 mm DIA. BY 1220 mm	2.000	EACH
153	807-04112 WIRE, XHHW, NO. 10	1,775.000	m
154	807-04309 PORTABLE TOWER LIGHTING DRIVE SYSTEM	1.000	EACH
155	807-04653 LIGHTING FOUNDATION	32.000	EACH
156	807-04866 LUMINAIRE	2.000	EACH
157	807-06935 INSULATION LINK, WATERPROOFED	8.000	EACH
158	807-07580 WIRE, NO. 4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	4,560.000	m
159	807-82440 LIGHT POLE, HIGH MAST, 40 m E.M.H.	4.000	EACH
160	807-84814 LIGHT POLE, 12.8 m E.M.H., 4.6 m MAST ARM, TRANSFORMER BASE	32.000	EACH
161	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	32.000	EACH
162	807-86665 LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM	24.000	EACH
163	807-86810 SERVICE POINT, II	2.000	EACH
164	807-86830 CONCRETE FOUNDATION WITH GROUNDING, 1220 mm DIA. X 6100 mm	4.000	EACH
165	807-86910 CONNECTOR KIT, UNFUSED	32.000	EACH
166	807-86915 CONNECTOR KIT, FUSED	32.000	EACH
167	807-86920 MULTIPLE COMPRESSION FITTING, NOT WATERPROOFED	78.000	EACH
168	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.000	EACH
169	807-86930 INSULATION LINK, NONWATERPROOFED	64.000	EACH
170	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	36.000	EACH
171	807-86955 CABLE DUCT MARKER	10.000	EACH
172	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	12,563.000	m
173	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	3,205.000	m
174	808-05534 LINE, EPOXY, SOLID, WHITE, 200 mm	1,443.000	m
175	808-06194 LINE, EPOXY, SOLID, WHITE, 300 mm	444.000	m
176	808-06716 LINE, REMOVE	9,054.000	m
177	808-07591 LINE, EPOXY, SOLID, WHITE, 600 mm	178.000	m
178	808-74811 LINE, EPOXY, BROKEN, WHITE, 125 mm	1,040.000	m
179	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	147.000	EACH
180	808-97664 PAVEMENT MESSAGE MARKINGS THERMOPLASTIC, HANDICAP SYMBOL	12.000	EACH

CALL ORDER : 150
 LETTING DATE :

CONTRACT ID : R -27385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-07040 FIELD OFFICE, C	32.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	5.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	160.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
8	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
9	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-02240 PAVEMENT REMOVAL	49,586.900	m2
15	202-02241 GUARDRAIL, REMOVE	1,742.900	m
16	202-02271 HEADWALL, REMOVE	17.000	EACH
17	202-02272 PAVED SIDE DITCH, REMOVE	1,963.500	m
18	202-02273 CENTER CURB, CONCRETE, REMOVE	1,494.900	m2
19	202-02278 CURB, CONCRETE, REMOVE	4,402.900	m
20	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	206.600	m2
21	202-04089 SIGN, SHEET, REMOVE	40.000	EACH
22	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
23	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
24	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
25	202-52710 SIDEWALK, CONCRETE, REMOVE	17.200	m2
26	202-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	23.000	EACH
27	202-74050 SIGN, OVERHEAD, REMOVE	3.000	EACH
28	202-74080 OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	4.000	EACH
29	202-91385 INLET, REMOVE	18.000	EACH
30	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	9.000	EACH
31	202-94810 CURB TURNOUT, REMOVE	20.000	EACH
32	202-95579 SERVICE POINT, REMOVE	3.000	EACH
33	202-96070 HIGH MAST TOWER, REMOVE	5.000	EACH
34	202-96133 PIPE, REMOVE	891.000	m
35	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
36	202-99187 FENCE, FARM FIELD, REMOVE	1,118.600	m
37	203-02000 EXCAVATION, COMMON	118,438.590	m3
38	203-02070 BORROW	12,140.670	m3
39	203-51223 EXCAVATION, WATERWAY	1,140.000	m3
40	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	748.500	Mg
41	205-06933 TEMPORARY DITCH INLET PROTECTION	42.000	EACH
42	205-06935 TEMPORARY SEDIMENT BASIN	2.000	EACH
43	205-06937 TEMPORARY SILT FENCE	1,671.500	m
44	206-51220 EXCAVATION, WET	191.700	m3
45	206-51225 EXCAVATION, DRY	24.700	m3
46	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	1,007.500	m3
47	206-51235 COFFERDAM	LUMP	LUMP
48	207-07498 SUBGRADE TREATMENT, TYPE A	8,243.600	m2

CALL ORDER : 150
 LETTING DATE :

CONTRACT ID : R -27385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK		
49	207-08262 SUBGRADE TREATMENT, TYPE I	33,517.700	m2
50	207-08263 SUBGRADE TREATMENT, TYPE IA	57,982.000	m2
51	207-08265 SUBGRADE TREATMENT, TYPE IIA	17,997.500	m2
52	210-08274 COMPOST	41.000	m3
53	211-02050 B BORROW	10,128.000	m3
54	211-06467 AGGREGATE FOR END BENT BACKFILL	408.900	m3
55	211-07454 STRUCTURE BACKFILL	24,668.600	m3
56	213-08058 FLOWABLE BACKFILL	96.600	m3
57	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	20,281.100	Mg
58	302-06464 SUBBASE FOR PCCP	8,050.200	m3
59	302-07455 DENSE GRADED SUBBASE	288.400	m3
60	303-07449 COMPACTED AGGREGATE, NO. 73	24.300	Mg
61	304-07493 WIDENING WITH HMA, TYPE B	1,457.200	Mg
62	304-07783 HMA PATCHING, TYPE D	70.100	Mg
63	306-08034 MILLING, ASPHALT, 38 mm	10,259.300	m2
64	306-08036 MILLING, ASPHALT, 50 mm	6,229.500	m2
65	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
66	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	6,272.800	Mg
67	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	663.800	Mg
68	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 MM	10,429.300	Mg
69	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 MM	1,098.900	Mg
70	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	14,508.100	Mg
71	401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm	7,589.300	Mg
72	401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm	6,496.500	Mg
73	402-07786 HMA BASE, TYPE D	46.500	Mg
74	404-05511 SEAL COAT, 2	1,361.200	m2
75	405-05517 ASPHALT FOR PRIME COAT	0.300	Mg
76	406-05520 ASPHALT FOR TACK COAT	83.330	Mg
77	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
78	501-06323 QC/QA-PCCP, 300 mm	30,522.600	m2
79	501-06325 QC/QA-PCCP, 350 mm	12,990.500	m2
80	503-03489 RETROFITTED TIE BARS	2,472.000	EACH
81	503-05240 D-1 CONTRACTION JOINT	7,878.700	m
82	503-05310 TERMINAL JOINT	126.700	m
83	601-01522 GUARDRAIL TRANSITION TYPE TGB	10.000	EACH
84	601-06224 IMPACT ATTENUATOR, CR, W1, TL-2	4.000	EACH
85	601-06228 IMPACT ATTENUATOR, CR, W1, TL-3	1.000	EACH
86	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
87	601-06238 IMPACT ATTENUATOR, R1, W1, TL-3	2.000	EACH
88	601-06416 IMPACT ATTENUATOR SPARE PARTS PACKAGE, ED, W1, TL-3	1.000	EACH
89	601-06421 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R1, W1, TL-3	1.000	EACH
90	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
91	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
92	601-94689 GUARDRAIL END TREATMENT, OS	11.000	EACH
93	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	739.140	m
94	602-06729 BARRIER DELINEATOR	17.000	EACH
95	602-91266 MEDIAN BARRIER, CONCRETE, MODIFIED	520.000	m
96	603-06045 FENCE, CHAIN LINK, 1220 mm	3,185.400	m

CALL ORDER : 150
 LETTING DATE :

CONTRACT ID : R -27385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001 ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK				
97	604-06070	SIDEWALK, CONCRETE	134.900	m2
98	604-07902	CURB RAMP, CONCRETE, H	10.800	m2
99	605-06090	CURB, INTEGRAL, CONCRETE	120.800	m
100	605-06095	CURB, INTEGRAL, B, CONCRETE	198.300	m
101	605-06120	CURB, CONCRETE	116.900	m
102	605-06140	CURB AND GUTTER, CONCRETE	1,202.700	m
103	605-06145	CURB AND GUTTER, B, CONCRETE	1,874.300	m
104	605-06255	CENTER CURB, D, CONCRETE	1,355.300	m2
105	607-06370	PAVED SIDE DITCH, H	74.200	m
106	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	1,576.700	m2
107	609-06263	REINFORCED CONCRETE BRIDGE APPROACH, 375 mm	155.100	m2
108	610-07486	HMA FOR APPROACHES, TYPE A	4,363.800	Mg
109	611-05330	CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 150 mm	2,897.400	m2
110	611-06497	MAILBOX ASSEMBLY, SINGLE	5.000	EACH
111	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
112	615-06490	RIGHT OF WAY MARKER	101.000	EACH
113	615-06500	MONUMENT, A	4.000	EACH
114	615-06505	MONUMENT, B	33.000	EACH
115	615-06510	MONUMENT, C	14.000	EACH
116	615-06515	MONUMENT, D	58.000	EACH
117	615-06527	MONUMENT, SECTION CORNER	2.000	EACH
118	616-02320	GEOTEXTILES	14,262.100	m2
119	616-05689	RIPRAP, CLASS 2	1,313.000	Mg
120	616-06405	RIPRAP, REVETMENT	5,165.500	Mg
121	616-06451	RIPRAP, UNIFORM	2,126.000	Mg
122	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
123	621-04258	SEED MIXTURE	3.200	kg
124	621-04258	SEED MIXTURE	40.000	kg
125	621-06545	FERTILIZER	7.400	Mg
126	621-06554	SEED MIXTURE, U	1,286.200	kg
127	621-06557	SEED MIXTURE, T	123.400	kg
128	621-06565	MULCHING MATERIAL	41.300	Mg
129	621-06574	SODDING	707.400	m2
130	621-06575	SODDING, NURSERY	64,839.700	m2
131	621-98038	MULCH, HARDWOOD SHREDDED BARK	48.000	m3
132	622-01937	PLANT	17.000	EACH
133	622-05626	PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 1800	33.000	EACH
134	622-05640	PLANT, DECIDUOUS SHRUB, OVER 600 TO 900 mm	340.000	EACH
135	622-05641	PLANT, DECIDUOUS SHRUB, OVER 900 TO 1200 mm	50.000	EACH
136	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 50 TO 63 mm	94.000	EACH
137	622-05654	PLANT, PERENNIAL	1,031.000	EACH
138	622-52436	SIGN, DO NOT MOW OR SPRAY	20.000	EACH
139	701-01814	MOBILIZATION FOR DYNAMIC PILE MONITORING AND EQUIPMENT	1.000	EACH
140	701-01849	PILE, CONCRETE, STEEL SHELL ENCASED, 7.92 mm, 356 mm	1,341.200	m
141	701-06011	DYNAMIC PILE LOAD TEST	3.000	EACH
142	701-06012	TEST PILE, RESTRIKE	3.000	EACH
143	701-06027	TEST PILE	3.000	EACH
144	701-95780	PILE, STEEL H, HP 310 X 110	1,847.200	m

CALL ORDER : 150
 LETTING DATE :

CONTRACT ID : R -27385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK			
145	701-98647 PILE, CONCRETE, STEEL SHELL ENCASED, 5.16 mm, 356 mm	60.000	m
146	702-51005 CONCRETE, A, SUBSTRUCTURE	754.900	m3
147	702-51015 CONCRETE, B, FOOTINGS	102.900	m3
148	702-51090 BRONZE PLATES	45.000	kg
149	702-51100 DRAIN PIPE, CAST IRON, 150 mm	1,183.400	kg
150	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	988.800	kg
151	702-51863 FIELD DRILLED HOLE IN CONCRETE	82.000	EACH
152	703-06028 REINFORCING BARS	17,842.000	kg
153	703-06029 REINFORCING BARS, EPOXY COATED	330,600.000	kg
154	703-97703 THREADED BAR SPLICE, EPOXY COATED	906.000	EACH
155	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	2,334.000	EACH
156	704-04850 CONCRETE	953.000	m2
157	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,614.300	m3
158	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
159	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	2.000	EACH
160	706-06349 RAILING, TX	134.800	m
161	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	4.000	EACH
162	706-51020 CONCRETE, C, RAILING	64.900	m3
163	707-05982 STRUCTURAL MEMBERS, CONCRETE I-BEAM, I, 711 mm X 305 mm	48.000	m
164	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 1143 mm X 406 mm	580.000	m
165	708-51813 PNEUMATICALLY PLACED MORTAR	2.000	m2
166	708-51814 WELDED STEEL WIRE FABRIC	2.000	m2
167	709-04919 COATING	3,781.000	m2
168	709-51821 SURFACE SEAL	LUMP	LUMP
169	709-51821 SURFACE SEAL	LUMP	LUMP
170	709-51821 SURFACE SEAL	LUMP	LUMP
171	711-01786 STRUCTURAL STEEL DRILLING, 25 mm DIA. HOLE	24.000	EACH
172	711-51038 STRUCTURAL STEEL	LUMP	LUMP
173	711-51038 STRUCTURAL STEEL	LUMP	LUMP
174	711-51070 ANCHOR PLATE, AP 1	86.000	EACH
175	711-51080 ANCHOR PLATE, AP 3	8.000	EACH
176	715-02397 SAFETY METAL END SECTION, 4:1, 900 mm	1.000	EACH
177	715-04618 SAFETY METAL END SECTION, 6:1, 750 mm	1.000	EACH
178	715-05019 PIPE, TYPE 1, CIRCULAR, 900 mm	53.400	m
179	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	561.900	m
180	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	9,191.700	m
181	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	559.900	m
182	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	100.800	m
183	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	643.600	m
184	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	1,435.700	m
185	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	590.600	m
186	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	99.500	m
187	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	300.300	m
188	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	492.400	m
189	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	74.300	m
190	715-05161 PIPE, TYPE 2, CIRCULAR, 1200 mm	0.600	m
191	715-05168 PIPE, TYPE 3, CIRCULAR, 300 mm	8.400	m
192	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	35.800	m

CALL ORDER : 150
 LETTING DATE :

CONTRACT ID : R -27385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK			
193	715-05171 PIPE, TYPE 3, CIRCULAR, 450 mm	15.600	m
194	715-05177 PIPE, TYPE 3, CIRCULAR, 900 mm	138.100	m
195	715-05363 PIPE, TYPE 3, DEFORMED, MIN. AREA 0.17 m2	9.100	m
196	715-05407 PIPE, END BENT DRAIN, 150 mm	64.400	m
197	715-05428 PIPE, SLOTTED VANE DRAIN, 300 mm	23.800	m
198	715-05596 PIPE EXTENSION, CIRCULAR, 450 mm	1.200	m
199	715-05597 PIPE EXTENSION, CIRCULAR, 600 mm	38.400	m
200	715-05842 CONCRETE ANCHOR, 1050 mm	1.000	EACH
201	715-06004 CONCRETE ANCHOR, 1200 mm	1.000	EACH
202	715-06337 PIPE EXTENSION, CIRCULAR, 1200 mm	4.300	m
203	715-07089 PIPE EXTENSION, DEFORMED, MIN. AREA 1.68 m2	4.500	m
204	715-46000 PIPE END SECTION, 300 mm	3.000	EACH
205	715-46005 PIPE END SECTION, 375 mm	17.000	EACH
206	715-46010 PIPE END SECTION, 450 mm	8.000	EACH
207	715-46015 PIPE END SECTION, 525 mm	1.000	EACH
208	715-46020 PIPE END SECTION, 600 mm	9.000	EACH
209	715-46030 PIPE END SECTION, 750 mm	3.000	EACH
210	715-46040 PIPE END SECTION, 900 mm	7.000	EACH
211	715-46055 PIPE END SECTION, MIN. AREA .17 m2	2.000	EACH
212	718-06528 OUTLET PROTECTOR, 1	23.000	EACH
213	718-06529 OUTLET PROTECTOR, 2	3.000	EACH
214	718-06531 OUTLET PROTECTOR, 3	28.000	EACH
215	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	m
216	718-52610 AGGREGATE FOR UNDERDRAINS	1,515.300	m3
217	718-99153 GEOTEXTILES FOR UNDERDRAIN	24,479.800	m2
218	720-01150 MANHOLE, F	1.000	EACH
219	720-44000 CASTING, ADJUST TO GRADE	11.000	EACH
220	720-44296 CAP INLET	1.000	EACH
221	720-45030 INLET, E7	3.000	EACH
222	720-45035 INLET, F7	2.000	EACH
223	720-45235 CATCH BASIN, E7	2.000	EACH
224	720-45251 CATCH BASIN, K10, MODIFIED	12.000	EACH
225	720-45265 PIPE CATCH BASIN, 375 mm	2.000	EACH
226	720-45270 PIPE CATCH BASIN, 450 mm	14.000	EACH
227	720-45410 MANHOLE, C4	36.000	EACH
228	720-45416 MANHOLE, E4	1.000	EACH
229	720-90129 MANHOLE, J2	9.000	EACH
230	720-90984 MANHOLE, C2	4.000	EACH
231	720-91352 CATCH BASIN, F7	3.000	EACH
232	720-93409 INLET, B15, MODIFIED	3.000	EACH
233	720-93411 INLET, C15, MODIFIED	1.000	EACH
234	720-94713 CATCH BASIN, C15, MODIFIED	1.000	EACH
235	720-95164 CATCH BASIN, B15, MODIFIED	10.000	EACH
236	720-95422 MANHOLE, J4	1.000	EACH
237	720-97958 MANHOLE, K2	1.000	EACH
238	720-98068 MANHOLE, E2	1.000	EACH
239	720-98174 INLET, B15	5.000	EACH
240	720-99416 CATCH BASIN, B15	13.000	EACH

CALL ORDER : 150
 LETTING DATE :

CONTRACT ID : R -27385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK			
241	720-99417 CATCH BASIN, C15	11.000	EACH
242	724-04163 STRUCTURAL EXPANSION JOINT SEAL, REPLACE	68.000	m
243	726-92532 BEARING ASSEMBLY, ELASTOMERIC, III	40.000	EACH
244	728-98377 MASONRY COATING	LUMP	LUMP
245	731-93945 FACE PANELS, CONCRETE	3,184.500	m2
246	731-93946 WALL ERECTION	3,184.500	m2
247	731-93947 LEVELING PAD, CONCRETE	520.000	m
248	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	26.000	EACH
249	801-01505 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (ONLY)	24.000	EACH
250	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
251	801-03291 CONSTRUCTION SIGN, D	4.000	EACH
252	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
253	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	15,105.300	m
254	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	35,981.000	m
255	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 600 mm	23.000	m
256	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 600 mm	7.500	m
257	801-06625 DETOUR ROUTE MARKER ASSEMBLY	35.000	EACH
258	801-06640 CONSTRUCTION SIGN, A	50.000	EACH
259	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
260	801-06710 FLASHING ARROW SIGN	840.000	DAY
261	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
262	801-07118 BARRICADE, III-A	489.600	m
263	801-07119 BARRICADE, III-B	100.800	m
264	801-07120 BARRICADE, III, PERMANENT	12.000	m
265	801-07612 TEMPORARY PAVEMENT MARKING, 600 mm	39.700	m
266	801-08388 TEMPORARY TRAFFIC BARRIER	2,518.000	m
267	801-08389 TEMPORARY TRAFFIC BARRIER, ANCHORED	1,341.500	m
268	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
269	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	5.000	EACH
270	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	290.670	m
271	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	189.870	m
272	802-07057 SIGN, PANEL, WITH LEGEND	341.608	m2
273	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	86.000	EACH
274	802-07060 SIGN, SHEET, RELOCATE	16.000	EACH
275	802-07101 SIGN LIGHTING SYSTEM, TRACK, BOX TRUSS	1.000	EACH
276	802-07102 SIGN LIGHTING SYSTEM, TRACK, CANTILEVER	1.000	EACH
277	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	14.000	EACH
278	802-07153 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	22.000	EACH
279	802-07158 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, I	1.000	EACH
280	802-07159 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, II	4.000	EACH
281	802-07275 BOX TRUSS SIGN FOUNDATION, V-C	1.000	EACH
282	802-07278 BOX TRUSS SIGN FOUNDATION, V-D	1.000	EACH
283	802-07285 BOX TRUSS SIGN FOUNDATION, VI-C	4.000	EACH
284	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	36.006	m2
285	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	48.240	m2
286	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	26.453	m2
287	802-76065 SIGN POST, B	6.000	m
288	802-76095 STRUCTURAL STEEL, BREAKAWAY	6,554.000	kg

CALL ORDER : 150
 LETTING DATE :

CONTRACT ID : R -27385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK			
289	802-76115 SPAN OVERHEAD SIGN STRUCTURE, TRI-CHORD TRUSS, SINGLE	2.000	EACH
290	802-76140 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM	1.000	EACH
291	802-76170 WALKWAY, HANDRAIL, AND LIGHTING SUPPORT ASSEMBLY	37.500	m
292	802-94494 SIGN STRUCTURE, OVERHEAD, RELOCATE	1.000	EACH
293	803-76110 SPAN OVERHEAD SIGN STRUCTURE, BOX TRUSS	2.000	EACH
294	804-06770 DELINEATOR POST	35.000	EACH
295	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	2.000	EACH
296	805-01842 HANDHOLE, SIGNAL	9.000	EACH
297	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
298	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	751.300	m
299	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
300	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	8.000	EACH
301	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER ARROW, GREEN	4.000	EACH
302	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
303	805-78420 DISCONNECT HANGER	4.000	EACH
304	805-78445 SIGNAL SERVICE	1.000	EACH
305	805-78467 SIGNAL CABLE, 3C 8GA.	14.200	m
306	805-78485 SIGNAL CABLE, 5C 14GA.	264.000	m
307	805-78490 SIGNAL CABLE, 7C 14GA.	329.000	m
308	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,199.400	m
309	805-78746 PREFORMED LOOP DETECTORS	463.900	m
310	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
311	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
312	805-86810 SERVICE POINT, II	4.000	EACH
313	805-86820 CONCRETE FOUNDATION WITH GROUNDING, 760 mm X 760 mm X	23.000	EACH
314	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	920.000	m
315	805-86920 MULTIPLE COMPRESSION FITTING, NOT WATERPROOFED	60.000	EACH
316	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	10.000	EACH
317	805-92512 MICROLOOP DETECTOR	2.000	EACH
318	805-96014 SAW CUT, FULL DEPTH	175.200	m
319	805-98335 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C	4,000.000	m
320	805-98336 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	300.000	m
321	807-07211 LIGHT POLE, 12.8 m E.M.H., 6.1 m MAST ARM,	1.000	EACH
322	807-82004 SIGN CIRCUIT INSTALLATION, BOX TRUSS, 5 LUMINAIRES	2.000	EACH
323	807-82058 UNDERPASS CIRCUIT INSTALLATION, 8 LUMINAIRES	1.000	EACH
324	807-82120 LIGHT POLE, HIGH MAST, 27 m E.M.H.	1.000	EACH
325	807-82400 LIGHT POLE, HIGH MAST, 38 m E.M.H.	2.000	EACH
326	807-84688 LIGHT POLE, 11.6 m E.M.H., 1.5 m MAST ARM, TRANSFORMER BASE	1.000	EACH
327	807-84740 LIGHT POLE, 12.2 m E.M.H., 1.5 m MAST ARM, TRANSFORMER BASE	1.000	EACH
328	807-84752 LIGHT POLE, 12.2 m E.M.H., 3.1 m MAST ARM, TRANSFORMER BASE	3.000	EACH
329	807-84760 LIGHT POLE, 12.2 m E.M.H., 4.6 m MAST ARM, TRANSFORMER BASE	1.000	EACH
330	807-84804 LIGHT POLE, 12.8 m E.M.H., 3.1 m MAST ARM, TRANSFORMER BASE	2.000	EACH
331	807-84814 LIGHT POLE, 12.8 m E.M.H., 4.6 m MAST ARM, TRANSFORMER BASE	14.000	EACH
332	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	23.000	EACH
333	807-86635 LUMINAIRE, ROADWAY, MERCURY VAPOR, 250 WATT	16.000	EACH
334	807-86665 LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM	16.000	EACH
335	807-86750 LUMINAIRE UNDERPASS, WALL MOUNTED, HIGH PRESSURE SODIUM, 150	8.000	EACH
336	807-86830 CONCRETE FOUNDATION WITH GROUNDING, 1220 mm DIA. X 6100 mm	3.000	EACH

CALL ORDER : 150
 LETTING DATE :

CONTRACT ID : R -27385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK		
337	807-86910 CONNECTOR KIT, UNFUSED	30.000	EACH
338	807-86915 CONNECTOR KIT, FUSED	34.000	EACH
339	807-86930 INSULATION LINK, NONWATERPROOFED	52.000	EACH
340	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	35.000	EACH
341	807-86955 CABLE DUCT MARKER	12.000	EACH
342	807-96868 LUMINAIRE, INSTALL	10.000	EACH
343	808-03002 LINE, EPOXY, BROKEN, WHITE, 100 mm	1,340.000	m
344	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	774.600	m
345	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	141.600	m
346	808-04896 LINE, EPOXY, BROKEN, YELLOW, 100 mm	35.400	m
347	808-05534 LINE, EPOXY, SOLID, WHITE, 200 mm	854.000	m
348	808-05535 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, CROSSHATCH LINE,	91.000	m
349	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	978.700	m
350	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	4,942.400	m
351	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	8,051.000	m
352	808-06714 LINE, PAINT, SOLID, YELLOW, 100 mm	5,002.000	m
353	808-06716 LINE, REMOVE	9,200.000	m
354	808-06848 LINE, EPOXY, DOTTED, WHITE, 100 mm, 600m LINE, 1200 mm GAP	152.000	m
355	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 600 mm	46.000	m
356	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	22.000	EACH
357	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	8.000	EACH
358	808-74811 LINE, EPOXY, BROKEN, WHITE, 125 mm	688.000	m
359	808-75008 LINE, PAINT, SOLID, WHITE, 200 mm	594.000	m
360	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	629.400	m
361	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	9,254.000	m
362	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	141.700	m
363	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	38.000	EACH
364	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	36.000	EACH
365	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	748.000	EACH

CALL ORDER : 160
 LETTING DATE :

CONTRACT ID : R -27433-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	20.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
9	202-02241 GUARDRAIL, REMOVE	102.000	LFT
10	202-02278 CURB, CONCRETE, REMOVE	1,600.000	LFT
11	202-05668 DEMOLITION	LUMP	LUMP
12	202-91385 INLET, REMOVE	21.000	EACH
13	203-02000 EXCAVATION, COMMON	1,796.000	CYS
14	203-02070 BORROW	700.000	CYS
15	205-03371 SEDIMENT, REMOVE	10.000	CYS
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	33.000	TON
17	205-06933 TEMPORARY DITCH INLET PROTECTION	108.000	EACH
18	205-06937 TEMPORARY SILT FENCE	5,645.000	LFT
19	207-08268 SUBGRADE TREATMENT, TYPE IV	13,476.000	SYS
20	211-02050 B BORROW	2,340.000	CYS
21	211-07454 STRUCTURE BACKFILL	12,237.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,596.000	TON
23	304-07493 WIDENING WITH HMA, TYPE B	5,515.000	TON
24	306-08043 MILLING, TRANSITION	803.000	SYS
25	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
26	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,232.000	TON
27	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,379.000	TON
28	402-07441 HMA BASE, TYPE B	1,133.000	TON
29	402-07451 HMA, TYPE B, WEDGE AND LEVEL	4,572.000	TON
30	406-05520 ASPHALT FOR TACK COAT	19.000	TON
31	604-07894 CURB RAMP, CONCRETE, A	42.000	SYS
32	604-07896 CURB RAMP, CONCRETE, B	22.000	SYS
33	604-07901 CURB RAMP, CONCRETE, G	83.000	SYS
34	604-91531 SIDEWALK, CONCRETE, 4 IN.	3,549.000	SYS
35	605-06120 CURB, CONCRETE	1,457.000	LFT
36	605-06120 CURB, CONCRETE	435.000	LFT
37	605-06140 CURB AND GUTTER, CONCRETE	10,964.000	LFT
38	607-06340 PAVED SIDE DITCH, B	100.000	LFT
39	610-07486 HMA FOR APPROACHES, TYPE A	638.000	TON
40	610-08446 PCCP FOR APPROACHES, 6 IN.	5,525.000	SYS
41	611-06497 MAILBOX ASSEMBLY, SINGLE	13.000	EACH
42	611-06498 MAILBOX ASSEMBLY, DOUBLE	10.000	EACH
43	615-06490 RIGHT OF WAY MARKER	88.000	EACH
44	615-06505 MONUMENT, B	11.000	EACH
45	616-02320 GEOTEXTILES	49.000	SYS
46	616-06405 RIPRAP, REVETMENT	40.000	TON
47	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
48	621-06545 FERTILIZER	1.000	TON

CALL ORDER : 160
 LETTING DATE :

CONTRACT ID : R -27433-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
49	621-06554 SEED MIXTURE, U	300.000	LBS
50	621-06565 MULCHING MATERIAL	3.000	TON
51	621-06567 WATER	22.000	KGAL
52	621-06574 SODDING	1,810.000	SYS
53	621-08161 PERMANENT TURF REINFORCEMENT MAT	95.000	SYS
54	702-90915 CONCRETE, A	367.000	CYS
55	703-06029 REINFORCING BARS, EPOXY COATED	28,923.000	LBS
56	703-51030 REINFORCING STEEL	843.000	LBS
57	715-02972 PIPE, SLOTTED VANE DRAIN, 15 IN.	171.000	LFT
58	715-03025 SANITARY MANHOLE	1.000	EACH
59	715-04836 GATE VALVE	32.000	EACH
60	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	2,149.000	LFT
61	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	8,796.000	LFT
62	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	4,009.000	LFT
63	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	761.000	LFT
64	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	824.000	LFT
65	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	489.000	LFT
66	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	775.000	LFT
67	715-06691 CONCRETE ANCHOR, 96 IN.	1.000	EACH
68	715-06910 PIPE, TYPE 2, CIRCULAR, 96 IN.	63.000	LFT
69	715-07794 WATER MAIN CONNECTIONS	9.000	EACH
70	715-07794 WATER MAIN CONNECTIONS	5.000	EACH
71	715-07794 WATER MAIN CONNECTIONS	1.000	EACH
72	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	161.000	TON
73	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	171.000	TON
74	715-08474 SEWER MAIN	114.000	LFT
75	715-08474 SEWER MAIN	118.000	LFT
76	715-46040 PIPE END SECTION, 36 IN.	1.000	EACH
77	715-90052 LIFT STATION	LUMP	LUMP
78	715-91739 WATER MAIN, DUCTILE IRON, 8 IN.	6,721.000	LFT
79	715-98265 WATER MAIN, DUCTILE IRON, 4 IN.	151.000	LFT
80	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,280.000	LFT
81	718-52610 AGGREGATE FOR UNDERDRAINS	778.000	CYS
82	718-99153 GEOTEXTILES FOR UNDERDRAIN	8,322.000	SYS
83	720-06607 SLOTTED DRAIN CLEANOUT	9.000	EACH
84	720-44000 CASTING, ADJUST TO GRADE	31.000	EACH
85	720-45030 INLET, E7	1.000	EACH
86	720-45035 INLET, F7	5.000	EACH
87	720-45075 INLET, R13	1.000	EACH
88	720-45275 PIPE CATCH BASIN, 24 IN.	2.000	EACH
89	720-45410 MANHOLE, C4	6.000	EACH
90	720-90129 MANHOLE, J2	15.000	EACH
91	720-90984 MANHOLE, C2	5.000	EACH
92	720-95422 MANHOLE, J4	7.000	EACH
93	720-98174 INLET, B15	45.000	EACH
94	720-98555 INLET, C15	34.000	EACH
95	731-93945 FACE PANELS, CONCRETE	5,900.000	SFT
96	731-93946 WALL ERECTION	5,900.000	SFT

CALL ORDER : 160
 LETTING DATE :

CONTRACT ID : R -27433-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ADDED TRAVEL LANES			
97	731-93947 LEVELING PAD, CONCRETE	289.000	LFT
98	732-04987 CONNECTION	36.000	EACH
99	732-04987 CONNECTION	5.000	EACH
100	732-91739 WATER MAIN, DUCTILE IRON, 8 IN.	6,721.000	LFT
101	732-91742 FIRE HYDRANT	15.000	EACH
102	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
103	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	19,504.000	LFT
104	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,730.000	LFT
105	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	48.000	LFT
106	801-06625 DETOUR ROUTE MARKER ASSEMBLY	38.000	EACH
107	801-06640 CONSTRUCTION SIGN, A	37.000	EACH
108	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
109	801-07118 BARRICADE, III-A	144.000	LFT
110	801-07119 BARRICADE, III-B	24.000	LFT
111	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	335.000	LFT
112	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	281.000	SFT
113	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
114	805-01842 HANDHOLE, SIGNAL	9.000	EACH
115	805-02069 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM	2.000	EACH
116	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	2.000	EACH
117	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
118	805-02151 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 12 IN.	8.000	EACH
119	805-02855 SIGNAL SUPPORT FOUNDATION, 2 FT. 6 IN. X 2 FT. 6 IN. X 6 FT.	2.000	EACH
120	805-05870 SIGNAL SUPPORT FOUNDATION	2.000	EACH
121	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,060.000	LFT
122	805-78060 CONTROLLER AND CABINET, MENU DRIVEN, 4 PHASE	1.000	EACH
123	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	14.000	EACH
124	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	2.000	EACH
125	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
126	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
127	805-78420 DISCONNECT HANGER	4.000	EACH
128	805-78445 SIGNAL SERVICE	2.000	EACH
129	805-78467 SIGNAL CABLE, 3C 8GA.	110.000	LFT
130	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	8,090.000	LFT
131	805-78480 SIGNAL CABLE, 3C 14GA.	810.000	LFT
132	805-78485 SIGNAL CABLE, 5C 14GA.	1,830.000	LFT
133	805-78490 SIGNAL CABLE, 7C 14GA.	560.000	LFT
134	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,510.000	LFT
135	805-78785 SIGNAL DETECTOR HOUSING	15.000	EACH
136	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,310.000	LFT
137	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
138	805-78930 CONTROLLER CABINET FOUNDATION, M	1.000	EACH
139	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000	EACH
140	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	8.000	EACH
141	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,008.000	LFT
142	808-06716 LINE, REMOVE	1,290.000	LFT
143	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,828.000	LFT
144	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	12,168.000	LFT

CALL ORDER : 160
 LETTING DATE :

CONTRACT ID : R -27433-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
145 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	303.000	LFT
146 808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,269.000	LFT
147 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	23.000	EACH
148 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	21.000	EACH

CALL ORDER : 170
 LETTING DATE :

CONTRACT ID : R -27488-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE CORRECTION PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	10.000	MOS
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
8	203-02000 EXCAVATION, COMMON	4,985.000	m3
9	205-06932 TEMPORARY CHECK DAM, STRAW BALES	152.000	m
10	205-06937 TEMPORARY SILT FENCE	145.000	m
11	207-08263 SUBGRADE TREATMENT, TYPE IA	3,597.000	m2
12	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,861.000	m2
13	211-07454 STRUCTURE BACKFILL	37.000	m3
14	303-01180 COMPACTED AGGREGATE, NO. 53	2,019.000	Mg
15	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
16	402-07432 HMA SURFACE, TYPE A	241.000	Mg
17	402-07433 HMA SURFACE, TYPE B	343.000	Mg
18	402-07435 HMA INTERMEDIATE, TYPE A	489.000	Mg
19	402-07438 HMA INTERMEDIATE, TYPE B	540.000	Mg
20	402-07441 HMA BASE, TYPE B	1,753.000	Mg
21	404-05514 SEAL COAT, 5	550.000	m2
22	406-05521 ASPHALT FOR TACK COAT	13,850.000	m2
23	610-07486 HMA FOR APPROACHES, TYPE A	27.000	Mg
24	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
25	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
26	615-06490 RIGHT OF WAY MARKER	27.000	EACH
27	615-06505 MONUMENT, B	6.000	EACH
28	616-02320 GEOTEXTILES	201.000	m2
29	616-06451 RIPRAP, UNIFORM	163.000	Mg
30	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
31	621-01371 SEED MIXTURE, LEGUME, 2	19.000	kg
32	621-01956 SEED MIXTURE, LEGUME, 1	86.000	kg
33	621-06545 FERTILIZER	1.000	Mg
34	621-06553 SEED MIXTURE, R	108.000	kg
35	621-06557 SEED MIXTURE, T	26.000	kg
36	621-06565 MULCHING MATERIAL	4.000	Mg
37	621-06567 WATER	24.000	kL
38	621-06574 SODDING	1,091.000	m2
39	713-51334 TEMPORARY PIPE AND APPROACHES	LUMP	LUMP
40	715-05123 PIPE, TYPE 1, CIRCULAR, 600 mm	17.000	m
41	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	46.000	m
42	715-46005 PIPE END SECTION, 375 mm	6.000	EACH
43	715-46020 PIPE END SECTION, 600 mm	2.000	EACH
44	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
45	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
46	801-06645 CONSTRUCTION SIGN, B	26.000	EACH
47	801-06649 TEMPORARY RAISED PAVEMENT MARKER, 1	47.000	EACH
48	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 170
 LETTING DATE :

CONTRACT ID : R -27488-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE CORRECTION PROJECT		
49	801-07118 BARRICADE, III-A	38.000	m
50	801-96495 TEMPORARY PAVEMENT MARKING, SOLID, YELLOW, 150 mm	890.000	m
51	801-96497 TEMPORARY PAVEMENT MARKING, SOLID, WHITE, 600 mm	890.000	m
52	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	2.000	EACH
53	802-02489 SIGN POST, SQUARE, REINFORCED ANCHOR BASE	6.000	m
54	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	2.000	EACH
55	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
56	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm AMBER	4.000	EACH
57	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm RED	4.000	EACH
58	805-78420 DISCONNECT HANGER	1.000	EACH
59	805-78445 SIGNAL SERVICE	1.000	EACH
60	805-78467 SIGNAL CABLE, 3C 8GA.	20.000	m
61	805-78485 SIGNAL CABLE, 5C 14GA.	100.000	m
62	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	2.000	EACH
63	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 600 mm	19.000	m
64	808-06712 LINE, PAINT, BROKEN, YELLOW, 100 mm	64.000	m
65	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	795.000	m
66	808-06714 LINE, PAINT, SOLID, YELLOW, 100 mm	524.000	m
67	808-06716 LINE, REMOVE	240.000	m

CALL ORDER : 190
 LETTING DATE :

CONTRACT ID : R -27847-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, PEDESTRIAN/BICYCLE FACILITY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	9.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
5	203-02000 EXCAVATION, COMMON	4,207.000	CYS
6	203-02070 BORROW	1,269.000	CYS
7	203-51223 EXCAVATION, WATERWAY	972.000	CYS
8	205-06933 TEMPORARY DITCH INLET PROTECTION	6.000	EACH
9	205-06937 TEMPORARY SILT FENCE	9,205.000	LFT
10	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	110.000	CYS
11	210-04181 BICYCLE RACK	3.000	EACH
12	210-06986 PAVEMENT	30.000	SYS
13	211-06467 AGGREGATE FOR END BENT BACKFILL	42.000	CYS
14	211-07454 STRUCTURE BACKFILL	134.000	CYS
15	212-06282 STOCKPILED SELECTED MATERIAL, SALVAGED	5,911.000	CYS
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5,178.500	TON
17	304-07489 HMA PATCHING, TYPE A	22.000	TON
18	304-07492 WIDENING WITH HMA, TYPE A	20.200	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN.	64.900	SYS
20	402-07432 HMA SURFACE, TYPE A	590.400	TON
21	402-07435 HMA INTERMEDIATE, TYPE A	1,180.900	TON
22	402-07440 HMA BASE, TYPE A	5.800	TON
23	402-07450 HMA, TYPE A, WEDGE AND LEVEL	267.100	TON
24	406-05520 ASPHALT FOR TACK COAT	2.800	TON
25	604-01920 CONCRETE PAVERS	24.300	SYS
26	604-07897 CURB RAMP, CONCRETE, C	28.000	SYS
27	604-07900 CURB RAMP, CONCRETE, F	144.300	SYS
28	604-90256 SIDEWALK, CONCRETE, 6 IN.	12.600	SYS
29	604-90256 SIDEWALK, CONCRETE, 6 IN.	163.000	SYS
30	604-90256 SIDEWALK, CONCRETE, 6 IN.	13.400	SYS
31	604-91531 SIDEWALK, CONCRETE, 4 IN.	299.000	SYS
32	604-91531 SIDEWALK, CONCRETE, 4 IN.	114.700	SYS
33	605-06125 CURB, CONCRETE, MODIFIED	28.000	LFT
34	611-03671 TRASH RECEPTACLE	4.000	EACH
35	616-02320 GEOTEXTILES	717.000	SYS
36	616-06405 RIPRAP, REVETMENT	468.000	TON
37	621-06559 MULCHED SEEDING, R	16,468.800	SYS
38	621-08161 PERMANENT TURF REINFORCEMENT MAT	319.400	SYS
39	621-98038 MULCH, HARDWOOD SHREDDED BARK	130.000	CYS
40	622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN.	10.000	EACH
41	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.	10.000	EACH
42	622-05654 PLANT, PERENNIAL	277.000	EACH
43	701-03753 PILE, CONCRETE, STEEL SHELL ENCASED, 0.209 IN., 14 IN.	525.000	LFT
44	702-51005 CONCRETE, A, SUBSTRUCTURE	40.800	CYS
45	703-51030 REINFORCING STEEL	4,908.000	LBS
46	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP
47	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP
48	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP

CALL ORDER : 190
 LETTING DATE :

CONTRACT ID : R -27847-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, PEDESTRIAN/BICYCLE FACILITY		
49	711-90932 EDGING, STEEL	300.000	LFT
50	712-03017 PARK BENCH	6.000	EACH
51	712-05098 TIMBER	1.000	EACH
52	713-08148 BRIDGE SUPPORTS	LUMP	LUMP
53	714-04802 CONCRETE MODULAR BLOCK WALL	6.000	SYS
54	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	257.000	LFT
55	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	44.000	LFT
56	715-05407 PIPE, END BENT DRAIN, 6 IN.	240.000	LFT
57	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
58	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
59	720-45235 CATCH BASIN, E7	3.000	EACH
60	720-45250 CATCH BASIN, K10	2.000	EACH
61	720-45275 PIPE CATCH BASIN, 24 IN.	1.000	EACH
62	731-93946 WALL ERECTION	54.000	SFT
63	731-93947 LEVELING PAD, CONCRETE	43.000	LFT
64	732-07653 COARSE AGGREGATE, NO. 8	2.000	TON
65	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
66	801-06645 CONSTRUCTION SIGN, B	7.000	EACH
67	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
68	802-03896 BOLLARD	15.000	EACH
69	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	240.000	LFT
70	802-07060 SIGN, SHEET, RELOCATE	6.000	EACH
71	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	112.800	SFT
72	805-06101 FOUNDATION	4.000	EACH
73	808-02977 TRANSVERSE MARKING, THERMOPLASTIC, BIKE SYMBOL	3.000	EACH
74	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	188.000	LFT
75	808-04096 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (LANE)	3.000	EACH
76	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	982.000	LFT
77	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,115.000	LFT
78	808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	548.000	LFT
79	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,230.000	LFT
80	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	63.000	LFT

CALL ORDER : 200
 LETTING DATE :

CONTRACT ID : R -27987-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION, ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	30.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	5.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	150.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	33,000.000	m2
13	202-02241 GUARDRAIL, REMOVE	685.000	m
14	202-02278 CURB, CONCRETE, REMOVE	1,310.000	m
15	202-04089 SIGN, SHEET, REMOVE	97.000	EACH
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
18	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
19	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
20	202-52710 SIDEWALK, CONCRETE, REMOVE	195.000	m2
21	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
22	202-99383 TERMINAL JOINT, REMOVE	15.000	m
23	203-02000 EXCAVATION, COMMON	148,878.000	m3
24	203-02070 BORROW	47.000	m3
25	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	464.000	Mg
26	205-06933 TEMPORARY DITCH INLET PROTECTION	65.000	EACH
27	205-06934 TEMPORARY MULCHING	38.200	Mg
28	205-06936 TEMPORARY SEDIMENT TRAP	162.800	Mg
29	205-06937 TEMPORARY SILT FENCE	4,331.000	m
30	206-93520 TEMPORARY SHEET PILING	46.800	m2
31	207-08267 SUBGRADE TREATMENT, TYPE IIIA	38,800.000	m2
32	207-08268 SUBGRADE TREATMENT, TYPE IV	111,540.000	m2
33	211-07454 STRUCTURE BACKFILL	14,909.000	m3
34	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	11,200.000	Mg
35	302-07455 DENSE GRADED SUBBASE	52.000	m3
36	303-07449 COMPACTED AGGREGATE, NO. 73	57.000	Mg
37	304-07490 HMA PATCHING, TYPE B	111.300	Mg
38	306-08043 MILLING, TRANSITION	1,020.000	m2
39	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
40	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	410.000	Mg
41	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	1,622.000	Mg
42	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	7,277.000	Mg
43	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	2,733.000	Mg
44	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 MM	11,909.000	Mg
45	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 MM	1,506.000	Mg
46	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	13,243.000	Mg
47	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	44,495.000	Mg
48	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	18,341.000	Mg

CALL ORDER : 200
 LETTING DATE :

CONTRACT ID : R -27987-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION, ADDED TRAVEL LANES		
49	402-07453 HMA FOR TEMPORARY PAVEMENT	28,383.000	Mg
50	406-05520 ASPHALT FOR TACK COAT	167.100	Mg
51	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
52	601-01839 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 6	1.000	EACH
53	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
54	601-02206 TEMPORARY GUARDRAIL, W BEAM, 1.905 m SPACING	95.250	m
55	601-02207 TEMPORARY GUARD RAIL TRANSITION, VH, 1.905 m SPACING	2.000	EACH
56	601-06854 GUARDRAIL, W-BEAM, NESTED	4.000	EACH
57	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	5.000	EACH
58	601-94689 GUARDRAIL END TREATMENT, OS	14.000	EACH
59	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	569.600	m
60	602-06729 BARRIER DELINEATOR	14.000	EACH
61	603-02940 FENCE GATE, CHAIN LINK, 1820 mm X 6.1 m	1.000	EACH
62	603-06045 FENCE, CHAIN LINK, 1220 mm	33.500	m
63	603-92636 FENCE, CHAIN LINK, 1830 mm	525.000	m
64	604-07900 CURB RAMP, CONCRETE, F	240.000	m2
65	604-07901 CURB RAMP, CONCRETE, G	520.000	m2
66	604-07902 CURB RAMP, CONCRETE, H	85.000	m2
67	604-91531 SIDEWALK, CONCRETE, 100 mm	10,035.000	m2
68	605-06120 CURB, CONCRETE	615.000	m
69	605-06140 CURB AND GUTTER, CONCRETE	7,160.000	m
70	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	1,445.000	m
71	605-06215 CENTER CURB, D, CONCRETE	310.000	m
72	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	349.800	m2
73	610-07487 HMA FOR APPROACHES, TYPE B	175.000	Mg
74	610-07712 PCCP FOR APPROACHES, 150 mm	7,494.000	m2
75	611-06497 MAILBOX ASSEMBLY, SINGLE	68.000	EACH
76	615-06490 RIGHT OF WAY MARKER	212.000	EACH
77	615-06505 MONUMENT, B	19.000	EACH
78	615-06510 MONUMENT, C	5.000	EACH
79	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
80	615-06530 POST, BENCHMARK	2.000	EACH
81	616-02320 GEOTEXTILES	7,702.000	m2
82	616-05688 RIPRAP, CLASS 1	501.800	Mg
83	616-05689 RIPRAP, CLASS 2	902.400	Mg
84	616-06405 RIPRAP, REVETMENT	1,849.400	Mg
85	616-06451 RIPRAP, UNIFORM	96.100	Mg
86	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
87	619-61505 CLEAN AND PAINT END DIAPHRAGMS EXPANSION SHOES AND BEAM ENDS	LUMP	LUMP
88	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
89	621-06545 FERTILIZER	13.000	Mg
90	621-06553 SEED MIXTURE, R	1,750.000	kg
91	621-06554 SEED MIXTURE, U	980.000	kg
92	621-06557 SEED MIXTURE, T	1,146.000	kg
93	621-06565 MULCHING MATERIAL	65.000	Mg
94	621-06567 WATER	3,154.000	kL
95	621-06570 TOP SOIL	16,060.000	m3
96	621-06575 SODDING, NURSERY	17,520.000	m2

CALL ORDER : 200
 LETTING DATE :

CONTRACT ID : R -27987-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION, ADDED TRAVEL LANES		
97	702-51863 FIELD DRILLED HOLE IN CONCRETE	1,356.000	EACH
98	703-51032 REINFORCING STEEL, EPOXY COATED	13,076.000	kg
99	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	170.000	EACH
100	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	88.000	EACH
101	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
102	706-51020 CONCRETE, C, RAILING	29.200	m3
103	709-51821 SURFACE SEAL	LUMP	LUMP
104	714-06613 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 4800 mm X 1800 mm	36.500	m
105	714-93978 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1200 mm x 600 mm	6.800	m
106	714-99346 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 900 mm x 600 mm	6.100	m
107	714-99348 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1500 mm x 900 mm	114.400	m
108	715-02397 SAFETY METAL END SECTION, 4:1, 900 mm	4.000	EACH
109	715-04612 PIPE	18.300	m
110	715-04612 PIPE	6.000	m
111	715-04612 PIPE	3.000	m
112	715-04855 PIPE END SECTION, 1050 mm	2.000	EACH
113	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	509.800	m
114	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	7,301.000	m
115	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	43.200	m
116	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	3,194.700	m
117	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	328.900	m
118	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	1,091.600	m
119	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	1,123.500	m
120	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	1,171.900	m
121	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	65.000	m
122	715-05165 PIPE, TYPE 2, CIRCULAR, 1800 mm	7.000	m
123	715-46000 PIPE END SECTION, 300 mm	8.000	EACH
124	715-46005 PIPE END SECTION, 375 mm	36.000	EACH
125	715-46010 PIPE END SECTION, 450 mm	6.000	EACH
126	715-46020 PIPE END SECTION, 600 mm	4.000	EACH
127	715-46030 PIPE END SECTION, 750 mm	4.000	EACH
128	715-46040 PIPE END SECTION, 900 mm	5.000	EACH
129	718-06528 OUTLET PROTECTOR, 1	5.000	EACH
130	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
131	718-52610 AGGREGATE FOR UNDERDRAINS	1,609.000	m3
132	718-99153 GEOTEXTILES FOR UNDERDRAIN	23,108.000	m2
133	720-01092 MANHOLE, J15, MODIFIED	80.000	EACH
134	720-03194 MANHOLE	1.000	EACH
135	720-04574 MANHOLE, J-5	2.000	EACH
136	720-08241 MANHOLE, K15, MODIFIED	4.000	EACH
137	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
138	720-45030 INLET, E7	16.000	EACH
139	720-45035 INLET, F7	8.000	EACH
140	720-45042 INLET, HA5	7.000	EACH
141	720-45105 INLET, A2, MODIFIED	2.000	EACH
142	720-45130 INLET, E7, MODIFIED	6.000	EACH
143	720-45410 MANHOLE, C4	5.000	EACH
144	720-45510 MANHOLE, C4, MODIFIED	6.000	EACH

CALL ORDER : 200
 LETTING DATE :

CONTRACT ID : R -27987-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION, ADDED TRAVEL LANES		
145	720-93409 INLET, B15, MODIFIED	108.000	EACH
146	720-93411 INLET, C15, MODIFIED	26.000	EACH
147	720-94157 MANHOLE, C	2.000	EACH
148	720-95422 MANHOLE, J4	3.000	EACH
149	720-97865 MANHOLE, C2, MODIFIED	2.000	EACH
150	720-98555 INLET, C15	27.000	EACH
151	723-06660 WINGWALL	58.300	m2
152	724-03276 EXPANSION JOINT SEALING SYSTEM	38.800	m
153	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	50.000	EACH
154	801-01505 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (ONLY)	45.000	EACH
155	801-02595 CONTROLLER, RESET TIMING	15.000	EACH
156	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
157	801-04308 ROAD CLOSURE SIGN ASSEMBLY	17.000	EACH
158	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	20,540.000	m
159	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	41,175.000	m
160	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	145.000	m
161	801-06539 TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	LUMP	LUMP
162	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 600 mm	360.000	m
163	801-06625 DETOUR ROUTE MARKER ASSEMBLY	57.000	EACH
164	801-06640 CONSTRUCTION SIGN, A	149.000	EACH
165	801-06645 CONSTRUCTION SIGN, B	14.000	EACH
166	801-06710 FLASHING ARROW SIGN	730.000	DAY
167	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
168	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	9.000	EACH
169	801-07119 BARRICADE, III-B	756.000	m
170	801-08388 TEMPORARY TRAFFIC BARRIER	281.000	m
171	801-08389 TEMPORARY TRAFFIC BARRIER, ANCHORED	610.000	m
172	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	6.000	EACH
173	801-94295 SIGNAL HEAD, RELOCATE	176.000	EACH
174	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	44.000	m
175	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	330.000	m
176	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	38.000	m2
177	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	58.000	m2
178	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	5.000	m2
179	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	20.000	EACH
180	805-01842 HANDHOLE, SIGNAL	43.000	EACH
181	805-01879 SIGNAL SERVICE	1.000	EACH
182	805-01879 SIGNAL SERVICE	4.000	EACH
183	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
184	805-04951 PLATE	1.000	EACH
185	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	2,500.000	m
186	805-08494 RADIO SPREAD SPECTRUM	5.000	EACH
187	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	5.000	EACH
188	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	40.000	EACH
189	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	4.000	EACH
190	805-78415 SPAN, CATENARY, AND TETHER	20.000	EACH
191	805-78420 DISCONNECT HANGER	20.000	EACH
192	805-78467 SIGNAL CABLE, 3C 8GA.	50.000	m

CALL ORDER : 200
 LETTING DATE :

CONTRACT ID : R -27987-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION, ADDED TRAVEL LANES		
193	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	5,480.000	m
194	805-78485 SIGNAL CABLE, 5C 14GA.	670.000	m
195	805-78490 SIGNAL CABLE, 7C 14GA.	1,075.000	m
196	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	3,530.000	m
197	805-78785 SIGNAL DETECTOR HOUSING	44.000	EACH
198	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,950.000	m
199	805-78925 CONTROLLER CABINET FOUNDATION, P1	5.000	EACH
200	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
201	805-96261 FIBER OPTIC CABLE, AERIAL	5,970.000	m
202	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	185.000	m
203	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	1,735.000	m
204	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	2,060.000	m
205	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	2,100.000	m
206	808-06716 LINE, REMOVE	9,140.000	m
207	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	850.000	m
208	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	7,675.000	m
209	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	190.000	m
210	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	370.000	m
211	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm	1,440.000	m
212	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	68.000	EACH
213	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	46.000	EACH
214	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	190.000	EACH
215	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	635.000	EACH
216	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	1,675.000	m

CALL ORDER : 210
 LETTING DATE :

CONTRACT ID : R -28017-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 STORM SEWER CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	36.000	MOS
3	105-07577 CELLULAR SERVICE	36.000	MOS
4	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	584.000	m2
11	202-05545 REGULATED MATERIALS, DISPOSE, C	3,050.000	m3
12	202-05550 REGULATED MATERIALS, REMOVE, C	3,050.000	m3
13	202-05555 REGULATED MATERIALS, TRANSPORT, C	3,050.000	m3
14	202-07602 TESTING FOR WASTE, B	4.000	EACH
15	202-07603 TESTING FOR WASTE, C	450.000	EACH
16	202-08429 REGULATED MATERIALS, DISPOSE, B	500.000	L
17	202-08430 REGULATED MATERIALS, REMOVE, B	500.000	L
18	202-08431 REGULATED MATERIALS, TRANSPORT, B	500.000	L
19	202-74070 OVERHEAD SIGN STRUCTURE, CABLE SPAN, REMOVE	1.000	EACH
20	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
21	203-02000 EXCAVATION, COMMON	37,908.000	m3
22	205-03371 SEDIMENT REMOVE	500.000	m3
23	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	230.000	Mg
24	205-06933 TEMPORARY DITCH INLET PROTECTION	35.000	EACH
25	205-06936 TEMPORARY SEDIMENT TRAP	43.500	Mg
26	205-06937 TEMPORARY SILT FENCE	100.000	m
27	207-08263 SUBGRADE TREATMENT, TYPE IA	66,699.000	m2
28	211-07454 STRUCTURE BACKFILL	29,836.000	m3
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	8,395.500	Mg
30	304-07489 HMA PATCHING, TYPE A	338.000	Mg
31	306-08034 MILLING, ASPHALT, 38 mm	9,530.400	m2
32	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
33	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	3,929.000	Mg
34	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	6,535.000	Mg
35	401-07418 QC/QA-HMA, 3, 76, BASE, 25.0 mm	19,047.000	Mg
36	401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm	9,477.000	Mg
37	402-07433 HMA SURFACE, TYPE B	1,370.000	Mg
38	402-07434 HMA SURFACE, TYPE C	736.000	Mg
39	402-07442 HMA BASE, TYPE C	2,208.000	Mg
40	406-05520 ASPHALT FOR TACK COAT	58.100	Mg
41	603-04124 FENCE GATE, CHAIN LINK, 1200 mm X 1.2 m	1.000	EACH
42	603-06045 FENCE, CHAIN LINK, 1220 mm	10.700	m
43	604-07897 CURB RAMP, CONCRETE, C	10.200	m2
44	604-07900 CURB RAMP, CONCRETE, F	555.100	m2
45	604-07901 CURB RAMP, CONCRETE, G	112.600	m2
46	604-07902 CURB RAMP, CONCRETE, H	150.000	m2
47	604-44251 STEPS, CONCRETE	30.800	m3
48	604-91531 SIDEWALK, CONCRETE, 100 mm	8,282.000	m2

CALL ORDER : 210
 LETTING DATE :

CONTRACT ID : R -28017-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 STORM SEWER CONSTRUCTION			
49	605-06120 CURB, CONCRETE	1,087.000	m
50	605-06140 CURB AND GUTTER, CONCRETE	7.000	m
51	605-06150 CURB AND GUTTER, C, CONCRETE	5,605.600	m
52	610-07486 HMA FOR APPROACHES, TYPE A	486.800	Mg
53	610-07487 HMA FOR APPROACHES, TYPE B	7,033.300	Mg
54	610-08446 PCCP FOR APPROACHES, 150 mm	4,572.100	m2
55	611-06497 MAILBOX ASSEMBLY, SINGLE	13.000	EACH
56	615-06490 RIGHT OF WAY MARKER	60.000	EACH
57	615-06496 PARKING BARRIER	30.000	EACH
58	615-06505 MONUMENT, B	41.000	EACH
59	616-02320 GEOTEXTILES	50.900	m2
60	616-06405 RIPRAP, REVETMENT	23.800	Mg
61	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	13.000	EACH
62	621-06545 FERTILIZER	2.400	Mg
63	621-06553 SEED MIXTURE, R	461.000	kg
64	621-06557 SEED MIXTURE, T	265.200	kg
65	621-06560 MULCHED SEEDING, U	2,290.000	m2
66	621-06565 MULCHING MATERIAL	13.300	Mg
67	621-06567 WATER	362.500	kL
68	621-06575 SODDING, NURSERY	20,112.300	m2
69	714-04802 CONCRETE MODULAR BLOCK WALL	389.000	m2
70	714-07539 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 2400 mm X 600 mm	27.500	m
71	714-44240 CONCRETE, A, STRUCTURES	26.000	m3
72	715-04855 PIPE END SECTION, 1050 mm	3.000	EACH
73	715-05019 PIPE, TYPE 1, CIRCULAR, 900 mm	21.000	m
74	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	1,722.800	m
75	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	9,795.000	m
76	715-05049 PIPE, TYPE 4, CIRCULAR, 200 mm	150.000	m
77	715-05051 PIPE, TYPE 4, CIRCULAR, 250 mm	50.000	m
78	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	183.000	m
79	715-05115 PIPE, TYPE 1, CIRCULAR, 150 mm	50.000	m
80	715-05116 PIPE, TYPE 1, CIRCULAR, 200 mm	50.000	m
81	715-05117 PIPE, TYPE 1, CIRCULAR, 250 mm	50.000	m
82	715-05127 PIPE, TYPE 1, CIRCULAR, 1050 mm	29.000	m
83	715-05147 PIPE, TYPE 2, CIRCULAR, 200 mm	5.000	m
84	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	1,769.700	m
85	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	1,052.000	m
86	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	406.000	m
87	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	402.000	m
88	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	451.000	m
89	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	793.000	m
90	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	1,910.000	m
91	715-05168 PIPE, TYPE 3, CIRCULAR, 300 mm	5.000	m
92	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	332.000	m
93	715-05171 PIPE, TYPE 3, CIRCULAR, 450 mm	131.500	m
94	715-05177 PIPE, TYPE 3, CIRCULAR, 900 mm	122.500	m
95	715-05203 PIPE, TYPE 4, CIRCULAR, 100 mm	7.000	m
96	715-05335 PIPE, TYPE 2, DEFORMED, MIN. AREA 0.47 m2	65.000	m

CALL ORDER : 210
 LETTING DATE :

CONTRACT ID : R -28017-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 STORM SEWER CONSTRUCTION			
97	715-05338 PIPE, TYPE 2, DEFORMED, MIN. AREA 0.68 m2	118.000	m
98	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	3,648.000	Mg
99	715-46000 PIPE END SECTION, 300 mm	1.000	EACH
100	715-46005 PIPE END SECTION, 375 mm	35.000	EACH
101	715-46010 PIPE END SECTION, 450 mm	10.000	EACH
102	715-46040 PIPE END SECTION, 900 mm	3.000	EACH
103	715-97691 GRATED BOX END SECTION, I, 3:1, 900 mm	2.000	EACH
104	716-02965 PIPE CASING, 750 mm, JACK AND BORE	19.500	m
105	716-04832 PIPE CASING,	40.000	m
106	716-04832 PIPE CASING,	72.000	m
107	716-04832 PIPE CASING,	33.000	m
108	718-06528 OUTLET PROTECTOR, 1	30.000	EACH
109	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
110	718-52610 AGGREGATE FOR UNDERDRAINS	2,116.000	m3
111	718-99153 GEOTEXTILES FOR UNDERDRAIN	21,252.000	m2
112	720-04721 MANHOLE, K	2.000	EACH
113	720-44000 CASTING, ADJUST TO GRADE	104.000	EACH
114	720-44296 CAP INLET	1.000	EACH
115	720-45035 INLET, F7	1.000	EACH
116	720-45080 INLET, S14	4.000	EACH
117	720-45250 CATCH BASIN, K10	1.000	EACH
118	720-45275 PIPE CATCH BASIN, 600 mm	53.000	EACH
119	720-45410 MANHOLE, C4	83.000	EACH
120	720-93411 INLET, C15, MODIFIED	2.000	EACH
121	720-94612 MANHOLE, K4	48.000	EACH
122	720-95422 MANHOLE, J4	49.000	EACH
123	720-98174 INLET, B15	201.000	EACH
124	720-98555 INLET, C15	36.000	EACH
125	731-93946 WALL ERECTION	389.000	m2
126	731-93947 LEVELING PAD, CONCRETE	320.000	m
127	732-07653 COARSE AGGREGATE, NO. 8	52.000	Mg
128	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	10.000	EACH
129	801-04308 ROAD CLOSURE SIGN ASSEMBLY	58.000	EACH
130	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	5,000.000	m
131	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	100.000	m
132	801-06625 DETOUR ROUTE MARKER ASSEMBLY	56.000	EACH
133	801-06640 CONSTRUCTION SIGN, A	107.000	EACH
134	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
135	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
136	801-07118 BARRICADE, III-A	309.600	m
137	801-07119 BARRICADE, III-B	133.200	m
138	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	936.000	m
139	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	100.561	m2
140	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	66.690	m2
141	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	3.260	m2
142	804-93726 DELINEATOR	30.000	EACH
143	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	14.000	EACH
144	805-01842 HANDHOLE, SIGNAL	12.000	EACH

CALL ORDER : 210
 LETTING DATE :

CONTRACT ID : R -28017-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	STORM SEWER CONSTRUCTION		
145	805-01879 SIGNAL SERVICE	4.000	EACH
146	805-01893 MAINTAINING TRAFFIC SIGNAL	LUMP	LUMP
147	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
148	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	3,388.000	m
149	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	595.000	m
150	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	3.000	EACH
151	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
152	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm RED	8.000	EACH
153	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	24.000	EACH
154	805-78415 SPAN, CATENARY, AND TETHER	13.000	EACH
155	805-78420 DISCONNECT HANGER	13.000	EACH
156	805-78467 SIGNAL CABLE, 3C 8GA.	65.000	m
157	805-78485 SIGNAL CABLE, 5C 14GA.	764.000	m
158	805-78490 SIGNAL CABLE, 7C 14GA.	1,132.000	m
159	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,128.000	m
160	805-78785 SIGNAL DETECTOR HOUSING	22.000	EACH
161	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,188.000	m
162	805-78925 CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
163	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	14.000	EACH
164	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	12.000	EACH
165	805-96121 PEDESTRIAN PUSH BUTTON AND SIGN	12.000	EACH
166	808-04298 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (R X R)	4.000	EACH
167	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	4,053.000	m
168	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	267.000	m
169	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	8,831.000	m
170	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	367.000	m
171	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm	478.000	m
172	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	26.000	EACH
173	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	22.000	EACH
174	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	250.000	EACH
175	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	320.000	EACH

CALL ORDER : 228
 LETTING DATE :

CONTRACT ID : R -28274-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, STREETScape			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
2	105-07039	FIELD OFFICE, B	18.000
3	108-01614	PARTNERING OVERHEAD	LUMP
4	109-08440	QUALITY ADJUSTMENTS, HMA	1.000
5	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000
6	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000
7	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
8	201-52370	CLEARING RIGHT OF WAY	LUMP
9	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP
10	202-02240	PAVEMENT REMOVAL	11,200.000
11	202-02245	TREE, 6 IN., REMOVE	2.000
12	202-02250	TREE, 10 IN., REMOVE	1.000
13	202-02255	TREE, 18 IN., REMOVE	4.000
14	202-02260	TREE, 30 IN., REMOVE	1.000
15	202-02278	CURB, CONCRETE, REMOVE	4,600.000
16	202-04089	SIGN, SHEET, REMOVE	35.000
17	202-06580	CONTAMINATED SOIL, REMOVE	1.000
18	202-52710	SIDEWALK, CONCRETE, REMOVE	3,120.000
19	202-74070	OVERHEAD SIGN STRUCTURE, CABLE SPAN, REMOVE	1.000
20	202-91010	TREE, 24 IN., REMOVE	2.000
21	202-91385	INLET, REMOVE	20.000
22	202-93047	MANHOLE, REMOVE	7.000
23	202-96133	PIPE, REMOVE	400.000
24	202-96151	TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP
25	202-96632	TRAFFIC SIGNALS AND EQUIPMENT, REMOVE	1.000
26	203-02000	EXCAVATION, COMMON	13,307.000
27	205-06932	TEMPORARY CHECK DAM, STRAW BALES	24.000
28	205-06933	TEMPORARY DITCH INLET PROTECTION	4.000
29	205-06937	TEMPORARY SILT FENCE	105.000
30	207-08268	SUBGRADE TREATMENT, TYPE IV	16,900.000
31	210-04181	BICYCLE RACK	2.000
32	210-05106	CONCRETE	84.000
33	210-05106	CONCRETE	84.000
34	210-05106	CONCRETE	8.000
35	211-07454	STRUCTURE BACKFILL	2,805.000
36	213-08058	FLOWABLE BACKFILL	2,975.000
37	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	1,434.000
38	304-07489	HMA PATCHING, TYPE A	910.000
39	401-07327	QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	1,117.000
40	401-07397	QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	1,862.000
41	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	6,322.000
42	401-08333	QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	1,792.000
43	402-07453	HMA FOR TEMPORARY PAVEMENT	405.000
44	406-05520	ASPHALT FOR TACK COAT	13.000
45	603-06065	FENCE, CHAIN LINK, RESET	90.000
46	604-01920	CONCRETE PAVERS	450.000
47	604-04439	TEXTURED CONCRETE PAVEMENT	280.000
48	604-06070	SIDEWALK, CONCRETE	4,093.000

CALL ORDER : 228
 LETTING DATE :

CONTRACT ID : R -28274-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
49	604-06367 JOINT MATERIAL	3,100.000	LFT
50	604-07894 CURB RAMP, CONCRETE, A	77.000	SYS
51	604-07896 CURB RAMP, CONCRETE, B	22.000	SYS
52	604-07898 CURB RAMP, CONCRETE, D	14.000	SYS
53	604-07899 CURB RAMP, CONCRETE, E	11.000	SYS
54	604-07901 CURB RAMP, CONCRETE, G	172.000	SYS
55	604-07902 CURB RAMP, CONCRETE, H	13.000	SYS
56	605-06140 CURB AND GUTTER, CONCRETE	5,860.000	LFT
57	610-07486 HMA FOR APPROACHES, TYPE A	170.000	TON
58	610-07712 PCCP FOR APPROACHES, 6 IN.	2,047.000	SYS
59	615-06496 PARKING BARRIER	73.000	EACH
60	616-05688 RIPRAP, CLASS 1	12.000	TON
61	621-06574 SODDING	7,000.000	SYS
62	621-93350 TAPPING TEE AND VALVE ASSEMBLY, 8 IN.	1.000	EACH
63	621-94463 TAPPING TEE AND VALVE ASSEMBLY, 4 IN.	3.000	EACH
64	621-94464 TAPPING TEE AND VALVE ASSEMBLY, 6 IN.	5.000	EACH
65	621-94771 GATE VALVE WITH ROADWAY BOX, 6 IN.	4.000	EACH
66	621-94772 GATE VALVE WITH ROADWAY BOX, 4 IN.	3.000	EACH
67	621-94780 WATER SERVICE CONNECTION	45.000	EACH
68	621-98038 MULCH, HARDWOOD SHREDDED BARK	102.000	CYS
69	622-04648 TREE GRATE	31.000	EACH
70	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	82.000	EACH
71	714-44240 CONCRETE, A, STRUCTURES	2.000	CYS
72	715-01970 RETAINER GLAND, DUCTILE IRON, 8 IN.	130.000	EACH
73	715-02144 ELBOW, DUCTILE IRON, 6 IN., 45 DEGREE	2.000	EACH
74	715-02145 ELBOW, DUCTILE IRON, 8 IN., 45 DEGREE	7.000	EACH
75	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	650.000	LFT
76	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	5,310.000	LFT
77	715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN.	120.000	LFT
78	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	1,750.000	LFT
79	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	380.000	LFT
80	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	1,330.000	LFT
81	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	960.000	LFT
82	715-08555 RETAINER GLAND	20.000	EACH
83	715-08555 RETAINER GLAND	30.000	EACH
84	715-26728 GRATED BOX END SECTION, II, 4:1, 12 IN.	2.000	EACH
85	715-46015 PIPE END SECTION, 21 IN.	1.000	EACH
86	715-91738 WATER MAIN, DUCTILE IRON, 6 IN.	200.000	LFT
87	715-91739 WATER MAIN, DUCTILE IRON, 8 IN.	2,360.000	LFT
88	715-98265 WATER MAIN, DUCTILE IRON, 4 IN.	110.000	LFT
89	718-52610 AGGREGATE FOR UNDERDRAINS	421.000	CYS
90	719-93351 TEE, RESTRAINED, 8 IN.	1.000	EACH
91	719-96684 ELL, RESTRAINED, 8 IN., 90 DEG.	1.000	EACH
92	719-96944 TEE, 8 IN. X 8 IN. X 6 IN.	4.000	EACH
93	719-96945 TEE, 8 IN. X 8 IN. X 4 IN.	3.000	EACH
94	719-96946 REDUCER, 8 IN. X 6 IN.	1.000	EACH
95	720-44000 CASTING, ADJUST TO GRADE	16.000	EACH
96	720-44080 CASTING, 15, FURNISH AND ADJUST TO GRADE	1.000	EACH

CALL ORDER : 228
 LETTING DATE :

CONTRACT ID : R -28274-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
97	720-45030 INLET, E7	3.000	EACH
98	720-45035 INLET, F7	2.000	EACH
99	720-45260 PIPE CATCH BASIN, 12 IN.	6.000	EACH
100	720-45410 MANHOLE, C4	31.000	EACH
101	720-96999 FIRE HYDRANT ASSEMBLY	7.000	EACH
102	720-98174 INLET, B15	32.000	EACH
103	720-98555 INLET, C15	22.000	EACH
104	732-02532 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 8 IN.	2.000	EACH
105	732-03072 TEE	5.000	EACH
106	732-04846 ELL	3.000	EACH
107	732-97009 FIRE HYDRANT ASSEMBLY, REMOVE	7.000	EACH
108	801-04308 ROAD CLOSURE SIGN ASSEMBLY	11.000	EACH
109	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	13,000.000	LFT
110	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12,000.000	LFT
111	801-06625 DETOUR ROUTE MARKER ASSEMBLY	43.000	EACH
112	801-06640 CONSTRUCTION SIGN, A	60.000	EACH
113	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
114	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
115	801-07119 BARRICADE, III-B	140.000	LFT
116	801-08388 TEMPORARY TRAFFIC BARRIER	3,000.000	LFT
117	801-08388 TEMPORARY TRAFFIC BARRIER	6,000.000	LFT
118	801-94295 SIGNAL HEAD, RELOCATE	4.000	EACH
119	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	456.000	LFT
120	802-76020 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.080 IN. THICKNESS	140.000	SFT
121	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	120.000	SFT
122	802-76125 SPAN OVERHEAD SIGN STRUCTURE, CABLESPAN	1.000	EACH
123	802-91084 OVERHEAD PANEL SIGN, REMOVE AND REINSTALL	4.000	EACH
124	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	1.000	EACH
125	805-01842 HANDHOLE, SIGNAL	5.000	EACH
126	805-02069 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM	3.000	EACH
127	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	1.000	EACH
128	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	8.000	EACH
129	805-02445 CONTROLLER CABINET, P1	2.000	EACH
130	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	3,352.000	LFT
131	805-02618 WIRE, NO. 2 COPPER, 3 1C	1,660.000	LFT
132	805-04593 CONDUIT, STEEL, GALVANIZED, 1.25 IN.	325.000	LFT
133	805-04973 CONDUIT	5,087.000	LFT
134	805-04973 CONDUIT	3,310.000	LFT
135	805-05698 SIGNAL SUPPORT FOUNDATION, 2 FT. 6 IN. X 2FT. 6 IN. X 7 FT.	3.000	EACH
136	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	452.000	LFT
137	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	1.000	EACH
138	805-08093 POLE	8.000	EACH
139	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
140	805-78445 SIGNAL SERVICE	1.000	EACH
141	805-78480 SIGNAL CABLE, 3C 14GA.	398.000	LFT
142	805-78485 SIGNAL CABLE, 5C 14GA.	618.000	LFT
143	805-78490 SIGNAL CABLE, 7C 14GA.	421.000	LFT
144	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	556.000	LFT

CALL ORDER : 228
 LETTING DATE :

CONTRACT ID : R -28274-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, STREETScape			
145	805-78785	SIGNAL DETECTOR HOUSING	5.000 EACH
146	805-78900	PEDESTAL FOUNDATION, A	1.000 EACH
147	805-78925	CONTROLLER CABINET FOUNDATION, P1	3.000 EACH
148	805-86843	WIRE, NO. 4 COPPER, 1C	20,600.000 LFT
149	805-86898	CONDUIT, STEEL, GALVANIZED, .75 IN.	504.000 LFT
150	805-90005	SIGNAL PEDESTAL, 10 FT.	1.000 EACH
151	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	3.000 EACH
152	805-95888	WIRE, NO. 8 COPPER, 1C	22,665.000 LFT
153	805-95889	WIRE, NO. 10 COPPER, 1C	7,190.000 LFT
154	805-95890	WIRE, NO. 12 COPPER, 1/C	200.000 LFT
155	805-96014	SAW CUT, FULL DEPTH	5,460.000 LFT
156	805-96121	PEDESTRIAN PUSH BUTTON AND SIGN	4.000 EACH
157	805-99338	WIRE, AWG, NO. 6 COPPER, GROUND, 1/C	147.000 LFT
158	807-01889	LIGHT POLE, ORNAMENTAL, 12 FT., E.M.H., WITH LUMINAIRE	50.000 EACH
159	807-02817	CONCRETE FOUNDATION WITH GROUNDING, 24 IN. X 24 IN. X 72 IN.	50.000 EACH
160	807-03954	ELECTRICAL PANEL, MAIN	2.000 EACH
161	807-03968	CONDUIT, PVC, 1 IN., SCHEDULE 80, FOR ELECTRIC	3,445.000 LFT
162	807-04651	WIRE	1,750.000 LFT
163	807-04651	WIRE	14,000.000 LFT
164	807-04651	WIRE	96.000 LFT
165	807-04651	WIRE	13,700.000 LFT
166	807-05073	JUNCTION BOX	84.000 EACH
167	807-05073	JUNCTION BOX	84.000 EACH
168	807-86805	SERVICE POINT, I	2.000 EACH
169	807-86955	CABLE DUCT MARKER	16.000 EACH
170	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	400.000 LFT
171	808-75215	LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	400.000 LFT
172	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	600.000 LFT
173	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,100.000 LFT
174	808-75278	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	160.000 LFT
175	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	220.000 LFT
176	808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,110.000 LFT
177	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	3.000 EACH
178	808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000 EACH
179	808-90909	CAP LINE	19.000 EACH

CALL ORDER : 240
 LETTING DATE :

CONTRACT ID : R -28305-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN INSTALLATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	27.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	6.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	162.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	1,174.000	SYS
13	202-02241 GUARDRAIL, REMOVE	420.000	LFT
14	202-02245 TREE, 6 IN., REMOVE	12.000	EACH
15	202-02250 TREE, 10 IN., REMOVE	13.000	EACH
16	202-02255 TREE, 18 IN., REMOVE	14.000	EACH
17	202-02260 TREE, 30 IN., REMOVE	5.000	EACH
18	202-02264 TREE, 42 IN., REMOVE	2.000	EACH
19	202-02265 TREE, 48 IN., REMOVE	1.000	EACH
20	202-02271 HEADWALL, REMOVE	1.000	EACH
21	202-02273 CENTER CURB, CONCRETE, REMOVE	88.000	SYS
22	202-02278 CURB, CONCRETE, REMOVE	19,315.000	LFT
23	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
24	202-06541 REMOVE	1.000	EACH
25	202-06542 RELOCATE	27.000	EACH
26	202-06542 RELOCATE	10.000	EACH
27	202-52710 SIDEWALK, CONCRETE, REMOVE	6,705.000	SYS
28	202-74035 SIGN, REMOVE	208.000	EACH
29	202-91010 TREE, 24 IN., REMOVE	3.000	EACH
30	202-91011 TREE, 36 IN., REMOVE	2.000	EACH
31	202-91385 INLET, REMOVE	30.000	EACH
32	202-93091 TREE, 15 IN., REMOVE	5.000	EACH
33	202-93898 TREE, 12 IN., REMOVE	10.000	EACH
34	202-95579 SERVICE POINT, REMOVE	1.000	EACH
35	202-96133 PIPE, REMOVE	2,416.000	LFT
36	203-02000 EXCAVATION, COMMON	5,337.000	CYS
37	203-02070 BORROW	5,626.000	CYS
38	203-91878 LINEAR DITCH GRADING	1,422.000	LFT
39	205-02459 EROSION CONTROL	LUMP	LUMP
40	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	11.000	TON
41	205-06933 TEMPORARY DITCH INLET PROTECTION	24.000	EACH
42	205-06937 TEMPORARY SILT FENCE	4,480.000	LFT
43	207-08267 SUBGRADE TREATMENT, TYPE IIIA	7,605.000	SYS
44	210-06547 PAINT	12.000	EACH
45	210-06547 PAINT	8.000	EACH
46	211-07454 STRUCTURE BACKFILL	4,995.000	CYS
47	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,209.000	TON
48	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	280.000	TON

CALL ORDER : 240
 LETTING DATE :

CONTRACT ID : R -28305-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN INSTALLATION			
49	306-08037 MILLING, ASPHALT, 3 IN.	130,936.000	SYS
50	306-08432 MILLING, APPROACH	3,819.000	SYS
51	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	11,126.000	TON
52	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	14,835.000	TON
53	402-07433 HMA SURFACE, TYPE B	49.000	TON
54	402-07438 HMA INTERMEDIATE, TYPE B	65.000	TON
55	402-07441 HMA BASE, TYPE B	195.000	TON
56	402-07452 HMA, TYPE C, WEDGE AND LEVEL	2,486.000	TON
57	406-05520 ASPHALT FOR TACK COAT	58.000	TON
58	601-05999 CURVED TERMINAL END	2.000	EACH
59	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
60	601-95434 HANDRAIL, STEEL PIPE, 1.5 IN.	722.000	LFT
61	601-96063 HANDRAIL, ALUMINUM, SCHEDULE 40, 2 IN. DIA. X 3 FT. 6 IN.	85.000	LFT
62	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	1.000	EACH
63	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	713.000	LFT
64	604-06070 SIDEWALK, CONCRETE	181.000	SYS
65	604-06070 SIDEWALK, CONCRETE	105.000	SYS
66	604-07894 CURB RAMP, CONCRETE, A	29.000	SYS
67	604-07896 CURB RAMP, CONCRETE, B	11.000	SYS
68	604-07897 CURB RAMP, CONCRETE, C	3.000	SYS
69	604-07898 CURB RAMP, CONCRETE, D	101.000	SYS
70	604-07900 CURB RAMP, CONCRETE, F	82.000	SYS
71	604-07901 CURB RAMP, CONCRETE, G	218.000	SYS
72	604-07902 CURB RAMP, CONCRETE, H	539.000	SYS
73	604-91531 SIDEWALK, CONCRETE, 4 IN.	12,361.000	SYS
74	605-06120 CURB, CONCRETE	93.000	LFT
75	605-06140 CURB AND GUTTER, CONCRETE	21,045.000	LFT
76	610-07486 HMA FOR APPROACHES, TYPE A	48.000	TON
77	610-07487 HMA FOR APPROACHES, TYPE B	817.000	TON
78	610-07712 PCCP FOR APPROACHES, 6 IN.	6,301.000	SYS
79	611-03671 TRASH RECEPTACLE	3.000	EACH
80	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	59.000	EACH
81	616-02320 GEOTEXTILES	212.000	SYS
82	616-06405 RIPRAP, REVETMENT	144.000	TON
83	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
84	621-06545 FERTILIZER	3.030	TON
85	621-06554 SEED MIXTURE, U	1,000.000	LBS
86	621-06565 MULCHING MATERIAL	13.000	TON
87	621-06567 WATER	469.000	KGAL
88	621-06575 SODDING, NURSERY	13,020.000	SYS
89	621-98038 MULCH, HARDWOOD SHREDDED BARK	2.000	CYS
90	622-03948 PLANTER	5.000	EACH
91	622-05605 PLANT, ANNUAL	60.000	EACH
92	622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN.	18.000	EACH
93	622-05647 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 120 IN.	5.000	EACH
94	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	45.000	EACH
95	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	199.000	EACH
96	622-05654 PLANT, PERENNIAL	14.000	EACH

CALL ORDER : 240
 LETTING DATE :

CONTRACT ID : R -28305-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN INSTALLATION			
97	622-05654 PLANT, PERENNIAL	12.000	EACH
98	711-05395 REPLACE	6.000	EACH
99	712-03812 BENCH	6.000	EACH
100	714-07665 RETAINING WALL	LUMP	LUMP
101	715-01354 CLEAN EXISTING PIPE	514.000	LFT
102	715-04548 GRATED BOX END SECTION, II, 6:1, 30 IN.	1.000	EACH
103	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	1,233.000	LFT
104	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	1,419.000	LFT
105	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	2,103.000	LFT
106	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	2,308.000	LFT
107	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	1,207.000	LFT
108	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	1,882.000	LFT
109	715-05155 PIPE, TYPE 2, CIRCULAR, 27 IN.	692.000	LFT
110	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	724.000	LFT
111	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	48.000	LFT
112	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	108.000	LFT
113	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN.	24.000	LFT
114	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN.	15.000	LFT
115	715-05177 PIPE, TYPE 3, CIRCULAR, 36 IN.	56.000	LFT
116	715-05331 PIPE, TYPE 2, DEFORMED, MIN. AREA 3.3 SFT.	50.000	LFT
117	715-08307 HMA FOR STRUCTURE INSTALLATION, TYPE D	2,176.000	TON
118	715-08560 GRATED BOX END SECTION, II, 3:1, 15 IN.	1.000	EACH
119	715-26729 GRATED BOX END SECTION, II, 6:1, 15 IN.	1.000	EACH
120	715-26770 GRATED BOX END SECTION, I, 3:1, 24 IN.	1.000	EACH
121	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
122	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
123	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
124	715-46025 PIPE END SECTION, 27 IN.	1.000	EACH
125	715-46030 PIPE END SECTION, 30 IN.	1.000	EACH
126	715-46040 PIPE END SECTION, 36 IN.	1.000	EACH
127	715-99044 GRATED BOX END SECTION, II, 6:1, 18 IN.	1.000	EACH
128	720-01987 CATCH BASIN, A10	1.000	EACH
129	720-02367 MANHOLE, J10	1.000	EACH
130	720-44000 CASTING, ADJUST TO GRADE	67.000	EACH
131	720-44015 CASTING, 2, FURNISH AND ADJUST TO GRADE	3.000	EACH
132	720-44040 CASTING, 7, FURNISH AND ADJUST TO GRADE	1.000	EACH
133	720-44050 CASTING, 9, FURNISH AND ADJUST TO GRADE	2.000	EACH
134	720-45030 INLET, E7	4.000	EACH
135	720-45035 INLET, F7	9.000	EACH
136	720-45240 CATCH BASIN, J10	9.000	EACH
137	720-45340 CATCH BASIN, J10, MODIFIED	1.000	EACH
138	720-45415 MANHOLE, D4	3.000	EACH
139	720-45416 MANHOLE, E4	1.000	EACH
140	720-90129 MANHOLE, J2	1.000	EACH
141	720-91917 INLET, A10	1.000	EACH
142	720-92025 MANHOLE, D2	3.000	EACH
143	720-98174 INLET, B15	74.000	EACH
144	730-26732 GRATED BOX END SECTION, II, 4:1, 36 IN.	1.000	EACH

CALL ORDER : 240
 LETTING DATE :

CONTRACT ID : R -28305-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN INSTALLATION			
145	732-02388 WATER MAIN	1.000	EACH
146	732-02388 WATER MAIN	3.000	EACH
147	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
148	801-06640 CONSTRUCTION SIGN, A	99.000	EACH
149	801-06645 CONSTRUCTION SIGN, B	32.000	EACH
150	801-06710 FLASHING ARROW SIGN	800.000	DAY
151	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
152	801-07119 BARRICADE, III-B	84.000	LFT
153	802-04314 SIGN	1.000	EACH
154	802-04314 SIGN	1.000	EACH
155	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	1,478.000	LFT
156	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	205.000	SFT
157	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	860.000	SFT
158	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	85.000	SFT
159	805-04973 CONDUIT	16,530.000	LFT
160	805-04973 CONDUIT	4,540.000	LFT
161	807-02191 HANDHOLE, LIGHTING	14.000	EACH
162	807-02194 SERVICE POINT, II, MODIFIED	14.000	EACH
163	807-03802 LIGHT STANDARDS	1.000	EACH
164	807-03802 LIGHT STANDARDS	32.000	EACH
165	807-03802 LIGHT STANDARDS	46.000	EACH
166	807-03802 LIGHT STANDARDS	64.000	EACH
167	807-03802 LIGHT STANDARDS	22.000	EACH
168	807-03950 LUMINAIRE, ORNAMENTAL	8.000	EACH
169	807-03950 LUMINAIRE, ORNAMENTAL	78.000	EACH
170	807-03950 LUMINAIRE, ORNAMENTAL	64.000	EACH
171	807-03950 LUMINAIRE, ORNAMENTAL	22.000	EACH
172	807-04651 WIRE	4,020.000	LFT
173	807-06585 CLOCK	1.000	EACH
174	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	1,425.000	LFT
175	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	660.000	LFT
176	807-86810 SERVICE POINT, II	4.000	EACH
177	807-93650 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY	1.000	SET
178	807-93650 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY	78.000	SET
179	807-93650 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY	2.000	SET
180	807-93651 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR POST TOP	63.000	SET
181	807-95514 SERVICE POINT RISER	1.000	EACH
182	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	5,025.000	LFT
183	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	14,481.000	LFT
184	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	30,205.000	LFT
185	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	1,055.000	LFT
186	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	3,923.000	LFT
187	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
188	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
189	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	4.000	EACH
190	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	440.000	EACH

CALL ORDER : 250
 LETTING DATE :

CONTRACT ID : R -28400-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, RESTORATION OF STUDEBAKER		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
3	201-06587 CLEARING AND GRUBBING	1.000	ACRE
4	202-02240 PAVEMENT REMOVAL	237.000	SYS
5	202-02278 CURB, CONCRETE, REMOVE	52.000	LFT
6	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
7	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	2,638.000	SFT
8	202-03875 CONCRETE STEPS, REMOVE	3.000	EACH
9	202-52710 SIDEWALK, CONCRETE, REMOVE	51.000	SYS
10	202-91010 TREE, 24 IN., REMOVE	6.000	EACH
11	202-96022 CONCRETE FOUNDATION, REMOVE	2.000	EACH
12	203-02000 EXCAVATION, COMMON	522.000	CYS
13	210-05758 BUILDING	LUMP	LUMP
14	210-06544 WINDOWS	4.000	EACH
15	211-02050 B BORROW	266.000	CYS
16	213-08058 FLOWABLE BACKFILL	244.100	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	313.530	TON
18	304-07489 HMA PATCHING, TYPE A	10.400	TON
19	402-07432 HMA SURFACE, TYPE A	75.370	TON
20	402-07440 HMA BASE, TYPE A	150.740	TON
21	604-07897 CURB RAMP, CONCRETE, C	20.800	SYS
22	604-91531 SIDEWALK, CONCRETE, 4 IN.	90.900	SYS
23	605-06120 CURB, CONCRETE	337.000	LFT
24	610-08446 PCCP FOR APPROACHES, 6 IN.	149.600	SYS
25	621-06559 MULCHED SEEDING, R	1,533.000	SYS
26	621-98038 MULCH, HARDWOOD SHREDDED BARK	11.000	CYS
27	622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 72 TO	11.000	EACH
28	622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN.	2,161.000	EACH
29	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	9.000	EACH
30	711-90932 EDGING, STEEL	134.000	LFT
31	712-04686 FIRE PROTECTION	LUMP	LUMP
32	715-05062 WATER SERVICE LINE	LUMP	LUMP
33	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	189.000	LFT
34	715-91361 PIPE, PVC, 6 IN.	32.000	LFT
35	715-98265 WATER MAIN, DUCTILE IRON, 4 IN.	1.000	LFT
36	720-45205 CATCH BASIN, A2	3.000	EACH
37	720-90984 MANHOLE, C2	1.000	EACH
38	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
39	802-03896 BOLLARD	3.000	EACH
40	805-08459 SHELVING	LUMP	LUMP
41	805-95889 WIRE, NO. 10 COPPER, 1C	765.000	LFT
42	807-03972 CONDUIT, PVC, 1 IN., SCHEDULE 40, FOR ELECTRIC	255.000	LFT
43	807-04654 LIGHT POLE	4.000	EACH
44	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	101.000	LFT
45	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	400.000	LFT
46	808-97222 PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	2.000	EACH

CALL ORDER : 260
 LETTING DATE :

CONTRACT ID : R -28401-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	13.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	13.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	2,031.800	m2
12	202-02278 CURB, CONCRETE, REMOVE	43.500	m
13	203-02080 LINEAR GRADING	1.850	km
14	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	53.000	EACH
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	14.700	Mg
16	207-08263 SUBGRADE TREATMENT, TYPE IA	11,939.000	m2
17	211-07454 STRUCTURE BACKFILL	3,943.600	m3
18	213-08058 FLOWABLE BACKFILL	366.100	m3
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,719.500	Mg
20	304-07493 WIDENING WITH HMA, TYPE B	727.000	Mg
21	306-08034 MILLING, ASPHALT, 38 mm	14,663.200	m2
22	306-08043 MILLING, TRANSITION	303.000	m2
23	306-08432 MILLING, APPROACH	966.800	m2
24	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 MM	1,908.000	Mg
25	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	1,539.000	Mg
26	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	2,335.000	Mg
27	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	481.000	Mg
28	402-07433 HMA SURFACE, TYPE B	451.000	Mg
29	402-07453 HMA FOR TEMPORARY PAVEMENT	902.000	Mg
30	406-05520 ASPHALT FOR TACK COAT	12.500	Mg
31	603-06060 FENCE, FARM FIELD, RESET	44.000	m
32	603-06065 FENCE, CHAIN LINK, RESET	7.600	m
33	605-06120 CURB, CONCRETE	16.400	m
34	605-06140 CURB AND GUTTER, CONCRETE	1,400.000	m
35	605-94811 CURB TURNOUT	2.000	EACH
36	610-07486 HMA FOR APPROACHES, TYPE A	413.000	Mg
37	610-07487 HMA FOR APPROACHES, TYPE B	169.000	Mg
38	610-07712 PCCP FOR APPROACHES, 150 mm	1,923.800	m2
39	611-06497 MAILBOX ASSEMBLY, SINGLE	20.000	EACH
40	615-06505 MONUMENT, B	2.000	EACH
41	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
42	616-02320 GEOTEXTILES	1,308.500	m2
43	616-06405 RIPRAP, REVETMENT	646.000	Mg
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
45	621-06545 FERTILIZER	0.830	Mg
46	621-06554 SEED MIXTURE, U	151.700	kg
47	621-06557 SEED MIXTURE, T	138.400	kg
48	621-06565 MULCHING MATERIAL	4.100	Mg

CALL ORDER : 260
 LETTING DATE :

CONTRACT ID : R -28401-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
49	621-06567 WATER	276.900	kL
50	621-06575 SODDING, NURSERY	15,382.000	m2
51	622-05625 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 1200	36.000	EACH
52	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	1,629.700	m
53	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	76.000	m
54	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	1,591.800	m
55	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	473.200	m
56	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	607.100	m
57	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	201.800	m
58	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	218.000	m
59	715-08283 PCCP FOR STRUCTURE INSTALLATION	501.000	m2
60	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	148.000	Mg
61	715-46005 PIPE END SECTION, 375 mm	26.000	EACH
62	715-46010 PIPE END SECTION, 450 mm	4.000	EACH
63	715-46015 PIPE END SECTION, 525 mm	1.000	EACH
64	716-07632 PIPE INSTALLATION, TRENCHLESS, 450 mm	73.500	m
65	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
66	718-52610 AGGREGATE FOR UNDERDRAINS	326.300	m3
67	718-99153 GEOTEXTILES FOR UNDERDRAIN	1,891.600	m2
68	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
69	720-45035 INLET, F7	1.000	EACH
70	720-45075 INLET, R13	15.000	EACH
71	720-45275 PIPE CATCH BASIN, 600 mm	24.000	EACH
72	720-45410 MANHOLE, C4	9.000	EACH
73	720-90984 MANHOLE, C2	14.000	EACH
74	720-98174 INLET, B15	30.000	EACH
75	720-98555 INLET, C15	51.000	EACH
76	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	6,688.000	m
77	801-06625 DETOUR ROUTE MARKER ASSEMBLY	14.000	EACH
78	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
79	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
80	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
81	801-07119 BARRICADE, III-B	14.400	m
82	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	110.300	m
83	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	16.140	m2
84	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,565.100	m
85	808-06716 LINE, REMOVE	37,010.000	m
86	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	110.700	m
87	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	4,237.000	m
88	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	59.300	m
89	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	9.000	EACH
90	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	9.000	EACH
91	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	207.000	EACH

CALL ORDER : 270
 LETTING DATE :

CONTRACT ID : R -28433-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	203-02000 EXCAVATION, COMMON	21,922.000	CYS
9	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	427.000	TON
10	205-06936 TEMPORARY SEDIMENT TRAP	147.000	TON
11	205-06937 TEMPORARY SILT FENCE	125.000	LFT
12	207-08267 SUBGRADE TREATMENT, TYPE IIIA	11,960.000	SYS
13	211-07454 STRUCTURE BACKFILL	341.000	CYS
14	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,792.000	TON
15	303-02051 STONE, 2	100.000	TON
16	303-07449 COMPACTED AGGREGATE, NO. 73	12.000	TON
17	306-08042 MILLING, SCARIFICATION/PROFILE	500.000	SYS
18	306-08043 MILLING, TRANSITION	400.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,018.000	TON
21	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,188.000	TON
22	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	3,160.000	TON
23	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	1,262.000	TON
24	406-05520 ASPHALT FOR TACK COAT	9.100	TON
25	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
26	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	500.000	LFT
27	605-06095 CURB, INTEGRAL, B, CONCRETE	250.000	LFT
28	605-94082 CURB TURNOUT, CONCRETE	1.000	EACH
29	610-07486 HMA FOR APPROACHES, TYPE A	51.000	TON
30	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
31	615-06490 RIGHT OF WAY MARKER	18.000	EACH
32	615-06505 MONUMENT, B	5.000	EACH
33	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
34	616-02320 GEOTEXTILES	2,434.000	SYS
35	616-05688 RIPRAP, CLASS 1	243.000	TON
36	616-05689 RIPRAP, CLASS 2	203.000	TON
37	616-06405 RIPRAP, REVETMENT	885.000	TON
38	616-06451 RIPRAP, UNIFORM	275.000	TON
39	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
40	621-06545 FERTILIZER	1.200	TON
41	621-06553 SEED MIXTURE, R	502.000	LBS
42	621-06565 MULCHING MATERIAL	5.900	TON
43	621-06567 WATER	13.500	KGAL
44	621-06574 SODDING	2,321.000	SYS
45	621-06575 SODDING, NURSERY	1,060.000	SYS
46	714-04661 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 11 FT. X 6 FT.	158.000	LFT
47	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	4,526.000	LFT
48	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	345.000	LFT

CALL ORDER : 270
 LETTING DATE :

CONTRACT ID : R -28433-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
49	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	258.000	LFT
50	715-46005 PIPE END SECTION, 15 IN.	9.000	EACH
51	718-06528 OUTLET PROTECTOR, 1	2.000	EACH
52	718-06529 OUTLET PROTECTOR, 2	11.000	EACH
53	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
54	718-52610 AGGREGATE FOR UNDERDRAINS	407.000	CYS
55	718-99153 GEOTEXTILES FOR UNDERDRAIN	3,103.000	SYS
56	720-45010 INLET, A3	1.000	EACH
57	801-04308 ROAD CLOSURE SIGN ASSEMBLY	19.000	EACH
58	801-06625 DETOUR ROUTE MARKER ASSEMBLY	27.000	EACH
59	801-06640 CONSTRUCTION SIGN, A	5.000	EACH
60	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
61	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
62	801-07118 BARRICADE, III-A	96.000	LFT
63	801-07119 BARRICADE, III-B	48.000	LFT
64	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	6,200.000	LFT
65	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	6,200.000	LFT
66	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.000	EACH
67	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	75.000	EACH

CALL ORDER : 280
 LETTING DATE :

CONTRACT ID : R -28438-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
5	202-02241 GUARDRAIL, REMOVE	396.000	LFT
6	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
7	203-02000 EXCAVATION, COMMON	911.000	CYS
8	205-06932 TEMPORARY CHECK DAM, STRAW BALES	144.000	LFT
9	205-06937 TEMPORARY SILT FENCE	725.000	LFT
10	207-08263 SUBGRADE TREATMENT, TYPE IA	1,829.000	SYS
11	211-07454 STRUCTURE BACKFILL	585.000	CYS
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	825.000	TON
13	306-08033 MILLING, ASPHALT, 1 IN.	1,800.000	SYS
14	306-08043 MILLING, TRANSITION	494.000	SYS
15	402-07432 HMA SURFACE, TYPE A	115.000	TON
16	402-07433 HMA SURFACE, TYPE B	200.000	TON
17	402-07438 HMA INTERMEDIATE, TYPE B	920.000	TON
18	402-07440 HMA BASE, TYPE A	330.000	TON
19	402-07441 HMA BASE, TYPE B	65.000	TON
20	406-05520 ASPHALT FOR TACK COAT	3.000	TON
21	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
22	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
23	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
24	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
25	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	525.000	LFT
26	615-06490 RIGHT OF WAY MARKER	16.000	EACH
27	615-06505 MONUMENT, B	2.000	EACH
28	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
29	616-02320 GEOTEXTILES	478.000	SYS
30	616-05688 RIPRAP, CLASS 1	100.000	TON
31	616-06405 RIPRAP, REVETMENT	664.000	TON
32	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
33	621-01371 SEED MIXTURE, LEGUME, 2	41.000	LBS
34	621-06545 FERTILIZER	0.500	TON
35	621-06553 SEED MIXTURE, R	118.000	LBS
36	621-06565 MULCHING MATERIAL	2.300	TON
37	621-06567 WATER	5.000	KGAL
38	621-06574 SODDING	1,146.000	SYS
39	621-52448 SIGN, DO NOT SPRAY	8.000	EACH
40	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	40.000	LFT
41	715-05440 PIPE, DRAINTILE TERMINAL SECTION, 8 IN.	50.000	LFT
42	715-05442 PIPE, DRAINTILE TERMINAL SECTION, 10 IN.	50.000	LFT
43	715-05443 PIPE, DRAINTILE TERMINAL SECTION, 12 IN.	50.000	LFT
44	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
45	723-06660 WINGWALL	92.000	SYS
46	723-07020 STRUCTURE, PRECAST THREE-SIDED, 216 IN. X 120 IN.	54.000	LFT
47	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
48	801-06625 DETOUR ROUTE MARKER ASSEMBLY	24.000	EACH

CALL ORDER : 280
LETTING DATE :

CONTRACT ID : R -28438-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
49 801-06640	CONSTRUCTION SIGN, A	14.000	EACH
50 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
51 801-07119	BARRICADE, III-B	96.000	LFT
52 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,800.000	LFT
53 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	225.000	LFT
54 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	12.000	EACH
55 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	12.000	EACH

CALL ORDER : 290
 LETTING DATE :

CONTRACT ID : R -28507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	33.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	132.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	10,110.000	m2
13	202-02241 GUARDRAIL, REMOVE	538.900	m
14	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
15	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
19	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
20	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
21	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
22	202-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	36.000	EACH
23	202-74080 OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	2.000	EACH
24	202-91385 INLET, REMOVE	1.000	EACH
25	203-02000 EXCAVATION, COMMON	2,000.000	m3
26	203-02010 EXCAVATION, ROCK	2,784.000	m3
27	203-02055 EMBANKMENT	1,114,668.000	m3
28	203-51223 EXCAVATION, WATERWAY	7,589.500	m3
29	204-02290 SETTLEMENT PLATE	92.000	EACH
30	205-03371 SEDIMENT REMOVE	1,448.000	m3
31	205-04931 SEDIMENT TRAP	39.000	EACH
32	205-06930 SPLASHPAD, RIPRAP	2.340	Mg
33	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	4,424.500	Mg
34	205-06932 TEMPORARY CHECK DAM, STRAW BALES	36.000	m
35	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
36	205-06934 TEMPORARY MULCHING	7.400	Mg
37	205-06935 TEMPORARY SEDIMENT BASIN	1.000	EACH
38	205-06936 TEMPORARY SEDIMENT TRAP	2,428.000	Mg
39	205-06937 TEMPORARY SILT FENCE	1,205.000	m
40	205-06938 TEMPORARY SLOPE DRAIN	488.000	m
41	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	568.000	m3
42	207-08262 SUBGRADE TREATMENT, TYPE I	263,071.300	m2
43	207-08263 SUBGRADE TREATMENT, TYPE IA	29,394.500	m2
44	207-08264 SUBGRADE TREATMENT, TYPE II	11,668.700	m2
45	207-08266 SUBGRADE TREATMENT, TYPE III	47,400.600	m2
46	207-08267 SUBGRADE TREATMENT, TYPE IIIA	8,852.400	m2
47	210-08082 COMPOSITE FILTER SOCK	379.400	m
48	211-02050 B BORROW	2,128.000	m3

CALL ORDER : 290
 LETTING DATE :

CONTRACT ID : R -28507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
49	211-06467	AGGREGATE FOR END BENT BACKFILL	288.600 m3
50	211-07454	STRUCTURE BACKFILL	33,621.300 m3
51	212-06281	STOCKPILED SELECTED MATERIAL	780.000 m3
52	212-06282	STOCKPILED SELECTED MATERIAL, SALVAGED	780.000 m3
53	213-52830	FLOWABLE MORTAR	1,060.000 m3
54	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	25,358.100 Mg
55	302-06464	SUBBASE FOR PCCP	58,425.800 m3
56	302-07455	DENSE GRADED SUBBASE	175.100 m3
57	303-01180	COMPACTED AGGREGATE, NO. 53	52,299.000 Mg
58	303-08210	COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	1,000.000 Mg
59	306-08034	MILLING, ASPHALT, 38 mm	8,447.000 m2
60	306-08043	MILLING, TRANSITION	360.000 m2
61	401-06264	PROFILOGRAPH, HMA	LUMP LUMP
62	401-07327	QC/QA-HMA, 2, 70, SURFACE, 9.5 MM	1,652.800 Mg
63	401-07333	QC/QA-HMA, 2, 76, SURFACE, 9.5 mm	3,097.400 Mg
64	401-07334	QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	943.400 Mg
65	401-07397	QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	4,685.200 Mg
66	401-07402	QC/QA-HMA, 2, 76, INTERMEDIATE, 19.0 mm	5,643.800 Mg
67	401-07403	QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	1,736.200 Mg
68	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	4,929.400 Mg
69	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	10,472.800 Mg
70	401-07429	QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	5,341.700 Mg
71	402-07432	HMA SURFACE, TYPE A	1,947.400 Mg
72	402-07433	HMA SURFACE, TYPE B	1,214.000 Mg
73	402-07435	HMA INTERMEDIATE, TYPE A	4,574.800 Mg
74	402-07438	HMA INTERMEDIATE, TYPE B	2,024.000 Mg
75	402-07441	HMA BASE, TYPE B	6,476.000 Mg
76	402-07453	HMA FOR TEMPORARY PAVEMENT	1,000.000 Mg
77	404-05514	SEAL COAT, 5	1,071.000 m2
78	406-05520	ASPHALT FOR TACK COAT	91.700 Mg
79	501-06266	PROFILOGRAPH, PCCP	LUMP LUMP
80	501-06322	QC/QA-PCCP, 275 mm	233,714.400 m2
81	501-06727	CORING, PCCP	LUMP LUMP
82	503-05240	D-1 CONTRACTION JOINT	42,620.400 m
83	503-05310	TERMINAL JOINT	253.800 m
84	601-01522	GUARDRAIL TRANSITION TYPE TGB	12.000 EACH
85	601-01626	GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 2	2.000 EACH
86	601-01740	GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 4	1.000 EACH
87	601-05999	CURVED TERMINAL END	11.000 EACH
88	601-06233	IMPACT ATTENUATOR, ED, W1, TL-3	10.000 EACH
89	601-06416	IMPACT ATTENUATOR SPARE PARTS PACKAGE, ED, W1, TL-3	8.000 EACH
90	601-06854	GUARDRAIL, W-BEAM, NESTED	4.000 EACH
91	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	4.000 EACH
92	601-61390	GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE,	6.000 EACH
93	601-94689	GUARDRAIL END TREATMENT, OS	50.000 EACH
94	601-94690	GUARDRAIL END TREATMENT, MS	4.000 EACH
95	601-99105	GUARDRAIL, W BEAM, 1.905 m SPACING	2,512.720 m
96	601-99105	GUARDRAIL, W BEAM, 1.905 m SPACING	19.050 m

CALL ORDER : 290
 LETTING DATE :

CONTRACT ID : R -28507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
97	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 1.905 m SPACING	304.800	m
98	602-06729 BARRIER DELINEATOR	88.000	EACH
99	603-01159 FENCE, CHAIN LINK, 1067 mm	66.100	m
100	603-06040 FENCE, FARM FIELD, 1190 mm	15,581.400	m
101	605-06150 CURB AND GUTTER, C, CONCRETE	754.000	m
102	606-07484 MILLED HMA SHOULDER CORRUGATIONS	784.600	m
103	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	19,808.200	m
104	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	1,190.800	m2
105	610-07486 HMA FOR APPROACHES, TYPE A	193.000	Mg
106	610-07487 HMA FOR APPROACHES, TYPE B	1,315.500	Mg
107	610-08526 PCCP FOR APPROACHES, 275 mm	3,392.000	m2
108	610-52817 TEMPORARY CROSSOVER, B	2.000	EACH
109	611-05330 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 150 mm	731.000	m2
110	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
111	611-06498 MAILBOX ASSEMBLY, DOUBLE	4.000	EACH
112	615-06490 RIGHT OF WAY MARKER	219.000	EACH
113	615-06505 MONUMENT, B	32.000	EACH
114	615-06510 MONUMENT, C	28.000	EACH
115	615-06515 MONUMENT, D	2.000	EACH
116	616-02320 GEOTEXTILES	18,080.000	m2
117	616-05688 RIPRAP, CLASS 1	2,710.000	Mg
118	616-05689 RIPRAP, CLASS 2	1,368.000	Mg
119	616-06405 RIPRAP, REVETMENT	14,635.900	Mg
120	616-06451 RIPRAP, UNIFORM	231.000	Mg
121	616-51367 SLOPEWALL, CONCRETE, 100 mm	907.700	m2
122	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	13.000	EACH
123	621-02770 EROSION CONTROL BLANKET	16,632.000	m2
124	621-04258 SEED MIXTURE	33.550	kg
125	621-04258 SEED MIXTURE	582.300	kg
126	621-04258 SEED MIXTURE	211.130	kg
127	621-06545 FERTILIZER	116.630	Mg
128	621-06553 SEED MIXTURE, R	24,159.500	kg
129	621-06555 SEED MIXTURE, P	95.200	kg
130	621-06557 SEED MIXTURE, T	355.600	kg
131	621-06565 MULCHING MATERIAL	654.800	Mg
132	621-06567 WATER	820.400	kL
133	621-06574 SODDING	47,188.200	m2
134	621-07082 DEFLECTOR	56.000	EACH
135	621-07618 COMPOST SOIL BLANKET	224,197.800	m2
136	621-08082 COMPOST FILTER SOCK	11,563.000	m
137	622-52436 SIGN, DO NOT MOW OR SPRAY	37.000	EACH
138	622-91786 SEEDLING	26,495.000	EACH
139	622-91786 SEEDLING	125.000	EACH
140	622-91786 SEEDLING	3,325.000	EACH
141	701-08072 PILE, STEEL H, HP 360 X 175	217.200	m
142	701-51195 PILE, STEEL H, HP 310 X 79	136.800	m
143	701-91792 PILE TIP, STEEL H	42.000	EACH
144	701-91792 PILE TIP, STEEL H	24.000	EACH

CALL ORDER : 290
 LETTING DATE :

CONTRACT ID : R -28507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
145	701-92043 CORED HOLE IN ROCK, 457 mm	6.000	m
146	701-95780 PILE, STEEL H, HP 310 X 110	87.600	m
147	702-51005 CONCRETE, A, SUBSTRUCTURE	172.800	m3
148	702-51015 CONCRETE, B, FOOTINGS	143.600	m3
149	702-51100 DRAIN PIPE, CAST IRON, 150 mm	497.200	kg
150	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	1,752.400	kg
151	702-90915 CONCRETE, A	576.070	m3
152	703-51030 REINFORCING STEEL	18,570.830	kg
153	703-51032 REINFORCING STEEL, EPOXY COATED	237,372.000	kg
154	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,281.300	m3
155	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	24.000	EACH
156	706-51020 CONCRETE, C, RAILING	127.300	m3
157	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 1143 mm X 406 mm	250.800	m
158	707-05996 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 1981 mm X 1524 mm	1,009.800	m
159	707-06524 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 1524mm x 1067mm	118.800	m
160	707-07605 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 1350 mm X 1200 mm	108.000	m
161	709-51821 SURFACE SEAL	LUMP	LUMP
162	709-51821 SURFACE SEAL	LUMP	LUMP
163	709-51821 SURFACE SEAL	LUMP	LUMP
164	709-51821 SURFACE SEAL	LUMP	LUMP
165	711-51070 ANCHOR PLATE, AP 1	16.000	EACH
166	713-97149 TEMPORARY RAMP	3.000	EACH
167	714-01366 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3000 mm x 1200 mm	61.800	m
168	714-01634 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 2100 mm x 1200 mm	27.000	m
169	714-02544 WINGWALL, PRECAST CONCRETE	213.000	EACH
170	714-03571 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3600 mm x 900 mm	24.500	m
171	714-06056 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3300 mm X 1200 mm	132.600	m
172	714-06056 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3300 mm X 1200 mm	28.500	m
173	714-07112 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 4800 mm X 1200 mm	80.000	m
174	714-07318 CULVERT, PRECAST BOX, REINFORCED CONCRETE,	22.000	m
175	714-07318 CULVERT, PRECAST BOX, REINFORCED CONCRETE,	25.900	m
176	714-26703 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1800 mm x 1200 mm	12.200	m
177	714-26709 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 2400 mm x 1500 mm	23.500	m
178	714-26717 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3000 mm x 1500 mm	55.300	m
179	714-26724 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3600 mm x 1200 mm	48.200	m
180	714-99348 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1500 mm x 900 mm	34.100	m
181	715-02398 SAFETY METAL END SECTION, 6:1, 900 mm	1.000	EACH
182	715-03475 SAFETY METAL END SECTION, 4:1, 375 mm	10.000	EACH
183	715-03476 SAFETY METAL END SECTION, 4:1, 600 mm	2.000	EACH
184	715-05019 PIPE, TYPE 1, CIRCULAR, 900 mm	798.500	m
185	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	36,798.400	m
186	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	3,065.500	m
187	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	23.000	m
188	715-05122 PIPE, TYPE 1, CIRCULAR, 525 mm	23.500	m
189	715-05122 PIPE, TYPE 1, CIRCULAR, 525 mm	23.500	m
190	715-05123 PIPE, TYPE 1, CIRCULAR, 600 mm	29.000	m
191	715-05128 PIPE, TYPE 1, CIRCULAR, 1200 mm	38.000	m
192	715-05145 PIPE, TYPE 1, CIRCULAR, 2400 mm	83.500	m

CALL ORDER : 290
 LETTING DATE :

CONTRACT ID : R -28507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
193	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	119.600	m
194	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	1,370.600	m
195	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	60.000	m
196	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	112.000	m
197	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	209.200	m
198	715-05171 PIPE, TYPE 3, CIRCULAR, 450 mm	14.000	m
199	715-05175 PIPE, TYPE 3, CIRCULAR, 750 mm	10.000	m
200	715-05361 PIPE, TYPE 3, DEFORMED, MIN. AREA 0.10 m2	21.900	m
201	715-05362 PIPE, TYPE 3, DEFORMED, MIN. AREA 0.15 m2	21.000	m
202	715-05371 PIPE, TYPE 3, DEFORMED, MIN. AREA 0.60 m2	33.000	m
203	715-05407 PIPE, END BENT DRAIN, 150 mm	337.000	m
204	715-06004 CONCRETE ANCHOR, 1200 mm	2.000	EACH
205	715-06691 CONCRETE ANCHOR, 2400 mm	2.000	EACH
206	715-07108 SAFETY METAL END SECTION, MIN. AREA 0.60 m2	4.000	EACH
207	715-46000 PIPE END SECTION, 300 mm	4.000	EACH
208	715-46005 PIPE END SECTION, 375 mm	70.000	EACH
209	715-46010 PIPE END SECTION, 450 mm	4.000	EACH
210	715-46015 PIPE END SECTION, 525 mm	2.000	EACH
211	715-46020 PIPE END SECTION, 600 mm	4.000	EACH
212	715-46030 PIPE END SECTION, 750 mm	2.000	EACH
213	715-46040 PIPE END SECTION, 900 mm	24.000	EACH
214	715-46050 PIPE END SECTION, MIN. AREA .15 m2	4.000	EACH
215	718-06528 OUTLET PROTECTOR, 1	44.000	EACH
216	718-06529 OUTLET PROTECTOR, 2	320.000	EACH
217	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	4,600.000	m
218	718-52610 AGGREGATE FOR UNDERDRAINS	10,726.200	m3
219	718-99153 GEOTEXTILES FOR UNDERDRAIN	8,696.300	m2
220	720-45025 INLET, D6	8.000	EACH
221	720-45035 INLET, F7	1.000	EACH
222	720-45066 INLET, N12, MODIFIED	2.000	EACH
223	720-45070 INLET, P12A	35.000	EACH
224	720-45410 MANHOLE, C4	4.000	EACH
225	720-98174 INLET, B15	5.000	EACH
226	723-06660 WINGWALL	300.240	m2
227	723-06971 STRUCTURE, PRECAST THREE-SIDED, 4800 mm X 2100 mm	69.000	m
228	723-07105 STRUCTURE, PRECAST THREE-SIDED, 6100 mm X 3050 mm	98.750	m
229	723-07311 STRUCTURE, PRECAST THREE-SIDED, 4870 mm X 2440 mm	29.600	m
230	723-07711 STRUCTURE, PRECAST THREE-SIDED, 4870 mm X 1520 mm	82.000	m
231	723-08050 STRUCTURE, PRECAST THREE-SIDED, 5480 mm x 2440 mm	25.600	m
232	723-08051 STRUCTURE, PRECAST THREE-SIDED, 4870 mm X 1830 mm	96.000	m
233	723-08051 STRUCTURE, PRECAST THREE-SIDED, 4870 mm X 1830 mm	26.000	m
234	723-08052 STRUCTURE, PRECAST THREE-SIDED, 4260 mm X 2440 mm	85.500	m
235	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
236	801-04308 ROAD CLOSURE SIGN ASSEMBLY	37.000	EACH
237	801-06199 ROAD CLOSURE SIGN ASSEMBLY, PERMANENT	6.000	EACH
238	801-06201 TEMPORARY PANEL SIGNS	90.000	m2
239	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	6,248.000	m
240	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	17,261.000	m

CALL ORDER : 290
 LETTING DATE :

CONTRACT ID : R -28507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
241	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 200 mm	800.000 m
242	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 600 mm	125.000 m
243	801-06586	TEMPORARY PAVEMENT MARKING, 200 mm	150.000 m
244	801-06625	DETOUR ROUTE MARKER ASSEMBLY	63.000 EACH
245	801-06640	CONSTRUCTION SIGN, A	115.000 EACH
246	801-06645	CONSTRUCTION SIGN, B	14.000 EACH
247	801-06710	FLASHING ARROW SIGN	630.000 DAY
248	801-06775	MAINTAINING TRAFFIC	LUMP LUMP
249	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000 EACH
250	801-07118	BARRICADE, III-A	28.800 m
251	801-07119	BARRICADE, III-B	476.000 m
252	801-07120	BARRICADE, III, PERMANENT	212.400 m
253	801-07606	TEMPORARY CROSSOVER DRAINAGE PIPE	510.000 m
254	801-08388	TEMPORARY TRAFFIC BARRIER	1,660.000 m
255	801-08389	TEMPORARY TRAFFIC BARRIER, ANCHORED	360.000 m
256	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	557.000 m
257	801-09133	TEMPORARY CHANGEABLE MESSAGE SIGN	2.000 EACH
258	802-02475	SIGN, PANEL, REMOVE AND RELOCATE	3.000 EACH
259	802-05694	OVERHEAD SIGN STRUCTURE	4.000 EACH
260	802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	518.220 m
261	802-05702	SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	238.500 m
262	802-05705	SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	69.410 m
263	802-07057	SIGN, PANEL, WITH LEGEND	471.000 m2
264	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	93.000 EACH
265	802-07060	SIGN, SHEET, RELOCATE	3.000 EACH
266	802-07138	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, IX	2.000 EACH
267	802-07151	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	20.000 EACH
268	802-07152	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, X	2.000 EACH
269	802-07153	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	24.000 EACH
270	802-07154	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XII	4.000 EACH
271	802-07158	CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, I	4.000 EACH
272	802-07275	BOX TRUSS SIGN FOUNDATION, V-C	3.000 EACH
273	802-07278	BOX TRUSS SIGN FOUNDATION, V-D	5.000 EACH
274	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	26.300 m2
275	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	180.130 m2
276	802-76045	SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	25.800 m2
277	802-76065	SIGN POST, B	7.000 m
278	802-76095	STRUCTURAL STEEL, BREAKAWAY	8,452.000 kg
279	802-76140	OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM	4.000 EACH
280	804-06740	DELINEATOR WITH POST, D2	199.000 EACH
281	805-06592	CONDUIT, STEEL, GALVANIZED, 50mm	157.000 m
282	805-86889	POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	112.500 m
283	805-98336	WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	628.000 m
284	807-02193	LIGHT STANDARD FOUNDATION, 915 mm DIA. X 2450 mm	9.000 EACH
285	807-07580	WIRE, NO. 4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	965.100 m
286	807-84804	LIGHT POLE, 12.8 m E.M.H., 3.1 m MAST ARM, TRANSFORMER BASE	7.000 EACH
287	807-84856	LIGHT POLE, 13.4 m E.M.H., 3.1 m MAST ARM, TRANSFORMER BASE	2.000 EACH
288	807-86620	LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	9.000 EACH

CALL ORDER : 290
 LETTING DATE :

CONTRACT ID : R -28507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
289	807-86810 SERVICE POINT, II	1.000	EACH
290	807-86910 CONNECTOR KIT, UNFUSED	9.000	EACH
291	807-86915 CONNECTOR KIT, FUSED	9.000	EACH
292	807-86920 MULTIPLE COMPRESSION FITTING, NOT WATERPROOFED	10.000	EACH
293	807-86930 INSULATION LINK, NONWATERPROOFED	17.000	EACH
294	807-86955 CABLE DUCT MARKER	6.000	EACH
295	808-01226 SNOWPLOWABLE RAISED PAVEMENT MARKER CASTING, INSTALL	1,514.000	EACH
296	808-03002 LINE, EPOXY, BROKEN, WHITE, 100 mm	11,866.000	m
297	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	40,384.000	m
298	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	33,380.000	m
299	808-05534 LINE, EPOXY, SOLID, WHITE, 200 mm	1,203.000	m
300	808-05535 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, CROSSHATCH LINE,	205.000	m
301	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	213.000	m
302	808-06716 LINE, REMOVE	5,679.000	m
303	808-06800 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW, CROSSHATCH LINE,	15.000	m
304	808-07310 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW,	186.000	m
305	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 600 mm	317.700	m
306	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	38.000	EACH
307	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	27.000	EACH
308	808-75073 PAVEMENT MESSAGE MARKINGS PREFORMED PLASTIC, WORD ONLY	8.000	EACH
309	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	2,514.000	m
310	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	11.000	m
311	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	5.000	EACH
312	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH

CALL ORDER : 300
 LETTING DATE :

CONTRACT ID : R -28547-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	24.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02189 BRIDGE IDENTIFICATION MARKERS, REMOVE AND RESET	1.000	EACH
9	202-02240 PAVEMENT REMOVAL	216.000	SYS
10	202-02241 GUARDRAIL, REMOVE	4,268.000	LFT
11	202-02272 PAVED SIDE DITCH, REMOVE	180.000	LFT
12	202-02276 GUTTER TURNOUT, REINFORCED CONCRETE, REMOVE	4.000	EACH
13	202-02771 CONCRETE APRON, REMOVE	1.000	EACH
14	202-02859 GRATED BOX END SECTION, REMOVE	1.000	EACH
15	202-51133 RAILING, REMOVE	908.000	LFT
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	202-51368 SLOPEWALL, REMOVE	244.000	SYS
18	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
19	202-91840 FENCE, CHAIN LINK, REMOVE	340.000	LFT
20	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	73.000	LFT
21	202-96133 PIPE, REMOVE	152.000	LFT
22	203-02000 EXCAVATION, COMMON	40,721.000	CYS
23	203-02070 BORROW	45,659.000	CYS
24	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	49.000	TON
25	205-06932 TEMPORARY CHECK DAM, STRAW BALES	216.000	LFT
26	205-06933 TEMPORARY DITCH INLET PROTECTION	39.000	EACH
27	205-06937 TEMPORARY SILT FENCE	5,200.000	LFT
28	206-51220 EXCAVATION, WET	193.000	CYS
29	206-51225 EXCAVATION, DRY	1,012.000	CYS
30	206-93520 TEMPORARY SHEET PILING	1,330.000	SFT
31	207-08263 SUBGRADE TREATMENT, TYPE IA	59,278.000	SYS
32	207-08266 SUBGRADE TREATMENT, TYPE III	1,315.000	SYS
33	210-05106 CONCRETE	2.000	EACH
34	210-08372 ROADWAY WEATHER INFORMATION SYSTEM	1.000	EACH
35	211-06467 AGGREGATE FOR END BENT BACKFILL	104.000	CYS
36	211-07454 STRUCTURE BACKFILL	18,457.000	CYS
37	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,248.000	TON
38	302-07455 DENSE GRADED SUBBASE	146.000	CYS
39	304-07490 HMA PATCHING, TYPE B	123.000	TON
40	306-08034 MILLING, ASPHALT, 1 1/2 IN.	2,875.000	SYS
41	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	4,619.000	TON
42	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	7,160.000	TON
43	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	23,356.000	TON
44	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	9,545.000	TON
45	402-07432 HMA SURFACE, TYPE A	537.000	TON
46	402-07433 HMA SURFACE, TYPE B	109.000	TON
47	402-07435 HMA INTERMEDIATE, TYPE A	925.000	TON
48	402-07438 HMA INTERMEDIATE, TYPE B	326.000	TON

CALL ORDER : 300
 LETTING DATE :

CONTRACT ID : R -28547-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
49	406-05520 ASPHALT FOR TACK COAT	52.110	TON
50	601-01522 GUARDRAIL TRANSITION TYPE TGB	5.000	EACH
51	601-05999 CURVED TERMINAL END	4.000	EACH
52	601-06035 GUARDRAIL, RESET	125.000	LFT
53	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
54	601-94690 GUARDRAIL END TREATMENT, MS	1.000	EACH
55	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	1.000	EACH
56	601-97803 GUARDRAIL END TREATMENT, MS, SPARE PARTS PACKAGE	1.000	EACH
57	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,125.000	LFT
58	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	763.000	LFT
59	602-06729 BARRIER DELINEATOR	13.000	EACH
60	603-01159 FENCE, CHAIN LINK, 42 IN.	275.000	LFT
61	603-06045 FENCE, CHAIN LINK, 48 IN.	874.000	LFT
62	604-07894 CURB RAMP, CONCRETE, A	196.000	SYS
63	604-07901 CURB RAMP, CONCRETE, G	14.000	SYS
64	604-07901 CURB RAMP, CONCRETE, G	311.000	SYS
65	604-07902 CURB RAMP, CONCRETE, H	5.000	SYS
66	604-07903 CURB RAMP, CONCRETE, K	48.000	SYS
67	604-91531 SIDEWALK, CONCRETE, 4 IN.	3,810.000	SYS
68	605-06120 CURB, CONCRETE	6,050.000	LFT
69	605-06140 CURB AND GUTTER, CONCRETE	14,526.000	LFT
70	605-06235 CENTER CURB, D, CONCRETE, MODIFIED	1,242.000	LFT
71	605-06255 CENTER CURB, D, CONCRETE	174.000	SYS
72	605-97937 CURB AND GUTTER, CONCRETE, ROLL	190.000	LFT
73	607-90826 GUTTER TURNOUT, CONCRETE	4.000	EACH
74	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	595.000	SYS
75	610-07486 HMA FOR APPROACHES, TYPE A	72.000	TON
76	610-07788 HMA FOR APPROACHES, TYPE D	178.000	TON
77	610-08446 PCCP FOR APPROACHES, 6 IN.	485.000	SYS
78	616-02320 GEOTEXTILES	3,111.000	SYS
79	616-06405 RIPRAP, REVETMENT	2,294.000	TON
80	616-93766 BREAKING CONCRETE SLOPEWALL	174.000	SYS
81	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
82	621-02770 EROSION CONTROL BLANKET	8,320.000	SYS
83	621-06545 FERTILIZER	12.400	TON
84	621-06554 SEED MIXTURE, U	2,325.000	LBS
85	621-06557 SEED MIXTURE, T	2,325.000	LBS
86	621-06565 MULCHING MATERIAL	40.000	TON
87	621-06567 WATER	5,100.000	KGAL
88	621-06574 SODDING	990.000	SYS
89	621-06575 SODDING, NURSERY	22,913.000	SYS
90	701-51190 PILE, STEEL H, HP 10 X 42	6,267.000	LFT
91	701-91792 PILE TIP, STEEL H	203.000	EACH
92	702-51005 CONCRETE, A, SUBSTRUCTURE	538.500	CYS
93	702-51015 CONCRETE, B, FOOTINGS	434.900	CYS
94	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	2,304.000	LBS
95	702-51863 FIELD DRILLED HOLE IN CONCRETE	183.000	EACH
96	702-90915 CONCRETE, A	6.700	CYS

CALL ORDER : 300
 LETTING DATE :

CONTRACT ID : R -28547-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
97	702-92857 CONCRETE, C, SUBSTRUCTURE	189.000	CYS
98	702-93722 CONCRETE, C	17.100	CYS
99	703-51030 REINFORCING STEEL	146,328.000	LBS
100	703-51032 REINFORCING STEEL, EPOXY COATED	440,318.000	LBS
101	703-90512 THREADED BAR SPLICE	53.000	EACH
102	703-97703 THREADED BAR SPLICE, EPOXY COATED	1,996.000	EACH
103	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,202.900	CYS
104	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	2.000	EACH
105	706-06341 RAILING, PF-2	992.000	LFT
106	706-06352 CONCRETE BRIDGE RAILING TRANSITION, TPF-2	2.000	EACH
107	706-51020 CONCRETE, C, RAILING	141.400	CYS
108	709-51821 SURFACE SEAL	LUMP	LUMP
109	710-51864 FIELD DRILLED HOLE	181.000	EACH
110	710-51870 REPOINTING MASONRY IN STRUCTURES	5.000	SFT
111	711-04121 ANCHOR BOLT, AB1	36.000	EACH
112	711-51038 STRUCTURAL STEEL	LUMP	LUMP
113	711-51824 EXPANSION ANCHOR, 0.625 IN.	26.000	EACH
114	715-02246 PIPE END SECTION, 48 IN.	1.000	EACH
115	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	2,041.000	LFT
116	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	13,803.000	LFT
117	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	46.000	LFT
118	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	20.000	LFT
119	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	450.000	LFT
120	715-05148 PIPE, TYPE 2, CIRCULAR, 10 IN.	100.000	LFT
121	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	3,083.000	LFT
122	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	2,217.000	LFT
123	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	1,615.000	LFT
124	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	277.000	LFT
125	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	3,692.000	LFT
126	715-05155 PIPE, TYPE 2, CIRCULAR, 27 IN.	10.000	LFT
127	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	295.000	LFT
128	715-05159 PIPE, TYPE 2, CIRCULAR, 42 IN.	284.000	LFT
129	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN.	1,047.000	LFT
130	715-05335 PIPE, TYPE 2, DEFORMED, MIN. AREA 5.1 SFT.	195.000	LFT
131	715-05407 PIPE, END BENT DRAIN, 6 IN.	130.000	LFT
132	715-08557 PIPE, TYPE 2, DEFORMED, MIN. AREA 14.3 SFT.	88.000	LFT
133	715-08558 PIPE, TYPE 2, DEFORMED, MIN. AREA 15.6 SFT.	163.000	LFT
134	715-46000 PIPE END SECTION, 12 IN.	1.000	EACH
135	715-46010 PIPE END SECTION, 18 IN.	5.000	EACH
136	715-46020 PIPE END SECTION, 24 IN.	6.000	EACH
137	715-46040 PIPE END SECTION, 36 IN.	1.000	EACH
138	715-91361 PIPE, PVC, 6 IN.	142.000	LFT
139	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,450.000	LFT
140	718-52610 AGGREGATE FOR UNDERDRAINS	1,128.000	CYS
141	718-99153 GEOTEXTILES FOR UNDERDRAIN	15,209.000	SYS
142	720-08559 BEST MANAGEMENT PRACITICES	1.000	EACH
143	720-08559 BEST MANAGEMENT PRACITICES	1.000	EACH
144	720-08559 BEST MANAGEMENT PRACITICES	1.000	EACH

CALL ORDER : 300
 LETTING DATE :

CONTRACT ID : R -28547-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ADDED TRAVEL LANES			
145	720-08559	BEST MANAGEMENT PRACITICES	1.000 EACH
146	720-08559	BEST MANAGEMENT PRACITICES	1.000 EACH
147	720-08559	BEST MANAGEMENT PRACITICES	1.000 EACH
148	720-08559	BEST MANAGEMENT PRACITICES	1.000 EACH
149	720-44000	CASTING, ADJUST TO GRADE	10.000 EACH
150	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000 EACH
151	720-45030	INLET, E7	26.000 EACH
152	720-45035	INLET, F7	4.000 EACH
153	720-45040	INLET, G7	1.000 EACH
154	720-45410	MANHOLE, C4	65.000 EACH
155	720-45415	MANHOLE, D4	30.000 EACH
156	720-45416	MANHOLE, E4	5.000 EACH
157	720-45425	MANHOLE, F4	1.000 EACH
158	720-98174	INLET, B15	95.000 EACH
159	720-98555	INLET, C15	11.000 EACH
160	724-51925	STRUCTURAL EXPANSION JOINT, SS	230.000 LFT
161	726-93524	BEARING ASSEMBLY, I	9.000 EACH
162	726-93526	BEARING ASSEMBLY, III	9.000 EACH
163	726-96038	BEARING ASSEMBLY, IV	9.000 EACH
164	728-98377	MASONRY COATING	LUMP LUMP
165	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	23.000 EACH
166	801-03290	CONSTRUCTION SIGN, C	4.000 EACH
167	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	39,500.000 LFT
168	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	11,872.000 LFT
169	801-06640	CONSTRUCTION SIGN, A	48.000 EACH
170	801-06645	CONSTRUCTION SIGN, B	33.000 EACH
171	801-06710	FLASHING ARROW SIGN	1,220.000 DAY
172	801-06775	MAINTAINING TRAFFIC	LUMP LUMP
173	801-07119	BARRICADE, III-B	23.000 LFT
174	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	450.000 LFT
175	801-08388	TEMPORARY TRAFFIC BARRIER	113.000 LFT
176	801-08389	TEMPORARY TRAFFIC BARRIER, ANCHORED	632.000 LFT
177	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1,208.000 LFT
178	801-09133	TEMPORARY CHANGEABLE MESSAGE SIGN	2.000 EACH
179	801-94295	SIGNAL HEAD, RELOCATE	80.000 EACH
180	802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	588.500 LFT
181	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	602.350 SFT
182	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	38.280 SFT
183	802-76045	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	200.060 SFT
184	802-97812	STREET NAME IDENTIFICATION SIGN	8.000 EACH
185	805-01815	SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	16.000 EACH
186	805-01842	HANDHOLE, SIGNAL	45.000 EACH
187	805-02151	PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 12 IN.	34.000 EACH
188	805-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	9,790.000 LFT
189	805-78100	CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	4.000 EACH
190	805-78205	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	32.000 EACH
191	805-78215	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000 EACH
192	805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	13.000 EACH

CALL ORDER : 300
 LETTING DATE :

CONTRACT ID : R -28547-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
193	805-78370 PEDESTRIAN PUSH BUTTON	34.000	EACH
194	805-78415 SPAN, CATENARY, AND TETHER	19.000	EACH
195	805-78420 DISCONNECT HANGER	20.000	EACH
196	805-78465 SIGNAL CABLE, 2C 8GA.	260.000	LFT
197	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	27,540.000	LFT
198	805-78480 SIGNAL CABLE, 3C 14GA.	3,950.000	LFT
199	805-78485 SIGNAL CABLE, 5C 14GA.	4,370.000	LFT
200	805-78490 SIGNAL CABLE, 7C 14GA.	640.000	LFT
201	805-78500 SIGNAL CABLE, 11C 14GA.	3,740.000	LFT
202	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	19,980.000	LFT
203	805-78785 SIGNAL DETECTOR HOUSING	51.000	EACH
204	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	6,755.000	LFT
205	805-78925 CONTROLLER CABINET FOUNDATION, P1	4.000	EACH
206	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	16.000	EACH
207	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	33.000	EACH
208	805-94971 FIBER OPTICS CABLE	4,720.000	LFT
209	805-97114 CABLE, INTERCONNECT, 6 PAIR 19	640.000	LFT
210	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	12,923.000	LFT
211	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,888.000	LFT
212	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	280.000	LFT
213	808-06716 LINE, REMOVE	18,628.000	LFT
214	808-06721 TRANSVERSE MARKINGS, PAINT, CROSSWALK LINE, 4 IN.	280.000	LFT
215	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	1,046.000	LFT
216	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	1,025.000	LFT
217	808-75059 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	1,025.000	LFT
218	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	14,972.000	LFT
219	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	91.000	LFT
220	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	936.000	LFT
221	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	4,232.000	LFT
222	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	41.000	EACH
223	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	37.000	EACH
224	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	262.000	EACH
225	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	435.000	LFT
226	808-95933 CURB PAINTING, YELLOW	429.000	LFT
227	808-98796 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN., 2 FT. LINE, 4 FT.	1,377.000	LFT

CALL ORDER : 310
 LETTING DATE :

CONTRACT ID : R -28573-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
5	202-02240 PAVEMENT REMOVAL	893.000	SYS
6	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
7	203-02000 EXCAVATION, COMMON	2,116.000	CYS
8	207-08268 SUBGRADE TREATMENT, TYPE IV	4,316.000	SYS
9	210-07739 TEMPORARY	101.000	EACH
10	210-07739 TEMPORARY	101.000	EACH
11	211-07454 STRUCTURE BACKFILL	281.000	CYS
12	303-01180 COMPACTED AGGREGATE, NO. 53	149.000	TON
13	402-07433 HMA SURFACE, TYPE B	312.000	TON
14	402-07438 HMA INTERMEDIATE, TYPE B	519.000	TON
15	402-07441 HMA BASE, TYPE B	1,792.000	TON
16	406-05520 ASPHALT FOR TACK COAT	2.830	TON
17	604-06070 SIDEWALK, CONCRETE	174.000	SYS
18	604-07900 CURB RAMP, CONCRETE, F	64.000	SYS
19	604-07901 CURB RAMP, CONCRETE, G	5.000	SYS
20	604-44251 STEPS, CONCRETE	5.000	CYS
21	604-91531 SIDEWALK, CONCRETE, 4 IN.	489.000	SYS
22	605-06090 CURB, INTEGRAL, CONCRETE	347.000	LFT
23	605-06120 CURB, CONCRETE	482.000	LFT
24	605-06140 CURB AND GUTTER, CONCRETE	1,069.000	LFT
25	610-07712 PCCP FOR APPROACHES, 6 IN.	220.000	SYS
26	615-06505 MONUMENT, B	6.000	EACH
27	621-06567 WATER	2.300	KGAL
28	621-06570 TOP SOIL	313.000	CYS
29	621-06574 SODDING	570.000	SYS
30	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	71.000	LFT
31	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	289.000	LFT
32	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
33	720-45090 INLET, UA	1.000	EACH
34	720-45095 INLET, WA	2.000	EACH
35	720-45410 MANHOLE, C4	3.000	EACH
36	720-93443 INLET, U	4.000	EACH
37	720-94525 INLET, W	1.000	EACH
38	720-97359 WATER METER AND LINE, RELOCATE	4.000	EACH
39	732-08419 MODULAR BLOCK WALL	38.000	SYS
40	732-08421 MODULAR BLOCK WALL ERECTION	38.000	SYS
41	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
42	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	276.000	LFT
43	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	6.000	EACH
44	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	20.000	LFT
45	801-06625 DETOUR ROUTE MARKER ASSEMBLY	42.000	EACH
46	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
47	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
48	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 310
 LETTING DATE :

CONTRACT ID : R -28573-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
49	801-07118 BARRICADE, III-A	30.000	LFT
50	801-07119 BARRICADE, III-B	80.000	LFT
51	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	61.000	LFT
52	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	9.000	EACH
53	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	65.750	SFT
54	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	72.000	SFT
55	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	6.000	EACH
56	805-01842 HANDHOLE, SIGNAL	9.000	EACH
57	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	2.000	EACH
58	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	2.000	EACH
59	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
60	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	16.000	EACH
61	805-03159 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM AND 30 FT. ARM	1.000	EACH
62	805-03162 TRAFFIC SIGNAL EQUIPMENT, REMOVAL, STORAGE AND INSTALLATION	LUMP	LUMP
63	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,011.000	LFT
64	805-78069 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 4 PHASE	1.000	EACH
65	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000	EACH
66	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	17.000	EACH
67	805-78445 SIGNAL SERVICE	2.000	EACH
68	805-78467 SIGNAL CABLE, 3C 8GA.	119.000	LFT
69	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	3,180.000	LFT
70	805-78480 SIGNAL CABLE, 3C 14GA.	1,030.000	LFT
71	805-78485 SIGNAL CABLE, 5C 14GA.	548.000	LFT
72	805-78490 SIGNAL CABLE, 7C 14GA.	2,216.000	LFT
73	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	931.000	LFT
74	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
75	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,086.000	LFT
76	805-78900 PEDESTAL FOUNDATION, A	2.000	EACH
77	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
78	805-78930 CONTROLLER CABINET FOUNDATION, M	1.000	EACH
79	805-90005 SIGNAL PEDESTAL, 10 FT.	2.000	EACH
80	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	4.000	EACH
81	805-96121 PEDESTRIAN PUSH BUTTON AND SIGN	8.000	EACH
82	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	19.200	SYS
83	808-06368 TRANSVERSE MARKING, REMOVE	40.000	LFT
84	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	63.000	LFT
85	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	541.000	LFT
86	808-06716 LINE, REMOVE	767.000	LFT
87	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,271.000	LFT
88	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	160.000	LFT
89	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	170.000	LFT
90	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	753.000	LFT
91	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	12.000	EACH
92	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000	EACH
93	808-95933 CURB PAINTING, YELLOW	266.000	LFT

CALL ORDER : 330
 LETTING DATE :

CONTRACT ID : R -28617-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	7.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
5	202-02240 PAVEMENT REMOVAL	100.000	SYS
6	202-02245 TREE, 6 IN., REMOVE	3.000	EACH
7	202-02250 TREE, 10 IN., REMOVE	2.000	EACH
8	202-02278 CURB, CONCRETE, REMOVE	1,790.000	LFT
9	202-02772 CASTING, REMOVE	1.000	EACH
10	202-04089 SIGN, SHEET, REMOVE	25.000	EACH
11	202-07003 REMOVE	LUMP	LUMP
12	202-52710 SIDEWALK, CONCRETE, REMOVE	2,136.900	SYS
13	202-74035 SIGN, REMOVE	25.000	EACH
14	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	6.000	EACH
15	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	6.000	EACH
16	202-92607 SIGN POST, CHANNEL, REMOVE	11.000	EACH
17	203-02020 EXCAVATION, UNCLASSIFIED	500.000	CYS
18	210-04181 BICYCLE RACK	4.000	EACH
19	210-05103 BUILDING	1.000	EACH
20	210-06313 SEAL	7,850.000	LFT
21	210-06984 ADJUST	7.000	EACH
22	210-06994 CONCRETE	LUMP	LUMP
23	210-07642 SOIL PREPARATION	294.400	CYS
24	210-07797 WATER	2.000	EACH
25	210-07797 WATER	2.000	EACH
26	210-08379 STEEL	1.000	EACH
27	211-02050 B BORROW	30.000	CYS
28	211-07454 STRUCTURE BACKFILL	1,250.000	CYS
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,350.000	TON
30	303-07662 STONE	57.000	TON
31	303-07662 STONE	440.000	TON
32	303-07662 STONE	30.000	TON
33	303-07662 STONE	6.000	TON
34	304-07489 HMA PATCHING, TYPE A	44.000	TON
35	305-07458 PCC BASE, 10 IN.	240.900	SYS
36	306-08034 MILLING, ASPHALT, 1 1/2 IN.	870.000	SYS
37	307-05402 CEMENT	185.900	SYS
38	307-05402 CEMENT	55.000	SYS
39	402-07432 HMA SURFACE, TYPE A	174.400	TON
40	406-05521 ASPHALT FOR TACK COAT	650.000	SYS
41	603-03829 FENCE	1,183.500	LFT
42	604-04740 PAVERS	7,450.000	SFT
43	604-04740 PAVERS	200.000	SFT
44	604-04740 PAVERS	1,600.000	SFT
45	604-07894 CURB RAMP, CONCRETE, A	168.000	SYS
46	604-91531 SIDEWALK, CONCRETE, 4 IN.	1,334.000	SYS
47	605-06120 CURB, CONCRETE	380.000	LFT
48	605-06120 CURB, CONCRETE	1,258.700	LFT

CALL ORDER : 330
 LETTING DATE :

CONTRACT ID : R -28617-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
49	605-95635 CURB, CONCRETE, INTEGRAL, MODIFIED	1,777.700	LFT
50	611-03671 TRASH RECEPTACLE	5.000	EACH
51	611-04923 CEMENT CONCRETE PAVEMENT FOR APPROACHES, 10 IN.	231.000	SYS
52	621-06545 FERTILIZER	1.000	TON
53	621-98038 MULCH, HARDWOOD SHREDDED BARK	35.200	CYS
54	622-01937 PLANT	92.000	EACH
55	622-03948 PLANTER	2.000	EACH
56	622-04648 TREE GRATE	3.000	EACH
57	622-05616 PLANT, BROADLEAF EVERGREEN, GLOBE, DWARF, OVER 18 TO 24 IN.	111.000	EACH
58	622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	90.000	EACH
59	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	48.000	EACH
60	622-05654 PLANT, PERENNIAL	483.000	EACH
61	704-04850 CONCRETE	148.500	SYS
62	704-04850 CONCRETE	297.000	SYS
63	712-03812 BENCH	4.000	EACH
64	715-01902 WATER SERVICE LINE, 2 IN.	39.000	LFT
65	715-02889 SERVICE LINE, 1 IN.	26.000	LFT
66	715-04612 PIPE	703.000	LFT
67	715-04612 PIPE	90.000	LFT
68	715-07073 WATER LINE	140.000	LFT
69	715-41045 PIPE, REINFORCED CONCRETE, 12 IN.	55.000	LFT
70	715-93910 WATER SERVICE LINE, ADJUST	8.000	EACH
71	720-03905 CATCH BASIN, A	1.000	EACH
72	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	2.000	EACH
73	732-02388 WATER MAIN	2.000	EACH
74	732-03944 BACKFLOW PREVENTER	1.000	EACH
75	732-03944 BACKFLOW PREVENTER	3.000	EACH
76	732-05559 COUPLING	10.000	EACH
77	732-91742 FIRE HYDRANT	1.000	EACH
78	732-97009 FIRE HYDRANT ASSEMBLY, REMOVE	1.000	EACH
79	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
80	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
81	802-04314 SIGN	26.000	EACH
82	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	73.300	SFT
83	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	80.000	SFT
84	802-97812 STREET NAME IDENTIFICATION SIGN	5.000	EACH
85	805-02426 WIRE, THW, NO. 4 CU, IN PLASTIC DUCT, IN CONDUIT, 4 1C	2,120.000	LFT
86	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,060.000	LFT
87	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	1,440.000	LFT
88	805-96014 SAW CUT, FULL DEPTH	1,755.000	LFT
89	807-02191 HANDHOLE, LIGHTING	4.000	EACH
90	807-03934 LIGHT STRUCTURE, REMOVE	11.000	EACH
91	807-03950 LUMINAIRE, ORNAMENTAL	21.000	EACH
92	807-04143 LIGHT STANDARD, 14 FT. E.M.H., 12 FT., DECORATIVE	21.000	EACH
93	807-04671 OUTLET BOX, ELECTRICAL, WEATHERPROOF	30.000	EACH
94	807-04922 LIGHT STANDARD FOUNDATION	21.000	EACH
95	807-06796 ELECTRIC	30.000	EACH
96	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	2,515.000	LFT

CALL ORDER : 330
 LETTING DATE :

CONTRACT ID : R -28617-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
97	807-08561 ELECTRICAL	2,170.000	LFT
98	807-86810 SERVICE POINT, II	2.000	EACH
99	807-86910 CONNECTOR KIT, UNFUSED	25.000	EACH
100	807-86915 CONNECTOR KIT, FUSED	25.000	EACH
101	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	45.000	EACH
102	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	32.000	EACH
103	807-86930 INSULATION LINK, NONWATERPROOFED	60.000	EACH
104	807-86935 INSULATION LINK, WATERPROOFED	40.000	EACH
105	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	25.000	EACH
106	807-98690 HANDHOLE ADJUSTED TO GRADE	12.000	EACH
107	808-01238 TRANSVERSE MARKING, PAINT, STOP LINE, REMOVE	8.000	EACH
108	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	8.000	EACH
109	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	4.000	EACH
110	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	378.000	LFT
111	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	5.000	SYS
112	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	925.000	LFT
113	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	160.000	LFT
114	808-06716 LINE, REMOVE	400.000	LFT
115	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	500.000	LFT
116	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	96.000	LFT
117	808-97222 PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	1.000	EACH

CALL ORDER : 340
 LETTING DATE :

CONTRACT ID : R -28621-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION OF HOUSES AND BUILDINGS		
1	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
2	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
3	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
4	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
5	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	4,662.000	SFT
6	205-06937 TEMPORARY SILT FENCE	800.000	LFT
7	621-06559 MULCHED SEEDING, R	2,500.000	SYS

CALL ORDER : 350
 LETTING DATE :

CONTRACT ID : R -28623-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	3.000	MOS
3	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02240 PAVEMENT REMOVAL	100.000	m2
8	202-02273 CENTER CURB, CONCRETE, REMOVE	6.000	m2
9	202-02274 CURB, CONCRETE, INTEGRAL, REMOVE	350.000	m
10	213-08058 FLOWABLE BACKFILL	4.000	m3
11	302-06464 SUBBASE FOR PCCP	142.000	m3
12	304-07491 HMA PATCHING, TYPE C	70.000	Mg
13	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
14	501-06323 QC/QA-PCCP, 300 mm	630.000	m2
15	503-05240 D-1 CONTRACTION JOINT	120.000	m
16	605-06095 CURB, INTEGRAL, B, CONCRETE	90.000	m
17	605-06205 CENTER CURB, B, CONCRETE	130.000	m
18	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
19	715-05118 PIPE, TYPE 1, CIRCULAR, 300 mm	2.000	m
20	720-04790 CASTING	2.000	EACH
21	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
22	720-44296 CAP INLET	2.000	EACH
23	720-90017 INLET, J	2.000	EACH
24	801-06640 CONSTRUCTION SIGN, A	25.000	EACH
25	801-06710 FLASHING ARROW SIGN	70.000	DAY
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	1.700	m2
28	808-06368 TRANSVERSE MARKING, REMOVE	6.000	m
29	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	55.000	m
30	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	40.000	m
31	808-06716 LINE, REMOVE	210.000	m
32	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	335.000	m
33	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	10.000	m
34	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	2.000	EACH

CALL ORDER : 360
 LETTING DATE :

CONTRACT ID : R -28679-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	9.000	MOS
3	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02241 GUARDRAIL, REMOVE	427.000	LFT
10	203-02000 EXCAVATION, COMMON	2,717.000	CYS
11	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
12	205-06937 TEMPORARY SILT FENCE	404.000	LFT
13	207-08266 SUBGRADE TREATMENT, TYPE III	6,275.000	SYS
14	211-07454 STRUCTURE BACKFILL	684.200	CYS
15	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	380.000	TON
16	303-07449 COMPACTED AGGREGATE, NO. 73	45.000	TON
17	304-07490 HMA PATCHING, TYPE B	92.000	TON
18	306-08043 MILLING, TRANSITION	381.000	SYS
19	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	480.000	TON
20	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	750.000	TON
21	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	1,510.000	TON
22	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	415.000	TON
23	406-05520 ASPHALT FOR TACK COAT	6.200	TON
24	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
25	604-07901 CURB RAMP, CONCRETE, G	8.000	SYS
26	604-07902 CURB RAMP, CONCRETE, H	231.000	SYS
27	604-07903 CURB RAMP, CONCRETE, K	71.000	SYS
28	604-44251 STEPS, CONCRETE	1.400	CYS
29	604-91531 SIDEWALK, CONCRETE, 4 IN.	1,102.000	SYS
30	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	2,640.000	LFT
31	605-06165 CURB AND GUTTER, C, CONCRETE, MODIFIED	382.000	LFT
32	605-94811 CURB TURNOUT	3.000	EACH
33	610-07487 HMA FOR APPROACHES, TYPE B	745.000	TON
34	610-07712 PCCP FOR APPROACHES, 6 IN.	1,027.000	SYS
35	616-02320 GEOTEXTILES	80.000	SYS
36	616-06405 RIPRAP, REVETMENT	63.000	TON
37	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
38	621-02770 EROSION CONTROL BLANKET	1,345.000	SYS
39	621-06560 MULCHED SEEDING, U	1,345.000	SYS
40	621-06575 SODDING, NURSERY	2,674.100	SYS
41	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	16.000	LFT
42	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	3,265.000	LFT
43	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	86.000	LFT
44	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	26.000	LFT
45	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	510.000	LFT
46	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
47	718-06531 OUTLET PROTECTOR, 3	2.000	EACH
48	718-52610 AGGREGATE FOR UNDERDRAINS	259.000	CYS

CALL ORDER : 360
 LETTING DATE :

CONTRACT ID : R -28679-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT		
49	718-99153 GEOTEXTILES FOR UNDERDRAIN	2,251.000	SYS
50	720-02810 INLET, B5	3.000	EACH
51	720-44000 CASTING, ADJUST TO GRADE	16.000	EACH
52	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	1.000	EACH
53	720-45045 INLET, J10	15.000	EACH
54	720-45260 PIPE CATCH BASIN, 12 IN.	3.000	EACH
55	720-95422 MANHOLE, J4	1.000	EACH
56	720-98174 INLET, B15	1.000	EACH
57	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
58	801-06625 DETOUR ROUTE MARKER ASSEMBLY	23.000	EACH
59	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
60	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
61	801-07119 BARRICADE, III-B	252.000	LFT
62	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	300.000	LFT
63	802-07060 SIGN, SHEET, RELOCATE	3.000	EACH
64	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	123.000	SFT
65	802-99058 SHEET SIGN, INSTALL	14.000	EACH
66	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	30.000	LFT
67	805-02389 SIGNAL CABLE, 2C/14	34.000	LFT
68	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	30.000	LFT
69	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	890.000	LFT
70	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	160.000	LFT
71	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
72	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	340.000	LFT
73	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	252.000	LFT
74	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4,024.000	LFT
75	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	128.000	LFT
76	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	514.000	LFT
77	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
78	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH

CALL ORDER : 380
 LETTING DATE :

CONTRACT ID : RS-27957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-01180 COMPACTED AGGREGATE, NO. 53	550.000	TON
8	304-07491 HMA PATCHING, TYPE C	235.500	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	124,519.000	SYS
10	306-08043 MILLING, TRANSITION	1,893.500	SYS
11	306-08432 MILLING, APPROACH	3,911.000	SYS
12	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
13	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	10,429.000	TON
14	402-07452 HMA, TYPE C, WEDGE AND LEVEL	200.000	TON
15	406-05520 ASPHALT FOR TACK COAT	45.500	TON
16	610-07488 HMA FOR APPROACHES, TYPE C	323.000	TON
17	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,000.000	LFT
18	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8,000.000	LFT
19	801-06640 CONSTRUCTION SIGN, A	25.000	EACH
20	801-06710 FLASHING ARROW SIGN	20.000	DAY
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	9.000	EACH
23	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	4,000.000	LFT
24	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	400.000	LFT
25	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,280.000	LFT
26	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	32,702.000	LFT
27	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	38,634.000	LFT
28	808-75001 LINE, PAINT, BROKEN, WHITE, 5 IN.	7,176.000	LFT
29	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	100.000	LFT
30	808-75072 TRANSVERSE MARKINGS, PAINT, SOLID, WHITE, CROSSHATCH LINE,	300.000	LFT
31	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	403.000	LFT
32	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	45.000	EACH
33	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	19.000	EACH
34	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	532.000	EACH
35	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	532.000	EACH
36	808-97322 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORDS (SIGNAL	2.000	EACH
37	808-97323 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	864.000	LFT

CALL ORDER : 390
 LETTING DATE :

CONTRACT ID : RS-28222-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	9.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02241 GUARDRAIL, REMOVE	75.000	LFT
8	202-93741 GUARD RAIL END TREATMENT, REMOVE	13.000	EACH
9	304-07491 HMA PATCHING, TYPE C	750.000	TON
10	306-08033 MILLING, ASPHALT, 1 IN.	61,000.000	SYS
11	306-08043 MILLING, TRANSITION	480.000	SYS
12	306-08432 MILLING, APPROACH	3,930.000	SYS
13	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
14	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	5,100.000	TON
15	401-07399 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	11,100.000	TON
16	402-07452 HMA, TYPE C, WEDGE AND LEVEL	2,200.000	TON
17	406-05520 ASPHALT FOR TACK COAT	45.000	TON
18	601-06035 GUARDRAIL, RESET	323.000	LFT
19	601-92948 GUARDRAIL, ADJUST HEIGHT	2,028.000	LFT
20	601-94689 GUARDRAIL END TREATMENT, OS	13.000	EACH
21	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	225.000	LFT
22	610-07488 HMA FOR APPROACHES, TYPE C	1,080.000	TON
23	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	4.000	EACH
24	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
25	616-02320 GEOTEXTILES	700.000	SYS
26	616-06451 RIPRAP, UNIFORM	550.000	TON
27	616-95754 PAVED SIDE DITCH, BREAK	15.000	LFT
28	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,168.000	LFT
29	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,084.000	LFT
30	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	40.000	LFT
33	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	44.000	LFT
34	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	1.000	EACH
35	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	250.000	LFT
36	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	4,500.000	LFT
37	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	41,640.000	LFT
38	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	22,774.000	LFT
39	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	15.000	LFT
40	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	483.000	EACH
41	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	483.000	EACH
42	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
43	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
44	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL

CALL ORDER : 400
 LETTING DATE :

CONTRACT ID : RS-28224-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02241 GUARDRAIL, REMOVE	2,257.000	LFT
8	202-93741 GUARD RAIL END TREATMENT, REMOVE	22.000	EACH
9	304-07490 HMA PATCHING, TYPE B	1,600.000	TON
10	306-08033 MILLING, ASPHALT, 1 IN.	115,000.000	SYS
11	306-08034 MILLING, ASPHALT, 1 1/2 IN.	14,000.000	SYS
12	306-08043 MILLING, TRANSITION	7,700.000	SYS
13	306-08432 MILLING, APPROACH	2,700.000	SYS
14	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
15	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	11,300.000	TON
16	401-07379 QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	13,000.000	TON
17	402-07451 HMA, TYPE B, WEDGE AND LEVEL	5,400.000	TON
18	406-05520 ASPHALT FOR TACK COAT	75.000	TON
19	601-01522 GUARDRAIL TRANSITION TYPE TGB	12.000	EACH
20	601-94689 GUARDRAIL END TREATMENT, OS	22.000	EACH
21	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	2,240.000	LFT
22	604-07896 CURB RAMP, CONCRETE, B	3.000	SYS
23	604-07901 CURB RAMP, CONCRETE, G	4.000	SYS
24	604-07901 CURB RAMP, CONCRETE, G	2.000	SYS
25	604-07902 CURB RAMP, CONCRETE, H	7.000	SYS
26	604-07903 CURB RAMP, CONCRETE, K	1.000	SYS
27	610-07487 HMA FOR APPROACHES, TYPE B	2,000.000	TON
28	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	80.000	TON
29	612-60410 DRILLED HOLE FOR UNDERSEAL	1,300.000	EACH
30	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
31	616-02320 GEOTEXTILES	125.000	SYS
32	616-06451 RIPRAP, UNIFORM	200.000	TON
33	621-06574 SODDING	10.000	SYS
34	706-08188 RAILING, TR	162.000	LFT
35	715-06675 PIPE LINER	101.000	LFT
36	732-08419 MODULAR BLOCK WALL	6.000	SYS
37	732-08421 MODULAR BLOCK WALL ERECTION	6.000	SYS
38	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,000.000	LFT
39	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,000.000	LFT
40	801-06640 CONSTRUCTION SIGN, A	56.000	EACH
41	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
42	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	8.000	EACH
43	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	6,200.000	LFT
44	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	76,700.000	LFT
45	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	41,500.000	LFT
46	808-75007 LINE, PAINT, SOLID, WHITE, 6 IN.	1,500.000	LFT
47	808-75272 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	600.000	LFT
48	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	75.000	LFT

CALL ORDER : 400
 LETTING DATE :

CONTRACT ID : RS-28224-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	50.000	LFT
50 808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	225.000	LFT
51 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
52 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000	EACH
53 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	852.000	EACH
54 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	852.000	EACH
55 808-98875	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	170.000	LFT

CALL ORDER : 410
 LETTING DATE :

CONTRACT ID : RS-28322-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-07039 FIELD OFFICE, B	10.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
6	105-08523 RADIO SERVICE	5.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	260.000	LFT
13	202-02278 CURB, CONCRETE, REMOVE	390.000	LFT
14	202-52710 SIDEWALK, CONCRETE, REMOVE	150.000	SYS
15	202-93741 GUARD RAIL END TREATMENT, REMOVE	8.000	EACH
16	303-01180 COMPACTED AGGREGATE, NO. 53	3,100.000	TON
17	303-07449 COMPACTED AGGREGATE, NO. 73	1,000.000	TON
18	304-07491 HMA PATCHING, TYPE C	2,000.000	TON
19	304-07494 WIDENING WITH HMA, TYPE C	3,100.000	TON
20	306-08034 MILLING, ASPHALT, 1 1/2 IN.	150,680.000	SYS
21	306-08043 MILLING, TRANSITION	2,140.000	SYS
22	306-08432 MILLING, APPROACH	7,772.000	SYS
23	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
24	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	13,300.000	TON
25	401-07372 QC/QA-HMA, 3, 64, INTERMEDIATE, 12.5 mm	5,900.000	TON
26	402-07452 HMA, TYPE C, WEDGE AND LEVEL	100.000	TON
27	406-05520 ASPHALT FOR TACK COAT	55.000	TON
28	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
29	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
30	601-93346 GUARD RAIL CONNECTOR, AS	4.000	EACH
31	601-94689 GUARDRAIL END TREATMENT, OS	10.000	EACH
32	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	643.750	LFT
33	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	8.000	EACH
34	604-07896 CURB RAMP, CONCRETE, B	6.000	SYS
35	604-07897 CURB RAMP, CONCRETE, C	21.600	SYS
36	604-07898 CURB RAMP, CONCRETE, D	24.300	SYS
37	604-07901 CURB RAMP, CONCRETE, G	98.000	SYS
38	605-06120 CURB, CONCRETE	390.000	LFT
39	608-04395 AGGREGATE FOR SHOULDER DRAINS	10.000	TON
40	610-07488 HMA FOR APPROACHES, TYPE C	868.000	TON
41	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
42	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,519.000	LFT
43	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,631.000	LFT
44	801-06640 CONSTRUCTION SIGN, A	50.000	EACH
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	1,106.000	LFT
47	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	651.000	LFT
48	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH

CALL ORDER : 410
 LETTING DATE :

CONTRACT ID : RS-28322-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	77.000	LFT
50	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	102,386.000	LFT
51	808-06716 LINE, REMOVE	1,834.000	LFT
52	808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1,280.000	LFT
53	808-75215 LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	84.000	LFT
54	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	9,912.000	LFT
55	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	46,517.000	LFT
56	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	63.000	LFT
57	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	100.000	LFT
58	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,050.000	EACH
59	808-97323 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	156.000	LFT

CALL ORDER : 420
 LETTING DATE :

CONTRACT ID : RS-28324-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02241 GUARDRAIL, REMOVE	62.000	LFT
10	202-93741 GUARD RAIL END TREATMENT, REMOVE	4.000	EACH
11	203-02118 LINEAR GRADING	LUMP	LUMP
12	303-01180 COMPACTED AGGREGATE, NO. 53	9,600.000	TON
13	303-07449 COMPACTED AGGREGATE, NO. 73	100.000	TON
14	304-07490 HMA PATCHING, TYPE B	3,450.000	TON
15	304-07493 WIDENING WITH HMA, TYPE B	5,450.000	TON
16	306-08033 MILLING, ASPHALT, 1 IN.	103,761.000	SYS
17	306-08043 MILLING, TRANSITION	7,720.000	SYS
18	306-08432 MILLING, APPROACH	775.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	10,400.000	TON
21	401-07371 QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm	13,600.000	TON
22	402-07451 HMA, TYPE B, WEDGE AND LEVEL	7,860.000	TON
23	406-05520 ASPHALT FOR TACK COAT	98.000	TON
24	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
25	610-07487 HMA FOR APPROACHES, TYPE B	653.000	TON
26	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
27	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,625.000	LFT
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,313.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	33.000	EACH
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	230.000	LFT
32	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	28.750	LFT
33	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	85,406.000	LFT
34	808-06716 LINE, REMOVE	258.750	LFT
35	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	8,310.000	LFT
36	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	35,630.000	LFT
37	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	12.000	LFT
38	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	826.000	EACH
39	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL

CALL ORDER : 440
 LETTING DATE :

CONTRACT ID : RS-28408-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE AND SIDEWALK RAMPS			
1	105-06899 RADIO	1.000	EACH
2	105-07039 FIELD OFFICE, B	5.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
5	105-08523 RADIO SERVICE	5.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	10.000	SYS
12	203-90014 LINEAR GRADING	12.000	STA
13	213-04324 FLOWABLE FILL	8.000	CYS
14	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	15.000	TON
15	303-01180 COMPACTED AGGREGATE, NO. 53	270.000	TON
16	304-07490 HMA PATCHING, TYPE B	70.000	TON
17	304-07492 WIDENING WITH HMA, TYPE A	440.000	TON
18	306-08034 MILLING, ASPHALT, 1 1/2 IN.	25,900.000	SYS
19	306-08041 MILLING, PCCP	100.000	SYS
20	306-08432 MILLING, APPROACH	1,475.000	SYS
21	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	2,250.000	TON
22	402-07432 HMA SURFACE, TYPE A	36.000	TON
23	406-05520 ASPHALT FOR TACK COAT	8.000	TON
24	507-07479 HMA PARTIAL DEPTH PATCH	100.000	TON
25	604-06070 SIDEWALK, CONCRETE	380.000	SYS
26	604-07894 CURB RAMP, CONCRETE, A	70.000	SYS
27	604-07896 CURB RAMP, CONCRETE, B	70.000	SYS
28	604-07897 CURB RAMP, CONCRETE, C	20.000	SYS
29	604-07898 CURB RAMP, CONCRETE, D	24.000	SYS
30	604-07899 CURB RAMP, CONCRETE, E	50.000	SYS
31	604-07900 CURB RAMP, CONCRETE, F	220.000	SYS
32	604-07903 CURB RAMP, CONCRETE, K	34.000	SYS
33	605-06120 CURB, CONCRETE	1,060.000	LFT
34	610-07486 HMA FOR APPROACHES, TYPE A	161.000	TON
35	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
36	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	7.000	EACH
37	621-06574 SODDING	200.000	SYS
38	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	35.000	LFT
39	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	20.000	TON
40	720-44000 CASTING, ADJUST TO GRADE	15.000	EACH
41	720-44041 CASTING, 7	1.000	EACH
42	720-45005 INLET, A2	1.000	EACH
43	720-45080 INLET, S14	2.000	EACH
44	720-60220 RECONSTRUCTED STRUCTURE	20.000	LFT
45	720-94473 INLET, RECONSTRUCT	40.000	LFT
46	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	940.000	LFT
47	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	940.000	LFT
48	801-06640 CONSTRUCTION SIGN, A	42.000	EACH

CALL ORDER : 440
 LETTING DATE :

CONTRACT ID : RS-28408-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE AND SIDEWALK RAMPS		
49	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
50	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
51	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	130.000	LFT
52	802-91122 SIGN, GROUND MOUNTED, RESET	9.000	EACH
53	808-05929 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 8 IN.	400.000	LFT
54	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	460.000	LFT
55	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	9,800.000	LFT
56	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,100.000	LFT
57	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,400.000	LFT
58	808-75272 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	180.000	LFT
59	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	150.000	LFT
60	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	2.000	EACH
61	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
62	808-75330 PAVEMENT MESSAGE MARKINGS THERMOPLASTIC, WORD (PEDX)	2.000	EACH
63	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
64	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	70.000	EACH
65	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	70.000	EACH

CALL ORDER : 450
 LETTING DATE :

CONTRACT ID : RS-28411-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	6,600.000	SYS
11	202-02676 TRANSPORTATION OF SALVAGEABLE MILLED MATERIAL	2,000.000	TON
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5.000	TON
13	303-07449 COMPACTED AGGREGATE, NO. 73	6,000.000	TON
14	304-07491 HMA PATCHING, TYPE C	6,100.000	TON
15	305-03375 CRACKS, TRANSVERSE, ROUT, CLEAN, AND SEAL	156.000	LFT
16	305-93341 SAW, CLEAN AND SEAL LONGITUDINAL JOINTS	68,616.000	LFT
17	305-93342 SAW, CLEAN AND SEAL TRANSVERSE JOINTS	84,459.000	LFT
18	306-08034 MILLING, ASPHALT, 1 1/2 IN.	319,000.000	SYS
19	306-08041 MILLING, PCCP	220.000	SYS
20	306-08432 MILLING, APPROACH	2,700.000	SYS
21	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
22	401-07330 QC/QA-HMA, 5, 70, SURFACE, 9.5 mm	26,000.000	TON
23	402-07432 HMA SURFACE, TYPE A	305.000	TON
24	406-05520 ASPHALT FOR TACK COAT	80.000	TON
25	507-07479 HMA PARTIAL DEPTH PATCH	1.000	TON
26	606-07484 MILLED HMA SHOULDER CORRUGATIONS	16,000.000	LFT
27	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	40,000.000	LFT
28	608-04396 SHOULDER DRAIN	1.000	EACH
29	610-07488 HMA FOR APPROACHES, TYPE C	220.000	TON
30	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	1.000	EACH
31	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	38.000	EACH
32	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	24,700.000	LFT
33	801-06208 TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	11,200.000	LFT
34	801-06640 CONSTRUCTION SIGN, A	81.000	EACH
35	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
36	801-06710 FLASHING ARROW SIGN	90.000	DAY
37	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
38	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH
39	801-08388 TEMPORARY TRAFFIC BARRIER	1,590.000	LFT
40	801-08389 TEMPORARY TRAFFIC BARRIER, ANCHORED	440.000	LFT
41	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
42	801-92448 CONSTRUCTION SIGNS, MOBILE	250.000	DAY
43	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	14.000	LFT
44	802-91122 SIGN, GROUND MOUNTED, RESET	2.000	EACH
45	804-04435 DELINEATOR POST, REMOVE	10.000	EACH
46	804-06771 DELINEATOR POST, FLEXIBLE	10.000	EACH
47	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	12,800.000	LFT
48	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	266,100.000	LFT

CALL ORDER : 450
 LETTING DATE :

CONTRACT ID : RS-28411-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	255,800.000	LFT
50	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN.	1,800.000	LFT
51	808-06716 LINE, REMOVE	32,600.000	LFT
52	808-07591 LINE, EPOXY, SOLID, WHITE, 24 IN.	575.000	LFT
53	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	1,205.000	LFT
54	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	22.000	EACH
55	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	24.000	EACH
56	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	7,500.000	LFT
57	808-75059 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	18,800.000	LFT
58	808-75994 PRISMATIC REFLECTOR	545.000	EACH
59	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,627.000	EACH
60	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,627.000	EACH

CALL ORDER : 460
 LETTING DATE :

CONTRACT ID : RS-28414-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	304-07490 HMA PATCHING, TYPE B	100.000	TON
11	306-08034 MILLING, ASPHALT, 1 1/2 IN.	318,400.000	SYS
12	306-08043 MILLING, TRANSITION	3,600.000	SYS
13	306-08432 MILLING, APPROACH	2,640.000	SYS
14	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
15	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	27,581.000	TON
16	406-05520 ASPHALT FOR TACK COAT	115.000	TON
17	610-07487 HMA FOR APPROACHES, TYPE B	2,287.000	TON
18	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
19	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	9,900.000	LFT
20	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,900.000	LFT
21	801-06640 CONSTRUCTION SIGN, A	80.000	EACH
22	801-06710 FLASHING ARROW SIGN	90.000	DAY
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
24	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
25	801-92448 CONSTRUCTION SIGNS, MOBILE	90.000	DAY
26	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	114,900.000	LFT
27	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	98,800.000	LFT
28	808-75061 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	24,700.000	LFT
29	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	320.000	LFT
30	808-75071 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC LANE INDICATION	84.000	EACH
31	808-75073 PAVEMENT MESSAGE MARKINGS PREFORMED PLASTIC, WORD ONLY	84.000	EACH
32	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,640.000	EACH
33	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,640.000	EACH

CALL ORDER : 466
 LETTING DATE :

CONTRACT ID : RS-28475-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02271 HEADWALL, REMOVE	2.000	EACH
8	202-96133 PIPE, REMOVE	48.000	LFT
9	303-01180 COMPACTED AGGREGATE, NO. 53	3,183.000	TON
10	304-07491 HMA PATCHING, TYPE C	500.000	TON
11	304-07494 WIDENING WITH HMA, TYPE C	376.000	TON
12	306-08033 MILLING, ASPHALT, 1 IN.	354,873.000	SYS
13	306-08043 MILLING, TRANSITION	1,147.000	SYS
14	306-08432 MILLING, APPROACH	14,393.000	SYS
15	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
16	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	29,372.000	TON
17	402-07452 HMA, TYPE C, WEDGE AND LEVEL	200.000	TON
18	406-05520 ASPHALT FOR TACK COAT	123.000	TON
19	610-07488 HMA FOR APPROACHES, TYPE C	1,187.500	TON
20	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
21	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
22	621-06567 WATER	2.000	KGAL
23	621-06626 MULCHED SEEDING, D	400.000	SYS
24	715-05233 PIPE, TYPE 1, DEFORMED, 3.3 SQ. FT.	80.000	LFT
25	715-07029 SAFETY METAL END SECTION, 4:1, MIN. AREA 3.3 SFT.	2.000	EACH
26	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
27	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	11,000.000	LFT
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	11,000.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	62.000	EACH
30	801-06710 FLASHING ARROW SIGN	30.000	DAY
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	4.000	EACH
33	802-76055 SIGN POST, A	6.000	LFT
34	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,785.000	LFT
35	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	287.500	LFT
36	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	920.000	LFT
37	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	8.000	EACH
38	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	99,000.000	LFT
39	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	87,000.000	LFT
40	808-75001 LINE, PAINT, BROKEN, WHITE, 5 IN.	22,000.000	LFT
41	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	1,700.000	LFT
42	808-75072 TRANSVERSE MARKINGS, PAINT, SOLID, WHITE, CROSSHATCH LINE,	1,100.000	LFT
43	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	290.000	LFT
44	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	47.000	EACH
45	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	21.000	EACH
46	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	4.000	EACH
47	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,115.000	EACH
48	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,115.000	EACH

CALL ORDER : 470
 LETTING DATE :

CONTRACT ID : RS-28477-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	303-01180 COMPACTED AGGREGATE, NO. 53	903.000	TON
11	304-07491 HMA PATCHING, TYPE C	500.000	TON
12	306-08034 MILLING, ASPHALT, 1 1/2 IN.	8,022.000	SYS
13	306-08042 MILLING, SCARIFICATION/PROFILE	166,517.000	SYS
14	306-08043 MILLING, TRANSITION	2,500.000	SYS
15	306-08432 MILLING, APPROACH	11,574.000	SYS
16	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
17	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	13,737.630	TON
18	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	661.800	TON
19	402-07452 HMA, TYPE C, WEDGE AND LEVEL	250.000	TON
20	406-05520 ASPHALT FOR TACK COAT	51.180	TON
21	610-07488 HMA FOR APPROACHES, TYPE C	954.860	TON
22	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	1.000	EACH
23	720-44000 CASTING, ADJUST TO GRADE	16.000	EACH
24	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,214.000	LFT
25	801-06640 CONSTRUCTION SIGN, A	41.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	808-05929 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 8 IN.	96.000	LFT
28	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	8,946.000	LFT
29	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	51,905.000	LFT
30	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	104,280.000	LFT
31	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	43.000	LFT
32	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
33	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
34	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,251.000	EACH
35	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,251.000	EACH

CALL ORDER : 480
 LETTING DATE :

CONTRACT ID : RS-28481-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06904 PHONE(SUPERVISOR)	1.000	EACH
3	105-06905 PHONE(INSPECTOR)	2.000	EACH
4	105-06906 CELLULAR SERVICE(SUPERVISOR)	4.000	MOS
5	105-06907 CELLULAR SERVICE(INSPECTOR)	8.000	MOS
6	105-07039 FIELD OFFICE, B	4.000	MOS
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-02241 GUARDRAIL, REMOVE	1,151.000	LFT
12	202-02271 HEADWALL, REMOVE	2.000	EACH
13	202-02278 CURB, CONCRETE, REMOVE	207.000	LFT
14	202-52710 SIDEWALK, CONCRETE, REMOVE	80.000	SYS
15	202-93741 GUARD RAIL END TREATMENT, REMOVE	5.000	EACH
16	203-02080 LINEAR GRADING	0.100	MILE
17	211-07454 STRUCTURE BACKFILL	11.000	CYS
18	303-07449 COMPACTED AGGREGATE, NO. 73	2,013.000	TON
19	304-07491 HMA PATCHING, TYPE C	520.000	TON
20	306-08033 MILLING, ASPHALT, 1 IN.	149,717.000	SYS
21	306-08043 MILLING, TRANSITION	2,307.000	SYS
22	306-08432 MILLING, APPROACH	2,255.000	SYS
23	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
24	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	12,352.000	TON
25	401-07372 QC/QA-HMA, 3, 64, INTERMEDIATE, 12.5 mm	16,445.000	TON
26	406-05520 ASPHALT FOR TACK COAT	72.000	TON
27	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	1.000	EACH
28	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	3.000	EACH
29	601-02159 GUARDRAIL, W BEAM, SPECIAL POST ATTACHMENT	25.000	LFT
30	601-93346 GUARD RAIL CONNECTOR, AS	4.000	EACH
31	601-94689 GUARDRAIL END TREATMENT, OS	7.000	EACH
32	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	4.000	EACH
33	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	937.500	LFT
34	601-99106 GUARDRAIL, W BEAM, 3 FT. 1.5 IN. SPACING	50.000	LFT
35	604-06070 SIDEWALK, CONCRETE	80.000	SYS
36	604-07894 CURB RAMP, CONCRETE, A	36.000	SYS
37	604-07901 CURB RAMP, CONCRETE, G	28.000	SYS
38	605-06120 CURB, CONCRETE	207.000	LFT
39	610-07488 HMA FOR APPROACHES, TYPE C	310.000	TON
40	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	3.060	TON
41	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
42	612-60410 DRILLED HOLE FOR UNDERSEAL	53.000	EACH
43	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
44	621-06574 SODDING	70.000	SYS
45	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	46.000	LFT
46	715-46005 PIPE END SECTION, 15 IN.	4.000	EACH
47	725-06866 PIPE LINER, THERMOPLASTIC, 15 IN.	42.000	LFT
48	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH

CALL ORDER : 480
 LETTING DATE :

CONTRACT ID : RS-28481-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
50	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,645.000	LFT
51	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,322.000	LFT
52	801-06625 DETOUR ROUTE MARKER ASSEMBLY	52.000	EACH
53	801-06640 CONSTRUCTION SIGN, A	38.000	EACH
54	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
55	801-07118 BARRICADE, III-A	72.000	LFT
56	801-07119 BARRICADE, III-B	48.000	LFT
57	804-06771 DELINEATOR POST, FLEXIBLE	4.000	EACH
58	804-06771 DELINEATOR POST, FLEXIBLE	38.000	EACH
59	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	86,128.000	LFT
60	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	9,378.000	LFT
61	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	18,664.000	LFT
62	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	65.000	LFT
63	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	635.000	EACH
64	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	635.000	EACH
65	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL

CALL ORDER : 486
 LETTING DATE :

CONTRACT ID : RS-28513-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	3,156.000	SYS
11	202-02241 GUARDRAIL, REMOVE	4,015.000	LFT
12	202-04089 SIGN, SHEET, REMOVE	1.000	EACH
13	202-93741 GUARD RAIL END TREATMENT, REMOVE	11.000	EACH
14	203-02080 LINEAR GRADING	0.260	MILE
15	207-08268 SUBGRADE TREATMENT, TYPE IV	1,747.000	SYS
16	210-06369 SAW CUT	1,202.000	LFT
17	303-07449 COMPACTED AGGREGATE, NO. 73	2,738.000	TON
18	304-07491 HMA PATCHING, TYPE C	500.000	TON
19	305-07465 PCC BASE PATCHING, 10 IN.	3,237.000	SYS
20	306-08033 MILLING, ASPHALT, 1 IN.	177,356.000	SYS
21	306-08043 MILLING, TRANSITION	12,488.000	SYS
22	306-08432 MILLING, APPROACH	2,496.000	SYS
23	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
24	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	3,692.000	TON
25	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	10,940.000	TON
26	401-07370 QC/QA-HMA, 1, 64, INTERMEDIATE, 12.5 mm	4,921.000	TON
27	401-07379 QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	14,692.000	TON
28	402-07442 HMA BASE, TYPE C	769.000	TON
29	406-05520 ASPHALT FOR TACK COAT	89.000	TON
30	601-05999 CURVED TERMINAL END	3.000	EACH
31	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
32	601-08436 GUARDRAIL END TREATMENT, TYPE MS, SPARE PARTS	1.000	EACH
33	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
34	601-94690 GUARDRAIL END TREATMENT, MS	4.000	EACH
35	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	4,325.000	LFT
36	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	2,175.000	LFT
37	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	2.000	TON
38	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
39	612-60410 DRILLED HOLE FOR UNDERSEAL	64.000	EACH
40	621-06574 SODDING	4,680.000	SYS
41	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	11,742.000	LFT
42	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,871.000	LFT
43	801-06640 CONSTRUCTION SIGN, A	36.000	EACH
44	801-06710 FLASHING ARROW SIGN	120.000	DAY
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
47	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	24.000	LFT
48	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	6.300	SFT

CALL ORDER : 486
 LETTING DATE :

CONTRACT ID : RS-28513-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	802-76030 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.100 IN. THICKNESS	3.900	SFT
50	804-06771 DELINEATOR POST, FLEXIBLE	172.000	EACH
51	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	9,324.000	LFT
52	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	40,298.000	LFT
53	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	37,298.000	LFT
54	808-75256 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	895.000	LFT
55	808-75274 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	5,332.000	LFT
56	808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	132.000	LFT
57	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	100.000	LFT
58	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	597.000	EACH
59	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	597.000	EACH

CALL ORDER : 490
 LETTING DATE :

CONTRACT ID : RS-28588-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 CONCRETE PREVENTIVE MAINTENANCE AND ASPHALT SHOULDER REHAB			
1	105-07039	7.000	MOS
2	105-08520	3.000	EACH
3	105-08521	21.000	MOS
4	105-08524	1.000	DOL
5	109-08440	1.000	DOL
6	109-08443	1.000	DOL
7	109-08444	1.000	DOL
8	110-01001	LUMP	LUMP
9	202-02241	2,079.000	LFT
10	202-90277	4.000	EACH
11	202-93741	14.000	EACH
12	301-07448	34,788.000	TON
13	303-01180	3,111.000	TON
14	304-07489	200.000	TON
15	304-07492	48.000	TON
16	305-03375	1,000.000	LFT
17	305-93341	60,600.000	LFT
18	305-93342	95,000.000	LFT
19	306-08039	80,778.000	SYS
20	306-08432	42,906.000	SYS
21	401-07320	6,497.000	TON
22	401-07406	19,495.000	TON
23	406-05520	52.000	TON
24	503-05240	24.500	LFT
25	506-06333	250.000	SYS
26	506-06334	50.000	SYS
27	507-07479	10.000	TON
28	601-94689	6.000	EACH
29	601-94690	2.000	EACH
30	601-99105	1,100.500	LFT
31	601-99108	563.000	LFT
32	606-07484	96,960.000	LFT
33	608-04395	12.000	TON
34	610-07486	3,725.000	TON
35	612-04315	68.200	TON
36	612-05081	1.000	EACH
37	612-60410	960.000	EACH
38	715-05048	7,160.000	LFT
39	715-05053	6,972.000	LFT
40	718-06526	775.000	TON
41	718-06528	185.000	EACH
42	718-06532	3,000.000	LFT
43	718-52610	644.000	CYS
44	801-06640	42.000	EACH
45	801-06710	50.000	DAY
46	801-06775	LUMP	LUMP
47	801-92448	300.000	DAY
48	805-78470	1,972.000	LFT

CALL ORDER : 490
 LETTING DATE :

CONTRACT ID : RS-28588-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	CONCRETE PREVENTIVE MAINTENANCE AND ASPHALT SHOULDER REHAB		
49	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
50	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	656.000	LFT
51	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	5,880.000	LFT
52	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	12,600.000	LFT
53	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	408.000	LFT
54	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	70.000	EACH
55	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	70.000	EACH
56	808-75994 PRISMATIC REFLECTOR	800.000	EACH
57	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	325.000	EACH
58	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	40.000	EACH
59	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	325.000	EACH

CALL ORDER : 500
 LETTING DATE :

CONTRACT ID : RS-28589-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06899 RADIO	1.000	EACH
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08523 RADIO SERVICE	6.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-90277 DETECTOR HOUSING, REMOVE	7.000	EACH
12	202-93741 GUARD RAIL END TREATMENT, REMOVE	9.000	EACH
13	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	282.000	TON
14	303-07449 COMPACTED AGGREGATE, NO. 73	2,417.000	TON
15	304-07490 HMA PATCHING, TYPE B	129.000	TON
16	306-08033 MILLING, ASPHALT, 1 IN.	151,492.000	SYS
17	306-08043 MILLING, TRANSITION	714.000	SYS
18	306-08432 MILLING, APPROACH	22,879.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	12,211.000	TON
21	402-07433 HMA SURFACE, TYPE B	287.000	TON
22	406-05520 ASPHALT FOR TACK COAT	46.000	TON
23	507-07479 HMA PARTIAL DEPTH PATCH	112.000	TON
24	601-91426 GUARD RAIL TERMINAL END SECTION, A	1.000	EACH
25	601-94689 GUARDRAIL END TREATMENT, OS	9.000	EACH
26	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	25.000	LFT
27	610-07486 HMA FOR APPROACHES, TYPE A	2,579.000	TON
28	611-06497 MAILBOX ASSEMBLY, SINGLE	19.000	EACH
29	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	76.000	EACH
30	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	34.100	TON
31	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
32	612-60410 DRILLED HOLE FOR UNDERSEAL	480.000	EACH
33	615-06520 MONUMENT, RE-ESTABLISH	7.000	EACH
34	715-01662 PIPE CLEANING, 12 IN. TO 48 IN. DIA.	30.000	LFT
35	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	96.000	LFT
36	720-45335 CATCH BASIN, E7, MODIFIED	1.000	EACH
37	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,183.000	LFT
38	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,183.000	LFT
39	801-06640 CONSTRUCTION SIGN, A	33.000	EACH
40	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
41	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
42	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	439.000	LFT
43	805-78785 SIGNAL DETECTOR HOUSING	7.000	EACH
44	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	439.000	LFT
45	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	85,938.000	LFT
46	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	39,973.000	LFT
47	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	8,024.000	LFT
48	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	302.000	LFT

CALL ORDER : 500
 LETTING DATE :

CONTRACT ID : RS-28589-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,066.000	EACH
50 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1,066.000	EACH

CALL ORDER : 510
 LETTING DATE :

CONTRACT ID : RS-28591-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-93741 GUARD RAIL END TREATMENT, REMOVE	16.000	EACH
8	203-90014 LINEAR GRADING	2.000	STA
9	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	862.000	TON
10	303-07449 COMPACTED AGGREGATE, NO. 73	5,531.000	TON
11	304-07490 HMA PATCHING, TYPE B	2,840.000	TON
12	306-08033 MILLING, ASPHALT, 1 IN.	139,967.000	SYS
13	306-08043 MILLING, TRANSITION	2,037.000	SYS
14	306-08432 MILLING, APPROACH	9,667.000	SYS
15	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
16	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	11,634.000	TON
17	401-07371 QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm	19,390.000	TON
18	402-07433 HMA SURFACE, TYPE B	257.000	TON
19	402-07438 HMA INTERMEDIATE, TYPE B	428.000	TON
20	402-07451 HMA, TYPE B, WEDGE AND LEVEL	212.000	TON
21	406-05520 ASPHALT FOR TACK COAT	78.000	TON
22	507-07479 HMA PARTIAL DEPTH PATCH	88.000	TON
23	601-06035 GUARDRAIL, RESET	138.000	LFT
24	601-94689 GUARDRAIL END TREATMENT, OS	16.000	EACH
25	608-04396 SHOULDER DRAIN	20.000	EACH
26	610-07486 HMA FOR APPROACHES, TYPE A	3,846.000	TON
27	611-06497 MAILBOX ASSEMBLY, SINGLE	20.000	EACH
28	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	78.000	EACH
29	615-06520 MONUMENT, RE-ESTABLISH	23.000	EACH
30	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	5,519.000	LFT
31	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,776.000	LFT
32	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
33	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
34	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
35	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	10,172.000	LFT
36	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	95,820.000	LFT
37	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	28,966.000	LFT
38	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	35.000	LFT
39	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	1.000	EACH
40	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	871.000	EACH
41	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	871.000	EACH

CALL ORDER : 518
 LETTING DATE :

CONTRACT ID : RS-28615-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	4.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	100.000	LFT
11	202-93741 GUARD RAIL END TREATMENT, REMOVE	6.000	EACH
12	203-02080 LINEAR GRADING	0.100	MILE
13	207-08268 SUBGRADE TREATMENT, TYPE IV	4,232.000	SYS
14	303-07449 COMPACTED AGGREGATE, NO. 73	5,700.000	TON
15	304-07491 HMA PATCHING, TYPE C	500.000	TON
16	304-07492 WIDENING WITH HMA, TYPE A	978.000	TON
17	306-08033 MILLING, ASPHALT, 1 IN.	52,438.000	SYS
18	306-08043 MILLING, TRANSITION	728.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	7,400.000	TON
21	401-07372 QC/QA-HMA, 3, 64, INTERMEDIATE, 12.5 mm	10,162.000	TON
22	406-05520 ASPHALT FOR TACK COAT	34.400	TON
23	601-93346 GUARD RAIL CONNECTOR, AS	4.000	EACH
24	601-94689 GUARDRAIL END TREATMENT, OS	6.000	EACH
25	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	2.000	EACH
26	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	381.250	LFT
27	610-07488 HMA FOR APPROACHES, TYPE C	573.000	TON
28	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
29	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	6,117.000	LFT
30	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,065.000	LFT
31	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
32	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
33	804-06771 DELINEATOR POST, FLEXIBLE	100.000	EACH
34	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	66,354.000	LFT
35	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	6,640.000	LFT
36	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	15,911.000	LFT
37	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	15.000	LFT
38	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	545.000	EACH
39	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	545.000	EACH

CALL ORDER : 524
 LETTING DATE :

CONTRACT ID : RS-28636-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	4.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	553.000	LFT
11	202-93741 GUARD RAIL END TREATMENT, REMOVE	5.000	EACH
12	203-02080 LINEAR GRADING	0.100	MILE
13	303-07449 COMPACTED AGGREGATE, NO. 73	7,879.000	TON
14	304-07491 HMA PATCHING, TYPE C	150.000	TON
15	306-08034 MILLING, ASPHALT, 1 1/2 IN.	750.000	SYS
16	306-08043 MILLING, TRANSITION	214,900.000	SYS
17	306-08432 MILLING, APPROACH	18,000.000	SYS
18	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
19	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	17,729.000	TON
20	402-07452 HMA, TYPE C, WEDGE AND LEVEL	1,500.000	TON
21	406-05520 ASPHALT FOR TACK COAT	58.000	TON
22	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	1.000	EACH
23	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
24	601-94689 GUARDRAIL END TREATMENT, OS	5.000	EACH
25	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	556.250	LFT
26	610-07488 HMA FOR APPROACHES, TYPE C	1,400.000	TON
27	615-06520 MONUMENT, RE-ESTABLISH	45.000	EACH
28	715-06675 PIPE LINER	150.000	LFT
29	715-46010 PIPE END SECTION, 18 IN.	4.000	EACH
30	715-46020 PIPE END SECTION, 24 IN.	8.000	EACH
31	715-46030 PIPE END SECTION, 30 IN.	6.000	EACH
32	715-46040 PIPE END SECTION, 36 IN.	2.000	EACH
33	725-06858 PIPE LINER, THERMOPLASTIC, 36 IN.	70.000	LFT
34	725-06859 PIPE LINER, THERMOPLASTIC, 48 IN.	260.000	LFT
35	725-06867 PIPE LINER, THERMOPLASTIC, 18 IN.	120.000	LFT
36	725-06870 PIPE LINER, THERMOPLASTIC, 30 IN.	205.000	LFT
37	725-08531 PIPE LINER, THERMOPLASTIC, AREA 16 5 SFT.	162.000	LFT
38	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
39	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,409.000	LFT
40	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8,409.000	LFT
41	801-06640 CONSTRUCTION SIGN, A	66.000	EACH
42	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
43	804-06771 DELINEATOR POST, FLEXIBLE	30.000	EACH
44	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
45	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	136,310.000	LFT
46	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	13,940.000	LFT
47	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	42,650.000	LFT
48	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	138.000	LFT

