

CALL ORDER : 300
 LETTING DATE :

CONTRACT ID : R -28918-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | INTERSECTION IMPROVEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 3 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 4 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 5 | 110-07025 MOBILIZATION AND DEMOBILIZATION | 1.000 | EACH |
| 6 | 202-02240 PAVEMENT REMOVAL | 4,436.000 | SYS |
| 7 | 202-02271 HEADWALL, REMOVE | 7.000 | EACH |
| 8 | 202-02278 CURB, CONCRETE, REMOVE | 700.000 | LFT |
| 9 | 202-02928 CATCH BASIN, REMOVE | 1.000 | EACH |
| 10 | 202-04089 SIGN, SHEET, REMOVE | 4.000 | EACH |
| 11 | 202-96133 PIPE, REMOVE | 259.000 | LFT |
| 12 | 203-02000 EXCAVATION, COMMON | 1,030.000 | CYS |
| 13 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 31.000 | TON |
| 14 | 205-06937 TEMPORARY SILT FENCE | 330.000 | LFT |
| 15 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 5,179.000 | SYS |
| 16 | 211-02060 B BORROW FOR STRUCTURE BACKFILL | 45.000 | CYS |
| 17 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 1,916.000 | TON |
| 18 | 304-07491 HMA PATCHING, TYPE C | 20.000 | TON |
| 19 | 306-08043 MILLING, TRANSITION | 275.000 | SYS |
| 20 | 306-08432 MILLING, APPROACH | 20.000 | SYS |
| 21 | 306-08595 MILLING ASPHALT, 3 1/2 IN. | 1,440.000 | SYS |
| 22 | 401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 520.000 | TON |
| 23 | 401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm | 800.000 | TON |
| 24 | 401-07413 QC/QA-HMA, 3, 70, BASE, 25.0 mm | 1,900.000 | TON |
| 25 | 406-05520 ASPHALT FOR TACK COAT | 6.000 | TON |
| 26 | 610-07488 HMA FOR APPROACHES, TYPE C | 700.000 | TON |
| 27 | 611-08232 MAILBOX ASSEMBLY, SINGLE, RESET | 1.000 | EACH |
| 28 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 1.000 | EACH |
| 29 | 621-06559 MULCHED SEEDING, R | 3,023.000 | SYS |
| 30 | 621-06567 WATER | 182.000 | KGAL |
| 31 | 621-06574 SODDING | 449.000 | SYS |
| 32 | 715-02628 SAFETY METAL END SECTION, 6:1, 15 IN. | 6.000 | EACH |
| 33 | 715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN. | 360.000 | LFT |
| 34 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 3.000 | EACH |
| 35 | 801-06625 DETOUR ROUTE MARKER ASSEMBLY | 10.000 | EACH |
| 36 | 801-06640 CONSTRUCTION SIGN, A | 2.000 | EACH |
| 37 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 38 | 801-07119 BARRICADE, III-B | 72.000 | LFT |
| 39 | 802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN. | 19.000 | SFT |
| 40 | 802-76055 SIGN POST, A | 30.000 | LFT |
| 41 | 802-91122 SIGN, GROUND MOUNTED, RESET | 8.000 | EACH |
| 42 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 2,400.000 | LFT |
| 43 | 808-75286 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID YELLOW, CROSSHATCH | 475.000 | LFT |
| 44 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 60.000 | LFT |
| 45 | 808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 4.000 | EACH |
| 46 | 808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 2.000 | EACH |
| 47 | 808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN. | 1,900.000 | LFT |
| 48 | 808-96016 LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN. | 2,400.000 | LFT |