

CALL ORDER : 172
 LETTING DATE :

CONTRACT ID : R -27848-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, SHELTER HOUSE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	203-02070 BORROW	30.000	CYS
5	205-06937 TEMPORARY SILT FENCE	760.000	LFT
6	210-05066 FOUNTAIN	1.000	EACH
7	604-90256 SIDEWALK, CONCRETE, 6 IN.	226.000	SYS
8	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
9	621-06560 MULCHED SEEDING, U	642.000	SYS
10	621-08161 PERMANENT TURF REINFORCEMENT MAT	410.000	SYS
11	711-03973 BUILDING ARCHITECTURAL	LUMP	LUMP
12	715-01902 WATER SERVICE LINE, 2 IN.	60.000	LFT
13	715-05711 PIPE, SANITARY SEWER, 6 IN.	500.000	LFT
14	719-03975 BUILDING PLUMBING	LUMP	LUMP
15	805-02971 ELECTRICAL SERVICE	LUMP	LUMP
16	807-03694 BUILDING ELECTRICAL	LUMP	LUMP
17	807-03974 BUILDING HEATING, VENTILATION, AIR CONDITIONING	LUMP	LUMP

CALL ORDER : 291

CONTRACT ID : R -28840-B

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	COMPOSITE AND CONCRETE PAVEMENT PATCHING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	910.000	TON
11	304-07783 HMA PATCHING, TYPE D	500.000	TON
12	306-08034 MILLING, ASPHALT, 1 1/2 IN.	1,600.000	SYS
13	402-07432 HMA SURFACE, TYPE A	132.000	TON
14	406-05521 ASPHALT FOR TACK COAT	1,600.000	SYS
15	503-05240 D-1 CONTRACTION JOINT	648.000	LFT
16	506-06333 PCCP PATCHING, FULL DEPTH	1,820.000	SYS
17	606-07484 MILLED HMA SHOULDER CORRUGATIONS	3,600.000	LFT
18	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
19	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
20	801-06640 CONSTRUCTION SIGN, A	54.000	EACH
21	801-06710 FLASHING ARROW SIGN	120.000	DAY
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
24	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	320.000	LFT
25	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	257.000	LFT
26	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,027.000	LFT
27	808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN.	80.000	LFT
28	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	25.000	EACH
29	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	25.000	EACH

CALL ORDER : 336
 LETTING DATE :

CONTRACT ID : RS-28632-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-01180 COMPACTED AGGREGATE, NO. 53	1,000.000	TON
8	304-07490 HMA PATCHING, TYPE B	524.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	18,000.000	SYS
10	306-08042 MILLING, SCARIFICATION/PROFILE	109,836.000	SYS
11	306-08043 MILLING, TRANSITION	2,200.000	SYS
12	306-08432 MILLING, APPROACH	17,553.000	SYS
13	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
14	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	10,728.000	TON
15	402-07451 HMA, TYPE B, WEDGE AND LEVEL	300.000	TON
16	406-05520 ASPHALT FOR TACK COAT	40.600	TON
17	604-07896 CURB RAMP, CONCRETE, B	181.000	SYS
18	604-07897 CURB RAMP, CONCRETE, C	3.000	SYS
19	604-07899 CURB RAMP, CONCRETE, E	75.000	SYS
20	604-07901 CURB RAMP, CONCRETE, G	26.000	SYS
21	604-07902 CURB RAMP, CONCRETE, H	10.000	SYS
22	610-07487 HMA FOR APPROACHES, TYPE B	1,449.000	TON
23	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
24	720-44000 CASTING, ADJUST TO GRADE	24.000	EACH
25	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,678.000	LFT
26	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,678.000	LFT
27	801-06640 CONSTRUCTION SIGN, A	59.000	EACH
28	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
29	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	6.000	EACH
30	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	48.000	LFT
31	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	7,594.000	LFT
32	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	95,000.000	LFT
33	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	50,732.000	LFT
34	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	196.000	LFT
35	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	7.000	EACH
36	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
37	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
38	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	758.000	EACH

CALL ORDER : 500
 LETTING DATE :

CONTRACT ID : M -28662-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	3.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02446 BRIDGE RAILING, CONCRETE, REMOVE	32.000	LFT
8	202-52710 SIDEWALK, CONCRETE, REMOVE	200.000	SYS
9	306-08041 MILLING, PCCP	1,945.000	SYS
10	306-08043 MILLING, TRANSITION	2,000.000	SYS
11	306-08432 MILLING, APPROACH	849.000	SYS
12	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	326.000	TON
13	401-07385 QC/QA-HMA, 3, 76, INTERMEDIATE, 12.5 mm	326.000	TON
14	402-07452 HMA, TYPE C, WEDGE AND LEVEL	100.000	TON
15	406-05520 ASPHALT FOR TACK COAT	2.000	TON
16	507-07479 HMA PARTIAL DEPTH PATCH	100.000	TON
17	604-06070 SIDEWALK, CONCRETE	200.000	SYS
18	604-07902 CURB RAMP, CONCRETE, H	31.000	SYS
19	610-07488 HMA FOR APPROACHES, TYPE C	140.000	TON
20	702-51863 FIELD DRILLED HOLE IN CONCRETE	30.000	EACH
21	703-06029 REINFORCING BARS, EPOXY COATED	274.000	LBS
22	706-06349 RAILING, TX	32.000	LFT
23	720-44000 CASTING, ADJUST TO GRADE	7.000	EACH
24	728-98377 MASONRY COATING	LUMP	LUMP
25	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	85.000	LFT
26	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8.000	LFT
27	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
28	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
29	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,250.000	LFT
30	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	225.000	LFT
31	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	720.000	LFT
32	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	5.000	EACH
33	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	150.000	LFT
34	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	1,854.000	LFT
35	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	60.000	LFT
36	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	1.000	EACH

CALL ORDER : 504
 LETTING DATE :

CONTRACT ID : M -28684-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-07039 FIELD OFFICE, B	4.000	MOS
2	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	100.000	TON
7	304-07490 HMA PATCHING, TYPE B	294.000	TON
8	306-08034 MILLING, ASPHALT, 1 1/2 IN.	25,724.000	SYS
9	306-08432 MILLING, APPROACH	2,397.000	SYS
10	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2,122.000	TON
11	406-05520 ASPHALT FOR TACK COAT	8.000	TON
12	604-06070 SIDEWALK, CONCRETE	567.000	SYS
13	604-07894 CURB RAMP, CONCRETE, A	252.000	SYS
14	604-07896 CURB RAMP, CONCRETE, B	187.000	SYS
15	604-07901 CURB RAMP, CONCRETE, G	18.000	SYS
16	604-07902 CURB RAMP, CONCRETE, H	8.000	SYS
17	605-06120 CURB, CONCRETE	1,875.000	LFT
18	610-07487 HMA FOR APPROACHES, TYPE B	265.000	TON
19	621-06575 SODDING, NURSERY	13.000	SYS
20	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
21	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	11.000	LFT
22	720-45610 STRUCTURE, CATCH BASIN, RECONSTRUCT	2.000	LFT
23	720-45615 STRUCTURE, INLET, RECONSTRUCT	2.000	LFT
24	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	5,664.000	LFT
25	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,664.000	LFT
26	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
29	808-02157 PAVEMENT MESSAGE MARKINGS, REMOVE	1.000	EACH
30	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	1.000	EACH
31	808-06368 TRANSVERSE MARKING, REMOVE	35.000	LFT
32	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,315.000	LFT
33	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	200.000	LFT
34	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	35.000	LFT
35	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	525.000	LFT
36	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7,077.000	LFT
37	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	146.000	LFT
38	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	108.000	LFT
39	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	575.000	LFT
40	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,945.000	LFT
41	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	27.000	EACH
42	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	23.000	EACH
43	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
44	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	541.000	LFT

CALL ORDER : 508
 LETTING DATE :

CONTRACT ID : M -28745-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HMA OVERLAY, PREVENTITIVE MAINTENANCE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	3.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	303-07449 COMPACTED AGGREGATE, NO. 73	4.000	TON
5	304-07490 HMA PATCHING, TYPE B	40.000	TON
6	306-08034 MILLING, ASPHALT, 1 1/2 IN.	10,099.000	SYS
7	306-08432 MILLING, APPROACH	661.000	SYS
8	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
9	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	834.000	TON
10	406-05520 ASPHALT FOR TACK COAT	3.000	TON
11	610-07487 HMA FOR APPROACHES, TYPE B	74.000	TON
12	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	2.000	EACH
13	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	285.000	LFT
14	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	412.000	LFT
17	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	4,392.000	LFT
18	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	2,438.000	LFT
19	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	72.000	LFT
20	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	192.000	LFT
21	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	51.000	EACH
22	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	51.000	EACH

