

CALL ORDER : 430
 LETTING DATE :

CONTRACT ID : B -28176-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
9	202-74035 SIGN, REMOVE	5.000	EACH
10	203-02000 EXCAVATION, COMMON	12,744.400	CYS
11	203-08279 EXPANDED POLYSTYRENE FILL	3,552.000	CYS
12	203-51223 EXCAVATION, WATERWAY	88.000	CYS
13	205-03371 SEDIMENT, REMOVE	25.000	CYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	84.800	TON
15	205-06937 TEMPORARY SILT FENCE	900.000	LFT
16	211-07454 STRUCTURE BACKFILL	517.300	CYS
17	213-08058 FLOWABLE BACKFILL	146.700	CYS
18	216-08528 HDPE GEO-MEMBRANE	1,128.400	SYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,986.100	TON
20	303-97820 AGGREGATE, 8	6,124.900	TON
21	306-08043 MILLING, TRANSITION	320.000	SYS
22	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	2,063.900	TON
23	402-07432 HMA SURFACE, TYPE A	136.600	TON
24	402-07434 HMA SURFACE, TYPE C	309.600	TON
25	402-07439 HMA INTERMEDIATE, TYPE C	448.400	TON
26	402-07440 HMA BASE, TYPE A	409.800	TON
27	406-05520 ASPHALT FOR TACK COAT	3.900	TON
28	502-06627 PCCP, 6 IN.	4,963.300	SYS
29	601-01839 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 6	1.000	EACH
30	601-02800 GUARDRAIL TRANSITION, TGT	4.000	EACH
31	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
32	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	525.000	LFT
33	615-06490 RIGHT OF WAY MARKER	8.000	EACH
34	615-06505 MONUMENT, B	2.000	EACH
35	616-02320 GEOTEXTILES	2,666.000	SYS
36	616-05688 RIPRAP, CLASS 1	998.000	TON
37	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
38	621-01597 EROSION CONTROL, MAT	14.000	SYS
39	621-06545 FERTILIZER	0.900	TON
40	621-06553 SEED MIXTURE, R	357.000	LBS
41	621-06565 MULCHING MATERIAL	4.200	TON
42	621-06567 WATER	2.200	KGAL
43	621-06574 SODDING	557.600	SYS
44	701-98647 PILE, CONCRETE, STEEL SHELL ENCASED, 0.203 IN., 14 IN.	720.000	LFT
45	706-06347 RAILING, CF-1	40.000	LFT
46	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	2,320.000	LFT
47	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	100.000	LFT
48	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	100.000	LFT

CALL ORDER : 430
 LETTING DATE :

CONTRACT ID : B -28176-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	212.000	LFT
50	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	40.000	LFT
51	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN.	110.000	LFT
52	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN.	74.000	LFT
53	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
54	715-46010 PIPE END SECTION, 18 IN.	4.000	EACH
55	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
56	718-06531 OUTLET PROTECTOR, 3	8.000	EACH
57	723-07105 STRUCTURE, PRECAST THREE-SIDED, 240 IN. X 120 IN.	45.000	LFT
58	723-08608 WINGWALL	598.500	SFT
59	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
60	801-06625 DETOUR ROUTE MARKER ASSEMBLY	37.000	EACH
61	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
62	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
63	801-07118 BARRICADE, III-A	96.000	LFT
64	801-07119 BARRICADE, III-B	96.000	LFT
65	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	10.500	LFT
66	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	6.000	SFT
67	804-06725 DELINEATOR WITH POST, D1, 3 IN. DIA.	4.000	EACH
68	808-01226 SNOWPLOWABLE RAISED PAVEMENT MARKER CASTING, INSTALL	26.000	EACH
69	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,000.000	LFT
70	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	375.000	LFT
71	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	250.000	LFT
72	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	18.000	EACH

CALL ORDER : 450
 LETTING DATE :

CONTRACT ID : B -28490-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	202-02279 CURB AND GUTTER, REMOVE	35.000	LFT
8	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	640.000	CYS
10	205-06932 TEMPORARY CHECK DAM, STRAW BALES	40.000	LFT
11	205-06937 TEMPORARY SILT FENCE	500.000	LFT
12	207-08266 SUBGRADE TREATMENT, TYPE III	445.000	SYS
13	211-07454 STRUCTURE BACKFILL	453.000	CYS
14	213-08058 FLOWABLE BACKFILL	54.000	CYS
15	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	295.000	TON
16	303-07449 COMPACTED AGGREGATE, NO. 73	14.000	TON
17	306-08043 MILLING, TRANSITION	541.000	SYS
18	402-07432 HMA SURFACE, TYPE A	95.000	TON
19	402-07435 HMA INTERMEDIATE, TYPE A	80.000	TON
20	402-07450 HMA, TYPE A, WEDGE AND LEVEL	41.000	TON
21	406-05521 ASPHALT FOR TACK COAT	1,239.000	SYS
22	601-95871 HANDRAIL	119.300	LFT
23	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	370.000	LFT
24	605-94811 CURB TURNOUT	1.000	EACH
25	607-06175 GUTTER, CONCRETE	100.000	LFT
26	610-07486 HMA FOR APPROACHES, TYPE A	24.500	TON
27	615-06505 MONUMENT, B	1.000	EACH
28	616-02320 GEOTEXTILES	408.000	SYS
29	616-05688 RIPRAP, CLASS 1	255.000	TON
30	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
31	621-06567 WATER	3.000	KGAL
32	621-06575 SODDING, NURSERY	675.000	SYS
33	701-51210 PILE ENCASEMENT, CONCRETE	70.000	LFT
34	714-08514 WINGWALL	346.500	SFT
35	715-02907 WATER LINE, 6 IN.	170.000	LFT
36	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	31.000	LFT
37	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	106.000	LFT
38	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	83.000	LFT
39	715-07073 WATER LINE	140.000	LFT
40	715-46005 PIPE END SECTION, 15 IN.	1.000	EACH
41	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
42	715-94064 WATER LINE, COPPER, 0.75 IN.	30.000	LFT
43	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
44	720-45075 INLET, R13	1.000	EACH
45	720-45410 MANHOLE, C4	1.000	EACH
46	720-96851 INLET, J13	1.000	EACH
47	723-07582 STRUCTURE, PRECAST THREE-SIDED, 336 IN. X 72 IN.	80.000	LFT
48	732-03063 TAPPING SLEEVE	2.000	EACH

CALL ORDER : 450
 LETTING DATE :

CONTRACT ID : B -28490-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	732-04836 GATE VALVE	2.000	EACH
50	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
51	801-06625 DETOUR ROUTE MARKER ASSEMBLY	13.000	EACH
52	801-06640 CONSTRUCTION SIGN, A	3.000	EACH
53	801-07118 BARRICADE, III-A	72.000	LFT
54	801-07119 BARRICADE, III-B	36.000	LFT

CALL ORDER : 460
 LETTING DATE :

CONTRACT ID : B -28688-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	12.000	MOS
3	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
9	203-02000 EXCAVATION, COMMON	838.000	CYS
10	203-02070 BORROW	2,654.000	CYS
11	203-51223 EXCAVATION, WATERWAY	720.000	CYS
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	19.600	TON
13	205-06936 TEMPORARY SEDIMENT TRAP	30.800	TON
14	205-06937 TEMPORARY SILT FENCE	585.000	LFT
15	207-08264 SUBGRADE TREATMENT, TYPE II	3,431.800	SYS
16	211-06467 AGGREGATE FOR END BENT BACKFILL	16.400	CYS
17	211-07454 STRUCTURE BACKFILL	1.400	CYS
18	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,139.400	TON
19	302-07455 DENSE GRADED SUBBASE	19.700	CYS
20	306-08043 MILLING, TRANSITION	424.300	SYS
21	402-07432 HMA SURFACE, TYPE A	235.600	TON
22	402-07435 HMA INTERMEDIATE, TYPE A	342.000	TON
23	404-05514 SEAL COAT, 5	450.000	SYS
24	406-05521 ASPHALT FOR TACK COAT	3,048.700	SYS
25	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
26	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
27	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	312.500	LFT
28	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	118.400	SYS
29	610-07486 HMA FOR APPROACHES, TYPE A	39.600	TON
30	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
31	616-02320 GEOTEXTILES	1,541.200	SYS
32	616-06405 RIPRAP, REVETMENT	985.600	TON
33	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
34	621-01371 SEED MIXTURE, LEGUME, 2	121.900	LBS
35	621-02770 EROSION CONTROL BLANKET	2,025.000	SYS
36	621-06545 FERTILIZER	1.000	TON
37	621-06553 SEED MIXTURE, R	217.900	LBS
38	621-06557 SEED MIXTURE, T	199.500	LBS
39	621-06565 MULCHING MATERIAL	7.700	TON
40	621-06567 WATER	1.700	KGAL
41	621-06575 SODDING, NURSERY	431.700	SYS
42	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
43	622-91786 SEEDLING	127.000	EACH
44	701-51195 PILE, STEEL H, HP 12 X 53	536.000	LFT
45	701-91792 PILE TIP, STEEL H	8.000	EACH
46	703-51032 REINFORCING STEEL, EPOXY COATED	15,870.000	LBS
47	704-51002 CONCRETE, C, SUPERSTRUCTURE	77.500	CYS
48	706-06344 RAILING, TS-1	125.000	LFT

CALL ORDER : 460
 LETTING DATE :

CONTRACT ID : B -28688-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	707-05979	1,096.000	SFT
50	709-51821	LUMP	LUMP
51	715-05169	34.000	LFT
52	715-05407	84.000	LFT
53	715-46005	2.000	EACH
54	801-04308	4.000	EACH
55	801-06625	13.000	EACH
56	801-06640	18.000	EACH
57	801-06775	LUMP	LUMP
58	801-07118	72.000	LFT
59	801-07119	48.000	LFT
60	802-76025	8.500	SFT
61	802-76065	15.100	LFT

CALL ORDER : 470

CONTRACT ID : B -28775-A

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE STRUCTURE REMOVAL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
3	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
4	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
5	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
6	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
7	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
8	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
9	105-06899 RADIO	1.000	EACH
10	105-07039 FIELD OFFICE, B	18.000	MOS
11	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
12	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
13	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
14	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
15	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
16	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
17	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
18	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
19	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
20	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
21	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
22	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
23	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
24	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
25	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
26	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
27	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
28	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
29	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
30	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
31	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
32	202-02240 PAVEMENT REMOVAL	2,692.400	SYS
33	202-02241 GUARDRAIL, REMOVE	7,622.000	LFT
34	202-02277 GUTTER, LIP, REMOVE	911.000	LFT
35	202-02278 CURB, CONCRETE, REMOVE	1,557.000	LFT
36	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
37	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
38	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
39	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
40	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
41	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
42	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
43	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
44	202-74080 OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	2.000	EACH
45	202-90413 SLOPEWALL, CONCRETE, 4 IN., REMOVE	239.000	SYS
46	202-95027 IMPACT ATTENUATOR, REMOVE	2.000	EACH

CALL ORDER : 470

CONTRACT ID : B -28775-A

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE STRUCTURE REMOVAL		
47	203-02000 EXCAVATION, COMMON	2,201.000	CYS
48	203-02070 BORROW	38,927.000	CYS
49	203-90014 LINEAR GRADING	12.840	STA
50	204-02290 SETTLEMENT PLATE	4.000	EACH
51	204-08415 STAKES, SETTLEMENT	4.000	EACH
52	205-03371 SEDIMENT, REMOVE	275.000	CYS
53	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	736.000	TON
54	205-06932 TEMPORARY CHECK DAM, STRAW BALES	276.000	LFT
55	205-06933 TEMPORARY DITCH INLET PROTECTION	7.000	EACH
56	205-06936 TEMPORARY SEDIMENT TRAP	187.000	TON
57	205-08517 ROCK FILTER BERM	125.000	TON
58	206-51220 EXCAVATION, WET	94.800	CYS
59	206-51225 EXCAVATION, DRY	744.000	CYS
60	207-08262 SUBGRADE TREATMENT, TYPE I	9,670.000	SYS
61	211-02050 B BORROW	219.200	CYS
62	211-06467 AGGREGATE FOR END BENT BACKFILL	254.000	CYS
63	211-07454 STRUCTURE BACKFILL	2,585.000	CYS
64	214-07202 GEOGRID, I	440.000	SYS
65	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,301.000	TON
66	302-07455 DENSE GRADED SUBBASE	189.200	CYS
67	303-01180 COMPACTED AGGREGATE, NO. 53	587.000	TON
68	303-07449 COMPACTED AGGREGATE, NO. 73	197.000	TON
69	306-08043 MILLING, TRANSITION	2,377.000	SYS
70	402-07432 HMA SURFACE, TYPE A	300.000	TON
71	402-07434 HMA SURFACE, TYPE C	999.000	TON
72	402-07439 HMA INTERMEDIATE, TYPE C	963.000	TON
73	402-07440 HMA BASE, TYPE A	825.000	TON
74	402-07442 HMA BASE, TYPE C	1,539.000	TON
75	406-05520 ASPHALT FOR TACK COAT	7.700	TON
76	502-06329 PCCP, 12 IN.	426.400	SYS
77	503-03489 RETROFITTED TIE BARS	192.000	EACH
78	503-05310 TERMINAL JOINT	192.000	LFT
79	601-01522 GUARDRAIL TRANSITION TYPE TGB	12.000	EACH
80	601-01522 GUARDRAIL TRANSITION TYPE TGB	2.000	EACH
81	601-01626 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 2	1.000	EACH
82	601-05999 CURVED TERMINAL END	8.000	EACH
83	601-06035 GUARDRAIL, RESET	25.000	LFT
84	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	2.000	EACH
85	601-94689 GUARDRAIL END TREATMENT, OS	5.000	EACH
86	601-94689 GUARDRAIL END TREATMENT, OS	6.000	EACH
87	601-94690 GUARDRAIL END TREATMENT, MS	4.000	EACH
88	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	6,793.750	LFT
89	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	750.000	LFT
90	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	550.000	LFT
91	601-99123 GUARDRAIL TRANSITION, GP	2.000	EACH
92	602-06729 BARRIER DELINEATOR	60.000	EACH

CALL ORDER : 470

CONTRACT ID : B -28775-A

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE STRUCTURE REMOVAL			
93	603-06040 FENCE, FARM FIELD, 47 IN.	418.000	LFT
94	605-05523 CURB, HMA	1,326.000	LFT
95	605-06210 CENTER CURB, C, CONCRETE	409.000	LFT
96	606-07484 MILLED HMA SHOULDER CORRUGATIONS	5,297.000	LFT
97	610-06259 REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	777.600	SYS
98	610-07486 HMA FOR APPROACHES, TYPE A	1,070.000	TON
99	615-06490 RIGHT OF WAY MARKER	10.000	EACH
100	615-06510 MONUMENT, C	5.000	EACH
101	616-02320 GEOTEXTILES	2,070.000	SYS
102	616-05689 RIPRAP, CLASS 2	1,310.000	TON
103	616-06405 RIPRAP, REVETMENT	108.000	TON
104	616-51367 SLOPEWALL, CONCRETE, 4 IN.	723.000	SYS
105	616-93766 BREAKING CONCRETE SLOPEWALL	740.000	SYS
106	616-95754 PAVED SIDE DITCH, BREAK	400.000	LFT
107	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	12.000	EACH
108	621-02770 EROSION CONTROL BLANKET	9,273.000	SYS
109	621-06545 FERTILIZER	2.700	TON
110	621-06553 SEED MIXTURE, R	957.000	LBS
111	621-06557 SEED MIXTURE, T	187.000	LBS
112	621-06565 MULCHING MATERIAL	16.000	TON
113	701-01849 PILE, CONCRETE, STEEL SHELL ENCASED, 0.312 IN., 14 IN.	504.000	LFT
114	701-98647 PILE, CONCRETE, STEEL SHELL ENCASED, 0.203 IN., 14 IN.	408.000	LFT
115	702-51005 CONCRETE, A, SUBSTRUCTURE	544.800	CYS
116	702-51015 CONCRETE, B, FOOTINGS	103.800	CYS
117	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	3,864.000	LBS
118	702-51863 FIELD DRILLED HOLE IN CONCRETE	876.000	EACH
119	703-51030 REINFORCING STEEL	60,385.000	LBS
120	703-51032 REINFORCING STEEL, EPOXY COATED	401,394.000	LBS
121	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,187.600	CYS
122	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	16.000	EACH
123	706-51020 CONCRETE, C, RAILING	162.800	CYS
124	707-07605 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 54 IN. X 48 IN.	1,733.400	LFT
125	709-51821 SURFACE SEAL	LUMP	LUMP
126	709-51821 SURFACE SEAL	LUMP	LUMP
127	709-51821 SURFACE SEAL	LUMP	LUMP
128	709-51821 SURFACE SEAL	LUMP	LUMP
129	711-51038 STRUCTURAL STEEL	LUMP	LUMP
130	711-51038 STRUCTURAL STEEL	LUMP	LUMP
131	711-51864 DRILLED HOLE	282.000	EACH
132	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
133	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
134	711-91149 STRAIGHTEN STEEL BEAM	LUMP	LUMP
135	711-96479 BOLT, REMOVE	440.000	EACH
136	711-96800 STUD SHEAR CONNECTORS	3,600.000	EACH
137	714-08514 WINGWALL	923.000	SFT
138	714-08514 WINGWALL	923.000	SFT

CALL ORDER : 470

CONTRACT ID : B -28775-A

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE STRUCTURE REMOVAL		
139	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	122.000	LFT
140	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	740.000	LFT
141	715-05407 PIPE, END BENT DRAIN, 6 IN.	488.000	LFT
142	715-05756 PIPE EXTENSION, CIRCULAR, 12 IN.	102.000	LFT
143	715-46005 PIPE END SECTION, 15 IN.	1.000	EACH
144	715-91361 PIPE, PVC, 6 IN.	54.000	LFT
145	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
146	720-44296 CAP INLET	4.000	EACH
147	720-45045 INLET, J10	9.000	EACH
148	720-45055 INLET, M10	3.000	EACH
149	720-45070 INLET, P12A	1.000	EACH
150	723-08518 STRUCTURE, PRECAST THREE-SIDED, 144 IN. X 162 IN.	182.000	LFT
151	723-08518 STRUCTURE, PRECAST THREE-SIDED, 144 IN. X 162 IN.	182.000	LFT
152	726-92406 BEARING ASSEMBLY, ELASTOMERIC	28.000	EACH
153	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	13.000	EACH
154	801-04308 ROAD CLOSURE SIGN ASSEMBLY	30.000	EACH
155	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	74,784.000	LFT
156	801-06640 CONSTRUCTION SIGN, A	82.000	EACH
157	801-06645 CONSTRUCTION SIGN, B	47.000	EACH
158	801-06710 FLASHING ARROW SIGN	180.000	DAY
159	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
160	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
161	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
162	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
163	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
164	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
165	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
166	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
167	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH
168	801-07118 BARRICADE, III-A	660.000	LFT
169	801-07119 BARRICADE, III-B	648.000	LFT
170	801-08389 TEMPORARY TRAFFIC BARRIER, ANCHORED	2,250.000	LFT
171	801-08389 TEMPORARY TRAFFIC BARRIER, ANCHORED	540.000	LFT
172	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
173	801-97643 TEMPORARY BUZZ STRIPS	2,588.000	LFT
174	802-07057 SIGN, PANEL, WITH LEGEND	240.000	SFT
175	802-07102 SIGN LIGHTING SYSTEM, TRACK, CANTILEVER	2.000	EACH
176	802-07159 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, II	2.000	EACH
177	802-76140 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM	2.000	EACH
178	802-76175 WALKWAY, HANDRAIL, AND LIGHTING SUPPORT ASSEMBLY	24.000	LFT
179	804-06770 DELINEATOR POST	4.000	EACH
180	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	250.000	LFT
181	805-98336 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	250.000	LFT
182	807-02191 HANDHOLE, LIGHTING	2.000	EACH
183	807-06935 INSULATING LINK, WATERPROOFED	9.000	EACH
184	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	89.000	LFT

CALL ORDER : 470

CONTRACT ID : B -28775-A

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE STRUCTURE REMOVAL		
185	807-82016 SIGN CIRCUIT INSTALLATION, CANTILEVER, 2 LUMINAIRES	2.000	EACH
186	807-86790 LUMINAIRE, SIGN, MERCURY VAPOR, WITH GLARE SHIELD, 250 WATT	4.000	EACH
187	807-86910 CONNECTOR KIT, UNFUSED	2.000	EACH
188	807-86915 CONNECTOR KIT, FUSED	4.000	EACH
189	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	3.000	EACH
190	807-86930 INSULATION LINK, NONWATERPROOFED	3.000	EACH
191	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	4.000	EACH
192	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	629.000	LFT
193	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	28,024.000	LFT
194	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	31,039.000	LFT
195	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	19,955.000	LFT
196	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	9,829.000	LFT
197	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	7,448.000	LFT
198	808-06716 LINE, REMOVE	4,471.000	LFT
199	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	217.000	LFT
200	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	42.000	EACH
201	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	62.000	EACH

CALL ORDER : 480
 LETTING DATE :

CONTRACT ID : B -28807-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	202-02240 PAVEMENT REMOVAL	2.700	SYS
5	202-02241 GUARDRAIL, REMOVE	1,070.000	LFT
6	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
7	213-08058 FLOWABLE BACKFILL	1.000	CYS
8	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
9	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
10	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	1.000	EACH
11	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,000.000	LFT
12	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	2.000	EACH
13	602-06729 BARRIER DELINEATOR	14.000	EACH
14	621-06559 MULCHED SEEDING, R	500.000	SYS
15	702-51863 FIELD DRILLED HOLE IN CONCRETE	732.000	EACH
16	703-51032 REINFORCING STEEL, EPOXY COATED	36,914.000	LBS
17	704-51002 CONCRETE, C, SUPERSTRUCTURE	125.800	CYS
18	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
19	706-51025 CONCRETE, C, RAILING	440.000	LFT
20	709-51821 SURFACE SEAL	LUMP	LUMP
21	724-03276 EXPANSION JOINT SEALING SYSTEM	70.000	LFT
22	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
23	801-06625 DETOUR ROUTE MARKER ASSEMBLY	25.000	EACH
24	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	801-07118 BARRICADE, III-A	72.000	LFT
27	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	284.000	LFT
28	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	284.000	LFT
29	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2.000	EACH

CALL ORDER : 490
 LETTING DATE :

CONTRACT ID : B -28849-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
1	105-07039 FIELD OFFICE, B	10.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	30.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
12	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
13	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
14	203-02000 EXCAVATION, COMMON	526.000	CYS
15	207-08262 SUBGRADE TREATMENT, TYPE I	1,323.000	SYS
16	210-06994 CONCRETE	LUMP	LUMP
17	211-06467 AGGREGATE FOR END BENT BACKFILL	54.000	CYS
18	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	80.000	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN.	2,308.000	SYS
20	402-07434 HMA SURFACE, TYPE C	322.000	TON
21	402-07439 HMA INTERMEDIATE, TYPE C	296.000	TON
22	402-07442 HMA BASE, TYPE C	763.000	TON
23	406-05521 ASPHALT FOR TACK COAT	7,032.000	SYS
24	502-06329 PCCP, 12 IN.	107.000	SYS
25	503-05310 TERMINAL JOINT	96.000	LFT
26	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
27	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	25.000	LFT
28	601-99133 GUARDRAIL TRANSITION VH, 12 FT. 6 IN. SPACING	2.000	EACH
29	606-07484 MILLED HMA SHOULDER CORRUGATIONS	2,565.000	LFT
30	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	328.000	SYS
31	702-51863 FIELD DRILLED HOLE IN CONCRETE	108.000	EACH
32	703-03622 THREADED TIE BAR ASSEMBLY, EPOXY COATED, MODIFIED	84.000	EACH
33	703-51030 REINFORCING STEEL	7,793.000	LBS
34	703-51032 REINFORCING STEEL, EPOXY COATED	26,013.000	LBS
35	704-51002 CONCRETE, C, SUPERSTRUCTURE	111.000	CYS
36	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
37	706-51025 CONCRETE, C, RAILING	24.000	LFT
38	709-51821 SURFACE SEAL	LUMP	LUMP
39	709-51821 SURFACE SEAL	LUMP	LUMP
40	711-51038 STRUCTURAL STEEL	LUMP	LUMP
41	711-95290 FIELD WELDING	45.000	LFT
42	711-96800 STUD SHEAR CONNECTORS	154.000	EACH
43	713-51820 TEMPORARY SUPPORT	LUMP	LUMP
44	713-51820 TEMPORARY SUPPORT	LUMP	LUMP
45	715-05407 PIPE, END BENT DRAIN, 6 IN.	150.000	LFT
46	724-03276 EXPANSION JOINT SEALING SYSTEM	120.000	LFT
47	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	28,797.000	LFT
48	801-06640 CONSTRUCTION SIGN, A	46.000	EACH

CALL ORDER : 490
 LETTING DATE :

CONTRACT ID : B -28849-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
49	801-06710 FLASHING ARROW SIGN	149.000	DAY
50	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
51	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
52	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
53	801-08388 TEMPORARY TRAFFIC BARRIER	346.000	LFT
54	801-08388 TEMPORARY TRAFFIC BARRIER	200.000	LFT
55	801-08389 TEMPORARY TRAFFIC BARRIER, ANCHORED	1,554.000	LFT
56	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	1,040.000	LFT
57	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
58	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	1,887.000	LFT
59	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	3,746.000	LFT
60	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,651.000	LFT
61	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	1,394.000	LFT
62	808-06716 LINE, REMOVE	7,336.000	LFT
63	808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN.	1,522.000	LFT
64	808-75001 LINE, PAINT, BROKEN, WHITE, 5 IN.	367.000	LFT