

CALL ORDER : 630  
 LETTING DATE :

CONTRACT ID : T -28425-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNAL PROJECT		
1	105-07038 FIELD OFFICE, A	6.000	MOS
2	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	202-02236 SURFACE, REMOVE	500.000	SYS
7	202-02241 GUARDRAIL, REMOVE	70.000	LFT
8	202-02278 CURB, CONCRETE, REMOVE	370.000	LFT
9	202-93615 CONCRETE, REMOVE	45.000	SYS
10	202-94810 CURB TURNOUT, REMOVE	1.000	EACH
11	211-02050 B BORROW	150.000	CYS
12	306-08038 MILLING, ASPHALT, 4 IN.	1,800.000	SYS
13	402-07433 HMA SURFACE, TYPE B	150.000	TON
14	402-07438 HMA INTERMEDIATE, TYPE B	250.000	TON
15	406-05520 ASPHALT FOR TACK COAT	1.000	TON
16	605-02042 CURB AND GUTTER TURNOUT, CONCRETE	1.000	EACH
17	605-06150 CURB AND GUTTER, C, CONCRETE	500.000	LFT
18	605-06160 CURB AND GUTTER, B, CONCRETE, MODIFIED	30.000	LFT
19	607-06385 PAVED SIDE DITCH, L	30.000	LFT
20	621-06574 SODDING	500.000	SYS
21	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
24	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	39.000	LFT
25	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	7.500	SFT
26	802-76030 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.100 IN. THICKNESS	72.000	SFT
27	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
28	805-01842 HANDHOLE, SIGNAL	7.000	EACH
29	805-01879 SIGNAL SERVICE, INSTALL	1.000	EACH
30	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,100.000	LFT
31	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	1.000	EACH
32	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
33	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	2.000	EACH
34	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
35	805-78420 DISCONNECT HANGER	5.000	EACH
36	805-78467 SIGNAL CABLE, 3C 8GA.	50.000	LFT
37	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,800.000	LFT
38	805-78485 SIGNAL CABLE, 5C 14GA.	200.000	LFT
39	805-78490 SIGNAL CABLE, 7C 14GA.	1,000.000	LFT
40	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,700.000	LFT
41	805-78785 SIGNAL DETECTOR HOUSING	5.000	EACH
42	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	600.000	LFT
43	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
44	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
45	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	4.000	EACH
46	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	1.000	EACH
47	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	450.000	LFT
48	808-06716 LINE, REMOVE	85.000	LFT

CALL ORDER : 630  
LETTING DATE :

CONTRACT ID : T -28425-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNAL PROJECT		
49 808-06716	LINE, REMOVE	2,410.000	LFT
50 808-06723	PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	2.000	EACH
51 808-75205	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	200.000	LFT
52 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,760.000	LFT
53 808-75290	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	90.000	LFT
54 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	200.000	LFT

CALL ORDER : 650  
 LETTING DATE :

CONTRACT ID : T -28740-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	RAISED PAVEMENT MARKINGS, NEW		
1 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
2 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
3 808-75994	PRISMATIC REFLECTOR	26,869.000	EACH
4 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2,985.000	EACH
5 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2,985.000	EACH

