

CALL ORDER : 135  
 LETTING DATE :

CONTRACT ID : R -26926-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PAVEMENT REPLACEMENT AND INTERSECTION IMPROVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	32.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	5.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	160.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	290.400	m2
13	202-02278 CURB, CONCRETE, REMOVE	22.500	m
14	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
15	202-52710 SIDEWALK, CONCRETE, REMOVE	2,654.300	m2
16	202-94627 HYDRANT, REMOVE	9.000	EACH
17	203-02000 EXCAVATION, COMMON	16,557.000	m3
18	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	364.400	Mg
19	205-06933 TEMPORARY DITCH INLET PROTECTION	5.000	EACH
20	207-08103 SOIL MODIFICATION	37.000	m3
21	207-08263 SUBGRADE TREATMENT, TYPE IA	32,172.000	m2
22	207-08265 SUBGRADE TREATMENT, TYPE IIA	3,613.000	m2
23	210-07767 LATERAL	19.000	EACH
24	210-08373 SIDEWALK	151.000	m3
25	210-08373 SIDEWALK	151.000	m3
26	211-07454 STRUCTURE BACKFILL	8,244.000	m3
27	303-01180 COMPACTED AGGREGATE, NO. 53	8,432.000	Mg
28	306-08034 MILLING, ASPHALT, 38 mm	1,025.000	m2
29	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
30	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	2,108.200	Mg
31	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	4,581.500	Mg
32	401-07418 QC/QA-HMA, 3, 76, BASE, 25.0 MM	12,444.300	Mg
33	401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm	4,818.000	Mg
34	402-07432 HMA SURFACE, TYPE A	252.700	Mg
35	402-07435 HMA INTERMEDIATE, TYPE A	423.200	Mg
36	406-05520 ASPHALT FOR TACK COAT	29.500	Mg
37	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
38	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	1.000	EACH
39	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	86.500	m
40	604-07896 CURB RAMP, CONCRETE, B	18.520	m2
41	604-07901 CURB RAMP, CONCRETE, G	404.000	m2
42	604-07902 CURB RAMP, CONCRETE, H	78.000	m2
43	604-44251 STEPS, CONCRETE	51.500	m3
44	604-91531 SIDEWALK, CONCRETE, 100 mm	1,297.500	m2
45	605-06121 CURB, CONCRETE, B	5.200	m
46	605-06140 CURB AND GUTTER, CONCRETE	2,346.400	m
47	610-07486 HMA FOR APPROACHES, TYPE A	500.900	Mg
48	611-05330 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 150 mm	1,444.400	m2

CALL ORDER : 135  
 LETTING DATE :

CONTRACT ID : R -26926-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT AND INTERSECTION IMPROVEMENT		
49	611-06497 MAILBOX ASSEMBLY, SINGLE	76.000	EACH
50	611-06498 MAILBOX ASSEMBLY, DOUBLE	4.000	EACH
51	611-95728 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 200 mm	214.900	m2
52	615-06490 RIGHT OF WAY MARKER	59.000	EACH
53	615-06505 MONUMENT, B	27.000	EACH
54	615-06510 MONUMENT, C	2.000	EACH
55	616-02320 GEOTEXTILES	2,792.000	m2
56	616-06405 RIPRAP, REVETMENT	519.000	Mg
57	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
58	621-04317 MULCHED SEEDING	230.000	m2
59	621-06545 FERTILIZER	3.000	Mg
60	621-06553 SEED MIXTURE, R	457.000	kg
61	621-06554 SEED MIXTURE, U	144.000	kg
62	621-06565 MULCHING MATERIAL	14.800	Mg
63	621-06574 SODDING	1,652.000	m2
64	621-98038 MULCH, HARDWOOD SHREDDED BARK	36.000	m3
65	622-05627 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 2400	47.000	EACH
66	622-05641 PLANT, DECIDUOUS SHRUB, OVER 900 TO 1200 mm	429.000	EACH
67	622-05646 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 2400 TO 3000 mm	27.000	EACH
68	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM OVER 32 TO 50 mm	16.000	EACH
69	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 63 TO 88 mm	148.000	EACH
70	702-51015 CONCRETE, B, FOOTINGS	64.300	m3
71	702-94139 CONCRETE, A, ABOVE FOOTINGS	35.500	m3
72	703-51030 REINFORCING STEEL	3,222.000	kg
73	703-51032 REINFORCING STEEL, EPOXY COATED	3,685.000	kg
74	714-44240 CONCRETE, A, STRUCTURES	15.000	m3
75	715-02876 GRANULAR BACKFILL	200.000	m
76	715-02876 GRANULAR BACKFILL	2,150.000	m
77	715-02876 GRANULAR BACKFILL	274.000	m
78	715-02876 GRANULAR BACKFILL	200.000	m
79	715-02876 GRANULAR BACKFILL	125.000	m
80	715-03184 GRAVITY SEWER, 200 mm	272.000	m
81	715-03184 GRAVITY SEWER, 200 mm	220.000	m
82	715-03795 PIPE, DUCTILE IRON, 150 mm	140.000	m
83	715-04612 PIPE	50.000	m
84	715-04612 PIPE	125.000	m
85	715-04612 PIPE	1,878.000	m
86	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	4,550.500	m
87	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	154.200	m
88	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	172.800	m
89	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	18.400	m
90	715-05125 PIPE, TYPE 1, CIRCULAR, 750 mm	27.000	m
91	715-05127 PIPE, TYPE 1, CIRCULAR, 1050 mm	27.200	m
92	715-05133 PIPE, TYPE 1, CIRCULAR, 1500 mm	17.000	m
93	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	328.100	m
94	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	209.800	m
95	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	137.600	m
96	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	75.500	m

CALL ORDER : 135  
 LETTING DATE :

CONTRACT ID : R -26926-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT AND INTERSECTION IMPROVEMENT		
97	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	349.400	m
98	715-05163 PIPE, TYPE 2, CIRCULAR, 1500 mm	19.200	m
99	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	11.000	m
100	715-05235 PIPE, TYPE 1, DEFORMED, MIN. AREA 0.42 m2	11.000	m
101	715-05356 PIPE, TYPE 2, DEFORMED, MIN. AREA 2.73 m2	69.900	m
102	715-05358 PIPE, TYPE 2, DEFORMED, MIN. AREA 3.21 m2	366.300	m
103	715-06923 PIPE, TYPE 2, CIRCULAR, 2100 mm	235.900	m
104	715-08314 SAFETY METAL END SECTION, 4:1, 1500 mm	2.000	EACH
105	715-46005 PIPE END SECTION, 375 mm	28.000	EACH
106	715-46010 PIPE END SECTION, 450 mm	2.000	EACH
107	715-46030 PIPE END SECTION, 750 mm	2.000	EACH
108	715-91361 PIPE, PVC, 150 mm	1,700.000	m
109	715-97544 PIPE, DUCTILE IRON, 200 mm	54.000	m
110	715-97607 PIPE END SECTION, MIN. AREA .42 m2	2.000	EACH
111	718-04986 CLEANOUT	1.000	EACH
112	718-06529 OUTLET PROTECTOR, 2	7.000	EACH
113	718-06531 OUTLET PROTECTOR, 3	5.000	EACH
114	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
115	718-52610 AGGREGATE FOR UNDERDRAINS	1,025.500	m3
116	718-99153 GEOTEXTILES FOR UNDERDRAIN	10,227.000	m2
117	720-03194 MANHOLE	6.000	EACH
118	720-03194 MANHOLE	6.000	EACH
119	720-03194 MANHOLE	2.000	EACH
120	720-03194 MANHOLE	2.000	EACH
121	720-03757 MANHOLE, C15	1.000	EACH
122	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
123	720-45045 INLET, J10	22.000	EACH
124	720-45055 INLET, M10	2.000	EACH
125	720-45240 CATCH BASIN, J10	2.000	EACH
126	720-45275 PIPE CATCH BASIN, 600 mm	4.000	EACH
127	720-45410 MANHOLE, C4	17.000	EACH
128	720-45416 MANHOLE, E4	1.000	EACH
129	720-45425 MANHOLE, F4	2.000	EACH
130	720-45430 MANHOLE, G4	4.000	EACH
131	720-91110 MANHOLE, N4	2.000	EACH
132	720-95335 MANHOLE, M4	1.000	EACH
133	720-95899 MANHOLE, E7	1.000	EACH
134	720-97962 MANHOLE, G4, MODIFIED	1.000	EACH
135	720-98174 INLET, B15	26.000	EACH
136	721-43075 AUTOMATIC DRAINAGE GATE, 2100 mm	1.000	EACH
137	732-03065 TAPPING SADDLE	3.000	EACH
138	732-03065 TAPPING SADDLE	9.000	EACH
139	732-03942 HYDRANT	8.000	EACH
140	732-03942 HYDRANT	3.000	EACH
141	732-04751 WATER SERVICE	19.000	EACH
142	732-04926 VALVE	2.000	EACH
143	732-04926 VALVE	2.000	EACH
144	732-90573 WATER SERVICE LINE, 18.75 mm	380.000	m

CALL ORDER : 135  
 LETTING DATE :

CONTRACT ID : R -26926-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PAVEMENT REPLACEMENT AND INTERSECTION IMPROVEMENT			
145	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
146	801-06625 DETOUR ROUTE MARKER ASSEMBLY	62.000	EACH
147	801-06640 CONSTRUCTION SIGN, A	32.000	EACH
148	801-06645 CONSTRUCTION SIGN, B	28.000	EACH
149	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
150	801-07118 BARRICADE, III-A	22.000	m
151	801-07119 BARRICADE, III-B	36.000	m
152	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	235.000	m
153	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	86.000	m
154	802-05706 SIGN POST, SQUARE, 3, UNREINFORCED ANCHOR	14.000	m
155	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	53.000	m2
156	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	13.000	m2
157	805-04982 CABLE	930.000	m
158	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	31.000	m
159	805-06595 CONDUIT, PVC, 50 mm	63.000	m
160	805-06600 CONDUIT, PVC, 75 mm	1,196.000	m
161	805-90267 CONDUIT, STEEL, GALVANIZED, 75 mm	670.000	m
162	807-02191 HANDHOLE, LIGHTING	43.000	EACH
163	807-02824 LUMINAIRE, HIGH PRESSURE SODIUM, 100 WATT, ORNAMENTAL	37.000	EACH
164	807-03951 LIGHT POLE, ORNAMENTAL	37.000	EACH
165	807-04651 WIRE	4,226.000	m
166	807-04653 LIGHTING FOUNDATION	37.000	EACH
167	807-05074 DISCONNECT	9.000	EACH
168	807-06935 INSULATION LINK, WATERPROOFED	372.000	EACH
169	807-86805 SERVICE POINT, I	3.000	EACH
170	807-86910 CONNECTOR KIT, UNFUSED	74.000	EACH
171	807-86915 CONNECTOR KIT, FUSED	74.000	EACH
172	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	256.000	EACH
173	807-86930 INSULATION LINK, NONWATERPROOFED	148.000	EACH
174	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	2,891.200	m
175	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 600 mm	81.700	m
176	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	4,334.200	m
177	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	12.900	m
178	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
179	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH
180	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	101.000	EACH
181	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	124.000	m

CALL ORDER : 165  
 LETTING DATE :

CONTRACT ID : R -27385-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-07040 FIELD OFFICE, C	32.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	5.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	160.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
8	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
9	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-02240 PAVEMENT REMOVAL	49,586.900	m2
15	202-02241 GUARDRAIL, REMOVE	1,742.900	m
16	202-02271 HEADWALL, REMOVE	17.000	EACH
17	202-02272 PAVED SIDE DITCH, REMOVE	1,963.500	m
18	202-02273 CENTER CURB, CONCRETE, REMOVE	1,494.900	m2
19	202-02278 CURB, CONCRETE, REMOVE	4,402.900	m
20	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
21	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
22	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
23	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	206.600	m2
24	202-04089 SIGN, SHEET, REMOVE	40.000	EACH
25	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
26	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
27	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
28	202-52710 SIDEWALK, CONCRETE, REMOVE	17.200	m2
29	202-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	23.000	EACH
30	202-74050 SIGN, OVERHEAD, REMOVE	3.000	EACH
31	202-74080 OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	4.000	EACH
32	202-91385 INLET, REMOVE	18.000	EACH
33	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	9.000	EACH
34	202-94810 CURB TURNOUT, REMOVE	20.000	EACH
35	202-95579 SERVICE POINT, REMOVE	3.000	EACH
36	202-96070 HIGH MAST TOWER, REMOVE	5.000	EACH
37	202-96133 PIPE, REMOVE	891.000	m
38	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
39	202-99187 FENCE, FARM FIELD, REMOVE	1,118.600	m
40	203-02000 EXCAVATION, COMMON	110,269.000	m3
41	203-02070 BORROW	9,240.000	m3
42	203-51223 EXCAVATION, WATERWAY	1,140.000	m3
43	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	748.500	Mg
44	205-06933 TEMPORARY DITCH INLET PROTECTION	42.000	EACH
45	205-06935 TEMPORARY SEDIMENT BASIN	2.000	EACH
46	205-06937 TEMPORARY SILT FENCE	1,671.500	m
47	206-51220 EXCAVATION, WET	191.700	m3
48	206-51225 EXCAVATION, DRY	24.700	m3

CALL ORDER : 165  
 LETTING DATE :

CONTRACT ID : R -27385-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK		
49	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	1,007.500	m3
50	206-51235 COFFERDAM	LUMP	LUMP
51	207-08262 SUBGRADE TREATMENT, TYPE I	41,761.300	m2
52	207-08263 SUBGRADE TREATMENT, TYPE IA	57,982.000	m2
53	207-08265 SUBGRADE TREATMENT, TYPE IIA	17,997.500	m2
54	210-08274 COMPOST	41.000	m3
55	211-02050 B BORROW	10,128.000	m3
56	211-06467 AGGREGATE FOR END BENT BACKFILL	408.900	m3
57	211-07454 STRUCTURE BACKFILL	24,668.600	m3
58	213-08058 FLOWABLE BACKFILL	96.600	m3
59	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	20,281.100	Mg
60	302-06464 SUBBASE FOR PCCP	8,050.200	m3
61	302-07455 DENSE GRADED SUBBASE	288.400	m3
62	303-07449 COMPACTED AGGREGATE, NO. 73	24.300	Mg
63	304-07493 WIDENING WITH HMA, TYPE B	1,457.200	Mg
64	304-07783 HMA PATCHING, TYPE D	70.100	Mg
65	306-08034 MILLING, ASPHALT, 38 mm	10,259.300	m2
66	306-08036 MILLING, ASPHALT, 50 mm	6,229.500	m2
67	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
68	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	6,272.800	Mg
69	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	663.800	Mg
70	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 MM	10,429.300	Mg
71	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 MM	1,098.900	Mg
72	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	18,161.600	Mg
73	401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm	7,589.300	Mg
74	401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm	6,496.500	Mg
75	402-07786 HMA BASE, TYPE D	46.500	Mg
76	404-05511 SEAL COAT, 2	1,361.200	m2
77	406-05520 ASPHALT FOR TACK COAT	83.330	Mg
78	501-04771 CORING CONCRETE PAVEMENT	LUMP	LUMP
79	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
80	501-06323 QC/QA-PCCP, 300 mm	30,522.600	m2
81	501-06325 QC/QA-PCCP, 350 mm	12,990.500	m2
82	503-03489 RETROFITTED TIE BARS	2,472.000	EACH
83	503-05240 D-1 CONTRACTION JOINT	7,878.700	m
84	503-05310 TERMINAL JOINT	126.700	m
85	601-01522 GUARDRAIL TRANSITION TYPE TGB	10.000	EACH
86	601-06224 IMPACT ATTENUATOR, CR, W1, TL-2	4.000	EACH
87	601-06228 IMPACT ATTENUATOR, CR, W1, TL-3	1.000	EACH
88	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
89	601-06238 IMPACT ATTENUATOR, R1, W1, TL-3	2.000	EACH
90	601-06416 IMPACT ATTENUATOR SPARE PARTS PACKAGE, ED, W1, TL-3	1.000	EACH
91	601-06421 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R1, W1, TL-3	1.000	EACH
92	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
93	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
94	601-94689 GUARDRAIL END TREATMENT, OS	11.000	EACH
95	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	739.140	m
96	602-06729 BARRIER DELINEATOR	17.000	EACH

CALL ORDER : 165  
 LETTING DATE :

CONTRACT ID : R -27385-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK			
97	602-91266 MEDIAN BARRIER, CONCRETE, MODIFIED	520.000	m
98	603-06045 FENCE, CHAIN LINK, 1220 mm	3,185.400	m
99	604-06070 SIDEWALK, CONCRETE	134.900	m2
100	604-07902 CURB RAMP, CONCRETE, H	10.800	m2
101	605-06090 CURB, INTEGRAL, CONCRETE	120.800	m
102	605-06095 CURB, INTEGRAL, B, CONCRETE	198.300	m
103	605-06120 CURB, CONCRETE	116.900	m
104	605-06140 CURB AND GUTTER, CONCRETE	1,202.700	m
105	605-06145 CURB AND GUTTER, B, CONCRETE	1,874.300	m
106	605-06255 CENTER CURB, D, CONCRETE	1,355.300	m2
107	607-06370 PAVED SIDE DITCH, H	74.200	m
108	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	1,576.700	m2
109	609-06262 REINFORCED CONCRETE BRIDGE	155.100	m2
110	610-07486 HMA FOR APPROACHES, TYPE A	4,363.800	Mg
111	611-05330 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 150 mm	2,897.400	m2
112	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
113	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
114	615-06490 RIGHT OF WAY MARKER	101.000	EACH
115	615-06500 MONUMENT, A	4.000	EACH
116	615-06505 MONUMENT, B	33.000	EACH
117	615-06510 MONUMENT, C	14.000	EACH
118	615-06515 MONUMENT, D	58.000	EACH
119	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
120	616-02320 GEOTEXTILES	14,262.100	m2
121	616-05689 RIPRAP, CLASS 2	1,313.000	Mg
122	616-06405 RIPRAP, REVETMENT	5,165.500	Mg
123	616-06451 RIPRAP, UNIFORM	2,126.000	Mg
124	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
125	621-04258 SEED MIXTURE	3.200	kg
126	621-04258 SEED MIXTURE	40.000	kg
127	621-06545 FERTILIZER	7.400	Mg
128	621-06554 SEED MIXTURE, U	1,286.200	kg
129	621-06557 SEED MIXTURE, T	123.400	kg
130	621-06565 MULCHING MATERIAL	41.300	Mg
131	621-06574 SODDING	707.400	m2
132	621-06575 SODDING, NURSERY	64,839.700	m2
133	621-98038 MULCH, HARDWOOD SHREDDED BARK	48.000	m3
134	622-01937 PLANT	17.000	EACH
135	622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 1800	33.000	EACH
136	622-05640 PLANT, DECIDUOUS SHRUB, OVER 600 TO 900 mm	420.000	EACH
137	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 50 TO 63 mm	87.000	EACH
138	622-05654 PLANT, PERENNIAL	1,031.000	EACH
139	622-52436 SIGN, DO NOT MOW OR SPRAY	20.000	EACH
140	701-01849 PILE, CONCRETE, STEEL SHELL ENCASED, 7.92 mm, 356 mm	1,341.200	m
141	701-06011 DYNAMIC PILE LOAD TEST	5.000	EACH
142	701-06012 TEST PILE, RESTRIKE	5.000	EACH
143	701-06027 TEST PILE	5.000	EACH
144	701-95780 PILE, STEEL H, HP 310 X 110	1,847.200	m

CALL ORDER : 165  
 LETTING DATE :

CONTRACT ID : R -27385-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK			
145	701-98647 PILE, CONCRETE, STEEL SHELL ENCASED, 5.16 mm, 356 mm	60.000	m
146	702-51005 CONCRETE, A, SUBSTRUCTURE	754.900	m3
147	702-51015 CONCRETE, B, FOOTINGS	102.900	m3
148	702-51090 BRONZE PLATES	45.000	kg
149	702-51100 DRAIN PIPE, CAST IRON, 150 mm	1,183.400	kg
150	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	988.800	kg
151	702-51863 FIELD DRILLED HOLE IN CONCRETE	82.000	EACH
152	703-06028 REINFORCING BARS	17,842.000	kg
153	703-06029 REINFORCING BARS, EPOXY COATED	330,600.000	kg
154	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	3,240.000	EACH
155	704-04850 CONCRETE	953.000	m2
156	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,614.300	m3
157	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
158	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	2.000	EACH
159	706-06349 RAILING, TX	134.800	m
160	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	4.000	EACH
161	706-51020 CONCRETE, C, RAILING	64.900	m3
162	707-05982 STRUCTURAL MEMBERS, CONCRETE I-BEAM, I, 711 mm X 305 mm	48.000	m
163	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 1143 mm X 406 mm	580.000	m
164	708-51813 PNEUMATICALLY PLACED MORTAR	2.000	m2
165	708-51814 WELDED STEEL WIRE FABRIC	2.000	m2
166	709-04919 COATING	3,781.000	m2
167	709-51821 SURFACE SEAL	LUMP	LUMP
168	709-51821 SURFACE SEAL	LUMP	LUMP
169	709-51821 SURFACE SEAL	LUMP	LUMP
170	711-01786 STRUCTURAL STEEL DRILLING, 25 mm DIA. HOLE	24.000	EACH
171	711-51038 STRUCTURAL STEEL	LUMP	LUMP
172	711-51038 STRUCTURAL STEEL	LUMP	LUMP
173	711-51070 ANCHOR PLATE, AP 1	86.000	EACH
174	711-51080 ANCHOR PLATE, AP 3	8.000	EACH
175	715-02397 SAFETY METAL END SECTION, 4:1, 900 mm	1.000	EACH
176	715-04618 SAFETY METAL END SECTION, 6:1, 750 mm	1.000	EACH
177	715-05019 PIPE, TYPE 1, CIRCULAR, 900 mm	53.400	m
178	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	561.900	m
179	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	9,191.700	m
180	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	559.900	m
181	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	100.800	m
182	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	643.600	m
183	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	1,435.700	m
184	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	590.600	m
185	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	99.500	m
186	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	300.300	m
187	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	492.400	m
188	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	74.300	m
189	715-05161 PIPE, TYPE 2, CIRCULAR, 1200 mm	0.600	m
190	715-05168 PIPE, TYPE 3, CIRCULAR, 300 mm	8.400	m
191	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	35.800	m
192	715-05171 PIPE, TYPE 3, CIRCULAR, 450 mm	15.600	m



CALL ORDER : 165  
 LETTING DATE :

CONTRACT ID : R -27385-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK			
193	715-05177 PIPE, TYPE 3, CIRCULAR, 900 mm	138.100	m
194	715-05363 PIPE, TYPE 3, DEFORMED, MIN. AREA 0.17 m2	9.100	m
195	715-05407 PIPE, END BENT DRAIN, 150 mm	64.400	m
196	715-05428 PIPE, SLOTTED VANE DRAIN, 300 mm	23.800	m
197	715-05596 PIPE EXTENSION, CIRCULAR, 450 mm	1.200	m
198	715-05597 PIPE EXTENSION, CIRCULAR, 600 mm	38.400	m
199	715-05842 CONCRETE ANCHOR, 1050 mm	1.000	EACH
200	715-06004 CONCRETE ANCHOR, 1200 mm	1.000	EACH
201	715-06337 PIPE EXTENSION, CIRCULAR, 1200 mm	4.300	m
202	715-07089 PIPE EXTENSION, DEFORMED, MIN. AREA 1.68 m2	4.500	m
203	715-46000 PIPE END SECTION, 300 mm	3.000	EACH
204	715-46005 PIPE END SECTION, 375 mm	17.000	EACH
205	715-46010 PIPE END SECTION, 450 mm	8.000	EACH
206	715-46015 PIPE END SECTION, 525 mm	1.000	EACH
207	715-46020 PIPE END SECTION, 600 mm	9.000	EACH
208	715-46030 PIPE END SECTION, 750 mm	3.000	EACH
209	715-46040 PIPE END SECTION, 900 mm	7.000	EACH
210	715-46055 PIPE END SECTION, MIN. AREA .17 m2	2.000	EACH
211	718-06528 OUTLET PROTECTOR, 1	23.000	EACH
212	718-06529 OUTLET PROTECTOR, 2	3.000	EACH
213	718-06531 OUTLET PROTECTOR, 3	28.000	EACH
214	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	m
215	718-52610 AGGREGATE FOR UNDERDRAINS	1,515.300	m3
216	718-99153 GEOTEXTILES FOR UNDERDRAIN	24,479.800	m2
217	720-01150 MANHOLE, F	1.000	EACH
218	720-44000 CASTING, ADJUST TO GRADE	11.000	EACH
219	720-44296 CAP INLET	1.000	EACH
220	720-45030 INLET, E7	3.000	EACH
221	720-45035 INLET, F7	2.000	EACH
222	720-45235 CATCH BASIN, E7	2.000	EACH
223	720-45251 CATCH BASIN, K10, MODIFIED	12.000	EACH
224	720-45265 PIPE CATCH BASIN, 375 mm	2.000	EACH
225	720-45270 PIPE CATCH BASIN, 450 mm	14.000	EACH
226	720-45410 MANHOLE, C4	36.000	EACH
227	720-45416 MANHOLE, E4	1.000	EACH
228	720-90129 MANHOLE, J2	9.000	EACH
229	720-90984 MANHOLE, C2	4.000	EACH
230	720-91352 CATCH BASIN, F7	3.000	EACH
231	720-93409 INLET, B15, MODIFIED	3.000	EACH
232	720-93411 INLET, C15, MODIFIED	1.000	EACH
233	720-94713 CATCH BASIN, C15, MODIFIED	1.000	EACH
234	720-95164 CATCH BASIN, B15, MODIFIED	10.000	EACH
235	720-95422 MANHOLE, J4	1.000	EACH
236	720-97958 MANHOLE, K2	1.000	EACH
237	720-98068 MANHOLE, E2	1.000	EACH
238	720-98174 INLET, B15	5.000	EACH
239	720-99416 CATCH BASIN, B15	13.000	EACH
240	720-99417 CATCH BASIN, C15	11.000	EACH

CALL ORDER : 165  
 LETTING DATE :

CONTRACT ID : R -27385-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK			
241	724-04163 STRUCTURAL EXPANSION JOINT SEAL, REPLACE	68.000	m
242	728-98377 MASONRY COATING	LUMP	LUMP
243	731-93945 FACE PANELS, CONCRETE	3,184.500	m2
244	731-93946 WALL ERECTION	3,184.500	m2
245	731-93947 LEVELING PAD, CONCRETE	520.000	m
246	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	26.000	EACH
247	801-01505 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (ONLY)	24.000	EACH
248	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
249	801-03291 CONSTRUCTION SIGN, D	4.000	EACH
250	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
251	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	15,105.300	m
252	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	35,981.000	m
253	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 600 mm	23.000	m
254	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 600 mm	7.500	m
255	801-06625 DETOUR ROUTE MARKER ASSEMBLY	35.000	EACH
256	801-06640 CONSTRUCTION SIGN, A	50.000	EACH
257	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
258	801-06710 FLASHING ARROW SIGN	840.000	DAY
259	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
260	801-07118 BARRICADE, III-A	489.600	m
261	801-07119 BARRICADE, III-B	100.800	m
262	801-07120 BARRICADE, III, PERMANENT	12.000	m
263	801-07612 TEMPORARY PAVEMENT MARKING, 600 mm	39.700	m
264	801-08388 TEMPORARY TRAFFIC BARRIER	2,518.000	m
265	801-08389 TEMPORARY TRAFFIC BARRIER, ANCHORED	1,341.500	m
266	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
267	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	5.000	EACH
268	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	290.670	m
269	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	189.870	m
270	802-07057 SIGN, PANEL, WITH LEGEND	341.608	m2
271	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	86.000	EACH
272	802-07060 SIGN, SHEET, RELOCATE	16.000	EACH
273	802-07101 SIGN LIGHTING SYSTEM, TRACK, BOX TRUSS	1.000	EACH
274	802-07102 SIGN LIGHTING SYSTEM, TRACK, CANTILEVER	1.000	EACH
275	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	14.000	EACH
276	802-07153 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	22.000	EACH
277	802-07158 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, I	1.000	EACH
278	802-07159 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, II	4.000	EACH
279	802-07275 BOX TRUSS SIGN FOUNDATION, V-C	1.000	EACH
280	802-07278 BOX TRUSS SIGN FOUNDATION, V-D	1.000	EACH
281	802-07285 BOX TRUSS SIGN FOUNDATION, VI-C	4.000	EACH
282	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	36.006	m2
283	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	48.240	m2
284	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	26.453	m2
285	802-76065 SIGN POST, B	6.000	m
286	802-76095 STRUCTURAL STEEL, BREAKAWAY	6,554.000	kg
287	802-76115 SPAN OVERHEAD SIGN STRUCTURE, TRI-CHORD TRUSS, SINGLE	2.000	EACH
288	802-76140 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM	1.000	EACH

CALL ORDER : 165  
 LETTING DATE :

CONTRACT ID : R -27385-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK		
289	802-76170 WALKWAY, HANDRAIL, AND LIGHTING SUPPORT ASSEMBLY	37.500	m
290	802-94494 SIGN STRUCTURE, OVERHEAD, RELOCATE	1.000	EACH
291	803-76110 SPAN OVERHEAD SIGN STRUCTURE, BOX TRUSS	2.000	EACH
292	804-06770 DELINEATOR POST	54.000	EACH
293	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	2.000	EACH
294	805-01842 HANDHOLE, SIGNAL	9.000	EACH
295	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
296	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	751.300	m
297	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
298	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	8.000	EACH
299	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER ARROW, GREEN	4.000	EACH
300	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
301	805-78420 DISCONNECT HANGER	4.000	EACH
302	805-78445 SIGNAL SERVICE	1.000	EACH
303	805-78467 SIGNAL CABLE, 3C 8GA.	14.200	m
304	805-78485 SIGNAL CABLE, 5C 14GA.	264.000	m
305	805-78490 SIGNAL CABLE, 7C 14GA.	329.000	m
306	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,199.400	m
307	805-78746 PREFORMED LOOP DETECTORS	463.900	m
308	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
309	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
310	805-86810 SERVICE POINT, II	4.000	EACH
311	805-86820 CONCRETE FOUNDATION WITH GROUNDING, 760 mm X 760 mm X	23.000	EACH
312	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	920.000	m
313	805-86920 MULTIPLE COMPRESSION FITTING, NOT WATERPROOFED	60.000	EACH
314	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	10.000	EACH
315	805-92512 MICROLOOP DETECTOR	2.000	EACH
316	805-96014 SAW CUT, FULL DEPTH	175.200	m
317	805-98335 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C	4,000.000	m
318	805-98336 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	300.000	m
319	807-07211 LIGHT POLE, 12.8 m E.M.H., 6.1 m MAST ARM,	1.000	EACH
320	807-82004 SIGN CIRCUIT INSTALLATION, BOX TRUSS, 5 LUMINAIRES	2.000	EACH
321	807-82058 UNDERPASS CIRCUIT INSTALLATION, 8 LUMINAIRES	1.000	EACH
322	807-82120 LIGHT POLE, HIGH MAST, 27 m E.M.H.	1.000	EACH
323	807-82400 LIGHT POLE, HIGH MAST, 38 m E.M.H.	2.000	EACH
324	807-84688 LIGHT POLE, 11.6 m E.M.H., 1.5 m MAST ARM, TRANSFORMER BASE	1.000	EACH
325	807-84740 LIGHT POLE, 12.2 m E.M.H., 1.5 m MAST ARM, TRANSFORMER BASE	1.000	EACH
326	807-84752 LIGHT POLE, 12.2 m E.M.H., 3.1 m MAST ARM, TRANSFORMER BASE	3.000	EACH
327	807-84760 LIGHT POLE, 12.2 m E.M.H., 4.6 m MAST ARM, TRANSFORMER BASE	1.000	EACH
328	807-84804 LIGHT POLE, 12.8 m E.M.H., 3.1 m MAST ARM, TRANSFORMER BASE	2.000	EACH
329	807-84814 LIGHT POLE, 12.8 m E.M.H., 4.6 m MAST ARM, TRANSFORMER BASE	14.000	EACH
330	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	23.000	EACH
331	807-86635 LUMINAIRE, ROADWAY, MERCURY VAPOR, 250 WATT	16.000	EACH
332	807-86665 LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM	16.000	EACH
333	807-86750 LUMINAIRE UNDERPASS, WALL MOUNTED, HIGH PRESSURE SODIUM, 150	8.000	EACH
334	807-86830 CONCRETE FOUNDATION WITH GROUNDING, 1220 mm DIA. X 6100 mm	3.000	EACH
335	807-86910 CONNECTOR KIT, UNFUSED	30.000	EACH
336	807-86915 CONNECTOR KIT, FUSED	34.000	EACH

CALL ORDER : 165  
 LETTING DATE :

CONTRACT ID : R -27385-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD AND MEDIAN CONSTRUCTION, SIGNS, AND BRIDGE WORK		
337	807-86930 INSULATION LINK, NONWATERPROOFED	52.000	EACH
338	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	35.000	EACH
339	807-86955 CABLE DUCT MARKER	12.000	EACH
340	807-96868 LUMINAIRE, INSTALL	10.000	EACH
341	808-03002 LINE, EPOXY, BROKEN, WHITE, 100 mm	1,340.000	m
342	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	774.600	m
343	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	141.600	m
344	808-04896 LINE, EPOXY, BROKEN, YELLOW, 100 mm	35.400	m
345	808-05534 LINE, EPOXY, SOLID, WHITE, 200 mm	854.000	m
346	808-05535 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, CROSSHATCH LINE,	91.000	m
347	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	978.700	m
348	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	4,942.400	m
349	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	8,051.000	m
350	808-06714 LINE, PAINT, SOLID, YELLOW, 100 mm	5,002.000	m
351	808-06716 LINE, REMOVE	9,200.000	m
352	808-06848 LINE, EPOXY, DOTTED, WHITE, 100 mm, 600m LINE, 1200 mm GAP	152.000	m
353	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 600 mm	46.000	m
354	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	22.000	EACH
355	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	8.000	EACH
356	808-74811 LINE, EPOXY, BROKEN, WHITE, 125 mm	688.000	m
357	808-75008 LINE, PAINT, SOLID, WHITE, 200 mm	594.000	m
358	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	629.400	m
359	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	9,254.000	m
360	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	141.700	m
361	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	38.000	EACH
362	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	36.000	EACH
363	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	748.000	EACH

CALL ORDER : 195  
 LETTING DATE :

CONTRACT ID : R -27847-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, PEDESTRIAN/BICYCLE FACILITY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	9.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
5	203-02000 EXCAVATION, COMMON	3,743.000	CYS
6	203-02070 BORROW	1,269.000	CYS
7	203-51223 EXCAVATION, WATERWAY	972.000	CYS
8	205-06933 TEMPORARY DITCH INLET PROTECTION	6.000	EACH
9	205-06937 TEMPORARY SILT FENCE	6,073.000	LFT
10	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	110.000	CYS
11	210-04181 BICYCLE RACK	3.000	EACH
12	210-06986 PAVEMENT	30.000	SYS
13	211-06467 AGGREGATE FOR END BENT BACKFILL	42.000	CYS
14	211-07454 STRUCTURE BACKFILL	134.000	CYS
15	212-06282 STOCKPILED SELECTED MATERIAL, SALVAGED	5,911.000	CYS
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,714.500	TON
17	304-07489 HMA PATCHING, TYPE A	22.000	TON
18	304-07492 WIDENING WITH HMA, TYPE A	20.200	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN.	64.900	SYS
20	402-07432 HMA SURFACE, TYPE A	590.400	TON
21	402-07435 HMA INTERMEDIATE, TYPE A	1,180.900	TON
22	402-07440 HMA BASE, TYPE A	5.800	TON
23	402-07450 HMA, TYPE A, WEDGE AND LEVEL	267.100	TON
24	406-05520 ASPHALT FOR TACK COAT	2.800	TON
25	604-01920 CONCRETE PAVERS	24.300	SYS
26	604-07897 CURB RAMP, CONCRETE, C	28.000	SYS
27	604-07900 CURB RAMP, CONCRETE, F	144.300	SYS
28	604-90256 SIDEWALK, CONCRETE, 6 IN.	12.600	SYS
29	604-90256 SIDEWALK, CONCRETE, 6 IN.	163.000	SYS
30	604-90256 SIDEWALK, CONCRETE, 6 IN.	13.400	SYS
31	604-91531 SIDEWALK, CONCRETE, 4 IN.	299.000	SYS
32	604-91531 SIDEWALK, CONCRETE, 4 IN.	114.700	SYS
33	605-06125 CURB, CONCRETE, MODIFIED	28.000	LFT
34	611-03671 TRASH RECEPTACLE	4.000	EACH
35	616-02320 GEOTEXTILES	717.000	SYS
36	616-06405 RIPRAP, REVETMENT	468.000	TON
37	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
38	621-06559 MULCHED SEEDING, R	16,468.800	SYS
39	621-08161 PERMANENT TURF REINFORCEMENT MAT	319.400	SYS
40	621-98038 MULCH, HARDWOOD SHREDDED BARK	130.000	CYS
41	622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN.	10.000	EACH
42	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.	10.000	EACH
43	622-05654 PLANT, PERENNIAL	277.000	EACH
44	701-03753 PILE, CONCRETE, STEEL SHELL ENCASED, 0.209 IN., 14 IN.	525.000	LFT
45	702-51005 CONCRETE, A, SUBSTRUCTURE	40.800	CYS
46	703-51030 REINFORCING STEEL	4,908.000	LBS
47	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP
48	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP

CALL ORDER : 195  
 LETTING DATE :

CONTRACT ID : R -27847-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, PEDESTRIAN/BICYCLE FACILITY		
49	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP
50	711-90932 EDGING, STEEL	300.000	LFT
51	712-03017 PARK BENCH	8.000	EACH
52	712-05098 TIMBER	1.000	EACH
53	713-08148 BRIDGE SUPPORTS	LUMP	LUMP
54	714-04802 CONCRETE MODULAR BLOCK WALL	6.000	SYS
55	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	257.000	LFT
56	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	44.000	LFT
57	715-05407 PIPE, END BENT DRAIN, 6 IN.	240.000	LFT
58	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
59	715-94530 ADJUST WATER VALVE TO GRADE	3.000	EACH
60	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
61	720-45235 CATCH BASIN, E7	3.000	EACH
62	720-45250 CATCH BASIN, K10	2.000	EACH
63	720-45275 PIPE CATCH BASIN, 24 IN.	1.000	EACH
64	731-93946 WALL ERECTION	54.000	SFT
65	731-93947 LEVELING PAD, CONCRETE	43.000	LFT
66	732-07653 COARSE AGGREGATE, NO. 8	2.000	TON
67	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
68	801-06645 CONSTRUCTION SIGN, B	7.000	EACH
69	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
70	802-03896 BOLLARD	15.000	EACH
71	802-04314 SIGN	4.000	EACH
72	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	240.000	LFT
73	802-07060 SIGN, SHEET, RELOCATE	6.000	EACH
74	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	112.800	SFT
75	808-02977 TRANSVERSE MARKING, THERMOPLASTIC, BIKE SYMBOL	3.000	EACH
76	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	188.000	LFT
77	808-04096 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (LANE)	3.000	EACH
78	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	982.000	LFT
79	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,115.000	LFT
80	808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	548.000	LFT
81	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,230.000	LFT
82	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	63.000	LFT

CALL ORDER : 205  
 LETTING DATE :

CONTRACT ID : R -27987-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION, ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	30.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	5.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	150.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	33,000.000	m2
13	202-02241 GUARDRAIL, REMOVE	685.000	m
14	202-02278 CURB, CONCRETE, REMOVE	1,310.000	m
15	202-04089 SIGN, SHEET, REMOVE	97.000	EACH
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
18	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
19	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
20	202-52710 SIDEWALK, CONCRETE, REMOVE	195.000	m2
21	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
22	202-99383 TERMINAL JOINT, REMOVE	15.000	m
23	203-02000 EXCAVATION, COMMON	148,878.000	m3
24	203-02070 BORROW	47.000	m3
25	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	464.000	Mg
26	205-06933 TEMPORARY DITCH INLET PROTECTION	65.000	EACH
27	205-06934 TEMPORARY MULCHING	38.200	Mg
28	205-06936 TEMPORARY SEDIMENT TRAP	162.800	Mg
29	205-06937 TEMPORARY SILT FENCE	4,331.000	m
30	206-93520 TEMPORARY SHEET PILING	46.800	m2
31	207-08267 SUBGRADE TREATMENT, TYPE IIIA	38,800.000	m2
32	207-08268 SUBGRADE TREATMENT, TYPE IV	111,540.000	m2
33	211-07454 STRUCTURE BACKFILL	14,909.000	m3
34	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	11,200.000	Mg
35	302-07455 DENSE GRADED SUBBASE	52.000	m3
36	303-07449 COMPACTED AGGREGATE, NO. 73	57.000	Mg
37	304-07490 HMA PATCHING, TYPE B	111.300	Mg
38	306-08043 MILLING, TRANSITION	1,020.000	m2
39	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
40	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	410.000	Mg
41	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	1,622.000	Mg
42	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	7,277.000	Mg
43	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	2,733.000	Mg
44	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 MM	11,909.000	Mg
45	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 MM	1,506.000	Mg
46	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	13,243.000	Mg
47	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	44,495.000	Mg
48	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	18,341.000	Mg

CALL ORDER : 205  
 LETTING DATE :

CONTRACT ID : R -27987-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION, ADDED TRAVEL LANES		
49	402-07453 HMA FOR TEMPORARY PAVEMENT	28,383.000	Mg
50	406-05520 ASPHALT FOR TACK COAT	167.100	Mg
51	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
52	601-01839 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 6	1.000	EACH
53	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
54	601-02206 TEMPORARY GUARDRAIL, W BEAM, 1.905 m SPACING	95.250	m
55	601-02207 TEMPORARY GUARD RAIL TRANSITION, VH, 1.905 m SPACING	2.000	EACH
56	601-06854 GUARDRAIL, W-BEAM, NESTED	4.000	EACH
57	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	5.000	EACH
58	601-94689 GUARDRAIL END TREATMENT, OS	14.000	EACH
59	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	569.600	m
60	602-06729 BARRIER DELINEATOR	14.000	EACH
61	603-02940 FENCE GATE, CHAIN LINK, 1820 mm X 6.1 m	1.000	EACH
62	603-06045 FENCE, CHAIN LINK, 1220 mm	33.500	m
63	603-92636 FENCE, CHAIN LINK, 1830 mm	525.000	m
64	604-07900 CURB RAMP, CONCRETE, F	240.000	m2
65	604-07901 CURB RAMP, CONCRETE, G	65.000	m2
66	604-07902 CURB RAMP, CONCRETE, H	5.000	m2
67	604-91531 SIDEWALK, CONCRETE, 100 mm	10,565.000	m2
68	605-06120 CURB, CONCRETE	615.000	m
69	605-06140 CURB AND GUTTER, CONCRETE	7,160.000	m
70	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	1,445.000	m
71	605-06215 CENTER CURB, D, CONCRETE	310.000	m
72	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	349.800	m2
73	610-07487 HMA FOR APPROACHES, TYPE B	175.000	Mg
74	610-07712 PCCP FOR APPROACHES, 150 mm	7,494.000	m2
75	611-06497 MAILBOX ASSEMBLY, SINGLE	68.000	EACH
76	615-06490 RIGHT OF WAY MARKER	206.000	EACH
77	615-06505 MONUMENT, B	18.000	EACH
78	615-06510 MONUMENT, C	4.000	EACH
79	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
80	615-06530 POST, BENCHMARK	2.000	EACH
81	616-02320 GEOTEXTILES	7,702.000	m2
82	616-05688 RIPRAP, CLASS 1	501.800	Mg
83	616-05689 RIPRAP, CLASS 2	902.400	Mg
84	616-06405 RIPRAP, REVETMENT	1,849.400	Mg
85	616-06451 RIPRAP, UNIFORM	96.100	Mg
86	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
87	619-61505 CLEAN AND PAINT END DIAPHRAGMS EXPANSION SHOES AND BEAM ENDS	LUMP	LUMP
88	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
89	621-03787 SEED MIXTURE, D	150.000	kg
90	621-06545 FERTILIZER	13.000	Mg
91	621-06553 SEED MIXTURE, R	1,760.000	kg
92	621-06554 SEED MIXTURE, U	865.000	kg
93	621-06557 SEED MIXTURE, T	1,146.000	kg
94	621-06565 MULCHING MATERIAL	65.000	Mg
95	621-06567 WATER	3,154.000	kL
96	621-06570 TOP SOIL	16,060.000	m3



CALL ORDER : 205  
 LETTING DATE :

CONTRACT ID : R -27987-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION, ADDED TRAVEL LANES		
97	621-06575 SODDING, NURSERY	17,530.000	m2
98	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
99	622-91786 SEEDLING	140.000	EACH
100	702-51863 FIELD DRILLED HOLE IN CONCRETE	1,356.000	EACH
101	703-51032 REINFORCING STEEL, EPOXY COATED	13,076.000	kg
102	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	170.000	EACH
103	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	88.000	EACH
104	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
105	706-51020 CONCRETE, C, RAILING	29.200	m3
106	709-51821 SURFACE SEAL	LUMP	LUMP
107	714-06613 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 4800 mm X 1800 mm	36.500	m
108	714-93978 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1200 mm x 600 mm	6.800	m
109	714-99346 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 900 mm x 600 mm	6.100	m
110	714-99348 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1500 mm x 900 mm	114.400	m
111	715-02397 SAFETY METAL END SECTION, 4:1, 900 mm	4.000	EACH
112	715-04612 PIPE	18.300	m
113	715-04612 PIPE	6.000	m
114	715-04612 PIPE	3.000	m
115	715-04855 PIPE END SECTION, 1050 mm	2.000	EACH
116	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	509.800	m
117	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	7,301.000	m
118	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	43.200	m
119	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	3,194.700	m
120	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	328.900	m
121	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	1,091.600	m
122	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	1,123.500	m
123	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	1,171.900	m
124	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	65.000	m
125	715-05165 PIPE, TYPE 2, CIRCULAR, 1800 mm	7.000	m
126	715-46000 PIPE END SECTION, 300 mm	8.000	EACH
127	715-46005 PIPE END SECTION, 375 mm	36.000	EACH
128	715-46010 PIPE END SECTION, 450 mm	6.000	EACH
129	715-46020 PIPE END SECTION, 600 mm	4.000	EACH
130	715-46030 PIPE END SECTION, 750 mm	4.000	EACH
131	715-46040 PIPE END SECTION, 900 mm	5.000	EACH
132	718-06528 OUTLET PROTECTOR, 1	5.000	EACH
133	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
134	718-52610 AGGREGATE FOR UNDERDRAINS	1,609.000	m3
135	718-99153 GEOTEXTILES FOR UNDERDRAIN	23,108.000	m2
136	720-01092 MANHOLE, J15, MODIFIED	80.000	EACH
137	720-03194 MANHOLE	1.000	EACH
138	720-04574 MANHOLE, J-5	2.000	EACH
139	720-08241 MANHOLE, K15, MODIFIED	4.000	EACH
140	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
141	720-45030 INLET, E7	16.000	EACH
142	720-45035 INLET, F7	8.000	EACH
143	720-45042 INLET, HA5	7.000	EACH
144	720-45105 INLET, A2, MODIFIED	2.000	EACH

CALL ORDER : 205  
 LETTING DATE :

CONTRACT ID : R -27987-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION, ADDED TRAVEL LANES		
145	720-45130 INLET, E7, MODIFIED	6.000	EACH
146	720-45410 MANHOLE, C4	5.000	EACH
147	720-45510 MANHOLE, C4, MODIFIED	6.000	EACH
148	720-93409 INLET, B15, MODIFIED	108.000	EACH
149	720-93411 INLET, C15, MODIFIED	26.000	EACH
150	720-94157 MANHOLE, C	2.000	EACH
151	720-95422 MANHOLE, J4	3.000	EACH
152	720-97865 MANHOLE, C2, MODIFIED	2.000	EACH
153	720-98555 INLET, C15	27.000	EACH
154	723-06660 WINGWALL	58.300	m2
155	724-03276 EXPANSION JOINT SEALING SYSTEM	38.800	m
156	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	50.000	EACH
157	801-01505 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (ONLY)	45.000	EACH
158	801-02595 CONTROLLER, RESET TIMING	15.000	EACH
159	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
160	801-04308 ROAD CLOSURE SIGN ASSEMBLY	17.000	EACH
161	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	20,540.000	m
162	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	41,175.000	m
163	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	145.000	m
164	801-06539 TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	LUMP	LUMP
165	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 600 mm	360.000	m
166	801-06625 DETOUR ROUTE MARKER ASSEMBLY	57.000	EACH
167	801-06640 CONSTRUCTION SIGN, A	149.000	EACH
168	801-06645 CONSTRUCTION SIGN, B	14.000	EACH
169	801-06710 FLASHING ARROW SIGN	730.000	DAY
170	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
171	801-07023 ENERGY ABSORBIBG TERMINAL, CZ, TL-2	9.000	EACH
172	801-07119 BARRICADE, III-B	756.000	m
173	801-08388 TEMPORARY TRAFFIC BARRIER	281.000	m
174	801-08389 TEMPORARY TRAFFIC BARRIER, ANCHORED	610.000	m
175	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	6.000	EACH
176	801-94295 SIGNAL HEAD, RELOCATE	176.000	EACH
177	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	58.000	m
178	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	330.000	m
179	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	38.000	m2
180	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	61.000	m2
181	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	5.000	m2
182	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	20.000	EACH
183	805-01842 HANDHOLE, SIGNAL	43.000	EACH
184	805-01879 SIGNAL SERVICE	5.000	EACH
185	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
186	805-04951 PLATE	1.000	EACH
187	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	2,500.000	m
188	805-08494 RADIO SPREAD SPECTRUM	5.000	EACH
189	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	5.000	EACH
190	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	40.000	EACH
191	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	4.000	EACH
192	805-78415 SPAN, CATENARY, AND TETHER	20.000	EACH

CALL ORDER : 205  
 LETTING DATE :

CONTRACT ID : R -27987-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION, ADDED TRAVEL LANES		
193	805-78420 DISCONNECT HANGER	20.000	EACH
194	805-78467 SIGNAL CABLE, 3C 8GA.	50.000	m
195	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	5,480.000	m
196	805-78485 SIGNAL CABLE, 5C 14GA.	670.000	m
197	805-78490 SIGNAL CABLE, 7C 14GA.	1,075.000	m
198	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	3,530.000	m
199	805-78785 SIGNAL DETECTOR HOUSING	44.000	EACH
200	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,950.000	m
201	805-78925 CONTROLLER CABINET FOUNDATION, P1	5.000	EACH
202	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
203	805-96261 FIBER OPTIC CABLE, AERIAL	5,970.000	m
204	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	185.000	m
205	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	1,735.000	m
206	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	2,060.000	m
207	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	2,100.000	m
208	808-06716 LINE, REMOVE	9,140.000	m
209	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	850.000	m
210	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	7,675.000	m
211	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	190.000	m
212	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	370.000	m
213	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm	1,440.000	m
214	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	68.000	EACH
215	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	46.000	EACH
216	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	190.000	EACH
217	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	635.000	EACH
218	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	1,675.000	m

CALL ORDER : 215  
 LETTING DATE :

CONTRACT ID : R -28017-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 STORM SEWER CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	36.000	MOS
3	105-07577 CELLULAR SERVICE	36.000	MOS
4	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	584.000	m2
11	202-05545 REGULATED MATERIALS, DISPOSE, C	3,050.000	m3
12	202-05550 REGULATED MATERIALS, REMOVE, C	3,050.000	m3
13	202-05555 REGULATED MATERIALS, TRANSPORT, C	3,050.000	m3
14	202-07602 TESTING FOR WASTE, B	4.000	EACH
15	202-07603 TESTING FOR WASTE, C	450.000	EACH
16	202-08429 REGULATED MATERIALS, DISPOSE, B	500.000	L
17	202-08430 REGULATED MATERIALS, REMOVE, B	500.000	L
18	202-08431 REGULATED MATERIALS, TRANSPORT, B	500.000	L
19	202-74070 OVERHEAD SIGN STRUCTURE, CABLE SPAN, REMOVE	1.000	EACH
20	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
21	203-02000 EXCAVATION, COMMON	37,908.000	m3
22	205-03371 SEDIMENT REMOVE	500.000	m3
23	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	230.000	Mg
24	205-06933 TEMPORARY DITCH INLET PROTECTION	35.000	EACH
25	205-06936 TEMPORARY SEDIMENT TRAP	43.500	Mg
26	205-06937 TEMPORARY SILT FENCE	100.000	m
27	207-08263 SUBGRADE TREATMENT, TYPE IA	66,699.000	m2
28	210-07095 TEMPORARY	LUMP	LUMP
29	210-07562 TEMPORARY	1,236.000	m
30	211-07454 STRUCTURE BACKFILL	32,030.000	m3
31	213-52830 FLOWABLE MORTAR	5,704.000	m3
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	9,847.500	Mg
33	304-07489 HMA PATCHING, TYPE A	338.000	Mg
34	306-08034 MILLING, ASPHALT, 38 mm	9,530.400	m2
35	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
36	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	3,929.000	Mg
37	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	6,535.000	Mg
38	401-07418 QC/QA-HMA, 3, 76, BASE, 25.0 MM	19,047.000	Mg
39	401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm	9,477.000	Mg
40	402-07432 HMA SURFACE, TYPE A	25.000	Mg
41	402-07433 HMA SURFACE, TYPE B	1,370.000	Mg
42	402-07434 HMA SURFACE, TYPE C	736.000	Mg
43	402-07440 HMA BASE, TYPE A	2,000.000	Mg
44	402-07442 HMA BASE, TYPE C	2,208.000	Mg
45	402-07453 HMA FOR TEMPORARY PAVEMENT	7,591.000	Mg
46	406-05520 ASPHALT FOR TACK COAT	69.800	Mg
47	603-04124 FENCE GATE, CHAIN LINK, 1200 mm X 1.2 m	1.000	EACH
48	603-06045 FENCE, CHAIN LINK, 1220 mm	10.700	m

CALL ORDER : 215  
 LETTING DATE :

CONTRACT ID : R -28017-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 STORM SEWER CONSTRUCTION			
49	604-07897 CURB RAMP, CONCRETE, C	10.200	m2
50	604-07900 CURB RAMP, CONCRETE, F	555.100	m2
51	604-07901 CURB RAMP, CONCRETE, G	112.600	m2
52	604-07902 CURB RAMP, CONCRETE, H	150.000	m2
53	604-44251 STEPS, CONCRETE	30.800	m3
54	604-91531 SIDEWALK, CONCRETE, 100 mm	8,377.000	m2
55	605-06120 CURB, CONCRETE	1,087.000	m
56	605-06140 CURB AND GUTTER, CONCRETE	7.000	m
57	605-06150 CURB AND GUTTER, C, CONCRETE	5,605.600	m
58	610-07486 HMA FOR APPROACHES, TYPE A	505.300	Mg
59	610-07487 HMA FOR APPROACHES, TYPE B	7,538.000	Mg
60	610-08446 PCCP FOR APPROACHES, 150 mm	4,566.100	m2
61	611-06497 MAILBOX ASSEMBLY, SINGLE	13.000	EACH
62	615-06490 RIGHT OF WAY MARKER	60.000	EACH
63	615-06496 PARKING BARRIER	30.000	EACH
64	615-06505 MONUMENT, B	41.000	EACH
65	616-02320 GEOTEXTILES	50.900	m2
66	616-06405 RIPRAP, REVETMENT	23.800	Mg
67	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	13.000	EACH
68	621-06545 FERTILIZER	2.400	Mg
69	621-06553 SEED MIXTURE, R	461.000	kg
70	621-06557 SEED MIXTURE, T	265.200	kg
71	621-06560 MULCHED SEEDING, U	2,504.000	m2
72	621-06565 MULCHING MATERIAL	13.300	Mg
73	621-06567 WATER	362.500	kL
74	621-06575 SODDING, NURSERY	20,112.300	m2
75	714-04802 CONCRETE MODULAR BLOCK WALL	389.000	m2
76	714-07539 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 2400 mm X 600 mm	27.500	m
77	714-44240 CONCRETE, A, STRUCTURES	26.000	m3
78	715-01378 PIPE, PVC, SDR-35, 254 mm	3.000	m
79	715-01902 WATER SERVICE LINE, 50 mm	21.000	m
80	715-01905 WATER SERVICE LINE, 75 mm	33.000	m
81	715-02919 GATE VALVE, 50 mm	2.000	EACH
82	715-02961 WATER MAIN, 400 mm	231.000	m
83	715-04612 PIPE	21.000	m
84	715-04612 PIPE	116.000	m
85	715-04612 PIPE	112.000	m
86	715-04612 PIPE	3.000	m
87	715-04612 PIPE	112.000	m
88	715-04612 PIPE	88.000	m
89	715-04612 PIPE	22.000	m
90	715-04612 PIPE	12.000	m
91	715-04612 PIPE	5.000	m
92	715-04612 PIPE	9.000	m
93	715-04612 PIPE	70.000	m
94	715-04612 PIPE	19.000	m
95	715-04612 PIPE	5.000	m
96	715-04612 PIPE	4.000	m

CALL ORDER : 215  
 LETTING DATE :

CONTRACT ID : R -28017-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 STORM SEWER CONSTRUCTION			
97	715-04612 PIPE	7.000	m
98	715-04612 PIPE	73.000	m
99	715-04855 PIPE END SECTION, 1050 mm	3.000	EACH
100	715-05019 PIPE, TYPE 1, CIRCULAR, 900 mm	21.000	m
101	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	1,722.800	m
102	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	9,795.000	m
103	715-05049 PIPE, TYPE 4, CIRCULAR, 200 mm	150.000	m
104	715-05051 PIPE, TYPE 4, CIRCULAR, 250 mm	50.000	m
105	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	183.000	m
106	715-05061 WATER SERVICE LINE, 150 mm	1.000	m
107	715-05115 PIPE, TYPE 1, CIRCULAR, 150 mm	50.000	m
108	715-05116 PIPE, TYPE 1, CIRCULAR, 200 mm	50.000	m
109	715-05117 PIPE, TYPE 1, CIRCULAR, 250 mm	50.000	m
110	715-05127 PIPE, TYPE 1, CIRCULAR, 1050 mm	29.000	m
111	715-05147 PIPE, TYPE 2, CIRCULAR, 200 mm	5.000	m
112	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	1,769.700	m
113	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	1,052.000	m
114	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	406.000	m
115	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	402.000	m
116	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	451.000	m
117	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	793.000	m
118	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	1,910.000	m
119	715-05168 PIPE, TYPE 3, CIRCULAR, 300 mm	5.000	m
120	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	332.000	m
121	715-05171 PIPE, TYPE 3, CIRCULAR, 450 mm	131.500	m
122	715-05177 PIPE, TYPE 3, CIRCULAR, 900 mm	122.500	m
123	715-05203 PIPE, TYPE 4, CIRCULAR, 100 mm	7.000	m
124	715-05335 PIPE, TYPE 2, DEFORMED, MIN. AREA 0.47 m2	65.000	m
125	715-05338 PIPE, TYPE 2, DEFORMED, MIN. AREA 0.68 m2	118.000	m
126	715-06692 LATERAL	1,612.000	m
127	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	3,648.000	Mg
128	715-46000 PIPE END SECTION, 300 mm	1.000	EACH
129	715-46005 PIPE END SECTION, 375 mm	35.000	EACH
130	715-46010 PIPE END SECTION, 450 mm	10.000	EACH
131	715-46040 PIPE END SECTION, 900 mm	3.000	EACH
132	715-92525 WATER MAIN, 250 mm	49.000	m
133	715-93912 WATER MAIN, 150 mm	3,977.000	m
134	715-93913 WATER MAIN, 200 mm	464.000	m
135	715-94456 PIPE, PVC, SDR-35, 381 mm	5.000	m
136	715-94456 PIPE, PVC, SDR-35, 381 mm	3.000	m
137	715-94456 PIPE, PVC, SDR-35, 381 mm	5.000	m
138	715-94457 PIPE, PVC, SDR 35, 200 mm	82.000	m
139	715-94457 PIPE, PVC, SDR 35, 200 mm	154.000	m
140	715-96040 PIPE, PVC, SDR 35, 300 mm	325.000	m
141	715-96040 PIPE, PVC, SDR 35, 300 mm	49.000	m
142	715-96040 PIPE, PVC, SDR 35, 300 mm	135.000	m
143	715-96629 WATER SERVICE LINE, 1 IN.	55.000	m
144	715-97691 GRATED BOX END SECTION, I, 3:1, 900 mm	2.000	EACH

CALL ORDER : 215  
 LETTING DATE :

CONTRACT ID : R -28017-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 STORM SEWER CONSTRUCTION			
145	715-98165 WATERMAIN, 300 mm	113.000	m
146	716-02965 PIPE CASING, 750 mm, JACK AND BORE	19.500	m
147	716-04832 PIPE CASING,	40.000	m
148	716-04832 PIPE CASING,	72.000	m
149	716-04832 PIPE CASING,	33.000	m
150	718-06528 OUTLET PROTECTOR, 1	30.000	EACH
151	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
152	718-52610 AGGREGATE FOR UNDERDRAINS	2,116.000	m3
153	718-99153 GEOTEXTILES FOR UNDERDRAIN	21,252.000	m2
154	720-03194 MANHOLE	5.000	EACH
155	720-03194 MANHOLE	4.000	EACH
156	720-03194 MANHOLE	5.000	EACH
157	720-03194 MANHOLE	2.000	EACH
158	720-03194 MANHOLE	1.000	EACH
159	720-03194 MANHOLE	2.000	EACH
160	720-03194 MANHOLE	1.000	EACH
161	720-03194 MANHOLE	1.000	EACH
162	720-04721 MANHOLE, K	2.000	EACH
163	720-44000 CASTING, ADJUST TO GRADE	104.000	EACH
164	720-44296 CAP INLET	1.000	EACH
165	720-45035 INLET, F7	1.000	EACH
166	720-45080 INLET, S14	4.000	EACH
167	720-45250 CATCH BASIN, K10	1.000	EACH
168	720-45275 PIPE CATCH BASIN, 600 mm	53.000	EACH
169	720-45410 MANHOLE, C4	83.000	EACH
170	720-93411 INLET, C15, MODIFIED	2.000	EACH
171	720-94612 MANHOLE, K4	48.000	EACH
172	720-95422 MANHOLE, J4	49.000	EACH
173	720-96999 FIRE HYDRANT ASSEMBLY	31.000	EACH
174	720-98174 INLET, B15	200.000	EACH
175	720-98555 INLET, C15	37.000	EACH
176	731-93946 WALL ERECTION	389.000	m2
177	731-93947 LEVELING PAD, CONCRETE	320.000	m
178	732-02185 WATER SERVICE LINE, 37.5 mm	14.000	m
179	732-02388 WATER MAIN	1.000	EACH
180	732-02388 WATER MAIN	1.000	EACH
181	732-02388 WATER MAIN	1.000	EACH
182	732-02388 WATER MAIN	1.000	EACH
183	732-02388 WATER MAIN	1.000	EACH
184	732-02388 WATER MAIN	1.000	EACH
185	732-02388 WATER MAIN	1.000	EACH
186	732-02388 WATER MAIN	1.000	EACH
187	732-02388 WATER MAIN	1.000	EACH
188	732-02388 WATER MAIN	1.000	EACH
189	732-02388 WATER MAIN	1.000	EACH
190	732-02388 WATER MAIN	1.000	EACH
191	732-02388 WATER MAIN	1.000	EACH
192	732-02388 WATER MAIN	1.000	EACH

CALL ORDER : 215  
 LETTING DATE :

CONTRACT ID : R -28017-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 STORM SEWER CONSTRUCTION			
193	732-02388 WATER MAIN	1.000	EACH
194	732-02388 WATER MAIN	1.000	EACH
195	732-02388 WATER MAIN	1.000	EACH
196	732-02388 WATER MAIN	1.000	EACH
197	732-02388 WATER MAIN	1.000	EACH
198	732-02388 WATER MAIN	1.000	EACH
199	732-02388 WATER MAIN	1.000	EACH
200	732-02388 WATER MAIN	1.000	EACH
201	732-02388 WATER MAIN	1.000	EACH
202	732-02388 WATER MAIN	1.000	EACH
203	732-02388 WATER MAIN	1.000	EACH
204	732-02388 WATER MAIN	1.000	EACH
205	732-02388 WATER MAIN	1.000	EACH
206	732-02388 WATER MAIN	1.000	EACH
207	732-02388 WATER MAIN	1.000	EACH
208	732-02388 WATER MAIN	1.000	EACH
209	732-02388 WATER MAIN	1.000	EACH
210	732-02388 WATER MAIN	1.000	EACH
211	732-02388 WATER MAIN	1.000	EACH
212	732-02388 WATER MAIN	1.000	EACH
213	732-02388 WATER MAIN	1.000	EACH
214	732-02388 WATER MAIN	1.000	EACH
215	732-02388 WATER MAIN	1.000	EACH
216	732-02388 WATER MAIN	1.000	EACH
217	732-02388 WATER MAIN	1.000	EACH
218	732-02388 WATER MAIN	1.000	EACH
219	732-02388 WATER MAIN	1.000	EACH
220	732-02388 WATER MAIN	1.000	EACH
221	732-02388 WATER MAIN	1.000	EACH
222	732-02388 WATER MAIN	1.000	EACH
223	732-02388 WATER MAIN	1.000	EACH
224	732-02388 WATER MAIN	1.000	EACH
225	732-02388 WATER MAIN	1.000	EACH
226	732-02388 WATER MAIN	1.000	EACH
227	732-02388 WATER MAIN	1.000	EACH
228	732-02388 WATER MAIN	1.000	EACH
229	732-02388 WATER MAIN	1.000	EACH
230	732-02388 WATER MAIN	1.000	EACH
231	732-02388 WATER MAIN	1.000	EACH
232	732-02388 WATER MAIN	1.000	EACH
233	732-02388 WATER MAIN	1.000	EACH
234	732-02388 WATER MAIN	1.000	EACH
235	732-04836 GATE VALVE	4.000	EACH
236	732-04836 GATE VALVE	62.000	EACH
237	732-04836 GATE VALVE	7.000	EACH
238	732-04836 GATE VALVE	5.000	EACH
239	732-04836 GATE VALVE	3.000	EACH
240	732-04836 GATE VALVE	6.000	EACH



CALL ORDER : 215  
 LETTING DATE :

CONTRACT ID : R -28017-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 STORM SEWER CONSTRUCTION			
241	732-04987 CONNECTION	2.000	EACH
242	732-04987 CONNECTION	6.000	EACH
243	732-04994 METER	304.000	EACH
244	732-07653 COARSE AGGREGATE, NO. 8	52.000	Mg
245	732-90573 WATER SERVICE LINE, 18.75 mm	2,345.000	m
246	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	10.000	EACH
247	801-04308 ROAD CLOSURE SIGN ASSEMBLY	58.000	EACH
248	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	5,000.000	m
249	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	100.000	m
250	801-06625 DETOUR ROUTE MARKER ASSEMBLY	56.000	EACH
251	801-06640 CONSTRUCTION SIGN, A	107.000	EACH
252	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
253	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
254	801-07118 BARRICADE, III-A	309.600	m
255	801-07119 BARRICADE, III-B	133.200	m
256	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	936.000	m
257	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	100.561	m2
258	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	66.690	m2
259	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	3.260	m2
260	804-93726 DELINEATOR	30.000	EACH
261	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	14.000	EACH
262	805-01842 HANDHOLE, SIGNAL	12.000	EACH
263	805-01879 SIGNAL SERVICE	4.000	EACH
264	805-01893 MAINTAINING TRAFFIC SIGNAL	LUMP	LUMP
265	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
266	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	3,388.000	m
267	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	595.000	m
268	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	3.000	EACH
269	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
270	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm RED	8.000	EACH
271	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	24.000	EACH
272	805-78415 SPAN, CATENARY, AND TETHER	13.000	EACH
273	805-78420 DISCONNECT HANGER	13.000	EACH
274	805-78467 SIGNAL CABLE, 3C 8GA.	65.000	m
275	805-78485 SIGNAL CABLE, 5C 14GA.	764.000	m
276	805-78490 SIGNAL CABLE, 7C 14GA.	1,132.000	m
277	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,128.000	m
278	805-78785 SIGNAL DETECTOR HOUSING	22.000	EACH
279	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,188.000	m
280	805-78925 CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
281	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	14.000	EACH
282	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	12.000	EACH
283	805-96121 PEDESTRIAN PUSH BUTTON AND SIGN	12.000	EACH
284	808-04298 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (R X R)	4.000	EACH
285	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	4,053.000	m
286	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	267.000	m
287	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	8,831.000	m
288	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	367.000	m

CALL ORDER : 215  
 LETTING DATE :

CONTRACT ID : R -28017-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	STORM SEWER CONSTRUCTION		
289 808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm	478.000	m
290 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	26.000	EACH
291 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	22.000	EACH
292 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	250.000	EACH
293 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	320.000	EACH

CALL ORDER : 265  
 LETTING DATE :

CONTRACT ID : R -28274-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	18.000	MOS
3	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	11,200.000	SYS
11	202-02245 TREE, 6 IN., REMOVE	2.000	EACH
12	202-02250 TREE, 10 IN., REMOVE	1.000	EACH
13	202-02255 TREE, 18 IN., REMOVE	4.000	EACH
14	202-02260 TREE, 30 IN., REMOVE	1.000	EACH
15	202-02278 CURB, CONCRETE, REMOVE	4,600.000	LFT
16	202-04089 SIGN, SHEET, REMOVE	35.000	EACH
17	202-06580 CONTAMINATED SOIL, REMOVE	1.000	CYS
18	202-52710 SIDEWALK, CONCRETE, REMOVE	3,120.000	SYS
19	202-74070 OVERHEAD SIGN STRUCTURE, CABLE SPAN, REMOVE	1.000	EACH
20	202-91010 TREE, 24 IN., REMOVE	2.000	EACH
21	202-91385 INLET, REMOVE	20.000	EACH
22	202-93047 MANHOLE, REMOVE	7.000	EACH
23	202-96133 PIPE, REMOVE	400.000	LFT
24	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
25	202-96632 TRAFFIC SIGNALS AND EQUIPMENT, REMOVE	1.000	EACH
26	203-02000 EXCAVATION, COMMON	13,307.000	CYS
27	205-06932 TEMPORARY CHECK DAM, STRAW BALES	24.000	LFT
28	205-06933 TEMPORARY DITCH INLET PROTECTION	4.000	EACH
29	205-06937 TEMPORARY SILT FENCE	105.000	LFT
30	207-08268 SUBGRADE TREATMENT, TYPE IV	16,900.000	SYS
31	210-04181 BICYCLE RACK	2.000	EACH
32	210-05106 CONCRETE	84.000	EACH
33	210-05106 CONCRETE	84.000	EACH
34	210-05106 CONCRETE	8.000	EACH
35	210-08592 GRANITE	51.000	EACH
36	211-07454 STRUCTURE BACKFILL	2,805.000	CYS
37	213-08058 FLOWABLE BACKFILL	2,975.000	CYS
38	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,434.000	TON
39	304-07489 HMA PATCHING, TYPE A	910.000	TON
40	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	1,117.000	TON
41	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	1,862.000	TON
42	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	6,322.000	TON
43	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	1,792.000	TON
44	402-07453 HMA FOR TEMPORARY PAVEMENT	405.000	TON
45	406-05520 ASPHALT FOR TACK COAT	13.000	TON
46	603-06065 FENCE, CHAIN LINK, RESET	90.000	LFT
47	604-01920 CONCRETE PAVERS	450.000	SYS
48	604-04439 TEXTURED CONCRETE PAVEMENT	280.000	SYS

CALL ORDER : 265  
 LETTING DATE :

CONTRACT ID : R -28274-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
49	604-06070 SIDEWALK, CONCRETE	4,093.000	SYS
50	604-06367 JOINT MATERIAL	3,100.000	LFT
51	604-07894 CURB RAMP, CONCRETE, A	77.000	SYS
52	604-07896 CURB RAMP, CONCRETE, B	22.000	SYS
53	604-07898 CURB RAMP, CONCRETE, D	14.000	SYS
54	604-07899 CURB RAMP, CONCRETE, E	11.000	SYS
55	604-07901 CURB RAMP, CONCRETE, G	172.000	SYS
56	604-07902 CURB RAMP, CONCRETE, H	13.000	SYS
57	605-06140 CURB AND GUTTER, CONCRETE	5,860.000	LFT
58	610-07486 HMA FOR APPROACHES, TYPE A	170.000	TON
59	610-07712 PCCP FOR APPROACHES, 6 IN.	2,047.000	SYS
60	615-06496 PARKING BARRIER	73.000	EACH
61	616-05688 RIPRAP, CLASS 1	12.000	TON
62	621-06574 SODDING	7,000.000	SYS
63	621-93350 TAPPING TEE AND VALVE ASSEMBLY, 8 IN.	1.000	EACH
64	621-94463 TAPPING TEE AND VALVE ASSEMBLY, 4 IN.	3.000	EACH
65	621-94464 TAPPING TEE AND VALVE ASSEMBLY, 6 IN.	5.000	EACH
66	621-94771 GATE VALVE WITH ROADWAY BOX, 6 IN.	4.000	EACH
67	621-94772 GATE VALVE WITH ROADWAY BOX, 4 IN.	3.000	EACH
68	621-94780 WATER SERVICE CONNECTION	45.000	EACH
69	621-98038 MULCH, HARDWOOD SHREDDED BARK	102.000	CYS
70	622-04648 TREE GRATE	31.000	EACH
71	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	82.000	EACH
72	714-44240 CONCRETE, A, STRUCTURES	2.000	CYS
73	715-01970 RETAINER GLAND, DUCTILE IRON, 8 IN.	130.000	EACH
74	715-02144 ELBOW, DUCTILE IRON, 6 IN., 45 DEGREE	2.000	EACH
75	715-02145 ELBOW, DUCTILE IRON, 8 IN., 45 DEGREE	7.000	EACH
76	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	650.000	LFT
77	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	5,310.000	LFT
78	715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN.	120.000	LFT
79	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	1,750.000	LFT
80	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	380.000	LFT
81	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	1,330.000	LFT
82	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	960.000	LFT
83	715-08555 RETAINER GLAND	20.000	EACH
84	715-08555 RETAINER GLAND	30.000	EACH
85	715-26728 GRATED BOX END SECTION, II, 4:1, 12 IN.	2.000	EACH
86	715-46015 PIPE END SECTION, 21 IN.	1.000	EACH
87	715-91738 WATER MAIN, DUCTILE IRON, 6 IN.	200.000	LFT
88	715-91739 WATER MAIN, DUCTILE IRON, 8 IN.	2,360.000	LFT
89	715-98265 WATER MAIN, DUCTILE IRON, 4 IN.	110.000	LFT
90	718-52610 AGGREGATE FOR UNDERDRAINS	421.000	CYS
91	719-93351 TEE, RESTRAINED, 8 IN.	1.000	EACH
92	719-96684 ELL, RESTRAINED, 8 IN., 90 DEG.	1.000	EACH
93	719-96944 TEE, 8 IN. X 8 IN. X 6 IN.	4.000	EACH
94	719-96945 TEE, 8 IN. X 8 IN. X 4 IN.	3.000	EACH
95	719-96946 REDUCER, 8 IN. X 6 IN.	1.000	EACH
96	720-44000 CASTING, ADJUST TO GRADE	16.000	EACH

CALL ORDER : 265  
 LETTING DATE :

CONTRACT ID : R -28274-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
97	720-44080 CASTING, 15, FURNISH AND ADJUST TO GRADE	1.000	EACH
98	720-45030 INLET, E7	3.000	EACH
99	720-45035 INLET, F7	2.000	EACH
100	720-45260 PIPE CATCH BASIN, 12 IN.	6.000	EACH
101	720-45410 MANHOLE, C4	31.000	EACH
102	720-96999 FIRE HYDRANT ASSEMBLY	7.000	EACH
103	720-98174 INLET, B15	32.000	EACH
104	720-98555 INLET, C15	22.000	EACH
105	732-02532 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 8 IN.	2.000	EACH
106	732-03072 TEE	5.000	EACH
107	732-04846 ELL	3.000	EACH
108	732-97009 FIRE HYDRANT ASSEMBLY, REMOVE	7.000	EACH
109	801-04308 ROAD CLOSURE SIGN ASSEMBLY	11.000	EACH
110	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	13,000.000	LFT
111	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12,000.000	LFT
112	801-06625 DETOUR ROUTE MARKER ASSEMBLY	43.000	EACH
113	801-06640 CONSTRUCTION SIGN, A	60.000	EACH
114	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
115	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
116	801-07119 BARRICADE, III-B	140.000	LFT
117	801-08388 TEMPORARY TRAFFIC BARRIER	3,000.000	LFT
118	801-08388 TEMPORARY TRAFFIC BARRIER	6,000.000	LFT
119	801-94295 SIGNAL HEAD, RELOCATE	4.000	EACH
120	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	456.000	LFT
121	802-76020 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.080 IN. THICKNESS	140.000	SFT
122	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	120.000	SFT
123	802-76125 SPAN OVERHEAD SIGN STRUCTURE, CABLESPAN	1.000	EACH
124	802-91084 OVERHEAD PANEL SIGN, REMOVE AND REINSTALL	4.000	EACH
125	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	1.000	EACH
126	805-01842 HANDHOLE, SIGNAL	5.000	EACH
127	805-02069 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM	3.000	EACH
128	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	1.000	EACH
129	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	8.000	EACH
130	805-02445 CONTROLLER CABINET, P1	2.000	EACH
131	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	3,352.000	LFT
132	805-02618 WIRE, NO. 2 COPPER, 3 1C	1,660.000	LFT
133	805-04593 CONDUIT, STEEL, GALVANIZED, 1.25 IN.	325.000	LFT
134	805-04973 CONDUIT	5,087.000	LFT
135	805-04973 CONDUIT	3,310.000	LFT
136	805-05698 SIGNAL SUPPORT FOUNDATION, 2 FT. 6 IN. X 2FT. 6 IN. X 7 FT.	3.000	EACH
137	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	452.000	LFT
138	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	1.000	EACH
139	805-08093 POLE	8.000	EACH
140	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
141	805-78445 SIGNAL SERVICE	1.000	EACH
142	805-78480 SIGNAL CABLE, 3C 14GA.	398.000	LFT
143	805-78485 SIGNAL CABLE, 5C 14GA.	618.000	LFT
144	805-78490 SIGNAL CABLE, 7C 14GA.	421.000	LFT

CALL ORDER : 265  
 LETTING DATE :

CONTRACT ID : R -28274-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001      ENHANCEMENT, STREETScape				
145	805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	556.000	LFT
146	805-78785	SIGNAL DETECTOR HOUSING	5.000	EACH
147	805-78900	PEDESTAL FOUNDATION, A	1.000	EACH
148	805-78925	CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
149	805-86843	WIRE, NO. 4 COPPER, 1C	20,600.000	LFT
150	805-86898	CONDUIT, STEEL, GALVANIZED, .75 IN.	504.000	LFT
151	805-90005	SIGNAL PEDESTAL, 10 FT.	1.000	EACH
152	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	3.000	EACH
153	805-95888	WIRE, NO. 8 COPPER, 1C	22,665.000	LFT
154	805-95889	WIRE, NO. 10 COPPER, 1C	7,190.000	LFT
155	805-95890	WIRE, NO. 12 COPPER, 1/C	200.000	LFT
156	805-96014	SAW CUT, FULL DEPTH	5,460.000	LFT
157	805-96121	PEDESTRIAN PUSH BUTTON AND SIGN	4.000	EACH
158	805-99338	WIRE, AWG, NO. 6 COPPER, GROUND, 1/C	147.000	LFT
159	807-01889	LIGHT POLE, ORNAMENTAL, 12 FT., E.M.H., WITH LUMINAIRE	50.000	EACH
160	807-02817	CONCRETE FOUNDATION WITH GROUNDING, 24 IN. X 24 IN. X 72 IN.	50.000	EACH
161	807-03954	ELECTRICAL PANEL, MAIN	2.000	EACH
162	807-03968	CONDUIT, PVC, 1 IN., SCHEDULE 80, FOR ELECTRIC	3,445.000	LFT
163	807-04651	WIRE	1,750.000	LFT
164	807-04651	WIRE	14,000.000	LFT
165	807-04651	WIRE	96.000	LFT
166	807-04651	WIRE	13,700.000	LFT
167	807-05073	JUNCTION BOX	84.000	EACH
168	807-05073	JUNCTION BOX	84.000	EACH
169	807-86805	SERVICE POINT, I	2.000	EACH
170	807-86955	CABLE DUCT MARKER	16.000	EACH
171	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	400.000	LFT
172	808-75215	LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	400.000	LFT
173	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	600.000	LFT
174	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,100.000	LFT
175	808-75278	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	160.000	LFT
176	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	220.000	LFT
177	808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,110.000	LFT
178	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	3.000	EACH
179	808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000	EACH
180	808-90909	CAP LINE	19.000	EACH

CALL ORDER : 285  
 LETTING DATE :

CONTRACT ID : R -28305-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN INSTALLATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	27.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	6.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	162.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	1,174.000	SYS
13	202-02241 GUARDRAIL, REMOVE	420.000	LFT
14	202-02245 TREE, 6 IN., REMOVE	12.000	EACH
15	202-02250 TREE, 10 IN., REMOVE	13.000	EACH
16	202-02255 TREE, 18 IN., REMOVE	14.000	EACH
17	202-02260 TREE, 30 IN., REMOVE	5.000	EACH
18	202-02264 TREE, 42 IN., REMOVE	2.000	EACH
19	202-02265 TREE, 48 IN., REMOVE	1.000	EACH
20	202-02271 HEADWALL, REMOVE	1.000	EACH
21	202-02273 CENTER CURB, CONCRETE, REMOVE	88.000	SYS
22	202-02278 CURB, CONCRETE, REMOVE	19,315.000	LFT
23	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
24	202-06541 REMOVE	1.000	EACH
25	202-06542 RELOCATE	27.000	EACH
26	202-06542 RELOCATE	10.000	EACH
27	202-52710 SIDEWALK, CONCRETE, REMOVE	6,705.000	SYS
28	202-74035 SIGN, REMOVE	208.000	EACH
29	202-91010 TREE, 24 IN., REMOVE	3.000	EACH
30	202-91011 TREE, 36 IN., REMOVE	2.000	EACH
31	202-91385 INLET, REMOVE	30.000	EACH
32	202-93091 TREE, 15 IN., REMOVE	5.000	EACH
33	202-93898 TREE, 12 IN., REMOVE	10.000	EACH
34	202-95579 SERVICE POINT, REMOVE	1.000	EACH
35	202-96133 PIPE, REMOVE	2,416.000	LFT
36	203-02000 EXCAVATION, COMMON	5,337.000	CYS
37	203-02070 BORROW	5,626.000	CYS
38	203-91878 LINEAR DITCH GRADING	1,422.000	LFT
39	205-02459 EROSION CONTROL	LUMP	LUMP
40	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	11.000	TON
41	205-06933 TEMPORARY DITCH INLET PROTECTION	24.000	EACH
42	205-06937 TEMPORARY SILT FENCE	4,480.000	LFT
43	207-08267 SUBGRADE TREATMENT, TYPE IIIA	7,605.000	SYS
44	210-06547 PAINT	12.000	EACH
45	210-06547 PAINT	8.000	EACH
46	211-07454 STRUCTURE BACKFILL	4,995.000	CYS
47	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,209.000	TON
48	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	280.000	TON

CALL ORDER : 285  
 LETTING DATE :

CONTRACT ID : R -28305-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN INSTALLATION			
49	306-08432 MILLING, APPROACH	3,819.000	SYS
50	306-08595 MILLING ASPHALT, 3 1/2 IN.	92,496.000	SYS
51	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	7,631.000	TON
52	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	10,175.000	TON
53	402-07433 HMA SURFACE, TYPE B	49.000	TON
54	402-07438 HMA INTERMEDIATE, TYPE B	65.000	TON
55	402-07441 HMA BASE, TYPE B	195.000	TON
56	402-07452 HMA, TYPE C, WEDGE AND LEVEL	2,486.000	TON
57	406-05520 ASPHALT FOR TACK COAT	58.000	TON
58	601-01701 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 2	2.000	EACH
59	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
60	601-95434 HANDRAIL, STEEL PIPE, 1.5 IN.	717.000	LFT
61	601-96063 HANDRAIL, ALUMINUM, SCHEDULE 40, 2 IN. DIA. X 3 FT. 6 IN.	98.500	LFT
62	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	1.000	EACH
63	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	713.000	LFT
64	604-06070 SIDEWALK, CONCRETE	181.000	SYS
65	604-06070 SIDEWALK, CONCRETE	105.000	SYS
66	604-07894 CURB RAMP, CONCRETE, A	29.000	SYS
67	604-07896 CURB RAMP, CONCRETE, B	11.000	SYS
68	604-07897 CURB RAMP, CONCRETE, C	3.000	SYS
69	604-07898 CURB RAMP, CONCRETE, D	101.000	SYS
70	604-07900 CURB RAMP, CONCRETE, F	82.000	SYS
71	604-07901 CURB RAMP, CONCRETE, G	218.000	SYS
72	604-07902 CURB RAMP, CONCRETE, H	539.000	SYS
73	604-91531 SIDEWALK, CONCRETE, 4 IN.	12,361.000	SYS
74	605-06120 CURB, CONCRETE	93.000	LFT
75	605-06140 CURB AND GUTTER, CONCRETE	21,045.000	LFT
76	610-07486 HMA FOR APPROACHES, TYPE A	48.000	TON
77	610-07487 HMA FOR APPROACHES, TYPE B	817.000	TON
78	610-07712 PCCP FOR APPROACHES, 6 IN.	6,301.000	SYS
79	611-03671 TRASH RECEPTACLE	3.000	EACH
80	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	59.000	EACH
81	616-02320 GEOTEXTILES	212.000	SYS
82	616-06405 RIPRAP, REVETMENT	144.000	TON
83	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
84	621-06545 FERTILIZER	3.030	TON
85	621-06554 SEED MIXTURE, U	1,000.000	LBS
86	621-06565 MULCHING MATERIAL	13.000	TON
87	621-06567 WATER	469.000	KGAL
88	621-06575 SODDING, NURSERY	13,020.000	SYS
89	621-98038 MULCH, HARDWOOD SHREDDED BARK	2.000	CYS
90	622-03948 PLANTER	5.000	EACH
91	622-05605 PLANT, ANNUAL	60.000	EACH
92	622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN.	18.000	EACH
93	622-05647 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 120 IN.	5.000	EACH
94	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	213.000	EACH
95	622-05654 PLANT, PERENNIAL	14.000	EACH
96	622-05654 PLANT, PERENNIAL	12.000	EACH



CALL ORDER : 285  
 LETTING DATE :

CONTRACT ID : R -28305-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN INSTALLATION			
97	711-05395 REPLACE	6.000	EACH
98	712-03812 BENCH	6.000	EACH
99	714-07665 RETAINING WALL	LUMP	LUMP
100	715-01354 CLEAN EXISTING PIPE	514.000	LFT
101	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	1,233.000	LFT
102	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	1,419.000	LFT
103	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	2,103.000	LFT
104	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	2,308.000	LFT
105	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	1,207.000	LFT
106	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	1,882.000	LFT
107	715-05155 PIPE, TYPE 2, CIRCULAR, 27 IN.	692.000	LFT
108	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	724.000	LFT
109	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	48.000	LFT
110	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	108.000	LFT
111	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN.	24.000	LFT
112	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN.	15.000	LFT
113	715-05177 PIPE, TYPE 3, CIRCULAR, 36 IN.	56.000	LFT
114	715-05331 PIPE, TYPE 2, DEFORMED, MIN. AREA 3.3 SFT.	50.000	LFT
115	715-08307 HMA FOR STRUCTURE INSTALLATION, TYPE D	2,176.000	TON
116	715-08560 GRATED BOX END SECTION, II, 3:1, 15 IN.	2.000	EACH
117	715-26729 GRATED BOX END SECTION, II, 6:1, 15 IN.	2.000	EACH
118	715-26770 GRATED BOX END SECTION, I, 3:1, 24 IN.	1.000	EACH
119	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
120	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
121	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
122	715-46025 PIPE END SECTION, 27 IN.	1.000	EACH
123	715-46030 PIPE END SECTION, 30 IN.	1.000	EACH
124	715-46040 PIPE END SECTION, 36 IN.	1.000	EACH
125	715-94976 GRATED BOX END SECTION, II, 3:1, 36 IN.	1.000	EACH
126	715-97751 GRATED BOX END SECTION, II, 6:1, 12 IN.	2.000	EACH
127	715-99044 GRATED BOX END SECTION, II, 6:1, 18 IN.	5.000	EACH
128	720-01987 CATCH BASIN, A10	1.000	EACH
129	720-02367 MANHOLE, J10	1.000	EACH
130	720-44000 CASTING, ADJUST TO GRADE	67.000	EACH
131	720-44015 CASTING, 2, FURNISH AND ADJUST TO GRADE	3.000	EACH
132	720-44040 CASTING, 7, FURNISH AND ADJUST TO GRADE	1.000	EACH
133	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	2.000	EACH
134	720-45030 INLET, E7	4.000	EACH
135	720-45035 INLET, F7	9.000	EACH
136	720-45240 CATCH BASIN, J10	9.000	EACH
137	720-45340 CATCH BASIN, J10, MODIFIED	1.000	EACH
138	720-45415 MANHOLE, D4	3.000	EACH
139	720-45416 MANHOLE, E4	1.000	EACH
140	720-90129 MANHOLE, J2	1.000	EACH
141	720-91917 INLET, A10	1.000	EACH
142	720-92025 MANHOLE, D2	3.000	EACH
143	720-98174 INLET, B15	36.000	EACH
144	720-98555 INLET, C15	38.000	EACH

CALL ORDER : 285  
 LETTING DATE :

CONTRACT ID : R -28305-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN INSTALLATION			
145	730-26732 GRATED BOX END SECTION, II, 4:1, 36 IN.	3.000	EACH
146	732-02388 WATER MAIN	1.000	EACH
147	732-02388 WATER MAIN	3.000	EACH
148	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
149	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	45,000.000	LFT
150	801-06640 CONSTRUCTION SIGN, A	99.000	EACH
151	801-06645 CONSTRUCTION SIGN, B	32.000	EACH
152	801-06710 FLASHING ARROW SIGN	800.000	DAY
153	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
154	801-07119 BARRICADE, III-B	84.000	LFT
155	802-04314 SIGN	1.000	EACH
156	802-04314 SIGN	1.000	EACH
157	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	1,478.000	LFT
158	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	205.000	SFT
159	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	860.000	SFT
160	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	85.000	SFT
161	805-04973 CONDUIT	16,530.000	LFT
162	805-04973 CONDUIT	4,540.000	LFT
163	807-02191 HANDHOLE, LIGHTING	14.000	EACH
164	807-02194 SERVICE POINT, II, MODIFIED	14.000	EACH
165	807-03802 LIGHT STANDARDS	1.000	EACH
166	807-03802 LIGHT STANDARDS	32.000	EACH
167	807-03802 LIGHT STANDARDS	46.000	EACH
168	807-03802 LIGHT STANDARDS	64.000	EACH
169	807-03802 LIGHT STANDARDS	22.000	EACH
170	807-03950 LUMINAIRE, ORNAMENTAL	8.000	EACH
171	807-03950 LUMINAIRE, ORNAMENTAL	78.000	EACH
172	807-03950 LUMINAIRE, ORNAMENTAL	64.000	EACH
173	807-03950 LUMINAIRE, ORNAMENTAL	22.000	EACH
174	807-04651 WIRE	4,020.000	LFT
175	807-06585 CLOCK	1.000	EACH
176	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	1,425.000	LFT
177	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	660.000	LFT
178	807-86810 SERVICE POINT, II	4.000	EACH
179	807-93650 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY	1.000	SET
180	807-93650 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY	78.000	SET
181	807-93650 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY	2.000	SET
182	807-93651 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR POST TOP	63.000	SET
183	807-95514 SERVICE POINT RISER	1.000	EACH
184	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	5,025.000	LFT
185	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	14,481.000	LFT
186	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	30,205.000	LFT
187	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	1,055.000	LFT
188	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	3,923.000	LFT
189	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
190	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
191	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	4.000	EACH
192	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	440.000	EACH

CALL ORDER : 325  
 LETTING DATE :

CONTRACT ID : R -28401-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	13.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	13.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	2,031.800	m2
12	202-02278 CURB, CONCRETE, REMOVE	43.500	m
13	203-02080 LINEAR GRADING	1.850	km
14	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	53.000	EACH
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	14.700	Mg
16	207-08263 SUBGRADE TREATMENT, TYPE IA	11,939.000	m2
17	211-07454 STRUCTURE BACKFILL	3,943.600	m3
18	213-08058 FLOWABLE BACKFILL	366.100	m3
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,719.500	Mg
20	304-07493 WIDENING WITH HMA, TYPE B	727.000	Mg
21	306-08034 MILLING, ASPHALT, 38 mm	14,663.200	m2
22	306-08043 MILLING, TRANSITION	303.000	m2
23	306-08432 MILLING, APPROACH	966.800	m2
24	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 MM	1,908.000	Mg
25	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	1,539.000	Mg
26	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	2,335.000	Mg
27	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	481.000	Mg
28	402-07433 HMA SURFACE, TYPE B	451.000	Mg
29	402-07453 HMA FOR TEMPORARY PAVEMENT	902.000	Mg
30	406-05520 ASPHALT FOR TACK COAT	12.500	Mg
31	603-06060 FENCE, FARM FIELD, RESET	44.000	m
32	603-06065 FENCE, CHAIN LINK, RESET	7.600	m
33	605-06120 CURB, CONCRETE	16.400	m
34	605-06140 CURB AND GUTTER, CONCRETE	1,400.000	m
35	605-94811 CURB TURNOUT	2.000	EACH
36	610-07486 HMA FOR APPROACHES, TYPE A	413.000	Mg
37	610-07487 HMA FOR APPROACHES, TYPE B	169.000	Mg
38	610-07712 PCCP FOR APPROACHES, 150 mm	1,923.800	m2
39	611-06497 MAILBOX ASSEMBLY, SINGLE	20.000	EACH
40	615-06505 MONUMENT, B	2.000	EACH
41	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
42	616-02320 GEOTEXTILES	1,308.500	m2
43	616-06405 RIPRAP, REVETMENT	646.000	Mg
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
45	621-06545 FERTILIZER	0.830	Mg
46	621-06554 SEED MIXTURE, U	151.700	kg
47	621-06557 SEED MIXTURE, T	138.400	kg
48	621-06565 MULCHING MATERIAL	4.100	Mg

CALL ORDER : 325  
 LETTING DATE :

CONTRACT ID : R -28401-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
49	621-06567 WATER	276.900	kL
50	621-06575 SODDING, NURSERY	15,382.000	m2
51	622-05625 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 1200	36.000	EACH
52	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	1,629.700	m
53	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	76.000	m
54	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	1,591.800	m
55	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	473.200	m
56	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	607.100	m
57	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	201.800	m
58	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	218.000	m
59	715-08283 PCCP FOR STRUCTURE INSTALLATION	501.000	m2
60	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	148.000	Mg
61	715-46005 PIPE END SECTION, 375 mm	26.000	EACH
62	715-46010 PIPE END SECTION, 450 mm	4.000	EACH
63	715-46015 PIPE END SECTION, 525 mm	1.000	EACH
64	716-07632 PIPE INSTALLATION, TRENCHLESS, 450 mm	73.500	m
65	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
66	718-52610 AGGREGATE FOR UNDERDRAINS	326.300	m3
67	718-99153 GEOTEXTILES FOR UNDERDRAIN	1,891.600	m2
68	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
69	720-45035 INLET, F7	1.000	EACH
70	720-45075 INLET, R13	15.000	EACH
71	720-45275 PIPE CATCH BASIN, 600 mm	24.000	EACH
72	720-45410 MANHOLE, C4	9.000	EACH
73	720-90984 MANHOLE, C2	14.000	EACH
74	720-98174 INLET, B15	30.000	EACH
75	720-98555 INLET, C15	51.000	EACH
76	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	6,688.000	m
77	801-06625 DETOUR ROUTE MARKER ASSEMBLY	14.000	EACH
78	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
79	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
80	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
81	801-07119 BARRICADE, III-B	14.400	m
82	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	110.300	m
83	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	16.140	m2
84	805-08102 DECORATIVE	2.000	EACH
85	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,565.100	m
86	808-06716 LINE, REMOVE	37,010.000	m
87	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	110.700	m
88	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	4,237.000	m
89	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	59.300	m
90	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	9.000	EACH
91	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	9.000	EACH
92	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	207.000	EACH

CALL ORDER : 345  
 LETTING DATE :

CONTRACT ID : R -28614-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-07040 FIELD OFFICE, C	8.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
6	105-08523 RADIO SERVICE	16.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02271 HEADWALL, REMOVE	2.000	EACH
14	202-96133 PIPE, REMOVE	128.000	m
15	203-02000 EXCAVATION, COMMON	7,290.000	m3
16	203-02070 BORROW	3,000.000	m3
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	39.000	Mg
18	205-06936 TEMPORARY SEDIMENT TRAP	22.000	Mg
19	207-08262 SUBGRADE TREATMENT, TYPE I	8,122.000	m2
20	211-07454 STRUCTURE BACKFILL	157.500	m3
21	303-01180 COMPACTED AGGREGATE, NO. 53	915.500	Mg
22	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	608.000	Mg
23	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	968.000	Mg
24	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	3,429.000	Mg
25	402-07432 HMA SURFACE, TYPE A	33.000	Mg
26	402-07440 HMA BASE, TYPE A	99.000	Mg
27	406-05520 ASPHALT FOR TACK COAT	6.000	Mg
28	610-07486 HMA FOR APPROACHES, TYPE A	201.000	Mg
29	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
30	615-06490 RIGHT OF WAY MARKER	12.000	EACH
31	615-06505 MONUMENT, B	1.000	EACH
32	616-02320 GEOTEXTILES	105.000	m2
33	616-06451 RIPRAP, UNIFORM	74.600	Mg
34	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
35	621-06545 FERTILIZER	0.540	Mg
36	621-06554 SEED MIXTURE, U	100.000	kg
37	621-06565 MULCHING MATERIAL	2.710	Mg
38	621-06567 WATER	129.500	kL
39	621-06574 SODDING	1,751.000	m2
40	621-06575 SODDING, NURSERY	5,425.000	m2
41	715-02397 SAFETY METAL END SECTION, 4:1, 900 mm	1.000	EACH
42	715-02629 SAFETY METAL END SECTION, 6:1, 450 mm	2.000	EACH
43	715-03584 SAFETY METAL END SECTION, 4:1, 450 mm	2.000	EACH
44	715-04799 SAFETY METAL END SECTION, 4:1, 1500 mm X 950 mm (MIN. AREA	2.000	EACH
45	715-05019 PIPE, TYPE 1, CIRCULAR, 900 mm	3.000	m
46	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	42.000	m
47	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	35.500	m
48	715-05171 PIPE, TYPE 3, CIRCULAR, 450 mm	20.500	m

CALL ORDER : 345  
 LETTING DATE :

CONTRACT ID : R -28614-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
49	715-05245 PIPE, TYPE 1, DEFORMED, MIN. AREA 1.20 m2	90.000	m
50	715-07071 SAFETY METAL END SECTION, 4:1, 750 mm	1.000	EACH
51	715-07103 SAFETY METAL END SECTION, 6:1, MIN. AREA 1.20 m2	2.000	EACH
52	715-46000 PIPE END SECTION, 300 mm	1.000	EACH
53	715-46010 PIPE END SECTION, 450 mm	3.000	EACH
54	718-06529 OUTLET PROTECTOR, 2	4.000	EACH
55	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
56	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
57	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	200.000	m
58	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
59	801-06710 FLASHING ARROW SIGN	60.000	DAY
60	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
61	801-07118 BARRICADE, III-A	75.000	m
62	801-07119 BARRICADE, III-B	75.000	m
63	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	1.000	EACH
64	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	7.600	m
65	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	9.340	m
66	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	1.130	m2
67	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	1.790	m2
68	805-01842 HANDHOLE, SIGNAL	2.000	EACH
69	805-01844 CONDUIT, STEEL, GALVANIZED, 50 mm, UNDERGROUND	175.000	m
70	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	473.000	m
71	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	183.000	m
72	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
73	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	140.000	m
74	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	176.500	m
75	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 200 mm	109.500	m
76	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 600 mm	55.500	m
77	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	870.500	m
78	808-06714 LINE, PAINT, SOLID, YELLOW, 100 mm	475.000	m
79	808-06716 LINE, REMOVE	200.000	m
80	808-75272 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE,	43.000	m
81	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	16.000	EACH
82	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	8.000	EACH
83	808-75998 SNOWFLOWABLE RAISED PAVEMENT MARKER	37.000	EACH

CALL ORDER : 347  
 LETTING DATE :

CONTRACT ID : R -28617-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001      ENHANCEMENT, STREETScape			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
2	105-07039	FIELD OFFICE, B	7.000
3	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
4	201-52370	CLEARING RIGHT OF WAY	LUMP
5	202-02240	PAVEMENT REMOVAL	100.000
6	202-02245	TREE, 6 IN., REMOVE	3.000
7	202-02250	TREE, 10 IN., REMOVE	2.000
8	202-02278	CURB, CONCRETE, REMOVE	1,790.000
9	202-02772	CASTING, REMOVE	1.000
10	202-07003	REMOVE	LUMP
11	202-52710	SIDEWALK, CONCRETE, REMOVE	2,136.900
12	202-74035	SIGN, REMOVE	25.000
13	203-02020	EXCAVATION, UNCLASSIFIED	500.000
14	210-04181	BICYCLE RACK	4.000
15	210-05103	BUILDING	1.000
16	210-06313	SEAL	7,850.000
17	210-06984	ADJUST	7.000
18	210-06994	CONCRETE	LUMP
19	210-07642	SOIL PREPARATION	294.400
20	210-07797	WATER	2.000
21	210-07797	WATER	2.000
22	210-08379	STEEL	1.000
23	211-02050	B BORROW	30.000
24	211-07454	STRUCTURE BACKFILL	1,250.000
25	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	1,350.000
26	303-07662	STONE	57.000
27	303-07662	STONE	30.000
28	303-07662	STONE	6.000
29	304-07489	HMA PATCHING, TYPE A	44.000
30	305-07458	PCC BASE, 10 IN.	240.900
31	306-08034	MILLING, ASPHALT, 1 1/2 IN.	870.000
32	307-05402	CEMENT	185.900
33	307-05402	CEMENT	55.000
34	402-07432	HMA SURFACE, TYPE A	174.400
35	402-07435	HMA INTERMEDIATE, TYPE A	250.000
36	406-05521	ASPHALT FOR TACK COAT	650.000
37	603-03829	FENCE	1,183.500
38	604-04740	PAVERS	7,450.000
39	604-04740	PAVERS	1,600.000
40	604-07894	CURB RAMP, CONCRETE, A	168.000
41	604-91531	SIDEWALK, CONCRETE, 4 IN.	1,334.000
42	605-06120	CURB, CONCRETE	380.000
43	605-06120	CURB, CONCRETE	1,258.700
44	605-95635	CURB, CONCRETE, INTEGRAL, MODIFIED	1,777.700
45	611-03671	TRASH RECEPTACLE	5.000
46	611-04923	CEMENT CONCRETE PAVEMENT FOR APPROACHES, 10 IN.	231.000
47	621-06545	FERTILIZER	1.000
48	621-98038	MULCH, HARDWOOD SHREDDED BARK	35.200

CALL ORDER : 347  
 LETTING DATE :

CONTRACT ID : R -28617-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
49	622-01937 PLANT	92.000	EACH
50	622-03948 PLANTER	2.000	EACH
51	622-04648 TREE GRATE	3.000	EACH
52	622-05616 PLANT, BROADLEAF EVERGREEN, GLOBE, DWARF, OVER 18 TO 24 IN.	111.000	EACH
53	622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	90.000	EACH
54	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	48.000	EACH
55	622-05654 PLANT, PERENNIAL	483.000	EACH
56	622-06573 IRRIGATION	1.000	EACH
57	704-04850 CONCRETE	148.500	SYS
58	704-04850 CONCRETE	297.000	SYS
59	712-03812 BENCH	4.000	EACH
60	715-01902 WATER SERVICE LINE, 2 IN.	39.000	LFT
61	715-02889 SERVICE LINE, 1 IN.	26.000	LFT
62	715-04612 PIPE	703.000	LFT
63	715-04612 PIPE	90.000	LFT
64	715-07073 WATER LINE	140.000	LFT
65	715-41045 PIPE, REINFORCED CONCRETE, 12 IN.	55.000	LFT
66	715-93910 WATER SERVICE LINE, ADJUST	8.000	EACH
67	720-03905 CATCH BASIN, A	1.000	EACH
68	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	2.000	EACH
69	732-02388 WATER MAIN	2.000	EACH
70	732-03944 BACKFLOW PREVENTER	1.000	EACH
71	732-03944 BACKFLOW PREVENTER	3.000	EACH
72	732-05559 COUPLING	10.000	EACH
73	732-91742 FIRE HYDRANT	1.000	EACH
74	732-97009 FIRE HYDRANT ASSEMBLY, REMOVE	1.000	EACH
75	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,500.000	LFT
76	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
77	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
78	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
79	801-07119 BARRICADE, III-B	64.000	LFT
80	802-04314 SIGN	26.000	EACH
81	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	73.300	SFT
82	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	80.000	SFT
83	802-97812 STREET NAME IDENTIFICATION SIGN	5.000	EACH
84	805-02426 WIRE, THW, NO. 4 CU, IN PLASTIC DUCT, IN CONDUIT, 4 1C	2,120.000	LFT
85	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,060.000	LFT
86	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	1,440.000	LFT
87	807-02191 HANDHOLE, LIGHTING	8.000	EACH
88	807-03934 LIGHT STRUCTURE, REMOVE	11.000	EACH
89	807-03950 LUMINAIRE, ORNAMENTAL	21.000	EACH
90	807-04143 LIGHT STANDARD, 14 FT. E.M.H., 12 FT., DECORATIVE	21.000	EACH
91	807-04671 OUTLET BOX, ELECTRICAL, WEATHERPROOF	30.000	EACH
92	807-04922 LIGHT STANDARD FOUNDATION	21.000	EACH
93	807-06796 ELECTRIC	30.000	EACH
94	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	2,515.000	LFT
95	807-08561 ELECTRICAL	2,170.000	LFT
96	807-86810 SERVICE POINT, II	2.000	EACH



CALL ORDER : 347  
 LETTING DATE :

CONTRACT ID : R -28617-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
97	807-86910 CONNECTOR KIT, UNFUSED	25.000	EACH
98	807-86915 CONNECTOR KIT, FUSED	25.000	EACH
99	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	45.000	EACH
100	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	32.000	EACH
101	807-86930 INSULATION LINK, NONWATERPROOFED	60.000	EACH
102	807-86935 INSULATION LINK, WATERPROOFED	40.000	EACH
103	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	25.000	EACH
104	807-98690 HANDHOLE ADJUSTED TO GRADE	12.000	EACH
105	808-01238 TRANSVERSE MARKING, PAINT, STOP LINE, REMOVE	8.000	EACH
106	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	8.000	EACH
107	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	4.000	EACH
108	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	378.000	LFT
109	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	5.000	SYS
110	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	500.000	LFT
111	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	925.000	LFT
112	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	160.000	LFT
113	808-06716 LINE, REMOVE	2,000.000	LFT
114	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,500.000	LFT
115	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	96.000	LFT
116	808-97222 PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	1.000	EACH

CALL ORDER : 401  
 LETTING DATE :

CONTRACT ID : R -28654-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	4.000	MOS
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
8	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
9	203-90014 LINEAR GRADING	6.000	STA
10	205-06937 TEMPORARY SILT FENCE	600.000	LFT
11	207-08268 SUBGRADE TREATMENT, TYPE IV	1,269.000	SYS
12	211-07454 STRUCTURE BACKFILL	62.000	CYS
13	303-01180 COMPACTED AGGREGATE, NO. 53	61.000	TON
14	304-07494 WIDENING WITH HMA, TYPE C	74.000	TON
15	306-08033 MILLING, ASPHALT, 1 IN.	916.000	SYS
16	306-08038 MILLING, ASPHALT, 4 IN.	845.000	SYS
17	306-08043 MILLING, TRANSITION	1,187.000	SYS
18	306-08432 MILLING, APPROACH	550.000	SYS
19	402-07434 HMA SURFACE, TYPE C	309.000	TON
20	402-07439 HMA INTERMEDIATE, TYPE C	696.000	TON
21	402-07442 HMA BASE, TYPE C	311.000	TON
22	406-05521 ASPHALT FOR TACK COAT	9,434.000	SYS
23	602-06944 BARRIER, CONCRETE, 33 IN.	20.000	LFT
24	603-97461 TEMPORARY FENCE	230.000	LFT
25	603-98226 FENCE, CHAIN LINK, BLACK VINYL COATED, 48 IN.	213.000	LFT
26	604-06070 SIDEWALK, CONCRETE	526.000	SYS
27	604-07903 CURB RAMP, CONCRETE, K	90.000	SYS
28	604-44251 STEPS, CONCRETE	0.500	CYS
29	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	1,318.000	LFT
30	610-07488 HMA FOR APPROACHES, TYPE C	162.000	TON
31	610-07712 PCCP FOR APPROACHES, 6 IN.	158.000	SYS
32	621-06557 SEED MIXTURE, T	15.000	LBS
33	621-06575 SODDING, NURSERY	812.000	SYS
34	714-44240 CONCRETE, A, STRUCTURES	4.000	CYS
35	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	142.000	LFT
36	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
37	720-44070 CASTING, 13, FURNISH AND ADJUST TO GRADE	1.000	EACH
38	720-45045 INLET, J10	4.000	EACH
39	720-45055 INLET, M10	1.000	EACH
40	720-45075 INLET, R13	2.000	EACH
41	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,120.000	LFT
42	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	120.000	LFT
43	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
44	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
45	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	521.000	SFT
46	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	36.000	SFT
47	802-76055 SIGN POST, A	123.000	LFT
48	802-76065 SIGN POST, B	91.000	LFT

CALL ORDER : 401  
 LETTING DATE :

CONTRACT ID : R -28654-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
49	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	4.000	EACH
50	805-01842 HANDHOLE, SIGNAL	9.000	EACH
51	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	950.000	LFT
52	805-02069 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM	2.000	EACH
53	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	2.000	EACH
54	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	8.000	EACH
55	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
56	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	6.000	EACH
57	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	2.000	EACH
58	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
59	805-78445 SIGNAL SERVICE	1.000	EACH
60	805-78467 SIGNAL CABLE, 3C 8GA.	200.000	LFT
61	805-78480 SIGNAL CABLE, 3C 14GA.	530.000	LFT
62	805-78485 SIGNAL CABLE, 5C 14GA.	870.000	LFT
63	805-78490 SIGNAL CABLE, 7C 14GA.	605.000	LFT
64	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,470.000	LFT
65	805-78746 PREFORMED LOOP DETECTORS	28.000	LFT
66	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
67	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	5.000	EACH
68	807-02781 LUMINAIRE MAST ARM, 10 FT.	2.000	EACH
69	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	535.000	LFT
70	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,274.000	LFT
71	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	31.000	LFT
72	808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	829.000	LFT
73	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	123.000	LFT
74	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	401.000	LFT
75	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	2.000	EACH
76	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH

CALL ORDER : 435  
 LETTING DATE :

CONTRACT ID : RS-28222-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	9.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	75.000	LFT
11	202-93741 GUARD RAIL END TREATMENT, REMOVE	13.000	EACH
12	304-07491 HMA PATCHING, TYPE C	750.000	TON
13	306-08033 MILLING, ASPHALT, 1 IN.	61,000.000	SYS
14	306-08043 MILLING, TRANSITION	480.000	SYS
15	306-08432 MILLING, APPROACH	3,930.000	SYS
16	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
17	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	5,100.000	TON
18	401-07399 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	11,100.000	TON
19	402-07452 HMA, TYPE C, WEDGE AND LEVEL	2,200.000	TON
20	406-05520 ASPHALT FOR TACK COAT	45.000	TON
21	601-06035 GUARDRAIL, RESET	323.000	LFT
22	601-92948 GUARDRAIL, ADJUST HEIGHT	2,028.000	LFT
23	601-94689 GUARDRAIL END TREATMENT, OS	13.000	EACH
24	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	225.000	LFT
25	610-07488 HMA FOR APPROACHES, TYPE C	1,080.000	TON
26	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	4.000	EACH
27	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
28	616-02320 GEOTEXTILES	700.000	SYS
29	616-06451 RIPRAP, UNIFORM	550.000	TON
30	616-95754 PAVED SIDE DITCH, BREAK	15.000	LFT
31	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,168.000	LFT
32	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,084.000	LFT
33	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	40.000	LFT
36	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	44.000	LFT
37	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	1.000	EACH
38	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	250.000	LFT
39	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	4,500.000	LFT
40	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	41,640.000	LFT
41	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	22,774.000	LFT
42	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	15.000	LFT
43	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	483.000	EACH
44	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	483.000	EACH

CALL ORDER : 445  
 LETTING DATE :

CONTRACT ID : RS-28224-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02241 GUARDRAIL, REMOVE	2,257.000	LFT
8	202-93741 GUARD RAIL END TREATMENT, REMOVE	22.000	EACH
9	304-07491 HMA PATCHING, TYPE C	1,600.000	TON
10	306-08033 MILLING, ASPHALT, 1 IN.	115,000.000	SYS
11	306-08034 MILLING, ASPHALT, 1 1/2 IN.	14,000.000	SYS
12	306-08043 MILLING, TRANSITION	7,700.000	SYS
13	306-08432 MILLING, APPROACH	2,700.000	SYS
14	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
15	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	11,300.000	TON
16	401-07379 QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	13,000.000	TON
17	402-07452 HMA, TYPE C, WEDGE AND LEVEL	5,400.000	TON
18	406-05520 ASPHALT FOR TACK COAT	75.000	TON
19	601-01522 GUARDRAIL TRANSITION TYPE TGB	12.000	EACH
20	601-94689 GUARDRAIL END TREATMENT, OS	22.000	EACH
21	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	2,240.000	LFT
22	604-07896 CURB RAMP, CONCRETE, B	3.000	SYS
23	604-07901 CURB RAMP, CONCRETE, G	4.000	SYS
24	604-07901 CURB RAMP, CONCRETE, G	2.000	SYS
25	604-07902 CURB RAMP, CONCRETE, H	7.000	SYS
26	604-07903 CURB RAMP, CONCRETE, K	1.000	SYS
27	610-07488 HMA FOR APPROACHES, TYPE C	2,000.000	TON
28	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	80.000	TON
29	612-60410 DRILLED HOLE FOR UNDERSEAL	1,300.000	EACH
30	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
31	616-02320 GEOTEXTILES	125.000	SYS
32	616-06451 RIPRAP, UNIFORM	200.000	TON
33	621-06574 SODDING	10.000	SYS
34	706-08188 RAILING, TR	162.000	LFT
35	715-06675 PIPE LINER	101.000	LFT
36	732-08419 MODULAR BLOCK WALL	6.000	SYS
37	732-08421 MODULAR BLOCK WALL ERECTION	6.000	SYS
38	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,000.000	LFT
39	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,000.000	LFT
40	801-06640 CONSTRUCTION SIGN, A	56.000	EACH
41	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
42	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	8.000	EACH
43	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	6,200.000	LFT
44	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	76,700.000	LFT
45	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	41,500.000	LFT
46	808-75007 LINE, PAINT, SOLID, WHITE, 6 IN.	1,500.000	LFT
47	808-75272 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	600.000	LFT
48	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	75.000	LFT

CALL ORDER : 445  
 LETTING DATE :

CONTRACT ID : RS-28224-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	50.000	LFT
50 808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	225.000	LFT
51 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
52 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000	EACH
53 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	852.000	EACH
54 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	852.000	EACH
55 808-98875	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	170.000	LFT

CALL ORDER : 485  
 LETTING DATE :

CONTRACT ID : RS-28324-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	62.000	LFT
11	202-93741 GUARD RAIL END TREATMENT, REMOVE	4.000	EACH
12	203-02070 BORROW	32.000	CYS
13	203-02080 LINEAR GRADING	7.400	MILE
14	205-03371 SEDIMENT, REMOVE	130.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	20.000	TON
16	205-06937 TEMPORARY SILT FENCE	20,800.000	LFT
17	303-01180 COMPACTED AGGREGATE, NO. 53	8,660.000	TON
18	303-07449 COMPACTED AGGREGATE, NO. 73	100.000	TON
19	304-07490 HMA PATCHING, TYPE B	3,450.000	TON
20	304-07493 WIDENING WITH HMA, TYPE B	4,750.000	TON
21	306-08033 MILLING, ASPHALT, 1 IN.	103,761.000	SYS
22	306-08043 MILLING, TRANSITION	7,720.000	SYS
23	306-08432 MILLING, APPROACH	775.000	SYS
24	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
25	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	10,400.000	TON
26	401-07371 QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm	13,600.000	TON
27	402-07451 HMA, TYPE B, WEDGE AND LEVEL	7,860.000	TON
28	406-05520 ASPHALT FOR TACK COAT	98.000	TON
29	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
30	610-07487 HMA FOR APPROACHES, TYPE B	653.000	TON
31	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
32	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,625.000	LFT
33	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,313.000	LFT
34	801-06640 CONSTRUCTION SIGN, A	33.000	EACH
35	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
36	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	230.000	LFT
37	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	28.750	LFT
38	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	85,406.000	LFT
39	808-06716 LINE, REMOVE	258.750	LFT
40	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	8,310.000	LFT
41	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	35,630.000	LFT
42	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	12.000	LFT
43	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	826.000	EACH

CALL ORDER : 495  
 LETTING DATE :

CONTRACT ID : RS-28411-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	6,600.000	SYS
11	202-02676 TRANSPORTATION OF SALVAGEABLE MILLED MATERIAL	2,000.000	TON
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5.000	TON
13	303-07449 COMPACTED AGGREGATE, NO. 73	6,000.000	TON
14	304-07491 HMA PATCHING, TYPE C	6,100.000	TON
15	305-03375 CRACKS, TRANSVERSE, ROUT, CLEAN, AND SEAL	156.000	LFT
16	305-93341 SAW, CLEAN AND SEAL LONGITUDINAL JOINTS	68,616.000	LFT
17	305-93342 SAW, CLEAN AND SEAL TRANSVERSE JOINTS	84,459.000	LFT
18	306-08034 MILLING, ASPHALT, 1 1/2 IN.	319,000.000	SYS
19	306-08041 MILLING, PCCP	220.000	SYS
20	306-08432 MILLING, APPROACH	2,700.000	SYS
21	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
22	401-07330 QC/QA-HMA, 5, 70, SURFACE, 9.5 mm	26,000.000	TON
23	402-07432 HMA SURFACE, TYPE A	305.000	TON
24	406-05520 ASPHALT FOR TACK COAT	80.000	TON
25	507-07479 HMA PARTIAL DEPTH PATCH	1.000	TON
26	606-07484 MILLED HMA SHOULDER CORRUGATIONS	16,000.000	LFT
27	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	40,000.000	LFT
28	608-04396 SHOULDER DRAIN	1.000	EACH
29	610-07488 HMA FOR APPROACHES, TYPE C	220.000	TON
30	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	1.000	EACH
31	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	38.000	EACH
32	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	24,700.000	LFT
33	801-06640 CONSTRUCTION SIGN, A	81.000	EACH
34	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
35	801-06710 FLASHING ARROW SIGN	90.000	DAY
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	4.000	EACH
38	801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1	3,180.000	LFT
39	801-08507 TEMPORARY TRAFFIC BARRIER, TYPE 1, ANCHORED	880.000	LFT
40	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
41	801-92448 CONSTRUCTION SIGNS, MOBILE	250.000	DAY
42	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	14.000	LFT
43	802-91122 SIGN, GROUND MOUNTED, RESET	2.000	EACH
44	804-04435 DELINEATOR POST, REMOVE	10.000	EACH
45	804-06771 DELINEATOR POST, FLEXIBLE	10.000	EACH
46	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	12,800.000	LFT
47	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	133,050.000	LFT
48	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	127,900.000	LFT



CALL ORDER : 495  
 LETTING DATE :

CONTRACT ID : RS-28411-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN.	1,800.000	LFT
50	808-06716 LINE, REMOVE	1,100.000	LFT
51	808-06716 LINE, REMOVE	57,100.000	LFT
52	808-07591 LINE, EPOXY, SOLID, WHITE, 24 IN.	575.000	LFT
53	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	1,205.000	LFT
54	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	22.000	EACH
55	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	24.000	EACH
56	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	7,500.000	LFT
57	808-75059 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	18,800.000	LFT
58	808-75994 PRISMATIC REFLECTOR	545.000	EACH
59	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,627.000	EACH
60	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,627.000	EACH

CALL ORDER : 501  
 LETTING DATE :

CONTRACT ID : RS-28414-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	304-07490 HMA PATCHING, TYPE B	100.000	TON
11	306-08034 MILLING, ASPHALT, 1 1/2 IN.	318,400.000	SYS
12	306-08043 MILLING, TRANSITION	3,600.000	SYS
13	306-08432 MILLING, APPROACH	2,640.000	SYS
14	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
15	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	27,581.000	TON
16	406-05520 ASPHALT FOR TACK COAT	115.000	TON
17	610-07487 HMA FOR APPROACHES, TYPE B	2,287.000	TON
18	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	18.000	EACH
19	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	9,900.000	LFT
20	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,900.000	LFT
21	801-06640 CONSTRUCTION SIGN, A	60.000	EACH
22	801-06710 FLASHING ARROW SIGN	30.000	DAY
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
24	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
25	801-92448 CONSTRUCTION SIGNS, MOBILE	180.000	DAY
26	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	114,900.000	LFT
27	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	98,800.000	LFT
28	808-75061 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	24,700.000	LFT
29	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	320.000	LFT
30	808-75071 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC LANE INDICATION	84.000	EACH
31	808-75073 PAVEMENT MESSAGE MARKINGS PREFORMED PLASTIC, WORD ONLY	84.000	EACH
32	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,640.000	EACH
33	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,640.000	EACH

CALL ORDER : 505  
 LETTING DATE :

CONTRACT ID : RS-28475-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02271 HEADWALL, REMOVE	2.000	EACH
8	202-96133 PIPE, REMOVE	48.000	LFT
9	303-01180 COMPACTED AGGREGATE, NO. 53	3,183.000	TON
10	304-07491 HMA PATCHING, TYPE C	500.000	TON
11	304-07494 WIDENING WITH HMA, TYPE C	376.000	TON
12	306-08033 MILLING, ASPHALT, 1 IN.	354,873.000	SYS
13	306-08043 MILLING, TRANSITION	1,147.000	SYS
14	306-08432 MILLING, APPROACH	14,393.000	SYS
15	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
16	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	29,372.000	TON
17	402-07452 HMA, TYPE C, WEDGE AND LEVEL	200.000	TON
18	406-05520 ASPHALT FOR TACK COAT	123.000	TON
19	610-07488 HMA FOR APPROACHES, TYPE C	1,187.500	TON
20	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
21	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
22	621-06567 WATER	2.000	KGAL
23	621-06626 MULCHED SEEDING, D	400.000	SYS
24	715-05233 PIPE, TYPE 1, DEFORMED, 3.3 SQ. FT.	80.000	LFT
25	715-07029 SAFETY METAL END SECTION, 4:1, MIN. AREA 3.3 SFT.	2.000	EACH
26	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
27	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	11,000.000	LFT
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	11,000.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	62.000	EACH
30	801-06710 FLASHING ARROW SIGN	30.000	DAY
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	4.000	EACH
33	802-76055 SIGN POST, A	51.000	LFT
34	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,785.000	LFT
35	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	287.500	LFT
36	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	920.000	LFT
37	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	8.000	EACH
38	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	99,000.000	LFT
39	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	87,000.000	LFT
40	808-75001 LINE, PAINT, BROKEN, WHITE, 5 IN.	22,000.000	LFT
41	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	1,700.000	LFT
42	808-75072 TRANSVERSE MARKINGS, PAINT, SOLID, WHITE, CROSSHATCH LINE,	1,100.000	LFT
43	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	290.000	LFT
44	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	47.000	EACH
45	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	21.000	EACH
46	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	4.000	EACH
47	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,115.000	EACH
48	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,115.000	EACH

CALL ORDER : 635  
 LETTING DATE :

CONTRACT ID : B -27366-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-06908 RADIO SERVICE	16.000	MOS
4	105-07039 FIELD OFFICE, B	16.000	MOS
5	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
6	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	380.000	m2
13	202-02241 GUARDRAIL, REMOVE	51.500	m
14	202-05544 REGULATED MATERIALS, DISPOSE, C	12,300.000	L
15	202-05545 REGULATED MATERIALS, DISPOSE, C	12.300	m3
16	202-05549 REGULATED MATERIALS, REMOVE, C	12,300.000	L
17	202-05550 REGULATED MATERIALS, REMOVE, C	12.300	m3
18	202-05554 REGULATED MATERIALS, TRANSPORT, C	12,300.000	L
19	202-05555 REGULATED MATERIALS, TRANSPORT, C	12.300	m3
20	202-05571 TESTING FOR WASTES	20.000	EACH
21	202-05571 TESTING FOR WASTES	20.000	EACH
22	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
23	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	12.000	EACH
24	202-74080 OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	2.000	EACH
25	203-02000 EXCAVATION, COMMON	2,852.000	m3
26	203-51223 EXCAVATION, WATERWAY	968.000	m3
27	205-03371 SEDIMENT REMOVE	25.000	m3
28	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	49.600	Mg
29	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
30	205-06936 TEMPORARY SEDIMENT TRAP	53.200	Mg
31	205-06937 TEMPORARY SILT FENCE	858.000	m
32	205-06938 TEMPORARY SLOPE DRAIN	17.700	m
33	206-51220 EXCAVATION, WET	270.500	m3
34	206-51225 EXCAVATION, DRY	21.800	m3
35	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,589.000	m2
36	207-08268 SUBGRADE TREATMENT, TYPE IV	4,332.600	m2
37	211-06467 AGGREGATE FOR END BENT BACKFILL	27.200	m3
38	211-07454 STRUCTURE BACKFILL	46.100	m3
39	213-08058 FLOWABLE BACKFILL	17.300	m3
40	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,064.900	Mg
41	302-07455 DENSE GRADED SUBBASE	56.100	m3
42	306-08033 MILLING, ASPHALT, 25 mm	1,720.000	m2
43	306-08043 MILLING, TRANSITION	899.000	m2
44	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
45	402-07433 HMA SURFACE, TYPE B	631.100	Mg
46	402-07438 HMA INTERMEDIATE, TYPE B	833.100	Mg
47	402-07441 HMA BASE, TYPE B	1,577.600	Mg
48	402-07453 HMA FOR TEMPORARY PAVEMENT	517.100	Mg

CALL ORDER : 635  
 LETTING DATE :

CONTRACT ID : B -27366-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	406-05520 ASPHALT FOR TACK COAT	4.300	Mg
50	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
51	601-02206 TEMPORARY GUARDRAIL, W BEAM, 1.905 m SPACING	106.680	m
52	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
53	601-97080 TEMPORARY GUARDRAIL END TREATMENT, OS	4.000	EACH
54	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	78.105	m
55	602-06729 BARRIER DELINEATOR	8.000	EACH
56	605-06140 CURB AND GUTTER, CONCRETE	164.000	m
57	605-94811 CURB TURNOUT	1.000	EACH
58	607-06335 PAVED SIDE DITCH, A	15.500	m
59	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	374.100	m2
60	610-07486 HMA FOR APPROACHES, TYPE A	28.900	Mg
61	610-07712 PCCP FOR APPROACHES, 150 mm	603.900	m2
62	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
63	615-06490 RIGHT OF WAY MARKER	25.000	EACH
64	615-06505 MONUMENT, B	4.000	EACH
65	616-02320 GEOTEXTILES	1,656.300	m2
66	616-06405 RIPRAP, REVETMENT	822.800	Mg
67	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
68	621-01371 SEED MIXTURE, LEGUME, 2	56.000	kg
69	621-06545 FERTILIZER	1.200	Mg
70	621-06553 SEED MIXTURE, R	128.000	kg
71	621-06557 SEED MIXTURE, T	30.400	kg
72	621-06565 MULCHING MATERIAL	6.100	Mg
73	621-06567 WATER	22.400	kL
74	621-06575 SODDING, NURSERY	1,237.400	m2
75	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
76	622-91786 SEEDLING	400.000	EACH
77	701-01849 PILE, CONCRETE, STEEL SHELL ENCASED, 7.92 mm, 356 mm	252.600	m
78	701-93633 OVERSIZED PREDRILLED PILE HOLES	15.000	m
79	702-51005 CONCRETE, A, SUBSTRUCTURE	140.400	m3
80	702-51015 CONCRETE, B, FOOTINGS	34.800	m3
81	703-51030 REINFORCING STEEL	13,028.000	kg
82	703-51032 REINFORCING STEEL, EPOXY COATED	38,817.000	kg
83	704-51002 CONCRETE, C, SUPERSTRUCTURE	201.200	m3
84	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
85	706-51020 CONCRETE, C, RAILING	17.500	m3
86	707-05979 STRUCTURAL MEMBERS, CONCRETE BOX BEAM, CB, 686 mm X 1219 mm	264.000	m2
87	709-51821 SURFACE SEAL	LUMP	LUMP
88	713-51335 TEMPORARY BRIDGE AND APPROACHES	LUMP	LUMP
89	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	25.500	m
90	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	94.000	m
91	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	18.500	m
92	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	49.000	m
93	715-05173 PIPE, TYPE 3, CIRCULAR, 600 mm	8.500	m
94	715-05407 PIPE, END BENT DRAIN, 150 mm	53.000	m
95	715-46000 PIPE END SECTION, 300 mm	1.000	EACH
96	715-46005 PIPE END SECTION, 375 mm	7.000	EACH

CALL ORDER : 635  
 LETTING DATE :

CONTRACT ID : B -27366-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
97	715-46010 PIPE END SECTION, 450 mm	2.000	EACH
98	715-46020 PIPE END SECTION, 600 mm	2.000	EACH
99	720-04666 CATCH BASIN	4.000	EACH
100	720-45035 INLET, F7	1.000	EACH
101	728-98377 MASONRY COATING	LUMP	LUMP
102	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
103	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	205.000	m
104	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	415.000	m
105	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	385.000	m
106	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	675.000	m
107	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	1.000	EACH
108	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 600 mm	12.200	m
109	801-06640 CONSTRUCTION SIGN, A	42.000	EACH
110	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
111	801-06649 TEMPORARY RAISED PAVEMENT MARKER, 1	37.000	EACH
112	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
113	801-07118 BARRICADE, III-A	18.000	m
114	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	28.400	m
115	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	12.500	m
116	802-05706 SIGN POST, SQUARE, 3, UNREINFORCED ANCHOR	7.400	m
117	802-07159 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, II	1.000	EACH
118	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	8.630	m2
119	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	4.640	m2
120	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	1.760	m2
121	802-76135 OVERHEAD SIGN STRUCTURE, CANTILEVER SINGLE ARM	1.000	EACH
122	804-06740 DELINEATOR WITH POST, D2	54.000	EACH
123	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	1,450.000	m
124	808-06714 LINE, PAINT, SOLID, YELLOW, 100 mm	960.000	m
125	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	25.500	m
126	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
127	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	13.000	EACH
128	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	31.000	EACH

CALL ORDER : 675  
LETTING DATE :

CONTRACT ID : B -28429-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPAIR & REHABILITATION		
1 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
2 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
3 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4 601-06035	GUARDRAIL, RESET	25.000	LFT
5 709-04647	FIBER WRAP CONCRETE CASING SYSTEM	LUMP	LUMP
6 727-90308	EPOXY INJECTION, CRACK PREPARATION	10.000	LFT
7 727-90309	EPOXY INJECTION, EPOXY MATERIAL	1.000	GAL
8 727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	LUMP	LUMP
9 801-06640	CONSTRUCTION SIGN, A	28.000	EACH
10 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 765  
 LETTING DATE :

CONTRACT ID : M -28598-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DRAINAGE DITCH CORRECTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	4.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
5	201-90788 DEBRIS, REMOVE	LUMP	LUMP
6	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
7	203-02000 EXCAVATION, COMMON	300.000	CYS
8	203-02070 BORROW	110.000	CYS
9	205-06932 TEMPORARY CHECK DAM, STRAW BALES	50.000	LFT
10	207-08266 SUBGRADE TREATMENT, TYPE III	1,075.000	SYS
11	303-01180 COMPACTED AGGREGATE, NO. 53	500.000	TON
12	304-07490 HMA PATCHING, TYPE B	7.000	TON
13	402-07433 HMA SURFACE, TYPE B	55.000	TON
14	402-07438 HMA INTERMEDIATE, TYPE B	160.000	TON
15	406-05520 ASPHALT FOR TACK COAT	0.400	TON
16	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
17	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
18	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	675.000	LFT
19	602-06729 BARRIER DELINEATOR	4.000	EACH
20	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
21	616-02320 GEOTEXTILES	120.000	SYS
22	616-06405 RIPRAP, REVETMENT	80.000	TON
23	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
24	621-06559 MULCHED SEEDING, R	850.000	SYS
25	702-51863 FIELD DRILLED HOLE IN CONCRETE	38.000	EACH
26	703-51032 REINFORCING STEEL, EPOXY COATED	679.000	LBS
27	706-51020 CONCRETE, C, RAILING	6.100	CYS
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	110.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1	340.000	LFT
32	804-06725 DELINEATOR WITH POST, D1, 3 IN. DIA.	10.000	EACH
33	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	275.000	LFT
34	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	2,200.000	LFT
35	808-06716 LINE, REMOVE	300.000	LFT



CALL ORDER : 769  
 LETTING DATE :

CONTRACT ID : M -28619-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INSTITUTION AND PARK ROAD MAINTENANCE		
1	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
2	202-02771 CONCRETE APRON, REMOVE	1.000	EACH
3	203-02000 EXCAVATION, COMMON	454.500	CYS
4	203-02070 BORROW	135.000	CYS
5	303-01180 COMPACTED AGGREGATE, NO. 53	200.500	TON
6	304-07489 HMA PATCHING, TYPE A	14.700	TON
7	306-08043 MILLING, TRANSITION	1,760.000	SYS
8	306-08432 MILLING, APPROACH	32.000	SYS
9	402-07432 HMA SURFACE, TYPE A	574.000	TON
10	402-07435 HMA INTERMEDIATE, TYPE A	395.500	TON
11	402-07440 HMA BASE, TYPE A	152.500	TON
12	406-05520 ASPHALT FOR TACK COAT	2.500	TON
13	604-06070 SIDEWALK, CONCRETE	378.000	SYS
14	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
15	621-06559 MULCHED SEEDING, R	343.000	SYS
16	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	7.000	LFT
17	715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN.	11.000	LFT
18	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
19	725-06859 PIPE LINER, THERMOPLASTIC, 48 IN.	56.000	LFT
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 785  
 LETTING DATE :

CONTRACT ID : M -28643-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-07038 FIELD OFFICE, A	3.000	MOS
2	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
3	303-01180 COMPACTED AGGREGATE, NO. 53	86.500	TON
4	304-07491 HMA PATCHING, TYPE C	200.000	TON
5	306-08043 MILLING, TRANSITION	500.000	SYS
6	306-08432 MILLING, APPROACH	2,200.000	SYS
7	402-07434 HMA SURFACE, TYPE C	7,442.000	TON
8	402-07452 HMA, TYPE C, WEDGE AND LEVEL	200.000	TON
9	406-05520 ASPHALT FOR TACK COAT	25.500	TON
10	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
11	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
12	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
13	808-04767 LINE	200.000	LFT
14	808-97222 PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	3.000	EACH

CALL ORDER : 825  
 LETTING DATE :

CONTRACT ID : MT-28461-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	WASTE WATER TREATMENT PLANT		
1	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	60.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	201-06587 CLEARING AND GRUBBING	2.000	ACRE
6	202-91840 FENCE, CHAIN LINK, REMOVE	375.000	LFT
7	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	50.000	TON
8	402-07434 HMA SURFACE, TYPE C	25.000	TON
9	715-97206 WASTE WATER TREATMENT PLANT	LUMP	LUMP
10	715-97206 WASTE WATER TREATMENT PLANT	LUMP	LUMP
11	805-01842 HANDHOLE, SIGNAL	2.000	EACH
12	805-04973 CONDUIT	100.000	LFT
13	807-04967 CABLE	750.000	LFT
14	807-04967 CABLE	750.000	LFT

CALL ORDER : 845  
 LETTING DATE :

CONTRACT ID : T -27190-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW SIGNAL AND FLASHER INSTALLATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	10.000	MOS
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	202-02240 PAVEMENT REMOVAL	1,006.000	SYS
8	202-02278 CURB, CONCRETE, REMOVE	470.000	LFT
9	202-02279 CURB AND GUTTER, REMOVE	480.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	572.000	SYS
11	202-74035 SIGN, REMOVE	4.000	EACH
12	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	260.000	CYS
14	203-02070 BORROW	25.000	CYS
15	203-02080 LINEAR GRADING	0.126	MILE
16	211-07454 STRUCTURE BACKFILL	400.000	CYS
17	304-07493 WIDENING WITH HMA, TYPE B	773.000	TON
18	306-08043 MILLING, TRANSITION	449.000	SYS
19	402-07433 HMA SURFACE, TYPE B	240.000	TON
20	402-07438 HMA INTERMEDIATE, TYPE B	450.000	TON
21	402-07451 HMA, TYPE B, WEDGE AND LEVEL	152.000	TON
22	406-05520 ASPHALT FOR TACK COAT	1.840	TON
23	601-06224 IMPACT ATTENUATOR, CR, W1, TL-2	1.000	EACH
24	604-06070 SIDEWALK, CONCRETE	444.000	SYS
25	605-06120 CURB, CONCRETE	355.000	LFT
26	605-06140 CURB AND GUTTER, CONCRETE	567.000	LFT
27	610-07712 PCCP FOR APPROACHES, 6 IN.	135.000	SYS
28	621-06567 WATER	1.200	KGAL
29	621-06575 SODDING, NURSERY	291.000	SYS
30	703-51030 REINFORCING STEEL	9,126.000	LBS
31	714-44240 CONCRETE, A, STRUCTURES	109.700	CYS
32	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	740.000	LFT
33	715-05407 PIPE, END BENT DRAIN, 6 IN.	206.000	LFT
34	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
35	720-45015 INLET, A8	2.000	EACH
36	720-45075 INLET, R13	1.000	EACH
37	720-45250 CATCH BASIN, K10	2.000	EACH
38	801-06606 BARRICADE, IIIB	22.000	EACH
39	801-06625 DETOUR ROUTE MARKER ASSEMBLY	74.000	EACH
40	801-06640 CONSTRUCTION SIGN, A	33.000	EACH
41	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
42	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	133.400	SFT
43	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	215.000	SFT
44	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	41.000	SFT
45	802-76055 SIGN POST, A	163.000	LFT
46	802-76065 SIGN POST, B	26.000	LFT
47	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	8.000	EACH
48	805-01842 HANDHOLE, SIGNAL	9.000	EACH

CALL ORDER : 845  
 LETTING DATE :

CONTRACT ID : T -27190-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW SIGNAL AND FLASHER INSTALLATION			
49	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	355.000	LFT
50	805-01879 SIGNAL SERVICE, INSTALL	2.000	EACH
51	805-02202 SIGNAL DETECTOR HOUSING, DOUBLE	6.000	EACH
52	805-02328 SIGNAL CABLE, 1C 14GA.	2,950.000	LFT
53	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	400.000	LFT
54	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	2.000	EACH
55	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
56	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. AMBER	4.000	EACH
57	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. RED	2.000	EACH
58	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	7.000	EACH
59	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	7.000	EACH
60	805-78415 SPAN, CATENARY, AND TETHER	9.000	EACH
61	805-78420 DISCONNECT HANGER	8.000	EACH
62	805-78445 SIGNAL SERVICE	1.000	EACH
63	805-78467 SIGNAL CABLE, 3C 8GA.	130.000	LFT
64	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,500.000	LFT
65	805-78480 SIGNAL CABLE, 3C 14GA.	290.000	LFT
66	805-78485 SIGNAL CABLE, 5C 14GA.	220.000	LFT
67	805-78490 SIGNAL CABLE, 7C 14GA.	980.000	LFT
68	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,810.000	LFT
69	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
70	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,550.000	LFT
71	805-78925 CONTROLLER CABINET FOUNDATION, P1	2.000	EACH
72	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	3.000	EACH
73	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	5.000	EACH
74	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	7.000	EACH
75	807-02781 LUMINAIRE MAST ARM, 10 FT.	1.000	EACH
76	807-02783 LUMINAIRE MAST ARM, 15 FT.	1.000	EACH
77	808-02066 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID WHITE CROSSHATCH	130.000	LFT
78	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	4.000	EACH
79	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	140.000	LFT
80	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	2,900.000	LFT
81	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	320.000	LFT
82	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	960.000	LFT
83	808-75071 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC LANE INDICATION	13.000	EACH
84	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	682.000	LFT
85	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	115.000	LFT
86	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
87	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000	EACH
88	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	762.000	LFT
89	808-96016 LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN.	212.000	LFT
90	808-98875 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	150.000	LFT
91	808-99077 LINE, PREFORMED PLASTIC, SOLID, WHITE, 24 IN.	150.000	LFT

CALL ORDER : 855  
 LETTING DATE :

CONTRACT ID : T -28043-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	10.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02272 PAVED SIDE DITCH, REMOVE	623.600	LFT
8	202-04089 SIGN, SHEET, REMOVE	1.000	EACH
9	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	4.000	EACH
10	203-02000 EXCAVATION, COMMON	507.700	CYS
11	205-06932 TEMPORARY CHECK DAM, STRAW BALES	260.000	LFT
12	205-06936 TEMPORARY SEDIMENT TRAP	64.200	TON
13	205-06937 TEMPORARY SILT FENCE	520.000	LFT
14	207-08263 SUBGRADE TREATMENT, TYPE IA	3,235.900	SYS
15	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	429.800	TON
16	306-08036 MILLING, ASPHALT, 2 IN.	4,233.900	SYS
17	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	596.600	TON
18	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	666.500	TON
19	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	1,637.400	TON
20	404-05511 SEAL COAT, 2	659.500	SYS
21	406-05520 ASPHALT FOR TACK COAT	3.500	TON
22	610-07486 HMA FOR APPROACHES, TYPE A	96.700	TON
23	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
24	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
25	616-02320 GEOTEXTILES	114.300	SYS
26	616-06451 RIPRAP, UNIFORM	17.300	TON
27	621-06567 WATER	13.100	KGAL
28	621-06574 SODDING	3,259.600	SYS
29	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,781.000	LFT
30	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
31	801-06710 FLASHING ARROW SIGN	30.000	DAY
32	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
33	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	35.000	LFT
34	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	1.000	EACH
35	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	7.500	SFT
36	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	25.500	SFT
37	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	22.500	SFT
38	802-99045 SIGN REMOUNTING	2.000	EACH
39	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
40	805-01842 HANDHOLE, SIGNAL	6.000	EACH
41	805-02328 SIGNAL CABLE, 1C 14GA.	652.000	LFT
42	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,028.000	LFT
43	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
44	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	6.000	EACH
45	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
46	805-78420 DISCONNECT HANGER	3.000	EACH
47	805-78445 SIGNAL SERVICE	1.000	EACH
48	805-78467 SIGNAL CABLE, 3C 8GA.	45.000	LFT

CALL ORDER : 855  
 LETTING DATE :

CONTRACT ID : T -28043-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
49	805-78485 SIGNAL CABLE, 5C 14GA.	138.000	LFT
50	805-78490 SIGNAL CABLE, 7C 14GA.	554.000	LFT
51	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,035.000	LFT
52	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
53	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	218.000	LFT
54	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
55	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000	EACH
56	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000	EACH
57	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	220.000	LFT
58	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	2,266.000	LFT
59	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	4,935.000	LFT
60	808-06716 LINE, REMOVE	2,645.000	LFT
61	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	77.000	LFT
62	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	2.000	EACH
63	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH
64	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	34.000	EACH
65	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	66.000	EACH

