

CALL ORDER : 131  
 LETTING DATE :

CONTRACT ID : R -26832-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REPLACEMENT AND ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	17.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	68.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	23,603.000	SYS
13	202-02241 GUARDRAIL, REMOVE	6,970.000	LFT
14	202-02272 PAVED SIDE DITCH, REMOVE	63.000	LFT
15	202-02273 CENTER CURB, CONCRETE, REMOVE	522.000	SYS
16	202-05441 GRIND CONCRETE PAVEMENT	50.000	SYS
17	202-86946 HANDHOLE, REMOVE	12.000	EACH
18	202-90277 DETECTOR HOUSING, REMOVE	6.000	EACH
19	202-91385 INLET, REMOVE	7.000	EACH
20	202-99187 FENCE, FARM FIELD, REMOVE	500.000	LFT
21	203-02000 EXCAVATION, COMMON	25,446.000	CYS
22	203-02070 BORROW	1,868.000	CYS
23	205-06933 TEMPORARY DITCH INLET PROTECTION	20.000	EACH
24	205-06934 TEMPORARY MULCHING	14.000	TON
25	205-06936 TEMPORARY SEDIMENT TRAP	30.000	TON
26	205-06937 TEMPORARY SILT FENCE	1,500.000	LFT
27	207-08268 SUBGRADE TREATMENT, TYPE IV	87,400.000	SYS
28	211-02050 B BORROW	1,150.000	CYS
29	213-04324 FLOWABLE FILL	110.000	CYS
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	27,935.000	TON
31	303-04489 COMPACTED CRUSHED AGGREGATE, 8	13,090.000	TON
32	306-08033 MILLING, ASPHALT, 1 IN.	9,499.000	SYS
33	306-08043 MILLING, TRANSITION	1,716.000	SYS
34	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	4,665.000	TON
35	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,750.000	TON
36	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	7,220.000	TON
37	402-07434 HMA SURFACE, TYPE C	246.000	TON
38	402-07452 HMA, TYPE C, WEDGE AND LEVEL	2,696.000	TON
39	402-07453 HMA FOR TEMPORARY PAVEMENT	10,000.000	TON
40	406-05521 ASPHALT FOR TACK COAT	17,639.000	SYS
41	501-06324 QC/QA-PCCP, 13 IN.	72,556.000	SYS
42	501-06324 QC/QA-PCCP, 13 IN.	8,275.000	SYS
43	501-06324 QC/QA-PCCP, 13 IN.	631.000	SYS
44	502-06330 PCCP, 13 IN.	230.000	SYS
45	503-05240 D-1 CONTRACTION JOINT	45,000.000	LFT
46	506-06333 PCCP PATCHING, FULL DEPTH	50.000	SYS
47	507-07505 RETROFIT LOAD TRANSFER	48.000	EACH
48	601-01115 GUARDRAIL, W BEAM, 1 FT. 6.75 IN. SPACING	50.000	LFT

CALL ORDER : 131  
 LETTING DATE :

CONTRACT ID : R -26832-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REPLACEMENT AND ADDED TRAVEL LANES		
49	601-01704 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, MODIFIED	6.000	EACH
50	601-03929 GUARDRAIL, W BEAM, SHOP CURVED, 3 FT. 1.5 IN. SPACING	219.000	LFT
51	601-06035 GUARDRAIL, RESET	1,110.000	LFT
52	601-06229 IMPACT ATTENUATOR, CR, W2, TL-3	4.000	EACH
53	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
54	601-94689 GUARDRAIL END TREATMENT, OS	12.000	EACH
55	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	15,980.000	LFT
56	601-99106 GUARDRAIL, W BEAM, 3 FT. 1.5 IN. SPACING	100.000	LFT
57	602-04333 CONCRETE BARRIER, 46 IN.	3,560.000	LFT
58	602-06729 BARRIER DELINEATOR	65.000	EACH
59	603-06040 FENCE, FARM FIELD, 47 IN.	500.000	LFT
60	605-06250 CENTER CURB, C, CONCRETE	377.000	SYS
61	606-07484 MILLED HMA SHOULDER CORRUGATIONS	1,000.000	LFT
62	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	22,760.000	LFT
63	610-03393 TEMPORARY CROSSOVER, B MODIFIED	1.000	EACH
64	610-07488 HMA FOR APPROACHES, TYPE C	774.000	TON
65	615-06510 MONUMENT, C	2.000	EACH
66	615-06515 MONUMENT, D	5.000	EACH
67	616-02320 GEOTEXTILES	2,392.000	SYS
68	616-06405 RIPRAP, REVETMENT	3,425.000	TON
69	616-06451 RIPRAP, UNIFORM	54.000	TON
70	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
71	621-02770 EROSION CONTROL BLANKET	17,051.000	SYS
72	621-06545 FERTILIZER	3.000	TON
73	621-06554 SEED MIXTURE, U	22,777.000	LBS
74	621-06557 SEED MIXTURE, T	551.000	LBS
75	621-06565 MULCHING MATERIAL	5.000	TON
76	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	2.000	EACH
77	715-03584 SAFETY METAL END SECTION, 4:1, 18 IN.	1.000	EACH
78	715-04798 SAFETY METAL END SECTION, 4:1, 21 IN.	1.000	EACH
79	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	24,919.000	LFT
80	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	3,004.000	LFT
81	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	414.000	LFT
82	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	74.000	LFT
83	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	120.000	LFT
84	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
85	715-46005 PIPE END SECTION, 15 IN.	18.000	EACH
86	715-46010 PIPE END SECTION, 18 IN.	5.000	EACH
87	715-91361 PIPE, PVC, 6 IN.	1,018.000	LFT
88	718-06529 OUTLET PROTECTOR, 2	35.000	EACH
89	718-52610 AGGREGATE FOR UNDERDRAINS	1,821.000	CYS
90	720-07301 INLET TYPE HA	16.000	EACH
91	720-44070 CASTING, 13, FURNISH AND ADJUST TO GRADE	2.000	EACH
92	720-45041 INLET, H5	17.000	EACH
93	720-45045 INLET, J10	3.000	EACH
94	720-45055 INLET, M10	9.000	EACH
95	720-45415 MANHOLE, D4	1.000	EACH
96	720-91246 INLET, N12A	3.000	EACH

CALL ORDER : 131  
 LETTING DATE :

CONTRACT ID : R -26832-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REPLACEMENT AND ADDED TRAVEL LANES		
97	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
98	801-04308 ROAD CLOSURE SIGN ASSEMBLY	13.000	EACH
99	801-06201 TEMPORARY PANEL SIGNS	32.000	SYS
100	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	26,281.000	LFT
101	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	44,102.000	LFT
102	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	53.000	EACH
103	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (ONLY)	24.000	EACH
104	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	174.000	LFT
105	801-06625 DETOUR ROUTE MARKER ASSEMBLY	21.000	EACH
106	801-06640 CONSTRUCTION SIGN, A	84.000	EACH
107	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
108	801-06710 FLASHING ARROW SIGN	400.000	DAY
109	801-06735 TUBULAR MARKER, PERMANENT	14.000	EACH
110	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
111	801-07117 TEMPORARY WORKSITE FLASHING LIGHT SIGN ASSEMBLY	10.000	EACH
112	801-07118 BARRICADE, III-A	30.000	LFT
113	801-07119 BARRICADE, III-B	290.000	LFT
114	801-07606 TEMPORARY CROSSEVER DRAINAGE PIPE	500.000	LFT
115	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	14.000	EACH
116	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	50.000	LFT
117	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	34.000	EACH
118	802-07060 SIGN, SHEET, RELOCATE	25.000	EACH
119	802-07060 SIGN, SHEET, RELOCATE	4.000	EACH
120	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	14.000	SFT
121	802-91084 OVERHEAD PANEL SIGN, REMOVE AND REINSTALL	1.000	EACH
122	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
123	805-01842 HANDHOLE, SIGNAL	17.000	EACH
124	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	3,950.000	LFT
125	805-01879 SIGNAL SERVICE, INSTALL	1.000	EACH
126	805-02438 COMMUNICATION TELEMETRY INTERCONNECT INTERFACE PANEL	3.000	EACH
127	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	400.000	LFT
128	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	2.000	EACH
129	805-08464 RADIO, INTERCONNECT	3.000	EACH
130	805-08465 RADIO ANTENNA, 6db, OMNI	1.000	EACH
131	805-08466 RADIO ANTENNA, 9db, YAGI	3.000	EACH
132	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000	EACH
133	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
134	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	6.000	EACH
135	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	3.000	EACH
136	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
137	805-78420 DISCONNECT HANGER	3.000	EACH
138	805-78467 SIGNAL CABLE, 3C 8GA.	120.000	LFT
139	805-78485 SIGNAL CABLE, 5C 14GA.	430.000	LFT
140	805-78490 SIGNAL CABLE, 7C 14GA.	690.000	LFT
141	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	13,030.000	LFT
142	805-78746 PREFORMED LOOP DETECTORS	2,280.000	LFT
143	805-78785 SIGNAL DETECTOR HOUSING	17.000	EACH
144	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	120.000	LFT

CALL ORDER : 131  
 LETTING DATE :

CONTRACT ID : R -26832-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REPLACEMENT AND ADDED TRAVEL LANES		
145	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
146	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	4.000	EACH
147	805-90734 TRAFFIC RESPONSIVE SYSTEM MASTER	1.000	EACH
148	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	19.000	EACH
149	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	49.000	EACH
150	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	15.000	EACH
151	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	54.000	SYS
152	808-06368 TRANSVERSE MARKING, REMOVE	182.000	LFT
153	808-06368 TRANSVERSE MARKING, REMOVE	663.000	LFT
154	808-06716 LINE, REMOVE	17,100.000	LFT
155	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	15,250.000	LFT
156	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	12,700.000	LFT
157	808-75061 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	7,650.000	LFT
158	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	550.000	LFT
159	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	230.000	EACH
160	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	910.000	EACH

CALL ORDER : 151  
 LETTING DATE :

CONTRACT ID : R -27047-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	27.000	MOS
3	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
4	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	32,162.000	m2
10	202-02278 CURB, CONCRETE, REMOVE	788.000	m
11	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
12	202-93615 CONCRETE, REMOVE	638.000	m2
13	203-02000 EXCAVATION, COMMON	105,940.000	m3
14	205-06932 TEMPORARY CHECK DAM, STRAW BALES	263.000	m
15	205-06933 TEMPORARY DITCH INLET PROTECTION	16.000	EACH
16	205-06936 TEMPORARY SEDIMENT TRAP	28.500	Mg
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	25,151.000	m2
18	207-08268 SUBGRADE TREATMENT, TYPE IV	93,320.000	m2
19	211-02050 B BORROW	2,726.000	m3
20	211-07454 STRUCTURE BACKFILL	8,606.000	m3
21	213-08058 FLOWABLE BACKFILL	28.000	m3
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	18,113.000	Mg
23	302-06464 SUBBASE FOR PCCP	16,011.000	m3
24	303-01180 COMPACTED AGGREGATE, NO. 53	630.000	Mg
25	303-07449 COMPACTED AGGREGATE, NO. 73	644.000	Mg
26	304-07491 HMA PATCHING, TYPE C	701.000	Mg
27	306-08037 MILLING, ASPHALT, 75 mm	8,477.000	m2
28	402-07440 HMA BASE, TYPE A	357.000	Mg
29	402-07453 HMA FOR TEMPORARY PAVEMENT	9,119.000	Mg
30	402-07784 HMA SURFACE, TYPE D	1,874.000	Mg
31	402-07785 HMA INTERMEDIATE, TYPE D	3,138.000	Mg
32	402-07786 HMA BASE, TYPE D	8,793.000	Mg
33	404-05511 SEAL COAT, 2	1,490.000	m2
34	406-05520 ASPHALT FOR TACK COAT	16.000	Mg
35	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
36	501-06323 QC/QA-PCCP, 300 mm	72,131.000	m2
37	501-06727 CORING, PCCP	LUMP	LUMP
38	502-06999 PCCP, 200 mm	1,163.000	m2
39	503-03489 RETROFITTED TIE BARS	126.000	EACH
40	503-05240 D-1 CONTRACTION JOINT	13,102.000	m
41	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	2.000	EACH
42	601-06234 IMPACT ATTENUATOR, R1, W1, TL-2	1.000	EACH
43	601-06417 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R1, W1, TL-2	1.000	EACH
44	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	9.500	m
45	602-06729 BARRIER DELINEATOR	54.000	EACH
46	602-08588 CONCRETE BARRIER, 1145 mm, MODIFIED	318.000	m
47	603-06045 FENCE, CHAIN LINK, 1220 mm	3.000	m
48	604-07894 CURB RAMP, CONCRETE, A	100.000	m2

CALL ORDER : 151  
 LETTING DATE :

CONTRACT ID : R -27047-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
49	604-07898 CURB RAMP, CONCRETE, D	23.000	m2
50	604-07901 CURB RAMP, CONCRETE, G	28.000	m2
51	604-07904 CURB RAMP, CONCRETE, L	455.000	m2
52	604-44251 STEPS, CONCRETE	2.710	m3
53	604-91531 SIDEWALK, CONCRETE, 100 mm	7,009.000	m2
54	605-06090 CURB, INTEGRAL, CONCRETE	4,954.000	m
55	605-06120 CURB, CONCRETE	41.000	m
56	605-06125 CURB, CONCRETE, MODIFIED	60.000	m
57	605-06210 CENTER CURB, C, CONCRETE	1,930.000	m
58	605-95635 CURB, CONCRETE, INTEGRAL, MODIFIED	54.000	m
59	606-07484 MILLED HMA SHOULDER CORRUGATIONS	1,025.000	m
60	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	150.000	m
61	610-07486 HMA FOR APPROACHES, TYPE A	775.000	Mg
62	611-05330 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 150 mm	2,992.000	m2
63	611-06497 MAILBOX ASSEMBLY, SINGLE	42.000	EACH
64	611-06498 MAILBOX ASSEMBLY, DOUBLE	8.000	EACH
65	615-06500 MONUMENT, A	1.000	EACH
66	615-06515 MONUMENT, D	13.000	EACH
67	616-02320 GEOTEXTILES	125.000	m2
68	616-06406 RIPRAP, REVETMENT	125.000	m2
69	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
70	621-06545 FERTILIZER	2.000	Mg
71	621-06553 SEED MIXTURE, R	173.000	kg
72	621-06557 SEED MIXTURE, T	120.000	kg
73	621-06565 MULCHING MATERIAL	10.100	Mg
74	621-06567 WATER	450.000	kL
75	621-06575 SODDING, NURSERY	24,951.000	m2
76	703-51030 REINFORCING STEEL	1,928.000	kg
77	703-51032 REINFORCING STEEL, EPOXY COATED	161.000	kg
78	714-02677 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1200 mm x 1200 mm	32.300	m
79	714-26707 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1800 mm x 1800 mm	61.000	m
80	714-44240 CONCRETE, A, STRUCTURES	12.400	m3
81	715-02628 SAFETY METAL END SECTION, 6:1, 375 mm	5.000	EACH
82	715-04548 GRATED BOX END SECTION, II, 6:1, 750 mm	1.000	EACH
83	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	524.000	m
84	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	6,562.000	m
85	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	66.000	m
86	715-05125 PIPE, TYPE 1, CIRCULAR, 750 mm	5.000	m
87	715-05146 PIPE, TYPE 2, CIRCULAR, 150 mm	21.000	m
88	715-05147 PIPE, TYPE 2, CIRCULAR, 200 mm	8.000	m
89	715-05148 PIPE, TYPE 2, CIRCULAR, 250 mm	10.000	m
90	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	355.000	m
91	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	447.000	m
92	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	830.000	m
93	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	1,450.000	m
94	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	586.000	m
95	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	128.000	m
96	715-05161 PIPE, TYPE 2, CIRCULAR, 1200 mm	184.000	m

CALL ORDER : 151  
 LETTING DATE :

CONTRACT ID : R -27047-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
97	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	199.000	m
98	715-26729 GRATED BOX END SECTION, II, 6:1, 375 mm	8.000	EACH
99	715-46005 PIPE END SECTION, 375 mm	22.000	EACH
100	715-46010 PIPE END SECTION, 450 mm	1.000	EACH
101	715-46030 PIPE END SECTION, 750 mm	1.000	EACH
102	718-06531 OUTLET PROTECTOR, 3	2.000	EACH
103	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
104	718-94889 AGGREGATE FOR UNDERDRAINS, 8	2,625.000	m3
105	718-99153 GEOTEXTILES FOR UNDERDRAIN	26,246.000	m2
106	720-04682 INLET	1.000	EACH
107	720-04682 INLET	1.000	EACH
108	720-44000 CASTING, ADJUST TO GRADE	15.000	EACH
109	720-45005 INLET, A2	3.000	EACH
110	720-45015 INLET, A8	30.000	EACH
111	720-45035 INLET, F7	4.000	EACH
112	720-45041 INLET, H5	1.000	EACH
113	720-45045 INLET, J10	14.000	EACH
114	720-45055 INLET, M10	7.000	EACH
115	720-45145 INLET, J10, MODIFIED	1.000	EACH
116	720-45270 PIPE CATCH BASIN, 450 mm	6.000	EACH
117	720-45275 PIPE CATCH BASIN, 600 mm	4.000	EACH
118	720-45410 MANHOLE, C4	28.000	EACH
119	720-45510 MANHOLE, C4, MODIFIED	2.000	EACH
120	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	2.600	m
121	720-92557 INLET, M13	1.000	EACH
122	720-93409 INLET, B15, MODIFIED	1.000	EACH
123	720-93411 INLET, C15, MODIFIED	2.000	EACH
124	720-93501 MANHOLE, L4	1.000	EACH
125	720-94612 MANHOLE, K4	3.000	EACH
126	720-95422 MANHOLE, J4	15.000	EACH
127	720-98174 INLET, B15	1.000	EACH
128	725-08587 PIPE LINER, THERMOPLASTIC, AREA 3.44 m2	81.000	EACH
129	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	4.000	EACH
130	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
131	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	15,520.000	m
132	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	25,860.000	m
133	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (ONLY)	2.000	EACH
134	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	106.000	m
135	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 200 mm	50.000	m
136	801-06605 BARRICADE, IIIA	27.000	EACH
137	801-06606 BARRICADE, IIIB	87.000	EACH
138	801-06625 DETOUR ROUTE MARKER ASSEMBLY	13.000	EACH
139	801-06640 CONSTRUCTION SIGN, A	84.000	EACH
140	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
141	801-06710 FLASHING ARROW SIGN	525.000	DAY
142	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
143	802-04893 REFERENCE POST	4.000	EACH
144	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	189.000	m

CALL ORDER : 151  
 LETTING DATE :

CONTRACT ID : R -27047-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001      ADDED TRAVEL LANES			
145	802-05702      SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	120.000	m
146	802-76025      SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	13.200	m2
147	802-76035      SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	63.500	m2
148	802-76040      SIGN, SHEET ENCLOSED LENS WITH LEGEND, 3.18 mm THICKNESS	2.700	m2
149	802-76045      SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	1.300	m2
150	802-76125      SPAN OVERHEAD SIGN STRUCTURE, CABLESPAN	2.000	EACH
151	803-06031      SIGN FOUNDATIONS, CONCRETE	9.500	m3
152	804-06770      DELINEATOR POST	2.000	EACH
153	805-01842      HANDHOLE, SIGNAL	19.000	EACH
154	805-02087      TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
155	805-06592      CONDUIT, STEEL, GALVANIZED, 50mm	635.000	m
156	805-78100      CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
157	805-78205      TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	6.000	EACH
158	805-78215      TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER ARROW, GREEN	4.000	EACH
159	805-78230      TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	2.000	EACH
160	805-78415      SPAN, CATENARY, AND TETHER	2.000	EACH
161	805-78420      DISCONNECT HANGER	4.000	EACH
162	805-78445      SIGNAL SERVICE	1.000	EACH
163	805-78467      SIGNAL CABLE, 3C 8GA.	18.000	m
164	805-78485      SIGNAL CABLE, 5C 14GA.	198.000	m
165	805-78490      SIGNAL CABLE, 7C 14GA.	236.000	m
166	805-78510      SIGNAL CABLE, 2C 16GA., SHIELDED	1,600.000	m
167	805-78746      PREFORMED LOOP DETECTORS	627.000	m
168	805-78906      SIGNAL SUPPORT FOUNDATION, 915 mm X 915 mm X 3.7m	4.000	EACH
169	805-78925      CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
170	805-81032      SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
171	805-92504      LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	12.000	EACH
172	806-06539      TEMPORARY SIGNAL INSTALLATION, MAINTAIN	LUMP	LUMP
173	806-53072      TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
174	808-03002      LINE, EPOXY, BROKEN, WHITE, 100 mm	648.000	m
175	808-03631      LINE, EPOXY, SOLID, WHITE, 100 mm	2,565.000	m
176	808-03632      LINE, EPOXY, SOLID, YELLOW, 100 mm	5,430.000	m
177	808-04896      LINE, EPOXY, BROKEN, YELLOW, 100 mm	462.000	m
178	808-05534      LINE, EPOXY, SOLID, WHITE, 200 mm	49.000	m
179	808-05535      TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, CROSSHATCH LINE,	12.000	m
180	808-06701      LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	184.000	m
181	808-06703      LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	2,710.000	m
182	808-06705      LINE, THERMOPLASTIC, SOLID, WHITE, 200 mm	130.000	m
183	808-06716      LINE, REMOVE	1,728.000	m
184	808-07310      TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW,	98.000	m
185	808-74805      TRANSVERSE MARKINGS, EPOXY, STOP LINE, 600 mm	63.000	m
186	808-74807      PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	62.000	EACH
187	808-74808      PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	48.000	EACH
188	808-75240      LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	2,000.000	m
189	808-75245      LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	1,467.000	m
190	808-75278      TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	174.000	m
191	808-75320      PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	3.000	EACH
192	808-75325      PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH



CALL ORDER : 151  
LETTING DATE :

CONTRACT ID : R -27047-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
193 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	300.000	EACH
194 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	589.000	EACH
195 808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	961.000	m
196 808-94455	TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 150 mm	449.000	m
197 808-98000	LINE, EPOXY, SOLID, YELLOW, 200 mm	509.000	m

CALL ORDER : 171  
 LETTING DATE :

CONTRACT ID : R -27514-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	15.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	30.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02241 GUARDRAIL, REMOVE	52.000	m
12	202-02279 CURB AND GUTTER, REMOVE	39.000	m
13	202-52710 SIDEWALK, CONCRETE, REMOVE	32.000	m2
14	203-02000 EXCAVATION, COMMON	32,607.000	m3
15	203-02070 BORROW	22,130.000	m3
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	644.000	Mg
17	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
18	205-06937 TEMPORARY SILT FENCE	1,248.000	m
19	207-08262 SUBGRADE TREATMENT, TYPE I	35,851.000	m2
20	211-07454 STRUCTURE BACKFILL	1,373.000	m3
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,348.000	Mg
22	303-60012 AGGREGATE, 2	262.000	Mg
23	303-97820 AGGREGATE, 8	262.000	Mg
24	306-08034 MILLING, ASPHALT, 38 mm	396.000	m2
25	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
26	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,282.000	Mg
27	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 MM	2,504.000	Mg
28	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	4,203.000	Mg
29	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	2,276.000	Mg
30	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	8,199.000	Mg
31	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	4,396.000	Mg
32	402-07450 HMA, TYPE A, WEDGE AND LEVEL	792.000	Mg
33	402-07453 HMA FOR TEMPORARY PAVEMENT	200.000	Mg
34	406-05520 ASPHALT FOR TACK COAT	40.000	Mg
35	601-01848 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 5	1.000	EACH
36	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 1.905 m SPACING	15.000	m
37	601-05999 CURVED TERMINAL END	2.000	EACH
38	601-06854 GUARDRAIL, W-BEAM, NESTED	1.000	EACH
39	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
40	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
41	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	1.000	EACH
42	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	351.000	m
43	604-07901 CURB RAMP, CONCRETE, G	6.000	m2
44	604-07902 CURB RAMP, CONCRETE, H	7.000	m2
45	605-06140 CURB AND GUTTER, CONCRETE	258.000	m
46	610-07486 HMA FOR APPROACHES, TYPE A	10.000	Mg
47	615-06505 MONUMENT, B	16.000	EACH
48	615-06510 MONUMENT, C	6.000	EACH

CALL ORDER : 171  
 LETTING DATE :

CONTRACT ID : R -27514-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
49	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
50	616-02320 GEOTEXTILES	7,075.000	m2
51	616-05688 RIPRAP, CLASS 1	436.000	Mg
52	616-05689 RIPRAP, CLASS 2	1,075.000	Mg
53	616-06405 RIPRAP, REVETMENT	3,618.000	Mg
54	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
55	621-06545 FERTILIZER	4.000	Mg
56	621-06559 MULCHED SEEDING, R	38,224.000	m2
57	621-06574 SODDING	3,049.000	m2
58	622-52436 SIGN, DO NOT MOW OR SPRAY	29.000	EACH
59	622-91786 SEEDLING	2,318.000	EACH
60	702-90915 CONCRETE, A	66.000	m3
61	703-51030 REINFORCING STEEL	6,526.000	kg
62	714-07534 CULVERT, PRECAST BOX, REINFORCED CONCRETE,	32.000	m
63	714-26702 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1800 mm x 900 mm	24.000	m
64	714-26717 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3000 mm x 1500 mm	48.000	m
65	714-26717 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3000 mm x 1500 mm	20.000	m
66	715-05019 PIPE, TYPE 1, CIRCULAR, 900 mm	37.000	m
67	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	4,497.000	m
68	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	230.000	m
69	715-05128 PIPE, TYPE 1, CIRCULAR, 1200 mm	36.000	m
70	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	34.000	m
71	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	54.000	m
72	715-05173 PIPE, TYPE 3, CIRCULAR, 600 mm	14.000	m
73	715-05242 PIPE, TYPE 1, DEFORMED, MIN. AREA 0.83 m2	30.000	m
74	715-05272 PIPE, TYPE 1, DEFORMED, MIN. AREA 3.44 m2	66.000	m
75	715-06004 CONCRETE ANCHOR, 1200 mm	2.000	EACH
76	715-06501 CONCRETE ANCHOR, MIN. AREA 0.83 m2	2.000	EACH
77	715-46005 PIPE END SECTION, 375 mm	8.000	EACH
78	715-46020 PIPE END SECTION, 600 mm	2.000	EACH
79	715-46040 PIPE END SECTION, 900 mm	2.000	EACH
80	718-06531 OUTLET PROTECTOR, 3	44.000	EACH
81	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
82	718-52610 AGGREGATE FOR UNDERDRAINS	944.000	m3
83	718-99153 GEOTEXTILES FOR UNDERDRAIN	8,414.000	m2
84	720-45030 INLET, E7	1.000	EACH
85	720-45055 INLET, M10	1.000	EACH
86	720-98174 INLET, B15	2.000	EACH
87	720-98555 INLET, C15	1.000	EACH
88	723-06660 WINGWALL	75.000	m2
89	801-04308 ROAD CLOSURE SIGN ASSEMBLY	14.000	EACH
90	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	3,304.000	m
91	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	1,680.000	m
92	801-06625 DETOUR ROUTE MARKER ASSEMBLY	22.000	EACH
93	801-06640 CONSTRUCTION SIGN, A	37.000	EACH
94	801-06645 CONSTRUCTION SIGN, B	22.000	EACH
95	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
96	801-07119 BARRICADE, III-B	36.000	m

CALL ORDER : 171  
 LETTING DATE :

CONTRACT ID : R -27514-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
97	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	51.000	m
98	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	28.000	m
99	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	6.000	m2
100	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	7.000	m2
101	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	419.000	m
102	808-06716 LINE, REMOVE	85.000	m
103	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	8,178.000	m
104	808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	125.000	m
105	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	28.000	m
106	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	8.000	EACH
107	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	8.000	EACH
108	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	1.000	EACH
109	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	422.000	EACH

CALL ORDER : 191  
 LETTING DATE :

CONTRACT ID : R -27795-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	622.000	m3
10	203-02070 BORROW	639.000	m3
11	205-03371 SEDIMENT REMOVE	10.000	m3
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	31.000	Mg
13	205-06937 TEMPORARY SILT FENCE	100.000	m
14	207-08263 SUBGRADE TREATMENT, TYPE IA	2,499.000	m2
15	211-07454 STRUCTURE BACKFILL	1.200	m3
16	213-08058 FLOWABLE BACKFILL	10.100	m3
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,302.000	Mg
18	304-07494 WIDENING WITH HMA, TYPE C	195.000	Mg
19	306-08036 MILLING, ASPHALT, 50 mm	6,689.000	m2
20	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	658.000	Mg
21	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	1,096.000	Mg
22	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	504.000	Mg
23	406-05520 ASPHALT FOR TACK COAT	4.200	Mg
24	610-07487 HMA FOR APPROACHES, TYPE B	15.000	Mg
25	615-06490 RIGHT OF WAY MARKER	13.000	EACH
26	615-06505 MONUMENT, B	6.000	EACH
27	615-06510 MONUMENT, C	1.000	EACH
28	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
29	621-06545 FERTILIZER	0.100	Mg
30	621-06557 SEED MIXTURE, T	34.000	kg
31	621-06559 MULCHED SEEDING, R	3,313.000	m2
32	621-06565 MULCHING MATERIAL	1.500	Mg
33	621-06567 WATER	7.600	kL
34	621-06575 SODDING, NURSERY	423.000	m2
35	715-05115 PIPE, TYPE 1, CIRCULAR, 150 mm	150.000	m
36	715-05116 PIPE, TYPE 1, CIRCULAR, 200 mm	150.000	m
37	715-05117 PIPE, TYPE 1, CIRCULAR, 250 mm	50.000	m
38	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	17.500	m
39	715-05596 PIPE EXTENSION, CIRCULAR, 450 mm	1.500	m
40	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	13.000	Mg
41	715-46010 PIPE END SECTION, 450 mm	3.000	EACH
42	715-46020 PIPE END SECTION, 600 mm	2.000	EACH
43	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	4,400.000	m
44	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
45	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	24.200	m
48	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	1.460	m2

CALL ORDER : 191  
 LETTING DATE :

CONTRACT ID : R -27795-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
49	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	1.620	m2
50	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	4.000	EACH
51	805-01842 HANDHOLE, SIGNAL	1.000	EACH
52	805-01879 SIGNAL SERVICE	1.000	EACH
53	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
54	805-04091 CONTROLLER AND CABINET, MENU DRIVEN, 2 PHASE	1.000	EACH
55	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	29.000	m
56	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm AMBER	4.000	EACH
57	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm RED	2.000	EACH
58	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
59	805-78420 DISCONNECT HANGER	3.000	EACH
60	805-78467 SIGNAL CABLE, 3C 8GA.	9.000	m
61	805-78485 SIGNAL CABLE, 5C 14GA.	189.000	m
62	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
63	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,432.000	m
64	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 200 mm	42.000	m
65	808-75215 LINE, THERMOPLASTIC, SOLID, WHITE, 300 mm	32.000	m
66	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	738.000	m
67	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	7.200	m
68	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
69	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000	EACH
70	808-75996 SNOWFLOWABLE RAISED PAVEMENT MARKER, REMOVE	65.000	EACH
71	808-75998 SNOWFLOWABLE RAISED PAVEMENT MARKER	65.000	EACH
72	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	371.000	m
73	808-99176 LINE, THERMOPLASTIC, SOLID, YELLOW, 600 mm	28.700	m

CALL ORDER : 231  
 LETTING DATE :

CONTRACT ID : R -28177-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	5.000	EACH
3	105-07040 FIELD OFFICE, C	30.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	90.000	MOS
6	105-08523 RADIO SERVICE	150.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-02240 PAVEMENT REMOVAL	2,890.000	m2
15	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
19	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
20	203-02010 EXCAVATION, ROCK	240.000	m3
21	203-02055 EMBANKMENT	1,723,156.000	m3
22	203-51223 EXCAVATION, WATERWAY	645.000	m3
23	204-02290 SETTLEMENT PLATE	14.000	EACH
24	204-08415 STAKES, SETTLEMENT	14.000	EACH
25	204-08552 VIBRATING WIRE SETTLEMENT SYSTEM	14.000	EACH
26	204-08553 DATA LOGGING SYSTEM	14.000	EACH
27	204-08554 HAND HELD VW READOUT	2.000	EACH
28	205-03371 SEDIMENT REMOVE	8,000.000	m3
29	205-06930 SPLASHPAD, RIPRAP	110.000	Mg
30	205-06932 TEMPORARY CHECK DAM, STRAW BALES	22.000	m
31	205-06933 TEMPORARY DITCH INLET PROTECTION	5.000	EACH
32	205-06935 TEMPORARY SEDIMENT BASIN	7.000	EACH
33	205-06936 TEMPORARY SEDIMENT TRAP	4,370.000	Mg
34	205-06937 TEMPORARY SILT FENCE	1,800.000	m
35	205-06938 TEMPORARY SLOPE DRAIN	2,915.000	m
36	206-51220 EXCAVATION, WET	740.000	m3
37	206-51225 EXCAVATION, DRY	239.000	m3
38	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	560.000	m3
39	206-51235 COFFERDAM	LUMP	LUMP
40	206-51817 SHEET PILING, STEEL	608.500	m2
41	207-08262 SUBGRADE TREATMENT, TYPE I	31,025.000	m2
42	210-07739 TEMPORARY	38.000	EACH
43	211-02050 B BORROW	275,999.000	m3
44	211-06467 AGGREGATE FOR END BENT BACKFILL	68.000	m3
45	211-07454 STRUCTURE BACKFILL	52,846.000	m3
46	213-08058 FLOWABLE BACKFILL	3.000	m3
47	213-52830 FLOWABLE MORTAR	14.000	m3
48	214-07202 GEOGRID, I	3,376.000	m2

CALL ORDER : 231  
 LETTING DATE :

CONTRACT ID : R -28177-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
49	214-07203 GEOGRID, II	9,603.000	m2
50	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,708.000	Mg
51	303-01180 COMPACTED AGGREGATE, NO. 53	2,440.000	Mg
52	303-60012 AGGREGATE, 2	8,000.000	Mg
53	305-05204 HMA FOR PATCHING	50.000	Mg
54	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
55	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	605.000	Mg
56	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	1,675.000	Mg
57	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	300.000	Mg
58	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	2,950.000	Mg
59	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 MM	1,540.000	Mg
60	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	8,815.000	Mg
61	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	3,505.000	Mg
62	402-07432 HMA SURFACE, TYPE A	240.000	Mg
63	402-07435 HMA INTERMEDIATE, TYPE A	400.000	Mg
64	406-05520 ASPHALT FOR TACK COAT	15.000	Mg
65	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
66	601-06228 IMPACT ATTENUATOR, CR, W1, TL-3	2.000	EACH
67	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	2.000	EACH
68	601-06411 IMPACT ATTENUATOR SPARE PARTS PACKAGE, CR, W1, TL-3	2.000	EACH
69	601-06454 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R2, W1, TL-3	2.000	EACH
70	601-94689 GUARDRAIL END TREATMENT, OS	6.000	EACH
71	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	165.000	m
72	602-06729 BARRIER DELINEATOR	134.000	EACH
73	603-06040 FENCE, FARM FIELD, 1190 mm	9,745.000	m
74	603-06045 FENCE, CHAIN LINK, 1220 mm	331.000	m
75	608-05741 WICK DRAIN	345,755.000	m
76	608-05742 DRAINAGE BLANKET	34,630.000	m3
77	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	317.800	m2
78	610-05330 PCCP FOR APPROACHES	440.000	m2
79	610-07486 HMA FOR APPROACHES, TYPE A	575.000	Mg
80	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
81	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
82	615-06490 RIGHT OF WAY MARKER	13.000	EACH
83	615-06505 MONUMENT, B	22.000	EACH
84	615-06510 MONUMENT, C	10.000	EACH
85	616-02320 GEOTEXTILES	10,705.000	m2
86	616-05688 RIPRAP, CLASS 1	1,488.000	Mg
87	616-05689 RIPRAP, CLASS 2	425.500	Mg
88	616-06405 RIPRAP, REVETMENT	7,742.000	Mg
89	616-06451 RIPRAP, UNIFORM	11.000	Mg
90	616-94426 GEOGRID	9,499.000	m2
91	619-04414 DRAIN EXTENSION	6.000	EACH
92	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	20.000	EACH
93	621-06545 FERTILIZER	170.000	Mg
94	621-06553 SEED MIXTURE, R	12,920.000	kg
95	621-06555 SEED MIXTURE, P	1,360.000	kg
96	621-06557 SEED MIXTURE, T	39,150.000	kg



CALL ORDER : 231  
 LETTING DATE :

CONTRACT ID : R -28177-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
97	621-06565 MULCHING MATERIAL	2,265.000	Mg
98	621-06567 WATER	780.000	kL
99	621-06574 SODDING	42,493.000	m2
100	622-91786 SEEDLING	800.000	EACH
101	701-06011 DYNAMIC PILE LOAD TEST	48.000	EACH
102	701-06012 TEST PILE, RESTRIKE	264.000	EACH
103	701-08253 PILE SLEEVES	54.000	EACH
104	701-51195 PILE, STEEL H, HP 310 X 79	3,754.800	m
105	701-91792 PILE TIP, STEEL H	236.000	EACH
106	701-92043 CORED HOLE IN ROCK, 457 mm	48.000	m
107	701-95780 PILE, STEEL H, HP 310 X 110	2,426.600	m
108	701-97874 PILE, STEEL H, REINFORCED CONCRETE ENCASED, HP 310 X 79	135.200	m
109	701-99086 PILE TIP, STEEL SHELL	28.000	EACH
110	702-51005 CONCRETE, A, SUBSTRUCTURE	609.900	m3
111	702-51015 CONCRETE, B, FOOTINGS	130.400	m3
112	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	660.000	kg
113	702-52376 CONCRETE, C, STRUCTURES	48.000	m3
114	702-92857 CONCRETE, C, SUBSTRUCTURE	653.000	m3
115	702-94656 CONCRETE, B	73.400	m3
116	703-51030 REINFORCING STEEL	87,862.000	kg
117	703-51032 REINFORCING STEEL, EPOXY COATED	391,913.000	kg
118	704-51002 CONCRETE, C, SUPERSTRUCTURE	2,333.300	m3
119	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
120	706-51020 CONCRETE, C, RAILING	277.800	m3
121	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 1143 mm X 406 mm	1,453.059	m
122	707-05985 STRUCTURAL MEMBERS, CONCRETE I-BEAM, IV, 1372 mm X 508 mm	886.350	m
123	707-05993 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 1524 mm X 1524 mm	496.200	m
124	709-51821 SURFACE SEAL	LUMP	LUMP
125	709-51821 SURFACE SEAL	LUMP	LUMP
126	709-51821 SURFACE SEAL	LUMP	LUMP
127	709-51821 SURFACE SEAL	LUMP	LUMP
128	709-51821 SURFACE SEAL	LUMP	LUMP
129	709-51821 SURFACE SEAL	LUMP	LUMP
130	709-51821 SURFACE SEAL	LUMP	LUMP
131	709-51821 SURFACE SEAL	LUMP	LUMP
132	709-51821 SURFACE SEAL	LUMP	LUMP
133	709-51821 SURFACE SEAL	LUMP	LUMP
134	709-51821 SURFACE SEAL	LUMP	LUMP
135	711-51035 STRUCTURAL STEEL	1,128.000	kg
136	711-51872 FILLET WELD, 6 mm	10.620	m
137	714-26702 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1800 mm x 900 mm	49.000	m
138	714-44240 CONCRETE, A, STRUCTURES	1.000	m3
139	714-93978 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1200 mm x 600 mm	126.000	m
140	715-02397 SAFETY METAL END SECTION, 4:1, 900 mm	8.000	EACH
141	715-02407 SAFETY METAL END SECTION, 4:1, 1200 mm	10.000	EACH
142	715-03475 SAFETY METAL END SECTION, 4:1, 375 mm	3.000	EACH
143	715-03476 SAFETY METAL END SECTION, 4:1, 600 mm	1.000	EACH
144	715-05019 PIPE, TYPE 1, CIRCULAR, 900 mm	523.000	m

CALL ORDER : 231  
 LETTING DATE :

CONTRACT ID : R -28177-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
145	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	3,440.000	m
146	715-05049 PIPE, TYPE 4, CIRCULAR, 200 mm	100.000	m
147	715-05051 PIPE, TYPE 4, CIRCULAR, 250 mm	100.000	m
148	715-05052 PIPE, TYPE 4, CIRCULAR, 300 mm	100.000	m
149	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	580.000	m
150	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	1,131.500	m
151	715-05128 PIPE, TYPE 1, CIRCULAR, 1200 mm	257.000	m
152	715-05141 PIPE, TYPE 1, CIRCULAR, 2100 mm	129.000	m
153	715-05146 PIPE, TYPE 2, CIRCULAR, 150 mm	100.000	m
154	715-05147 PIPE, TYPE 2, CIRCULAR, 200 mm	100.000	m
155	715-05148 PIPE, TYPE 2, CIRCULAR, 250 mm	100.000	m
156	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	45.000	m
157	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	100.000	m
158	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	100.000	m
159	715-05168 PIPE, TYPE 3, CIRCULAR, 300 mm	25.000	m
160	715-05177 PIPE, TYPE 3, CIRCULAR, 900 mm	143.000	m
161	715-05203 PIPE, TYPE 4, CIRCULAR, 100 mm	100.000	m
162	715-05208 PIPE, TYPE 4, CIRCULAR, 375 mm	100.000	m
163	715-05209 PIPE, TYPE 4, CIRCULAR, 450 mm	100.000	m
164	715-05370 PIPE, TYPE 3, DEFORMED, MIN. AREA 0.59 m2	129.000	m
165	715-05422 PIPE, SLOTTED DRAIN, 300 mm	375.000	m
166	715-07150 CONCRETE ANCHOR, 2100 mm	2.000	EACH
167	715-46000 PIPE END SECTION, 300 mm	3.000	EACH
168	715-46005 PIPE END SECTION, 375 mm	24.000	EACH
169	715-46040 PIPE END SECTION, 900 mm	17.000	EACH
170	715-91361 PIPE, PVC, 150 mm	120.000	m
171	716-07631 PIPE INSTALLATION, TRENCHLESS, 375 mm	21.000	m
172	716-07637 PIPE INSTALLATION, TRENCHLESS, 1200 mm	91.000	m
173	718-06528 OUTLET PROTECTOR, 1	22.000	EACH
174	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
175	718-08308 UNDERDRAIN, PATCHING	65.000	m
176	718-52610 AGGREGATE FOR UNDERDRAINS	584.000	m3
177	718-99153 GEOTEXTILES FOR UNDERDRAIN	5,307.000	m2
178	720-06607 SLOTTED DRAIN PIPE CLEANOUT PORT	4.000	EACH
179	720-45065 INLET, N12	26.000	EACH
180	720-45070 INLET, P12A	1.000	EACH
181	720-94612 MANHOLE, K4	1.000	EACH
182	723-06660 WINGWALL	45.000	m2
183	730-05910 GRATED BOX END SECTION, II 10:1, 0.6 m2	2.000	EACH
184	731-93945 FACE PANELS, CONCRETE	7,280.670	m2
185	731-93946 WALL ERECTION	7,280.670	m2
186	731-93947 LEVELING PAD, CONCRETE	1,004.374	m
187	732-06623 SLEEVE	28.000	EACH
188	801-04308 ROAD CLOSURE SIGN ASSEMBLY	23.000	EACH
189	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	6,000.000	m
190	801-06625 DETOUR ROUTE MARKER ASSEMBLY	22.000	EACH
191	801-06640 CONSTRUCTION SIGN, A	83.000	EACH
192	801-06645 CONSTRUCTION SIGN, B	8.000	EACH

CALL ORDER : 231  
 LETTING DATE :

CONTRACT ID : R -28177-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
193	801-06710 FLASHING ARROW SIGN	540.000	DAY
194	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
195	801-07118 BARRICADE, III-A	397.000	m
196	801-07119 BARRICADE, III-B	72.000	m
197	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	6.000	EACH
198	802-04893 REFERENCE POST	20.000	EACH
199	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	65.000	m
200	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	30.000	m
201	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	5.290	m2
202	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	7.830	m2
203	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	1.480	m2
204	808-06711 LINE, PAINT, BROKEN, WHITE, 100 mm	1,370.000	m
205	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	4,570.000	m
206	808-06714 LINE, PAINT, SOLID, YELLOW, 100 mm	4,740.000	m
207	808-06716 LINE, REMOVE	3,168.000	m
208	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 600 mm	10.000	m

CALL ORDER : 251  
 LETTING DATE :

CONTRACT ID : R -28214-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	4,918.750	LFT
11	202-93741 GUARD RAIL END TREATMENT, REMOVE	8.000	EACH
12	304-07783 HMA PATCHING, TYPE D	50.000	TON
13	305-97026 AGGREGATE, NO. 73	2,000.000	TON
14	306-08033 MILLING, ASPHALT, 1 IN.	102,319.000	SYS
15	306-08036 MILLING, ASPHALT, 2 IN.	6,064.000	SYS
16	306-08039 MILLING, ASPHALT REMOVAL	54,135.000	SYS
17	306-08043 MILLING, TRANSITION	7,399.000	SYS
18	401-05467 MILLED HMA CORRUGATIONS	55,956.000	LFT
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	13,836.000	TON
21	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 mm	21,371.000	TON
22	406-05520 ASPHALT FOR TACK COAT	80.600	TON
23	506-06333 PCCP PATCHING, FULL DEPTH	4,024.000	SYS
24	601-06035 GUARDRAIL, RESET	4,918.750	LFT
25	601-07050 GUARDRAIL END TREATMENT, OS, RESET	8.000	EACH
26	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	40.400	TON
27	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
28	612-60410 DRILLED HOLE FOR UNDERSEAL	673.000	EACH
29	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
30	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
31	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	6,100.000	LFT
32	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,100.000	LFT
33	801-06640 CONSTRUCTION SIGN, A	42.000	EACH
34	801-06710 FLASHING ARROW SIGN	300.000	DAY
35	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
36	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	14,679.000	LFT
37	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	28,037.000	LFT
38	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	7,967.000	LFT
39	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	780.000	LFT
40	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	26,928.000	LFT
41	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	913.000	EACH
42	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	913.000	EACH

CALL ORDER : 271  
 LETTING DATE :

CONTRACT ID : R -28284-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	REST AREA CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-07040 FIELD OFFICE, C	9.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	9.000	MOS
6	105-08523 RADIO SERVICE	9.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	84.100	CYS
12	203-02070 BORROW	83.110	CYS
13	205-06937 TEMPORARY SILT FENCE	270.000	LFT
14	210-03825 SHELTER	1.000	EACH
15	210-05714 PLAYGROUND	LUMP	LUMP
16	210-05714 PLAYGROUND	LUMP	LUMP
17	210-05714 PLAYGROUND	LUMP	LUMP
18	210-05758 BUILDING	LUMP	LUMP
19	210-06988 MASONRY	4.000	EACH
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	30.800	TON
21	303-04489 COMPACTED CRUSHED AGGREGATE, 8	77.600	TON
22	303-07662 STONE	7.700	TON
23	604-91531 SIDEWALK, CONCRETE, 4 IN.	122.000	SYS
24	610-07712 PCCP FOR APPROACHES, 6 IN.	16.500	SYS
25	611-03671 TRASH RECEPTACLE	4.000	EACH
26	616-02320 GEOTEXTILES	240.000	SYS
27	616-06405 RIPRAP, REVETMENT	2.000	TON
28	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
29	621-02770 EROSION CONTROL BLANKET	56.000	SYS
30	621-06560 MULCHED SEEDING, U	375.000	SYS
31	621-98038 MULCH, HARDWOOD SHREDDED BARK	4.800	CYS
32	622-05618 PLANT, BROADLEAF EVERGREEN, SPREADING, SEMISPREADING, 15 IN.	10.000	EACH
33	622-05642 PLANT, DECIDUOUS SHRUB, OVER 48 IN.	11.000	EACH
34	622-05748 TIMBER	90.000	LFT
35	622-05748 TIMBER	138.000	LFT
36	712-03812 BENCH	2.000	EACH
37	715-04612 PIPE	34.000	LFT
38	715-07556 FORCE MAIN	LUMP	LUMP
39	715-07556 FORCE MAIN	LUMP	LUMP
40	715-07556 FORCE MAIN	LUMP	LUMP
41	719-03975 BUILDING PLUMBING	LUMP	LUMP
42	720-02545 CASTING, 1	1.000	EACH
43	720-45275 PIPE CATCH BASIN, 24 IN.	1.000	EACH
44	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
45	802-04314 SIGN	1.000	EACH
46	802-07696 POST, WOOD, 6 IN. X 6 IN.	60.000	EACH
47	805-08490 INTERPRETIVE	1.000	EACH
48	807-03694 BUILDING ELECTRICAL	LUMP	LUMP

CALL ORDER : 351  
 LETTING DATE :

CONTRACT ID : R -28624-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS		
1 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
2 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
3 621-06559	MULCHED SEEDING, R	1,000.000	SYS
4 802-99060	SIGN AND SUPPORT, WOOD POST, REMOVE	1.000	EACH

CALL ORDER : 361  
 LETTING DATE :

CONTRACT ID : R -28625-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	6.000	EACH
3	105-07040 FIELD OFFICE, C	18.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	54.000	MOS
6	105-08523 RADIO SERVICE	108.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
9	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-02240 PAVEMENT REMOVAL	9,990.000	m2
15	202-02241 GUARDRAIL, REMOVE	295.000	m
16	202-02278 CURB, CONCRETE, REMOVE	1,579.000	m
17	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	233.000	m2
18	202-06541 REMOVE	4.000	EACH
19	203-02000 EXCAVATION, COMMON	23,473.000	m3
20	203-02070 BORROW	3,475.000	m3
21	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	14.400	Mg
22	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
23	205-06937 TEMPORARY SILT FENCE	2,874.000	m
24	207-08268 SUBGRADE TREATMENT, TYPE IV	65,590.000	m2
25	211-07454 STRUCTURE BACKFILL	8,603.000	m3
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,737.000	Mg
27	302-06464 SUBBASE FOR PCCP	14,388.000	m3
28	303-07449 COMPACTED AGGREGATE, NO. 73	505.000	Mg
29	304-07493 WIDENING WITH HMA, TYPE B	1,277.000	Mg
30	306-08432 MILLING, APPROACH	1,794.000	m2
31	402-05481 HMA BASE 25.0 mm, SHOULDER	320.000	Mg
32	402-07451 HMA, TYPE B, WEDGE AND LEVEL	516.000	Mg
33	402-07453 HMA FOR TEMPORARY PAVEMENT	7,388.000	Mg
34	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
35	501-06321 QC/QA-PCCP, 250 mm	16,510.000	m2
36	501-06322 QC/QA-PCCP, 275 mm	25,020.000	m2
37	501-06323 QC/QA-PCCP, 300 mm	21,157.000	m2
38	501-06727 CORING, PCCP	LUMP	LUMP
39	503-05240 D-1 CONTRACTION JOINT	9,725.000	m
40	506-06333 PCCP PATCHING, FULL DEPTH	80.000	m2
41	601-94689 GUARDRAIL END TREATMENT, OS	12.000	EACH
42	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	613.500	m
43	604-06069 CURB RAMP, CONCRETE	51.000	m2
44	604-91531 SIDEWALK, CONCRETE, 100 mm	1,451.000	m2
45	605-06090 CURB, INTEGRAL, CONCRETE	919.000	m
46	605-06095 CURB, INTEGRAL, B, CONCRETE	2,372.000	m
47	605-06145 CURB AND GUTTER, B, CONCRETE	245.000	m
48	605-06215 CENTER CURB, D, CONCRETE	920.000	m

CALL ORDER : 361  
 LETTING DATE :

CONTRACT ID : R -28625-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
49	610-07486 HMA FOR APPROACHES, TYPE A	718.000	Mg
50	610-07712 PCCP FOR APPROACHES, 150 mm	2,748.000	m2
51	611-06497 MAILBOX ASSEMBLY, SINGLE	20.000	EACH
52	615-06490 RIGHT OF WAY MARKER	126.000	EACH
53	615-06515 MONUMENT, D	4.000	EACH
54	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
55	616-02320 GEOTEXTILES	1,453.000	m2
56	616-05689 RIPRAP, CLASS 2	1,294.000	Mg
57	616-06405 RIPRAP, REVETMENT	168.000	Mg
58	621-02318 SEED MIXTURE, PRAIRIE GRASS	15.000	kg
59	621-02356 SEEDING, WETLAND	2.500	kg
60	621-06545 FERTILIZER	3.200	Mg
61	621-06554 SEED MIXTURE, U	590.000	kg
62	621-06557 SEED MIXTURE, T	322.000	kg
63	621-06565 MULCHING MATERIAL	18.100	Mg
64	621-06574 SODDING	485.000	m2
65	622-05648 PLANT, DECIDUOUS TREE, SINGLE STEM, 32 mm OR UNDER	34.000	EACH
66	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM OVER 32 TO 50 mm	12.000	EACH
67	622-91786 SEEDLING	425.000	EACH
68	714-06677 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 5400 mm X 1800 mm	42.000	m
69	714-08409 CULVERT, PRECAST BOX, REINFORCED CONCRETE,	46.500	m
70	714-26717 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3000 mm x 1500 mm	50.000	m
71	714-26724 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3600 mm x 1200 mm	9.000	m
72	715-02628 SAFETY METAL END SECTION, 6:1, 375 mm	34.000	EACH
73	715-02629 SAFETY METAL END SECTION, 6:1, 450 mm	4.000	EACH
74	715-02630 SAFETY METAL END SECTION, 6:1, 600 mm	1.000	EACH
75	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	181.000	m
76	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	6,018.000	m
77	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	260.000	m
78	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	1,617.000	m
79	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	64.000	m
80	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	956.000	m
81	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	368.000	m
82	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	555.000	m
83	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	76.000	m
84	715-46020 PIPE END SECTION, 600 mm	1.000	EACH
85	715-91361 PIPE, PVC, 150 mm	341.000	m
86	718-52610 AGGREGATE FOR UNDERDRAINS	1,443.000	m3
87	718-99153 GEOTEXTILES FOR UNDERDRAIN	21,089.000	m2
88	720-04596 MANHOLE, J-10 MODIFIED	2.000	EACH
89	720-44000 CASTING, ADJUST TO GRADE	34.000	EACH
90	720-45250 CATCH BASIN, K10	56.000	EACH
91	720-45251 CATCH BASIN, K10, MODIFIED	58.000	EACH
92	720-45410 MANHOLE, C4	35.000	EACH
93	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	7.000	m
94	720-93411 INLET, C15, MODIFIED	12.000	EACH
95	720-94612 MANHOLE, K4	3.000	EACH
96	720-95409 MANHOLE, J4, MODIFIED	1.000	EACH



CALL ORDER : 361  
 LETTING DATE :

CONTRACT ID : R -28625-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
97	720-95422 MANHOLE, J4	21.000	EACH
98	801-04308 ROAD CLOSURE SIGN ASSEMBLY	18.000	EACH
99	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	57,354.000	m
100	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	68.000	EACH
101	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 600 mm	170.000	m
102	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
103	801-06640 CONSTRUCTION SIGN, A	35.000	EACH
104	801-06645 CONSTRUCTION SIGN, B	36.000	EACH
105	801-06710 FLASHING ARROW SIGN	420.000	DAY
106	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
107	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	24.000	EACH
108	801-07118 BARRICADE, III-A	61.000	m
109	801-07119 BARRICADE, III-B	198.000	m
110	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	2,492.000	m
111	801-94295 SIGNAL HEAD, RELOCATE	48.000	EACH
112	802-03126 OVERHEAD SIGN, RELOCATE	8.000	EACH
113	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	148.200	m
114	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	44.000	m
115	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	40.000	EACH
116	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	33.200	m2
117	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	7.800	m2
118	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	4.050	m2
119	805-01842 HANDHOLE, SIGNAL	8.000	EACH
120	805-01844 CONDUIT, STEEL, GALVANIZED, 50 mm, UNDERGROUND	892.000	m
121	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER ARROW, GREEN	6.000	EACH
122	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	4.000	EACH
123	805-78485 SIGNAL CABLE, 5C 14GA.	508.000	m
124	805-78490 SIGNAL CABLE, 7C 14GA.	367.000	m
125	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	3,116.000	m
126	805-78746 PREFORMED LOOP DETECTORS	1,790.000	m
127	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	11.000	EACH
128	808-03002 LINE, EPOXY, BROKEN, WHITE, 100 mm	1,253.000	m
129	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	42.000	EACH
130	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	35.000	EACH
131	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	6,560.000	m
132	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	2,636.000	m
133	808-04767 LINE	277.000	m
134	808-04767 LINE	380.000	m
135	808-04896 LINE, EPOXY, BROKEN, YELLOW, 100 mm	87.000	m
136	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,253.000	m
137	808-06716 LINE, REMOVE	494.000	m
138	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 600 mm	171.000	m
139	808-75069 TRANSVERSE MARKINGS, PREFORMED PLASTIC, CROSSWALK LINE,	734.000	m
140	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	500.000	m
141	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	378.000	EACH
142	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	360.000	m
143	808-98000 LINE, EPOXY, SOLID, YELLOW, 200 mm	1,932.000	m
144	808-99176 LINE, THERMOPLASTIC, SOLID, YELLOW, 600 mm	33.000	m

CALL ORDER : 391  
 LETTING DATE :

CONTRACT ID : R -28641-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PARKING AREA RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02278 CURB, CONCRETE, REMOVE	1,321.500	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	187.000	SYS
11	203-02000 EXCAVATION, COMMON	1,700.000	CYS
12	303-01180 COMPACTED AGGREGATE, NO. 53	1,134.000	TON
13	303-93506 AGGREGATE, 2	380.000	CYS
14	304-07783 HMA PATCHING, TYPE D	50.000	TON
15	402-07784 HMA SURFACE, TYPE D	141.000	TON
16	402-07785 HMA INTERMEDIATE, TYPE D	234.000	TON
17	402-07786 HMA BASE, TYPE D	1,122.000	TON
18	406-05520 ASPHALT FOR TACK COAT	2.000	TON
19	503-03489 RETROFITTED TIE BARS	2,000.000	EACH
20	503-05240 D-1 CONTRACTION JOINT	6,128.500	LFT
21	506-06333 PCCP PATCHING, FULL DEPTH	18,397.000	SYS
22	604-07894 CURB RAMP, CONCRETE, A	55.340	SYS
23	604-07902 CURB RAMP, CONCRETE, H	4.440	SYS
24	604-91531 SIDEWALK, CONCRETE, 4 IN.	127.000	SYS
25	605-06120 CURB, CONCRETE	2,545.500	LFT
26	720-44000 CASTING, ADJUST TO GRADE	7.000	EACH
27	801-03290 CONSTRUCTION SIGN, C	14.000	EACH
28	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
29	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
30	801-07118 BARRICADE, III-A	250.000	LFT

CALL ORDER : 411  
 LETTING DATE :

CONTRACT ID : R -28683-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT PAVING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	2.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	203-02000 EXCAVATION, COMMON	344.000	CYS
8	205-08511 EROSION CONTROL	5.000	LFT
9	215-07043 CHEMICAL MODIFICATION, SOILS	3,100.000	SYS
10	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	774.000	TON
11	303-07449 COMPACTED AGGREGATE, NO. 73	22.000	TON
12	402-07432 HMA SURFACE, TYPE A	292.500	TON
13	402-07435 HMA INTERMEDIATE, TYPE A	487.500	TON
14	621-06748 SEEDING	1,612.000	SYS
15	715-02839 PIPE, POLYETHYLENE LINER, 24 IN.	60.000	LFT

CALL ORDER : 431  
 LETTING DATE :

CONTRACT ID : RS-27328-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	27.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02278 CURB, CONCRETE, REMOVE	420.000	LFT
11	202-52710 SIDEWALK, CONCRETE, REMOVE	1,250.120	SYS
12	203-02000 EXCAVATION, COMMON	177.780	CYS
13	203-02070 BORROW	20.000	CYS
14	213-04324 FLOWABLE FILL	50.000	CYS
15	303-01180 COMPACTED AGGREGATE, NO. 53	307.080	TON
16	304-07491 HMA PATCHING, TYPE C	1,060.000	TON
17	306-08033 MILLING, ASPHALT, 1 IN.	31,895.670	SYS
18	306-08034 MILLING, ASPHALT, 1 1/2 IN.	18,876.330	SYS
19	306-08043 MILLING, TRANSITION	2,000.000	SYS
20	306-08432 MILLING, APPROACH	9,935.060	SYS
21	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	4,265.460	TON
22	401-07385 QC/QA-HMA, 3, 76, INTERMEDIATE, 12.5 mm	3,610.880	TON
23	402-07442 HMA BASE, TYPE C	307.080	TON
24	402-07452 HMA, TYPE C, WEDGE AND LEVEL	150.000	TON
25	406-05520 ASPHALT FOR TACK COAT	32.020	TON
26	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
27	503-03489 RETROFITTED TIE BARS	30.000	EACH
28	503-05240 D-1 CONTRACTION JOINT	100.000	LFT
29	506-06333 PCCP PATCHING, FULL DEPTH	4,412.000	SYS
30	506-06334 PCCP PATCHING, PARTIAL DEPTH	100.000	SYS
31	507-07480 PCCP PROFILING	46,032.000	SYS
32	601-95344 HANDRAIL, PEDESTRIAN	75.000	LFT
33	604-06070 SIDEWALK, CONCRETE	600.000	SYS
34	604-07894 CURB RAMP, CONCRETE, A	186.600	SYS
35	604-07896 CURB RAMP, CONCRETE, B	355.520	SYS
36	604-07897 CURB RAMP, CONCRETE, C	33.330	SYS
37	604-07898 CURB RAMP, CONCRETE, D	38.730	SYS
38	604-07899 CURB RAMP, CONCRETE, E	41.340	SYS
39	605-01870 CURB, CONCRETE, A	215.000	LFT
40	610-07488 HMA FOR APPROACHES, TYPE C	819.640	TON
41	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
42	621-06567 WATER	2.000	KGAL
43	621-06575 SODDING, NURSERY	350.000	SYS
44	702-90915 CONCRETE, A	28.000	CYS
45	720-44000 CASTING, ADJUST TO GRADE	82.000	EACH
46	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	9,350.000	LFT
47	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,350.000	LFT
48	801-06640 CONSTRUCTION SIGN, A	67.000	EACH

CALL ORDER : 431  
 LETTING DATE :

CONTRACT ID : RS-27328-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
50	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	2.000	EACH
51	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	20.000	EACH
52	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	8,375.000	LFT
53	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	837.500	LFT
54	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,680.000	LFT
55	805-96014 SAW CUT, FULL DEPTH	5,000.000	LFT
56	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	2,500.000	LFT
57	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	4,110.000	LFT
58	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	16,440.000	LFT
59	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	16,440.000	LFT
60	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	70.000	LFT
61	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	22,062.000	LFT
62	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	150.000	LFT
63	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	730.000	LFT
64	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	21,974.000	LFT
65	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	727.000	LFT
66	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,856.000	LFT
67	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	18.000	EACH
68	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	6.000	EACH
69	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
70	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	126.000	EACH
71	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	126.000	EACH

CALL ORDER : 451  
 LETTING DATE :

CONTRACT ID : RS-28225-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	8.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	3,534.000	LFT
11	202-04089 SIGN, SHEET, REMOVE	3.000	EACH
12	202-62420 BRIDGE RAILING, REMOVE	232.000	LFT
13	202-93741 GUARD RAIL END TREATMENT, REMOVE	9.000	EACH
14	203-90014 LINEAR GRADING	19.500	STA
15	211-07454 STRUCTURE BACKFILL	14.600	CYS
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	275.000	TON
17	304-07783 HMA PATCHING, TYPE D	1,525.000	TON
18	304-07789 WIDENING WITH HMA, TYPE D	485.000	TON
19	306-08033 MILLING, ASPHALT, 1 IN.	104,564.000	SYS
20	306-08036 MILLING, ASPHALT, 2 IN.	133,810.000	SYS
21	306-08041 MILLING, PCCP	826.000	SYS
22	306-08043 MILLING, TRANSITION	9,040.000	SYS
23	306-08432 MILLING, APPROACH	19,300.000	SYS
24	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
25	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	20,560.000	TON
26	401-07399 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	47,270.000	TON
27	402-07787 HMA, TYPE D, WEDGE AND LEVEL	7,900.000	TON
28	406-05520 ASPHALT FOR TACK COAT	204.000	TON
29	601-01522 GUARDRAIL TRANSITION TYPE TGB	8.000	EACH
30	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	2.000	EACH
31	601-01867 GUARDRAIL TRANSITION, TGB RETROFIT	4.000	EACH
32	601-06035 GUARDRAIL, RESET	657.000	LFT
33	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
34	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
35	601-07050 GUARDRAIL END TREATMENT, OS, RESET	8.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
37	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	3,375.000	LFT
38	610-07788 HMA FOR APPROACHES, TYPE D	5,400.000	TON
39	611-02825 MAILBOX ASSEMBLY, TRIPLE	4.000	EACH
40	611-06497 MAILBOX ASSEMBLY, SINGLE	75.000	EACH
41	611-06498 MAILBOX ASSEMBLY, DOUBLE	12.000	EACH
42	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
43	616-02320 GEOTEXTILES	370.000	SYS
44	616-06451 RIPRAP, UNIFORM	650.000	TON
45	621-06574 SODDING	2,100.000	SYS
46	706-08188 RAILING, TR	252.000	LFT
47	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN.	9.000	EACH
48	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	110.000	LFT

CALL ORDER : 451  
 LETTING DATE :

CONTRACT ID : RS-28225-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	76.000	LFT
50	718-52610 AGGREGATE FOR UNDERDRAINS	170.000	CYS
51	718-99153 GEOTEXTILES FOR UNDERDRAIN	1,274.000	SYS
52	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	14,700.000	LFT
53	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,950.000	LFT
54	801-06640 CONSTRUCTION SIGN, A	62.000	EACH
55	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
56	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
57	802-91122 SIGN, GROUND MOUNTED, RESET	12.000	EACH
58	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	11.000	EACH
59	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	6,480.000	LFT
60	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,544.000	LFT
61	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	20.000	EACH
62	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	803.000	LFT
63	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	11,578.000	LFT
64	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	72,020.000	LFT
65	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	58,300.000	LFT
66	808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	1,087.000	LFT
67	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	331.000	LFT
68	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	30.000	EACH
69	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	6.000	EACH
70	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,324.000	EACH
71	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,605.000	EACH
72	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	6,542.000	LFT

CALL ORDER : 471  
 LETTING DATE :

CONTRACT ID : RS-28231-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	8.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	313.000	LFT
11	202-93741 GUARD RAIL END TREATMENT, REMOVE	22.000	EACH
12	303-07449 COMPACTED AGGREGATE, NO. 73	100.000	TON
13	304-07490 HMA PATCHING, TYPE B	1,000.000	TON
14	306-08033 MILLING, ASPHALT, 1 IN.	34,337.000	SYS
15	306-08034 MILLING, ASPHALT, 1 1/2 IN.	164,863.000	SYS
16	306-08432 MILLING, APPROACH	1,498.000	SYS
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	16,434.000	TON
19	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	22,668.000	TON
20	406-05520 ASPHALT FOR TACK COAT	91.000	TON
21	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
22	601-94689 GUARDRAIL END TREATMENT, OS	22.000	EACH
23	604-07900 CURB RAMP, CONCRETE, F	14.300	SYS
24	604-07901 CURB RAMP, CONCRETE, G	49.000	SYS
25	604-07902 CURB RAMP, CONCRETE, H	6.300	SYS
26	604-07903 CURB RAMP, CONCRETE, K	8.900	SYS
27	610-07487 HMA FOR APPROACHES, TYPE B	2,700.000	TON
28	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	6,200.000	LFT
29	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,200.000	LFT
30	801-06640 CONSTRUCTION SIGN, A	92.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,104.000	LFT
33	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,104.000	LFT
34	808-01296 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORDS (STOP AHEAD)	1.000	EACH
35	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	10,733.000	LFT
36	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	62,000.000	LFT
37	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	53,242.000	LFT
38	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	162.000	LFT
39	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	209.000	LFT
40	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	406.000	LFT
41	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
42	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
43	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,112.000	EACH
44	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,112.000	EACH



CALL ORDER : 491  
 LETTING DATE :

CONTRACT ID : RS-28406-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE AND WIDENING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02241 GUARDRAIL, REMOVE	652.000	LFT
8	202-02255 TREE, 18 IN., REMOVE	1.000	EACH
9	202-02260 TREE, 30 IN., REMOVE	5.000	EACH
10	202-02270 TREE, 60 IN., REMOVE	2.000	EACH
11	202-02271 HEADWALL, REMOVE	3.000	EACH
12	202-04095 TREE, 54 IN., REMOVE	1.000	EACH
13	202-91010 TREE, 24 IN., REMOVE	3.000	EACH
14	202-91011 TREE, 36 IN., REMOVE	3.000	EACH
15	202-93741 GUARD RAIL END TREATMENT, REMOVE	10.000	EACH
16	203-02070 BORROW	100.000	CYS
17	203-90014 LINEAR GRADING	23.220	STA
18	211-07454 STRUCTURE BACKFILL	20.000	CYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,085.000	TON
20	303-07449 COMPACTED AGGREGATE, NO. 73	2,263.000	TON
21	304-07493 WIDENING WITH HMA, TYPE B	6,146.000	TON
22	306-08033 MILLING, ASPHALT, 1 IN.	6,890.000	SYS
23	306-08034 MILLING, ASPHALT, 1 1/2 IN.	1,391.000	SYS
24	306-08037 MILLING, ASPHALT, 3 IN.	14,702.000	SYS
25	306-08043 MILLING, TRANSITION	4,701.000	SYS
26	306-08432 MILLING, APPROACH	4,295.000	SYS
27	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
28	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	8,422.000	TON
29	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3,881.000	TON
30	402-07432 HMA SURFACE, TYPE A	1,882.000	TON
31	402-07450 HMA, TYPE A, WEDGE AND LEVEL	1,877.000	TON
32	402-07451 HMA, TYPE B, WEDGE AND LEVEL	7,640.000	TON
33	406-05520 ASPHALT FOR TACK COAT	75.000	TON
34	507-07479 HMA PARTIAL DEPTH PATCH	100.000	TON
35	601-91426 GUARD RAIL TERMINAL END SECTION, A	3.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	10.000	EACH
37	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,390.000	LFT
38	610-07486 HMA FOR APPROACHES, TYPE A	2,372.000	TON
39	611-06497 MAILBOX ASSEMBLY, SINGLE	8.000	EACH
40	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	30.000	EACH
41	615-06520 MONUMENT, RE-ESTABLISH	2.000	EACH
42	616-02320 GEOTEXTILES	9,120.000	SYS
43	616-06451 RIPRAP, UNIFORM	1,708.000	TON
44	621-02770 EROSION CONTROL BLANKET	1,548.000	SYS
45	715-01662 PIPE CLEANING, 12 IN. TO 48 IN. DIA.	71.000	LFT
46	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	60.000	LFT
47	715-05595 PIPE EXTENSION, CIRCULAR, 15 IN.	7.000	LFT
48	715-05597 PIPE EXTENSION, CIRCULAR, 24 IN.	8.000	LFT

CALL ORDER : 491  
 LETTING DATE :

CONTRACT ID : RS-28406-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE AND WIDENING		
49	715-05756 PIPE EXTENSION, CIRCULAR, 12 IN.	7.000	LFT
50	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
51	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
52	720-99315 CLEAN EXISTING CATCH BASINS	1.000	EACH
53	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,190.000	LFT
54	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,540.000	LFT
55	801-06640 CONSTRUCTION SIGN, A	27.000	EACH
56	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
57	801-92448 CONSTRUCTION SIGNS, MOBILE	600.000	DAY
58	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	308.000	LFT
59	802-05705 SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	112.000	LFT
60	802-91122 SIGN, GROUND MOUNTED, RESET	26.000	EACH
61	804-06771 DELINEATOR POST, FLEXIBLE	40.000	EACH
62	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	4,812.000	LFT
63	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	70,800.000	LFT
64	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	54,662.000	LFT
65	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	110.000	LFT
66	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	817.000	EACH
67	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	817.000	EACH

CALL ORDER : 511  
 LETTING DATE :

CONTRACT ID : RS-28587-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-07039 FIELD OFFICE, B	4.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	8.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	1,040.000	SYS
9	202-90277 DETECTOR HOUSING, REMOVE	17.000	EACH
10	202-93741 GUARD RAIL END TREATMENT, REMOVE	18.000	EACH
11	203-02070 BORROW	100.000	CYS
12	203-90014 LINEAR GRADING	15.000	STA
13	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	745.000	TON
14	303-07449 COMPACTED AGGREGATE, NO. 73	2,890.000	TON
15	304-07491 HMA PATCHING, TYPE C	100.000	TON
16	304-07494 WIDENING WITH HMA, TYPE C	1,246.000	TON
17	306-08034 MILLING, ASPHALT, 1 1/2 IN.	200,619.000	SYS
18	306-08432 MILLING, APPROACH	4,840.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	16,132.000	TON
21	402-07452 HMA, TYPE C, WEDGE AND LEVEL	993.000	TON
22	406-05520 ASPHALT FOR TACK COAT	51.000	TON
23	601-94689 GUARDRAIL END TREATMENT, OS	14.000	EACH
24	601-94690 GUARDRAIL END TREATMENT, MS	4.000	EACH
25	606-07484 MILLED HMA SHOULDER CORRUGATIONS	91,126.000	LFT
26	610-07486 HMA FOR APPROACHES, TYPE A	403.000	TON
27	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	68.200	TON
28	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
29	612-60410 DRILLED HOLE FOR UNDERSEAL	960.000	EACH
30	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
31	725-08079 PIPE LINER, THERMOPLASTIC, AREA 14.7 SFT.	148.000	LFT
32	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	9,261.000	LFT
33	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,261.000	LFT
34	801-06640 CONSTRUCTION SIGN, A	48.000	EACH
35	801-06710 FLASHING ARROW SIGN	30.000	DAY
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
38	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	6,960.000	LFT
39	805-78785 SIGNAL DETECTOR HOUSING	17.000	EACH
40	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,615.000	LFT
41	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	147,583.000	LFT
42	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	53,687.000	LFT
43	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	405.000	LFT
44	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,800.000	LFT
45	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	1,800.000	LFT
46	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	5.000	EACH
47	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	5.000	EACH
48	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	72.000	LFT

CALL ORDER : 511  
LETTING DATE :

CONTRACT ID : RS-28587-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49 808-74805	TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	466.000	LFT
50 808-74807	PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	31.000	EACH
51 808-74808	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	22.000	EACH
52 808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	17,827.000	LFT
53 808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	14,550.000	LFT
54 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	722.000	EACH
55 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	807.000	EACH

CALL ORDER : 521  
 LETTING DATE :

CONTRACT ID : RS-28590-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06899 RADIO	1.000	EACH
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08523 RADIO SERVICE	6.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-90277 DETECTOR HOUSING, REMOVE	6.000	EACH
12	202-93741 GUARD RAIL END TREATMENT, REMOVE	2.000	EACH
13	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	120.000	TON
14	304-07491 HMA PATCHING, TYPE C	361.000	TON
15	306-08034 MILLING, ASPHALT, 1 1/2 IN.	166,202.000	SYS
16	306-08432 MILLING, APPROACH	3,078.000	SYS
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	401-07330 QC/QA-HMA, 5, 70, SURFACE, 9.5 mm	13,712.000	TON
19	406-05520 ASPHALT FOR TACK COAT	43.000	TON
20	507-07479 HMA PARTIAL DEPTH PATCH	81.000	TON
21	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
22	606-07484 MILLED HMA SHOULDER CORRUGATIONS	94,406.000	LFT
23	610-07486 HMA FOR APPROACHES, TYPE A	254.000	TON
24	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
25	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,485.000	LFT
26	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,485.000	LFT
27	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
28	801-06710 FLASHING ARROW SIGN	60.000	DAY
29	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
30	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
31	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,918.000	LFT
32	805-78785 SIGNAL DETECTOR HOUSING	7.000	EACH
33	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	970.000	LFT
34	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	48,690.000	LFT
35	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	49,579.000	LFT
36	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	192.000	LFT
37	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	17.000	EACH
38	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	17.000	EACH
39	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	10,745.000	LFT
40	808-75059 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	11,216.000	LFT
41	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,239.000	EACH
42	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,239.000	EACH

CALL ORDER : 531  
 LETTING DATE :

CONTRACT ID : RS-28593-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-07039 FIELD OFFICE, B	9.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02271 HEADWALL, REMOVE	9.000	EACH
10	203-90014 LINEAR GRADING	87.000	STA
11	213-04324 FLOWABLE FILL	90.000	CYS
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,390.000	TON
13	303-07449 COMPACTED AGGREGATE, NO. 73	6,000.000	TON
14	304-07490 HMA PATCHING, TYPE B	3,849.000	TON
15	304-07492 WIDENING WITH HMA, TYPE A	830.000	TON
16	306-08034 MILLING, ASPHALT, 1 1/2 IN.	141,718.000	SYS
17	306-08043 MILLING, TRANSITION	8,240.000	SYS
18	306-08432 MILLING, APPROACH	6,564.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	12,700.000	TON
21	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	20,800.000	TON
22	402-07432 HMA SURFACE, TYPE A	600.000	TON
23	402-07435 HMA INTERMEDIATE, TYPE A	1,000.000	TON
24	402-07451 HMA, TYPE B, WEDGE AND LEVEL	700.000	TON
25	406-05520 ASPHALT FOR TACK COAT	89.000	TON
26	608-04395 AGGREGATE FOR SHOULDER DRAINS	130.000	TON
27	610-07486 HMA FOR APPROACHES, TYPE A	1,352.000	TON
28	611-06497 MAILBOX ASSEMBLY, SINGLE	9.000	EACH
29	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	34.000	EACH
30	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	34.100	TON
31	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
32	612-60410 DRILLED HOLE FOR UNDERSEAL	480.000	EACH
33	615-06520 MONUMENT, RE-ESTABLISH	1.000	EACH
34	615-06527 MONUMENT, SECTION CORNER	16.000	EACH
35	616-02320 GEOTEXTILES	624.000	SYS
36	616-06405 RIPRAP, REVETMENT	484.000	TON
37	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	10.000	LFT
38	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	140.000	LFT
39	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	98.000	LFT
40	715-05595 PIPE EXTENSION, CIRCULAR, 15 IN.	9.000	LFT
41	715-05596 PIPE EXTENSION, CIRCULAR, 18 IN.	6.000	LFT
42	715-05889 PIPE EXTENSION, CIRCULAR, 30 IN.	6.000	LFT
43	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	66.000	TON
44	715-46000 PIPE END SECTION, 12 IN.	1.000	EACH
45	715-46005 PIPE END SECTION, 15 IN.	10.000	EACH
46	715-46010 PIPE END SECTION, 18 IN.	6.000	EACH
47	715-46030 PIPE END SECTION, 30 IN.	3.000	EACH
48	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH

CALL ORDER : 531  
 LETTING DATE :

CONTRACT ID : RS-28593-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	ASPHALT RESURFACE			
49	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	10,575.000	LFT
50	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,290.000	LFT
51	801-06640	CONSTRUCTION SIGN, A	32.000	EACH
52	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
53	801-92448	CONSTRUCTION SIGNS, MOBILE	300.000	DAY
54	804-06771	DELINEATOR POST, FLEXIBLE	50.000	EACH
55	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	11,896.000	LFT
56	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	105,888.000	LFT
57	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	23,366.000	LFT
58	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	61.000	LFT
59	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
60	808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH
61	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	903.000	EACH
62	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	903.000	EACH
63	808-97323	LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	144.000	LFT

CALL ORDER : 541  
 LETTING DATE :

CONTRACT ID : RS-28600-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06899 RADIO	1.000	EACH
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08523 RADIO SERVICE	6.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-90277 DETECTOR HOUSING, REMOVE	6.000	EACH
11	202-93741 GUARD RAIL END TREATMENT, REMOVE	8.000	EACH
12	203-90014 LINEAR GRADING	10.000	STA
13	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	260.000	TON
14	303-01180 COMPACTED AGGREGATE, NO. 53	1,500.000	TON
15	304-07490 HMA PATCHING, TYPE B	530.000	TON
16	304-07492 WIDENING WITH HMA, TYPE A	160.000	TON
17	306-08033 MILLING, ASPHALT, 1 IN.	187,500.000	SYS
18	306-08043 MILLING, TRANSITION	1,200.000	SYS
19	306-08432 MILLING, APPROACH	25,700.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	10,455.000	TON
22	402-07432 HMA SURFACE, TYPE A	5,075.000	TON
23	406-05520 ASPHALT FOR TACK COAT	55.000	TON
24	507-07479 HMA PARTIAL DEPTH PATCH	50.000	TON
25	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
26	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
27	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
28	610-07486 HMA FOR APPROACHES, TYPE A	2,800.000	TON
29	611-06497 MAILBOX ASSEMBLY, SINGLE	10.000	EACH
30	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	20.000	EACH
31	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	34.100	TON
32	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
33	612-60410 DRILLED HOLE FOR UNDERSEAL	480.000	EACH
34	615-06520 MONUMENT, RE-ESTABLISH	2.000	EACH
35	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
36	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	9,500.000	LFT
37	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,500.000	LFT
38	801-06640 CONSTRUCTION SIGN, A	42.000	EACH
39	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
40	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
41	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	14.000	LFT
42	802-05705 SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	28.000	LFT
43	802-91122 SIGN, GROUND MOUNTED, RESET	3.000	EACH
44	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	4,500.000	LFT
45	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
46	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,400.000	LFT
47	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	90,100.000	LFT
48	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	23,500.000	LFT



CALL ORDER : 541  
LETTING DATE :

CONTRACT ID : RS-28600-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49 808-04896	LINE, EPOXY, BROKEN, YELLOW, 4 IN.	7,690.000	LFT
50 808-07310	TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW,	975.000	LFT
51 808-74805	TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	280.000	LFT
52 808-74807	PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	8.000	EACH
53 808-74808	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	8.000	EACH
54 808-75078	TRANSVERSE MARKINGS, PAINT, SOLID, YELLOW CROSSHATCH LINE,	344.000	LFT
55 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,000.000	EACH
56 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1,000.000	EACH
57 808-94455	TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 6 IN.	170.000	LFT
58 808-98000	LINE, EPOXY, SOLID, YELLOW, 8 IN.	8,440.000	LFT

CALL ORDER : 551  
 LETTING DATE :

CONTRACT ID : RS-28601-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	6.000	EACH
3	105-07039 FIELD OFFICE, B	6.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
6	105-08523 RADIO SERVICE	6.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-90277 DETECTOR HOUSING, REMOVE	4.000	EACH
13	202-93741 GUARD RAIL END TREATMENT, REMOVE	8.000	EACH
14	203-90014 LINEAR GRADING	4.000	STA
15	210-04901 RETROFIT	100.000	LFT
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	50.000	TON
17	303-01180 COMPACTED AGGREGATE, NO. 53	691.000	TON
18	304-07490 HMA PATCHING, TYPE B	670.000	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN.	25,590.000	SYS
20	306-08042 MILLING, SCARIFICATION/PROFILE	129,550.000	SYS
21	306-08043 MILLING, TRANSITION	1,340.000	SYS
22	306-08432 MILLING, APPROACH	7,400.000	SYS
23	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
24	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	9,700.000	TON
25	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	1,670.000	TON
26	402-07432 HMA SURFACE, TYPE A	1,553.000	TON
27	406-05520 ASPHALT FOR TACK COAT	41.000	TON
28	507-07479 HMA PARTIAL DEPTH PATCH	50.000	TON
29	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
30	604-07894 CURB RAMP, CONCRETE, A	62.000	SYS
31	605-06144 CURB AND GUTTER, A, CONCRETE	6.000	LFT
32	610-07486 HMA FOR APPROACHES, TYPE A	680.000	TON
33	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	10.000	EACH
34	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	35.000	TON
35	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
36	612-60410 DRILLED HOLE FOR UNDERSEAL	480.000	EACH
37	615-06520 MONUMENT, RE-ESTABLISH	5.000	EACH
38	615-06527 MONUMENT, SECTION CORNER	6.000	EACH
39	621-06574 SODDING	100.000	SYS
40	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	490.000	LFT
41	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
42	720-45085 INLET, T14	2.000	EACH
43	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,138.000	LFT
44	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8,138.000	LFT
45	801-06640 CONSTRUCTION SIGN, A	46.000	EACH
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	801-92448 CONSTRUCTION SIGNS, MOBILE	340.000	DAY
48	802-76055 SIGN POST, A	24.000	LFT

CALL ORDER : 551  
 LETTING DATE :

CONTRACT ID : RS-28601-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	802-91122 SIGN, GROUND MOUNTED, RESET	1.000	EACH
50	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	12,400.000	LFT
51	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
52	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	4,000.000	LFT
53	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	88,138.000	LFT
54	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	15,105.000	LFT
55	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	26,943.000	LFT
56	808-07310 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW,	364.000	LFT
57	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	263.000	LFT
58	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	2.000	EACH
59	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	2.000	EACH
60	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	841.000	EACH
61	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	841.000	EACH
62	808-98000 LINE, EPOXY, SOLID, YELLOW, 8 IN.	1,768.000	LFT

CALL ORDER : 561  
 LETTING DATE :

CONTRACT ID : RS-28602-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-07039 FIELD OFFICE, B	6.000	MOS
4	105-08523 RADIO SERVICE	6.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-93741 GUARD RAIL END TREATMENT, REMOVE	4.000	EACH
11	303-07449 COMPACTED AGGREGATE, NO. 73	1,310.000	TON
12	304-07490 HMA PATCHING, TYPE B	100.000	TON
13	306-08042 MILLING, SCARIFICATION/PROFILE	49,000.000	SYS
14	306-08043 MILLING, TRANSITION	400.000	SYS
15	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
16	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	4,109.000	TON
17	402-07432 HMA SURFACE, TYPE A	123.000	TON
18	406-05520 ASPHALT FOR TACK COAT	13.000	TON
19	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
20	610-07486 HMA FOR APPROACHES, TYPE A	295.000	TON
21	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	35.000	TON
22	612-60410 DRILLED HOLE FOR UNDERSEAL	450.000	EACH
23	615-06520 MONUMENT, RE-ESTABLISH	3.000	EACH
24	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,421.000	LFT
25	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,421.000	LFT
26	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	801-92448 CONSTRUCTION SIGNS, MOBILE	340.000	DAY
29	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	28,420.000	LFT
30	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2,753.000	LFT
31	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	10,330.000	LFT
32	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	18.000	LFT
33	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	270.000	EACH
34	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	270.000	EACH

CALL ORDER : 571  
 LETTING DATE :

CONTRACT ID : RS-28603-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06899 RADIO	1.000	EACH
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08523 RADIO SERVICE	6.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	65.000	TON
12	303-07449 COMPACTED AGGREGATE, NO. 73	1,520.000	TON
13	304-07490 HMA PATCHING, TYPE B	65.000	TON
14	306-08042 MILLING, SCARIFICATION/PROFILE	89,700.000	SYS
15	306-08043 MILLING, TRANSITION	1,080.000	SYS
16	306-08432 MILLING, APPROACH	6,000.000	SYS
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	7,210.000	TON
19	402-07432 HMA SURFACE, TYPE A	540.000	TON
20	406-05520 ASPHALT FOR TACK COAT	20.000	TON
21	507-07479 HMA PARTIAL DEPTH PATCH	200.000	TON
22	610-07486 HMA FOR APPROACHES, TYPE A	600.000	TON
23	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	35.000	TON
24	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
25	612-60410 DRILLED HOLE FOR UNDERSEAL	480.000	EACH
26	711-91996 REPAIR EXISTING STRUCTURE	LUMP	LUMP
27	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,750.000	LFT
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,750.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	25.000	EACH
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	801-92448 CONSTRUCTION SIGNS, MOBILE	90.000	DAY
32	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	65,042.000	LFT
33	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	38,239.000	LFT
34	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	2,888.000	LFT
35	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	86.000	LFT
36	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	680.000	EACH
37	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	680.000	EACH

CALL ORDER : 581  
 LETTING DATE :

CONTRACT ID : RS-28605-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-07039 FIELD OFFICE, B	6.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-96133 PIPE, REMOVE	425.000	LFT
10	203-90014 LINEAR GRADING	4.000	STA
11	213-04324 FLOWABLE FILL	150.000	CYS
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	889.000	TON
13	303-01180 COMPACTED AGGREGATE, NO. 53	1,085.000	TON
14	304-07490 HMA PATCHING, TYPE B	575.000	TON
15	304-07493 WIDENING WITH HMA, TYPE B	677.000	TON
16	306-08034 MILLING, ASPHALT, 1 1/2 IN.	8,710.000	SYS
17	306-08042 MILLING, SCARIFICATION/PROFILE	111,475.000	SYS
18	306-08043 MILLING, TRANSITION	330.000	SYS
19	306-08432 MILLING, APPROACH	7,765.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	11,215.000	TON
22	402-07451 HMA, TYPE B, WEDGE AND LEVEL	20.000	TON
23	406-05520 ASPHALT FOR TACK COAT	36.000	TON
24	604-06070 SIDEWALK, CONCRETE	80.000	SYS
25	604-07894 CURB RAMP, CONCRETE, A	90.000	SYS
26	605-06120 CURB, CONCRETE	100.000	LFT
27	610-07486 HMA FOR APPROACHES, TYPE A	985.000	TON
28	615-06520 MONUMENT, RE-ESTABLISH	4.000	EACH
29	621-06575 SODDING, NURSERY	275.000	SYS
30	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	189.000	LFT
31	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	102.000	LFT
32	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	174.000	LFT
33	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	160.000	TON
34	715-46005 PIPE END SECTION, 15 IN.	8.000	EACH
35	715-46010 PIPE END SECTION, 18 IN.	4.000	EACH
36	715-46020 PIPE END SECTION, 24 IN.	8.000	EACH
37	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
38	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,370.000	LFT
39	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,370.000	LFT
40	801-06640 CONSTRUCTION SIGN, A	57.000	EACH
41	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
42	801-92448 CONSTRUCTION SIGNS, MOBILE	60.000	DAY
43	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	42.000	LFT
44	802-91122 SIGN, GROUND MOUNTED, RESET	3.000	EACH
45	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	3,499.000	LFT
46	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	87,550.000	LFT
47	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	73,111.000	LFT
48	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	100.000	LFT

CALL ORDER : 581  
 LETTING DATE :

CONTRACT ID : RS-28605-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49 808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	800.000	LFT
50 808-75340	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	3.000	EACH
51 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	937.000	EACH
52 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	937.000	EACH

CALL ORDER : 591  
 LETTING DATE :

CONTRACT ID : RS-28696-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	4.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-93741 GUARD RAIL END TREATMENT, REMOVE	8.000	EACH
11	203-02080 LINEAR GRADING	0.100	MILE
12	303-07449 COMPACTED AGGREGATE, NO. 73	1,000.000	TON
13	304-07490 HMA PATCHING, TYPE B	500.000	TON
14	306-08034 MILLING, ASPHALT, 1 1/2 IN.	105,628.000	SYS
15	306-08043 MILLING, TRANSITION	320.000	SYS
16	306-08432 MILLING, APPROACH	1,800.000	SYS
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	8,714.000	TON
19	406-05520 ASPHALT FOR TACK COAT	26.400	TON
20	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
21	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
22	610-07487 HMA FOR APPROACHES, TYPE B	150.000	TON
23	725-06870 PIPE LINER, THERMOPLASTIC, 30 IN.	52.000	LFT
24	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,045.000	LFT
25	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,045.000	LFT
26	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	804-06771 DELINEATOR POST, FLEXIBLE	2.000	EACH
29	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	1.000	EACH
30	805-02441 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	80.000	LFT
31	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	20.000	LFT
32	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
33	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	84,585.000	LFT
34	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	10,130.000	LFT
35	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4,913.000	LFT