

CALL ORDER : 177
 LETTING DATE :

CONTRACT ID : R -28310-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	15.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
9	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
10	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	7,575.000	CYS
12	203-02070 BORROW	100.000	CYS
13	205-04931 SEDIMENT TRAP	14.000	EACH
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	393.000	TON
15	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
16	205-06937 TEMPORARY SILT FENCE	672.000	LFT
17	207-08263 SUBGRADE TREATMENT, TYPE IA	12,202.000	SYS
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,680.000	SYS
19	211-07454 STRUCTURE BACKFILL	736.400	CYS
20	213-08058 FLOWABLE BACKFILL	501.000	CYS
21	303-01180 COMPACTED AGGREGATE, NO. 53	3,300.000	TON
22	303-07449 COMPACTED AGGREGATE, NO. 73	20.700	TON
23	306-08036 MILLING, ASPHALT, 2 IN.	2,662.000	SYS
24	306-08043 MILLING, TRANSITION	1,076.000	SYS
25	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	920.900	TON
26	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	1,427.000	TON
27	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	3,547.000	TON
28	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	2,298.700	TON
29	402-07433 HMA SURFACE, TYPE B	390.000	TON
30	402-07438 HMA INTERMEDIATE, TYPE B	1,555.000	TON
31	402-07442 HMA BASE, TYPE C	298.500	TON
32	402-07453 HMA FOR TEMPORARY PAVEMENT	1,360.000	TON
33	406-05520 ASPHALT FOR TACK COAT	12.600	TON
34	601-01626 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 2	2.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
36	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	781.300	LFT
37	610-07486 HMA FOR APPROACHES, TYPE A	58.000	TON
38	610-07487 HMA FOR APPROACHES, TYPE B	47.200	TON
39	615-06505 MONUMENT, B	11.000	EACH
40	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
41	616-02320 GEOTEXTILES	4,413.800	SYS
42	616-05688 RIPRAP, CLASS 1	41.000	TON
43	616-06405 RIPRAP, REVETMENT	1,790.400	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
45	621-06545 FERTILIZER	1.460	TON
46	621-06553 SEED MIXTURE, R	436.000	LBS
47	621-06557 SEED MIXTURE, T	345.000	LBS
48	621-06565 MULCHING MATERIAL	14.000	TON

CALL ORDER : 177
 LETTING DATE :

CONTRACT ID : R -28310-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
49	621-06574 SODDING	2,586.400	SYS
50	621-06575 SODDING, NURSERY	5,595.000	SYS
51	714-26717 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 10 FT. X 5 FT.	104.000	LFT
52	714-99348 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 5 FT. X 3 FT.	101.000	LFT
53	715-02629 SAFETY METAL END SECTION, 6:1, 18 IN.	1.000	EACH
54	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	2.000	EACH
55	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	4,392.000	LFT
56	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	50.000	LFT
57	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	50.000	LFT
58	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	204.000	LFT
59	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	269.500	LFT
60	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	146.000	LFT
61	715-05129 PIPE, TYPE 1, CIRCULAR, 54 IN.	102.000	LFT
62	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	500.000	LFT
63	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	77.000	LFT
64	715-05208 PIPE, TYPE 4, CIRCULAR, 15 IN.	100.000	LFT
65	715-06492 CONCRETE ANCHOR, 54 IN.	2.000	EACH
66	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	19.700	TON
67	715-46000 PIPE END SECTION, 12 IN.	6.000	EACH
68	715-46005 PIPE END SECTION, 15 IN.	4.000	EACH
69	715-46010 PIPE END SECTION, 18 IN.	1.000	EACH
70	718-06529 OUTLET PROTECTOR, 2	20.000	EACH
71	718-52610 AGGREGATE FOR UNDERDRAINS	347.600	CYS
72	718-99153 GEOTEXTILES FOR UNDERDRAIN	2,727.100	SYS
73	720-45260 PIPE CATCH BASIN, 12 IN.	1.000	EACH
74	720-45265 PIPE CATCH BASIN, 15 IN.	1.000	EACH
75	720-45410 MANHOLE, C4	1.000	EACH
76	723-06660 WINGWALL	6.900	SYS
77	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	3.000	EACH
78	801-01505 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (ONLY)	1.000	EACH
79	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
80	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	15,088.000	LFT
81	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	22,344.000	LFT
82	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	1.000	EACH
83	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	85.000	LFT
84	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
85	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
86	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	4.000	EACH
87	801-07119 BARRICADE, III-B	330.000	LFT
88	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN.	45.000	LFT
89	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	635.000	LFT
90	801-97643 TEMPORARY BUZZ STRIPS	84.000	LFT
91	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	103.000	LFT
92	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	53.840	SFT
93	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	2.000	EACH
94	805-01879 SIGNAL SERVICE, INSTALL	1.000	EACH
95	805-02262 FLASHER INSTALLATION	LUMP	LUMP
96	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH

CALL ORDER : 177
 LETTING DATE :

CONTRACT ID : R -28310-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
97	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. AMBER	4.000	EACH
98	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. RED	4.000	EACH
99	805-78415 SPAN, CATENARY, AND TETHER	1.000	EACH
100	805-78420 DISCONNECT HANGER	1.000	EACH
101	805-78467 SIGNAL CABLE, 3C 8GA.	65.000	LFT
102	805-78485 SIGNAL CABLE, 5C 14GA.	779.000	LFT
103	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
104	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5,927.000	LFT
105	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	97.000	LFT
106	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	2.000	EACH
107	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	2.000	EACH
108	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7,532.000	LFT
109	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	100.000	EACH
110	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	104.000	EACH

CALL ORDER : 179
 LETTING DATE :

CONTRACT ID : R -28840-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	COMPOSITE AND CONCRETE PAVEMENT PATCHING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	910.000	TON
11	304-07783 HMA PATCHING, TYPE D	500.000	TON
12	306-08034 MILLING, ASPHALT, 1 1/2 IN.	1,600.000	SYS
13	402-07432 HMA SURFACE, TYPE A	132.000	TON
14	406-05521 ASPHALT FOR TACK COAT	1,600.000	SYS
15	503-05240 D-1 CONTRACTION JOINT	648.000	LFT
16	506-06333 PCCP PATCHING, FULL DEPTH	1,820.000	SYS
17	606-07484 MILLED HMA SHOULDER CORRUGATIONS	3,600.000	LFT
18	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
19	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
20	801-06640 CONSTRUCTION SIGN, A	54.000	EACH
21	801-06710 FLASHING ARROW SIGN	120.000	DAY
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
24	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	320.000	LFT
25	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	257.000	LFT
26	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,027.000	LFT
27	808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN.	80.000	LFT
28	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	25.000	EACH
29	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	25.000	EACH

