

SCHEDULE OF PAY ITEMS

PAGE 1

CALL ORDER : 343  
 LETTING DATE :

CONTRACT ID : R -27713-B

ITEM NO.	DESCRIPTION	UNITS	
QUANTITY			
-----			
SECTION NO. 0001 BEAUTIFICATION/WILDFLOWERS			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
LUMP			
2	109-08359	LIQUIDATED DAMAGES	
1.000	DOL		
3	109-08360	CONTRACT LIENS	
1.000	DOL		
4	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	
1.000	DOL		
5	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	
1.000	DOL		
6	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
LUMP			
7	621-06545	FERTILIZER	
11.900	TON		
8	622-03761	SEED MIXTURE NO. 1	
286.000	LBS		
9	622-03762	SEED MIXTURE NO. 2	
92.000	LBS		
10	622-52436	SIGN, DO NOT MOW OR SPRAY	
32.000	EACH		
11	624-92647	HERBICIDE TREATMENT	
47.400	ACRE		
12	801-03290	CONSTRUCTION SIGN, C	
4.000	EACH		
13	801-06775	MAINTAINING TRAFFIC	LUMP
LUMP			

SCHEDULE OF PAY ITEMS

PAGE 2

CALL ORDER : 345  
 LETTING DATE :

CONTRACT ID : R -29339-C

ITEM NO.	DESCRIPTION	UNITS	
QUANTITY			
-----			
SECTION NO. 0001 REASSEMBLE EXISTING TRUSS BRIDGE			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
LUMP			
2	105-07039	FIELD OFFICE, B	
6.000	MOS		
3	105-09198	LAPTOP COMPUTER SYSTEM	
12.000	MOS		
4	105-09199	FIELD OFFICE INTERNET SERVICE	
6.000	MOS		
5	109-08359	LIQUIDATED DAMAGES	
1.000	DOL		
6	109-08360	CONTRACT LIENS	
1.000	DOL		
7	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
LUMP			
8	202-04681	RESET BRICK SIDEWALK AND PAVEMENT	
27.000	SYS		
9	203-02000	EXCAVATION, COMMON	
136.000	CYS		
10	203-02070	BORROW	
734.000	CYS		
11	205-06937	TEMPORARY SILT FENCE	
290.000	LFT		
12	206-51220	EXCAVATION, WET	
11.000	CYS		
13	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	
19.000	CYS		
14	210-06389	LIMESTONE	
27.200	TON		
15	211-06467	AGGREGATE FOR END BENT BACKFILL	
45.600	CYS		
16	211-07454	STRUCTURE BACKFILL	
23.000	CYS		
17	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	
149.000	TON		
18	402-07432	HMA SURFACE, TYPE A	
14.500	TON		
19	402-07435	HMA INTERMEDIATE, TYPE A	
30.400	TON		
20	601-03667	RAILING, ORNAMENTAL	
444.800	LFT		
21	601-03871	RAILING, WOOD, END TREATMENT	
4.000	EACH		
22	610-07712	PCCP FOR APPROACHES, 6 IN.	
70.000	SYS		
23	611-03671	TRASH RECEPTACLE	
2.000	EACH		
24	616-02320	GEOTEXTILES	
413.000	SYS		
25	616-05688	RIPRAP, CLASS 1	
164.000	TON		
26	619-05926	ENVIRONMENTAL CONTROL	LUMP
LUMP			
27	619-51859	PAINT STEEL BRIDGE	LUMP
LUMP			
28	619-61000	CLEAN STEEL BRIDGE	LUMP
LUMP			

29	621-01004		MOBILIZATION AND DEMOBILIZATION FOR SEEDING
2.000		EACH	
30	621-01852		MULCHED SEEDING, GRASS, 2
660.000		SYS	
31	621-02770		EROSION CONTROL BLANKET
311.000		SYS	
32	621-06545		FERTILIZER
0.055		TON	
33	621-06567		WATER
2.400		KGAL	
34	621-98038		MULCH, HARDWOOD SHREDDED BARK
1.000		CYS	
35	622-03948		PLANTER
18.000		EACH	
36	622-05623		PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, 36 IN. OR
4.000		EACH	
37	622-05649		PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.
8.000		EACH	
38	622-05653		PLANT, GROUND COVER
6.000		EACH	
39	622-05654		PLANT, PERENNIAL
6.000		EACH	
40	701-01849		PILE, CONCRETE, STEEL SHELL ENCASED, 0.312 IN., 14 IN.
535.000		LFT	
41	701-99086		PILE TIP, STEEL SHELL
16.000		EACH	
42	702-51005		CONCRETE, A, SUBSTRUCTURE
139.300		CYS	
43	702-51863		FIELD DRILLED HOLE IN CONCRETE
8.000		EACH	
44	703-51030		REINFORCING STEEL
16,823.000		LBS	
45	703-51032		REINFORCING STEEL, EPOXY COATED
736.000		LBS	
46	706-04683		RAILING
174.000		LFT	
47	706-90676		EXPANSION ANCHOR
14.000		EACH	
48	706-90676		EXPANSION ANCHOR
8.000		EACH	

SCHEDULE OF PAY ITEMS

PAGE 3

CALL ORDER : 345  
 LETTING DATE :

CONTRACT ID : R -29339-C

ITEM NO.	DESCRIPTION	UNITS	
QUANTITY			
-----			
SECTION NO. 0001	REASSEMBLE EXISTING TRUSS BRIDGE		
49	709-51821	SURFACE SEAL	LUMP
LUMP			
50	711-51038	STRUCTURAL STEEL	LUMP
LUMP			
51	711-51038	STRUCTURAL STEEL	LUMP
LUMP			
52	712-03812	BENCH	
6.000	EACH		
53	712-94080	TIMBER DECK	
2,093.000	SFT		
54	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	
40.000	LFT		
55	715-05407	PIPE, END BENT DRAIN, 6 IN.	
110.000	LFT		
56	715-46005	PIPE END SECTION, 15 IN.	
1.000	EACH		
57	720-45030	INLET, E7	
1.000	EACH		
58	724-03855	EXPANSION JOINT, SLIDING PLATE	
26.400	LFT		
59	726-92406	BEARING ASSEMBLY, ELASTOMERIC	
2.000	EACH		
60	726-97941	BEARING ASSEMBLY, TFE ELASTOMERIC	
2.000	EACH		
61	728-98377	MASONRY COATING	LUMP
LUMP			
62	732-08420	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	
7.700	SYS		
63	732-08421	MODULAR BLOCK WALL ERECTION	
7.700	SYS		
64	802-03896	BOLLARD	
2.000	EACH		
65	802-04314	SIGN	
1.000	EACH		
66	805-02618	WIRE, NO. 2 COPPER, 3 1C	
80.000	LFT		
67	805-02728	CONDUIT, PVC, 1 IN.	
260.000	LFT		
68	805-03083	CONDUIT, RIGID, P.V.C., 1.50 IN.	
140.000	LFT		
69	805-06003	POLE, WOOD	
1.000	EACH		
70	805-86900	JUNCTION BOX	
18.000	EACH		
71	805-91703	CONDUIT, STEEL, GALVANIZED, 1.5 IN.	
80.000	LFT		
72	805-93562	WIRE, THW, NO. 10 COPPER IN PLASTIC DUCT, IN CONDUIT, 3 1/C	
210.000	LFT		
73	805-95519	FLEXIBLE CONDUIT, 0.75 IN.	
110.000	LFT		
74	807-02191	HANDHOLE, LIGHTING	
1.000	EACH		
75	807-04443	CONDUIT	
210.000	LFT		
76	807-04651	WIRE	
260.000	LFT		

77	807-04651	WIRE
140.000	LFT	
78	807-04866	LUMINAIRE
18.000	EACH	
79	807-06935	INSULATING LINK, WATERPROOFED
8.000	EACH	
80	807-86810	SERVICE POINT, II
1.000	EACH	
81	807-86910	CONNECTOR KIT, UNFUSED
60.000	EACH	
82	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED
4.000	EACH	

SCHEDULE OF PAY ITEMS

PAGE 4

CALL ORDER : 355  
 LETTING DATE :

CONTRACT ID : R -29572-C

ITEM NO.	DESCRIPTION	UNITS	
QUANTITY			
-----			
SECTION NO. 0001 BIKE/PEDESTRIAN FACILITY, ENHANCEMENT			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
LUMP			
2	105-07039	FIELD OFFICE, B	
6.000	MOS		
3	105-09198	LAPTOP COMPUTER SYSTEM	
12.000	MOS		
4	105-09199	FIELD OFFICE INTERNET SERVICE	
6.000	MOS		
5	109-08359	LIQUIDATED DAMAGES	
1.000	DOL		
6	109-08360	CONTRACT LIENS	
1.000	DOL		
7	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	
1.000	DOL		
8	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	
1.000	DOL		
9	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
LUMP			
10	201-52370	CLEARING RIGHT OF WAY	LUMP
LUMP			
11	202-02241	GUARDRAIL, REMOVE	
10.000	LFT		
12	202-52710	SIDEWALK, CONCRETE, REMOVE	
24.000	SYS		
13	203-02000	EXCAVATION, COMMON	
468.500	CYS		
14	205-03371	SEDIMENT, REMOVE	
30.000	CYS		
15	205-06937	TEMPORARY SILT FENCE	
2,300.000	LFT		
16	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	
29.300	CYS		
17	210-07827	TEXTURED	
490.000	SYS		
18	303-01180	COMPACTED AGGREGATE, NO. 53	
1,358.000	TON		
19	303-04489	COMPACTED CRUSHED AGGREGATE, 8	
11.000	TON		
20	303-07449	COMPACTED AGGREGATE, NO. 73	
497.000	TON		
21	402-07434	HMA SURFACE, TYPE C	
102.600	TON		
22	402-07439	HMA INTERMEDIATE, TYPE C	
153.000	TON		
23	406-05521	ASPHALT FOR TACK COAT	
3,110.000	SYS		
24	601-03970	RAILING, WOOD, 4 FT. 6 IN.	
130.000	LFT		
25	601-97770	POST, GUARDRAIL, WOOD	
45.000	EACH		
26	604-07902	CURB RAMP, CONCRETE, H	
16.000	SYS		
27	604-07903	CURB RAMP, CONCRETE, K	
21.300	SYS		
28	605-06120	CURB, CONCRETE	
1,233.000	LFT		

29	614-06475	HEADER, CEMENT CONCRETE, B	
4.000	LFT		
30	616-02320	GEOTEXTILES	
36.000	SYS		
31	616-06405	RIPRAP, REVETMENT	
30.000	TON		
32	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	
1.000	EACH		
33	621-06560	MULCHED SEEDING, U	
47,440.000	SYS		
34	621-06570	TOP SOIL	
650.000	CYS		
35	701-01849	PILE, CONCRETE, STEEL SHELL ENCASED, 0.312 IN., 14 IN.	
216.000	LFT		
36	701-99086	PILE TIP, STEEL SHELL	
14.000	EACH		
37	702-51005	CONCRETE, A, SUBSTRUCTURE	
27.560	CYS		
38	702-51015	CONCRETE, B, FOOTINGS	
14.220	CYS		
39	702-94656	CONCRETE, B	
11.000	CYS		
40	703-51030	REINFORCING STEEL	
5,131.000	LBS		
41	712-03862	PREFABRICATED BRIDGE	LUMP
LUMP			
42	715-05203	PIPE, TYPE 4, CIRCULAR, 4 IN.	
35.000	LFT		
43	724-03855	EXPANSION JOINT, SLIDING PLATE	
20.000	LFT		
44	732-07653	COARSE AGGREGATE, NO. 8	
50.000	TON		
45	732-08419	MODULAR BLOCK WALL	
71.000	SYS		
46	801-06775	MAINTAINING TRAFFIC	LUMP
LUMP			
47	802-03821	SIGN, SHEET WITH LEGEND	
14.000	EACH		
48	805-95466	FLASHING BEACON WITH SIGNAL AHEAD SIGN, 6 IN. I BEAM AND	
2.000	EACH		

SCHEDULE OF PAY ITEMS

PAGE 5

CALL ORDER : 355  
LETTING DATE :

CONTRACT ID : R -29572-C

---

ITEM NO.	DESCRIPTION
QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITY, ENHANCEMENT
49 805-96014	SAW CUT, FULL DEPTH
775.000 LFT	
50 807-04652	SERVICE POINT
2.000 EACH	
51 808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.
490.000 LFT	

---



SCHEDULE OF PAY ITEMS

PAGE 6

CALL ORDER : 445  
 LETTING DATE :

CONTRACT ID : T -29197-B

ITEM NO.	DESCRIPTION	UNITS	
QUANTITY			
-----			
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
LUMP			
2	105-07038	FIELD OFFICE, A	
11.000	MOS		
3	105-08520	CELLULAR TELEPHONE/RADIO	
2.000	EACH		
4	105-08521	CELLULAR TELEPHONE/RADIO SERVICE	
22.000	MOS		
5	105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	
1.000	DOL		
6	105-09198	LAPTOP COMPUTER SYSTEM	
22.000	MOS		
7	105-09199	FIELD OFFICE INTERNET SERVICE	
22.000	MOS		
8	109-08359	LIQUIDATED DAMAGES	
1.000	DOL		
9	109-08360	CONTRACT LIENS	
1.000	DOL		
10	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	
1.000	DOL		
11	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	
1.000	DOL		
12	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
LUMP			
13	202-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	
4.000	EACH		
14	202-96151	TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP
LUMP			
15	801-03290	CONSTRUCTION SIGN, C	
6.000	EACH		
16	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	LUMP
LUMP			
17	801-06640	CONSTRUCTION SIGN, A	
45.000	EACH		
18	801-06710	FLASHING ARROW SIGN	
200.000	DAY		
19	801-06775	MAINTAINING TRAFFIC	LUMP
LUMP			
20	801-09133	TEMPORARY CHANGEABLE MESSAGE SIGN	
4.000	EACH		
21	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	
87.000	SFT		
22	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	
240.000	SFT		
23	802-76045	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	
69.000	SFT		
24	805-01842	HANDHOLE, SIGNAL	
16.000	EACH		
25	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	
5,200.000	LFT		
26	805-04952	CONTROLLER AND CABINET	
4.000	EACH		
27	805-04977	MICROLOOP	
96.000	EACH		
28	805-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	
25.000	LFT		

29	805-06595		CONDUIT, PVC, 2 IN.
1,480.000		LFT	
30	805-06600		CONDUIT, PVC, 3 IN.
1,400.000		LFT	
31	805-78205		TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN
52.000		EACH	
32	805-78215		TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN
7.000		EACH	
33	805-78230		TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,
13.000		EACH	
34	805-78420		DISCONNECT HANGER
24.000		EACH	
35	805-78445		SIGNAL SERVICE
1.000		EACH	
36	805-78467		SIGNAL CABLE, 3C 8GA.
134.000		LFT	
37	805-78470		SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.
26,350.000		LFT	
38	805-78485		SIGNAL CABLE, 5C 14GA.
1,500.000		LFT	
39	805-78490		SIGNAL CABLE, 7C 14GA.
10,725.000		LFT	
40	805-78510		SIGNAL CABLE, 2C 16GA., SHIELDED
57,325.000		LFT	
41	805-78785		SIGNAL DETECTOR HOUSING
65.000		EACH	
42	805-78795		SAW CUT FOR ROADWAY LOOP AND SEALER
8,600.000		LFT	
43	805-78925		CONTROLLER CABINET FOUNDATION, P1
3.000		EACH	
44	805-92504		LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL
58.000		EACH	
45	805-92512		MICROLOOP DETECTOR
12.000		EACH	
46	808-05534		LINE, EPOXY, SOLID, WHITE, 8 IN.
460.000		LFT	
47	808-06194		LINE, EPOXY, SOLID, WHITE, 12 IN.
230.000		LFT	
48	808-07310		TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW,
120.000		LFT	

SCHEDULE OF PAY ITEMS

PAGE 7

CALL ORDER : 445  
 LETTING DATE :

CONTRACT ID : T -29197-B

ITEM NO.	DESCRIPTION
QUANTITY	UNITS
-----	
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION
49 808-74805	TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.
1,000.000	LFT
50 808-74807	PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS
91.000	EACH
51 808-74808	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)
25.000	EACH
52 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION
10.000	EACH
53 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)
6.000	EACH
54 808-94455	TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 6 IN.
2,150.000	LFT
55 808-98000	LINE, EPOXY, SOLID, YELLOW, 8 IN.
320.000	LFT

