

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-27047-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	27.000	MOS
3	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
4	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	32,162.000	m2
10	202-02278 CURB, CONCRETE, REMOVE	788.000	m
11	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
12	202-93615 CONCRETE, REMOVE	638.000	m2
13	203-02000 EXCAVATION, COMMON	105,940.000	m3
14	205-06932 TEMPORARY CHECK DAM, STRAW BALES	263.000	m
15	205-06933 TEMPORARY DITCH INLET PROTECTION	16.000	EACH
16	205-06936 TEMPORARY SEDIMENT TRAP	28.500	Mg
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	25,151.000	m2
18	207-08268 SUBGRADE TREATMENT, TYPE IV	93,320.000	m2
19	211-02050 B BORROW	2,726.000	m3
20	211-07454 STRUCTURE BACKFILL	8,606.000	m3
21	213-08058 FLOWABLE BACKFILL	28.000	m3
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	18,113.000	Mg
23	302-06464 SUBBASE FOR PCCP	16,011.000	m3
24	303-01180 COMPACTED AGGREGATE, NO. 53	630.000	Mg
25	303-07449 COMPACTED AGGREGATE, NO. 73	644.000	Mg
26	304-07491 HMA PATCHING, TYPE C	701.000	Mg
27	306-08037 MILLING, ASPHALT, 75 mm	8,477.000	m2
28	402-07440 HMA BASE, TYPE A	357.000	Mg
29	402-07453 HMA FOR TEMPORARY PAVEMENT	9,119.000	Mg
30	402-07784 HMA SURFACE, TYPE D	1,874.000	Mg
31	402-07785 HMA INTERMEDIATE, TYPE D	3,138.000	Mg
32	402-07786 HMA BASE, TYPE D	8,793.000	Mg
33	404-05511 SEAL COAT, 2	1,490.000	m2
34	406-05520 ASPHALT FOR TACK COAT	16.000	Mg
35	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
36	501-06323 QC/QA-PCCP, 300 mm	72,131.000	m2
37	501-06727 CORING, PCCP	LUMP	LUMP
38	502-06999 PCCP, 200 mm	1,163.000	m2
39	503-03489 RETROFITTED TIE BARS	126.000	EACH
40	503-05240 D-1 CONTRACTION JOINT	13,102.000	m
41	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	2.000	EACH
42	601-06234 IMPACT ATTENUATOR, R1, W1, TL-2	1.000	EACH
43	601-06417 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R1, W1, TL-2	1.000	EACH
44	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	9.500	m
45	602-06729 BARRIER DELINEATOR	54.000	EACH
46	602-08588 CONCRETE BARRIER, 1145 mm, MODIFIED	318.000	m
47	603-06045 FENCE, CHAIN LINK, 1220 mm	3.000	m
48	604-07894 CURB RAMP, CONCRETE, A	100.000	m2

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-27047-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
49	604-07898 CURB RAMP, CONCRETE, D	23.000	m2
50	604-07901 CURB RAMP, CONCRETE, G	28.000	m2
51	604-07904 CURB RAMP, CONCRETE, L	455.000	m2
52	604-44251 STEPS, CONCRETE	2.710	m3
53	604-91531 SIDEWALK, CONCRETE, 100 mm	7,009.000	m2
54	605-06090 CURB, INTEGRAL, CONCRETE	4,954.000	m
55	605-06120 CURB, CONCRETE	41.000	m
56	605-06125 CURB, CONCRETE, MODIFIED	60.000	m
57	605-06210 CENTER CURB, C, CONCRETE	1,930.000	m
58	605-95635 CURB, CONCRETE, INTEGRAL, MODIFIED	54.000	m
59	606-07484 MILLED HMA SHOULDER CORRUGATIONS	1,025.000	m
60	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	150.000	m
61	610-07486 HMA FOR APPROACHES, TYPE A	775.000	Mg
62	611-05330 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 150 mm	2,992.000	m2
63	611-06497 MAILBOX ASSEMBLY, SINGLE	42.000	EACH
64	611-06498 MAILBOX ASSEMBLY, DOUBLE	8.000	EACH
65	615-06500 MONUMENT, A	1.000	EACH
66	615-06515 MONUMENT, D	13.000	EACH
67	616-02320 GEOTEXTILES	125.000	m2
68	616-06406 RIPRAP, REVETMENT	125.000	m2
69	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
70	621-06545 FERTILIZER	2.000	Mg
71	621-06553 SEED MIXTURE, R	173.000	kg
72	621-06557 SEED MIXTURE, T	120.000	kg
73	621-06565 MULCHING MATERIAL	10.100	Mg
74	621-06567 WATER	450.000	kL
75	621-06575 SODDING, NURSERY	24,951.000	m2
76	703-51030 REINFORCING STEEL	1,928.000	kg
77	703-51032 REINFORCING STEEL, EPOXY COATED	161.000	kg
78	714-02677 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1200 mm x 1200 mm	32.300	m
79	714-26707 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1800 mm x 1800 mm	61.000	m
80	714-44240 CONCRETE, A, STRUCTURES	12.400	m3
81	715-02628 SAFETY METAL END SECTION, 6:1, 375 mm	5.000	EACH
82	715-04548 GRATED BOX END SECTION, II, 6:1, 750 mm	1.000	EACH
83	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	524.000	m
84	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	6,562.000	m
85	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	66.000	m
86	715-05125 PIPE, TYPE 1, CIRCULAR, 750 mm	5.000	m
87	715-05146 PIPE, TYPE 2, CIRCULAR, 150 mm	21.000	m
88	715-05147 PIPE, TYPE 2, CIRCULAR, 200 mm	8.000	m
89	715-05148 PIPE, TYPE 2, CIRCULAR, 250 mm	10.000	m
90	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	355.000	m
91	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	447.000	m
92	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	830.000	m
93	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	1,450.000	m
94	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	586.000	m
95	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	128.000	m
96	715-05161 PIPE, TYPE 2, CIRCULAR, 1200 mm	184.000	m

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-27047-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
97	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	199.000	m
98	715-26729 GRATED BOX END SECTION, II, 6:1, 375 mm	8.000	EACH
99	715-46005 PIPE END SECTION, 375 mm	22.000	EACH
100	715-46010 PIPE END SECTION, 450 mm	1.000	EACH
101	715-46030 PIPE END SECTION, 750 mm	1.000	EACH
102	718-06531 OUTLET PROTECTOR, 3	2.000	EACH
103	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
104	718-94889 AGGREGATE FOR UNDERDRAINS, 8	2,625.000	m3
105	718-99153 GEOTEXTILES FOR UNDERDRAIN	26,246.000	m2
106	720-04682 INLET	1.000	EACH
107	720-04682 INLET	1.000	EACH
108	720-44000 CASTING, ADJUST TO GRADE	15.000	EACH
109	720-45005 INLET, A2	3.000	EACH
110	720-45015 INLET, A8	30.000	EACH
111	720-45035 INLET, F7	4.000	EACH
112	720-45041 INLET, H5	1.000	EACH
113	720-45045 INLET, J10	14.000	EACH
114	720-45055 INLET, M10	7.000	EACH
115	720-45145 INLET, J10, MODIFIED	1.000	EACH
116	720-45270 PIPE CATCH BASIN, 450 mm	6.000	EACH
117	720-45275 PIPE CATCH BASIN, 600 mm	4.000	EACH
118	720-45410 MANHOLE, C4	28.000	EACH
119	720-45510 MANHOLE, C4, MODIFIED	2.000	EACH
120	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	2.600	m
121	720-92557 INLET, M13	1.000	EACH
122	720-93409 INLET, B15, MODIFIED	1.000	EACH
123	720-93411 INLET, C15, MODIFIED	2.000	EACH
124	720-93501 MANHOLE, L4	1.000	EACH
125	720-94612 MANHOLE, K4	3.000	EACH
126	720-95422 MANHOLE, J4	15.000	EACH
127	720-98174 INLET, B15	1.000	EACH
128	725-08587 PIPE LINER, THERMOPLASTIC, AREA 3.44 m2	81.000	EACH
129	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	4.000	EACH
130	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
131	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	15,520.000	m
132	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	25,860.000	m
133	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (ONLY)	2.000	EACH
134	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	106.000	m
135	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 200 mm	50.000	m
136	801-06605 BARRICADE, IIIA	27.000	EACH
137	801-06606 BARRICADE, IIIB	87.000	EACH
138	801-06625 DETOUR ROUTE MARKER ASSEMBLY	13.000	EACH
139	801-06640 CONSTRUCTION SIGN, A	84.000	EACH
140	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
141	801-06710 FLASHING ARROW SIGN	525.000	DAY
142	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
143	802-04893 REFERENCE POST	4.000	EACH
144	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	189.000	m

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-27047-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
145	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	120.000	m
146	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	13.200	m2
147	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	63.500	m2
148	802-76040 SIGN, SHEET ENCLOSED LENS WITH LEGEND, 3.18 mm THICKNESS	2.700	m2
149	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	1.300	m2
150	802-76125 SPAN OVERHEAD SIGN STRUCTURE, CABLESPAN	2.000	EACH
151	803-06031 SIGN FOUNDATIONS, CONCRETE	9.500	m3
152	804-06770 DELINEATOR POST	2.000	EACH
153	805-01842 HANDHOLE, SIGNAL	19.000	EACH
154	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
155	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	635.000	m
156	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
157	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	6.000	EACH
158	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER ARROW, GREEN	4.000	EACH
159	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	2.000	EACH
160	805-78415 SPAN, CATENARY, AND TETHER	2.000	EACH
161	805-78420 DISCONNECT HANGER	4.000	EACH
162	805-78445 SIGNAL SERVICE	1.000	EACH
163	805-78467 SIGNAL CABLE, 3C 8GA.	18.000	m
164	805-78485 SIGNAL CABLE, 5C 14GA.	198.000	m
165	805-78490 SIGNAL CABLE, 7C 14GA.	236.000	m
166	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,600.000	m
167	805-78746 PREFORMED LOOP DETECTORS	627.000	m
168	805-78906 SIGNAL SUPPORT FOUNDATION, 915 mm X 915 mm X 3.7m	4.000	EACH
169	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
170	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
171	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	12.000	EACH
172	806-06539 TEMPORARY SIGNAL INSTALLATION, MAINTAIN	LUMP	LUMP
173	806-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
174	808-03002 LINE, EPOXY, BROKEN, WHITE, 100 mm	648.000	m
175	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	2,565.000	m
176	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	5,430.000	m
177	808-04896 LINE, EPOXY, BROKEN, YELLOW, 100 mm	462.000	m
178	808-05534 LINE, EPOXY, SOLID, WHITE, 200 mm	49.000	m
179	808-05535 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, CROSSHATCH LINE,	12.000	m
180	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	184.000	m
181	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	2,710.000	m
182	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 200 mm	130.000	m
183	808-06716 LINE, REMOVE	1,728.000	m
184	808-07310 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW,	98.000	m
185	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 600 mm	63.000	m
186	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	62.000	EACH
187	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	48.000	EACH
188	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	2,000.000	m
189	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	1,467.000	m
190	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	174.000	m
191	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	3.000	EACH
192	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH

CALL ORDER : 131
LETTING DATE :

CONTRACT ID : IR-27047-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
193 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	300.000	EACH
194 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	589.000	EACH
195 808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	961.000	m
196 808-94455	TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 150 mm	449.000	m
197 808-98000	LINE, EPOXY, SOLID, YELLOW, 200 mm	509.000	m

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : R -27724-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BEAUTIFICATION/WILDFLOWERS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	12.000	MOS
3	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	202-02250 TREE, 10 IN., REMOVE	7.000	EACH
6	203-05859 FILL	770.000	CYS
7	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
8	621-02318 SEED MIXTURE, PRAIRIE GRASS	84.000	LBS
9	621-02318 SEED MIXTURE, PRAIRIE GRASS	115.000	LBS
10	621-06567 WATER	604.000	KGAL
11	621-98038 MULCH, HARDWOOD SHREDDED BARK	36.000	CYS
12	622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN.	58.000	EACH
13	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	21.000	EACH
14	622-52436 SIGN, DO NOT MOW OR SPRAY	20.000	EACH

CALL ORDER : 151

CONTRACT ID : R -28651-A

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	MEDIAN CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	14.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	56.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-01405 CONTAMINATED SOIL, REMOVE AND DISPOSE	4,924.000	m3
12	202-02240 PAVEMENT REMOVAL	273.000	m2
13	202-02271 HEADWALL, REMOVE	8.000	EACH
14	202-02273 CENTER CURB, CONCRETE, REMOVE	99.000	m2
15	202-02278 CURB, CONCRETE, REMOVE	182.000	m
16	202-02279 CURB AND GUTTER, REMOVE	387.000	m
17	202-52710 SIDEWALK, CONCRETE, REMOVE	963.000	m2
18	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	76.000	EACH
19	202-91385 INLET, REMOVE	28.000	EACH
20	202-91840 FENCE, CHAIN LINK, REMOVE	28.000	m
21	202-93047 MANHOLE, REMOVE	7.000	EACH
22	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	58.000	EACH
23	202-96133 PIPE, REMOVE	673.000	m
24	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
25	203-02000 EXCAVATION, COMMON	9,447.000	m3
26	205-03371 SEDIMENT REMOVE	255.000	m3
27	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	87.000	Mg
28	205-06933 TEMPORARY DITCH INLET PROTECTION	67.000	EACH
29	205-06937 TEMPORARY SILT FENCE	1,530.000	m
30	207-08268 SUBGRADE TREATMENT, TYPE IV	19,221.000	m2
31	211-07454 STRUCTURE BACKFILL	9,850.000	m3
32	213-08058 FLOWABLE BACKFILL	3,223.000	m3
33	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,947.000	Mg
34	302-06464 SUBBASE FOR PCCP	37.000	m3
35	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	1,594.000	Mg
36	306-08034 MILLING, ASPHALT, 38 mm	29,264.000	m2
37	306-08041 MILLING, PCCP	1,352.000	m2
38	306-08043 MILLING, TRANSITION	1,015.000	m2
39	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	4,727.000	Mg
40	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	10,574.000	Mg
41	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	8,220.000	Mg
42	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	4,315.000	Mg
43	402-07441 HMA BASE, TYPE B	10.000	Mg
44	402-07453 HMA FOR TEMPORARY PAVEMENT	28.000	Mg
45	406-05520 ASPHALT FOR TACK COAT	34.000	Mg
46	603-91304 FENCE, WOOD, RESET	28.000	m

CALL ORDER : 151

CONTRACT ID : R -28651-A

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	MEDIAN CONSTRUCTION			
47	604-06070	SIDEWALK, CONCRETE	7,102.000	m2
48	604-07900	CURB RAMP, CONCRETE, F	120.000	m2
49	604-07901	CURB RAMP, CONCRETE, G	7.000	m2
50	604-07902	CURB RAMP, CONCRETE, H	129.000	m2
51	604-44251	STEPS, CONCRETE	7.240	m3
52	605-06120	CURB, CONCRETE	107.000	m
53	605-06140	CURB AND GUTTER, CONCRETE	3,908.000	m
54	605-06255	CENTER CURB, D, CONCRETE	96.000	m2
55	605-92578	CURB WALK, CONCRETE	141.000	m2
56	605-96305	CURB AND GUTTER, CONCRETE, DEPRESSED	20.000	m
57	610-07486	HMA FOR APPROACHES, TYPE A	1,286.000	Mg
58	610-07712	PCCP FOR APPROACHES, 150 mm	8,424.000	m2
59	611-06497	MAILBOX ASSEMBLY, SINGLE	36.000	EACH
60	611-06498	MAILBOX ASSEMBLY, DOUBLE	19.000	EACH
61	611-95023	MAILBOX ASSEMBLY, RESET	1.000	EACH
62	615-06490	RIGHT OF WAY MARKER	81.000	EACH
63	615-06496	PARKING BARRIER	5.000	EACH
64	615-06500	MONUMENT, A	23.000	EACH
65	615-06505	MONUMENT, B	3.000	EACH
66	615-06520	MONUMENT, RE-ESTABLISH	1.000	EACH
67	615-06527	MONUMENT, SECTION CORNER	2.000	EACH
68	615-97768	PARKING BARRIER, RESET	5.000	EACH
69	616-02320	GEOTEXTILES	108.000	m2
70	616-06451	RIPRAP, UNIFORM	100.000	Mg
71	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
72	621-06545	FERTILIZER	1.210	Mg
73	621-06557	SEED MIXTURE, T	413.000	kg
74	621-06560	MULCHED SEEDING, U	2,941.000	m2
75	621-06567	WATER	167.000	kL
76	621-06575	SODDING, NURSERY	14,974.000	m2
77	622-05623	PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, 900 mm OR	14.000	EACH
78	715-04855	PIPE END SECTION, 1050 mm	1.000	EACH
79	715-05024	PIPE, TYPE 2, CIRCULAR, 900 mm	430.800	m
80	715-05048	PIPE, TYPE 4, CIRCULAR, 150 mm	5,751.000	m
81	715-05149	PIPE, TYPE 2, CIRCULAR, 300 mm	1,815.100	m
82	715-05151	PIPE, TYPE 2, CIRCULAR, 375 mm	634.000	m
83	715-05152	PIPE, TYPE 2, CIRCULAR, 450 mm	278.800	m
84	715-05154	PIPE, TYPE 2, CIRCULAR, 600 mm	744.800	m
85	715-05156	PIPE, TYPE 2, CIRCULAR, 750 mm	583.600	m
86	715-05157	PIPE, TYPE 2, CIRCULAR, 825 mm	165.000	m
87	715-05159	PIPE, TYPE 2, CIRCULAR, 1050 mm	347.700	m
88	715-08283	PCCP FOR STRUCTURE INSTALLATION	1,084.000	m2
89	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	597.000	Mg
90	715-44240	CONCRETE, A, STRUCTURES	13.600	m3
91	715-46040	PIPE END SECTION, 900 mm	1.000	EACH
92	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	2,000.000	m

CALL ORDER : 151

CONTRACT ID : R -28651-A

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	MEDIAN CONSTRUCTION		
93	718-52610 AGGREGATE FOR UNDERDRAINS	1,306.000	m3
94	720-03481 MANHOLE, H4, MODIFIED	2.000	EACH
95	720-04182 CASTING, 4	1.000	EACH
96	720-04666 CATCH BASIN	2.000	EACH
97	720-04720 MANHOLE, H	3.000	EACH
98	720-04720 MANHOLE, H	4.000	EACH
99	720-07301 INLET TYPE HA	4.000	EACH
100	720-44000 CASTING, ADJUST TO GRADE	13.000	EACH
101	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000	EACH
102	720-44080 CASTING, 15, FURNISH AND ADJUST TO GRADE	2.000	EACH
103	720-45030 INLET, E7	2.000	EACH
104	720-45035 INLET, F7	1.000	EACH
105	720-45235 CATCH BASIN, E7	32.000	EACH
106	720-45335 CATCH BASIN, E7, MODIFIED	2.000	EACH
107	720-45405 MANHOLE, B4	3.000	EACH
108	720-45410 MANHOLE, C4	28.000	EACH
109	720-45415 MANHOLE, D4	1.000	EACH
110	720-45510 MANHOLE, C4, MODIFIED	5.000	EACH
111	720-45515 MANHOLE, D4, MODIFIED	1.000	EACH
112	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	1.000	m
113	720-91973 MANHOLE, H4	10.000	EACH
114	720-92025 MANHOLE, D2	8.000	EACH
115	720-92492 MANHOLE, B	1.000	EACH
116	720-92605 MANHOLE, K2, MODIFIED	1.000	EACH
117	720-93409 INLET, B15, MODIFIED	5.000	EACH
118	720-93411 INLET, C15, MODIFIED	14.000	EACH
119	720-94157 MANHOLE, C	9.000	EACH
120	720-94612 MANHOLE, K4	5.000	EACH
121	720-94713 CATCH BASIN, C15, MODIFIED	9.000	EACH
122	720-95164 CATCH BASIN, B15, MODIFIED	2.000	EACH
123	720-98174 INLET, B15	33.000	EACH
124	720-98555 INLET, C15	12.000	EACH
125	720-99416 CATCH BASIN, B15	1.000	EACH
126	720-99417 CATCH BASIN, C15	47.000	EACH
127	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	108.000	EACH
128	801-01506 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (RXR)	8.000	EACH
129	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
130	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	22,123.000	m
131	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	25,450.000	m
132	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	318.000	m
133	801-06640 CONSTRUCTION SIGN, A	140.000	EACH
134	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
135	801-06710 FLASHING ARROW SIGN	1,020.000	DAY
136	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
137	801-07119 BARRICADE, III-B	643.000	m
138	801-94295 SIGNAL HEAD, RELOCATE	20.000	EACH

CALL ORDER : 151

CONTRACT ID : R -28651-A

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 MEDIAN CONSTRUCTION			
139	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	231.600	m
140	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	43.690	m2
141	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	9.460	m2
142	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	8.000	EACH
143	805-01842 HANDHOLE, SIGNAL	24.000	EACH
144	805-01879 SIGNAL SERVICE	2.000	EACH
145	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
146	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 450mm	16.000	EACH
147	805-02373 INTERCONNECT CABLE, FIBER OPTIC	1,008.000	m
148	805-02438 COMMUNICATION TELEMETRY INTERCONNECT INTERFACE PANEL	2.000	EACH
149	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	1,963.000	m
150	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	2.000	EACH
151	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	13.000	EACH
152	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER ARROW, GREEN	6.000	EACH
153	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	3.000	EACH
154	805-78370 PEDESTRIAN PUSH BUTTON	16.000	EACH
155	805-78415 SPAN, CATENARY, AND TETHER	8.000	EACH
156	805-78420 DISCONNECT HANGER	8.000	EACH
157	805-78467 SIGNAL CABLE, 3C 8GA.	30.000	m
158	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	3,124.000	m
159	805-78485 SIGNAL CABLE, 5C 14GA.	549.000	m
160	805-78490 SIGNAL CABLE, 7C 14GA.	979.000	m
161	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,097.000	m
162	805-78785 SIGNAL DETECTOR HOUSING	20.000	EACH
163	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,026.000	m
164	805-78925 CONTROLLER CABINET FOUNDATION, P1	2.000	EACH
165	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	8.000	EACH
166	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	1,350.000	m
167	805-86930 INSULATING LINK, NOT WATERPROOFED	80.000	EACH
168	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	20.000	EACH
169	805-96014 SAW CUT, FULL DEPTH	204.000	m
170	805-98335 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C	2,500.000	m
171	805-98336 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	600.000	m
172	807-02370 LIGHT STRUCTURE, REMOVE AND RESET	40.000	EACH
173	807-02428 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING,	40.000	EACH
174	807-86605 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 150 WATT	5.000	EACH
175	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	35.000	EACH
176	807-86910 CONNECTOR KIT, UNFUSED	40.000	EACH
177	807-86915 CONNECTOR KIT, FUSED	40.000	EACH
178	807-86920 MULTIPLE COMPRESSION FITTING, NOT WATERPROOFED	140.000	EACH
179	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	40.000	EACH
180	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	1,041.000	m
181	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,395.000	m
182	808-06716 LINE, REMOVE	6,805.000	m
183	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	720.000	m
184	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	5,499.000	m

CALL ORDER : 151

CONTRACT ID : R -28651-A

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 MEDIAN CONSTRUCTION			
185	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	174.000	m
186	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	152.000	m
187	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm	660.000	m
188	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	66.000	EACH
189	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	42.000	EACH
190	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	4.000	EACH
191	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	629.000	m

CALL ORDER : 161
 LETTING DATE :

CONTRACT ID : R -28744-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02278 CURB, CONCRETE, REMOVE	1,746.000	LFT
9	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
10	202-52710 SIDEWALK, CONCRETE, REMOVE	686.000	SYS
11	202-52710 SIDEWALK, CONCRETE, REMOVE	143.900	SYS
12	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
13	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
14	202-90277 DETECTOR HOUSING, REMOVE	4.000	EACH
15	202-91385 INLET, REMOVE	9.000	EACH
16	203-02000 EXCAVATION, COMMON	2,714.000	CYS
17	205-04948 TEMPORARY CONSTRUCTION ENTRANCE/EXIT	LUMP	LUMP
18	207-08266 SUBGRADE TREATMENT, TYPE III	4,336.000	SYS
19	211-07454 STRUCTURE BACKFILL	175.300	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	83.000	TON
21	306-08034 MILLING, ASPHALT, 1 1/2 IN.	1,417.000	SYS
22	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	422.000	TON
23	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	508.000	TON
24	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	1,624.000	TON
25	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	904.000	TON
26	406-05520 ASPHALT FOR TACK COAT	1.400	TON
27	604-06070 SIDEWALK, CONCRETE	423.800	SYS
28	604-07894 CURB RAMP, CONCRETE, A	21.000	SYS
29	604-07900 CURB RAMP, CONCRETE, F	108.400	SYS
30	604-07902 CURB RAMP, CONCRETE, H	12.600	SYS
31	604-07903 CURB RAMP, CONCRETE, K	8.900	SYS
32	604-07904 CURB RAMP, CONCRETE, L	33.100	SYS
33	605-06120 CURB, CONCRETE	111.000	LFT
34	605-06140 CURB AND GUTTER, CONCRETE	2,099.000	LFT
35	605-06255 CENTER CURB, D, CONCRETE	30.100	SYS
36	610-08446 PCCP FOR APPROACHES, 6 IN.	42.400	SYS
37	610-08462 PCCP FOR APPROACHES, 8 IN.	249.600	SYS
38	621-06560 MULCHED SEEDING, U	650.000	SYS
39	621-06567 WATER	1.000	KGAL
40	621-06570 TOP SOIL	114.600	CYS
41	621-06574 SODDING	655.400	SYS
42	621-98038 MULCH, HARDWOOD SHREDDED BARK	10.200	CYS
43	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	43.000	EACH
44	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	48.000	EACH
45	622-05653 PLANT, GROUND COVER	37.000	EACH
46	622-05654 PLANT, PERENNIAL	8.000	EACH
47	622-05654 PLANT, PERENNIAL	26.000	EACH
48	702-51015 CONCRETE, B, FOOTINGS	3.500	CYS

CALL ORDER : 161
 LETTING DATE :

CONTRACT ID : R -28744-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
49	702-90915 CONCRETE, A	42.450	CYS
50	703-51030 REINFORCING STEEL	3,793.500	LBS
51	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	1,434.000	LFT
52	715-41045 PIPE, REINFORCED CONCRETE, 12 IN.	201.400	LFT
53	718-52610 AGGREGATE FOR UNDERDRAINS	115.000	CYS
54	718-99153 GEOTEXTILES FOR UNDERDRAIN	1,494.000	SYS
55	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
56	720-45045 INLET, J10	6.000	EACH
57	720-45080 INLET, S14	2.000	EACH
58	720-45085 INLET, T14	1.000	EACH
59	720-45410 MANHOLE, C4	6.000	EACH
60	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
61	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	250.000	LFT
62	801-06625 DETOUR ROUTE MARKER ASSEMBLY	25.000	EACH
63	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
64	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
65	801-07119 BARRICADE, III-B	220.000	LFT
66	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	127.250	SFT
67	802-76055 SIGN POST, A	156.000	LFT
68	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	1.000	EACH
69	805-01842 HANDHOLE, SIGNAL	6.000	EACH
70	805-01885 MAST ARM, 30 FT.	1.000	EACH
71	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
72	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	4.000	EACH
73	805-02262 FLASHER INSTALLATION	LUMP	LUMP
74	805-02445 CONTROLLER CABINET, P1	1.000	EACH
75	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	487.000	LFT
76	805-78370 PEDESTRIAN PUSH BUTTON	3.000	EACH
77	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,320.000	LFT
78	805-78480 SIGNAL CABLE, 3C 14GA.	280.000	LFT
79	805-78485 SIGNAL CABLE, 5C 14GA.	660.000	LFT
80	805-78490 SIGNAL CABLE, 7C 14GA.	465.000	LFT
81	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	965.000	LFT
82	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
83	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	760.000	LFT
84	805-78900 PEDESTAL FOUNDATION, A	1.000	EACH
85	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	1.000	EACH
86	805-86838 WIRE, NO. 4 COPPER IN CONDUIT, 1C	510.000	LFT
87	805-90187 CONDUIT, STEEL, GALVANIZED, 4 IN.	37.000	LFT
88	805-95466 FLASHING BEACON WITH SIGNAL AHEAD SIGN, 6 IN. I BEAM AND	2.000	EACH
89	807-03738 LIGHT POLE ASSEMBLY, STREET	5.000	EACH
90	807-06935 INSULATING LINK, WATERPROOFED	8.000	EACH
91	807-86805 SERVICE POINT, I	2.000	EACH
92	807-86910 CONNECTOR KIT, UNFUSED	5.000	EACH
93	807-86915 CONNECTOR KIT, FUSED	5.000	EACH
94	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	4.000	EACH
95	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	312.000	LFT
96	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	68.000	LFT

CALL ORDER : 161
 LETTING DATE :

CONTRACT ID : R -28744-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
97	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	485.000	LFT
98	808-06721 TRANSVERSE MARKINGS, PAINT, CROSSWALK LINE, 4 IN.	48.000	LFT
99	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	10.000	LFT
100	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	28.000	LFT
101	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	520.000	LFT
102	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	29.000	LFT
103	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	117.000	LFT
104	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	280.000	LFT
105	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	10.000	EACH
106	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	10.000	EACH
107	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	1.000	EACH
108	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	134.000	LFT

CALL ORDER : 171
 LETTING DATE :

CONTRACT ID : R -28746-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	18.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	8,905.000	SYS
9	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	18,215.000	CYS
11	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	4.000	EACH
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	28.000	TON
13	205-06937 TEMPORARY SILT FENCE	5,067.000	LFT
14	207-08268 SUBGRADE TREATMENT, TYPE IV	34,924.000	SYS
15	211-07454 STRUCTURE BACKFILL	11,334.000	CYS
16	213-08058 FLOWABLE BACKFILL	10.000	CYS
17	303-01180 COMPACTED AGGREGATE, NO. 53	2,001.000	TON
18	303-07449 COMPACTED AGGREGATE, NO. 73	102.000	TON
19	304-07489 HMA PATCHING, TYPE A	160.000	TON
20	304-07493 WIDENING WITH HMA, TYPE B	46.000	TON
21	306-08043 MILLING, TRANSITION	1,005.000	SYS
22	401-07325 QC/QA-HMA, 1, 70, SURFACE, 9.5 mm	789.000	TON
23	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	1,666.000	TON
24	401-07395 QC/QA-HMA, 1, 70, INTERMEDIATE, 19.0 mm	1,270.000	TON
25	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	2,698.000	TON
26	401-07422 QC/QA-HMA, 1, 64, BASE, 19.0 mm	3,683.000	TON
27	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	7,848.000	TON
28	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	5,522.000	TON
29	402-07453 HMA FOR TEMPORARY PAVEMENT	1,310.000	TON
30	406-05520 ASPHALT FOR TACK COAT	32.000	TON
31	604-05528 SIDEWALK, HMA	385.000	TON
32	604-07894 CURB RAMP, CONCRETE, A	28.000	SYS
33	604-07896 CURB RAMP, CONCRETE, B	42.000	SYS
34	604-07901 CURB RAMP, CONCRETE, G	29.000	SYS
35	604-07902 CURB RAMP, CONCRETE, H	13.000	SYS
36	604-91531 SIDEWALK, CONCRETE, 4 IN.	4,739.000	SYS
37	605-06100 CURB, INTEGRAL, C, CONCRETE	178.000	LFT
38	605-06120 CURB, CONCRETE	18.000	LFT
39	605-06140 CURB AND GUTTER, CONCRETE	10,460.000	LFT
40	605-97937 CURB AND GUTTER, CONCRETE, ROLL	272.000	LFT
41	610-07486 HMA FOR APPROACHES, TYPE A	54.000	TON
42	610-07487 HMA FOR APPROACHES, TYPE B	1,252.000	TON
43	610-07713 PCCP FOR APPROACHES, 8 IN.	536.000	SYS
44	610-08446 PCCP FOR APPROACHES, 6 IN.	3,640.000	SYS
45	611-06497 MAILBOX ASSEMBLY, SINGLE	34.000	EACH
46	611-06498 MAILBOX ASSEMBLY, DOUBLE	4.000	EACH
47	615-06505 MONUMENT, B	14.000	EACH
48	615-06527 MONUMENT, SECTION CORNER	2.000	EACH

CALL ORDER : 171
 LETTING DATE :

CONTRACT ID : R -28746-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
49	616-02320 GEOTEXTILES	196.000	SYS
50	616-06405 RIPRAP, REVETMENT	90.000	TON
51	616-06451 RIPRAP, UNIFORM	59.000	TON
52	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
53	621-06560 MULCHED SEEDING, U	2,398.000	SYS
54	621-06575 SODDING, NURSERY	14,556.000	SYS
55	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	1,410.000	LFT
56	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	12,358.000	LFT
57	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	15.000	LFT
58	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	129.000	LFT
59	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	2,898.000	LFT
60	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	1,030.000	LFT
61	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	1,287.000	LFT
62	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	510.000	LFT
63	715-05159 PIPE, TYPE 2, CIRCULAR, 42 IN.	368.000	LFT
64	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN.	450.000	LFT
65	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	40.000	LFT
66	715-05335 PIPE, TYPE 2, DEFORMED, MIN. AREA 5.1 SFT.	624.000	LFT
67	715-05408 PIPE, SANITARY SEWER, 8 IN.	1,547.000	LFT
68	715-05411 PIPE, SANITARY SEWER, 12 IN.	241.000	LFT
69	715-05711 PIPE, SANITARY SEWER, 6 IN.	214.000	LFT
70	715-06696 PIPE, PVC, 10 IN.	100.000	LFT
71	715-08069 CONCRETE ANCHOR, MIN. AREA 5.1 SQ. FT.	1.000	EACH
72	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	19.000	TON
73	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
74	715-91361 PIPE, PVC, 6 IN.	100.000	LFT
75	715-92537 PIPE, PVC, 8 IN.	100.000	LFT
76	718-04986 CLEANOUT	20.000	EACH
77	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,300.000	LFT
78	718-52610 AGGREGATE FOR UNDERDRAINS	1,060.000	CYS
79	718-99153 GEOTEXTILES FOR UNDERDRAIN	13,236.000	SYS
80	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
81	720-45005 INLET, A2	1.000	EACH
82	720-45030 INLET, E7	1.000	EACH
83	720-45045 INLET, J10	1.000	EACH
84	720-45235 CATCH BASIN, E7	2.000	EACH
85	720-45275 PIPE CATCH BASIN, 24 IN.	1.000	EACH
86	720-45410 MANHOLE, C4	24.000	EACH
87	720-45410 MANHOLE, C4	7.000	EACH
88	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	5.000	LFT
89	720-93501 MANHOLE, L4	1.000	EACH
90	720-95422 MANHOLE, J4	13.000	EACH
91	720-98174 INLET, B15	20.000	EACH
92	720-98555 INLET, C15	4.000	EACH
93	720-99416 CATCH BASIN, B15	19.000	EACH
94	720-99417 CATCH BASIN, C15	24.000	EACH
95	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
96	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	23,290.000	LFT

CALL ORDER : 171
 LETTING DATE :

CONTRACT ID : R -28746-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
97	801-06207	14,995.000	LFT
98	801-06625	39.000	EACH
99	801-06640	26.000	EACH
100	801-06645	5.000	EACH
101	801-06710	120.000	DAY
102	801-06775	LUMP	LUMP
103	801-07119	323.000	LFT
104	802-05701	152.000	LFT
105	802-07135	8.000	EACH
106	802-76025	109.000	SFT
107	802-76035	23.000	SFT
108	802-76035	156.000	SFT
109	802-76045	36.000	SFT
110	802-76125	4.000	EACH
111	805-01815	4.000	EACH
112	805-01842	10.000	EACH
113	805-02152	8.000	EACH
114	805-02426	410.000	LFT
115	805-06592	1,127.000	LFT
116	805-78100	1.000	EACH
117	805-78205	6.000	EACH
118	805-78230	2.000	EACH
119	805-78370	8.000	EACH
120	805-78420	4.000	EACH
121	805-78445	1.000	EACH
122	805-78467	52.000	LFT
123	805-78480	1,133.000	LFT
124	805-78485	1,403.000	LFT
125	805-78490	435.000	LFT
126	805-78510	1,564.000	LFT
127	805-78746	1,542.000	LFT
128	805-78925	1.000	EACH
129	805-81032	4.000	EACH
130	805-96014	260.000	LFT
131	807-02191	1.000	EACH
132	807-02193	10.000	EACH
133	807-03051	720.000	LFT
134	807-04654	10.000	EACH
135	807-07580	1,040.000	LFT
136	807-86620	10.000	EACH
137	807-86805	3.000	EACH
138	807-86910	10.000	EACH
139	807-86915	10.000	EACH
140	807-86920	18.000	EACH
141	807-86925	4.000	EACH
142	807-86930	20.000	EACH
143	807-86935	4.000	EACH
144	808-06703	1,531.000	LFT

CALL ORDER : 171
 LETTING DATE :

CONTRACT ID : R -28746-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
145	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	303.000	LFT
146	808-06716 LINE, REMOVE	1,040.000	LFT
147	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,901.000	LFT
148	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	16,564.000	LFT
149	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	191.000	LFT
150	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	853.000	LFT
151	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	39.000	EACH
152	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	36.000	EACH

CALL ORDER : 181
 LETTING DATE :

CONTRACT ID : R -28851-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PIPE LINING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
5	616-02320 GEOTEXTILES	335.000	SYS
6	616-05688 RIPRAP, CLASS 1	106.000	TON
7	616-06405 RIPRAP, REVETMENT	30.000	TON
8	725-06859 PIPE LINER, THERMOPLASTIC, 48 IN.	165.000	LFT
9	725-06873 PIPE LINER, THERMOPLASTIC, 54 IN.	224.000	LFT
10	725-06875 PIPE LINER, THERMOPLASTIC, 66 IN.	95.000	LFT
11	725-06876 PIPE LINER, THERMOPLASTIC, 72 IN.	102.000	LFT
12	725-09032 PIPE LINER, THERMOPLASTIC, 28 SFT.	120.000	LFT
13	725-09033 PIPE LINER, THERMOPLASTIC, 31 SFT.	110.000	LFT
14	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 191
 LETTING DATE :

CONTRACT ID : R -29043-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BEAUTIFICATION/WILDFLOWERS		
1 105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
2 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
3 621-06545	FERTILIZER	2.600	TON
4 622-03761	SEED MIXTURE NO. 1	523.000	LBS
5 622-03762	SEED MIXTURE NO. 2	121.000	LBS
6 622-52436	SIGN, DO NOT MOW OR SPRAY	12.000	EACH
7 624-92647	HERBICIDE TREATMENT	11.700	ACRE
8 801-06640	CONSTRUCTION SIGN, A	8.000	EACH
9 802-04893	REFERENCE POST	20.000	EACH

CALL ORDER : 201
 LETTING DATE :

CONTRACT ID : R -29238-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS		
1 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
2 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
3 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
4 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
5 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP

CALL ORDER : 231
 LETTING DATE :

CONTRACT ID : RS-28830-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-01180 COMPACTED AGGREGATE, NO. 53	500.000	TON
8	304-07491 HMA PATCHING, TYPE C	100.000	TON
9	306-08033 MILLING, ASPHALT, 1 IN.	71,004.000	SYS
10	306-08043 MILLING, TRANSITION	1,200.000	SYS
11	306-08432 MILLING, APPROACH	8,700.000	SYS
12	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,054.000	TON
13	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	4,805.000	TON
14	402-07452 HMA, TYPE C, WEDGE AND LEVEL	100.000	TON
15	406-05520 ASPHALT FOR TACK COAT	22.000	TON
16	610-07488 HMA FOR APPROACHES, TYPE C	720.000	TON
17	720-44000 CASTING, ADJUST TO GRADE	15.000	EACH
18	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,450.000	LFT
19	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,450.000	LFT
20	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	156.000	LFT
21	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	156.000	LFT
22	801-06640 CONSTRUCTION SIGN, A	33.000	EACH
23	801-06710 FLASHING ARROW SIGN	10.000	DAY
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
25	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	4,750.000	LFT
26	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	475.000	LFT
27	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,550.000	LFT
28	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	11.000	EACH
29	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
30	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	250.000	LFT
31	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	29,250.000	LFT
32	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	6,400.000	LFT
33	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	13,450.000	LFT
34	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	156.000	LFT
35	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	10.000	EACH
36	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	5.000	EACH

CALL ORDER : 261
 LETTING DATE :

CONTRACT ID : B -27147-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
8	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	29,944.000	CYS
10	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	92.000	TON
11	205-06932 TEMPORARY CHECK DAM, STRAW BALES	45.000	LFT
12	205-06937 TEMPORARY SILT FENCE	1,275.000	LFT
13	207-08266 SUBGRADE TREATMENT, TYPE III	2,550.000	SYS
14	211-06467 AGGREGATE FOR END BENT BACKFILL	59.300	CYS
15	211-07454 STRUCTURE BACKFILL	25.000	CYS
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,722.000	TON
17	303-07449 COMPACTED AGGREGATE, NO. 73	132.000	TON
18	402-07432 HMA SURFACE, TYPE A	346.000	TON
19	402-07435 HMA INTERMEDIATE, TYPE A	558.000	TON
20	406-05521 ASPHALT FOR TACK COAT	4,185.000	SYS
21	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	34.700	LFT
22	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
23	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
24	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	240.200	LFT
25	603-04622 FENCE GATE, FARM FIELD, 47 IN. X 32 FT.	1.000	EACH
26	603-06040 FENCE, FARM FIELD, 47 IN.	640.000	LFT
27	604-04927 CONCRETE	80.000	LFT
28	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	178.400	SYS
29	615-06505 MONUMENT, B	2.000	EACH
30	615-06510 MONUMENT, C	1.000	EACH
31	616-02320 GEOTEXTILES	2,463.000	SYS
32	616-05689 RIPRAP, CLASS 2	1,850.000	TON
33	616-06405 RIPRAP, REVETMENT	385.000	TON
34	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
35	621-01743 SEED MIXTURE, GRASS, 2	253.000	LBS
36	621-06545 FERTILIZER	2.000	TON
37	621-06553 SEED MIXTURE, R	446.000	LBS
38	621-06565 MULCHING MATERIAL	10.000	TON
39	621-06567 WATER	3.000	KGAL
40	621-06574 SODDING	721.000	SYS
41	622-52436 SIGN, DO NOT MOW OR SPRAY	2.000	EACH
42	622-91786 SEEDLING	380.000	EACH
43	622-98200 SIGN, DO NOT DISTURB	2.000	EACH
44	701-02938 CORED HOLE IN ROCK, 24 IN.	109.000	LFT
45	701-51190 PILE, STEEL H, HP 10 X 42	160.000	LFT
46	701-91792 PILE TIP, STEEL H	10.000	EACH
47	702-90915 CONCRETE, A	1.300	CYS
48	703-51032 REINFORCING STEEL, EPOXY COATED	29,416.000	LBS

CALL ORDER : 261
 LETTING DATE :

CONTRACT ID : B -27147-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	704-51002 CONCRETE, C, SUPERSTRUCTURE	156.500	CYS
50	706-06344 RAILING, TS-1	212.500	LFT
51	707-05985 STRUCTURAL MEMBERS, CONCRETE I-BEAM, IV, 54 IN. X 20 IN.	425.000	LFT
52	709-51821 SURFACE SEAL	LUMP	LUMP
53	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	28.000	LFT
54	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	104.000	LFT
55	715-05407 PIPE, END BENT DRAIN, 6 IN.	150.000	LFT
56	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
57	715-46010 PIPE END SECTION, 18 IN.	4.000	EACH
58	732-02744 GATE VALVE AND BOX, 6 IN.	2.000	EACH
59	732-91738 WATER MAIN, DUCTILE IRON, 6 IN.	1,225.000	LFT
60	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
61	801-06625 DETOUR ROUTE MARKER ASSEMBLY	19.000	EACH
62	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
63	801-07118 BARRICADE, III-A	72.000	LFT
64	801-07119 BARRICADE, III-B	72.000	LFT
65	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	25.000	SFT
66	802-76055 SIGN POST, A	28.000	LFT
67	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	3,260.000	LFT

CALL ORDER : 281
 LETTING DATE :

CONTRACT ID : M -29158-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HERIBICIDE TREATMENT		
1 624-92647	HERBICIDE TREATMENT	1,966.000	ACRE
2 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 291
 LETTING DATE :

CONTRACT ID : M -29174-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	District Maintenance Work		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	1.000	MOS
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	202-96133 PIPE, REMOVE	40.000	LFT
7	214-07202 GEOGRID, I	115.000	SYS
8	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5.000	TON
9	303-01180 COMPACTED AGGREGATE, NO. 53	3.000	TON
10	303-60012 AGGREGATE, 2	83.000	TON
11	303-94433 AGGREGATE, 12	314.000	CYS
12	406-05520 ASPHALT FOR TACK COAT	2.000	TON
13	616-02320 GEOTEXTILES	165.000	SYS
14	616-06405 RIPRAP, REVETMENT	15.000	TON
15	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
16	621-06559 MULCHED SEEDING, R	178.000	SYS
17	621-06570 TOP SOIL	125.000	CYS
18	715-05116 PIPE, TYPE 1, CIRCULAR, 8 IN.	25.000	LFT
19	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	25.000	LFT
20	715-05133 PIPE, TYPE 1, CIRCULAR, 60 IN.	70.000	LFT
21	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	30.000	TON
22	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
23	801-06625 DETOUR ROUTE MARKER ASSEMBLY	70.000	EACH
24	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	801-07118 BARRICADE, III-A	120.000	LFT
27	801-07119 BARRICADE, III-B	120.000	LFT

CALL ORDER : 301
 LETTING DATE :

CONTRACT ID : M -29181-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
1	105-07038 FIELD OFFICE, A	12.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	601-01522 GUARDRAIL TRANSITION TYPE TGB	5.000	EACH
9	601-03452 EXCAVATION OF DAMAGED STEEL BEAM GUARDRAIL BURIED END	1.000	EACH
10	601-03453 GUARDRAIL, CLAMP BAR, 7.125 IN., ALUMINUM	40.000	EACH
11	601-03454 GUARDRAIL, ALUMINUM MODIFIED TERMINAL ENDS	1.000	EACH
12	601-03455 GUARDRAIL, ALUMINUM OFFSET BRACKET, TYPE E	1.000	EACH
13	601-03456 GUARDRAIL POST, WOOD TYPE W5	5.000	EACH
14	601-03457 GUARDRAIL W THRIE BEAM RAIL SECTION, 12 FT. 6 IN.	25.000	EACH
15	601-03460 GUARDRAIL, CHANNEL 6.7 LBS PER LFT., LABOR ONLY	250.000	LFT
16	601-03462 GUARDRAIL, POST STEEL, 8.5 LBS PER LFT, 7 FT. 0 IN.	400.000	EACH
17	601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION	15.000	EACH
18	601-03469 W BEAM BACK UP PLATE, STEEL	400.000	EACH
19	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	5.000	EACH
20	601-03492 GUARDRAIL, MISCELLANEOUS MATERIAL, AND LABOR FOR REPAIR	LUMP	LUMP
21	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
22	601-06798 TIMBER BLOCK	200.000	EACH
23	601-07179 ET_2000 OS UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL	50.000	EACH
24	601-07564 SOIL TUBE AND PLATE FOR END TREATMENT, OS OR MS	100.000	EACH
25	601-08131 GUARDRAIL, THRIE BEAM, BACKUP PLATE, STEEL	1.000	EACH
26	601-08132 GUARDRAIL, THRIE BEAM, BLOCKOUT, STEEL	15.000	EACH
27	601-08133 GUARDRAIL, POST STEEL, 8.5 LBS. PER LFT., 10 FT. 0 IN.	5.000	EACH
28	601-61370 GUARDRAIL POST BRACKET, 8.5 LBS PER LFT., GALVANIZED	160.000	EACH
29	601-61545 GUARDRAIL POST, ALUMINUM, INSTALL	5.000	EACH
30	601-62070 GUARDRAIL, STEEL BEAM, GALVANIZED	15,000.000	LFT
31	601-62080 GUARDRAIL, STEEL BEAM, CURVED SECTION, GALVANIZED	150.000	LFT
32	601-62100 GUARDRAIL POST, STEEL, INSTALL	30.000	EACH
33	601-62540 GUARDRAIL POST, PLUMB	800.000	EACH
34	601-62555 GUARDRAIL,, TUBING, ELIPTICAL, ALUMINUM, LABOR ONLY	65.000	LFT
35	601-62570 GUARDRAIL DIAPHRAGM, ALUMINUM	10.000	EACH
36	601-62580 GUARDRAIL SPLICE BAR, ALUMINUM	10.000	EACH
37	601-90678 CONCRETE, A, BURIED END SECTION	3.000	CYS
38	601-91504 GUARDRAIL POST, W1, 10 IN X 10 IN	2.000	EACH
39	601-91505 GUARDRAIL POST, W2, 8 IN. X 8 IN.	2.000	EACH
40	601-91510 GUARDRAIL POST, W3, 8 IN. X 8 IN.	2.000	EACH
41	601-91511 GUARDRAIL POST, W4, 8 IN. X 8 IN.	2.000	EACH
42	601-91542 GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	10.000	EACH
43	601-91575 GUARDRAIL BLOCK, 6 IN. X 8 IN., B2	2.000	EACH
44	601-91576 GUARDRAIL BLOCK, 6 IN. X 8 IN., B3	2.000	EACH
45	601-91649 GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	5.000	EACH
46	601-91653 GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	3.000	EACH
47	601-92271 GUARDRAIL POST BRACKET, GALVANIZED, LABOR ONLY	15.000	EACH
48	601-92355 GUARDRAIL STANDARD TERMINAL CONNECTOR, MICHIGAN END SHOE	1.000	EACH

CALL ORDER : 301
 LETTING DATE :

CONTRACT ID : M -29181-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
49 601-95342	GUARDRAIL SPLICE PLATE, C, GALVANIZED	1.000	EACH
50 601-97054	GUARDRAIL BRACKET, STEEL, OFFSET	15.000	EACH
51 801-06640	CONSTRUCTION SIGN, A	6.000	EACH
52 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 311
 LETTING DATE :

CONTRACT ID : M -29182-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
1	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	601-01522 GUARDRAIL TRANSITION TYPE TGB	2.000	EACH
8	601-03452 EXCAVATION OF DAMAGED STEEL BEAM GUARDRAIL BURIED END	10.000	EACH
9	601-03453 GUARDRAIL, CLAMP BAR, 7.125 IN., ALUMINUM	20.000	EACH
10	601-03454 GUARDRAIL, ALUMINUM MODIFIED TERMINAL ENDS	1.000	EACH
11	601-03455 GUARDRAIL, ALUMINUM OFFSET BRACKET, TYPE E	1.000	EACH
12	601-03456 GUARDRAIL POST, WOOD TYPE W5	20.000	EACH
13	601-03457 GUARDRAIL W THRIE BEAM RAIL SECTION, 12 FT. 6 IN.	5.000	EACH
14	601-03460 GUARDRAIL, CHANNEL 6.7 LBS PER LFT., LABOR ONLY	500.000	LFT
15	601-03462 GUARDRAIL, POST STEEL, 8.5 LBS PER LFT, 7 FT. 0 IN.	200.000	EACH
16	601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION	5.000	EACH
17	601-03469 W BEAM BACK UP PLATE, STEEL	500.000	EACH
18	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	4.000	EACH
19	601-03492 GUARDRAIL, MISCELLANEOUS MATERIAL, AND LABOR FOR REPAIR	LUMP	LUMP
20	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
21	601-06798 TIMBER BLOCK	150.000	EACH
22	601-07179 ET_2000 OS UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL	20.000	EACH
23	601-07564 SOIL TUBE AND PLATE FOR END TREATMENT, OS OR MS	25.000	EACH
24	601-08131 GUARDRAIL, THRIE BEAM, BACKUP PLATE, STEEL	1.000	EACH
25	601-08132 GUARDRAIL, THRIE BEAM, BLOCKOUT, STEEL	1.000	EACH
26	601-08133 GUARDRAIL, POST STEEL, 8.5 LBS. PER LFT., 10 FT. 0 IN.	1.000	EACH
27	601-61370 GUARDRAIL POST BRACKET, 8.5 LBS PER LFT., GALVANIZED	125.000	EACH
28	601-61545 GUARDRAIL POST, ALUMINUM, INSTALL	5.000	EACH
29	601-62070 GUARDRAIL, STEEL BEAM, GALVANIZED	10,000.000	LFT
30	601-62080 GUARDRAIL, STEEL BEAM, CURVED SECTION, GALVANIZED	300.000	LFT
31	601-62100 GUARDRAIL POST, STEEL, INSTALL	40.000	EACH
32	601-62540 GUARDRAIL POST, PLUMB	700.000	EACH
33	601-62555 GUARDRAIL,, TUBING, ELIPTICAL, ALUMINUM, LABOR ONLY	65.000	LFT
34	601-62570 GUARDRAIL DIAPHRAGM, ALUMINUM	10.000	EACH
35	601-62580 GUARDRAIL SPLICE BAR, ALUMINUM	10.000	EACH
36	601-90678 CONCRETE, A, BURIED END SECTION	3.000	CYS
37	601-91504 GUARDRAIL POST, W1, 10 IN X 10 IN	1.000	EACH
38	601-91505 GUARDRAIL POST, W2, 8 IN. X 8 IN.	1.000	EACH
39	601-91510 GUARDRAIL POST, W3, 8 IN. X 8 IN.	1.000	EACH
40	601-91511 GUARDRAIL POST, W4, 8 IN. X 8 IN.	1.000	EACH
41	601-91542 GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	2.000	EACH
42	601-91575 GUARDRAIL BLOCK, 6 IN. X 8 IN., B2	1.000	EACH
43	601-91576 GUARDRAIL BLOCK, 6 IN. X 8 IN., B3	1.000	EACH
44	601-91649 GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	3.000	EACH
45	601-91653 GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	1.000	EACH
46	601-92271 GUARDRAIL POST BRACKET, GALVANIZED, LABOR ONLY	30.000	EACH
47	601-92355 GUARDRAIL STANDARD TERMINAL CONNECTOR, MICHIGAN END SHOE	2.000	EACH
48	601-95342 GUARDRAIL SPLICE PLATE, C, GALVANIZED	10.000	EACH

CALL ORDER : 311
 LETTING DATE :

CONTRACT ID : M -29182-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
49 601-97054	GUARDRAIL BRACKET, STEEL, OFFSET	15.000	EACH
50 801-06640	CONSTRUCTION SIGN, A	6.000	EACH
51 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 321
LETTING DATE :

CONTRACT ID : M -29218-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT MAINTENANCE WORK		
1 105-08520	CELLULAR TELEPHONE/RADIO	2.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 623-04884	MOWING, CYCLE NO. 1	1.000	CYCL
5 623-04885	MOWING, CYCLE NO. 2	1.000	CYCL
6 623-04886	MOWING, CYCLE NO. 3	1.000	CYCL
7 623-04887	MOWING, CYCLE NO. 4	1.000	CYCL
8 623-61013	MOWING, FULL WIDTH, URBAN	4.000	CYCL

CALL ORDER : 331
 LETTING DATE :

CONTRACT ID : M -29219-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE - MOWING		
1	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	623-04884 MOWING, CYCLE NO. 1	1.000	CYCL
5	623-04884 MOWING, CYCLE NO. 1	1.000	CYCL
6	623-04885 MOWING, CYCLE NO. 2	1.000	CYCL
7	623-04885 MOWING, CYCLE NO. 2	1.000	CYCL
8	623-04886 MOWING, CYCLE NO. 3	1.000	CYCL
9	623-04886 MOWING, CYCLE NO. 3	1.000	CYCL
10	623-04887 MOWING, CYCLE NO. 4	1.000	CYCL
11	623-04887 MOWING, CYCLE NO. 4	1.000	CYCL

CALL ORDER : 341
LETTING DATE :

CONTRACT ID : M -29221-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT MAINTENANCE WORK		
1 105-08520	CELLULAR TELEPHONE/RADIO	2.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 623-04884	MOWING, CYCLE NO. 1	1.000	CYCL
5 623-04884	MOWING, CYCLE NO. 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO. 2	1.000	CYCL
7 623-04885	MOWING, CYCLE NO. 2	1.000	CYCL
8 623-04886	MOWING, CYCLE NO. 3	1.000	CYCL
9 623-04886	MOWING, CYCLE NO. 3	1.000	CYCL
10 623-04887	MOWING, CYCLE NO. 4	1.000	CYCL
11 623-04887	MOWING, CYCLE NO. 4	1.000	CYCL

CALL ORDER : 351
 LETTING DATE :

CONTRACT ID : M -29222-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT MAINTENANCE WORK		
1 105-08520	CELLULAR TELEPHONE/RADIO	2.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 623-04884	MOWING, CYCLE NO. 1	2.000	CYCL
5 623-04885	MOWING, CYCLE NO. 2	2.000	CYCL
6 623-04886	MOWING, CYCLE NO. 3	2.000	CYCL
7 623-04887	MOWING, CYCLE NO. 4	2.000	CYCL

CALL ORDER : 361
LETTING DATE :

CONTRACT ID : M -29223-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT MAINTENANCE WORK		
1 105-08520	CELLULAR TELEPHONE/RADIO	2.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 623-04884	MOWING, CYCLE NO. 1	1.000	CYCL
5 623-04885	MOWING, CYCLE NO. 2	1.000	CYCL
6 623-04886	MOWING, CYCLE NO. 3	1.000	CYCL

CALL ORDER : 371
 LETTING DATE :

CONTRACT ID : M -29224-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT MAINTENANCE WORK		
1	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	623-04884 MOWING, CYCLE NO. 1	1.000	CYCL
5	623-04884 MOWING, CYCLE NO. 1	1.000	CYCL
6	623-04885 MOWING, CYCLE NO. 2	1.000	CYCL
7	623-04885 MOWING, CYCLE NO. 2	1.000	CYCL
8	623-04886 MOWING, CYCLE NO. 3	1.000	CYCL
9	623-04886 MOWING, CYCLE NO. 3	1.000	CYCL
10	623-04887 MOWING, CYCLE NO. 4	1.000	CYCL
11	623-04887 MOWING, CYCLE NO. 4	1.000	CYCL

CALL ORDER : 381
LETTING DATE :

CONTRACT ID : M -29225-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT MAINTENANCE WORK		
1 105-08520	CELLULAR TELEPHONE/RADIO	2.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 623-04884	MOWING, CYCLE NO. 1	1.000	CYCL
5 623-04885	MOWING, CYCLE NO. 2	1.000	CYCL
6 623-04886	MOWING, CYCLE NO. 3	1.000	CYCL
7 623-04887	MOWING, CYCLE NO. 4	1.000	CYCL
8 623-05684	MOWING, CYCLE NO. 5	1.000	CYCL
9 623-06008	MOWING, CYCLE NO. 7	1.000	CYCL
10 623-06010	MOWING, CYCLE NO. 9	1.000	CYCL
11 623-06704	MOWING, CYCLE NO. 6	1.000	CYCL
12 623-06707	MOWING, CYCLE NO. 8	1.000	CYCL

CALL ORDER : 391
LETTING DATE :

CONTRACT ID : M -29226-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HERBICIDE TREATMENT		
1 105-08520	CELLULAR TELEPHONE/RADIO	3.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	27.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5 624-92647	HERBICIDE TREATMENT	1,508.000	ACRE

CALL ORDER : 401
LETTING DATE :

CONTRACT ID : M -29227-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HERBICIDE TREATMENT		
1 105-08520	CELLULAR TELEPHONE/RADIO	3.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	36.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5 624-92647	HERBICIDE TREATMENT	54.000	ACRE
6 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 411
LETTING DATE :

CONTRACT ID : M -29228-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HERBICIDE TREATMENT		
1 105-08520	CELLULAR TELEPHONE/RADIO	3.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	9.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5 624-92647	HERBICIDE TREATMENT	3,162.000	ACRE

CALL ORDER : 421
 LETTING DATE :

CONTRACT ID : M -29231-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT MAINTENANCE WORK		
1	105-06904 PHONE(SUPERVISOR)	1.000	EACH
2	105-06906 CELLULAR SERVICE(SUPERVISOR)	12.000	MOS
3	105-07039 FIELD OFFICE, B	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02241 GUARDRAIL, REMOVE	12,000.000	LFT
9	202-93741 GUARD RAIL END TREATMENT, REMOVE	33.000	EACH
10	601-01128 GUARDRAIL TRANSITION TYPE WGB	1.000	EACH
11	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
12	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	500.000	LFT
13	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	3.000	EACH
14	601-62540 GUARDRAIL POST, PLUMB	100.000	EACH
15	601-91428 GUARDRAIL ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	1.000	EACH
16	601-94645 GUARDRAIL END TREATMENT, SENTRE	1.000	EACH
17	601-94689 GUARDRAIL END TREATMENT, OS	20.000	EACH
18	601-94690 GUARDRAIL END TREATMENT, MS	10.000	EACH
19	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	12,000.000	LFT
20	601-99109 GUARDRAIL, W BEAM, DOUBLE FACED, 3 FT. 1.5 IN. SPACING	50.000	LFT
21	601-99123 GUARDRAIL TRANSITION, GP	1.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 431
 LETTING DATE :

CONTRACT ID : M -29232-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
1	105-06904 PHONE(SUPERVISOR)	1.000	EACH
2	105-06906 CELLULAR SERVICE(SUPERVISOR)	12.000	MOS
3	105-07038 FIELD OFFICE, A	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02241 GUARDRAIL, REMOVE	12,000.000	LFT
9	202-93741 GUARD RAIL END TREATMENT, REMOVE	20.000	EACH
10	601-01128 GUARDRAIL TRANSITION TYPE WGB	1.000	EACH
11	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
12	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	500.000	LFT
13	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	3.000	EACH
14	601-62540 GUARDRAIL POST, PLUMB	100.000	EACH
15	601-91428 GUARDRAIL ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	1.000	EACH
16	601-94645 GUARDRAIL END TREATMENT, SENTRE	1.000	EACH
17	601-94689 GUARDRAIL END TREATMENT, OS	10.000	EACH
18	601-94690 GUARDRAIL END TREATMENT, MS	5.000	EACH
19	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	12,000.000	LFT
20	601-99109 GUARDRAIL, W BEAM, DOUBLE FACED, 3 FT. 1.5 IN. SPACING	50.000	LFT
21	601-99123 GUARDRAIL TRANSITION, GP	1.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 451
 LETTING DATE :

CONTRACT ID : T -28782-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
8	202-02240 PAVEMENT REMOVAL	192.000	m2
9	202-02250 TREE, 250 mm, REMOVE	4.000	EACH
10	202-02279 CURB AND GUTTER, REMOVE	255.000	m
11	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	4.000	EACH
12	202-96022 CONCRETE FOUNDATION, REMOVE	4.000	EACH
13	202-96133 PIPE, REMOVE	286.000	m
14	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
15	203-02000 EXCAVATION, COMMON	1,700.000	m3
16	205-06932 TEMPORARY CHECK DAM, STRAW BALES	203.000	m
17	205-06933 TEMPORARY DITCH INLET PROTECTION	4.000	EACH
18	205-06937 TEMPORARY SILT FENCE	250.000	m
19	207-08263 SUBGRADE TREATMENT, TYPE IA	1,662.000	m2
20	211-07454 STRUCTURE BACKFILL	359.390	m3
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,504.260	Mg
22	304-07493 WIDENING WITH HMA, TYPE B	682.000	Mg
23	306-08043 MILLING, TRANSITION	640.000	m2
24	402-07433 HMA SURFACE, TYPE B	912.000	Mg
25	402-07438 HMA INTERMEDIATE, TYPE B	622.000	Mg
26	402-07451 HMA, TYPE B, WEDGE AND LEVEL	522.000	Mg
27	406-05520 ASPHALT FOR TACK COAT	5.000	Mg
28	605-06120 CURB, CONCRETE	120.000	m
29	605-06140 CURB AND GUTTER, CONCRETE	420.400	m
30	607-06335 PAVED SIDE DITCH, A	31.300	m
31	610-07487 HMA FOR APPROACHES, TYPE B	245.000	Mg
32	610-07712 PCCP FOR APPROACHES, 150 mm	258.000	m2
33	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
34	615-06505 MONUMENT, B	5.000	EACH
35	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
36	616-06451 RIPRAP, UNIFORM	12.000	Mg
37	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
38	621-06545 FERTILIZER	8.000	Mg
39	621-06554 SEED MIXTURE, U	1,323.000	kg
40	621-06565 MULCHING MATERIAL	36.000	Mg
41	621-06574 SODDING	1,586.000	m2
42	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	8.000	m
43	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	18.000	m
44	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	23.000	m
45	715-05168 PIPE, TYPE 3, CIRCULAR, 300 mm	286.000	m
46	715-46000 PIPE END SECTION, 300 mm	29.000	EACH
47	720-44040 CASTING, 7, FURNISH AND ADJUST TO GRADE	1.000	EACH
48	720-45235 CATCH BASIN, E7	2.000	EACH

CALL ORDER : 451
 LETTING DATE :

CONTRACT ID : T -28782-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
49	720-45410 MANHOLE, C4	1.000	EACH
50	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
51	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	1,100.000	m
52	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
53	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
54	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	29.200	m
55	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	4.630	m2
56	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	0.720	m2
57	805-01816 SIGNAL SUPPORT FOUNDATION, 900 mm X 900 mm X 2500 mm	4.000	EACH
58	805-01842 HANDHOLE, SIGNAL	7.000	EACH
59	805-01844 CONDUIT, STEEL, GALVANIZED, 50 mm, UNDERGROUND	611.000	m
60	805-01879 SIGNAL SERVICE	1.000	EACH
61	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	1,026.000	m
62	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	1.000	EACH
63	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	8.000	EACH
64	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
65	805-78420 DISCONNECT HANGER	4.000	EACH
66	805-78467 SIGNAL CABLE, 3C 8GA.	4.000	m
67	805-78485 SIGNAL CABLE, 5C 14GA.	92.000	m
68	805-78490 SIGNAL CABLE, 7C 14GA.	169.000	m
69	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	804.000	m
70	805-78785 SIGNAL DETECTOR HOUSING	12.000	EACH
71	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	378.000	m
72	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
73	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
74	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	6.000	EACH
75	807-01878 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	2.000	EACH
76	807-02783 LUMINAIRE MAST ARM, 4.6 m	2.000	EACH
77	807-04651 WIRE	44.000	m
78	807-04651 WIRE	200.000	m
79	807-86805 SERVICE POINT, I	1.000	EACH
80	807-86910 CONNECTOR KIT, UNFUSED	2.000	EACH
81	807-86915 CONNECTOR KIT, FUSED	2.000	EACH
82	807-86920 MULTIPLE COMPRESSION FITTING, NOT WATERPROOFED	3.000	EACH
83	807-86930 INSULATION LINK, NONWATERPROOFED	4.000	EACH
84	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,770.000	m
85	808-06716 LINE, REMOVE	427.000	m
86	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	560.000	m
87	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	44.000	m
88	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	6.000	EACH
89	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH
90	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	1,254.000	m
91	808-96016 LINE, THERMOPLASTIC, SOLID, YELLOW, 300 mm	93.000	m

CALL ORDER : 461
 LETTING DATE :

CONTRACT ID : T -29336-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW TRAFFIC SIGNALS			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	67.000	SYS
9	203-02000 EXCAVATION, COMMON	394.000	CYS
10	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
11	205-06937 TEMPORARY SILT FENCE	2,000.000	LFT
12	207-08268 SUBGRADE TREATMENT, TYPE IV	1,045.000	SYS
13	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	93.000	TON
14	302-07455 DENSE GRADED SUBBASE	128.000	CYS
15	303-01180 COMPACTED AGGREGATE, NO. 53	70.000	TON
16	402-07432 HMA SURFACE, TYPE A	23.000	TON
17	402-07435 HMA INTERMEDIATE, TYPE A	69.000	TON
18	406-05521 ASPHALT FOR TACK COAT	278.000	SYS
19	502-06329 PCCP, 12 IN.	767.000	SYS
20	503-03489 RETROFITTED TIE BARS	208.000	EACH
21	503-05240 D-1 CONTRACTION JOINT	375.000	LFT
22	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
23	621-06560 MULCHED SEEDING, U	1,200.000	SYS
24	720-91972 INLET, RELOCATE	1.000	EACH
25	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
26	801-06710 FLASHING ARROW SIGN	14.000	DAY
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	3.000	EACH
29	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	22.500	SFT
30	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
31	805-01842 HANDHOLE, SIGNAL	6.000	EACH
32	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,092.000	LFT
33	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
34	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	5.000	EACH
35	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	1.000	EACH
36	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
37	805-78420 DISCONNECT HANGER	3.000	EACH
38	805-78445 SIGNAL SERVICE	1.000	EACH
39	805-78467 SIGNAL CABLE, 3C 8GA.	22.000	LFT
40	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,799.000	LFT
41	805-78485 SIGNAL CABLE, 5C 14GA.	132.000	LFT
42	805-78490 SIGNAL CABLE, 7C 14GA.	852.000	LFT
43	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	4,109.000	LFT
44	805-78785 SIGNAL DETECTOR HOUSING	5.000	EACH
45	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	626.000	LFT
46	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
47	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
48	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	4.000	EACH

CALL ORDER : 461
LETTING DATE :

CONTRACT ID : T -29336-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW TRAFFIC SIGNALS		
49 808-03631	LINE, EPOXY, SOLID, WHITE, 4 IN.	675.000	LFT
50 808-03632	LINE, EPOXY, SOLID, YELLOW, 4 IN.	925.000	LFT
51 808-06716	LINE, REMOVE	100.000	LFT
52 808-07591	LINE, EPOXY, SOLID, WHITE, 24 IN.	132.000	LFT
53 808-74807	PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	9.000	EACH
54 808-74808	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	3.000	EACH
55 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6.000	EACH

