

CALL ORDER : 120
 LETTING DATE :

CONTRACT ID : IR-29348-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERCHANGE MODIFICATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	18.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	6.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	108.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
7	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	4,765.000	LFT
13	202-02928 CATCH BASIN, REMOVE	3.000	EACH
14	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
19	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
20	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
21	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
22	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
23	202-51368 SLOPEWALL, REMOVE	6.000	SYS
24	202-51822 BRIDGE DECK OVERLAY, REMOVE	702.000	SYS
25	202-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	10.000	EACH
26	202-91385 INLET, REMOVE	1.000	EACH
27	202-91840 FENCE, CHAIN LINK, REMOVE	2,560.000	LFT
28	202-95579 SERVICE POINT, REMOVE	3.000	EACH
29	202-96133 PIPE, REMOVE	929.000	LFT
30	202-99187 FENCE, FARM FIELD, REMOVE	9,360.000	LFT
31	203-02000 EXCAVATION, COMMON	367,301.000	CYS
32	203-02070 BORROW	83,649.000	CYS
33	204-08415 STAKES, SETTLEMENT	6.000	EACH
34	205-06930 SPLASHPAD, RIPRAP	15.000	TON
35	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	81.200	TON
36	205-06932 TEMPORARY CHECK DAM, STRAW BALES	648.000	LFT
37	205-06933 TEMPORARY DITCH INLET PROTECTION	5.000	EACH
38	205-06936 TEMPORARY SEDIMENT TRAP	173.000	TON
39	205-06937 TEMPORARY SILT FENCE	1,850.000	LFT
40	205-06938 TEMPORARY SLOPE DRAIN	1,328.000	LFT
41	206-51220 EXCAVATION, WET	300.000	CYS
42	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	1,276.000	CYS
43	207-08263 SUBGRADE TREATMENT, TYPE IA	12,265.000	SYS
44	207-08267 SUBGRADE TREATMENT, TYPE IIIA	14,544.000	SYS
45	211-02050 B BORROW	5,167.000	CYS
46	211-06467 AGGREGATE FOR END BENT BACKFILL	330.100	CYS
47	211-07454 STRUCTURE BACKFILL	9,549.900	CYS
48	213-04324 FLOWABLE FILL	2.000	CYS

CALL ORDER : 120
 LETTING DATE :

CONTRACT ID : IR-29348-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERCHANGE MODIFICATION		
49	213-52830 FLOWABLE MORTAR	37.200	CYS
50	214-07202 GEOGRID, I	90.000	SYS
51	215-07043 CHEMICAL MODIFICATION, SOILS	2,140.000	SYS
52	215-07043 CHEMICAL MODIFICATION, SOILS	120,472.000	SYS
53	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,509.800	TON
54	302-06464 SUBBASE FOR PCCP	26,907.000	CYS
55	302-07455 DENSE GRADED SUBBASE	171.500	CYS
56	302-08562 COARSE AGGREGATE, 8	31.100	TON
57	303-01180 COMPACTED AGGREGATE, NO. 53	16,799.000	TON
58	402-07432 HMA SURFACE, TYPE A	1,181.400	TON
59	402-07435 HMA INTERMEDIATE, TYPE A	2,006.000	TON
60	406-05521 ASPHALT FOR TACK COAT	102.000	SYS
61	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
62	501-06321 QC/QA-PCCP, 10 IN.	10,790.000	SYS
63	501-08194 QC/QA-PCCP, 11.5 IN.	90,509.000	SYS
64	503-05240 D-1 CONTRACTION JOINT	6,474.000	LFT
65	503-05310 TERMINAL JOINT	396.000	LFT
66	601-01522 GUARDRAIL TRANSITION TYPE TGB	6.000	EACH
67	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
68	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
69	601-94689 GUARDRAIL END TREATMENT, OS	9.000	EACH
70	601-94690 GUARDRAIL END TREATMENT, MS	2.000	EACH
71	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,550.000	LFT
72	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	300.000	LFT
73	602-06729 BARRIER DELINEATOR	67.000	EACH
74	602-08472 CONCRETE BARRIER, 33 IN.	400.000	LFT
75	603-01159 FENCE, CHAIN LINK, 42 IN.	8,602.000	LFT
76	603-06040 FENCE, FARM FIELD, 47 IN.	2,900.000	LFT
77	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	1,027.300	SYS
78	615-06490 RIGHT OF WAY MARKER	44.000	EACH
79	615-06505 MONUMENT, B	5.000	EACH
80	615-06510 MONUMENT, C	6.000	EACH
81	615-06515 MONUMENT, D	9.000	EACH
82	616-02320 GEOTEXTILES	4,502.000	SYS
83	616-05688 RIPRAP, CLASS 1	180.000	TON
84	616-06405 RIPRAP, REVETMENT	750.000	TON
85	616-06406 RIPRAP, REVETMENT	22.000	SYS
86	616-06451 RIPRAP, UNIFORM	1,113.000	TON
87	616-51367 SLOPEWALL, CONCRETE, 4 IN.	6.000	SYS
88	621-06545 FERTILIZER	34.520	TON
89	621-06553 SEED MIXTURE, R	11,275.000	LBS
90	621-06559 MULCHED SEEDING, R	9,000.000	SYS
91	621-06565 MULCHING MATERIAL	132.600	TON
92	621-06567 WATER	27.300	KGAL
93	621-06574 SODDING	7,555.000	SYS
94	622-91786 SEEDLING	90.000	EACH
95	622-98200 SIGN, DO NOT DISTURB	4.000	EACH
96	701-04732 PILE	1,427.600	LFT

CALL ORDER : 120
 LETTING DATE :

CONTRACT ID : IR-29348-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERCHANGE MODIFICATION			
97	701-51195 PILE, STEEL H, HP 12 X 53	2,100.000	LFT
98	701-91792 PILE TIP, STEEL H	402.000	EACH
99	701-95780 PILE, STEEL H, HP 12 X 74	19,924.500	LFT
100	702-51005 CONCRETE, A, SUBSTRUCTURE	1,842.800	CYS
101	702-51015 CONCRETE, B, FOOTINGS	443.200	CYS
102	702-90915 CONCRETE, A	103.600	CYS
103	703-06028 REINFORCING BARS	187,455.000	LBS
104	703-06029 REINFORCING BARS, EPOXY COATED	612,328.000	LBS
105	703-51030 REINFORCING STEEL	20,718.000	LBS
106	703-51032 REINFORCING STEEL, EPOXY COATED	70,593.000	LBS
107	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	138.000	EACH
108	704-04850 CONCRETE	260.000	SYS
109	704-51002 CONCRETE, C, SUPERSTRUCTURE	2,202.500	CYS
110	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	12.000	EACH
111	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN.	125.000	SYS
112	706-51020 CONCRETE, C, RAILING	179.300	CYS
113	707-09183 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	6,130.000	LFT
114	707-09193 STRUCTURAL MEMBERS, CONCRETE BOX BEAM,	1,564.000	SFT
115	709-51821 SURFACE SEAL	LUMP	LUMP
116	709-51821 SURFACE SEAL	LUMP	LUMP
117	709-51821 SURFACE SEAL	LUMP	LUMP
118	709-51821 SURFACE SEAL	LUMP	LUMP
119	709-51821 SURFACE SEAL	LUMP	LUMP
120	710-51864 FIELD DRILLED HOLE	289.000	EACH
121	710-51870 REPOINTING MASONRY IN STRUCTURES	160.000	SFT
122	714-26724 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 12 FT. X 4 FT.	78.000	LFT
123	714-44240 CONCRETE, A, STRUCTURES	13.300	CYS
124	714-93641 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 4 FT. X 3 FT.	212.000	LFT
125	715-02876 GRANULAR BACKFILL	1.000	LFT
126	715-03172 TAPPING SLEEVE AND VALVE, 14IN.	2.000	EACH
127	715-03177 GATE VALVE, 14 IN.	1.000	EACH
128	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	625.000	LFT
129	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	44,132.600	LFT
130	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	5,272.500	LFT
131	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	161.000	LFT
132	715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN.	174.000	LFT
133	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	394.000	LFT
134	715-05232 PIPE, TYPE 1, DEFORMED, MIN. AREA 2.9 SQ.FT.	20.000	LFT
135	715-05237 PIPE, TYPE 1, DEFORMED, MIN. AREA 6.4 SQ. FT.	154.000	LFT
136	715-05407 PIPE, END BENT DRAIN, 6 IN.	295.000	LFT
137	715-46005 PIPE END SECTION, 15 IN.	6.000	EACH
138	715-46020 PIPE END SECTION, 24 IN.	8.000	EACH
139	715-46040 PIPE END SECTION, 36 IN.	1.000	EACH
140	715-46060 PIPE END SECTION, MIN. AREA 2.2 SQ. FT.	1.000	EACH
141	715-46095 PIPE END SECTION, MIN. AREA 6.4 SQ. FT.	1.000	EACH
142	715-90834 PIPE, DRAINTILE, 12 IN.	2,000.000	LFT
143	715-93919 WATER MAIN, 14 IN.	4,694.000	LFT
144	715-95868 WATER LINE, STEEL CASING, 36 IN.	474.000	LFT

CALL ORDER : 120
 LETTING DATE :

CONTRACT ID : IR-29348-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERCHANGE MODIFICATION			
145	716-98960 CASING, STEEL	369.000	LFT
146	718-06528 OUTLET PROTECTOR, 1	78.000	EACH
147	718-06531 OUTLET PROTECTOR, 3	4.000	EACH
148	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
149	718-52610 AGGREGATE FOR UNDERDRAINS	4,759.800	CYS
150	718-99153 GEOTEXTILES FOR UNDERDRAIN	47,679.200	SYS
151	720-09109 COMBINATION	2.000	EACH
152	720-45030 INLET, E7	3.000	EACH
153	720-45070 INLET, P12A	2.000	EACH
154	720-45141 INLET, H5, MODIFIED	1.000	EACH
155	720-45416 MANHOLE, E4	1.000	EACH
156	720-95310 INLET, P12A, MODIFIED	2.000	EACH
157	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	20.000	SFT
158	722-51842 BRIDGE DECK OVERLAY	1,178.000	SYS
159	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	6.000	CYS
160	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	500.000	SFT
161	724-51925 STRUCTURAL EXPANSION JOINT, SS	271.000	LFT
162	731-93945 FACE PANELS, CONCRETE	10,776.000	SFT
163	731-93946 WALL ERECTION	10,776.000	SFT
164	731-93947 LEVELING PAD, CONCRETE	548.000	LFT
165	732-04995 LINE STOP	2.000	EACH
166	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
167	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
168	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13,667.000	LFT
169	801-06625 DETOUR ROUTE MARKER ASSEMBLY	4.000	EACH
170	801-06640 CONSTRUCTION SIGN, A	27.000	EACH
171	801-06645 CONSTRUCTION SIGN, B	16.000	EACH
172	801-06710 FLASHING ARROW SIGN	455.000	DAY
173	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
174	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	1.000	EACH
175	801-07118 BARRICADE, III-A	372.000	LFT
176	801-07119 BARRICADE, III-B	108.000	LFT
177	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	10,450.000	LFT
178	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
179	802-02372 OVERHEAD SIGN STRUCTURE, INSTALL	8.000	EACH
180	802-04893 REFERENCE POST	2.000	EACH
181	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	434.000	LFT
182	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	560.500	LFT
183	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	36.000	EACH
184	802-07101 SIGN LIGHTING SYSTEM, TRACK, BOX TRUSS	2.000	EACH
185	802-07102 SIGN LIGHTING SYSTEM, TRACK, CANTILEVER	3.000	EACH
186	802-07137 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	4.000	EACH
187	802-07138 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, IX	2.000	EACH
188	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	20.000	EACH
189	802-07153 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	4.000	EACH
190	802-07158 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, I	3.000	EACH
191	802-07275 BOX TRUSS SIGN FOUNDATION, V-C	2.000	EACH
192	802-07278 BOX TRUSS SIGN FOUNDATION, V-D	2.000	EACH

CALL ORDER : 120
 LETTING DATE :

CONTRACT ID : IR-29348-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERCHANGE MODIFICATION			
193	802-76015 SIGN,PANEL,ENCAPSULATED LENS WITH LEGEND	1,923.000	SFT
194	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	14.250	SFT
195	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	688.670	SFT
196	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	36.000	SFT
197	802-76095 STRUCTURAL STEEL, BREAKAWAY	4,144.000	LBS
198	802-76110 SPAN OVERHEAD SIGN STRUCTURE, BOX TRUSS	2.000	EACH
199	802-76140 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM	3.000	EACH
200	804-06725 DELINEATOR WITH POST, D1, 3 IN. DIA.	22.000	EACH
201	804-06725 DELINEATOR WITH POST, D1, 3 IN. DIA.	252.000	EACH
202	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,550.000	LFT
203	805-08652 POLE CIRCUIT CABLE	3,660.000	LFT
204	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	3,576.000	LFT
205	805-86898 CONDUIT, STEEL, GALVANIZED, .75 IN.	750.000	LFT
206	805-95889 WIRE, NO. 10 COPPER, 1C	2,673.000	LFT
207	805-96014 SAW CUT, FULL DEPTH	11,062.000	LFT
208	807-01603 SERVICE POINT, TYPE II	4.000	EACH
209	807-02109 LUMINAIRE, SIGN, MERCURY VAPOR, WITH GLARE SHIELD, WITH	14.000	EACH
210	807-02191 HANDHOLE, LIGHTING	4.000	EACH
211	807-02857 CIRCUIT BREAKER PANEL	1.000	EACH
212	807-03934 LIGHT STRUCTURE, REMOVE	29.000	EACH
213	807-04653 LIGHTING FOUNDATION	36.000	EACH
214	807-04653 LIGHTING FOUNDATION	8.000	EACH
215	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	20,515.000	LFT
216	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	302.000	LFT
217	807-82001 SIGN CIRCUIT INSTALLATION, BOX TRUSS, 2 LUMINAIRES	2.000	EACH
218	807-82003 SIGN CIRCUIT INSTALLATION, BOX TRUSS, 4 LUMINAIRES	2.000	EACH
219	807-82016 SIGN CIRCUIT INSTALLATION, CANTILEVER, 2 LUMINAIRES	3.000	EACH
220	807-82480 LIGHT POLE, HIGH MAST, 135 FT. E.M.H.	8.000	EACH
221	807-84752 LIGHT POLE, 40 FT. E.M.H., 10.0 FT. MAST ARM, TRANSFORMER	5.000	EACH
222	807-84762 LIGHT POLE, 40 FT. E.M.H., 15.0 FT. MAST ARM, TRANSFORMER	1.000	EACH
223	807-84804 LIGHT POLE, 42 FT. E.M.H., 10.0 FT. MAST ARM, TRANSFORMER	13.000	EACH
224	807-84814 LIGHT POLE, 42 FT. E.M.H., 15.0 FT. MAST ARM, TRANSFORMER	17.000	EACH
225	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE	36.000	EACH
226	807-86665 LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM	48.000	EACH
227	807-86750 LUMINAIRE UNDERPASS, WALL MOUNTED, HIGH PRESSURE SODIUM, 150	6.000	EACH
228	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	56.000	EACH
229	807-86955 CABLE DUCT MARKER	13.000	EACH
230	807-87556 WIRE, THW OR TW, NO. 10 COPPER STRANDED	2,250.000	LFT
231	807-95488 NEMA 4/5 UNDERPASS OR SIGN CIRCUIT BREAKER, ENCLOSURE	1.000	EACH
232	808-01328 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WRONG WAY RAMP	3.000	EACH
233	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	5,027.000	LFT
234	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	915.000	LFT
235	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	601.000	LFT
236	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	72.000	LFT
237	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	39,431.000	LFT
238	808-75053 LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	8,212.000	LFT
239	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	28,210.000	LFT
240	808-75061 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	7,857.000	LFT

CALL ORDER : 120
LETTING DATE :

CONTRACT ID : IR-29348-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERCHANGE MODIFICATION		
241 808-75067	TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	126.000	LFT
242 808-75071	PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC LANE INDICATION	4.000	EACH
243 808-75073	PAVEMENT MESSAGE MARKINGS PREFORMED PLASTIC, WORD ONLY	4.000	EACH
244 808-75326	LINE, PREFORMED PLASTIC, SOLID, WHITE, 12 IN.	1,909.000	LFT
245 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	767.000	EACH

CALL ORDER : 150
 LETTING DATE :

CONTRACT ID : IR-29723-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS		
1	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
2	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
3	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
4	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
5	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
6	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
7	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
8	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
9	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
11	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	1,232.000	SFT
12	205-06937 TEMPORARY SILT FENCE	12,000.000	LFT
13	621-06560 MULCHED SEEDING, U	4,500.000	SYS

CALL ORDER : 190
 LETTING DATE :

CONTRACT ID : R -29283-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING INSTALLATION AND MAINTENANCE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
3	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	202-52710 SIDEWALK, CONCRETE, REMOVE	52.900	SYS
6	203-02000 EXCAVATION, COMMON	291.500	CYS
7	203-02070 BORROW	139.800	CYS
8	210-07532 GRASS	218.000	EACH
9	210-07893 IRRIGATION	LUMP	LUMP
10	212-06282 STOCKPILED SELECTED MATERIAL, SALVAGED	102.100	CYS
11	604-07894 CURB RAMP, CONCRETE, A	8.800	SYS
12	604-91531 SIDEWALK, CONCRETE, 4 IN.	47.700	SYS
13	605-06125 CURB, CONCRETE, MODIFIED	1,474.000	LFT
14	605-06255 CENTER CURB, D, CONCRETE	67.500	SYS
15	621-06560 MULCHED SEEDING, U	4,482.400	SYS
16	621-06567 WATER	0.980	KGAL
17	621-06570 TOP SOIL	195.500	CYS
18	621-06574 SODDING	273.000	SYS
19	621-98038 MULCH, HARDWOOD SHREDDED BARK	35.000	CYS
20	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	17.000	EACH
21	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	11.000	EACH
22	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	43.000	EACH
23	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	29.000	EACH
24	622-05654 PLANT, PERENNIAL	111.000	EACH
25	622-05654 PLANT, PERENNIAL	90.000	EACH
26	622-05654 PLANT, PERENNIAL	56.000	EACH
27	622-05654 PLANT, PERENNIAL	106.000	EACH
28	622-05654 PLANT, PERENNIAL	149.000	EACH
29	622-05654 PLANT, PERENNIAL	105.000	EACH
30	711-90932 EDGING, STEEL	1,060.200	LFT
31	715-04612 PIPE	540.000	LFT
32	715-04612 PIPE	788.600	LFT
33	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
34	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
35	801-06710 FLASHING ARROW SIGN	120.000	DAY
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
38	805-78480 SIGNAL CABLE, 3C 14GA.	107.000	LFT
39	805-95466 FLASHING BEACON WITH SIGNAL AHEAD SIGN, 6 IN. I BEAM AND	2.000	EACH
40	807-02191 HANDHOLE, LIGHTING	6.000	EACH
41	807-04654 LIGHT POLE	43.000	EACH
42	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	3,854.000	LFT
43	807-08469 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING,	45.000	EACH
44	807-86810 SERVICE POINT, II	2.000	EACH
45	807-86810 SERVICE POINT, II	1.000	EACH

CALL ORDER : 200
 LETTING DATE :

CONTRACT ID : R -29432-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
5	203-02000 EXCAVATION, COMMON	9,944.000	CYS
6	203-02070 BORROW	663.000	CYS
7	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	151.000	TON
8	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
9	207-08264 SUBGRADE TREATMENT, TYPE II	11,673.000	SYS
10	211-02050 B BORROW	50.000	CYS
11	211-07454 STRUCTURE BACKFILL	360.500	CYS
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	76.000	TON
13	306-08043 MILLING, TRANSITION	251.000	SYS
14	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	764.000	TON
15	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,249.000	TON
16	401-07422 QC/QA-HMA, 1, 64, BASE, 19.0 mm	2,523.000	TON
17	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	1,538.000	TON
18	406-05520 ASPHALT FOR TACK COAT	6.940	TON
19	610-07486 HMA FOR APPROACHES, TYPE A	38.000	TON
20	616-02320 GEOTEXTILES	66.000	SYS
21	616-06405 RIPRAP, REVETMENT	38.000	TON
22	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
23	621-06545 FERTILIZER	2.000	TON
24	621-06553 SEED MIXTURE, R	800.000	LBS
25	621-06565 MULCHING MATERIAL	10.000	TON
26	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	64.000	LFT
27	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	6,085.000	LFT
28	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	100.000	LFT
29	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	100.000	LFT
30	715-05052 PIPE, TYPE 4, CIRCULAR, 12 IN.	100.000	LFT
31	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	588.000	LFT
32	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	886.000	LFT
33	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	48.000	LFT
34	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
35	715-46030 PIPE END SECTION, 30 IN.	2.000	EACH
36	715-46040 PIPE END SECTION, 36 IN.	2.000	EACH
37	718-06531 OUTLET PROTECTOR, 3	17.000	EACH
38	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
39	718-52610 AGGREGATE FOR UNDERDRAINS	549.000	CYS
40	718-99153 GEOTEXTILES FOR UNDERDRAIN	4,166.000	SYS
41	720-45040 INLET, G7	1.000	EACH
42	720-45415 MANHOLE, D4	1.000	EACH
43	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
44	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
45	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
46	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
47	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
48	801-07119 BARRICADE, III-B	48.000	LFT

CALL ORDER : 200
LETTING DATE :

CONTRACT ID : R -29432-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
49 802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	9.500	LFT
50 802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	9.000	SFT
51 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	6,400.000	LFT
52 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	800.000	LFT

CALL ORDER : 210
 LETTING DATE :

CONTRACT ID : R -29453-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-07039 FIELD OFFICE, B	8.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	8.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-86946 HANDHOLE, REMOVE	3.000	EACH
12	202-96022 CONCRETE FOUNDATION, REMOVE	1.000	EACH
13	202-96632 TRAFFIC SIGNALS AND EQUIPMENT, REMOVE	1.000	EACH
14	303-01180 COMPACTED AGGREGATE, NO. 53	161.000	TON
15	304-07783 HMA PATCHING, TYPE D	700.000	TON
16	306-08034 MILLING, ASPHALT, 1 1/2 IN.	401,862.000	SYS
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	33,154.000	TON
19	406-05520 ASPHALT FOR TACK COAT	96.500	TON
20	503-05240 D-1 CONTRACTION JOINT	252.000	LFT
21	506-06333 PCCP PATCHING, FULL DEPTH	450.000	SYS
22	507-07482 CRACKS AND JOINTS IN PCCP, ROUT AND SEAL	24,000.000	LFT
23	725-06872 PIPE LINER, THERMOPLASTIC, 42 IN.	228.000	LFT
24	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
25	801-03290 CONSTRUCTION SIGN, C	29.000	EACH
26	801-06204 TEMPORARY PAVEMENT MARKING, 5 IN.	12,713.000	LFT
27	801-06208 TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	12,713.000	LFT
28	801-06640 CONSTRUCTION SIGN, A	77.000	EACH
29	801-06710 FLASHING ARROW SIGN	300.000	DAY
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
32	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	9,120.000	LFT
33	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	9,120.000	LFT
34	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	32,723.000	LFT
35	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	133,883.000	LFT
36	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	9,508.000	LFT
37	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	1,300.000	LFT
38	808-06716 LINE, REMOVE	20,520.000	LFT
39	808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN.	2,280.000	LFT
40	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	133,883.000	LFT
41	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,987.000	EACH

CALL ORDER : 240
 LETTING DATE :

CONTRACT ID : RS-28478-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	7.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	110.000	TON
8	304-07783 HMA PATCHING, TYPE D	1,642.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	220,388.000	SYS
10	306-08043 MILLING, TRANSITION	4,993.000	SYS
11	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
12	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	18,182.000	TON
13	402-07787 HMA WEDGE AND LEVEL, TYPE D	490.000	TON
14	406-05520 ASPHALT FOR TACK COAT	73.000	TON
15	506-06333 PCCP PATCHING, FULL DEPTH	1,516.000	SYS
16	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	14,784.000	LFT
17	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	14,784.000	LFT
18	801-06640 CONSTRUCTION SIGN, A	44.000	EACH
19	801-06710 FLASHING ARROW SIGN	300.000	DAY
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
21	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
22	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	500.000	LFT
23	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	50.000	LFT
24	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	160.000	LFT
25	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	2.000	EACH
26	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	5,303.000	LFT
27	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	4,890.000	LFT
28	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	4,890.000	LFT
29	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	14,784.000	LFT
30	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	68,209.000	LFT
31	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	9,012.000	LFT
32	808-75215 LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	3,972.000	LFT
33	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
34	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
35	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,549.000	EACH
36	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,549.000	EACH

CALL ORDER : 244
 LETTING DATE :

CONTRACT ID : RS-28664-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	4.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02676 TRANSPORTATION OF SALVAGEABLE MILLED MATERIAL	300.000	TON
8	203-02000 EXCAVATION, COMMON	60.000	CYS
9	303-60012 AGGREGATE, 2	86.700	TON
10	304-07491 HMA PATCHING, TYPE C	566.900	TON
11	306-08034 MILLING, ASPHALT, 1 1/2 IN.	52,155.300	SYS
12	306-08041 MILLING, PCCP	200.000	SYS
13	306-08043 MILLING, TRANSITION	740.000	SYS
14	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	4,500.000	TON
15	406-05520 ASPHALT FOR TACK COAT	17.900	TON
16	604-07902 CURB RAMP, CONCRETE, H	15.400	SYS
17	616-02320 GEOTEXTILES	428.000	SYS
18	621-06559 MULCHED SEEDING, R	66.700	SYS
19	621-06575 SODDING, NURSERY	12.000	SYS
20	801-04308 ROAD CLOSURE SIGN ASSEMBLY	1.000	EACH
21	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,085.000	LFT
22	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,085.000	LFT
23	801-06625 DETOUR ROUTE MARKER ASSEMBLY	67.000	EACH
24	801-06640 CONSTRUCTION SIGN, A	32.000	EACH
25	801-06710 FLASHING ARROW SIGN	41.000	DAY
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	801-07118 BARRICADE, III-A	20.000	LFT
28	804-06771 DELINEATOR POST, FLEXIBLE	140.000	EACH
29	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	4,636.000	LFT
30	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,672.000	LFT
31	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	10,426.000	LFT
32	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,700.000	LFT
33	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	560.000	LFT
34	808-06716 LINE, REMOVE	560.000	LFT
35	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	570.000	LFT
36	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	17,912.000	LFT
37	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	240.000	LFT
38	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	18.000	EACH
39	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	16.000	EACH
40	808-75994 PRISMATIC REFLECTOR	27.000	EACH
41	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	251.000	EACH
42	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	251.000	EACH

CALL ORDER : 250

CONTRACT ID : RS-28779-B

LETTING DATE :

NOTE : USER DEFINED, BOILERPLATE TEXT WILL BE DISPLAYED. THE TEXT DISPLAYED IN THIS AREA WILL BE DETERMINED BY THE SETASID CODE. A MAXIMUM OF 25 LINES WILL BE DISPLAYED.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-07038 FIELD OFFICE, A	7.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	7.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-93741 GUARD RAIL END TREATMENT, REMOVE	8.000	EACH
11	203-02070 BORROW	40.000	CYS
12	203-90014 LINEAR GRADING	11.000	STA
13	303-01180 COMPACTED AGGREGATE, NO. 53	400.000	TON
14	303-07449 COMPACTED AGGREGATE, NO. 73	100.000	TON
15	304-07489 HMA PATCHING, TYPE A	9,736.000	TON
16	305-60400 COMPACTED AGGREGATE FOR PATCHING	100.000	TON
17	306-08033 MILLING, ASPHALT, 1 IN.	136,989.000	SYS
18	306-08043 MILLING, TRANSITION	1,600.000	SYS
19	306-08432 MILLING, APPROACH	8,329.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	10,444.000	TON
22	402-07432 HMA SURFACE, TYPE A	68.000	TON
23	402-07450 HMA WEDGE AND LEVEL, TYPE A	667.000	TON
24	406-05520 ASPHALT FOR TACK COAT	36.000	TON
25	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
26	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	4.000	EACH
27	608-04395 AGGREGATE FOR SHOULDER DRAINS	100.000	TON
28	610-07486 HMA FOR APPROACHES, TYPE A	687.000	TON
29	615-06505 MONUMENT, B	80.000	EACH
30	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
31	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
32	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
33	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	5,697.000	LFT
34	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,697.000	LFT
35	801-06640 CONSTRUCTION SIGN, A	51.000	EACH
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	644.000	LFT
38	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	360.000	LFT
39	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	35.000	LFT
40	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	112,197.000	LFT
41	808-06716 LINE, REMOVE	1,146.000	LFT
42	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	8,891.000	LFT
43	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	57,619.000	LFT
44	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	51.000	LFT
45	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,165.000	EACH

CALL ORDER : 260
 LETTING DATE :

CONTRACT ID : RS-29115-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06904 PHONE(SUPERVISOR)	1.000	EACH
2	105-06905 PHONE(INSPECTOR)	1.000	EACH
3	105-06905 PHONE(INSPECTOR)	1.000	EACH
4	105-06905 PHONE(INSPECTOR)	1.000	EACH
5	105-06905 PHONE(INSPECTOR)	1.000	EACH
6	105-06906 CELLULAR SERVICE(SUPERVISOR)	6.000	MOS
7	105-06907 CELLULAR SERVICE(INSPECTOR)	6.000	MOS
8	105-06907 CELLULAR SERVICE(INSPECTOR)	6.000	MOS
9	105-06907 CELLULAR SERVICE(INSPECTOR)	6.000	MOS
10	105-06907 CELLULAR SERVICE(INSPECTOR)	6.000	MOS
11	105-07039 FIELD OFFICE, B	6.000	MOS
12	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
13	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
14	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
15	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
16	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
17	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
18	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
19	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
20	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
21	202-02772 CASTING, REMOVE	1.000	EACH
22	304-07783 HMA PATCHING, TYPE D	1,312.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN.	55,540.000	SYS
24	306-08043 MILLING, TRANSITION	1,500.000	SYS
25	306-08432 MILLING, APPROACH	170.000	SYS
26	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
27	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	4,582.000	TON
28	402-07787 HMA WEDGE AND LEVEL, TYPE D	100.000	TON
29	404-05511 SEAL COAT, 2	15,953.000	SYS
30	406-05520 ASPHALT FOR TACK COAT	15.000	TON
31	602-02476 BARRIER, CONCRETE, MODIFIED	120.000	LFT
32	610-07788 HMA FOR APPROACHES, TYPE D	14.000	TON
33	720-01355 CLEAN EXISTING INLET	3.000	EACH
34	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
35	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
36	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,145.000	LFT
37	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7,145.000	LFT
38	801-06640 CONSTRUCTION SIGN, A	50.000	EACH
39	801-06710 FLASHING ARROW SIGN	90.000	DAY
40	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
41	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
42	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	358.000	LFT
43	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	3,371.000	LFT
44	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	3,831.000	LFT
45	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN.	310.000	LFT
46	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1,220.000	LFT
47	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	3,889.000	LFT
48	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	13,563.000	LFT

CALL ORDER : 260
LETTING DATE :

CONTRACT ID : RS-29115-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49 808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	3,068.000	LFT
50 808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	745.000	LFT
51 808-07591	LINE, EPOXY, SOLID, WHITE, 24 IN.	50.000	LFT
52 808-74811	LINE, EPOXY, BROKEN, WHITE, 5 IN.	1,256.000	LFT
53 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	12,858.000	LFT
54 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	310.000	EACH
55 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	310.000	EACH

CALL ORDER : 270
 LETTING DATE :

CONTRACT ID : RS-29310-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	406.250	LFT
11	202-93741 GUARD RAIL END TREATMENT, REMOVE	2.000	EACH
12	203-08607 LINEAR GRADING	400.000	LFT
13	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
14	205-06937 TEMPORARY SILT FENCE	2,300.000	LFT
15	207-08263 SUBGRADE TREATMENT, TYPE IA	9,589.000	SYS
16	303-07449 COMPACTED AGGREGATE, NO. 73	4,685.000	TON
17	304-07490 HMA PATCHING, TYPE B	2,332.000	TON
18	304-07783 HMA PATCHING, TYPE D	6,662.000	TON
19	306-08033 MILLING, ASPHALT, 1 IN.	227,253.000	SYS
20	306-08043 MILLING, TRANSITION	1,200.000	SYS
21	306-08432 MILLING, APPROACH	20,322.000	SYS
22	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
23	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	6,520.000	TON
24	401-07348 QC/QA-HMA, 4, 70, SURFACE, 12.5 mm	18,800.000	TON
25	406-05520 ASPHALT FOR TACK COAT	77.000	TON
26	601-01522 GUARDRAIL TRANSITION TYPE TGB	2.000	EACH
27	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
28	601-94690 GUARDRAIL END TREATMENT, MS	1.000	EACH
29	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	1.000	EACH
30	601-97803 GUARDRAIL END TREATMENT, MS, SPARE PARTS PACKAGE	1.000	EACH
31	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	81.250	LFT
32	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	250.000	LFT
33	606-07484 MILLED HMA SHOULDER CORRUGATIONS	84,035.000	LFT
34	610-07788 HMA FOR APPROACHES, TYPE D	2,800.000	TON
35	615-06527 MONUMENT, SECTION CORNER	4.000	EACH
36	619-91969 CLEAN UNDERDRAIN OUTLET	106.000	EACH
37	715-01354 CLEAN EXISTING PIPE	93,251.000	LFT
38	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	300.000	LFT
39	718-34010 PIPE, UNDERDRAIN, PERFORATED, 0.064 IN., 6 IN.	4,500.000	LFT
40	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	16.000	EACH
41	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,850.000	LFT
42	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,850.000	LFT
43	801-06640 CONSTRUCTION SIGN, A	32.000	EACH
44	801-06710 FLASHING ARROW SIGN	100.000	DAY
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH
47	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	2,300.000	LFT
48	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH

CALL ORDER : 270
LETTING DATE :

CONTRACT ID : RS-29310-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49 804-06771	DELINEATOR POST, FLEXIBLE	100.000	EACH
50 804-06771	DELINEATOR POST, FLEXIBLE	80.000	EACH
51 808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	12,240.000	LFT
52 808-75205	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	49,738.000	LFT
53 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	49,738.000	LFT
54 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,091.000	EACH
55 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1,091.000	EACH

CALL ORDER : 310
 LETTING DATE :

CONTRACT ID : B -28124-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
9	203-02000 EXCAVATION, COMMON	495.000	CYS
10	203-02070 BORROW	3,689.000	CYS
11	203-51223 EXCAVATION, WATERWAY	104.000	CYS
12	205-06932 TEMPORARY CHECK DAM, STRAW BALES	48.000	LFT
13	205-06937 TEMPORARY SILT FENCE	2,181.000	LFT
14	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	98.000	CYS
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,682.000	SYS
16	211-06467 AGGREGATE FOR END BENT BACKFILL	35.000	CYS
17	211-07454 STRUCTURE BACKFILL	36.100	CYS
18	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	470.600	TON
19	302-07455 DENSE GRADED SUBBASE	36.100	CYS
20	306-08034 MILLING, ASPHALT, 1 1/2 IN.	489.000	SYS
21	402-07432 HMA SURFACE, TYPE A	268.000	TON
22	402-07435 HMA INTERMEDIATE, TYPE A	296.300	TON
23	402-07440 HMA BASE, TYPE A	985.000	TON
24	402-07450 HMA WEDGE AND LEVEL, TYPE A	91.220	TON
25	404-05511 SEAL COAT, 2	572.000	SYS
26	405-05518 ASPHALT FOR PRIME COAT	454.000	SYS
27	406-05521 ASPHALT FOR TACK COAT	7,865.000	SYS
28	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
29	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
30	601-01701 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 2	1.000	EACH
31	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
32	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
33	610-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	206.700	SYS
34	610-07486 HMA FOR APPROACHES, TYPE A	99.800	TON
35	615-06490 RIGHT OF WAY MARKER	8.000	EACH
36	615-06505 MONUMENT, B	2.000	EACH
37	615-99189 PLAQUE, ALUMINUM	1.000	EACH
38	616-02320 GEOTEXTILES	649.000	SYS
39	616-06405 RIPRAP, REVETMENT	435.000	TON
40	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
41	621-06559 MULCHED SEEDING, R	2,622.000	SYS
42	701-51195 PILE, STEEL H, HP 12 X 53	614.600	LFT
43	701-91792 PILE TIP, STEEL H	14.000	EACH
44	702-51005 CONCRETE, A, SUBSTRUCTURE	19.400	CYS
45	703-51032 REINFORCING STEEL, EPOXY COATED	18,832.000	LBS
46	704-51002 CONCRETE, C, SUPERSTRUCTURE	78.000	CYS
47	706-06344 RAILING, TS-1	150.000	LFT
48	707-05973 STRUCTURAL MEMBERS, CONCRETE BOX BEAM, CB, 27 IN. X 36 IN.	2,673.000	SFT

CALL ORDER : 310
 LETTING DATE :

CONTRACT ID : B -28124-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	709-51821 SURFACE SEAL	LUMP	LUMP
50	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN.	287.500	LFT
51	715-05407 PIPE, END BENT DRAIN, 6 IN.	118.000	LFT
52	715-46010 PIPE END SECTION, 18 IN.	6.000	EACH
53	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
54	801-06625 DETOUR ROUTE MARKER ASSEMBLY	22.000	EACH
55	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
56	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
57	801-07118 BARRICADE, III-A	48.000	LFT
58	801-07119 BARRICADE, III-B	48.000	LFT
59	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	300.000	LFT
60	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	2,400.000	LFT

CALL ORDER : 320
 LETTING DATE :

CONTRACT ID : B -28361-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	10.000	MOS
3	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	920.000	m3
10	203-02070 BORROW	260.000	m3
11	203-51223 EXCAVATION, WATERWAY	470.000	m3
12	205-06934 TEMPORARY MULCHING	1.000	Mg
13	205-06937 TEMPORARY SILT FENCE	212.000	m
14	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,228.000	m2
15	211-06467 AGGREGATE FOR END BENT BACKFILL	26.000	m3
16	211-07454 STRUCTURE BACKFILL	9.000	m3
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	836.000	Mg
18	302-07455 DENSE GRADED SUBBASE	14.000	m3
19	306-08043 MILLING, TRANSITION	166.000	m2
20	402-07432 HMA SURFACE, TYPE A	137.000	Mg
21	402-07435 HMA INTERMEDIATE, TYPE A	202.000	Mg
22	405-05518 ASPHALT FOR PRIME COAT	1,212.000	m2
23	406-05521 ASPHALT FOR TACK COAT	1,227.000	m2
24	601-01839 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 6	1.000	EACH
25	601-05586 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 9	1.000	EACH
26	601-06037 GUARDRAIL END TREATMENT, I	2.000	EACH
27	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
28	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	57.150	m
29	603-06040 FENCE, FARM FIELD, 1190 mm	265.000	m
30	603-95915 CATTLE GUARD	1.000	EACH
31	603-96042 FENCE GATE, FARM FIELD, 1190 mm X 7.3 m	1.000	EACH
32	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 250 mm	92.000	m2
33	610-07486 HMA FOR APPROACHES, TYPE A	29.000	Mg
34	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
35	616-02320 GEOTEXTILES	696.000	m2
36	616-05688 RIPRAP, CLASS 1	382.000	Mg
37	616-06405 RIPRAP, REVETMENT	149.000	Mg
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
39	621-02770 EROSION CONTROL BLANKET	1,790.000	m2
40	621-06545 FERTILIZER	1.000	Mg
41	621-06557 SEED MIXTURE, T	45.000	kg
42	621-06559 MULCHED SEEDING, R	2,330.000	m2
43	621-06567 WATER	8.000	kL
44	621-06574 SODDING	94.000	m2
45	621-06575 SODDING, NURSERY	321.000	m2
46	622-98200 SIGN, DO NOT DISTURB	4.000	EACH
47	701-51195 PILE, STEEL H, HP 310 X 79	144.000	m
48	701-91792 PILE TIP, STEEL H	12.000	EACH

CALL ORDER : 320
 LETTING DATE :

CONTRACT ID : B -28361-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	702-92857 CONCRETE, C, SUBSTRUCTURE	12.600	m3
50	703-51032 REINFORCING STEEL, EPOXY COATED	10,640.000	kg
51	704-51002 CONCRETE, C, SUPERSTRUCTURE	95.000	m3
52	706-06344 RAILING, TS-1	57.152	m
53	707-06831 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 1372 mm x 1067 mm	93.900	m
54	709-51821 SURFACE SEAL	LUMP	LUMP
55	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	45.000	m
56	715-05407 PIPE, END BENT DRAIN, 150 mm	22.000	m
57	715-46005 PIPE END SECTION, 375 mm	3.000	EACH
58	720-45230 CATCH BASIN, D6	2.000	EACH
59	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
60	801-06625 DETOUR ROUTE MARKER ASSEMBLY	9.000	EACH
61	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
62	801-07118 BARRICADE, III-A	14.400	m
63	801-07119 BARRICADE, III-B	14.400	m
64	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	1.046	m2
65	802-76055 SIGN POST, A	8.000	m

CALL ORDER : 340
 LETTING DATE :

CONTRACT ID : B -29289-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION OR REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
9	202-52710 SIDEWALK, CONCRETE, REMOVE	65.000	SYS
10	206-51215 EXCAVATION, X	16.000	CYS
11	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	34.000	CYS
12	211-07454 STRUCTURE BACKFILL	1,950.000	CYS
13	302-06464 SUBBASE FOR PCCP	365.000	CYS
14	303-01180 COMPACTED AGGREGATE, NO. 53	60.000	TON
15	502-06327 PCCP, 10 IN.	896.000	SYS
16	503-05240 D-1 CONTRACTION JOINT	500.000	LFT
17	604-90256 SIDEWALK, CONCRETE, 6 IN.	91.000	SYS
18	604-91531 SIDEWALK, CONCRETE, 4 IN.	155.000	SYS
19	605-06090 CURB, INTEGRAL, CONCRETE	454.000	LFT
20	610-07487 HMA FOR APPROACHES, TYPE B	310.000	TON
21	611-95728 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 8 IN.	23.000	SYS
22	616-02320 GEOTEXTILES	90.000	SYS
23	616-06405 RIPRAP, REVETMENT	73.000	TON
24	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
25	621-06559 MULCHED SEEDING, R	1,200.000	SYS
26	621-06567 WATER	3.000	KGAL
27	621-06575 SODDING, NURSERY	267.000	SYS
28	702-03607 CORED HOLE IN CONCRETE	9.000	EACH
29	702-51015 CONCRETE, B, FOOTINGS	12.000	CYS
30	702-51863 FIELD DRILLED HOLE IN CONCRETE	488.000	EACH
31	703-06029 REINFORCING BARS, EPOXY COATED	36,589.000	LBS
32	704-51002 CONCRETE, C, SUPERSTRUCTURE	226.700	CYS
33	706-51020 CONCRETE, C, RAILING	70.100	CYS
34	708-51813 PNEUMATICALLY PLACED MORTAR	1,100.000	SFT
35	708-51814 WELDED STEEL WIRE FABRIC	1,100.000	SFT
36	709-51821 SURFACE SEAL	LUMP	LUMP
37	711-91981 TIE ROD	23.000	EACH
38	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	96.000	LFT
39	715-92037 PIPE, PVC, 4 IN.	45.000	LFT
40	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
41	720-45410 MANHOLE, C4	2.000	EACH
42	720-98174 INLET, B15	2.000	EACH
43	720-98555 INLET, C15	2.000	EACH
44	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
45	801-06625 DETOUR ROUTE MARKER ASSEMBLY	6.000	EACH
46	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
47	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
48	801-07118 BARRICADE, III-A	96.000	LFT

CALL ORDER : 340
LETTING DATE :

CONTRACT ID : B -29289-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION OR REPAIR		
49 801-07119	BARRICADE, III-B	96.000	LFT
50 802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	43.200	LFT
51 802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	16.000	SFT

CALL ORDER : 350
 LETTING DATE :

CONTRACT ID : B -29360-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02240 PAVEMENT REMOVAL	546.000	SYS
8	202-51368 SLOPEWALL, REMOVE	12.000	SYS
9	202-62420 BRIDGE RAILING, REMOVE	19.000	LFT
10	205-02770 EROSION CONTROL BLANKET	8.000	SYS
11	213-08058 FLOWABLE BACKFILL	46.000	CYS
12	303-02051 STONE, 2	8.000	TON
13	304-07492 WIDENING WITH HMA, TYPE A	1.500	TON
14	305-91919 JOINT AND CRACK CLEANING AND SEALING	20.000	LFT
15	306-08043 MILLING, TRANSITION	2,800.000	SYS
16	402-07452 HMA WEDGE AND LEVEL, TYPE C	324.000	TON
17	601-01522 GUARDRAIL TRANSITION TYPE TGB	8.000	EACH
18	602-06944 BARRIER, CONCRETE, 33 IN.	19.000	LFT
19	605-06105 CURB, INTEGRAL, CONCRETE, MODIFIED	17.000	LFT
20	605-09176 CURB TURNOUT, CONCRETE	26.000	LFT
21	605-97170 CURB, PRECAST CONCRETE	17.000	LFT
22	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	546.000	SYS
23	616-02320 GEOTEXTILES	88.000	SYS
24	616-06405 RIPRAP, REVETMENT	66.000	TON
25	616-51367 SLOPEWALL, CONCRETE, 4 IN.	12.000	SYS
26	616-93772 INSPECTION HOLE	4.000	EACH
27	621-06559 MULCHED SEEDING, R	8.000	SYS
28	702-51863 FIELD DRILLED HOLE IN CONCRETE	116.000	EACH
29	703-51032 REINFORCING STEEL, EPOXY COATED	19,810.000	LBS
30	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	8.000	EACH
31	715-99020 PIPE, POLYETHYLENE, 6 IN.	54.000	LFT
32	720-03129 INLET AND CASTING, RESET	1.000	EACH
33	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	450.000	SFT
34	724-03276 EXPANSION JOINT SEALING SYSTEM	250.000	LFT
35	724-51887 STRUCTURAL EXPANSION JOINT, BS8	188.000	LFT
36	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
37	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
38	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	3,720.000	LFT
39	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	24.000	LFT
40	801-06625 DETOUR ROUTE MARKER ASSEMBLY	31.000	EACH
41	801-06640 CONSTRUCTION SIGN, A	41.000	EACH
42	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
43	801-06710 FLASHING ARROW SIGN	33.000	DAY
44	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
48	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 350
 LETTING DATE :

CONTRACT ID : B -29360-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
49	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
50	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
51	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
52	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
53	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
54	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
55	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
56	801-07118 BARRICADE, III-A	150.000	LFT
57	801-07119 BARRICADE, III-B	150.000	LFT
58	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	950.000	LFT
59	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
60	808-06716 LINE, REMOVE	80.000	LFT
61	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	80.000	LFT

CALL ORDER : 400
 LETTING DATE :

CONTRACT ID : M -29362-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	4.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-07449 COMPACTED AGGREGATE, NO. 73	275.000	TON
8	304-07489 HMA PATCHING, TYPE A	320.000	TON
9	306-08043 MILLING, TRANSITION	1,000.000	SYS
10	401-93793 WEDGE AND LEVELING	625.000	TON
11	402-05497 HMA FOR PARK ROAD	2,510.000	TON
12	406-05520 ASPHALT FOR TACK COAT	10.200	TON
13	610-07486 HMA FOR APPROACHES, TYPE A	200.000	TON
14	801-06640 CONSTRUCTION SIGN, A	3.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 410
 LETTING DATE :

CONTRACT ID : M -29784-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE OR REPAIR		
1	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000 DOL
2	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000 DOL
3	601-01522	GUARDRAIL TRANSITION TYPE TGB	1.000 EACH
4	601-01838	GUARDRAIL POST, GALVANIZED, PLUMB IN PLACE	100.000 EACH
5	601-03599	GUARDRAIL, THRIE BEAM, RAIL SECTION, 12 FT. 6 IN	10.000 EACH
6	601-05999	CURVED TERMINAL END	25.000 EACH
7	601-06053	GUARDRAIL	10.000 EACH
8	601-52540	GUARDRAIL TERMINAL SECTION, W BEAM	4.000 EACH
9	601-61340	GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN.	100.000 EACH
10	601-61390	GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE,	25.000 EACH
11	601-61400	GUARDRAIL BURIED END, GALVANIZED, SINGLE FACE	10.000 EACH
12	601-61401	GUARDRAIL BURIED END, STEEL, WITH CONCRETE	4.000 EACH
13	601-61545	GUARDRAIL POST, ALUMINUM, INSTALL	30.000 EACH
14	601-61550	GUARDRAIL TERMINAL END SECTION, ALUMINUM	4.000 EACH
15	601-62070	GUARDRAIL, STEEL BEAM, GALVANIZED	8,000.000 LFT
16	601-62080	GUARDRAIL, STEEL BEAM, CURVED SECTION, GALVANIZED	200.000 LFT
17	601-62090	GUARDRAIL, STEEL BEAM, INSTALL	1,000.000 LFT
18	601-62100	GUARDRAIL POST, STEEL, INSTALL	400.000 EACH
19	601-62110	GUARDRAIL, CHANNEL, 6.7 LBS PER LFT., INSTALL	1,000.000 LFT
20	601-62150	GUARDRAIL POST, 15.5 LBS PER LFT., GALVANIZED,	30.000 EACH
21	601-62450	GUARDRAIL BREAKAWAY CABLE TERMINAL, GALVANIZED, TOTAL	3.000 EACH
22	601-62460	GUARDRAIL ANCHOR CABLE ASSEMBLY, 0.75 IN.	5.000 EACH
23	601-62480	GUARDRAIL BREAKAWAY CABLE TERMINAL, POST OR ALTERNATE	5.000 EACH
24	601-62490	GUARDRAIL, A, BREAKAWAY CABLE TERMINAL FOUNDATION POST	2.000 EACH
25	601-62510	GUARDRAIL BREAKAWAY CABLE TERMINAL, MICHIGAN END SHOE	4.000 EACH
26	601-62554	GUARDRAIL, TUBING, ELLIPTICAL, ALUMINUM, INSTALL	700.000 LFT
27	601-62580	GUARDRAIL SPLICE BAR, ALUMINUM	35.000 EACH
28	601-91197	GUARDRAIL POST BRACKET, 15 LBS PER LFT., ADJUSTABLE,	150.000 EACH
29	601-91426	GUARDRAIL TERMINAL END SECTION, A	2.000 EACH
30	601-91504	GUARDRAIL POST, W1, 10 IN X 10 IN	4.000 EACH
31	601-91505	GUARDRAIL POST, W2, 8 IN. X 8 IN.	4.000 EACH
32	601-91511	GUARDRAIL POST, W4, 8 IN. X 8 IN.	4.000 EACH
33	601-92271	GUARDRAIL POST BRACKET, GALVANIZED, LABOR ONLY	300.000 EACH
34	601-93346	GUARDRAIL CONNECTOR, AS	3.000 EACH
35	601-94689	GUARDRAIL END TREATMENT, OS	10.000 EACH
36	601-94689	GUARDRAIL END TREATMENT, OS	6.000 EACH
37	601-94689	GUARDRAIL END TREATMENT, OS	6.000 EACH
38	601-94689	GUARDRAIL END TREATMENT, OS	6.000 EACH
39	601-94690	GUARDRAIL END TREATMENT, MS	2.000 EACH
40	601-94690	GUARDRAIL END TREATMENT, MS	2.000 EACH
41	601-94690	GUARDRAIL END TREATMENT, MS	2.000 EACH
42	601-94690	GUARDRAIL END TREATMENT, MS	2.000 EACH
43	601-95972	GUARDRAIL POST (CRT), 8 IN.X 6 IN.TREATED LUMBER,	10.000 EACH
44	601-97054	GUARDRAIL BRACKET, STEEL, OFFSET	10.000 EACH
45	601-97950	GUARDRAIL POST BRACKET, TREATED TIMBER, 6 IN. X 6 IN.	60.000 EACH
46	601-99108	GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	200.000 LFT
47	601-99123	GUARDRAIL TRANSITION, GP	1.000 EACH
48	702-93722	CONCRETE, C	7.000 CYS

CALL ORDER : 410
 LETTING DATE :

CONTRACT ID : M -29784-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE OR REPAIR		
49 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
50 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
51 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
52 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
53 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
54 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 450
 LETTING DATE :

CONTRACT ID : T -29431-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL, NEW OR MODERNIZED		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	5.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
10	202-01874 SHEET SIGN AND POST, REMOVE	2.000	EACH
11	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
12	801-06710 FLASHING ARROW SIGN	40.000	DAY
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
14	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	50.000	SFT
15	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	2.000	EACH
16	805-01842 HANDHOLE, SIGNAL	7.000	EACH
17	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	1,295.000	LFT
18	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
19	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
20	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
21	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
22	805-78420 DISCONNECT HANGER	4.000	EACH
23	805-78467 SIGNAL CABLE, 3C 8GA.	36.000	LFT
24	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,070.000	LFT
25	805-78485 SIGNAL CABLE, 5C 14GA.	480.000	LFT
26	805-78490 SIGNAL CABLE, 7C 14GA.	790.000	LFT
27	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,710.000	LFT
28	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
29	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	400.000	LFT
30	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
31	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	2.000	EACH
32	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	4.000	EACH
33	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	250.000	LFT
34	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	500.000	LFT
35	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	95.000	LFT

