

CALL ORDER : 170  
 LETTING DATE :

CONTRACT ID : R -28127-C

| ITEM NO.         | DESCRIPTION   | QUANTITY  | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | ENHANCEMENT, RAILROAD DEPOT REHABILITATION                      |           |       |
| 1                | 105-06845 CONSTRUCTION ENGINEERING                              | LUMP      | LUMP  |
| 2                | 105-07039 FIELD OFFICE, B                                       | 12.000    | MOS   |
| 3                | 110-01001 MOBILIZATION AND DEMOBILIZATION                       | LUMP      | LUMP  |
| 4                | 201-01015 CLEARING AND GRUBBING                                 | LUMP      | LUMP  |
| 5                | 203-02000 EXCAVATION, COMMON                                    | 910.000   | CYS   |
| 6                | 205-07802 EROSION CONTROL                                       | 4.000     | MOS   |
| 7                | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE                     | 666.000   | TON   |
| 8                | 303-90933 STONE, RIVERSIDE, 1 IN. TO 3 IN.                      | 240.000   | SYS   |
| 9                | 402-07433 HMA SURFACE, TYPE B                                   | 135.000   | TON   |
| 10               | 402-07438 HMA INTERMEDIATE, TYPE B                              | 372.000   | TON   |
| 11               | 604-90256 SIDEWALK, CONCRETE, 6 IN.                             | 23.000    | SYS   |
| 12               | 604-91531 SIDEWALK, CONCRETE, 4 IN.                             | 160.000   | SYS   |
| 13               | 605-06120 CURE, CONCRETE  | 300.000   | LFT   |
| 14               | 615-06496 PARKING BARRIER                                       | 12.000    | EACH  |
| 15               | 621-06560 MULCHED SEEDING, U                                    | 4,840.000 | SYS   |
| 16               | 621-06570 TOP SOIL  | 1,250.000 | CYS   |
| 17               | 621-98038 MULCH, HARDWOOD SHREDDED BARK                         | 12.000    | CYS   |
| 18               | 622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN. | 9.000     | EACH  |
| 19               | 707-99085 FLAG POLE   | 1.000     | EACH  |
| 20               | 711-03973 BUILDING ARCHITECTURAL                                | LUMP      | LUMP  |
| 21               | 711-98751 BUILDING, MECHANICAL                                  | LUMP      | LUMP  |
| 22               | 715-01902 WATER SERVICE LINE, 2 IN.                             | 150.000   | LFT   |
| 23               | 715-05408 PIPE, SANITARY SEWER, 8 IN.                           | 255.000   | LFT   |
| 24               | 715-41045 PIPE, REINFORCED CONCRETE, 12 IN.                     | 50.000    | LFT   |
| 25               | 720-45030 INLET, E7   | 1.000     | EACH  |
| 26               | 720-45410 MANHOLE, C4   | 1.000     | EACH  |
| 27               | 729-51875 CONCRETE, A, PATCHING                                 | 605.000   | SFT   |
| 28               | 732-01913 CLEANOUT, PVC, 4 IN.                                  | 1.000     | EACH  |
| 29               | 732-05075 CONNECT   | 1.000     | EACH  |
| 30               | 732-91742 FIRE HYDRANT  | 1.000     | EACH  |
| 31               | 801-03290 CONSTRUCTION SIGN, C                                  | 4.000     | EACH  |
| 32               | 802-03896 BOLLARD   | 5.000     | EACH  |
| 33               | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE          | 14.000    | LFT   |
| 34               | 802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN. | 3.000     | SFT   |
| 35               | 807-03694 BUILDING ELECTRICAL                                   | LUMP      | LUMP  |
| 36               | 808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.                      | 518.000   | LFT   |

