

CALL ORDER : 181
 LETTING DATE :

CONTRACT ID : R -28031-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|---------------|-------|
| SECTION NO. 0001 | ASPHALT RESURFACE | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-07039 FIELD OFFICE, B | 9.000 | MOS |
| 3 | 105-08520 CELLULAR TELEPHONE/RADIO | 9.000 | EACH |
| 4 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 54.000 | MOS |
| 5 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 6 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 10 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 11 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 17,194.000 | TON |
| 12 | 304-07783 HMA PATCHING, TYPE D | 2,500.000 | TON |
| 13 | 306-08033 MILLING, ASPHALT, 1 IN. | 1,179,811.000 | SYS |
| 14 | 306-08034 MILLING, ASPHALT, 1 1/2 IN. | 89,324.000 | SYS |
| 15 | 306-08043 MILLING, TRANSITION | 7,490.000 | SYS |
| 16 | 401-06264 PROFILOGRAPH, HMA | LUMP | LUMP |
| 17 | 401-09046 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm-PWL | 43,827.000 | TON |
| 18 | 401-09049 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm-PWL | 61,506.000 | TON |
| 19 | 406-05520 ASPHALT FOR TACK COAT | 297.500 | TON |
| 20 | 606-07484 MILLED HMA SHOULDER CORRUGATIONS | 571,297.000 | LFT |
| 21 | 612-04315 ASPHALT MATERIAL FOR UNDERSEAL | 12.200 | TON |
| 22 | 612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL | 2.000 | EACH |
| 23 | 612-60410 DRILLED HOLE FOR UNDERSEAL | 204.000 | EACH |
| 24 | 801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY | 12.000 | EACH |
| 25 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 28,422.000 | LFT |
| 26 | 801-06640 CONSTRUCTION SIGN, A | 36.000 | EACH |
| 27 | 801-06710 FLASHING ARROW SIGN | 720.000 | DAY |
| 28 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 29 | 801-07215 TEMPORARY CHANGEABLE MESSAGE SIGN | 720.000 | DAY |
| 30 | 805-05406 DATA COLLECTION SITE | 1.000 | EACH |
| 31 | 805-05905 ATR STATION- 4 LANE | 1.000 | EACH |
| 32 | 808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN. | 71,413.000 | LFT |
| 33 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 348,742.500 | LFT |
| 34 | 808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN. | 17,500.000 | LFT |
| 35 | 808-75215 LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN. | 3,040.000 | LFT |
| 36 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 348,742.500 | LFT |
| 37 | 808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 4,262.000 | EACH |
| 38 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 4,262.000 | EACH |

CALL ORDER : 201
 LETTING DATE :

CONTRACT ID : R -28120-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | SAFETY REVISIONS | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-07039 FIELD OFFICE, B | 6.000 | MOS |
| 3 | 105-08520 CELLULAR TELEPHONE/RADIO | 2.000 | EACH |
| 4 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 12.000 | MOS |
| 5 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 6 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 10 | 202-02240 PAVEMENT REMOVAL | 4,185.000 | SYS |
| 11 | 202-02241 GUARDRAIL, REMOVE | 907.000 | LFT |
| 12 | 202-04089 SIGN, SHEET, REMOVE | 4.000 | EACH |
| 13 | 202-93741 GUARD RAIL END TREATMENT, REMOVE | 1.000 | EACH |
| 14 | 202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE | 386.000 | LFT |
| 15 | 202-95027 IMPACT ATTENUATOR, REMOVE | 1.000 | EACH |
| 16 | 202-96022 CONCRETE FOUNDATION, REMOVE | 4.000 | EACH |
| 17 | 202-99626 FOUNDATION FOR SIGNING, REMOVE | 1.000 | EACH |
| 18 | 203-02000 EXCAVATION, COMMON | 7,052.000 | CYS |
| 19 | 203-02070 BORROW | 1,874.000 | CYS |
| 20 | 205-03371 SEDIMENT, REMOVE | 50.000 | CYS |
| 21 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 87.000 | TON |
| 22 | 205-06937 TEMPORARY SILT FENCE | 2,858.000 | LFT |
| 23 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 9,924.000 | SYS |
| 24 | 211-07454 STRUCTURE BACKFILL | 8.330 | CYS |
| 25 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 1,644.000 | TON |
| 26 | 306-08034 MILLING, ASPHALT, 1 1/2 IN. | 329.000 | SYS |
| 27 | 401-07332 QC/QA-HMA, 1, 76, SURFACE, 9.5 mm | 160.000 | TON |
| 28 | 401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm | 608.000 | TON |
| 29 | 401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm | 993.000 | TON |
| 30 | 401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm | 452.000 | TON |
| 31 | 401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm | 3,057.000 | TON |
| 32 | 401-08338 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm | 1,308.000 | TON |
| 33 | 402-07453 HMA FOR TEMPORARY PAVEMENT | 122.000 | TON |
| 34 | 406-05520 ASPHALT FOR TACK COAT | 7.840 | TON |
| 35 | 406-07772 EXTRUDED POLYMERIC ASPHALT JOINT COMPOUND | 8,598.000 | LFT |
| 36 | 601-01115 GUARDRAIL, W BEAM, 1 FT. 6.75 IN. SPACING | 12.500 | LFT |
| 37 | 601-01522 GUARDRAIL TRANSITION TYPE TGB | 1.000 | EACH |
| 38 | 601-05999 CURVED TERMINAL END | 1.000 | EACH |
| 39 | 601-07050 GUARDRAIL END TREATMENT, OS, RESET | 1.000 | EACH |
| 40 | 601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING | 843.800 | LFT |
| 41 | 601-99106 GUARDRAIL, W BEAM, 3 FT. 1.5 IN. SPACING | 25.000 | LFT |
| 42 | 615-06505 MONUMENT, B | 5.000 | EACH |
| 43 | 615-06510 MONUMENT, C | 2.000 | EACH |
| 44 | 615-06515 MONUMENT, D | 1.000 | EACH |
| 45 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 2.000 | EACH |
| 46 | 621-02770 EROSION CONTROL BLANKET | 16,990.000 | SYS |
| 47 | 621-06545 FERTILIZER | 1.400 | TON |
| 48 | 621-06553 SEED MIXTURE, R | 596.760 | LBS |

CALL ORDER : 201
 LETTING DATE :

CONTRACT ID : R -28120-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | SAFETY REVISIONS | | |
| 49 | 621-06565 MULCHING MATERIAL | 7.000 | TON |
| 50 | 621-06574 SODDING | 1,088.000 | SYS |
| 51 | 715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN. | 4,547.000 | LFT |
| 52 | 715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN. | 283.000 | LFT |
| 53 | 718-06528 OUTLET PROTECTOR, 1 | 11.000 | EACH |
| 54 | 718-06532 VIDEO INSPECTION FOR UNDERDRAINS | 4,547.000 | LFT |
| 55 | 718-52610 AGGREGATE FOR UNDERDRAINS | 410.000 | CYS |
| 56 | 801-06203 TEMPORARY PAVEMENT MARKING, 4 IN. | 1,350.000 | LFT |
| 57 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 11,664.000 | LFT |
| 58 | 801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE | 2.000 | EACH |
| 59 | 801-06640 CONSTRUCTION SIGN, A | 12.000 | EACH |
| 60 | 801-06710 FLASHING ARROW SIGN | 60.000 | DAY |
| 61 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 62 | 801-07118 BARRICADE, III-A | 12.000 | LFT |
| 63 | 802-03821 SIGN, SHEET WITH LEGEND | 2.000 | EACH |
| 64 | 802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE | 48.150 | LFT |
| 65 | 802-05705 SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE | 98.920 | LFT |
| 66 | 802-07060 SIGN, SHEET, RELOCATE | 7.000 | EACH |
| 67 | 802-07159 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, II | 1.000 | EACH |
| 68 | 802-91122 SIGN, GROUND MOUNTED, RESET | 1.000 | EACH |
| 69 | 804-06771 DELINEATOR POST, FLEXIBLE | 48.000 | EACH |
| 70 | 807-02193 LIGHT STANDARD FOUNDATION, 3 FT. DIA. X 8 FT. | 4.000 | EACH |
| 71 | 807-02603 LIGHT STANDARD, RELOCATE | 4.000 | EACH |
| 72 | 808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN. | 68.000 | LFT |
| 73 | 808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN. | 285.000 | LFT |
| 74 | 808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN. | 410.000 | LFT |
| 75 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 4,957.000 | LFT |
| 76 | 808-06716 LINE, REMOVE | 4,000.000 | LFT |
| 77 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 920.000 | LFT |
| 78 | 808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW, | 89.000 | LFT |
| 79 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 24.000 | LFT |
| 80 | 808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 4.000 | EACH |
| 81 | 808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 2.000 | EACH |
| 82 | 808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 40.000 | EACH |
| 83 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 33.000 | EACH |
| 84 | 808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN. | 1,476.000 | LFT |

CALL ORDER : 233
 LETTING DATE :

CONTRACT ID : R -28651-B

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | MEDIAN CONSTRUCTION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-07039 FIELD OFFICE, B | 14.000 | MOS |
| 3 | 105-08520 CELLULAR TELEPHONE/RADIO | 4.000 | EACH |
| 4 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 56.000 | MOS |
| 5 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 6 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 10 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 11 | 202-01405 CONTAMINATED SOIL, REMOVE AND DISPOSE | 4,924.000 | m3 |
| 12 | 202-02240 PAVEMENT REMOVAL | 273.000 | m2 |
| 13 | 202-02271 HEADWALL, REMOVE | 8.000 | EACH |
| 14 | 202-02273 CENTER CURB, CONCRETE, REMOVE | 99.000 | m2 |
| 15 | 202-02278 CURB, CONCRETE, REMOVE | 182.000 | m |
| 16 | 202-02279 CURB AND GUTTER, REMOVE | 387.000 | m |
| 17 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 963.000 | m2 |
| 18 | 202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE | 76.000 | EACH |
| 19 | 202-91385 INLET, REMOVE | 28.000 | EACH |
| 20 | 202-91840 FENCE, CHAIN LINK, REMOVE | 28.000 | m |
| 21 | 202-93047 MANHOLE, REMOVE | 7.000 | EACH |
| 22 | 202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE | 58.000 | EACH |
| 23 | 202-96133 PIPE, REMOVE | 673.000 | m |
| 24 | 202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS | LUMP | LUMP |
| 25 | 203-02000 EXCAVATION, COMMON | 9,447.000 | m3 |
| 26 | 205-03371 SEDIMENT REMOVE | 255.000 | m3 |
| 27 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 87.000 | Mg |
| 28 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 67.000 | EACH |
| 29 | 205-06937 TEMPORARY SILT FENCE | 1,530.000 | m |
| 30 | 207-08268 SUBGRADE TREATMENT, TYPE IV | 19,221.000 | m2 |
| 31 | 211-07454 STRUCTURE BACKFILL | 9,850.000 | m3 |
| 32 | 213-08058 FLOWABLE BACKFILL | 3,223.000 | m3 |
| 33 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 3,947.000 | Mg |
| 34 | 302-06464 SUBBASE FOR PCCP | 37.000 | m3 |
| 35 | 303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS | 1,594.000 | Mg |
| 36 | 306-08034 MILLING, ASPHALT, 38 mm | 29,264.000 | m2 |
| 37 | 306-08041 MILLING, PCCP | 1,352.000 | m2 |
| 38 | 306-08043 MILLING, TRANSITION | 1,015.000 | m2 |
| 39 | 401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm | 4,727.000 | Mg |
| 40 | 401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm | 10,574.000 | Mg |
| 41 | 401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm | 8,220.000 | Mg |
| 42 | 401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm | 4,315.000 | Mg |
| 43 | 402-07441 HMA BASE, TYPE B | 10.000 | Mg |
| 44 | 402-07453 HMA FOR TEMPORARY PAVEMENT | 28.000 | Mg |
| 45 | 406-05520 ASPHALT FOR TACK COAT | 34.000 | Mg |
| 46 | 603-91304 FENCE, WOOD, RESET | 28.000 | m |
| 47 | 604-06070 SIDEWALK, CONCRETE | 7,102.000 | m2 |
| 48 | 604-07900 CURB RAMP, CONCRETE, F | 120.000 | m2 |

CALL ORDER : 233
 LETTING DATE :

CONTRACT ID : R -28651-B

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | MEDIAN CONSTRUCTION | | |
| 49 | 604-07901 CURB RAMP, CONCRETE, G | 7.000 | m2 |
| 50 | 604-07902 CURB RAMP, CONCRETE, H | 129.000 | m2 |
| 51 | 604-44251 STEPS, CONCRETE | 7.240 | m3 |
| 52 | 605-06120 CURB, CONCRETE | 107.000 | m |
| 53 | 605-06140 CURB AND GUTTER, CONCRETE | 3,908.000 | m |
| 54 | 605-06255 CENTER CURB, D, CONCRETE | 96.000 | m2 |
| 55 | 605-92578 CURB WALK, CONCRETE | 141.000 | m2 |
| 56 | 605-96305 CURB AND GUTTER, CONCRETE, DEPRESSED | 20.000 | m |
| 57 | 610-07486 HMA FOR APPROACHES, TYPE A | 1,286.000 | Mg |
| 58 | 610-07712 PCCP FOR APPROACHES, 150 mm | 8,424.000 | m2 |
| 59 | 611-06497 MAILBOX ASSEMBLY, SINGLE | 36.000 | EACH |
| 60 | 611-06498 MAILBOX ASSEMBLY, DOUBLE | 19.000 | EACH |
| 61 | 611-95023 MAILBOX ASSEMBLY, RESET | 1.000 | EACH |
| 62 | 615-06490 RIGHT OF WAY MARKER | 81.000 | EACH |
| 63 | 615-06496 PARKING BARRIER | 5.000 | EACH |
| 64 | 615-06500 MONUMENT, A | 23.000 | EACH |
| 65 | 615-06505 MONUMENT, B | 3.000 | EACH |
| 66 | 615-06520 MONUMENT, RE-ESTABLISH | 1.000 | EACH |
| 67 | 615-06527 MONUMENT, SECTION CORNER | 2.000 | EACH |
| 68 | 615-97768 PARKING BARRIER, RESET | 5.000 | EACH |
| 69 | 616-02320 GEOTEXTILES | 108.000 | m2 |
| 70 | 616-06451 RIPRAP, UNIFORM | 100.000 | Mg |
| 71 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 8.000 | EACH |
| 72 | 621-06545 FERTILIZER | 1.210 | Mg |
| 73 | 621-06557 SEED MIXTURE, T | 413.000 | kg |
| 74 | 621-06560 MULCHED SEEDING, U | 2,941.000 | m2 |
| 75 | 621-06567 WATER | 167.000 | kL |
| 76 | 621-06575 SODDING, NURSERY | 14,974.000 | m2 |
| 77 | 622-05623 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, 900 mm OR | 14.000 | EACH |
| 78 | 715-04855 PIPE END SECTION, 1050 mm | 1.000 | EACH |
| 79 | 715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm | 430.800 | m |
| 80 | 715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm | 5,751.000 | m |
| 81 | 715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm | 1,815.100 | m |
| 82 | 715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm | 634.000 | m |
| 83 | 715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm | 278.800 | m |
| 84 | 715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm | 744.800 | m |
| 85 | 715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm | 583.600 | m |
| 86 | 715-05157 PIPE, TYPE 2, CIRCULAR, 825 mm | 165.000 | m |
| 87 | 715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm | 347.700 | m |
| 88 | 715-08283 PCCP FOR STRUCTURE INSTALLATION | 1,084.000 | m2 |
| 89 | 715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C | 597.000 | Mg |
| 90 | 715-44240 CONCRETE, A, STRUCTURES | 13.600 | m3 |
| 91 | 715-46040 PIPE END SECTION, 900 mm | 1.000 | EACH |
| 92 | 718-06532 VIDEO INSPECTION FOR UNDERDRAINS | 2,000.000 | m |
| 93 | 718-52610 AGGREGATE FOR UNDERDRAINS | 1,306.000 | m3 |
| 94 | 720-03481 MANHOLE, H4, MODIFIED | 2.000 | EACH |
| 95 | 720-04182 CASTING, 4 | 1.000 | EACH |
| 96 | 720-04666 CATCH BASIN | 2.000 | EACH |

CALL ORDER : 233
 LETTING DATE :

CONTRACT ID : R -28651-B

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | MEDIAN CONSTRUCTION | | |
| 97 | 720-04720 MANHOLE, H | 3.000 | EACH |
| 98 | 720-04720 MANHOLE, H | 4.000 | EACH |
| 99 | 720-07301 INLET TYPE HA | 4.000 | EACH |
| 100 | 720-44000 CASTING, ADJUST TO GRADE | 13.000 | EACH |
| 101 | 720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE | 1.000 | EACH |
| 102 | 720-44080 CASTING, 15, FURNISH AND ADJUST TO GRADE | 2.000 | EACH |
| 103 | 720-45030 INLET, E7 | 2.000 | EACH |
| 104 | 720-45035 INLET, F7 | 1.000 | EACH |
| 105 | 720-45235 CATCH BASIN, E7 | 32.000 | EACH |
| 106 | 720-45335 CATCH BASIN, E7, MODIFIED | 2.000 | EACH |
| 107 | 720-45405 MANHOLE, B4 | 3.000 | EACH |
| 108 | 720-45410 MANHOLE, C4 | 28.000 | EACH |
| 109 | 720-45415 MANHOLE, D4 | 1.000 | EACH |
| 110 | 720-45510 MANHOLE, C4, MODIFIED | 5.000 | EACH |
| 111 | 720-45515 MANHOLE, D4, MODIFIED | 1.000 | EACH |
| 112 | 720-45605 STRUCTURE, MANHOLE, RECONSTRUCT | 1.000 | m |
| 113 | 720-91973 MANHOLE, H4 | 10.000 | EACH |
| 114 | 720-92025 MANHOLE, D2 | 8.000 | EACH |
| 115 | 720-92492 MANHOLE, B | 1.000 | EACH |
| 116 | 720-92605 MANHOLE, K2, MODIFIED | 1.000 | EACH |
| 117 | 720-93409 INLET, B15, MODIFIED | 5.000 | EACH |
| 118 | 720-93411 INLET, C15, MODIFIED | 14.000 | EACH |
| 119 | 720-94157 MANHOLE, C | 9.000 | EACH |
| 120 | 720-94612 MANHOLE, K4 | 5.000 | EACH |
| 121 | 720-94713 CATCH BASIN, C15, MODIFIED | 9.000 | EACH |
| 122 | 720-95164 CATCH BASIN, B15, MODIFIED | 2.000 | EACH |
| 123 | 720-98174 INLET, B15 | 33.000 | EACH |
| 124 | 720-98555 INLET, C15 | 12.000 | EACH |
| 125 | 720-99416 CATCH BASIN, B15 | 1.000 | EACH |
| 126 | 720-99417 CATCH BASIN, C15 | 47.000 | EACH |
| 127 | 801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW | 108.000 | EACH |
| 128 | 801-01506 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (RXR) | 8.000 | EACH |
| 129 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 2.000 | EACH |
| 130 | 801-06203 TEMPORARY PAVEMENT MARKING, 100 mm | 22,123.000 | m |
| 131 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm | 25,450.000 | m |
| 132 | 801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm | 318.000 | m |
| 133 | 801-06640 CONSTRUCTION SIGN, A | 140.000 | EACH |
| 134 | 801-06645 CONSTRUCTION SIGN, B | 8.000 | EACH |
| 135 | 801-06710 FLASHING ARROW SIGN | 1,020.000 | DAY |
| 136 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 137 | 801-07119 BARRICADE, III-B | 643.000 | m |
| 138 | 801-94295 SIGNAL HEAD, RELOCATE | 20.000 | EACH |
| 139 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 231.600 | m |
| 140 | 802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm | 43.690 | m2 |
| 141 | 802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS | 9.460 | m2 |
| 142 | 805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m | 8.000 | EACH |
| 143 | 805-01842 HANDHOLE, SIGNAL | 24.000 | EACH |
| 144 | 805-01879 SIGNAL SERVICE | 2.000 | EACH |

CALL ORDER : 233
 LETTING DATE :

CONTRACT ID : R -28651-B

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|---|-------------|---|--------------|
| SECTION NO. 0001 MEDIAN CONSTRUCTION | | | |
| 145 | 805-02087 | TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT | LUMP |
| 146 | 805-02152 | PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 450mm | 16.000 EACH |
| 147 | 805-02373 | INTERCONNECT CABLE, FIBER OPTIC | 1,008.000 m |
| 148 | 805-02438 | COMMUNICATION TELEMETRY INTERCONNECT INTERFACE PANEL | 2.000 EACH |
| 149 | 805-06592 | CONDUIT, STEEL, GALVANIZED, 50mm | 1,963.000 m |
| 150 | 805-78100 | CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE | 2.000 EACH |
| 151 | 805-78205 | TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN | 13.000 EACH |
| 152 | 805-78215 | TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER ARROW, GREEN | 6.000 EACH |
| 153 | 805-78230 | TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN, | 3.000 EACH |
| 154 | 805-78370 | PEDESTRIAN PUSH BUTTON | 16.000 EACH |
| 155 | 805-78415 | SPAN, CATENARY, AND TETHER | 8.000 EACH |
| 156 | 805-78420 | DISCONNECT HANGER | 8.000 EACH |
| 157 | 805-78467 | SIGNAL CABLE, 3C 8GA. | 30.000 m |
| 158 | 805-78470 | SIGNAL CABLE, ROADWAY LOOP, 1C 14GA. | 3,124.000 m |
| 159 | 805-78485 | SIGNAL CABLE, 5C 14GA. | 549.000 m |
| 160 | 805-78490 | SIGNAL CABLE, 7C 14GA. | 979.000 m |
| 161 | 805-78510 | SIGNAL CABLE, 2C 16GA., SHIELDED | 1,097.000 m |
| 162 | 805-78785 | SIGNAL DETECTOR HOUSING | 20.000 EACH |
| 163 | 805-78795 | SAW CUT FOR ROADWAY LOOP AND SEALER | 1,026.000 m |
| 164 | 805-78925 | CONTROLLER CABINET FOUNDATION, P1 | 2.000 EACH |
| 165 | 805-81032 | SIGNAL STRAIN POLE, STEEL, 9.2m | 8.000 EACH |
| 166 | 805-86889 | POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER | 1,350.000 m |
| 167 | 805-86930 | INSULATING LINK, NOT WATERPROOFED | 80.000 EACH |
| 168 | 805-92504 | LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL | 20.000 EACH |
| 169 | 805-96014 | SAW CUT, FULL DEPTH | 204.000 m |
| 170 | 805-98335 | WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C | 2,500.000 m |
| 171 | 805-98336 | WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C | 600.000 m |
| 172 | 807-02370 | LIGHT STRUCTURE, REMOVE AND RESET | 40.000 EACH |
| 173 | 807-02428 | LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, | 40.000 EACH |
| 174 | 807-86605 | LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 150 WATT | 5.000 EACH |
| 175 | 807-86620 | LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT | 35.000 EACH |
| 176 | 807-86910 | CONNECTOR KIT, UNFUSED | 40.000 EACH |
| 177 | 807-86915 | CONNECTOR KIT, FUSED | 40.000 EACH |
| 178 | 807-86920 | MULTIPLE COMPRESSION FITTING, NOT WATERPROOFED | 140.000 EACH |
| 179 | 807-86950 | SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION | 40.000 EACH |
| 180 | 808-06701 | LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm | 1,041.000 m |
| 181 | 808-06703 | LINE, THERMOPLASTIC, SOLID, WHITE, 100mm | 1,395.000 m |
| 182 | 808-06716 | LINE, REMOVE | 6,805.000 m |
| 183 | 808-75240 | LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm | 720.000 m |
| 184 | 808-75245 | LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm | 5,499.000 m |
| 185 | 808-75278 | TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW, | 174.000 m |
| 186 | 808-75297 | TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm | 152.000 m |
| 187 | 808-75300 | TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm | 660.000 m |
| 188 | 808-75320 | PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 66.000 EACH |
| 189 | 808-75325 | PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 42.000 EACH |
| 190 | 808-75340 | PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR | 4.000 EACH |
| 191 | 808-92027 | LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm | 629.000 m |

CALL ORDER : 291
 LETTING DATE :

CONTRACT ID : R -29160-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | SMALL STRUCTURE REPLACEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-07039 FIELD OFFICE, B | 8.000 | MOS |
| 3 | 109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE | 1.000 | DOL |
| 4 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 5 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 6 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 7 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 8 | 203-02000 EXCAVATION, COMMON | 16,383.000 | CYS |
| 9 | 205-02224 TEMPORARY EROSION AND SEDIMENT CONTROL, PERIMETER PROTECTION | 725.000 | LFT |
| 10 | 205-04931 SEDIMENT TRAP | 4.000 | EACH |
| 11 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 158.800 | TON |
| 12 | 206-51220 EXCAVATION, WET | 2,033.000 | CYS |
| 13 | 207-08265 SUBGRADE TREATMENT, TYPE IIA | 1,376.800 | SYS |
| 14 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 4,189.000 | SYS |
| 15 | 211-07454 STRUCTURE BACKFILL | 360.400 | CYS |
| 16 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 1,337.800 | TON |
| 17 | 303-03096 RIVER ROCK | 7.700 | TON |
| 18 | 303-07449 COMPACTED AGGREGATE, NO. 73 | 1,987.300 | TON |
| 19 | 402-07433 HMA SURFACE, TYPE B | 279.000 | TON |
| 20 | 402-07438 HMA INTERMEDIATE, TYPE B | 611.500 | TON |
| 21 | 406-05520 ASPHALT FOR TACK COAT | 3.000 | TON |
| 22 | 603-06045 FENCE, CHAIN LINK, 48 IN. | 160.000 | LFT |
| 23 | 610-07487 HMA FOR APPROACHES, TYPE B | 638.000 | TON |
| 24 | 615-06490 RIGHT OF WAY MARKER | 25.000 | EACH |
| 25 | 615-06505 MONUMENT, B | 4.000 | EACH |
| 26 | 616-02320 GEOTEXTILES | 1,633.000 | SYS |
| 27 | 616-06451 RIPRAP, UNIFORM | 908.000 | TON |
| 28 | 616-07266 COIR ROLL | 336.000 | LFT |
| 29 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 3.000 | EACH |
| 30 | 621-03307 STRIPPING TOPSOIL | 685.000 | CYS |
| 31 | 621-03909 SEED MIXTURE, NATIVE | 38.000 | LBS |
| 32 | 621-06545 FERTILIZER | 1.140 | TON |
| 33 | 621-06553 SEED MIXTURE, R | 306.000 | LBS |
| 34 | 621-06565 MULCHING MATERIAL | 5.600 | TON |
| 35 | 621-06567 WATER | 4.200 | KGAL |
| 36 | 621-06570 TOP SOIL | 100.000 | CYS |
| 37 | 621-06574 SODDING | 334.000 | SYS |
| 38 | 621-06575 SODDING, NURSERY | 339.000 | SYS |
| 39 | 621-07109 WATER PUMPING | LUMP | LUMP |
| 40 | 622-05605 PLANT, ANNUAL | 100.000 | EACH |
| 41 | 622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN. | 27.000 | EACH |
| 42 | 622-05647 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 120 IN. | 23.000 | EACH |
| 43 | 622-52436 SIGN, DO NOT MOW OR SPRAY | 4.000 | EACH |
| 44 | 622-91786 SEEDLING | 96.000 | EACH |
| 45 | 704-09031 ARTICULATING CONCRETE MATTRESS | 591.000 | SYS |
| 46 | 714-06660 WINGWALL | 823.000 | SYS |
| 47 | 714-26714 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 8 FT. X 8 FT. | 110.000 | LFT |
| 48 | 715-03476 SAFETY METAL END SECTION, 4:1, 24 IN. | 4.000 | EACH |

CALL ORDER : 291
 LETTING DATE :

CONTRACT ID : R -29160-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | SMALL STRUCTURE REPLACEMENT | | |
| 49 | 715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN. | 188.000 | LFT |
| 50 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 8.000 | EACH |
| 51 | 801-06625 DETOUR ROUTE MARKER ASSEMBLY | 23.000 | EACH |
| 52 | 801-06640 CONSTRUCTION SIGN, A | 20.000 | EACH |
| 53 | 801-06645 CONSTRUCTION SIGN, B | 2.000 | EACH |
| 54 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 55 | 801-07118 BARRICADE, III-A | 120.000 | LFT |
| 56 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 22.000 | LFT |
| 57 | 802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN. | 18.000 | SFT |
| 58 | 808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN. | 113.000 | LFT |
| 59 | 808-06713 LINE, PAINT, SOLID, WHITE, 4 IN. | 3,164.000 | LFT |
| 60 | 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN. | 2,398.000 | LFT |
| 61 | 808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN. | 90.000 | LFT |
| 62 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 11.000 | EACH |

CALL ORDER : 341
 LETTING DATE :

CONTRACT ID : RS-28631-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-------------|-------|
| SECTION NO. 0001 | ASPHALT RESURFACE | | |
| 1 | 105-07039 FIELD OFFICE, B | 12.000 | MOS |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 3.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 36.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 5 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 6 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 7 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 8 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 9 | 202-02278 CURB, CONCRETE, REMOVE | 1,154.000 | LFT |
| 10 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 975.000 | SYS |
| 11 | 202-74035 SIGN, REMOVE | 1.000 | EACH |
| 12 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 500.000 | TON |
| 13 | 304-07491 HMA PATCHING, TYPE C | 7,250.000 | TON |
| 14 | 306-08034 MILLING, ASPHALT, 1 1/2 IN. | 264,668.000 | SYS |
| 15 | 306-08038 MILLING, ASPHALT, 4 IN. | 6,906.000 | SYS |
| 16 | 306-08043 MILLING, TRANSITION | 2,540.000 | SYS |
| 17 | 306-08432 MILLING, APPROACH | 13,244.000 | SYS |
| 18 | 401-06264 PROFILOGRAPH, HMA | LUMP | LUMP |
| 19 | 401-09050 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm-PWL | 21,836.000 | TON |
| 20 | 402-07439 HMA INTERMEDIATE, TYPE C | 1,520.000 | TON |
| 21 | 402-07452 HMA, TYPE C, WEDGE AND LEVEL | 250.000 | TON |
| 22 | 406-05520 ASPHALT FOR TACK COAT | 78.000 | TON |
| 23 | 604-06070 SIDEWALK, CONCRETE | 440.000 | SYS |
| 24 | 604-07896 CURB RAMP, CONCRETE, B | 257.000 | SYS |
| 25 | 604-07899 CURB RAMP, CONCRETE, E | 70.000 | SYS |
| 26 | 604-07900 CURB RAMP, CONCRETE, F | 108.000 | SYS |
| 27 | 604-07903 CURB RAMP, CONCRETE, K | 19.000 | SYS |
| 28 | 605-06090 CURB, INTEGRAL, CONCRETE | 725.000 | LFT |
| 29 | 605-06120 CURB, CONCRETE | 428.000 | LFT |
| 30 | 610-07488 HMA FOR APPROACHES, TYPE C | 1,093.000 | TON |
| 31 | 621-06574 SODDING | 10.000 | SYS |
| 32 | 720-44000 CASTING, ADJUST TO GRADE | 10.000 | EACH |
| 33 | 801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY | 2.000 | EACH |
| 34 | 801-06203 TEMPORARY PAVEMENT MARKING, 4 IN. | 14,475.000 | LFT |
| 35 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 14,475.000 | LFT |
| 36 | 801-06640 CONSTRUCTION SIGN, A | 49.000 | EACH |
| 37 | 801-06710 FLASHING ARROW SIGN | 160.000 | DAY |
| 38 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 39 | 801-07215 TEMPORARY CHANGEABLE MESSAGE SIGN | 100.000 | DAY |
| 40 | 802-76055 SIGN POST, A | 10.000 | LFT |
| 41 | 802-94715 SIGNS, SHEET, REMOVE AND RESET | LUMP | LUMP |
| 42 | 805-02503 CABLE, ROADWAY LOOP, 1C 14GA. | 60,552.000 | LFT |
| 43 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 6,055.000 | LFT |
| 44 | 805-78785 SIGNAL DETECTOR HOUSING | 40.000 | EACH |
| 45 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER | 19,040.000 | LFT |
| 46 | 805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE | 10.000 | EACH |
| 47 | 808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN. | 18,931.000 | LFT |
| 48 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 76,995.000 | LFT |

CALL ORDER : 341
 LETTING DATE :

CONTRACT ID : RS-28631-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | ASPHALT RESURFACE | | |
| 49 | 808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN. | 2,508.000 | LFT |
| 50 | 808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN. | 2,588.000 | LFT |
| 51 | 808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN. | 7,397.000 | LFT |
| 52 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 57,612.000 | LFT |
| 53 | 808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH | 365.000 | LFT |
| 54 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 1,695.000 | LFT |
| 55 | 808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN. | 2,588.000 | LFT |
| 56 | 808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 179.000 | EACH |
| 57 | 808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 156.000 | EACH |
| 58 | 808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR | 4.000 | EACH |
| 59 | 808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 1,350.000 | EACH |
| 60 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 1,408.000 | EACH |
| 61 | 808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN. | 8,443.000 | LFT |
| 62 | 808-96016 LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN. | 3,246.000 | LFT |

CALL ORDER : 365
 LETTING DATE :

CONTRACT ID : RS-28835-C

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-------------|-------|
| SECTION NO. 0001 | ASPHALT RESURFACE | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-07038 FIELD OFFICE, A | 6.000 | MOS |
| 3 | 105-08520 CELLULAR TELEPHONE/RADIO | 2.000 | EACH |
| 4 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 12.000 | MOS |
| 5 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 6 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 10 | 202-02241 GUARDRAIL, REMOVE | 25.000 | LFT |
| 11 | 202-93741 GUARD RAIL END TREATMENT, REMOVE | 24.000 | EACH |
| 12 | 203-02070 BORROW | 120.000 | CYS |
| 13 | 203-02080 LINEAR GRADING | 10.000 | MILE |
| 14 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 1,200.000 | TON |
| 15 | 303-07449 COMPACTED AGGREGATE, NO. 73 | 100.000 | TON |
| 16 | 304-07490 HMA PATCHING, TYPE B | 1,201.000 | TON |
| 17 | 305-60400 COMPACTED AGGREGATE FOR PATCHING | 20.000 | TON |
| 18 | 306-08033 MILLING, ASPHALT, 1 IN. | 163,436.000 | SYS |
| 19 | 306-08043 MILLING, TRANSITION | 1,920.000 | SYS |
| 20 | 306-08432 MILLING, APPROACH | 9,024.000 | SYS |
| 21 | 401-06264 PROFILOGRAPH, HMA | LUMP | LUMP |
| 22 | 401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm | 13,606.000 | TON |
| 23 | 401-07371 QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm | 22,678.000 | TON |
| 24 | 406-05520 ASPHALT FOR TACK COAT | 85.000 | TON |
| 25 | 601-06035 GUARDRAIL, RESET | 250.000 | LFT |
| 26 | 601-94689 GUARDRAIL END TREATMENT, OS | 24.000 | EACH |
| 27 | 601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING | 25.000 | LFT |
| 28 | 601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING | 24.000 | EACH |
| 29 | 610-07487 HMA FOR APPROACHES, TYPE B | 2,691.000 | TON |
| 30 | 612-04315 ASPHALT MATERIAL FOR UNDERSEAL | 26.000 | TON |
| 31 | 612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL | 1.000 | EACH |
| 32 | 612-60410 DRILLED HOLE FOR UNDERSEAL | 429.000 | EACH |
| 33 | 615-06505 MONUMENT, B | 6.000 | EACH |
| 34 | 615-06525 CASTING ADJUSTED TO GRADE, MONUMENT | 2.000 | EACH |
| 35 | 801-03290 CONSTRUCTION SIGN, C | 2.000 | EACH |
| 36 | 801-06203 TEMPORARY PAVEMENT MARKING, 4 IN. | 10,380.000 | LFT |
| 37 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 5,190.000 | LFT |
| 38 | 801-06640 CONSTRUCTION SIGN, A | 38.000 | EACH |
| 39 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 40 | 808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN. | 450.000 | LFT |
| 41 | 808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN. | 56.000 | LFT |
| 42 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 102,689.000 | LFT |
| 43 | 808-06716 LINE, REMOVE | 506.000 | LFT |
| 44 | 808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN. | 9,170.000 | LFT |
| 45 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 48,360.000 | LFT |
| 46 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 313.000 | LFT |
| 47 | 808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 1,229.000 | EACH |

CALL ORDER : 371
 LETTING DATE :

CONTRACT ID : RS-29172-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | ASPHALT RESURFACE | | |
| 1 | 105-07039 FIELD OFFICE, B | 6.000 | MOS |
| 2 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 3 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 4 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 5 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 6 | 303-52309 COMPACTED AGGREGATE FOR SHOULDER, 0, 53 | 390.000 | TON |
| 7 | 304-07489 HMA PATCHING, TYPE A | 131.000 | TON |
| 8 | 306-08034 MILLING, ASPHALT, 1 1/2 IN. | 31,264.000 | SYS |
| 9 | 306-08043 MILLING, TRANSITION | 350.000 | SYS |
| 10 | 306-08432 MILLING, APPROACH | 1,907.000 | SYS |
| 11 | 401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm | 2,462.000 | TON |
| 12 | 401-93793 WEDGE AND LEVELING | 100.000 | TON |
| 13 | 402-07432 HMA SURFACE, TYPE A | 118.000 | TON |
| 14 | 406-05520 ASPHALT FOR TACK COAT | 10.000 | TON |
| 15 | 610-07486 HMA FOR APPROACHES, TYPE A | 157.000 | TON |
| 16 | 616-06451 RIPRAP, UNIFORM | 100.000 | TON |
| 17 | 801-06203 TEMPORARY PAVEMENT MARKING, 4 IN. | 1,605.000 | LFT |
| 18 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 1,605.000 | LFT |
| 19 | 801-06640 CONSTRUCTION SIGN, A | 15.000 | EACH |
| 20 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 21 | 804-06771 DELINEATOR POST, FLEXIBLE | 25.000 | EACH |
| 22 | 808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN. | 679.000 | LFT |
| 23 | 808-06713 LINE, PAINT, SOLID, WHITE, 4 IN. | 21,400.000 | LFT |
| 24 | 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN. | 18,045.000 | LFT |
| 25 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 12.000 | LFT |
| 26 | 808-97323 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN. | 216.000 | LFT |

CALL ORDER : 401
 LETTING DATE :

CONTRACT ID : B -28447-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | BRIDGE WIDENING | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-07039 FIELD OFFICE, B | 9.000 | MOS |
| 3 | 109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE | 1.000 | DOL |
| 4 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 5 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 6 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 7 | 202-02240 PAVEMENT REMOVAL | 325.000 | SYS |
| 8 | 202-02241 GUARDRAIL, REMOVE | 790.000 | LFT |
| 9 | 202-51328 PRESENT STRUCTURE, REMOVE PORTIONS | LUMP | LUMP |
| 10 | 202-51822 BRIDGE DECK OVERLAY, REMOVE | 489.000 | SYS |
| 11 | 203-02000 EXCAVATION, COMMON | 294.000 | CYS |
| 12 | 203-02070 BORROW | 914.000 | CYS |
| 13 | 206-51220 EXCAVATION, WET | 160.000 | CYS |
| 14 | 206-51225 EXCAVATION, DRY | 96.000 | CYS |
| 15 | 211-06467 AGGREGATE FOR END BENT BACKFILL | 7.400 | CYS |
| 16 | 211-07454 STRUCTURE BACKFILL | 180.000 | CYS |
| 17 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 4,904.000 | TON |
| 18 | 302-07455 DENSE GRADED SUBBASE | 76.000 | CYS |
| 19 | 306-08043 MILLING, TRANSITION | 664.000 | SYS |
| 20 | 402-07433 HMA SURFACE, TYPE B | 59.000 | TON |
| 21 | 402-07438 HMA INTERMEDIATE, TYPE B | 50.000 | TON |
| 22 | 402-07441 HMA BASE, TYPE B | 219.000 | TON |
| 23 | 406-05521 ASPHALT FOR TACK COAT | 2,374.000 | SYS |
| 24 | 601-01522 GUARDRAIL TRANSITION TYPE TGB | 4.000 | EACH |
| 25 | 601-94689 GUARDRAIL END TREATMENT, OS | 4.000 | EACH |
| 26 | 601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE | 1.000 | EACH |
| 27 | 601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING | 463.000 | LFT |
| 28 | 604-07902 CURB RAMP, CONCRETE, H | 11.000 | SYS |
| 29 | 604-91531 SIDEWALK, CONCRETE, 4 IN. | 134.000 | SYS |
| 30 | 605-06120 CURB, CONCRETE | 256.000 | LFT |
| 31 | 609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN. | 462.000 | SYS |
| 32 | 610-07487 HMA FOR APPROACHES, TYPE B | 302.000 | TON |
| 33 | 616-02320 GEOTEXTILES | 24.000 | SYS |
| 34 | 616-06405 RIPRAP, REVETMENT | 90.000 | TON |
| 35 | 621-06559 MULCHED SEEDING, R | 1,350.000 | SYS |
| 36 | 701-03753 PILE, CONCRETE, STEEL SHELL ENCASED, 0.209 IN., 14 IN. | 590.000 | LFT |
| 37 | 702-51005 CONCRETE, A, SUBSTRUCTURE | 71.100 | CYS |
| 38 | 702-51015 CONCRETE, B, FOOTINGS | 69.800 | CYS |
| 39 | 702-51863 FIELD DRILLED HOLE IN CONCRETE | 150.000 | EACH |
| 40 | 703-08247 EMBEDDED GALVANIC ANODE | 376.000 | EACH |
| 41 | 703-51030 REINFORCING STEEL | 9,522.000 | LBS |
| 42 | 703-51032 REINFORCING STEEL, EPOXY COATED | 58,878.000 | LBS |
| 43 | 703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED | 109.000 | EACH |
| 44 | 704-51002 CONCRETE, C, SUPERSTRUCTURE | 165.600 | CYS |
| 45 | 706-06339 RAILING, PF-1 | 120.000 | LFT |
| 46 | 706-06342 RAILING, PS-1 | 120.000 | LFT |
| 47 | 706-06351 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 | 2.000 | EACH |
| 48 | 706-06353 CONCRETE BRIDGE RAILING TRANSITION, TPS-1 | 2.000 | EACH |

CALL ORDER : 401
 LETTING DATE :

CONTRACT ID : B -28447-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | BRIDGE WIDENING | | |
| 49 | 706-51020 CONCRETE, C, RAILING | 14.300 | CYS |
| 50 | 708-51813 PNEUMATICALLY PLACED MORTAR | 50.000 | SFT |
| 51 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 52 | 715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN. | 28.000 | LFT |
| 53 | 715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN. | 235.000 | LFT |
| 54 | 715-05407 PIPE, END BENT DRAIN, 6 IN. | 50.000 | LFT |
| 55 | 715-05595 PIPE EXTENSION, CIRCULAR, 15 IN. | 5.000 | LFT |
| 56 | 715-46005 PIPE END SECTION, 15 IN. | 1.000 | EACH |
| 57 | 715-46020 PIPE END SECTION, 24 IN. | 1.000 | EACH |
| 58 | 720-45015 INLET, A8 | 2.000 | EACH |
| 59 | 720-45410 MANHOLE, C4 | 1.000 | EACH |
| 60 | 722-51401 BRIDGE DECK PATCHING, FULL DEPTH | 100.000 | SFT |
| 61 | 722-51842 BRIDGE DECK OVERLAY | 629.000 | SYS |
| 62 | 722-51846 BRIDGE DECK OVERLAY, ADDITIONAL | 4.300 | CYS |
| 63 | 722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH | 400.000 | SFT |
| 64 | 722-60824 SURFACE MILLING | 489.000 | SYS |
| 65 | 801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS | LUMP | LUMP |
| 66 | 801-06203 TEMPORARY PAVEMENT MARKING, 4 IN. | 490.000 | LFT |
| 67 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 5,234.000 | LFT |
| 68 | 801-06640 CONSTRUCTION SIGN, A | 33.000 | EACH |
| 69 | 801-06645 CONSTRUCTION SIGN, B | 8.000 | EACH |
| 70 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 71 | 801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2 | 2.000 | EACH |
| 72 | 801-07118 BARRICADE, III-A | 24.000 | LFT |
| 73 | 801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2 | 660.000 | LFT |
| 74 | 801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED | 250.000 | LFT |
| 75 | 808-06713 LINE, PAINT, SOLID, WHITE, 4 IN. | 2,339.000 | LFT |
| 76 | 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN. | 2,090.000 | LFT |
| 77 | 808-06716 LINE, REMOVE | 2,536.000 | LFT |
| 78 | 808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 26.000 | EACH |
| 79 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 26.000 | EACH |

CALL ORDER : 411
 LETTING DATE :

CONTRACT ID : B -28689-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | BRIDGE REPLACEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-07039 FIELD OFFICE, B | 8.000 | MOS |
| 3 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 4 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 5 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 6 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 7 | 202-51330 PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 8 | 203-02000 EXCAVATION, COMMON | 1,339.000 | CYS |
| 9 | 203-02070 BORROW | 4,705.000 | CYS |
| 10 | 203-51223 EXCAVATION, WATERWAY | 90.000 | CYS |
| 11 | 205-06932 TEMPORARY CHECK DAM, STRAW BALES | 90.000 | LFT |
| 12 | 205-06937 TEMPORARY SILT FENCE | 818.000 | LFT |
| 13 | 206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED | 150.000 | CYS |
| 14 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 3,061.000 | SYS |
| 15 | 211-06467 AGGREGATE FOR END BENT BACKFILL | 66.000 | CYS |
| 16 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 1,251.000 | TON |
| 17 | 302-07455 DENSE GRADED SUBBASE | 38.400 | CYS |
| 18 | 306-08034 MILLING, ASPHALT, 1 1/2 IN. | 294.000 | SYS |
| 19 | 402-07432 HMA SURFACE, TYPE A | 256.000 | TON |
| 20 | 402-07435 HMA INTERMEDIATE, TYPE A | 293.000 | TON |
| 21 | 402-07440 HMA BASE, TYPE A | 531.000 | TON |
| 22 | 406-05520 ASPHALT FOR TACK COAT | 3.000 | TON |
| 23 | 601-01128 GUARDRAIL TRANSITION TYPE WGB | 4.000 | EACH |
| 24 | 601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1 | 6.000 | EACH |
| 25 | 601-94689 GUARDRAIL END TREATMENT, OS | 2.000 | EACH |
| 26 | 601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING | 287.500 | LFT |
| 27 | 602-06729 BARRIER DELINEATOR | 6.000 | EACH |
| 28 | 610-06259 REINFORCED CONCRETE BRIDGE APPROACH, 12 IN. | 231.000 | SYS |
| 29 | 615-06505 MONUMENT, B | 5.000 | EACH |
| 30 | 616-02320 GEOTEXTILES | 800.000 | SYS |
| 31 | 616-06405 RIPRAP, REVETMENT | 501.000 | TON |
| 32 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 1.000 | EACH |
| 33 | 621-06545 FERTILIZER | 1.000 | TON |
| 34 | 621-06553 SEED MIXTURE, R | 335.000 | LBS |
| 35 | 621-06565 MULCHING MATERIAL | 4.000 | TON |
| 36 | 621-06567 WATER | 1.000 | KGAL |
| 37 | 621-06574 SODDING | 70.000 | SYS |
| 38 | 701-91792 PILE TIP, STEEL H | 10.000 | EACH |
| 39 | 701-95780 PILE, STEEL H, HP 12 X 74 | 470.000 | LFT |
| 40 | 703-51032 REINFORCING STEEL, EPOXY COATED | 46,195.000 | LBS |
| 41 | 704-51002 CONCRETE, C, SUPERSTRUCTURE | 169.800 | CYS |
| 42 | 706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC | 4.000 | EACH |
| 43 | 706-51020 CONCRETE, C, RAILING | 19.400 | CYS |
| 44 | 707-08512 STRUCTURAL MEMBERS, CONCRETE BOX BEAM, | 1,997.000 | LFT |
| 45 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 46 | 715-02628 SAFETY METAL END SECTION, 6:1, 15 IN. | 4.000 | EACH |
| 47 | 715-04629 PIPE | 4.000 | EACH |
| 48 | 715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN. | 1,544.000 | LFT |

CALL ORDER : 411
 LETTING DATE :

CONTRACT ID : B -28689-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | BRIDGE REPLACEMENT | | |
| 49 | 715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN. | 81.000 | LFT |
| 50 | 715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN. | 495.000 | LFT |
| 51 | 715-05407 PIPE, END BENT DRAIN, 6 IN. | 120.000 | LFT |
| 52 | 718-06528 OUTLET PROTECTOR, 1 | 4.000 | EACH |
| 53 | 718-52610 AGGREGATE FOR UNDERDRAINS | 232.000 | CYS |
| 54 | 718-99153 GEOTEXTILES FOR UNDERDRAIN | 1,544.000 | SYS |
| 55 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 6.000 | EACH |
| 56 | 801-06625 DETOUR ROUTE MARKER ASSEMBLY | 18.000 | EACH |
| 57 | 801-06640 CONSTRUCTION SIGN, A | 12.000 | EACH |
| 58 | 801-06645 CONSTRUCTION SIGN, B | 2.000 | EACH |
| 59 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 60 | 801-07118 BARRICADE, III-A | 96.000 | LFT |
| 61 | 801-07119 BARRICADE, III-B | 48.000 | LFT |
| 62 | 808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN. | 320.000 | LFT |
| 63 | 808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN. | 320.000 | LFT |
| 64 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 1,545.000 | LFT |
| 65 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 1,545.000 | LFT |

CALL ORDER : 470
LETTING DATE :

CONTRACT ID : M -29227-B

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--------------------------------------|----------|-------|
| SECTION NO. 0001 | HERBICIDE TREATMENT | | |
| 1 105-08520 | CELLULAR TELEPHONE/RADIO | 3.000 | EACH |
| 2 105-08521 | CELLULAR TELEPHONE/RADIO SERVICE | 36.000 | MOS |
| 3 105-08524 | CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 4 110-01001 | MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 5 624-92647 | HERBICIDE TREATMENT | 54.000 | ACRE |
| 6 801-06775 | MAINTAINING TRAFFIC | LUMP | LUMP |

CALL ORDER : 491
 LETTING DATE :

CONTRACT ID : M -29249-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | RESURFACE OVER ASPHALT PAVEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 3 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 4 | 304-07783 HMA PATCHING, TYPE D | 120.000 | TON |
| 5 | 411-08438 MICRO-SURFACING, WARRANTED | 14,500.000 | SYS |
| 6 | 720-44000 CASTING, ADJUST TO GRADE | 2.000 | EACH |
| 7 | 801-06640 CONSTRUCTION SIGN, A | 17.000 | EACH |
| 8 | 801-06710 FLASHING ARROW SIGN | 30.000 | DAY |
| 9 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 10 | 808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN. | 1,300.000 | LFT |
| 11 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 450.000 | LFT |
| 12 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 5,780.000 | LFT |
| 13 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 142.000 | LFT |
| 14 | 808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN. | 225.000 | LFT |
| 15 | 808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 16.000 | EACH |
| 16 | 808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 4.000 | EACH |

CALL ORDER : 501
 LETTING DATE :

CONTRACT ID : M -29250-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | RESURFACE OVER ASPHALT PAVEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-07038 FIELD OFFICE, A | 3.000 | MOS |
| 3 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 4 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 5 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 6 | 304-07783 HMA PATCHING, TYPE D | 250.000 | TON |
| 7 | 411-08438 MICRO-SURFACING, WARRANTED | 20,510.000 | SYS |
| 8 | 801-06640 CONSTRUCTION SIGN, A | 36.000 | EACH |
| 9 | 801-06710 FLASHING ARROW SIGN | 30.000 | DAY |
| 10 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 11 | 808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR) | 1.000 | EACH |
| 12 | 808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN. | 10.000 | LFT |
| 13 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 305.000 | LFT |
| 14 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 10,880.000 | LFT |
| 15 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 402.000 | LFT |
| 16 | 808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN. | 980.000 | LFT |
| 17 | 808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 10.000 | EACH |
| 18 | 808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 6.000 | EACH |

CALL ORDER : 511
 LETTING DATE :

CONTRACT ID : M -29300-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---------------------|----------|-------|
| SECTION NO. 0001 | MOWING | | |
| 1 623-04884 | MOWING, CYCLE NO. 1 | 1.000 | CYCL |
| 2 623-04885 | MOWING, CYCLE NO. 2 | 1.000 | CYCL |
| 3 623-04886 | MOWING, CYCLE NO. 3 | 1.000 | CYCL |

CALL ORDER : 521
 LETTING DATE :

CONTRACT ID : M -29301-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|------------------------------|----------|-------|
| SECTION NO. 0001 | ROADSIDE MAINTENANCE, MOWING | | |
| 1 623-04884 | MOWING, CYCLE NO. 1 | 1.000 | CYCL |
| 2 623-04885 | MOWING, CYCLE NO. 2 | 1.000 | CYCL |
| 3 623-04886 | MOWING, CYCLE NO. 3 | 1.000 | CYCL |

CALL ORDER : 531
LETTING DATE :

CONTRACT ID : M -29303-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|----------------------|-----------|-------|
| SECTION NO. 0001 | ROADSIDE MAINTENANCE | | |
| 1 624-92647 | HERBICIDE TREATMENT | 4,681.000 | ACRE |

CALL ORDER : 541
 LETTING DATE :

CONTRACT ID : M -29304-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|------------------------------|----------|-------|
| SECTION NO. 0001 | ROADSIDE MAINTENANCE, MOWING | | |
| 1 623-04884 | MOWING, CYCLE NO. 1 | 1.000 | CYCL |
| 2 623-04885 | MOWING, CYCLE NO. 2 | 1.000 | CYCL |
| 3 623-04886 | MOWING, CYCLE NO. 3 | 1.000 | CYCL |

CALL ORDER : 581
 LETTING DATE :

CONTRACT ID : T -28427-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|----------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNALS MODERNIZATION | | |
| 1 | 105-07038 FIELD OFFICE, A | 4.000 | MOS |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 4.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 5 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 6 | 801-06640 CONSTRUCTION SIGN, A | 16.000 | EACH |
| 7 | 801-06710 FLASHING ARROW SIGN | 60.000 | DAY |
| 8 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 9 | 805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN. | 186.000 | EACH |
| 10 | 805-02266 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN. | 135.000 | EACH |
| 11 | 805-02266 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN. | 548.000 | EACH |
| 12 | 805-02266 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN. | 542.000 | EACH |
| 13 | 805-02266 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN. | 139.000 | EACH |
| 14 | 805-02279 VISOR, TRAFFIC SIGNAL, REPLACE | 5.000 | EACH |
| 15 | 805-03372 TETHER FOR SIGNAL | 8.000 | EACH |
| 16 | 805-09061 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN., AMBER | 634.000 | EACH |
| 17 | 805-09062 LENS REPLACEMENT, INTERNATIONAL, PEDESTRIAN, 18 IN. | 10.000 | EACH |
| 18 | 805-09067 TRAFFIC SIGNAL HEAD, REMOVE | 269.000 | EACH |
| 19 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN | 37.000 | EACH |
| 20 | 805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN, | 15.000 | EACH |

CALL ORDER : 591
 LETTING DATE :

CONTRACT ID : T -29126-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNAL MODERNIZATION | | |
| 1 | 105-08520 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 2 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 5.000 | MOS |
| 3 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 4 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 5 | 202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE | LUMP | LUMP |
| 6 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 7 | 805-01842 HANDHOLE, SIGNAL | 39.000 | EACH |
| 8 | 805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT | LUMP | LUMP |
| 9 | 805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN. | 6,274.000 | LFT |
| 10 | 805-06595 CONDUIT, PVC, 2 IN. | 30.000 | LFT |
| 11 | 805-06595 CONDUIT, PVC, 2 IN. | 160.000 | LFT |
| 12 | 805-08493 RADIO SYSTEM TESTING INTERCONNECT | LUMP | LUMP |
| 13 | 805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA. | 20,702.000 | LFT |
| 14 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 27,705.000 | LFT |
| 15 | 805-78785 SIGNAL DETECTOR HOUSING | 50.000 | EACH |
| 16 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER | 7,045.000 | LFT |
| 17 | 805-79020 TRAFFIC SIGNAL INSTALLATION | LUMP | LUMP |
| 18 | 805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL | 58.000 | EACH |
| 19 | 805-92512 MICROLOOP DETECTOR | 4.000 | EACH |
| 20 | 807-04967 CABLE | 835.000 | LFT |
| 21 | 807-05073 JUNCTION BOX | 1.000 | EACH |

CALL ORDER : 621
 LETTING DATE :

CONTRACT ID : TM-29325-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS | |
|------------------|----------------------|---|------------|------|
| SECTION NO. 0001 | LIGHTING MAINTENANCE | | | |
| 1 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 2 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 3 | 202-90277 | DETECTOR HOUSING, REMOVE | 1.000 | EACH |
| 4 | 202-93763 | LIGHT STANDARD AND FOUNDATION, REMOVE | 1.000 | EACH |
| 5 | 702-90915 | CONCRETE, A | 20.000 | CYS |
| 6 | 803-87715 | GROUND ROD WITH CONNECTOR | 3.000 | EACH |
| 7 | 805-01523 | MAST ARM, INSTALL | 10.000 | EACH |
| 8 | 805-01815 | SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT. | 6.000 | EACH |
| 9 | 805-06592 | CONDUIT, STEEL, GALVANIZED, 2 IN. | 60.000 | LFT |
| 10 | 805-78470 | SIGNAL CABLE, ROADWAY LOOP, 1C 14GA. | 1,000.000 | LFT |
| 11 | 805-78510 | SIGNAL CABLE, 2C 16GA., SHIELDED | 200.000 | LFT |
| 12 | 805-78785 | SIGNAL DETECTOR HOUSING | 1.000 | EACH |
| 13 | 805-78795 | SAW CUT FOR ROADWAY LOOP AND SEALER | 300.000 | LFT |
| 14 | 805-86843 | WIRE, NO. 4 COPPER, 1C | 1,400.000 | LFT |
| 15 | 805-86889 | POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER | 1,200.000 | LFT |
| 16 | 805-86898 | CONDUIT, STEEL, GALVANIZED, .75 IN. | 20.000 | LFT |
| 17 | 805-87640 | BREAKAWAY COUPLING | 2.000 | SET |
| 18 | 805-87780 | CIRCUIT BREAKER | 4.000 | EACH |
| 19 | 805-91706 | ANCHOR BOLT, REPAIR | 3.000 | EACH |
| 20 | 805-95518 | FLEXIBLE CONDUIT, 2 IN. | 15.000 | LFT |
| 21 | 805-95520 | EXPANSION FITTING, 2 IN. | 1.000 | EACH |
| 22 | 805-95521 | EXPANSION FITTING, 0.75 IN. | 2.000 | EACH |
| 23 | 807-01425 | SHAFT FOR ANY E.M.H., ANY M.A., INSTALL | 15.000 | EACH |
| 24 | 807-01562 | POWER DISCONNECT PLUG FOR HIGH MAST TOWER | 3.000 | EACH |
| 25 | 807-01617 | HANDHOLE COVER AND RING | 1.000 | EACH |
| 26 | 807-05104 | ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM, 175 | 24.000 | MOS |
| 27 | 807-78590 | HANDHOLE | 2.000 | EACH |
| 28 | 807-86615 | LUMINAIRE, ROADWAY, 250 WATT, HIGH PRESSURE SODIUM | 20.000 | EACH |
| 29 | 807-86620 | LUMINAIRE, ROADWAY, HIGH PRESSURE | 30.000 | EACH |
| 30 | 807-86665 | LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM | 1.000 | EACH |
| 31 | 807-86800 | LUMINAIRE, SIGN, MERCURY VAPOR WITH GLARE SHIELD AND VANDAL | 1.000 | EACH |
| 32 | 807-86805 | SERVICE POINT, I | 1.000 | EACH |
| 33 | 807-86810 | SERVICE POINT, II | 1.000 | EACH |
| 34 | 807-86910 | CONNECTOR KIT, UNFUSED | 20.000 | EACH |
| 35 | 807-86915 | CONNECTOR KIT, FUSED | 25.000 | EACH |
| 36 | 807-86920 | MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED | 25.000 | EACH |
| 37 | 807-86930 | INSULATION LINK, NONWATERPROOFED | 30.000 | EACH |
| 38 | 807-86950 | SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION | 1.000 | EACH |
| 39 | 807-86955 | CABLE DUCT MARKER | 2.000 | EACH |
| 40 | 807-87022 | ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM, | 10,356.000 | MOS |
| 41 | 807-87028 | ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM, | 7,992.000 | MOS |
| 42 | 807-87042 | ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM, | 1,596.000 | MOS |
| 43 | 807-87043 | ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM, | 504.000 | MOS |
| 44 | 807-87050 | ROUTINE MAINTENANCE, LUMINAIRE, SIGN, 250 WATT | 6,240.000 | MOS |
| 45 | 807-87085 | ELECTRICIAN | 15.000 | HRS |
| 46 | 807-87098 | CALL OUT, REPAIR | 5.000 | EACH |
| 47 | 807-87620 | VANDAL SHIELD, LEXAN, INSTALL | 5.000 | EACH |
| 48 | 807-87800 | CABLE DUCT, INSTALL | 600.000 | LFT |

CALL ORDER : 621
 LETTING DATE :

CONTRACT ID : TM-29325-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | LIGHTING MAINTENANCE | | |
| 49 | 807-91704 LIGHT POLE HANDHOLE COVER | 1.000 | EACH |
| 50 | 807-91705 CONDUIT, POLYETHYLENE, REPAIR | 2.000 | EACH |
| 51 | 807-93650 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY | 1.000 | SET |
| 52 | 807-93746 TOWER RING LIFT CABLE, 0.375 | 150.000 | LFT |
| 53 | 807-95078 TRANSFORMER BASE | 12.000 | EACH |
| 54 | 807-95488 NEMA 4/5 UNDERPASS OR SIGN CIRCUIT BREAKER, ENCLOSURE | 1.000 | EACH |
| 55 | 807-95492 SERVICE POINT, II, BREAKER ENCLOSURE | 1.000 | EACH |
| 56 | 807-95509 GLARE SHIELD | 8.000 | EACH |
| 57 | 807-95513 SERVICE POINT MAIN BREAKER | 2.000 | EACH |
| 58 | 807-95514 SERVICE POINT RISER | 1.000 | EACH |
| 59 | 807-95515 SERVICE POINT WEATHERHEAD | 1.000 | EACH |
| 60 | 807-95516 RELAY SWITCH | 1.000 | EACH |
| 61 | 807-95519 FLEXIBLE CONDUIT, .75 IN. | 5.000 | LFT |
| 62 | 807-95522 PIPE STRAP | 6.000 | EACH |
| 63 | 807-95523 WATERPROOFING OF ELECTRICAL CONNECTOR | 35.000 | EACH |
| 64 | 807-95525 LIGHTING, HIGHWAY SUPPORT, REPAIR | 1.000 | EACH |
| 65 | 807-95528 GROUP RELAMP HIGH PRESSURE SODIUM LUMINAIRES | LUMP | LUMP |
| 66 | 807-95529 GROUP RELAMP MERCURY VAPOR LUMINAIRES | LUMP | LUMP |
| 67 | 807-95709 PHOTOCELLS | 25.000 | EACH |
| 68 | 807-96194 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM, | 4,896.000 | MOS |
| 69 | 807-96203 LIGHT POLE, HIGH MAST, TOWER SUSPENSION CABLE | 1.000 | EACH |
| 70 | 807-96204 LOWERING AND RAISING OF TOWER | 4.000 | EACH |
| 71 | 807-96236 LIGHT POLE, HIGH MAST, TOWER POWER CABLE | 1.000 | EACH |
| 72 | 807-96868 LUMINAIRE, INSTALL | 1.000 | EACH |
| 73 | 807-98716 KELLUM GRIP, STAINLESS STEEL | 1.000 | EACH |

CALL ORDER : 631
 LETTING DATE :

CONTRACT ID : TM-29393-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNAL MAINTENANCE | | |
| 1 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 2 | 210-07224 VIDEO | 10.000 | EACH |
| 3 | 702-76240 CONCRETE | 4.000 | CYS |
| 4 | 805-01523 MAST ARM, INSTALL | 1.000 | EACH |
| 5 | 805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT. | 1.000 | EACH |
| 6 | 805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT. | 1.000 | EACH |
| 7 | 805-01820 SIGNAL STRAIN POLE, STEEL, INSTALL | 1.000 | EACH |
| 8 | 805-01821 SIGNAL CANTILEVER STRUCTURE, INSTALL | 1.000 | EACH |
| 9 | 805-01822 SPAN, CATENARY AND TETHER, INSTALL | 5.000 | EACH |
| 10 | 805-01823 TETHER CABLE, INSTALL | 5.000 | EACH |
| 11 | 805-01824 SPAN, CATENARY, AND TETHER, TIGHTEN | 5.000 | EACH |
| 12 | 805-01825 DISCONNECT HANGER, INSTALL | 5.000 | EACH |
| 13 | 805-01827 TRAFFIC SIGNAL HEAD, INSTALL | 20.000 | EACH |
| 14 | 805-01829 SIGN, INSTALL | 10.000 | EACH |
| 15 | 805-01830 CONFLICT MONITOR CHANGEOUT | 218.000 | EACH |
| 16 | 805-01833 LOOP SYSTEM CHECK | 120.000 | EACH |
| 17 | 805-01835 TRAFFIC SIGNAL HEAD, REPAIR | 25.000 | EACH |
| 18 | 805-01842 HANDHOLE, SIGNAL | 2.000 | EACH |
| 19 | 805-01843 SIGNAL HANDHOLE ADJUST TO GRADE | 2.000 | EACH |
| 20 | 805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND | 200.000 | LFT |
| 21 | 805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND | 180.000 | LFT |
| 22 | 805-02266 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN. | 50.000 | EACH |
| 23 | 805-03690 SIGNAL CABLE, INSTALL | 3,000.000 | LFT |
| 24 | 805-05707 PRE-WARNING FLASHER, BULB REPLACEMENT, GROUND INSPECTION | 7.000 | EACH |
| 25 | 805-06363 FIBER OPTIC ST TERMINATION | 14.000 | EACH |
| 26 | 805-06364 FIBER OPTIC BREAKOUT KIT | 1.000 | EACH |
| 27 | 805-06891 VIDEO CAMERA DETECTOR, INSTALL | 4.000 | EACH |
| 28 | 805-06892 VIDEO SIGNAL CABLE | 160.000 | LFT |
| 29 | 805-06893 VIDEO CABLE CONNECTOR | 3.000 | EACH |
| 30 | 805-06894 VIDEO CABLE JUNCTION BOX, INSTALL | 1.000 | EACH |
| 31 | 805-09072 AERIAL INSPECTION | 100.000 | EACH |
| 32 | 805-09073 TRUCK, SERVICE | 10.000 | HRS |
| 33 | 805-78370 PEDESTRIAN PUSH BUTTON | 5.000 | EACH |
| 34 | 805-78445 SIGNAL SERVICE | 5.000 | EACH |
| 35 | 805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA. | 3,000.000 | LFT |
| 36 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 500.000 | LFT |
| 37 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER | 2,000.000 | LFT |
| 38 | 805-78800 SIGNAL DETECTOR HOUSING INSTALL | 4.000 | EACH |
| 39 | 805-78900 PEDESTAL FOUNDATION, A | 1.000 | EACH |
| 40 | 805-78925 CONTROLLER CABINET FOUNDATION, P1 | 1.000 | EACH |
| 41 | 805-87068 TRUCK, BUCKET | 10.000 | HRS |
| 42 | 805-87076 TRUCK, PICKUP | 10.000 | HRS |
| 43 | 805-87090 LABOR, SKILLED, OVERTIME | 10.000 | HRS |
| 44 | 805-87092 LABOR, SKILLED, STRAIGHT TIME | 20.000 | HRS |
| 45 | 805-87093 LABOR, SKILLED, DOUBLETIME | 5.000 | HRS |
| 46 | 805-91706 ANCHOR BOLT, REPAIR | 2.000 | EACH |
| 47 | 805-92327 SIGNAL PEDESTAL, INSTALL | 2.000 | EACH |
| 48 | 805-92336 SIGNAL POLE, WOOD, INSTALL | 1.000 | EACH |

CALL ORDER : 631
 LETTING DATE :

CONTRACT ID : TM-29393-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNAL MAINTENANCE | | |
| 49 | 805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE | 2.000 | EACH |
| 50 | 805-92983 TRAFFIC SIGNAL CONTROLLER AND CABINET, INSTALL | 2.000 | EACH |
| 51 | 805-94636 SIGNAL CABINET FOUNDATION EXPANSION | 1.000 | EACH |
| 52 | 805-94677 EMERGENCY RESPONSE MAINTENANCE OF DIGITAL CONTROLLER | 2,616.000 | MOS |
| 53 | 805-94680 EMERGENCY RESPONSE MAINTENANCE OF FLASHER CONTROLLER | 84.000 | MOS |
| 54 | 805-94680 EMERGENCY RESPONSE MAINTENANCE OF FLASHER CONTROLLER | 144.000 | MOS |
| 55 | 805-94682 LOOP TESTING | 204.000 | EACH |
| 56 | 805-94687 LOCATE UNDERGROUND SIGNAL FACILITIES | 5.000 | EACH |
| 57 | 805-94721 SIGNAL BULB REPLACEMENT, AERIAL INSPECTION | 128.000 | EACH |
| 58 | 805-94724 FLASHER, BULB REPLACEMENT, AERIAL INSPECTION | 8.000 | EACH |
| 59 | 805-94971 FIBER OPTICS CABLE | 330.000 | LFT |
| 60 | 805-95695 EXPANSION ANCHOR BOLT (PEDESTAL AND CONTROLLER ONLY) | 3.000 | EACH |
| 61 | 805-97042 SIGNAL POLE, WOOD, 5, 35 FT. | 1.000 | EACH |

