

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-29162-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNS, LIGHTING, SIGNALS AND MARKINGS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	3.000	EACH
3	105-07040 FIELD OFFICE, C	36.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	36.000	MOS
6	105-08523 RADIO SERVICE	108.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	105-09198 LAPTOP COMPUTER SYSTEM	108.000	MOS
9	105-09199 FIELD OFFICE INTERNET SERVICE	36.000	MOS
10	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
11	108-09283 CPM SCHEDULE	LUMP	LUMP
12	108-09284 CPM SCHEDULE, MONTHLY UPDATE	26.000	EACH
13	108-09285 CPM SCHEDULE, REVISED	6.000	EACH
14	109-08359 LIQUIDATED DAMAGES	1.000	DOL
15	109-08360 CONTRACT LIENS	1.000	DOL
16	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
17	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
18	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
19	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
20	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
21	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
22	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
23	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.000	EACH
24	202-02240 PAVEMENT REMOVAL	37,297.000	SYS
25	202-02241 GUARDRAIL, REMOVE	1,925.000	LFT
26	202-02273 CENTER CURB, CONCRETE, REMOVE	73.190	SYS
27	202-02274 CURB, CONCRETE, INTEGRAL, REMOVE	777.000	LFT
28	202-02278 CURB, CONCRETE, REMOVE	196.000	LFT
29	202-02279 CURB AND GUTTER, REMOVE	1,969.000	LFT
30	202-03783 SIGN, PANEL, REMOVE	3.000	EACH
31	202-05677 BARRIER ISLAND, REMOVE	9.000	EACH
32	202-52710 SIDEWALK, CONCRETE, REMOVE	34.770	SYS
33	202-60815 CENTER CURB, REMOVE	59.000	LFT
34	202-74035 SIGN, REMOVE	5.000	EACH
35	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	143.000	EACH
36	202-90277 DETECTOR HOUSING, REMOVE	52.000	EACH
37	202-93974 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM, REMOVE	2.000	EACH
38	202-94749 CURB, ASPHALT, REMOVE	69.000	LFT
39	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	1,735.000	LFT
40	202-94954 BARRIER WALL, CONCRETE, REMOVE	5,689.000	LFT
41	202-95027 IMPACT ATTENUATOR, REMOVE	2.000	EACH
42	202-96133 PIPE, REMOVE	128.000	LFT
43	202-96133 PIPE, REMOVE	520.000	LFT
44	203-02000 EXCAVATION, COMMON	31,221.000	CYS
45	203-02070 BORROW	358.000	CYS
46	205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	55.000	EACH
47	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	15.000	TON
48	205-06932 TEMPORARY CHECK DAM, STRAW BALES	14.000	LFT

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-29162-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNS, LIGHTING, SIGNALS AND MARKINGS		
49	205-06933	TEMPORARY DITCH INLET PROTECTION	1.000 EACH
50	205-06937	TEMPORARY SILT FENCE	1,120.000 LFT
51	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	2,450.000 CYS
52	207-08263	SUBGRADE TREATMENT, TYPE IA	56,535.000 SYS
53	207-08267	SUBGRADE TREATMENT, TYPE IIIA	592.000 SYS
54	207-08268	SUBGRADE TREATMENT, TYPE IV	1,064.000 SYS
55	211-07454	STRUCTURE BACKFILL	4,917.000 CYS
56	211-09264	STRUCTURE BACKFILL, TYPE 1	2.500 CYS
57	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	1,573.000 TON
58	302-06464	SUBBASE FOR PCCP	14,793.000 CYS
59	302-07455	DENSE GRADED SUBBASE	137.000 CYS
60	303-01180	COMPACTED AGGREGATE, NO. 53	4,046.400 TON
61	304-07491	HMA PATCHING, TYPE C	3,868.000 TON
62	304-07492	WIDENING WITH HMA, TYPE A	238.000 TON
63	306-08042	MILLING, SCARIFICATION/PROFILE	66,326.000 SYS
64	306-08043	MILLING, TRANSITION	8,659.000 SYS
65	306-08432	MILLING, APPROACH	9,871.000 SYS
66	401-06264	PROFILOGRAPH, HMA	LUMP LUMP
67	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	6,647.000 TON
68	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	11,289.000 TON
69	402-05496	HMA FOR ISLANDS	6.000 TON
70	402-07453	HMA FOR TEMPORARY PAVEMENT	3,696.000 TON
71	406-05520	ASPHALT FOR TACK COAT	42.000 TON
72	501-05240	CONTRACTION JOINT, D1	30,760.000 LFT
73	501-06325	QC/QA-PCCP, 14 IN.	53,137.000 SYS
74	501-06727	CORING, PCCP	LUMP LUMP
75	503-03489	RETROFITTED TIE BARS	124.000 EACH
76	503-05240	D-1 CONTRACTION JOINT	383.000 LFT
77	506-06333	PCCP PATCHING, FULL DEPTH	100.000 SYS
78	601-06246	IMPACT ATTENUATOR, R2, W1, TL-3	6.000 EACH
79	601-06306	IMPACT ATTENUATOR, RESET, R2, W1, TL-3	16.000 EACH
80	601-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000 EACH
81	602-06729	BARRIER DELINEATOR	280.000 EACH
82	602-08472	CONCRETE BARRIER, 33 IN.	5,871.000 LFT
83	604-06070	SIDEWALK, CONCRETE	34.770 SYS
84	604-07483	HMA FOR SIDEWALK	98.000 TON
85	604-91531	SIDEWALK, CONCRETE, 4 IN.	3,852.000 SYS
86	605-02493	CURB ISLAND, CONCRETE	38.390 SYS
87	605-06090	CURB, INTEGRAL, CONCRETE	115.000 LFT
88	605-06095	CURB, INTEGRAL, B, CONCRETE	577.000 LFT
89	605-06100	CURB, INTEGRAL, C, CONCRETE	7,985.000 LFT
90	605-06120	CURB, CONCRETE	1,378.000 LFT
91	605-06140	CURB AND GUTTER, CONCRETE	1,969.000 LFT
92	605-06215	CENTER CURB, D, CONCRETE	59.000 LFT
93	605-06250	CENTER CURB, C, CONCRETE	785.000 SYS
94	607-06335	PAVED SIDE DITCH, A	620.000 LFT
95	610-07488	HMA FOR APPROACHES, TYPE C	2,274.000 TON
96	610-09253	PCCP FOR APPROACHES, 9.5 IN.	773.000 SYS

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-29162-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNS, LIGHTING, SIGNALS AND MARKINGS		
97	615-06490 RIGHT OF WAY MARKER	2.000	EACH
98	615-06505 MONUMENT, B	4.000	EACH
99	615-06510 MONUMENT, C	3.000	EACH
100	615-06515 MONUMENT, D	17.000	EACH
101	615-06527 MONUMENT, SECTION CORNER	8.000	EACH
102	616-02320 GEOTEXTILES	505.000	SYS
103	616-06406 RIPRAP, REVETMENT	376.000	SYS
104	616-51367 SLOPEWALL, CONCRETE, 4 IN.	350.000	SYS
105	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
106	621-06545 FERTILIZER	0.010	TON
107	621-06557 SEED MIXTURE, T	8.000	LBS
108	621-06559 MULCHED SEEDING, R	27,911.000	SYS
109	621-06565 MULCHING MATERIAL	0.200	TON
110	621-06567 WATER	2.400	KGAL
111	621-06575 SODDING, NURSERY	25,215.000	SYS
112	621-06575 SODDING, NURSERY	1,164.000	SYS
113	702-51015 CONCRETE, B, FOOTINGS	260.000	CYS
114	702-90915 CONCRETE, A	250.000	CYS
115	702-90915 CONCRETE, A	12.000	CYS
116	703-51032 REINFORCING STEEL, EPOXY COATED	74,336.000	LBS
117	715-01384 PIPE, DUCTILE IRON, 10 IN.	546.000	LFT
118	715-02398 SAFETY METAL END SECTION, 6:1, 36 IN.	2.000	EACH
119	715-02630 SAFETY METAL END SECTION, 6:1, 24 IN.	4.000	EACH
120	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	1,169.000	LFT
121	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	24.000	LFT
122	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	10,506.000	LFT
123	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	618.000	LFT
124	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	165.000	LFT
125	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	2,237.000	LFT
126	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	1,418.000	LFT
127	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	36.000	LFT
128	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	826.000	LFT
129	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	48.000	LFT
130	715-05335 PIPE, TYPE 2, DEFORMED, MIN. AREA 5.1 SFT.	446.000	LFT
131	715-08450 SAFETY METAL END SECTION, 6:1, MIN. AREA 5.1 SQ. FT.	1.000	EACH
132	715-09191 PIPE, TYPE 2, DEFORMED, MIN. AREA 7.4 SFT.	793.000	LFT
133	715-46000 PIPE END SECTION, 12 IN.	10.000	EACH
134	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
135	715-46010 PIPE END SECTION, 18 IN.	2.000	EACH
136	715-46040 PIPE END SECTION, 36 IN.	5.000	EACH
137	715-97804 PIPE END SECTION, MIN. AREA 7.4 SQ. FT.	2.000	EACH
138	718-06528 OUTLET PROTECTOR, 1	18.000	EACH
139	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
140	718-52610 AGGREGATE FOR UNDERDRAINS	1,251.000	CYS
141	718-99153 GEOTEXTILES FOR UNDERDRAIN	21,773.000	SYS
142	720-44000 CASTING, ADJUST TO GRADE	33.000	EACH
143	720-45045 INLET, J10	23.000	EACH
144	720-45055 INLET, M10	28.000	EACH

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-29162-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNS, LIGHTING, SIGNALS AND MARKINGS		
145	720-45235 CATCH BASIN, E7	1.000	EACH
146	720-45410 MANHOLE, C4	5.000	EACH
147	720-45415 MANHOLE, D4	7.000	EACH
148	720-98555 INLET, C15	2.000	EACH
149	732-03273 HYDRA STOP	2.000	EACH
150	732-08419 MODULAR BLOCK WALL	38.000	SYS
151	732-09202 VALVE WITH BOX, RESTRAINED, GATE,	2.000	EACH
152	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
153	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	9.000	EACH
154	801-03290 CONSTRUCTION SIGN, C	14.000	EACH
155	801-03291 CONSTRUCTION SIGN, D	3.000	EACH
156	801-04308 ROAD CLOSURE SIGN ASSEMBLY	10.000	EACH
157	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	29,494.000	LFT
158	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	66,534.000	LFT
159	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	4.000	EACH
160	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	2,584.000	LFT
161	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	87.000	LFT
162	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	2,751.000	LFT
163	801-06625 DETOUR ROUTE MARKER ASSEMBLY	14.000	EACH
164	801-06640 CONSTRUCTION SIGN, A	63.000	EACH
165	801-06645 CONSTRUCTION SIGN, B	9.000	EACH
166	801-06710 FLASHING ARROW SIGN	2,160.000	DAY
167	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
168	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	1.000	EACH
169	801-07118 BARRICADE, III-A	1,224.000	LFT
170	801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1	311.000	LFT
171	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	5,921.000	LFT
172	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	341.000	LFT
173	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
174	801-94295 SIGNAL HEAD, RELOCATE	60.000	EACH
175	801-99182 TEMPORARY CHANGEABLE MESSAGE SIGN, INSTALL AND MAINTAIN	2.000	EACH
176	802-02158 SIGN, PANEL, REMOVE AND REINSTALL	3.000	EACH
177	802-03706 SIGN PANEL, INSTALL	3.000	EACH
178	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	614.000	LFT
179	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	529.000	LFT
180	802-07102 SIGN LIGHTING SYSTEM, TRACK, CANTILEVER	2.000	EACH
181	802-07138 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, IX	4.000	EACH
182	802-07153 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	4.000	EACH
183	802-07158 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, I	1.000	EACH
184	802-07159 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, II	1.000	EACH
185	802-76015 SIGN,PANEL,ENCAPSULATED LENS WITH LEGEND	517.000	SFT
186	802-76020 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.080 IN. THICKNESS	26.500	SFT
187	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	289.560	SFT
188	802-76030 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.100 IN. THICKNESS	6.000	SFT
189	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	353.130	SFT
190	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	101.880	SFT
191	802-76095 STRUCTURAL STEEL, BREAKAWAY	2,658.500	LBS
192	802-76140 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM	2.000	EACH

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-29162-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGNS, LIGHTING, SIGNALS AND MARKINGS			
193	802-99058 SHEET SIGN, INSTALL	17.000	EACH
194	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	12.000	EACH
195	805-01842 HANDHOLE, SIGNAL	40.000	EACH
196	805-01879 SIGNAL SERVICE, INSTALL	3.000	EACH
197	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
198	805-02441 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	460.000	LFT
199	805-04956 PANEL FOR FIBER OPTICS	1.000	EACH
200	805-05582 FIBER OPTIC TERMINATION	1.000	EACH
201	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	4,856.000	LFT
202	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	3.000	EACH
203	805-08464 RADIO, INTERCONNECT	3.000	EACH
204	805-08466 RADIO ANTENNA, 9db, YAGI	3.000	EACH
205	805-08493 RADIO SYSTEM TESTING INTERCONNECT	LUMP	LUMP
206	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	25.000	EACH
207	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	5.000	EACH
208	805-78415 SPAN, CATENARY, AND TETHER	12.000	EACH
209	805-78420 DISCONNECT HANGER	12.000	EACH
210	805-78467 SIGNAL CABLE, 3C 8GA.	134.000	LFT
211	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	19,460.000	LFT
212	805-78485 SIGNAL CABLE, 5C 14GA.	1,798.000	LFT
213	805-78490 SIGNAL CABLE, 7C 14GA.	1,917.000	LFT
214	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	16,368.000	LFT
215	805-78746 PREFORMED LOOP DETECTORS	5,192.000	LFT
216	805-78785 SIGNAL DETECTOR HOUSING	52.000	EACH
217	805-78790 LOOP DETECTOR DELAY AMPLIFIER, 4 CHANNEL	14.000	EACH
218	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	17,096.000	LFT
219	805-78925 CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
220	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	12.000	EACH
221	805-94295 SIGNAL HEAD, RELOCATE	75.000	EACH
222	805-96014 SAW CUT, FULL DEPTH	1,319.000	LFT
223	807-98690 HANDHOLE ADJUSTED TO GRADE	40.000	EACH
224	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	10,981.000	LFT
225	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	14,367.000	LFT
226	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	7,498.000	LFT
227	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN.	986.300	LFT
228	808-06194 LINE, EPOXY, SOLID, WHITE, 12 IN.	443.300	LFT
229	808-06368 TRANSVERSE MARKING, REMOVE	30.000	LFT
230	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	3,494.000	LFT
231	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	23,501.000	LFT
232	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	506.000	LFT
233	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	257.000	LFT
234	808-06716 LINE, REMOVE	24,150.000	LFT
235	808-06848 LINE, EPOXY, DOTTED, WHITE, 4 IN, 24 IN LINE, 48 IN GAP	433.400	LFT
236	808-06849 LINE, EPOXY, DOTTED, YELLOW, 4 IN, 24 IN LINE, 48 IN GAP	378.600	LFT
237	808-07591 LINE, EPOXY, SOLID, WHITE, 24 IN.	730.600	LFT
238	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	51.000	EACH
239	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	17.000	EACH
240	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	14,432.000	LFT

SCHEDULE OF PAY ITEMS

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-29162-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNS, LIGHTING, SIGNALS AND MARKINGS		
241 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	1,292.000	LFT
242 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	69.000	EACH
243 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	19.000	EACH
244 808-75340	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	4.000	EACH
245 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	782.000	EACH
246 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	151.000	EACH
247 808-98796	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN., 2 FT. LINE, 4 FT.	250.000	LFT

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-29470-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	12.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	12.000	MOS
8	108-09283 CPM SCHEDULE	LUMP	LUMP
9	108-09284 CPM SCHEDULE, MONTHLY UPDATE	7.000	EACH
10	108-09285 CPM SCHEDULE, REVISED	4.000	EACH
11	109-08359 LIQUIDATED DAMAGES	1.000	DOL
12	109-08360 CONTRACT LIENS	1.000	DOL
13	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
14	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
15	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
16	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
17	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
18	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
19	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
20	203-02000 EXCAVATION, COMMON	32,826.000	CYS
21	203-02070 BORROW	67,434.000	CYS
22	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	262.000	TON
23	205-06932 TEMPORARY CHECK DAM, STRAW BALES	435.000	LFT
24	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
25	205-06937 TEMPORARY SILT FENCE	21,931.000	LFT
26	207-08263 SUBGRADE TREATMENT, TYPE IA	48,093.000	SYS
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	38.000	SYS
28	211-09264 STRUCTURE BACKFILL, TYPE 1	1,431.000	CYS
29	214-07202 GEOGRID, I	24,047.000	SYS
30	215-07043 CHEMICAL MODIFICATION, SOILS	24,047.000	SYS
31	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	33,158.000	TON
32	303-07662 STONE	75.000	TON
33	306-08034 MILLING, ASPHALT, 1 1/2 IN.	3,154.000	SYS
34	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	3,766.000	TON
35	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	5,844.000	TON
36	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	6,375.000	TON
37	401-09060 QC/QA-HMA, 2, 64, BASE, 25.0 mm-PWL	14,025.000	TON
38	406-05520 ASPHALT FOR TACK COAT	43.300	TON
39	610-07487 HMA FOR APPROACHES, TYPE B	11.000	TON
40	615-06505 MONUMENT, B	35.000	EACH
41	616-02320 GEOTEXTILES	1,881.000	SYS
42	616-05688 RIPRAP, CLASS 1	78.000	TON
43	616-06405 RIPRAP, REVETMENT	836.000	TON
44	616-06451 RIPRAP, UNIFORM	83.000	TON
45	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
46	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	73,650.000	SYS
47	621-06559 MULCHED SEEDING, R	49,102.000	SYS
48	621-06567 WATER	47.000	KGAL

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-29470-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD		
49	621-06574 SODDING	11,567.000	SYS
50	621-06575 SODDING, NURSERY	108.000	SYS
51	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	59.000	LFT
52	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	11,173.000	LFT
53	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	750.000	LFT
54	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	69.000	LFT
55	715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN.	84.000	LFT
56	715-05234 PIPE, TYPE 1, DEFORMED, MIN. AREA 4.1 SQ. FT.	282.000	LFT
57	715-05252 PIPE, TYPE 1, DEFORMED, 20.5 SQ. FT.	77.000	LFT
58	715-07536 CONCRETE ANCHOR, MIN. AREA 12.9 SFT.	2.000	EACH
59	715-08171 PIPE, TYPE 1, DEFORMED, MIN. AREA 12.9 SFT.	129.000	LFT
60	715-08181 PIPE END SECTION, MIN. AREA 4.1 SFT.	8.000	EACH
61	715-08303 CONCRETE ANCHOR, MIN. AREA 20.5 SQ. FT.	2.000	EACH
62	715-08447 PIPE, TYPE 1, DEFORMED, MIN. AREA 5.1 SQ. FT.	116.000	LFT
63	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
64	715-46030 PIPE END SECTION, 30 IN.	2.000	EACH
65	715-46040 PIPE END SECTION, 36 IN.	2.000	EACH
66	718-06529 OUTLET PROTECTOR, 2	10.000	EACH
67	718-06531 OUTLET PROTECTOR, 3	24.000	EACH
68	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
69	718-52610 AGGREGATE FOR UNDERDRAINS	1,013.000	CYS
70	718-99153 GEOTEXTILES FOR UNDERDRAIN	7,665.000	SYS
71	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
72	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,732.000	LFT
73	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	1.000	EACH
74	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (ONLY)	1.000	EACH
75	801-06625 DETOUR ROUTE MARKER ASSEMBLY	25.000	EACH
76	801-06640 CONSTRUCTION SIGN, A	33.000	EACH
77	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
78	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
79	801-07119 BARRICADE, III-B	216.000	LFT
80	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN.	78.000	LFT
81	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	637.600	LFT
82	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	31.000	EACH
83	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	172.550	SFT
84	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	413.790	SFT
85	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	48.500	SFT
86	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	1.000	EACH
87	805-01842 HANDHOLE, SIGNAL	3.000	EACH
88	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	1.000	EACH
89	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,003.000	LFT
90	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	10.000	EACH
91	805-78415 SPAN, CATENARY, AND TETHER	6.000	EACH
92	805-78420 DISCONNECT HANGER	4.000	EACH
93	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	3,590.000	LFT
94	805-78485 SIGNAL CABLE, 5C 14GA.	289.000	LFT
95	805-78490 SIGNAL CABLE, 7C 14GA.	811.000	LFT
96	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,935.000	LFT

SCHEDULE OF PAY ITEMS

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-29470-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD		
97	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
98	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,450.000	LFT
99	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	1.000	EACH
100	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	5.000	EACH
101	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	25,957.000	LFT
102	808-06716 LINE, REMOVE	3,578.000	LFT
103	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,040.000	LFT
104	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	16,271.000	LFT
105	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	1,031.000	LFT
106	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	177.000	LFT
107	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	10.000	EACH
108	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	9.000	EACH
109	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	240.000	EACH
110	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	2,540.000	LFT

CALL ORDER : 171
 LETTING DATE :

CONTRACT ID : IR-29962-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	24.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	5.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	120.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	72.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	24.000	MOS
8	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
9	108-09283 CPM SCHEDULE	LUMP	LUMP
10	108-09284 CPM SCHEDULE, MONTHLY UPDATE	2.000	EACH
11	108-09285 CPM SCHEDULE, REVISED	4.000	EACH
12	109-08359 LIQUIDATED DAMAGES	1.000	DOL
13	109-08360 CONTRACT LIENS	1.000	DOL
14	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
15	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
16	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
17	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
18	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
19	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
20	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
21	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
22	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
23	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	20.000	SFT
24	202-04089 SIGN, SHEET, REMOVE	1.000	EACH
25	203-02000 EXCAVATION, COMMON	130,627.000	CYS
26	203-02070 BORROW	230.000	CYS
27	203-06747 EXCAVATE	15,653.000	LFT
28	203-51223 EXCAVATION, WATERWAY	5,960.000	CYS
29	205-04948 TEMPORARY CONSTRUCTION ENTRANCE/EXIT	LUMP	LUMP
30	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	230.000	TON
31	205-06933 TEMPORARY DITCH INLET PROTECTION	12.000	EACH
32	205-06934 TEMPORARY MULCHING	100.000	TON
33	205-06936 TEMPORARY SEDIMENT TRAP	620.000	TON
34	205-06937 TEMPORARY SILT FENCE	2,900.000	LFT
35	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	883.000	CYS
36	206-96716 SHEET PILING, STEEL, S 1.9	600.000	SFT
37	210-05873 TESTING	LUMP	LUMP
38	210-07314 FORCE MAIN	325.000	LFT
39	210-07314 FORCE MAIN	175.000	LFT
40	211-02050 B BORROW	1,996.000	CYS
41	211-06467 AGGREGATE FOR END BENT BACKFILL	438.000	CYS
42	211-09264 STRUCTURE BACKFILL, TYPE 1	1,576.000	CYS
43	211-09266 STRUCTURE BACKFILL, TYPE 3	3,230.000	CYS
44	212-06282 STOCKPILED SELECTED MATERIAL, SALVAGED	137,000.000	CYS
45	215-07043 CHEMICAL MODIFICATION, SOILS	110,800.000	SYS
46	215-07706 CHEMICAL MODIFICATION, SOILS	6,872.000	TON
47	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,890.000	TON
48	302-06464 SUBBASE FOR PCCP	24,430.000	CYS

CALL ORDER : 171
 LETTING DATE :

CONTRACT ID : IR-29962-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
49	302-07455 DENSE GRADED SUBBASE	304.000	CYS
50	303-01180 COMPACTED AGGREGATE, NO. 53	21,040.000	TON
51	303-07449 COMPACTED AGGREGATE, NO. 73	18.000	TON
52	306-08043 MILLING, TRANSITION	585.000	SYS
53	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
54	401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm	3,730.000	TON
55	402-07432 HMA SURFACE, TYPE A	1,085.000	TON
56	402-07435 HMA INTERMEDIATE, TYPE A	1,740.000	TON
57	402-07440 HMA BASE, TYPE A	80.000	TON
58	406-05520 ASPHALT FOR TACK COAT	8.000	TON
59	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
60	501-06325 QC/QA-PCCP, 14 IN.	88,900.000	SYS
61	502-06999 PCCP, 8 IN.	315.000	SYS
62	503-05240 D-1 CONTRACTION JOINT	53,630.000	LFT
63	503-05310 TERMINAL JOINT	336.000	LFT
64	601-01522 GUARDRAIL TRANSITION TYPE TGB	12.000	EACH
65	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
66	601-05999 CURVED TERMINAL END	4.000	EACH
67	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
68	601-06416 IMPACT ATTENUATOR SPARE PARTS PACKAGE, ED, W1, TL-3	2.000	EACH
69	601-94689 GUARDRAIL END TREATMENT, OS	9.000	EACH
70	601-94690 GUARDRAIL END TREATMENT, MS	4.000	EACH
71	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	9.000	EACH
72	601-97803 GUARDRAIL END TREATMENT, MS, SPARE PARTS PACKAGE	4.000	EACH
73	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	3,562.500	LFT
74	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	1,100.000	LFT
75	602-06729 BARRIER DELINEATOR	52.000	EACH
76	603-06040 FENCE, FARM FIELD, 47 IN.	20,950.000	LFT
77	605-06095 CURB, INTEGRAL, B, CONCRETE	47.600	LFT
78	605-06145 CURB AND GUTTER, B, CONCRETE	85.000	LFT
79	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	38,970.000	LFT
80	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	278.800	SYS
81	609-06262 REINFORCED CONCRETE BRIDGE APPROACH, 14 IN.	1,033.200	SYS
82	615-06490 RIGHT OF WAY MARKER	39.000	EACH
83	615-06510 MONUMENT, C	14.000	EACH
84	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
85	616-02320 GEOTEXTILES	13,740.000	SYS
86	616-05688 RIPRAP, CLASS 1	10,034.000	TON
87	616-06405 RIPRAP, REVETMENT	571.700	TON
88	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
89	621-06545 FERTILIZER	26.000	TON
90	621-06553 SEED MIXTURE, R	11,050.000	LBS
91	621-06557 SEED MIXTURE, T	5,700.000	LBS
92	621-06565 MULCHING MATERIAL	130.000	TON
93	621-06567 WATER	2,900.000	KGAL
94	621-06574 SODDING	57,968.000	SYS
95	701-06011 DYNAMIC PILE LOAD TEST	3.000	EACH
96	701-06012 TEST PILE, RESTRIKE	3.000	EACH

CALL ORDER : 171
 LETTING DATE :

CONTRACT ID : IR-29962-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
97	701-06027 TEST PILE	4.000	EACH
98	701-08152 STATIC PILE LOAD TEST	1.000	EACH
99	701-91792 PILE TIP, STEEL H	65.000	EACH
100	701-95780 PILE, STEEL H, HP 12 X 74	2,635.000	LFT
101	702-51005 CONCRETE, A, SUBSTRUCTURE	83.400	CYS
102	702-51015 CONCRETE, B, FOOTINGS	33.800	CYS
103	702-51100 DRAIN PIPE, CAST IRON, 6 IN.	1,296.000	LBS
104	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	3,542.000	LBS
105	703-51030 REINFORCING STEEL	15,044.000	LBS
106	703-51032 REINFORCING STEEL, EPOXY COATED	433,977.000	LBS
107	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,367.300	CYS
108	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
109	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	16.000	EACH
110	706-51020 CONCRETE, C, RAILING	145.300	CYS
111	707-08492 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	1,060.000	LFT
112	707-08643 STRUCTURAL MEMBERS, CONCRETE BULB-T	950.000	LFT
113	707-09316 STRUCTURALMEMBERS, CONCRETE BULB-T BEAM,	1,140.000	LFT
114	707-09332 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	1,060.000	LFT
115	709-51821 SURFACE SEAL	LUMP	LUMP
116	709-51821 SURFACE SEAL	LUMP	LUMP
117	709-51821 SURFACE SEAL	LUMP	LUMP
118	709-51821 SURFACE SEAL	LUMP	LUMP
119	709-51821 SURFACE SEAL	LUMP	LUMP
120	715-02246 PIPE END SECTION, 48 IN.	5.000	EACH
121	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	238.000	LFT
122	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	138.000	LFT
123	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	39,222.000	LFT
124	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	4,814.000	LFT
125	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	60.000	LFT
126	715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN.	240.000	LFT
127	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	278.000	LFT
128	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	52.000	LFT
129	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN.	206.000	LFT
130	715-05162 PIPE, TYPE 2, CIRCULAR, 54 IN.	54.000	LFT
131	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	235.000	LFT
132	715-05219 PIPE, TYPE 5, CIRCULAR, 18 IN.	354.000	LFT
133	715-05407 PIPE, END BENT DRAIN, 6 IN.	810.000	LFT
134	715-05438 PIPE, DRAIN TILE TERMINAL SECTION, 4 IN.	1,565.000	LFT
135	715-05439 PIPE, DRAINTILE TERMINAL SECTION, 6 IN.	4,696.000	LFT
136	715-05440 PIPE, DRAINTILE TERMINAL SECTION, 8 IN.	1,565.000	LFT
137	715-05443 PIPE, DRAINTILE TERMINAL SECTION, 12 IN.	6,261.000	LFT
138	715-05445 PIPE, DRAIN TILE, TERMINAL SECTION, 18 IN.	480.000	LFT
139	715-05998 PIPE, TYPE 3, CIRCULAR, 8 IN.	4,696.000	LFT
140	715-06004 CONCRETE ANCHOR, 48 IN.	6.000	EACH
141	715-06492 CONCRETE ANCHOR, 54 IN.	2.000	EACH
142	715-26729 GRATED BOX END SECTION, II, 6:1, 15 IN.	2.000	EACH
143	715-26764 GRATED BOX END SECTION, II, 10:1, 18 IN.	2.000	EACH
144	715-46005 PIPE END SECTION, 15 IN.	8.000	EACH

CALL ORDER : 171
 LETTING DATE :

CONTRACT ID : IR-29962-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
145	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
146	715-46040 PIPE END SECTION, 36 IN.	4.000	EACH
147	715-96881 PIPE END SECTION, 54 IN.	1.000	EACH
148	715-97403 GRATED BOX END SECTION, I, 6:1, 15 IN.	4.000	EACH
149	715-97404 GRATED BOX END SECTION, I, 3:1, 15 IN.	4.000	EACH
150	718-06531 OUTLET PROTECTOR, 3	42.000	EACH
151	718-06531 OUTLET PROTECTOR, 3	8.000	EACH
152	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	6,500.000	LFT
153	718-52610 AGGREGATE FOR UNDERDRAINS	4,450.000	CYS
154	718-99153 GEOTEXTILES FOR UNDERDRAIN	40,802.000	SYS
155	720-03194 MANHOLE	16.000	EACH
156	720-08299 DROP INLET	7.000	EACH
157	731-93945 FACE PANELS, CONCRETE	5,723.000	SFT
158	731-93946 WALL ERECTION	5,723.000	SFT
159	731-93947 LEVELING PAD, CONCRETE	359.000	LFT
160	732-02745 GATE VALVE AND BOX, 8 IN.	2.000	EACH
161	801-04308 ROAD CLOSURE SIGN ASSEMBLY	10.000	EACH
162	801-06625 DETOUR ROUTE MARKER ASSEMBLY	23.000	EACH
163	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
164	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
165	801-07118 BARRICADE, III-A	120.000	LFT
166	801-07119 BARRICADE, III-B	120.000	LFT
167	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	51.000	LFT
168	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	11.000	SFT
169	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	25.000	SFT
170	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	21,005.000	LFT
171	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	21,005.000	LFT
172	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,850.000	LFT
173	808-75059 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	5,180.000	LFT
174	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4,385.000	LFT
175	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	285.000	EACH

CALL ORDER : 181
 LETTING DATE :

CONTRACT ID : IR-30250-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HOUSES AND BUILDINGS, REMOVE		
1 105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
2 105-09198	LAPTOP COMPUTER SYSTEM	3.000	MOS
3 105-09291	MOBILE BROADBAND ACCESS	3.000	MOS
4 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
5 205-06937	TEMPORARY SILT FENCE	200.000	LFT
6 621-06559	MULCHED SEEDING, R	500.000	SYS

CALL ORDER : 205
 LETTING DATE :

CONTRACT ID : R -28108-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	12.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	24.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	12.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
17	202-02240 PAVEMENT REMOVAL	402.000	m2
18	202-02241 GUARDRAIL, REMOVE	12.000	m
19	202-02271 HEADWALL, REMOVE	2.000	EACH
20	202-02278 CURB, CONCRETE, REMOVE	57.000	m
21	202-02279 CURB AND GUTTER, REMOVE	833.000	m
22	202-60815 CENTER CURB, REMOVE	356.000	m
23	202-74035 SIGN, REMOVE	13.000	EACH
24	202-74080 OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	1.000	EACH
25	202-91385 INLET, REMOVE	12.000	EACH
26	202-93047 MANHOLE, REMOVE	2.000	EACH
27	202-96133 PIPE, REMOVE	270.000	m
28	202-98488 PIPE END SECTION, REMOVE	2.000	EACH
29	203-02000 EXCAVATION, COMMON	3,410.000	m3
30	205-03371 SEDIMENT REMOVE	2.000	m3
31	205-06932 TEMPORARY CHECK DAM, STRAW BALES	14.000	m
32	205-06933 TEMPORARY DITCH INLET PROTECTION	4.000	EACH
33	205-06936 TEMPORARY SEDIMENT TRAP	19.300	Mg
34	205-06937 TEMPORARY SILT FENCE	348.000	m
35	207-08268 SUBGRADE TREATMENT, TYPE IV	3,549.000	m2
36	211-07454 STRUCTURE BACKFILL	960.000	m3
37	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	85.000	Mg
38	306-08036 MILLING, ASPHALT, 50 mm	12,774.000	m2
39	306-08043 MILLING, TRANSITION	1,884.000	m2
40	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	1,506.000	Mg
41	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	2,142.000	Mg
42	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	2,525.000	Mg
43	406-05520 ASPHALT FOR TACK COAT	12.000	Mg
44	605-06120 CURB, CONCRETE	88.000	m
45	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	765.000	m
46	605-06215 CENTER CURB, D, CONCRETE	702.000	m
47	605-94811 CURB TURNOUT	5.000	EACH
48	610-07486 HMA FOR APPROACHES, TYPE A	293.000	Mg

CALL ORDER : 205
 LETTING DATE :

CONTRACT ID : R -28108-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SMALL STRUCTURE REPLACEMENT			
49	610-08446 PCCP FOR APPROACHES, 150 mm	239.000	m2
50	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
51	615-06490 RIGHT OF WAY MARKER	22.000	EACH
52	615-06505 MONUMENT, B	3.000	EACH
53	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
54	616-02320 GEOTEXTILES	664.000	m2
55	616-06451 RIPRAP, UNIFORM	342.000	Mg
56	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
57	621-06560 MULCHED SEEDING, U	2,700.000	m2
58	621-06567 WATER	36.000	kL
59	621-06575 SODDING, NURSERY	1,972.000	m2
60	702-94656 CONCRETE, B	15.000	m3
61	714-08514 WINGWALL	92.000	m2
62	714-26726 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3600 mm x 2400 mm	50.000	m
63	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	294.000	m
64	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	23.000	m
65	715-05596 PIPE EXTENSION, CIRCULAR, 450 mm	1.800	m
66	715-05597 PIPE EXTENSION, CIRCULAR, 600 mm	1.000	m
67	715-05756 PIPE EXTENSION, CIRCULAR, 300 mm	26.000	m
68	715-05889 PIPE EXTENSION, CIRCULAR, 750 mm	1.800	m
69	715-08307 HMA FOR STRUCTURE INSTALLATION, TYPE D	18.000	Mg
70	715-09279 PIPE EXTENSION, CIRCULAR, 1350 mm	3.000	m
71	715-46000 PIPE END SECTION, 300 mm	3.000	EACH
72	715-46005 PIPE END SECTION, 375 mm	1.000	EACH
73	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
74	720-45030 INLET, E7	4.000	EACH
75	720-45045 INLET, J10	4.000	EACH
76	720-45055 INLET, M10	7.000	EACH
77	720-90984 MANHOLE, C2	3.000	EACH
78	720-96995 CLEAN INLET	1.000	EACH
79	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
80	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
81	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	5,395.000	m
82	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	53.000	m
83	801-06625 DETOUR ROUTE MARKER ASSEMBLY	34.000	EACH
84	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
85	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
86	801-06710 FLASHING ARROW SIGN	180.000	DAY
87	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
88	801-07118 BARRICADE, III-A	168.000	m
89	801-07119 BARRICADE, III-B	84.000	m
90	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
91	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	58.000	m
92	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	40.000	m
93	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
94	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	10.710	m2
95	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	3.380	m2
96	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	13.500	m2

CALL ORDER : 205
 LETTING DATE :

CONTRACT ID : R -28108-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
97	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	4.000	EACH
98	805-01842 HANDHOLE, SIGNAL	9.000	EACH
99	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	1.000	EACH
100	805-01893 MAINTAINING TRAFFIC SIGNAL	LUMP	LUMP
101	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
102	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	2,210.000	m
103	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	657.000	m
104	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
105	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	7.000	EACH
106	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER ARROW, GREEN	8.000	EACH
107	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	1.000	EACH
108	805-78245 TRAFFIC SIGNAL HEAD, OPTICALLY PROGRAMMED, 3 FACE, 305 mm	2.000	EACH
109	805-78255 TRAFFIC SIGNAL HEAD, OPTICALLY PROGRAMMED, 3 FACE, 305 mm	2.000	EACH
110	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
111	805-78420 DISCONNECT HANGER	5.000	EACH
112	805-78445 SIGNAL SERVICE	1.000	EACH
113	805-78467 SIGNAL CABLE, 3C 8GA.	20.000	m
114	805-78485 SIGNAL CABLE, 5C 14GA.	853.000	m
115	805-78490 SIGNAL CABLE, 7C 14GA.	70.000	m
116	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,266.000	m
117	805-78785 SIGNAL DETECTOR HOUSING	16.000	EACH
118	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	733.000	m
119	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
120	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
121	805-97114 CABLE, INTERCONNECT, 6 PAIR 19	80.000	m
122	808-04298 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (R X R)	9.000	EACH
123	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	308.000	m
124	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	879.000	m
125	808-06716 LINE, REMOVE	2,335.000	m
126	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	712.000	m
127	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	278.000	m
128	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	80.000	m
129	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	17.000	EACH
130	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	12.000	EACH
131	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	38.000	EACH
132	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	520.000	m
133	808-98796 LINE, THERMOPLASTIC, DOTTED, WHITE, 100 mm, 600 mm LINE,	107.000	m

CALL ORDER : 211
 LETTING DATE :

CONTRACT ID : R -28260-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PCCP PATCHING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	6.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	506-06333 PCCP PATCHING, FULL DEPTH	2,183.500	SYS
14	507-07505 RETROFIT LOAD TRANSFER	402.000	EACH
15	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
16	801-06640 CONSTRUCTION SIGN, A	70.000	EACH
17	801-06710 FLASHING ARROW SIGN	720.000	DAY
18	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
19	801-07215 TEMPORARY CHANGEABLE MESSAGE SIGN	720.000	DAY

CALL ORDER : 221
 LETTING DATE :

CONTRACT ID : R -28580-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	6.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	610.000	CYS
13	203-02070 BORROW	175.000	CYS
14	205-03371 SEDIMENT, REMOVE	61.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	18.000	TON
16	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
17	205-06936 TEMPORARY SEDIMENT TRAP	45.000	TON
18	205-06937 TEMPORARY SILT FENCE	350.000	LFT
19	207-08264 SUBGRADE TREATMENT, TYPE II	632.000	SYS
20	207-08267 SUBGRADE TREATMENT, TYPE IIIA	108.000	SYS
21	211-09264 STRUCTURE BACKFILL, TYPE 1	22.500	CYS
22	211-09268 STRUCTURE BACKFILL, TYPE 5	213.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	499.000	TON
24	303-04489 COMPACTED CRUSHED AGGREGATE, 8	41.000	TON
25	304-07492 WIDENING WITH HMA, TYPE A	13.000	TON
26	306-08042 MILLING, SCARIFICATION/PROFILE	1,184.000	SYS
27	306-08043 MILLING, TRANSITION	526.000	SYS
28	402-07432 HMA SURFACE, TYPE A	175.000	TON
29	402-07435 HMA INTERMEDIATE, TYPE A	56.000	TON
30	402-07440 HMA BASE, TYPE A	42.000	TON
31	402-07450 HMA WEDGE AND LEVEL, TYPE A	407.000	TON
32	406-05520 ASPHALT FOR TACK COAT	1.260	TON
33	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
34	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
36	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	256.250	LFT
37	610-07486 HMA FOR APPROACHES, TYPE A	30.000	TON
38	615-06505 MONUMENT, B	2.000	EACH
39	616-02320 GEOTEXTILES	473.000	SYS
40	616-05688 RIPRAP, CLASS 1	256.000	TON
41	616-06451 RIPRAP, UNIFORM	69.000	TON
42	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
43	621-01660 MULCHED SEEDING, LEGUME, 2	1,426.000	SYS
44	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	2,566.000	SYS
45	621-06559 MULCHED SEEDING, R	2,168.000	SYS
46	621-06567 WATER	1.600	KGAL
47	621-06574 SODDING	398.000	SYS
48	621-52448 SIGN, DO NOT SPRAY	8.000	EACH

CALL ORDER : 221
 LETTING DATE :

CONTRACT ID : R -28580-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
49	714-02168 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 16 FT. X 9 FT.	LUMP	LUMP
50	715-02407 SAFETY METAL END SECTION, 4:1, 48 IN.	2.000	EACH
51	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	68.000	LFT
52	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	115.000	LFT
53	715-05186 PIPE, TYPE 3, CIRCULAR, 48 IN.	34.000	LFT
54	715-05711 PIPE, SANITARY SEWER, 6 IN.	103.000	LFT
55	715-46010 PIPE END SECTION, 18 IN.	1.000	EACH
56	720-45035 INLET, F7	1.000	EACH
57	723-08608 WINGWALL	569.000	SFT
58	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
59	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
60	801-06625 DETOUR ROUTE MARKER ASSEMBLY	23.000	EACH
61	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
62	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
63	801-07118 BARRICADE, III-A	96.000	LFT
64	801-07119 BARRICADE, III-B	48.000	LFT
65	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	168.000	LFT
66	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	91.200	SFT
67	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	2,700.000	LFT
68	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	22,840.000	LFT
69	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	12,070.000	LFT

CALL ORDER : 231
 LETTING DATE :

CONTRACT ID : R -28678-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN TRAIL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	16.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	32.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	16.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-01405 CONTAMINATED SOIL, REMOVE AND DISPOSE	5,165.000	CYS
13	202-02240 PAVEMENT REMOVAL	113.400	SYS
14	202-02273 CENTER CURB, CONCRETE, REMOVE	20.700	SYS
15	202-06541 REMOVE	6.000	EACH
16	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
17	202-91840 FENCE, CHAIN LINK, REMOVE	690.000	LFT
18	202-96133 PIPE, REMOVE	40.000	LFT
19	205-06937 TEMPORARY SILT FENCE	1,560.000	LFT
20	206-51215 EXCAVATION, X	2.900	CYS
21	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	8.900	CYS
22	210-04181 BICYCLE RACK	11.000	EACH
23	210-06192 WALL	181.000	LFT
24	210-06276 FURNITURE	LUMP	LUMP
25	210-06276 FURNITURE	LUMP	LUMP
26	210-06276 FURNITURE	LUMP	LUMP
27	210-06547 PAINT	4.000	EACH
28	210-06749 INSTALL	95.000	LFT
29	210-06990 LIMESTONE	28.000	EACH
30	210-06990 LIMESTONE	4.000	EACH
31	210-07893 IRRIGATION	LUMP	LUMP
32	210-09249 POLE BANNER	21.000	EACH
33	211-07454 STRUCTURE BACKFILL	46.400	CYS
34	213-08058 FLOWABLE BACKFILL	280.100	CYS
35	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,250.000	TON
36	303-04489 COMPACTED CRUSHED AGGREGATE, 8	12.300	TON
37	303-04853 COMPACTED AGGREGATE	125.000	TON
38	303-06074 GRAVEL	128.000	TON
39	304-03768 SAND LEVELING COURSE	135.000	CYS
40	402-07432 HMA SURFACE, TYPE A	177.800	TON
41	402-07435 HMA INTERMEDIATE, TYPE A	358.500	TON
42	501-51112 ANCHOR BOLT	4.000	EACH
43	502-06457 PCCP, 9 IN.	113.400	SYS
44	601-03667 RAILING, ORNAMENTAL	353.000	LFT
45	601-06242 IMPACT ATTENUATOR, R2, W1, TL-2	2.000	EACH
46	601-95344 HANDRAIL, PEDESTRIAN	122.700	LFT
47	603-03692 FENCE, WOOD	10.000	LFT
48	603-03829 FENCE	705.000	LFT

CALL ORDER : 231
 LETTING DATE :

CONTRACT ID : R -28678-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN TRAIL		
49	604-04740 PAVERS	28,858.000	SFT
50	604-04740 PAVERS	321.400	SFT
51	604-04740 PAVERS	14,988.000	SFT
52	604-04740 PAVERS	9,073.000	SFT
53	604-04740 PAVERS	2,794.000	SFT
54	604-04740 PAVERS	366.800	SFT
55	604-04740 PAVERS	366.800	SFT
56	604-04740 PAVERS	366.800	SFT
57	604-04740 PAVERS	366.800	SFT
58	604-04740 PAVERS	504.000	SFT
59	604-07894 CURB RAMP, CONCRETE, A	35.000	SYS
60	604-07896 CURB RAMP, CONCRETE, B	65.600	SYS
61	604-07901 CURB RAMP, CONCRETE, G	31.600	SYS
62	604-07902 CURB RAMP, CONCRETE, H	12.600	SYS
63	604-07904 CURB RAMP, CONCRETE, L	30.100	SYS
64	604-08373 SIDEWALK	1,892.000	SYS
65	604-44251 STEPS, CONCRETE	13.000	CYS
66	604-90256 SIDEWALK, CONCRETE, 6 IN.	61.800	SYS
67	605-06120 CURB, CONCRETE	1,830.000	LFT
68	605-06120 CURB, CONCRETE	86.000	LFT
69	605-06255 CENTER CURB, D, CONCRETE	5.200	SYS
70	616-02320 GEOTEXTILES	4,448.000	SYS
71	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
72	619-95457 CLEAN AND PAINT STRUCTURAL STEEL	LUMP	LUMP
73	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
74	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
75	621-04978 SEED MIXTURE	744.000	SYS
76	621-04978 SEED MIXTURE	5,760.000	SYS
77	621-04978 SEED MIXTURE	1,730.000	SYS
78	621-06570 TOP SOIL	2,074.000	CYS
79	621-06570 TOP SOIL	420.200	CYS
80	621-98038 MULCH, HARDWOOD SHREDDED BARK	118.000	CYS
81	622-03948 PLANTER	23.000	EACH
82	622-04648 TREE GRATE	4.000	EACH
83	622-04990 LANDSCAPE EDGING	3,730.000	LFT
84	622-04992 DRAIN	181.000	EACH
85	622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	130.000	EACH
86	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	41.000	EACH
87	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	44.000	EACH
88	622-05653 PLANT, GROUND COVER	15,831.000	EACH
89	702-51005 CONCRETE, A, SUBSTRUCTURE	40.800	CYS
90	702-51863 FIELD DRILLED HOLE IN CONCRETE	106.000	EACH
91	702-51864 FIELD DRILLED HOLE	2.000	EACH
92	702-90915 CONCRETE, A	30.000	CYS
93	703-03489 TIE BAR, RETROFIT	90.000	EACH
94	703-51030 REINFORCING STEEL	2,459.000	LBS
95	706-92237 HANDRAIL, STEEL	64.000	LFT
96	707-03917 PRESTRESSED STEEL, WIRE OR STRAND	1,016.000	LBS

CALL ORDER : 231
 LETTING DATE :

CONTRACT ID : R -28678-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN TRAIL		
97	709-07733 ANTI-GRAFFITI COAT	LUMP	LUMP
98	711-51038 STRUCTURAL STEEL	LUMP	LUMP
99	712-03812 BENCH	42.000	EACH
100	715-03420 FILL, SAND	113.000	CYS
101	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	331.000	LFT
102	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	150.000	LFT
103	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	228.000	LFT
104	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	538.000	LFT
105	715-08282 HMA FOR STRUCTURE INSTALLATION, TYPE A	51.000	TON
106	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
107	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000	EACH
108	720-44296 CAP INLET	4.000	EACH
109	720-45030 INLET, E7	3.000	EACH
110	720-45035 INLET, F7	5.000	EACH
111	720-93409 INLET, B15, MODIFIED	1.000	EACH
112	720-93411 INLET, C15, MODIFIED	4.000	EACH
113	720-98174 INLET, B15	1.000	EACH
114	720-98555 INLET, C15	1.000	EACH
115	732-04751 WATER SERVICE	5.000	EACH
116	801-06624 STANDARD BARRICADE, IIIB, WITH SIGNS	14.000	EACH
117	801-06640 CONSTRUCTION SIGN, A	62.000	EACH
118	801-06710 FLASHING ARROW SIGN	60.000	DAY
119	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
120	802-03896 BOLLARD	14.000	EACH
121	802-03896 BOLLARD	6.000	EACH
122	802-04314 SIGN	2.000	EACH
123	802-04314 SIGN	9.000	EACH
124	802-04314 SIGN	2.000	EACH
125	802-04314 SIGN	40.000	EACH
126	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	136.500	LFT
127	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	81.250	SFT
128	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	100.500	SFT
129	805-08093 POLE	8.000	EACH
130	805-08093 POLE	4.000	EACH
131	805-08093 POLE	4.000	EACH
132	805-08093 POLE	19.000	EACH
133	805-08093 POLE	14.000	EACH
134	805-86810 SERVICE POINT, II	7.000	EACH
135	805-86900 JUNCTION BOX	1.000	EACH
136	805-86930 INSULATING LINK, NOT WATERPROOFED	98.000	EACH
137	805-90697 COMPRESSION CONNECTORS	102.000	EACH
138	805-91703 CONDUIT, STEEL, GALVANIZED, 1.5 IN.	226.000	LFT
139	805-94971 FIBER OPTICS CABLE	7,932.000	LFT
140	805-95889 WIRE, NO. 10 COPPER, 1C	15,790.000	LFT
141	805-96014 SAW CUT, FULL DEPTH	1,060.000	LFT
142	807-02191 HANDHOLE, LIGHTING	19.000	EACH
143	807-02819 LIGHTING RECEPTACLE, SINGLE, WATERPROOF	10.000	EACH
144	807-02819 LIGHTING RECEPTACLE, SINGLE, WATERPROOF	10.000	EACH

CALL ORDER : 231
 LETTING DATE :

CONTRACT ID : R -28678-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN TRAIL		
145	807-02819 LIGHTING RECEPTACLE, SINGLE, WATERPROOF	12.000	EACH
146	807-03051 LIGHT CABLE, 1C 10GA.	945.000	LFT
147	807-04651 WIRE	1,425.000	LFT
148	807-04651 WIRE	345.000	LFT
149	807-04651 WIRE	7,600.000	LFT
150	807-04651 WIRE	896.000	LFT
151	807-04651 WIRE	5,524.000	LFT
152	807-08469 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING,	43.000	EACH
153	807-78590 HANDHOLE	13.000	EACH
154	807-86910 CONNECTOR KIT, UNFUSED	49.000	EACH
155	807-86915 CONNECTOR KIT, FUSED	49.000	EACH
156	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	24.000	EACH
157	807-86935 INSULATION LINK, WATERPROOFED	68.000	EACH
158	807-87556 WIRE, THW OR TW, NO. 10 COPPER STRANDED	345.000	LFT
159	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	12.000	EACH
160	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	12.000	EACH
161	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	534.000	LFT

CALL ORDER : 241
 LETTING DATE :

CONTRACT ID : R -28818-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	12.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	36.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	12.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-01874 SHEET SIGN AND POST, REMOVE	2.000	EACH
16	202-02241 GUARDRAIL, REMOVE	9,686.000	LFT
17	202-02272 PAVED SIDE DITCH, REMOVE	2,860.000	LFT
18	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
19	202-96022 CONCRETE FOUNDATION, REMOVE	2.000	EACH
20	203-02000 EXCAVATION, COMMON	6,190.000	CYS
21	203-02070 BORROW	786.000	CYS
22	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	250.000	TON
23	205-06937 TEMPORARY SILT FENCE	8,000.000	LFT
24	207-08263 SUBGRADE TREATMENT, TYPE IA	10,397.000	SYS
25	211-07454 STRUCTURE BACKFILL	20.000	CYS
26	303-01180 COMPACTED AGGREGATE, NO. 53	21,260.000	TON
27	304-07490 HMA PATCHING, TYPE B	200.000	TON
28	306-08033 MILLING, ASPHALT, 1 IN.	26,879.000	SYS
29	306-08043 MILLING, TRANSITION	22,143.000	SYS
30	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
31	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	7,288.000	TON
32	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	33,981.000	TON
33	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	15,822.000	TON
34	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	293.000	TON
35	401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm	96.000	TON
36	401-09056 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm-PWL	63,851.000	TON
37	401-93793 WEDGE AND LEVELING	1,379.000	TON
38	406-05520 ASPHALT FOR TACK COAT	108.000	TON
39	503-05240 D-1 CONTRACTION JOINT	1,164.000	LFT
40	506-06333 PCCP PATCHING, FULL DEPTH	5,721.000	SYS
41	601-06242 IMPACT ATTENUATOR, R2, W1, TL-2	2.000	EACH
42	601-06294 IMPACT ATTENUATOR, RESET, ED, W1, TL-3	8.000	EACH
43	601-94689 GUARDRAIL END TREATMENT, OS	18.000	EACH
44	601-94690 GUARDRAIL END TREATMENT, MS	7.000	EACH
45	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	8,249.250	LFT
46	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	2,331.250	LFT
47	601-99123 GUARDRAIL TRANSITION, GP	9.000	EACH
48	606-07484 MILLED HMA SHOULDER CORRUGATIONS	141,251.000	LFT

CALL ORDER : 241
 LETTING DATE :

CONTRACT ID : R -28818-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
49	616-02320 GEOTEXTILES	5,176.000	SYS
50	616-06025 BORROW, COHESIVE	1,284.000	CYS
51	616-06405 RIPRAP, REVETMENT	3,885.000	TON
52	621-06559 MULCHED SEEDING, R	53,869.000	SYS
53	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	1.000	EACH
54	715-03584 SAFETY METAL END SECTION, 4:1, 18 IN.	2.000	EACH
55	715-05218 PIPE, TYPE 5, CIRCULAR, 15 IN.	10.000	LFT
56	715-05219 PIPE, TYPE 5, CIRCULAR, 18 IN.	48.000	LFT
57	715-08452 SAFETY METAL END SECTION, 4:1, 34 IN. X 22 IN.	1.000	EACH
58	715-09321 PIPE, TYPE, DEFORMED, MIN. AREA 4.5 SQ. FT.	10.000	LFT
59	715-96881 PIPE END SECTION, 54 IN.	1.000	EACH
60	718-06529 OUTLET PROTECTOR, 2	56.000	EACH
61	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
62	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
63	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	27,366.000	LFT
64	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	82,098.000	LFT
65	801-06640 CONSTRUCTION SIGN, A	80.000	EACH
66	801-06710 FLASHING ARROW SIGN	500.000	DAY
67	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
68	804-04435 DELINEATOR POST, REMOVE	200.000	EACH
69	804-06771 DELINEATOR POST, FLEXIBLE	200.000	EACH
70	805-01842 HANDHOLE, SIGNAL	2.000	EACH
71	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	35.000	EACH
72	805-02441 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	14,529.000	LFT
73	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	635.000	LFT
74	805-78467 SIGNAL CABLE, 3C 8GA.	635.000	LFT
75	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	4,664.000	LFT
76	805-95466 FLASHING BEACON WITH SIGNAL AHEAD SIGN, 6 IN. I BEAM AND	2.000	EACH
77	807-02200 BREAKAWAY COUPLINGS WITH COVER, INSTALL	4.000	SET
78	807-98690 HANDHOLE ADJUSTED TO GRADE	10.000	EACH
79	808-01428 TEMPORARY TRANSVERSE MARKINGS, WHITE, STOP LINE, 24 IN.	568.000	LFT
80	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	27,366.000	LFT
81	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	101,829.000	LFT
82	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	14,813.000	LFT
83	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	568.000	LFT
84	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	95,897.000	LFT
85	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	3,645.000	LFT
86	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	285.000	LFT
87	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	568.000	LFT
88	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	35.000	EACH
89	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	20.000	EACH
90	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,700.000	EACH
91	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,700.000	EACH
92	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	725.000	LFT

CALL ORDER : 245
 LETTING DATE :

CONTRACT ID : R -28930-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	24.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	96.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	24.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	24.000	MOS
8	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
9	109-08359 LIQUIDATED DAMAGES	1.000	DOL
10	109-08360 CONTRACT LIENS	1.000	DOL
11	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
12	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
13	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
14	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
15	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
16	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
17	202-02278 CURB, CONCRETE, REMOVE	136.500	m
18	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
19	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
20	202-96133 PIPE, REMOVE	184.300	m
21	203-02000 EXCAVATION, COMMON	59,024.000	m3
22	203-02070 BORROW	10,661.000	m3
23	203-02100 EXCAVATION, PEAT	10,229.000	m3
24	203-90014 LINEAR GRADING	1.050	STA
25	205-03371 SEDIMENT REMOVE	4,500.000	m3
26	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	228.000	Mg
27	205-06936 TEMPORARY SEDIMENT TRAP	400.000	Mg
28	205-06937 TEMPORARY SILT FENCE	3,764.000	m
29	207-08262 SUBGRADE TREATMENT, TYPE I	61,707.000	m2
30	207-08263 SUBGRADE TREATMENT, TYPE IA	12,524.000	m2
31	207-08267 SUBGRADE TREATMENT, TYPE IIIA	7,467.000	m2
32	211-02050 B BORROW	4.000	m3
33	211-07454 STRUCTURE BACKFILL	932.200	m3
34	213-08058 FLOWABLE BACKFILL	24.000	m3
35	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	11,641.600	Mg
36	303-07449 COMPACTED AGGREGATE, NO. 73	1,475.000	Mg
37	306-08033 MILLING, ASPHALT, 25 mm	35,819.000	m2
38	306-08034 MILLING, ASPHALT, 38 mm	501.000	m2
39	306-08043 MILLING, TRANSITION	1,032.120	m2
40	306-08432 MILLING, APPROACH	900.000	m2
41	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
42	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	4,905.220	Mg
43	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	4,157.000	Mg
44	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	3,000.000	Mg
45	401-07363 QC/QA-HMA, 4, 70, INTERMEDIATE, 9.5 mm	3,000.000	Mg
46	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	6,227.900	Mg
47	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 MM	6,705.560	Mg
48	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	5,402.800	Mg

CALL ORDER : 245
 LETTING DATE :

CONTRACT ID : R -28930-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	5,745.830	Mg
50	401-09336 QC/QA-HMA, 3, 64, BASE, 19.0 mm-PWL	10,729.090	Mg
51	402-07432 HMA SURFACE, TYPE A	438.970	Mg
52	402-07435 HMA INTERMEDIATE, TYPE A	731.610	Mg
53	402-07451 HMA WEDGE AND LEVEL, TYPE B	471.100	Mg
54	406-05520 ASPHALT FOR TACK COAT	106.200	Mg
55	601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION	2.000	EACH
56	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	7.620	m
57	603-06040 FENCE, FARM FIELD, 1190 mm	150.000	m
58	605-06120 CURB, CONCRETE	215.100	m
59	605-94811 CURB TURNOUT	2.000	EACH
60	607-06385 PAVED SIDE DITCH, L	23.000	m
61	610-07486 HMA FOR APPROACHES, TYPE A	890.000	Mg
62	610-07487 HMA FOR APPROACHES, TYPE B	433.200	Mg
63	610-08446 PCCP FOR APPROACHES, 150 mm	63.350	m2
64	610-09108 PCCP FOR APPROACHES, 225 mm	426.640	m2
65	611-06497 MAILBOX ASSEMBLY, SINGLE	10.000	EACH
66	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	1.000	Mg
67	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
68	612-60410 DRILLED HOLE FOR UNDERSEAL	17.000	EACH
69	615-06490 RIGHT OF WAY MARKER	116.000	EACH
70	615-06505 MONUMENT, B	16.000	EACH
71	615-06510 MONUMENT, C	1.000	EACH
72	615-06527 MONUMENT, SECTION CORNER	6.000	EACH
73	616-02320 GEOTEXTILES	648.700	m2
74	616-06405 RIPRAP, REVETMENT	125.300	Mg
75	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
76	621-06545 FERTILIZER	9.000	Mg
77	621-06553 SEED MIXTURE, R	1,900.000	kg
78	621-06565 MULCHING MATERIAL	45.000	Mg
79	621-06567 WATER	100.000	kL
80	621-06574 SODDING	15,680.000	m2
81	621-06575 SODDING, NURSERY	4,309.000	m2
82	622-52436 SIGN, DO NOT MOW OR SPRAY	20.000	EACH
83	622-98200 SIGN, DO NOT DISTURB	21.000	EACH
84	715-02628 SAFETY METAL END SECTION, 6:1, 375 mm	14.000	EACH
85	715-03476 SAFETY METAL END SECTION, 4:1, 600 mm	1.000	EACH
86	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	6,284.900	m
87	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	662.700	m
88	715-05118 PIPE, TYPE 1, CIRCULAR, 300 mm	45.000	m
89	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	99.500	m
90	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	49.300	m
91	715-05123 PIPE, TYPE 1, CIRCULAR, 600 mm	78.200	m
92	715-05128 PIPE, TYPE 1, CIRCULAR, 1200 mm	38.500	m
93	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	44.000	m
94	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	107.200	m
95	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	69.100	m
96	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	189.400	m

CALL ORDER : 245
 LETTING DATE :

CONTRACT ID : R -28930-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
97	715-05171 PIPE, TYPE 3, CIRCULAR, 450 mm	125.700	m
98	715-05233 PIPE, TYPE 1, DEFORMED, MIN. AREA 0.31 m2	26.700	m
99	715-05331 PIPE, TYPE 2, DEFORMED, MIN. AREA 0.31 m2	23.000	m
100	715-06004 CONCRETE ANCHOR, 1200 mm	2.000	EACH
101	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	37.000	Mg
102	715-26764 GRATED BOX END SECTION, II, 10:1, 450 mm	2.000	EACH
103	715-26808 GRATED BOX END SECTION, I, 4:1, 700 mm x 500 mm	2.000	EACH
104	715-46000 PIPE END SECTION, 300 mm	1.000	EACH
105	715-46005 PIPE END SECTION, 375 mm	21.000	EACH
106	715-46010 PIPE END SECTION, 450 mm	2.000	EACH
107	715-46020 PIPE END SECTION, 600 mm	3.000	EACH
108	715-97402 GRATED BOX END SECTION, I, 4:1, 375 mm	2.000	EACH
109	715-97687 GRATED BOX END SECTION, I, 4:1, 600 mm	4.000	EACH
110	715-97836 GRATED BOX END SECTION, II, 4:1, 375 mm	2.000	EACH
111	715-99044 GRATED BOX END SECTION, II, 6:1, 450 mm	12.000	EACH
112	718-06528 OUTLET PROTECTOR, 1	22.000	EACH
113	718-06529 OUTLET PROTECTOR, 2	12.000	EACH
114	718-06531 OUTLET PROTECTOR, 3	7.000	EACH
115	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
116	718-52610 AGGREGATE FOR UNDERDRAINS	1,326.200	m3
117	720-45015 INLET, A8	4.000	EACH
118	720-45030 INLET, E7	1.000	EACH
119	720-45070 INLET, P12A	1.000	EACH
120	720-45410 MANHOLE, C4	2.000	EACH
121	720-95422 MANHOLE, J4	2.000	EACH
122	720-98555 INLET, C15	3.000	EACH
123	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
124	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
125	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	6,244.000	m
126	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	2,470.000	m
127	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	14.400	m
128	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 600 mm	14.400	m
129	801-06625 DETOUR ROUTE MARKER ASSEMBLY	22.000	EACH
130	801-06640 CONSTRUCTION SIGN, A	81.000	EACH
131	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
132	801-07118 BARRICADE, III-A	187.200	m
133	801-07119 BARRICADE, III-B	36.000	m
134	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
135	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	50.400	m
136	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	148.300	m
137	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	35.000	m
138	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	11.088	m2
139	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	25.776	m2
140	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	5.625	m2
141	802-91122 SIGN, GROUND MOUNTED, RESET	2.000	EACH
142	804-76350 DELINEATOR WITH POST, D3, 75 mm DIA.	2.000	EACH
143	805-01842 HANDHOLE, SIGNAL	11.000	EACH
144	805-01893 MAINTAINING TRAFFIC SIGNAL	LUMP	LUMP

CALL ORDER : 245
 LETTING DATE :

CONTRACT ID : R -28930-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
145	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	647.700	m
146	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,471.800	m
147	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,024.900	m
148	805-78785 SIGNAL DETECTOR HOUSING	14.000	EACH
149	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	504.900	m
150	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	7.000	EACH
151	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	8,354.100	m
152	808-06712 LINE, PAINT, BROKEN, YELLOW, 100 mm	200.000	m
153	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	9,130.000	m
154	808-06714 LINE, PAINT, SOLID, YELLOW, 100 mm	12,000.000	m
155	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	704.000	m
156	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	6,001.200	m
157	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	86.600	m
158	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	86.100	m
159	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
160	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH
161	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	682.000	EACH
162	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	899.000	EACH
163	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	173.400	m

CALL ORDER : 251
 LETTING DATE :

CONTRACT ID : R -28944-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT AND WIDENING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	48.000	MOS
3	108-09283 CPM SCHEDULE	LUMP	LUMP
4	108-09284 CPM SCHEDULE, MONTHLY UPDATE	2.000	EACH
5	108-09285 CPM SCHEDULE, REVISED	4.000	EACH
6	109-08359 LIQUIDATED DAMAGES	1.000	DOL
7	109-08360 CONTRACT LIENS	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	592.000	m2
14	202-02241 GUARDRAIL, REMOVE	856.000	m
15	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	202-51368 SLOPEWALL, REMOVE	36.000	m2
18	203-02000 EXCAVATION, COMMON	5,645.000	m3
19	205-06932 TEMPORARY CHECK DAM, STRAW BALES	393.000	m
20	205-06933 TEMPORARY DITCH INLET PROTECTION	7.000	EACH
21	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	494.000	m3
22	207-08263 SUBGRADE TREATMENT, TYPE IA	8,315.000	m2
23	211-06467 AGGREGATE FOR END BENT BACKFILL	46.000	m3
24	213-52830 FLOWABLE MORTAR	16.000	m3
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,480.000	Mg
26	302-07455 DENSE GRADED SUBBASE	172.800	m3
27	306-08033 MILLING, ASPHALT, 25 mm	2,678.000	m2
28	402-07434 HMA SURFACE, TYPE C	1,479.000	Mg
29	402-07439 HMA INTERMEDIATE, TYPE C	1,153.000	Mg
30	402-07442 HMA BASE, TYPE C	3,992.000	Mg
31	402-07452 HMA WEDGE AND LEVEL, TYPE C	987.000	Mg
32	406-05520 ASPHALT FOR TACK COAT	2.400	Mg
33	601-01522 GUARDRAIL TRANSITION TYPE TGB	12.000	EACH
34	601-94690 GUARDRAIL END TREATMENT, MS	4.000	EACH
35	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	215.000	m
36	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 1.905 m SPACING	432.000	m
37	602-06729 BARRIER DELINEATOR	204.000	EACH
38	606-07484 MILLED HMA SHOULDER CORRUGATIONS	2,083.000	m
39	609-06263 REINFORCED CONCRETE BRIDGE APPROACH, 375 mm	343.000	m2
40	610-06263 REINFORCED CONCRETE BRIDGE APPROACH, 375 mm	362.400	m2
41	610-52817 TEMPORARY CROSSOVER, B	2.000	EACH
42	616-02320 GEOTEXTILES	387.000	m2
43	616-06405 RIPRAP, REVETMENT	540.000	Mg
44	616-06406 RIPRAP, REVETMENT	255.000	m2
45	616-06451 RIPRAP, UNIFORM	61.000	Mg
46	616-51366 SLOPEWALL, CONCRETE, 125 mm	36.000	m2
47	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.000	EACH
48	621-06545 FERTILIZER	0.700	Mg

CALL ORDER : 251
 LETTING DATE :

CONTRACT ID : R -28944-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT AND WIDENING		
49	621-06553 SEED MIXTURE, R	130.000	kg
50	621-06565 MULCHING MATERIAL	3.100	Mg
51	701-03753 PILE, CONCRETE, STEEL SHELL ENCASED, 5.31 mm, 356 mm	665.000	m
52	702-51005 CONCRETE, A, SUBSTRUCTURE	527.000	m3
53	702-51015 CONCRETE, B, FOOTINGS	87.000	m3
54	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	6,968.000	kg
55	702-51863 FIELD DRILLED HOLE IN CONCRETE	1,456.000	EACH
56	703-06029 REINFORCING BARS, EPOXY COATED	620,094.000	kg
57	703-51032 REINFORCING STEEL, EPOXY COATED	161,154.000	kg
58	704-51002 CONCRETE, C, SUPERSTRUCTURE	3,884.200	m3
59	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	16.000	EACH
60	706-51020 CONCRETE, C, RAILING	890.400	m3
61	709-51821 SURFACE SEAL	LUMP	LUMP
62	709-51821 SURFACE SEAL	LUMP	LUMP
63	710-09158 PATCHING CONCRETE STRUCTURES	4.500	m2
64	711-01786 STRUCTURAL STEEL DRILLING, 25 mm DIA. HOLE	170.000	EACH
65	711-09138 STRUCTURAL STEEL DRILLING, 13 mm, DIA. HOLE	1,472.000	EACH
66	711-51038 STRUCTURAL STEEL	LUMP	LUMP
67	711-51038 STRUCTURAL STEEL	LUMP	LUMP
68	711-51867 STRUCTURAL STEEL CUTTING	1,297,000.000	mm2
69	711-95290 FIELD WELDING	65.000	m
70	711-95291 SUPPORTING STEEL BEAMS	LUMP	LUMP
71	711-96479 BOLT, REMOVE	1,281.000	EACH
72	711-96800 STUD SHEAR CONNECTOR	40,296.000	EACH
73	715-26729 GRATED BOX END SECTION, II, 6:1, 375 mm	2.000	EACH
74	715-91361 PIPE, PVC, 150 mm	152.400	m
75	724-51925 STRUCTURAL EXPANSION JOINT, SS	125.800	m
76	724-51927 EXPANSION JOINT, M	24.600	m
77	726-92406 BEARING ASSEMBLY, ELASTOMERIC	96.000	EACH
78	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
79	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	16,567.000	m
80	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
81	801-06645 CONSTRUCTION SIGN, B	18.000	EACH
82	801-06710 FLASHING ARROW SIGN	1,400.000	DAY
83	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
84	801-07118 BARRICADE, III-A	22.000	m
85	801-07119 BARRICADE, III-B	24.000	m
86	801-07606 TEMPORARY CROSSOVER DRAINAGE PIPE	303.000	m
87	801-08400 TEMPORARY TRAFFIC BARRIER,, TYPE 1	1,323.000	m
88	801-08507 TEMPORARY TRAFFIC BARRIER, TYPE 1, ANCHORED	813.000	m
89	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	1,512.000	m
90	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	1,512.000	m
91	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 125 mm	1,149.000	m
92	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	2,357.000	m
93	808-06716 LINE, REMOVE	7,351.000	m
94	808-74811 LINE, EPOXY, BROKEN, WHITE, 125 mm	378.000	m
95	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	2,641.000	m
96	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	253.000	EACH

CALL ORDER : 261
 LETTING DATE :

CONTRACT ID : R -28955-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	24.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	6.000	EACH
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	105-09198 LAPTOP COMPUTER SYSTEM	48.000	MOS
6	105-09199 FIELD OFFICE INTERNET SERVICE	24.000	MOS
7	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
8	108-09283 CPM SCHEDULE	LUMP	LUMP
9	108-09284 CPM SCHEDULE, MONTHLY UPDATE	24.000	EACH
10	108-09285 CPM SCHEDULE, REVISED	12.000	EACH
11	109-08359 LIQUIDATED DAMAGES	1.000	DOL
12	109-08360 CONTRACT LIENS	1.000	DOL
13	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
14	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
15	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
16	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
17	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
18	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
19	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
20	202-02240 PAVEMENT REMOVAL	51,412.000	SYS
21	202-02241 GUARDRAIL, REMOVE	10,378.500	LFT
22	202-02272 PAVED SIDE DITCH, REMOVE	7,774.000	LFT
23	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
24	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
25	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
26	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
27	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
28	202-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	55.000	EACH
29	202-74050 SIGN, OVERHEAD, REMOVE	13.000	EACH
30	202-74085 OVERHEAD SIGN STRUCTURE, TWIN CANTILEVER, REMOVE	4.000	EACH
31	202-74095 BRIDGE BRACKET ASSEMBLY, REMOVE	3.000	EACH
32	202-91385 INLET, REMOVE	4.000	EACH
33	202-99187 FENCE, FARM FIELD, REMOVE	10,296.000	LFT
34	203-02000 EXCAVATION, COMMON	71,208.000	CYS
35	203-08607 LINEAR GRADING	144,171.000	LFT
36	203-91878 LINEAR DITCH GRADING	2,000.000	LFT
37	205-03371 SEDIMENT, REMOVE	2,532.000	CYS
38	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,197.000	TON
39	205-06932 TEMPORARY CHECK DAM, STRAW BALES	108.000	LFT
40	205-06933 TEMPORARY DITCH INLET PROTECTION	55.000	EACH
41	205-06934 TEMPORARY MULCHING	74.000	TON
42	205-06937 TEMPORARY SILT FENCE	163,474.000	LFT
43	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	82.000	CYS
44	207-08263 SUBGRADE TREATMENT, TYPE IA	53.000	SYS
45	207-08267 SUBGRADE TREATMENT, TYPE IIIA	93,987.000	SYS
46	211-02050 B BORROW	89.000	CYS
47	211-07454 STRUCTURE BACKFILL	82.000	CYS
48	211-09264 STRUCTURE BACKFILL, TYPE 1	79.000	CYS

CALL ORDER : 261
 LETTING DATE :

CONTRACT ID : R -28955-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
49	213-08058 FLOWABLE BACKFILL	36.000	CYS
50	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,328.400	TON
51	302-07455 DENSE GRADED SUBBASE	209.000	CYS
52	306-08033 MILLING, ASPHALT, 1 IN.	771.100	SYS
53	306-08041 MILLING, PCCP	15,973.670	SYS
54	306-08043 MILLING, TRANSITION	13,521.300	SYS
55	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
56	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	15,681.000	TON
57	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	39,628.400	TON
58	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	54,325.200	TON
59	401-09056 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm-PWL	171,375.400	TON
60	402-07433 HMA SURFACE, TYPE B	6,852.000	TON
61	402-07434 HMA SURFACE, TYPE C	64.000	TON
62	402-07438 HMA INTERMEDIATE, TYPE B	11,587.000	TON
63	402-07439 HMA INTERMEDIATE, TYPE C	4.000	TON
64	402-07441 HMA BASE, TYPE B	46,426.000	TON
65	402-07442 HMA BASE, TYPE C	13.000	TON
66	406-05520 ASPHALT FOR TACK COAT	261.000	TON
67	506-06333 PCCP PATCHING, FULL DEPTH	52,739.000	SYS
68	601-01522 GUARDRAIL TRANSITION TYPE TGB	21.000	EACH
69	601-02205 TEMPORARY GUARD RAIL TRANSITION, TGB	4.000	EACH
70	601-02206 TEMPORARY GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,300.000	LFT
71	601-05999 CURVED TERMINAL END	20.000	EACH
72	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	3.000	EACH
73	601-07661 GUARDRAIL END TREATMENT, OS, TEMPORARY BRIDGE APPROACH	4.000	EACH
74	601-94689 GUARDRAIL END TREATMENT, OS	35.000	EACH
75	601-94690 GUARDRAIL END TREATMENT, MS	6.000	EACH
76	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	18,756.250	LFT
77	601-99106 GUARDRAIL, W BEAM, 3 FT. 1.5 IN. SPACING	75.000	LFT
78	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	1,225.000	LFT
79	601-99123 GUARDRAIL TRANSITION, GP	8.000	EACH
80	602-06729 BARRIER DELINEATOR	84.000	EACH
81	603-06040 FENCE, FARM FIELD, 47 IN.	10,296.000	LFT
82	605-05523 CURB, HMA	915.000	LFT
83	606-07484 MILLED HMA SHOULDER CORRUGATIONS	590,090.000	LFT
84	607-06335 PAVED SIDE DITCH, A	1,105.000	LFT
85	607-06340 PAVED SIDE DITCH, B	2,628.000	LFT
86	607-06345 PAVED SIDE DITCH, C	2,180.000	LFT
87	607-06350 PAVED SIDE DITCH, D	379.000	LFT
88	607-06355 PAVED SIDE DITCH, E	958.000	LFT
89	607-06360 PAVED SIDE DITCH, F	296.000	LFT
90	607-06365 PAVED SIDE DITCH, G	220.000	LFT
91	607-06370 PAVED SIDE DITCH, H	20.000	LFT
92	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	1,210.000	SYS
93	610-03393 TEMPORARY CROSSOVER, B MODIFIED	1.000	EACH
94	610-52817 TEMPORARY CROSSOVER, B	1.000	EACH
95	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	34.700	TON
96	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH

CALL ORDER : 261
 LETTING DATE :

CONTRACT ID : R -28955-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
97	612-60410 DRILLED HOLE FOR UNDERSEAL	578.000	EACH
98	615-06520 MONUMENT, RE-ESTABLISH	1.000	EACH
99	616-02305 GABIONS	150.000	CYS
100	616-02320 GEOTEXTILES	5,344.000	SYS
101	616-06405 RIPRAP, REVETMENT	15.000	TON
102	616-06451 RIPRAP, UNIFORM	19,084.000	TON
103	619-91969 CLEAN UNDERDRAIN OUTLET	17.000	EACH
104	619-95457 CLEAN AND PAINT STRUCTURAL STEEL	LUMP	LUMP
105	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	11.000	EACH
106	621-02770 EROSION CONTROL BLANKET	5,000.000	SYS
107	621-06545 FERTILIZER	77.000	TON
108	621-06553 SEED MIXTURE, R	24,557.000	LBS
109	621-06557 SEED MIXTURE, T	8,719.000	LBS
110	621-06565 MULCHING MATERIAL	361.000	TON
111	621-06567 WATER	53.100	KGAL
112	621-06574 SODDING	41,662.700	SYS
113	622-52436 SIGN, DO NOT MOW OR SPRAY	6.000	EACH
114	622-91786 SEEDLING	680.000	EACH
115	702-51005 CONCRETE, A, SUBSTRUCTURE	12.300	CYS
116	702-51863 FIELD DRILLED HOLE IN CONCRETE	2,524.000	EACH
117	703-51032 REINFORCING STEEL, EPOXY COATED	110,610.000	LBS
118	704-51002 CONCRETE, C, SUPERSTRUCTURE	133.100	CYS
119	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	16.000	EACH
120	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	8.000	EACH
121	706-51025 CONCRETE, C, RAILING	1,789.000	LFT
122	709-51821 SURFACE SEAL	LUMP	LUMP
123	709-51821 SURFACE SEAL	LUMP	LUMP
124	709-51821 SURFACE SEAL	LUMP	LUMP
125	709-51821 SURFACE SEAL	LUMP	LUMP
126	709-51821 SURFACE SEAL	LUMP	LUMP
127	710-51870 REPOINTING MASONRY IN STRUCTURES	25.000	SFT
128	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
129	715-01662 PIPE CLEANING, 12 IN. TO 48 IN. DIA.	120.000	LFT
130	715-02397 SAFETY METAL END SECTION, 4:1, 36 IN.	1.000	EACH
131	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN.	3.000	EACH
132	715-03321 SAFETY METAL END SECTION, 6:1, 12 IN.	1.000	EACH
133	715-04611 SAFETY METAL END SECTION, 4:1, 12 IN.	1.000	EACH
134	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	72.000	LFT
135	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	7,431.000	LFT
136	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	336.000	LFT
137	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	32.000	LFT
138	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	176.000	LFT
139	715-05757 PIPE EXTENSION, CIRCULAR, 36 IN.	9.000	LFT
140	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
141	715-46040 PIPE END SECTION, 36 IN.	1.000	EACH
142	715-97559 GRATED BOX END SECTION, II, 10:1, 12 IN.	2.000	EACH
143	718-06526 HMA FOR UNDERDRAINS	34.000	TON
144	718-06528 OUTLET PROTECTOR, 1	111.000	EACH

CALL ORDER : 261
 LETTING DATE :

CONTRACT ID : R -28955-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
145	718-06529 OUTLET PROTECTOR, 2	85.000	EACH
146	718-06531 OUTLET PROTECTOR, 3	56.000	EACH
147	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
148	720-44000 CASTING, ADJUST TO GRADE	13.000	EACH
149	720-45045 INLET, J10	1.000	EACH
150	720-45055 INLET, M10	7.000	EACH
151	720-96995 CLEAN INLET	12.000	EACH
152	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	1,860.000	SFT
153	722-51842 BRIDGE DECK OVERLAY	4,010.000	SYS
154	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	16.000	CYS
155	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	5,000.000	SFT
156	722-60824 SURFACE MILLING	4,010.000	SYS
157	724-03276 EXPANSION JOINT SEALING SYSTEM	160.000	LFT
158	724-51925 STRUCTURAL EXPANSION JOINT, SS	90.000	LFT
159	726-92406 BEARING ASSEMBLY, ELASTOMERIC	28.000	EACH
160	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	22.000	EACH
161	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
162	801-06198 PATROLLER	400.000	DAY
163	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	535,649.000	LFT
164	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	6,579.000	LFT
165	801-06640 CONSTRUCTION SIGN, A	59.000	EACH
166	801-06645 CONSTRUCTION SIGN, B	17.000	EACH
167	801-06710 FLASHING ARROW SIGN	1,380.000	DAY
168	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
169	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	3.000	EACH
170	801-07118 BARRICADE, III-A	80.000	LFT
171	801-07119 BARRICADE, III-B	160.000	LFT
172	801-07606 TEMPORARY CROSSOVER DRAINAGE PIPE	1,600.000	LFT
173	801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1	65,763.000	LFT
174	801-08507 TEMPORARY TRAFFIC BARRIER, TYPE 1, ANCHORED	900.000	LFT
175	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	320.000	LFT
176	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	7.000	EACH
177	802-02372 OVERHEAD SIGN STRUCTURE, INSTALL	7.000	EACH
178	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	2.000	EACH
179	802-03706 SIGN PANEL, INSTALL	2.000	EACH
180	802-03706 SIGN PANEL, INSTALL	6.000	EACH
181	802-04893 REFERENCE POST	35.000	EACH
182	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	456.390	LFT
183	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	635.000	LFT
184	802-05705 SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	60.000	LFT
185	802-07057 SIGN, PANEL, WITH LEGEND	7,012.000	SFT
186	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	176.000	EACH
187	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
188	802-07138 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, IX	8.000	EACH
189	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	48.000	EACH
190	802-07152 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, X	2.000	EACH
191	802-07153 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	24.000	EACH
192	802-07154 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XII	8.000	EACH

CALL ORDER : 261
 LETTING DATE :

CONTRACT ID : R -28955-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
193	802-07159 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, II	3.000	EACH
194	802-08456 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	8.000	EACH
195	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	357.610	SFT
196	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	1,124.000	SFT
197	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	332.550	SFT
198	802-76055 SIGN POST, A	779.500	LFT
199	802-76065 SIGN POST, B	1,137.000	LFT
200	802-76095 STRUCTURAL STEEL, BREAKAWAY	29,622.000	LBS
201	802-76140 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM	3.000	EACH
202	802-76160 BRIDGE BRACKET ASSEMBLY	4.000	EACH
203	802-76175 WALKWAY, HANDRAIL, AND LIGHTING SUPPORT ASSEMBLY	39.000	LFT
204	802-76235 INSTALL OVERHEAD SIGN	7.000	EACH
205	802-99058 SHEET SIGN, INSTALL	2.000	EACH
206	804-06771 DELINEATOR POST, FLEXIBLE	479.000	EACH
207	807-02108 LUMINAIRE, SIGN, MERCURY VAPOR, WITH GLARE SHIELD, 250 WATT,	6.000	EACH
208	807-82016 SIGN CIRCUIT INSTALLATION, CANTILEVER, 2 LUMINAIRES	3.000	EACH
209	807-86910 CONNECTOR KIT, UNFUSED	3.000	EACH
210	807-86915 CONNECTOR KIT, FUSED	6.000	EACH
211	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	9.000	EACH
212	807-86935 INSULATION LINK, WATERPROOFED	3.000	EACH
213	807-96868 LUMINAIRE, INSTALL	6.000	EACH
214	808-01328 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WRONG WAY RAMP	2.000	EACH
215	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	80,877.000	LFT
216	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	151,129.000	LFT
217	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	3,684.000	LFT
218	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	139.000	LFT
219	808-06716 LINE, REMOVE	200,000.000	LFT
220	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	150,996.000	LFT
221	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	292.000	LFT
222	808-75272 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	528.000	LFT
223	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
224	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2,047.000	EACH
225	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2,047.000	EACH

CALL ORDER : 271
 LETTING DATE :

CONTRACT ID : R -29040-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	8.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	8.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02240 PAVEMENT REMOVAL	4,587.000	SYS
16	202-02241 GUARDRAIL, REMOVE	245.000	LFT
17	202-02271 HEADWALL, REMOVE	8.000	EACH
18	202-52710 SIDEWALK, CONCRETE, REMOVE	5.000	SYS
19	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	10.000	EACH
20	202-96133 PIPE, REMOVE	162.000	LFT
21	202-96718 POST, GUARD RAIL, REMOVE	40.000	EACH
22	202-99187 FENCE, FARM FIELD, REMOVE	938.000	LFT
23	203-02000 EXCAVATION, COMMON	22,603.000	CYS
24	205-03371 SEDIMENT, REMOVE	164.000	CYS
25	205-06930 SPLASHPAD, RIPRAP	5.000	TON
26	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	60.000	TON
27	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
28	205-06936 TEMPORARY SEDIMENT TRAP	63.000	TON
29	205-06937 TEMPORARY SILT FENCE	700.000	LFT
30	205-06938 TEMPORARY SLOPE DRAIN	70.000	LFT
31	207-08263 SUBGRADE TREATMENT, TYPE IA	8,038.000	SYS
32	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,120.000	SYS
33	211-09264 STRUCTURE BACKFILL, TYPE 1	272.000	CYS
34	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,237.000	TON
35	303-02051 STONE, NO 2	90.000	TON
36	303-07449 COMPACTED AGGREGATE, NO. 73	25.000	TON
37	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	1,119.000	TON
38	306-08043 MILLING, TRANSITION	630.000	SYS
39	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
40	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	636.000	TON
41	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	1,160.000	TON
42	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	3,026.000	TON
43	406-05520 ASPHALT FOR TACK COAT	7.100	TON
44	603-06040 FENCE, FARM FIELD, 47 IN.	797.000	LFT
45	610-07486 HMA FOR APPROACHES, TYPE A	385.000	TON
46	610-07487 HMA FOR APPROACHES, TYPE B	298.000	TON
47	610-08446 PCCP FOR APPROACHES, 6 IN.	94.000	SYS
48	611-06497 MAILBOX ASSEMBLY, SINGLE	8.000	EACH

CALL ORDER : 271
 LETTING DATE :

CONTRACT ID : R -29040-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
49	615-06490 RIGHT OF WAY MARKER	42.000	EACH
50	615-06505 MONUMENT, B	8.000	EACH
51	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
52	616-02320 GEOTEXTILES	203.000	SYS
53	616-06451 RIPRAP, UNIFORM	280.000	TON
54	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
55	621-02770 EROSION CONTROL BLANKET	9,305.000	SYS
56	621-06545 FERTILIZER	4.000	TON
57	621-06553 SEED MIXTURE, R	503.000	LBS
58	621-06565 MULCHING MATERIAL	7.000	TON
59	621-06567 WATER	8.000	KGAL
60	621-06574 SODDING	1,060.000	SYS
61	622-98200 SIGN, DO NOT DISTURB	5.000	EACH
62	715-02397 SAFETY METAL END SECTION, 4:1, 36 IN.	2.000	EACH
63	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN.	11.000	EACH
64	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	3.000	EACH
65	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	83.000	LFT
66	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	73.000	LFT
67	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	348.000	LFT
68	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	120.000	LFT
69	720-45105 INLET, A2, MODIFIED	1.000	EACH
70	720-91352 CATCH BASIN, F7	1.000	EACH
71	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
72	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
73	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
74	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
75	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
76	801-07119 BARRICADE, III-B	168.000	LFT
77	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	81.300	LFT
78	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	25.500	LFT
79	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	6.250	SFT
80	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	45.000	SFT
81	805-96014 SAW CUT, FULL DEPTH	113.000	LFT
82	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,736.000	LFT
83	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4,500.000	LFT
84	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	53.000	LFT

CALL ORDER : 281
 LETTING DATE :

CONTRACT ID : R -29053-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	9.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	9.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	9.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	9.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-02240 PAVEMENT REMOVAL	182.000	m2
17	202-02241 GUARDRAIL, REMOVE	329.000	m
18	203-02000 EXCAVATION, COMMON	2,640.000	m3
19	203-02070 BORROW	3,460.000	m3
20	205-03371 SEDIMENT REMOVE	115.000	m3
21	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	93.000	Mg
22	205-06936 TEMPORARY SEDIMENT TRAP	60.000	Mg
23	205-06937 TEMPORARY SILT FENCE	680.000	m
24	206-51817 SHEET PILING, STEEL	186.400	m2
25	207-08263 SUBGRADE TREATMENT, TYPE IA	2,951.000	m2
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	136.000	m2
27	211-09264 STRUCTURE BACKFILL, TYPE 1	25.000	m3
28	211-09265 STRUCTURE BACKFILL, TYPE 2	484.600	m3
29	211-09268 STRUCTURE BACKFILL, TYPE 5	95.000	m3
30	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	5.600	m3
31	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,310.000	Mg
32	303-07449 COMPACTED AGGREGATE, NO. 73	20.000	Mg
33	303-07662 STONE	180.000	Mg
34	306-08036 MILLING, ASPHALT, 50 mm	2,557.000	m2
35	306-08043 MILLING, TRANSITION	864.000	m2
36	402-07432 HMA SURFACE, TYPE A	212.000	Mg
37	402-07433 HMA SURFACE, TYPE B	326.000	Mg
38	402-07438 HMA INTERMEDIATE, TYPE B	474.000	Mg
39	402-07440 HMA BASE, TYPE A	644.000	Mg
40	402-07441 HMA BASE, TYPE B	104.000	Mg
41	404-05514 SEAL COAT, 5	373.000	m2
42	406-05520 ASPHALT FOR TACK COAT	2.560	Mg
43	601-01626 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 2	1.000	EACH
44	601-01701 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 2	1.000	EACH
45	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 1.905 m SPACING	3.810	m
46	601-05999 CURVED TERMINAL END	2.000	EACH
47	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH

48 601-94689

GUARDRAIL END TREATMENT, OS

6.000

EACH

CALL ORDER : 281
 LETTING DATE :

CONTRACT ID : R -29053-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
49	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	476.250	m
50	605-06145 CURB AND GUTTER, B, CONCRETE	50.400	m
51	610-07486 HMA FOR APPROACHES, TYPE A	239.000	Mg
52	615-06490 RIGHT OF WAY MARKER	19.000	EACH
53	615-06500 MONUMENT, A	10.000	EACH
54	616-02320 GEOTEXTILES	1,643.000	m2
55	616-05688 RIPRAP, CLASS 1	427.000	Mg
56	616-05689 RIPRAP, CLASS 2	132.000	Mg
57	616-06405 RIPRAP, REVETMENT	438.000	Mg
58	616-06451 RIPRAP, UNIFORM	117.000	Mg
59	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
60	621-01660 MULCHED SEEDING, LEGUME, 2	4,698.000	m2
61	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	10,110.000	m2
62	621-06559 MULCHED SEEDING, R	8,294.000	m2
63	621-06567 WATER	14.500	kL
64	621-06574 SODDING	805.000	m2
65	622-52436 SIGN, DO NOT MOW OR SPRAY	6.000	EACH
66	622-91786 SEEDLING	158.000	EACH
67	714-08514 WINGWALL	22.400	m2
68	714-26717 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3000 mm x 1500 mm	17.500	m
69	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	16.000	m
70	715-05123 PIPE, TYPE 1, CIRCULAR, 600 mm	45.000	m
71	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	32.000	m
72	715-46005 PIPE END SECTION, 375 mm	6.000	EACH
73	715-46020 PIPE END SECTION, 600 mm	1.000	EACH
74	723-07105 STRUCTURE, PRECAST THREE-SIDED, 6100 mm X 3050 mm	22.000	m
75	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
76	801-04308 ROAD CLOSURE SIGN ASSEMBLY	13.000	EACH
77	801-06625 DETOUR ROUTE MARKER ASSEMBLY	64.000	EACH
78	801-06640 CONSTRUCTION SIGN, A	34.000	EACH
79	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
80	801-07118 BARRICADE, III-A	72.000	m
81	801-07119 BARRICADE, III-B	14.400	m
82	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	18.500	m
83	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	3.320	m2
84	808-06712 LINE, PAINT, BROKEN, YELLOW, 100 mm	48.000	m
85	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	1,074.000	m
86	808-06714 LINE, PAINT, SOLID, YELLOW, 100 mm	560.000	m
87	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	22.000	m
88	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	30.000	EACH
89	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	30.000	EACH

CALL ORDER : 291
 LETTING DATE :

CONTRACT ID : R -29236-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	12.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	24.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	12.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-02240 PAVEMENT REMOVAL	4,344.000	SYS
17	202-02241 GUARDRAIL, REMOVE	574.000	LFT
18	202-02272 PAVED SIDE DITCH, REMOVE	138.000	LFT
19	203-02020 EXCAVATION, UNCLASSIFIED	19,580.000	CYS
20	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	992.000	TON
21	205-06932 TEMPORARY CHECK DAM, STRAW BALES	331.000	LFT
22	205-06934 TEMPORARY MULCHING	15.000	TON
23	205-06937 TEMPORARY SILT FENCE	1,570.000	LFT
24	207-08263 SUBGRADE TREATMENT, TYPE IA	9,991.000	SYS
25	207-08264 SUBGRADE TREATMENT, TYPE II	5,301.000	SYS
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	585.000	SYS
27	211-09264 STRUCTURE BACKFILL, TYPE 1	392.000	CYS
28	211-09265 STRUCTURE BACKFILL, TYPE 2	3,672.000	CYS
29	211-09268 STRUCTURE BACKFILL, TYPE 5	21.000	CYS
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,949.000	TON
31	306-08043 MILLING, TRANSITION	534.000	SYS
32	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
33	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	981.000	TON
34	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	1,833.000	TON
35	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	3,218.000	TON
36	402-07434 HMA SURFACE, TYPE C	221.000	TON
37	402-07442 HMA BASE, TYPE C	663.000	TON
38	406-05520 ASPHALT FOR TACK COAT	7.000	TON
39	601-01626 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 2	1.000	EACH
40	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
41	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	63.000	LFT
42	601-05586 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 9	1.000	EACH
43	601-05999 CURVED TERMINAL END	2.000	EACH
44	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
45	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	838.000	LFT
46	607-06350 PAVED SIDE DITCH, D	133.000	LFT
47	607-06370 PAVED SIDE DITCH, H	1,405.000	LFT
48	610-07486 HMA FOR APPROACHES, TYPE A	230.000	TON

CALL ORDER : 291
 LETTING DATE :

CONTRACT ID : R -29236-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
49	611-06497 MAILBOX ASSEMBLY, SINGLE	6.000	EACH
50	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
51	615-06490 RIGHT OF WAY MARKER	40.000	EACH
52	615-06505 MONUMENT, B	2.000	EACH
53	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
54	616-02320 GEOTEXTILES	1,231.000	SYS
55	616-05688 RIPRAP, CLASS 1	942.000	TON
56	616-05689 RIPRAP, CLASS 2	55.000	TON
57	616-06405 RIPRAP, REVETMENT	30.000	TON
58	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.000	EACH
59	621-01956 SEED MIXTURE, LEGUME, 1	880.000	LBS
60	621-06545 FERTILIZER	2.000	TON
61	621-06557 SEED MIXTURE, T	1,100.000	LBS
62	621-06565 MULCHING MATERIAL	9.000	TON
63	621-06567 WATER	30.000	KGAL
64	621-06575 SODDING, NURSERY	7,610.000	SYS
65	622-52436 SIGN, DO NOT MOW OR SPRAY	21.000	EACH
66	714-26719 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 10 FT. X 7 FT.	168.000	LFT
67	714-44240 CONCRETE, A, STRUCTURES	5.000	CYS
68	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	162.000	LFT
69	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	90.000	LFT
70	715-05133 PIPE, TYPE 1, CIRCULAR, 60 IN.	114.000	LFT
71	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	30.000	LFT
72	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	238.000	LFT
73	715-05841 CONCRETE ANCHOR, 60 IN.	2.000	EACH
74	715-46005 PIPE END SECTION, 15 IN.	18.000	EACH
75	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
76	723-06660 WINGWALL	38.000	SYS
77	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
78	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
79	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,600.000	LFT
80	801-06625 DETOUR ROUTE MARKER ASSEMBLY	22.000	EACH
81	801-06640 CONSTRUCTION SIGN, A	25.000	EACH
82	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
83	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
84	801-07118 BARRICADE, III-A	132.000	LFT
85	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	73.000	LFT
86	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	38.000	LFT
87	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	5.000	SFT
88	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	38.000	SFT
89	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	20.000	SFT
90	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	6,474.000	LFT
91	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,916.000	LFT
92	808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	171.000	LFT
93	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	83.000	LFT
94	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	5.000	EACH
95	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000	EACH
96	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	61.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 291
 LETTING DATE :

CONTRACT ID : R -29236-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
97 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	46.000	EACH
98 808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1,648.000	LFT

CALL ORDER : 301
 LETTING DATE :

CONTRACT ID : R -29257-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPAIR OR REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	9.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	9.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	9.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	2,085.000	m3
14	203-02070 BORROW	660.000	m3
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	80.000	Mg
16	205-06937 TEMPORARY SILT FENCE	1,510.000	m
17	207-08262 SUBGRADE TREATMENT, TYPE I	8,812.000	m2
18	211-07454 STRUCTURE BACKFILL	25.000	m3
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,329.000	Mg
20	306-08043 MILLING, TRANSITION	131.000	m2
21	401-07333 QC/QA-HMA, 2, 76, SURFACE, 9.5 mm	558.000	Mg
22	401-07366 QC/QA-HMA, 2, 76, INTERMEDIATE, 9.5 MM	920.000	Mg
23	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	1,969.000	Mg
24	401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm	1,447.000	Mg
25	402-07433 HMA SURFACE, TYPE B	229.000	Mg
26	402-07441 HMA BASE, TYPE B	685.000	Mg
27	406-05520 ASPHALT FOR TACK COAT	8.000	Mg
28	604-06070 SIDEWALK, CONCRETE	25.000	m2
29	604-07899 CURB RAMP, CONCRETE, E	8.000	m2
30	605-97937 CURB AND GUTTER, CONCRETE, ROLL	50.000	m
31	610-07487 HMA FOR APPROACHES, TYPE B	73.000	Mg
32	616-02320 GEOTEXTILES	200.000	m2
33	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
34	621-01371 SEED MIXTURE, LEGUME, 2	21.000	kg
35	621-06545 FERTILIZER	1.000	Mg
36	621-06554 SEED MIXTURE, U	79.000	kg
37	621-06557 SEED MIXTURE, T	78.000	kg
38	621-06565 MULCHING MATERIAL	3.000	Mg
39	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	663.000	m
40	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	33.500	m
41	715-05123 PIPE, TYPE 1, CIRCULAR, 600 mm	47.500	m
42	715-46020 PIPE END SECTION, 600 mm	2.000	EACH
43	718-06528 OUTLET PROTECTOR, 1	2.000	EACH
44	718-06529 OUTLET PROTECTOR, 2	4.000	EACH
45	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	663.000	m
46	718-52610 AGGREGATE FOR UNDERDRAINS	489.000	m3
47	718-99153 GEOTEXTILES FOR UNDERDRAIN	3,735.000	m2
48	801-03290 CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 301
 LETTING DATE :

CONTRACT ID : R -29257-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPAIR OR REHABILITATION		
49	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
50	801-06625 DETOUR ROUTE MARKER ASSEMBLY	7.000	EACH
51	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
52	801-07118 BARRICADE, III-A	32.500	m
53	801-07119 BARRICADE, III-B	7.500	m
54	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	8.500	m
55	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	2.000	m2
56	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,435.000	m
57	808-74815 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 300 mm	52.000	m
58	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	1,152.000	m
59	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	19.000	m
60	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	8.000	m
61	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm	40.000	m
62	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	162.000	m

CALL ORDER : 311
 LETTING DATE :

CONTRACT ID : R -29354-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PIPE LINING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	203-51223 EXCAVATION, WATERWAY	16.000	CYS
13	211-09265 STRUCTURE BACKFILL, TYPE 2	487.000	CYS
14	616-02281 GROUT FOR RIPRAP	4.000	CYS
15	616-02320 GEOTEXTILES	462.500	SYS
16	616-05688 RIPRAP, CLASS 1	18.000	TON
17	616-06405 RIPRAP, REVETMENT	10.000	TON
18	616-06451 RIPRAP, UNIFORM	60.000	TON
19	616-93019 RIPRAP, GROUTED, 18 IN.	66.000	SYS
20	715-06492 CONCRETE ANCHOR, 54 IN.	2.000	EACH
21	715-09277 PIPE EXTENSION, DEFORMED, MIN. AREA 15.9 SFT.	95.000	LFT
22	725-06873 PIPE LINER, THERMOPLASTIC, 54 IN.	316.500	LFT
23	725-09251 PIPE LINER, THERMOPLASTIC, AREA 42.4 SFT.	85.000	LFT
24	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
25	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 321
 LETTING DATE :

CONTRACT ID : R -29652-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPAIR OR REHAB		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	7.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	7.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	7.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-52710 SIDEWALK, CONCRETE, REMOVE	1,790.000	SYS
13	202-91385 INLET, REMOVE	5.000	EACH
14	202-96133 PIPE, REMOVE	111.000	LFT
15	203-02000 EXCAVATION, COMMON	1,243.000	CYS
16	205-03371 SEDIMENT, REMOVE	10.000	CYS
17	205-06933 TEMPORARY DITCH INLET PROTECTION	23.000	EACH
18	205-06937 TEMPORARY SILT FENCE	1,326.000	LFT
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,064.000	SYS
20	207-08268 SUBGRADE TREATMENT, TYPE IV	916.000	SYS
21	211-07454 STRUCTURE BACKFILL	331.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	545.000	TON
23	306-08033 MILLING, ASPHALT, 1 IN.	5,067.000	SYS
24	306-08034 MILLING, ASPHALT, 1 1/2 IN.	261.000	SYS
25	401-07333 QC/QA-HMA, 2, 76, SURFACE, 9.5 mm	486.000	TON
26	401-07402 QC/QA-HMA, 2, 76, INTERMEDIATE, 19.0 mm	793.000	TON
27	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	363.000	TON
28	402-07451 HMA WEDGE AND LEVEL, TYPE B	430.000	TON
29	406-05520 ASPHALT FOR TACK COAT	4.600	TON
30	604-03654 BRICK PAVERS, RESET	10.000	SYS
31	604-06070 SIDEWALK, CONCRETE	1,790.000	SYS
32	604-07897 CURB RAMP, CONCRETE, C	66.100	SYS
33	604-07901 CURB RAMP, CONCRETE, G	58.800	SYS
34	605-52807 CURB AND GUTTER, COMBINED	3,114.000	LFT
35	610-07487 HMA FOR APPROACHES, TYPE B	877.000	TON
36	610-08446 PCCP FOR APPROACHES, 6 IN.	103.000	SYS
37	610-09108 PCCP FOR APPROACHES, 9 IN.	343.000	SYS
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
39	621-06560 MULCHED SEEDING, U	4,550.000	SYS
40	621-06567 WATER	1.500	KGAL
41	621-06574 SODDING	453.000	SYS
42	702-90915 CONCRETE, A	6.000	CYS
43	703-06028 REINFORCING BARS	380.000	LBS
44	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	262.000	LFT
45	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	675.000	LFT
46	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	113.000	LFT
47	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	20.000	LFT
48	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	20.000	LFT

CALL ORDER : 321
 LETTING DATE :

CONTRACT ID : R -29652-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPAIR OR REHAB		
49	715-05428 PIPE, SLOTTED VANE DRAIN, 12 IN.	15.000	LFT
50	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	13.000	TON
51	715-09064 VIDEO INSPECTION FOR PIPE	1,079.000	LFT
52	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
53	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
54	720-45035 INLET, F7	1.000	EACH
55	720-45260 PIPE CATCH BASIN, 12 IN.	10.000	EACH
56	720-45410 MANHOLE, C4	3.000	EACH
57	720-96999 FIRE HYDRANT ASSEMBLY	3.000	EACH
58	720-98174 INLET, B15	2.000	EACH
59	720-98555 INLET, C15	9.000	EACH
60	732-90573 WATER SERVICE LINE, 0.75 IN	205.000	LFT
61	732-97009 FIRE HYDRANT ASSEMBLY, REMOVE	2.000	EACH
62	801-06625 DETOUR ROUTE MARKER ASSEMBLY	21.000	EACH
63	801-06640 CONSTRUCTION SIGN, A	27.000	EACH
64	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
65	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
66	801-07118 BARRICADE, III-A	144.000	LFT
67	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	144.000	LFT
68	802-07060 SIGN, SHEET, RELOCATE	5.000	EACH
69	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	66.250	SFT
70	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	460.000	LFT
71	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	144.000	LFT
72	808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	610.000	LFT
73	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,800.000	LFT
74	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	146.000	LFT

CALL ORDER : 331
 LETTING DATE :

CONTRACT ID : R -29712-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, HISTORIC PRESERVATION		
1 105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
2 109-08359	LIQUIDATED DAMAGES	1.000	DOL
3 109-08360	CONTRACT LIENS	1.000	DOL
4 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5 711-03973	BUILDING ARCHITECTURAL	LUMP	LUMP
6 719-03975	BUILDING PLUMBING	LUMP	LUMP
7 802-04993	SIGN	LUMP	LUMP
8 807-03694	BUILDING ELECTRICAL	LUMP	LUMP
9 807-03974	BUILDING HEATING, VENTILATION, AIR CONDITIONING	LUMP	LUMP

CALL ORDER : 335
 LETTING DATE :

CONTRACT ID : R -29745-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 AUXILIARY LANES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	16.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	8.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-07553 REGULATED MATERIALS, REMOVE, TYPE Y	500.000	CYS
16	202-07554 REGULATED MATERIALS, TRANSPORT, TYPE Y	500.000	CYS
17	202-07555 REGULATED MATERIALS, DISPOSE, TYPE Y	500.000	CYS
18	202-08429 REGULATED MATERIALS, DISPOSE, B	1,000.000	GAL
19	202-08430 REGULATED MATERIALS, REMOVE, B	1,000.000	GAL
20	202-08431 REGULATED MATERIALS, TRANSPORT, B	1,000.000	GAL
21	202-09106 TESTING FOR CONTAMINATED MATERIALS, MTBE AND	6.000	EACH
22	202-92222 TESTING FOR CONTAMINATED MATERIALS, TPH	6.000	EACH
23	203-02000 EXCAVATION, COMMON	5,961.000	CYS
24	205-06932 TEMPORARY CHECK DAM, STRAW BALES	224.000	LFT
25	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
26	205-06937 TEMPORARY SILT FENCE	400.000	LFT
27	207-08263 SUBGRADE TREATMENT, TYPE IA	13,904.000	SYS
28	207-08267 SUBGRADE TREATMENT, TYPE IIIA	445.000	SYS
29	211-07454 STRUCTURE BACKFILL	8.600	CYS
30	303-01180 COMPACTED AGGREGATE, NO. 53	3,672.000	TON
31	306-08033 MILLING, ASPHALT, 1 IN.	5,953.000	SYS
32	306-08034 MILLING, ASPHALT, 1 1/2 IN.	750.000	SYS
33	306-08043 MILLING, TRANSITION	267.000	SYS
34	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
35	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,406.000	TON
36	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1,953.000	TON
37	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	3,703.000	TON
38	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	966.000	TON
39	406-05520 ASPHALT FOR TACK COAT	8.500	TON
40	606-07484 MILLED HMA SHOULDER CORRUGATIONS	3,687.000	LFT
41	610-07487 HMA FOR APPROACHES, TYPE B	434.000	TON
42	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
43	615-06490 RIGHT OF WAY MARKER	18.000	EACH
44	615-06505 MONUMENT, B	13.000	EACH
45	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
46	621-06545 FERTILIZER	0.900	TON
47	621-06553 SEED MIXTURE, R	371.000	LBS
48	621-06565 MULCHING MATERIAL	4.400	TON

CALL ORDER : 335
 LETTING DATE :

CONTRACT ID : R -29745-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 AUXILIARY LANES			
49	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	130.000	LFT
50	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	41.000	LFT
51	715-46000 PIPE END SECTION, 12 IN.	3.000	EACH
52	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
53	720-45030 INLET, E7	2.000	EACH
54	720-45270 PIPE CATCH BASIN, 18 IN.	1.000	EACH
55	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
56	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
57	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	22,749.000	LFT
58	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	68.000	LFT
59	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
60	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
61	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
62	801-07119 BARRICADE, III-B	178.000	LFT
63	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	146.000	LFT
64	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	24.000	LFT
65	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	130.000	SFT
66	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	11.500	SFT
67	805-01842 HANDHOLE, SIGNAL	8.000	EACH
68	805-02328 SIGNAL CABLE, 1C 14GA.	2,600.000	LFT
69	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,202.000	LFT
70	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
71	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	7.000	EACH
72	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	1.000	EACH
73	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
74	805-78420 DISCONNECT HANGER	4.000	EACH
75	805-78445 SIGNAL SERVICE	1.000	EACH
76	805-78467 SIGNAL CABLE, 3C 8GA.	32.000	LFT
77	805-78485 SIGNAL CABLE, 5C 14GA.	222.000	LFT
78	805-78490 SIGNAL CABLE, 7C 14GA.	611.000	LFT
79	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,337.000	LFT
80	805-78520 MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	LUMP	LUMP
81	805-78785 SIGNAL DETECTOR HOUSING	8.000	EACH
82	805-78790 LOOP DETECTOR DELAY AMPLIFIER, 4 CHANNEL	1.000	EACH
83	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	650.000	LFT
84	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
85	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000	EACH
86	805-96014 SAW CUT, FULL DEPTH	5,630.000	LFT
87	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,983.000	LFT
88	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,356.000	LFT
89	808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	341.000	LFT
90	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	160.000	LFT
91	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	11.000	EACH
92	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	9.000	EACH
93	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	91.000	EACH
94	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	2,074.000	LFT
95	202-02240 PAVEMENT REMOVAL	920.000	SYS
96	402-07433 HMA SURFACE, TYPE B	51.000	TON

SCHEDULE OF PAY ITEMS

CALL ORDER : 335
 LETTING DATE :

CONTRACT ID : R -29745-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	AUXILIARY LANES		
97 402-07438	HMA INTERMEDIATE, TYPE B	168.000	TON

CALL ORDER : 341
 LETTING DATE :

CONTRACT ID : R -30068-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	203-02000 EXCAVATION, COMMON	276.000	CYS
9	203-02010 EXCAVATION, ROCK	26.000	CYS
10	203-02070 BORROW	1,666.000	CYS
11	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	144.000	TON
12	205-06937 TEMPORARY SILT FENCE	633.000	LFT
13	207-08262 SUBGRADE TREATMENT, TYPE I	644.000	SYS
14	213-08058 FLOWABLE BACKFILL	1.500	CYS
15	303-01180 COMPACTED AGGREGATE, NO. 53	139.000	TON
16	306-08043 MILLING, TRANSITION	2,028.000	SYS
17	402-07433 HMA SURFACE, TYPE B	166.000	TON
18	402-07438 HMA INTERMEDIATE, TYPE B	242.000	TON
19	402-07441 HMA BASE, TYPE B	586.000	TON
20	406-05520 ASPHALT FOR TACK COAT	2.600	TON
21	610-07487 HMA FOR APPROACHES, TYPE B	616.000	TON
22	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
23	615-06490 RIGHT OF WAY MARKER	8.000	EACH
24	615-06505 MONUMENT, B	5.000	EACH
25	616-02320 GEOTEXTILES	149.000	SYS
26	616-06451 RIPRAP, UNIFORM	31.000	TON
27	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
28	621-06559 MULCHED SEEDING, R	3,303.000	SYS
29	621-06567 WATER	1.900	KGAL
30	621-06575 SODDING, NURSERY	519.000	SYS
31	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	1.000	EACH
32	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
33	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
34	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	49.000	LFT
35	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	2.000	EACH
36	802-07060 SIGN, SHEET, RELOCATE	4.000	EACH
37	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,393.000	LFT
38	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,472.000	LFT
39	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	41.000	LFT
40	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
41	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH

CALL ORDER : 351
 LETTING DATE :

CONTRACT ID : R -30193-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-07039 FIELD OFFICE, B	9.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	9.000	MOS
6	105-08523 RADIO SERVICE	18.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	105-09198 LAPTOP COMPUTER SYSTEM	9.000	MOS
9	105-09199 FIELD OFFICE INTERNET SERVICE	9.000	MOS
10	109-08359 LIQUIDATED DAMAGES	1.000	DOL
11	109-08360 CONTRACT LIENS	1.000	DOL
12	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
13	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	303-01180 COMPACTED AGGREGATE, NO. 53	1,940.200	TON
16	304-07489 HMA PATCHING, TYPE A	177.210	TON
17	306-08043 MILLING, TRANSITION	440.000	SYS
18	402-07450 HMA WEDGE AND LEVEL, TYPE A	1,645.420	TON
19	404-05511 SEAL COAT, 2	42,277.720	SYS
20	406-05520 ASPHALT FOR TACK COAT	5.550	TON
21	608-04395 AGGREGATE FOR SHOULDER DRAINS	25.000	TON
22	610-07486 HMA FOR APPROACHES, TYPE A	99.230	TON
23	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
24	801-06640 CONSTRUCTION SIGN, A	17.000	EACH
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 361
 LETTING DATE :

CONTRACT ID : R -30325-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS		
1 105-07039	FIELD OFFICE, B	3.000	MOS
2 105-08520	CELLULAR TELEPHONE/RADIO	1.000	EACH
3 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	3.000	MOS
4 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5 105-09198	LAPTOP COMPUTER SYSTEM	3.000	MOS
6 105-09199	FIELD OFFICE INTERNET SERVICE	3.000	MOS
7 109-08359	LIQUIDATED DAMAGES	1.000	DOL
8 109-08360	CONTRACT LIENS	1.000	DOL
9 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
11 205-06937	TEMPORARY SILT FENCE	200.000	LFT
12 621-06559	MULCHED SEEDING, R	500.000	SYS

CALL ORDER : 371
 LETTING DATE :

CONTRACT ID : R -30326-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS		
1 105-07039	FIELD OFFICE, B	3.000	MOS
2 105-08520	CELLULAR TELEPHONE/RADIO	1.000	EACH
3 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	3.000	MOS
4 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5 105-09198	LAPTOP COMPUTER SYSTEM	3.000	MOS
6 105-09199	FIELD OFFICE INTERNET SERVICE	3.000	MOS
7 109-08359	LIQUIDATED DAMAGES	1.000	DOL
8 109-08360	CONTRACT LIENS	1.000	DOL
9 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
11 205-06937	TEMPORARY SILT FENCE	200.000	LFT
12 621-06559	MULCHED SEEDING, R	500.000	SYS

CALL ORDER : 391
 LETTING DATE :

CONTRACT ID : R -30609-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS		
1 105-07039	FIELD OFFICE, B	3.000	MOS
2 105-08520	CELLULAR TELEPHONE/RADIO	1.000	EACH
3 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	3.000	MOS
4 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5 105-09198	LAPTOP COMPUTER SYSTEM	3.000	MOS
6 105-09199	FIELD OFFICE INTERNET SERVICE	3.000	MOS
7 109-08359	LIQUIDATED DAMAGES	1.000	DOL
8 109-08360	CONTRACT LIENS	1.000	DOL
9 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
10 205-06937	TEMPORARY SILT FENCE	200.000	LFT
11 621-06559	MULCHED SEEDING, R	500.000	SYS

CALL ORDER : 401
 LETTING DATE :

CONTRACT ID : RS-28657-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	9.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	9.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	1,170.500	LFT
13	202-93741 GUARD RAIL END TREATMENT, REMOVE	29.000	EACH
14	203-02070 BORROW	15.000	CYS
15	206-51215 EXCAVATION, X	49.300	CYS
16	211-07454 STRUCTURE BACKFILL	20.400	CYS
17	303-01180 COMPACTED AGGREGATE, NO. 53	1,300.000	TON
18	304-07490 HMA PATCHING, TYPE B	800.000	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN.	183.000	SYS
20	306-08042 MILLING, SCARIFICATION/PROFILE	138,339.000	SYS
21	306-08043 MILLING, TRANSITION	3,640.000	SYS
22	306-08432 MILLING, APPROACH	12,000.000	SYS
23	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
24	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	13,510.000	TON
25	406-05520 ASPHALT FOR TACK COAT	40.000	TON
26	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	4.000	EACH
27	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	2.000	EACH
28	601-04162 GUARDRAIL, W THRIE BEAM TRANSITION SECTION	1.000	EACH
29	601-94689 GUARDRAIL END TREATMENT, OS	29.000	EACH
30	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	250.000	LFT
31	610-07487 HMA FOR APPROACHES, TYPE B	1,000.000	TON
32	616-02305 GABIONS	148.000	CYS
33	616-02320 GEOTEXTILES	165.000	SYS
34	616-05689 RIPRAP, CLASS 2	15.000	TON
35	616-06451 RIPRAP, UNIFORM	14.000	TON
36	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
37	621-06559 MULCHED SEEDING, R	500.000	SYS
38	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	6.000	EACH
39	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	90.000	LFT
40	715-05841 CONCRETE ANCHOR, 60 IN.	2.000	EACH
41	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	26.000	TON
42	715-46005 PIPE END SECTION, 15 IN.	3.000	EACH
43	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
44	725-06857 PIPE LINER, THERMOPLASTIC, 24 IN.	40.000	LFT
45	725-06866 PIPE LINER, THERMOPLASTIC, 15 IN.	444.000	LFT
46	725-06867 PIPE LINER, THERMOPLASTIC, 18 IN.	163.000	LFT
47	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
48	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	5,378.000	LFT

CALL ORDER : 401
 LETTING DATE :

CONTRACT ID : RS-28657-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,378.000	LFT
50	801-06640 CONSTRUCTION SIGN, A	41.000	EACH
51	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
52	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	7,850.000	LFT
53	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	108,000.000	LFT
54	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	97,250.000	LFT
55	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,278.000	EACH
56	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,279.000	EACH

CALL ORDER : 411
 LETTING DATE :

CONTRACT ID : RS-28860-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	202-02278 CURB, CONCRETE, REMOVE	440.000	LFT
16	202-02772 CASTING, REMOVE	1.000	EACH
17	202-52710 SIDEWALK, CONCRETE, REMOVE	234.000	SYS
18	304-07491 HMA PATCHING, TYPE C	429.000	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN.	26,551.000	SYS
20	306-08043 MILLING, TRANSITION	500.000	SYS
21	306-08432 MILLING, APPROACH	4,827.000	SYS
22	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2,190.000	TON
23	402-07452 HMA WEDGE AND LEVEL, TYPE C	50.000	TON
24	406-05520 ASPHALT FOR TACK COAT	9.000	TON
25	604-06070 SIDEWALK, CONCRETE	234.000	SYS
26	604-06367 JOINT MATERIAL	400.000	LFT
27	604-07894 CURB RAMP, CONCRETE, A	166.000	SYS
28	604-07896 CURB RAMP, CONCRETE, B	184.000	SYS
29	604-07897 CURB RAMP, CONCRETE, C	67.000	SYS
30	604-07898 CURB RAMP, CONCRETE, D	4.000	SYS
31	604-07899 CURB RAMP, CONCRETE, E	11.000	SYS
32	604-07900 CURB RAMP, CONCRETE, F	70.000	SYS
33	604-07901 CURB RAMP, CONCRETE, G	24.000	SYS
34	604-07902 CURB RAMP, CONCRETE, H	8.000	SYS
35	604-07904 CURB RAMP, CONCRETE, L	19.000	SYS
36	605-01870 CURB, CONCRETE, A	222.000	LFT
37	605-06090 CURB, INTEGRAL, CONCRETE	218.000	LFT
38	610-07488 HMA FOR APPROACHES, TYPE C	398.000	TON
39	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	36.000	TON
40	612-60410 DRILLED HOLE FOR UNDERSEAL	772.000	EACH
41	621-06574 SODDING	70.000	SYS
42	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
43	720-44000 CASTING, ADJUST TO GRADE	67.000	EACH
44	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
45	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,606.000	LFT
46	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,606.000	LFT
47	801-06640 CONSTRUCTION SIGN, A	32.000	EACH
48	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

SCHEDULE OF PAY ITEMS

CALL ORDER : 411
 LETTING DATE :

CONTRACT ID : RS-28860-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	802-91122 SIGN, GROUND MOUNTED, RESET	2.000	EACH
50	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	32.000	EACH
51	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	13,000.000	LFT
52	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	3,000.000	LFT
53	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,600.000	LFT
54	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	5,120.000	LFT
55	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	50.000	LFT
56	808-05929 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 8 IN.	2,225.000	LFT
57	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,085.000	LFT
58	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	975.000	LFT
59	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,475.000	LFT
60	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	380.000	LFT
61	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	55.000	EACH
62	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	14.000	EACH

CALL ORDER : 421
 LETTING DATE :

CONTRACT ID : RS-29243-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-07039 FIELD OFFICE, B	11.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	11.000	MOS
6	105-08523 RADIO SERVICE	22.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	105-09198 LAPTOP COMPUTER SYSTEM	33.000	MOS
9	105-09199 FIELD OFFICE INTERNET SERVICE	11.000	MOS
10	109-08359 LIQUIDATED DAMAGES	1.000	DOL
11	109-08360 CONTRACT LIENS	1.000	DOL
12	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
13	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
14	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
15	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
16	202-02241 GUARDRAIL, REMOVE	385.000	LFT
17	202-93741 GUARD RAIL END TREATMENT, REMOVE	16.000	EACH
18	203-02070 BORROW	75.000	CYS
19	203-08607 LINEAR GRADING	42,420.000	LFT
20	303-01180 COMPACTED AGGREGATE, NO. 53	750.000	TON
21	303-07449 COMPACTED AGGREGATE, NO. 73	100.000	TON
22	304-07490 HMA PATCHING, TYPE B	3,752.000	TON
23	305-60400 COMPACTED AGGREGATE FOR PATCHING	100.000	TON
24	306-08033 MILLING, ASPHALT, 1 IN.	116,146.000	SYS
25	306-08034 MILLING, ASPHALT, 1 1/2 IN.	24,883.000	SYS
26	306-08043 MILLING, TRANSITION	3,707.000	SYS
27	306-08432 MILLING, APPROACH	4,752.000	SYS
28	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
29	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	11,534.000	TON
30	401-09335 QC/QA-HMA, 2, 64, INTERMEDIATE,	12,668.000	TON
31	402-07433 HMA SURFACE, TYPE B	407.000	TON
32	402-07438 HMA INTERMEDIATE, TYPE B	542.000	TON
33	406-05520 ASPHALT FOR TACK COAT	66.000	TON
34	601-01839 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 6	1.000	EACH
35	601-93346 GUARDRAIL CONNECTOR, AS	3.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	15.000	EACH
37	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	225.000	LFT
38	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	6.000	EACH
39	608-04395 AGGREGATE FOR SHOULDER DRAINS	100.000	TON
40	610-07487 HMA FOR APPROACHES, TYPE B	1,539.000	TON
41	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	153.000	TON
42	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
43	612-60410 DRILLED HOLE FOR UNDERSEAL	2,551.000	EACH
44	615-06505 MONUMENT, B	7.000	EACH
45	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	7.000	EACH
46	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
47	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,443.600	LFT
48	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,990.000	LFT

CALL ORDER : 421
 LETTING DATE :

CONTRACT ID : RS-29243-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	801-06640 CONSTRUCTION SIGN, A	39.000	EACH
50	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
51	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	798.000	LFT
52	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	491.000	LFT
53	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
54	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	57.000	LFT
55	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	72,700.000	LFT
56	808-06716 LINE, REMOVE	1,346.000	LFT
57	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	8,016.000	LFT
58	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	29,111.000	LFT
59	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	160.000	LFT
60	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	3.000	EACH
61	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	932.000	EACH

CALL ORDER : 431
 LETTING DATE :

CONTRACT ID : RS-29501-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	3.000	EACH
3	105-07039 FIELD OFFICE, B	3.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
6	105-08523 RADIO SERVICE	5.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	202-02241 GUARDRAIL, REMOVE	300.000	LFT
15	202-93741 GUARD RAIL END TREATMENT, REMOVE	3.000	EACH
16	303-07449 COMPACTED AGGREGATE, NO. 73	5,471.000	TON
17	306-08033 MILLING, ASPHALT, 1 IN.	82,020.000	SYS
18	306-08043 MILLING, TRANSITION	400.000	SYS
19	306-08432 MILLING, APPROACH	150.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	7,187.250	TON
22	406-05520 ASPHALT FOR TACK COAT	21.000	TON
23	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
24	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
25	601-91653 GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	4.000	EACH
26	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
27	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	225.000	LFT
28	610-07488 HMA FOR APPROACHES, TYPE C	140.000	TON
29	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
30	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	9.600	TON
31	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
32	612-60410 DRILLED HOLE FOR UNDERSEAL	400.000	EACH
33	615-06520 MONUMENT, RE-ESTABLISH	2.000	EACH
34	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
35	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
36	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,513.000	LFT
37	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,513.000	LFT
38	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
39	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
40	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	52,694.000	LFT
41	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	5,640.000	LFT
42	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	9,822.000	LFT
43	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	35.000	LFT
44	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	410.000	EACH
45	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	410.000	EACH

CALL ORDER : 441
 LETTING DATE :

CONTRACT ID : RS-29502-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	202-93741 GUARD RAIL END TREATMENT, REMOVE	23.000	EACH
15	203-08607 LINEAR GRADING	2,640.000	LFT
16	210-08373 SIDEWALK	131.000	SYS
17	303-07449 COMPACTED AGGREGATE, NO. 73	6,650.000	TON
18	306-08042 MILLING, SCARIFICATION/PROFILE	103,147.300	SYS
19	306-08043 MILLING, TRANSITION	2,296.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	21,237.000	TON
22	401-09052 QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm-PWL	21,250.000	TON
23	406-05520 ASPHALT FOR TACK COAT	48.000	TON
24	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	6.000	EACH
25	601-94689 GUARDRAIL END TREATMENT, OS	23.000	EACH
26	604-06070 SIDEWALK, CONCRETE	131.000	SYS
27	604-07897 CURB RAMP, CONCRETE, C	20.000	SYS
28	604-07902 CURB RAMP, CONCRETE, H	1.000	SYS
29	605-06120 CURB, CONCRETE	230.000	LFT
30	610-07488 HMA FOR APPROACHES, TYPE C	1,657.000	TON
31	615-06520 MONUMENT, RE-ESTABLISH	7.000	EACH
32	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
33	801-06640 CONSTRUCTION SIGN, A	45.000	EACH
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	141,821.000	LFT
36	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	16,450.000	LFT
37	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	32,198.000	LFT
38	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	124.000	LFT
39	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,051.000	EACH
40	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,051.000	EACH

CALL ORDER : 451
 LETTING DATE :

CONTRACT ID : RS-29541-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-07039 FIELD OFFICE, B	6.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
6	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	303-01180 COMPACTED AGGREGATE, NO. 53	1,325.000	TON
14	304-07491 HMA PATCHING, TYPE C	376.000	TON
15	306-08034 MILLING, ASPHALT, 1 1/2 IN.	7,550.000	SYS
16	306-08042 MILLING, SCARIFICATION/PROFILE	89,127.000	SYS
17	306-08043 MILLING, TRANSITION	750.000	SYS
18	306-08432 MILLING, APPROACH	7,559.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	7,976.000	TON
21	402-07452 HMA WEDGE AND LEVEL, TYPE C	200.000	TON
22	404-05515 SEAL COAT, 6	996.000	SYS
23	406-05520 ASPHALT FOR TACK COAT	29.000	TON
24	610-07488 HMA FOR APPROACHES, TYPE C	624.000	TON
25	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	2.000	EACH
26	720-44000 CASTING, ADJUST TO GRADE	13.000	EACH
27	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
28	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,807.000	LFT
29	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8,807.000	LFT
30	801-06640 CONSTRUCTION SIGN, A	36.000	EACH
31	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
32	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
33	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	1.000	EACH
34	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	40.000	LFT
35	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	5,609.000	LFT
36	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	57,210.000	LFT
37	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	21,320.000	LFT
38	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	50.000	LFT
39	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	130.000	LFT
40	808-75015 LINE, PAINT, SOLID, WHITE, 12 IN.	50.000	LFT
41	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,075.000	LFT
42	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,080.000	LFT
43	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	475.000	LFT
44	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	223.000	LFT
45	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	10.000	EACH
46	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	5.000	EACH
47	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	556.000	EACH
48	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	559.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 451
 LETTING DATE :

CONTRACT ID : RS-29541-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49 808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1,294.000	LFT
50 808-94435	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (STOP)	4.000	EACH

CALL ORDER : 461
 LETTING DATE :

CONTRACT ID : RS-29542-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	5.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	15.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	10.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	5.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	303-01180 COMPACTED AGGREGATE, NO. 53	1,679.000	TON
15	304-07490 HMA PATCHING, TYPE B	744.000	TON
16	306-08042 MILLING, SCARIFICATION/PROFILE	68,125.000	SYS
17	306-08043 MILLING, TRANSITION	750.000	SYS
18	306-08432 MILLING, APPROACH	5,301.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	7,494.000	TON
21	402-07451 HMA WEDGE AND LEVEL, TYPE B	250.000	TON
22	406-05520 ASPHALT FOR TACK COAT	40.000	TON
23	610-07487 HMA FOR APPROACHES, TYPE B	1,020.000	TON
24	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	1.000	EACH
25	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
26	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
27	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,071.000	LFT
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,536.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
30	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	3.000	EACH
33	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	1,089.000	LFT
34	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	47,815.000	LFT
35	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	42,585.000	LFT
36	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	111.000	LFT
37	808-97323 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	144.000	LFT

CALL ORDER : 471
 LETTING DATE :

CONTRACT ID : RS-29807-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PATCH AND REHABD BITUMINOUS PAVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	6.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	303-01180 COMPACTED AGGREGATE, NO. 53	200.000	TON
15	304-07490 HMA PATCHING, TYPE B	2,359.000	TON
16	306-08034 MILLING, ASPHALT, 1 1/2 IN.	132,388.000	SYS
17	306-08432 MILLING, APPROACH	7,068.000	SYS
18	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
19	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	10,922.000	TON
20	402-07451 HMA WEDGE AND LEVEL, TYPE B	200.000	TON
21	406-05520 ASPHALT FOR TACK COAT	38.000	TON
22	610-07487 HMA FOR APPROACHES, TYPE B	583.000	TON
23	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	1.000	EACH
24	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
25	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
26	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	5,200.000	LFT
27	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,200.000	LFT
28	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
29	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
30	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	5,214.000	LFT
31	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	105,430.000	LFT
32	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	85,255.000	LFT
33	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	50.000	LFT
34	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,340.000	EACH
35	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,342.000	EACH

CALL ORDER : 481
 LETTING DATE :

CONTRACT ID : RS-29808-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	303-01180 COMPACTED AGGREGATE, NO. 53	1,020.000	TON
12	304-07490 HMA PATCHING, TYPE B	781.000	TON
13	306-08034 MILLING, ASPHALT, 1 1/2 IN.	126,303.000	SYS
14	306-08043 MILLING, TRANSITION	1,240.000	SYS
15	306-08432 MILLING, APPROACH	12,851.000	SYS
16	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
17	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	10,420.000	TON
18	402-07451 HMA WEDGE AND LEVEL, TYPE B	250.000	TON
19	406-05520 ASPHALT FOR TACK COAT	38.000	TON
20	610-07487 HMA FOR APPROACHES, TYPE B	1,060.000	TON
21	615-01469 MONUMENT, SECTION CORNER, INSTALL	1.000	EACH
22	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
23	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,259.000	LFT
24	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,259.000	LFT
25	801-06640 CONSTRUCTION SIGN, A	46.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	3,905.000	LFT
28	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	111,260.000	LFT
29	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	92,700.000	LFT
30	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	60.000	LFT

CALL ORDER : 491
 LETTING DATE :

CONTRACT ID : RS-29810-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASHPALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	7.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	21.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	14.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	7.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	202-52710 SIDEWALK, CONCRETE, REMOVE	10.000	SYS
15	303-01180 COMPACTED AGGREGATE, NO. 53	2,698.000	TON
16	304-07491 HMA PATCHING, TYPE C	400.000	TON
17	306-08042 MILLING, SCARIFICATION/PROFILE	194,449.000	SYS
18	306-08043 MILLING, TRANSITION	750.000	SYS
19	306-08432 MILLING, APPROACH	13,674.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	16,042.000	TON
22	402-07452 HMA WEDGE AND LEVEL, TYPE C	200.000	TON
23	404-05510 SEAL COAT, 1	704.000	SYS
24	406-05520 ASPHALT FOR TACK COAT	57.000	TON
25	604-06070 SIDEWALK, CONCRETE	10.000	SYS
26	604-07901 CURB RAMP, CONCRETE, G	12.000	SYS
27	610-07488 HMA FOR APPROACHES, TYPE C	1,128.000	TON
28	621-06574 SODDING	10.000	SYS
29	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	1.000	EACH
30	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
31	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
32	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	5,556.000	LFT
33	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,556.000	LFT
34	801-06640 CONSTRUCTION SIGN, A	45.000	EACH
35	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
36	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	12,014.000	LFT
37	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	112,225.000	LFT
38	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	20,130.000	LFT
39	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	50.000	LFT
40	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	830.000	EACH
41	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	835.000	EACH

CALL ORDER : 501
 LETTING DATE :

CONTRACT ID : RS-29812-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PATCH AND REHAB BITUMINOUS PAVEMENT		
1	105-07039 FIELD OFFICE, B	5.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	15.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	105-09198 LAPTOP COMPUTER SYSTEM	10.000	MOS
6	105-09199 FIELD OFFICE INTERNET SERVICE	5.000	MOS
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	303-01180 COMPACTED AGGREGATE, NO. 53	1,408.000	TON
14	304-07491 HMA PATCHING, TYPE C	194.000	TON
15	306-08043 MILLING, TRANSITION	750.000	SYS
16	306-08432 MILLING, APPROACH	8,621.000	SYS
17	306-08563 MILLING ASPHALT, 1 1/4 IN.	91,092.000	SYS
18	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
19	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	7,097.000	TON
20	402-07452 HMA WEDGE AND LEVEL, TYPE C	100.000	TON
21	404-05511 SEAL COAT, 2	5,069.000	SYS
22	406-05520 ASPHALT FOR TACK COAT	27.000	TON
23	610-07488 HMA FOR APPROACHES, TYPE C	711.000	TON
24	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	3.000	EACH
25	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
26	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
27	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,413.000	LFT
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,413.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	27.000	EACH
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	1.000	EACH
32	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,500.000	LFT
33	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	150.000	LFT
34	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
35	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	480.000	LFT
36	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
37	808-06694 LINE, PAINT, SOLID, YELLOW, 8 IN.	610.000	LFT
38	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	70.000	LFT
39	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	3,059.000	LFT
40	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	59,375.000	LFT
41	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	44,460.000	LFT
42	808-74815 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 12 IN.	42.000	LFT
43	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	1,220.000	LFT
44	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	700.000	LFT
45	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	700.000	LFT
46	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	89.000	LFT
47	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	709.000	EACH
48	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	724.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 501
 LETTING DATE :

CONTRACT ID : RS-29812-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PATCH AND REHAB BITUMINOUS PAVEMENT		
49 808-94435	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (STOP)	1.000	EACH

CALL ORDER : 511
 LETTING DATE :

CONTRACT ID : RS-29814-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	303-01180 COMPACTED AGGREGATE, NO. 53	2,501.000	TON
12	304-07491 HMA PATCHING, TYPE C	654.000	TON
13	306-08033 MILLING, ASPHALT, 1 IN.	173,331.000	SYS
14	306-08043 MILLING, TRANSITION	600.000	SYS
15	306-08432 MILLING, APPROACH	13,922.000	SYS
16	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
17	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	14,300.000	TON
18	402-07452 HMA WEDGE AND LEVEL, TYPE C	300.000	TON
19	406-05520 ASPHALT FOR TACK COAT	51.000	TON
20	610-07488 HMA FOR APPROACHES, TYPE C	1,149.000	TON
21	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	1.000	EACH
22	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
23	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
24	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,862.000	LFT
25	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8,862.000	LFT
26	801-06640 CONSTRUCTION SIGN, A	47.000	EACH
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	3.000	EACH
29	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	750.000	LFT
30	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	75.000	LFT
31	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	240.000	LFT
32	808-06694 LINE, PAINT, SOLID, YELLOW, 8 IN.	3,340.000	LFT
33	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	4,583.000	LFT
34	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	108,880.000	LFT
35	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	83,790.000	LFT
36	808-75090 TRANSVERSE MARKINGS, PAINT, SOLID, YELLOW CROSSHATCH LINE,	500.000	LFT
37	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	208.000	LFT
38	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	15.000	EACH
39	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	6.000	EACH
40	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,278.000	EACH
41	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	7.000	EACH

CALL ORDER : 521
 LETTING DATE :

CONTRACT ID : RS-29865-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	MICROSURFACING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	283.000	LFT
11	202-93741 GUARD RAIL END TREATMENT, REMOVE	28.000	EACH
12	203-02070 BORROW	130.000	CYS
13	304-07490 HMA PATCHING, TYPE B	1,100.000	TON
14	402-07451 HMA WEDGE AND LEVEL, TYPE B	400.000	TON
15	406-05520 ASPHALT FOR TACK COAT	2.500	TON
16	411-08438 MICRO-SURFACING, WARRANTED	128,363.000	SYS
17	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	2.000	EACH
18	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	7.000	EACH
19	601-06037 GUARDRAIL END TREATMENT, I	2.000	EACH
20	601-06038 GUARDRAIL END TREATMENT, II	1.000	EACH
21	601-93346 GUARDRAIL CONNECTOR, AS	4.000	EACH
22	601-94689 GUARDRAIL END TREATMENT, OS	26.000	EACH
23	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	32.000	LFT
24	616-02320 GEOTEXTILES	400.000	SYS
25	616-06405 RIPRAP, REVETMENT	260.000	TON
26	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
27	801-06640 CONSTRUCTION SIGN, A	48.000	EACH
28	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
29	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	5,714.000	LFT
30	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	93,010.000	LFT
31	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	62,000.000	LFT
32	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	45.000	LFT
33	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,076.000	EACH
34	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,076.000	EACH

CALL ORDER : 531
 LETTING DATE :

CONTRACT ID : RS-29867-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	11.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	22.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	22.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	11.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
16	202-02241 GUARDRAIL, REMOVE	275.250	LFT
17	202-02278 CURB, CONCRETE, REMOVE	40.000	LFT
18	202-52710 SIDEWALK, CONCRETE, REMOVE	20.000	SYS
19	202-86946 HANDHOLE, REMOVE	1.000	EACH
20	202-93741 GUARD RAIL END TREATMENT, REMOVE	8.000	EACH
21	203-02000 EXCAVATION, COMMON	395.500	CYS
22	203-02070 BORROW	305.000	CYS
23	205-06932 TEMPORARY CHECK DAM, STRAW BALES	20.000	LFT
24	210-06369 SAW CUT	1,450.000	LFT
25	211-09265 STRUCTURE BACKFILL, TYPE 2	20.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,175.000	TON
27	303-01180 COMPACTED AGGREGATE, NO. 53	3,000.000	TON
28	304-07783 HMA PATCHING, TYPE D	2,025.000	TON
29	306-08034 MILLING, ASPHALT, 1 1/2 IN.	13,350.000	SYS
30	306-08042 MILLING, SCARIFICATION/PROFILE	192,000.000	SYS
31	306-08043 MILLING, TRANSITION	3,275.000	SYS
32	306-08432 MILLING, APPROACH	15,225.000	SYS
33	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
34	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	22,500.000	TON
35	406-05520 ASPHALT FOR TACK COAT	64.000	TON
36	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	1.000	EACH
37	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
38	604-06070 SIDEWALK, CONCRETE	3.000	SYS
39	604-07901 CURB RAMP, CONCRETE, G	18.000	SYS
40	604-07902 CURB RAMP, CONCRETE, H	14.000	SYS
41	610-07788 HMA FOR APPROACHES, TYPE D	1,700.000	TON
42	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	3.000	EACH
43	616-02320 GEOTEXTILES	50.000	SYS
44	616-05688 RIPRAP, CLASS 1	20.000	TON
45	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
46	621-06559 MULCHED SEEDING, R	800.000	SYS
47	621-06575 SODDING, NURSERY	25.000	SYS
48	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	80.000	LFT

CALL ORDER : 531
 LETTING DATE :

CONTRACT ID : RS-29867-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
49	732-08419 MODULAR BLOCK WALL	5.500	SYS
50	732-08421 MODULAR BLOCK WALL ERECTION	5.500	SYS
51	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
52	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
53	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	78,090.000	LFT
54	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	78,090.000	LFT
55	801-06640 CONSTRUCTION SIGN, A	70.000	EACH
56	801-06710 FLASHING ARROW SIGN	10.000	DAY
57	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
58	801-07119 BARRICADE, III-B	60.000	LFT
59	805-01842 HANDHOLE, SIGNAL	1.000	EACH
60	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	1.000	EACH
61	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
62	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	2.000	EACH
63	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	200.000	LFT
64	805-78370 PEDESTRIAN PUSH BUTTON	2.000	EACH
65	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	3,074.000	LFT
66	805-78480 SIGNAL CABLE, 3C 14GA.	310.000	LFT
67	805-78485 SIGNAL CABLE, 5C 14GA.	520.000	LFT
68	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	500.000	LFT
69	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
70	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,148.000	LFT
71	805-79040 TRAFFIC SIGNAL MODERNIZATION	LUMP	LUMP
72	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000	EACH
73	807-98690 HANDHOLE ADJUSTED TO GRADE	7.000	EACH
74	808-06368 TRANSVERSE MARKING, REMOVE	126.000	LFT
75	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1,070.000	LFT
76	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	118,857.000	LFT
77	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	170.000	LFT
78	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	120.000	LFT
79	808-06716 LINE, REMOVE	13.000	LFT
80	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	10,780.000	LFT
81	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	58,587.000	LFT
82	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	219.000	LFT
83	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	204.000	LFT
84	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	8.000	EACH
85	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	6.000	EACH
86	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,134.000	EACH
87	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,147.000	EACH

CALL ORDER : 541

CONTRACT ID : RS-29869-A

LETTING DATE :

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-07039 FIELD OFFICE, B	8.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	8.000	MOS
6	105-08523 RADIO SERVICE	8.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	105-09198 LAPTOP COMPUTER SYSTEM	16.000	MOS
9	105-09199 FIELD OFFICE INTERNET SERVICE	8.000	MOS
10	109-08359 LIQUIDATED DAMAGES	1.000	DOL
11	109-08360 CONTRACT LIENS	1.000	DOL
12	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
13	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
14	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
15	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
16	202-02241 GUARDRAIL, REMOVE	565.000	LFT
17	202-02273 CENTER CURB, CONCRETE, REMOVE	200.000	SYS
18	202-02278 CURB, CONCRETE, REMOVE	136.000	LFT
19	202-93741 GUARD RAIL END TREATMENT, REMOVE	6.000	EACH
20	203-02000 EXCAVATION, COMMON	3,026.000	CYS
21	205-06934 TEMPORARY MULCHING	1.000	TON
22	205-06937 TEMPORARY SILT FENCE	325.000	LFT
23	211-07454 STRUCTURE BACKFILL	326.000	CYS
24	302-08562 COARSE AGGREGATE, 8	19.000	TON
25	303-01180 COMPACTED AGGREGATE, NO. 53	1,470.000	TON
26	303-60012 AGGREGATE, 2	805.000	TON
27	304-07491 HMA PATCHING, TYPE C	703.000	TON
28	306-08042 MILLING, SCARIFICATION/PROFILE	124,251.000	SYS
29	306-08043 MILLING, TRANSITION	2,462.000	SYS
30	306-08432 MILLING, APPROACH	4,749.000	SYS
31	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
32	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	10,454.000	TON
33	402-07452 HMA WEDGE AND LEVEL, TYPE C	1,146.000	TON
34	406-05520 ASPHALT FOR TACK COAT	37.000	TON
35	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
36	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
37	601-93346 GUARDRAIL CONNECTOR, AS	2.000	EACH
38	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
39	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	760.000	LFT
40	610-07488 HMA FOR APPROACHES, TYPE C	392.000	TON
41	616-02320 GEOTEXTILES	1,984.000	SYS
42	616-05689 RIPRAP, CLASS 2	156.000	TON
43	616-06405 RIPRAP, REVETMENT	6,020.000	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
45	621-06559 MULCHED SEEDING, R	228.000	SYS
46	715-02630 SAFETY METAL END SECTION, 6:1, 24 IN.	2.000	EACH
47	715-04231 SAFETY METAL END SECTION, 4:1, 57 IN. X 38 IN.	2.000	EACH

48 715-05123

PIPE, TYPE 1, CIRCULAR, 24 IN.

80.000

LFT

CALL ORDER : 541
 LETTING DATE :

CONTRACT ID : RS-29869-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	715-05244 PIPE, TYPE 1, DEFORMED, MIN. AREA 11.6 SQ. FT.	65.000	LFT
50	715-06268 PIPE, PERFORATED, POLYVINYL CHLORIDE, SEMICIRCULAR, 150 LFT	325.000	LFT
51	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	49.000	TON
52	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
53	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
54	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,010.000	LFT
55	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,010.000	LFT
56	801-06625 DETOUR ROUTE MARKER ASSEMBLY	18.000	EACH
57	801-06640 CONSTRUCTION SIGN, A	35.000	EACH
58	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
59	801-07118 BARRICADE, III-A	208.000	LFT
60	801-07119 BARRICADE, III-B	72.000	LFT
61	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
62	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	12.000	LFT
63	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	20.000	LFT
64	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	5.000	EACH
65	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	13.000	SFT
66	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	8.000	SFT
67	808-04097 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (AHEAD)	1.000	EACH
68	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	190.000	LFT
69	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	74.000	LFT
70	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	3,325.000	LFT
71	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	80,150.000	LFT
72	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	63,600.000	LFT
73	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	14.000	LFT
74	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	939.000	EACH
75	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	960.000	EACH
76	808-94435 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (STOP)	1.000	EACH

CALL ORDER : 551
 LETTING DATE :

CONTRACT ID : RS-29881-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	18.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	9.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	202-02278 CURB, CONCRETE, REMOVE	160.000	LFT
15	202-52710 SIDEWALK, CONCRETE, REMOVE	73.000	SYS
16	202-94749 CURB, ASPHALT, REMOVE	82.000	LFT
17	303-01180 COMPACTED AGGREGATE, NO. 53	2,913.000	TON
18	304-07490 HMA PATCHING, TYPE B	1,200.000	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN.	3,095.000	SYS
20	306-08042 MILLING, SCARIFICATION/PROFILE	389,685.000	SYS
21	306-08043 MILLING, TRANSITION	200.000	SYS
22	306-08432 MILLING, APPROACH	24,628.000	SYS
23	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
24	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	32,404.000	TON
25	402-07451 HMA WEDGE AND LEVEL, TYPE B	500.000	TON
26	406-05520 ASPHALT FOR TACK COAT	115.000	TON
27	604-06070 SIDEWALK, CONCRETE	73.000	SYS
28	604-06367 JOINT MATERIAL	20.000	LFT
29	604-07900 CURB RAMP, CONCRETE, F	67.000	SYS
30	605-01870 CURB, CONCRETE, A	74.000	LFT
31	605-06090 CURB, INTEGRAL, CONCRETE	86.000	LFT
32	605-08354 CURB	82.000	SYS
33	610-07487 HMA FOR APPROACHES, TYPE B	2,032.000	TON
34	615-01469 MONUMENT, SECTION CORNER, INSTALL	2.000	EACH
35	621-06574 SODDING	10.000	SYS
36	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	4.000	EACH
37	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	3.000	EACH
38	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
39	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
40	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	20,385.000	LFT
41	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	20,385.000	LFT
42	801-06640 CONSTRUCTION SIGN, A	79.000	EACH
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	802-91122 SIGN, GROUND MOUNTED, RESET	2.000	EACH
45	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	2.000	EACH
46	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,000.000	LFT
47	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	100.000	LFT
48	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	320.000	LFT

SCHEDULE OF PAY ITEMS

CALL ORDER : 551
 LETTING DATE :

CONTRACT ID : RS-29881-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	808-01296 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORDS (STOP AHEAD)	2.000	EACH
50	808-04723 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 4 IN.	288.000	LFT
51	808-05929 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 8 IN.	150.000	LFT
52	808-06694 LINE, PAINT, SOLID, YELLOW, 8 IN.	2,376.000	LFT
53	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	1,167.000	LFT
54	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	24,965.000	LFT
55	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	243,435.000	LFT
56	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	79,165.000	LFT
57	808-75262 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	713.000	LFT
58	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	567.000	LFT
59	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	6.000	EACH
60	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH
61	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2,907.000	EACH
62	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2,929.000	EACH
63	808-94435 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (STOP)	4.000	EACH

CALL ORDER : 561
 LETTING DATE :

CONTRACT ID : RS-29882-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	7.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	14.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	14.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	303-01180 COMPACTED AGGREGATE, NO. 53	2,670.000	TON
12	304-07490 HMA PATCHING, TYPE B	1,111.000	TON
13	306-08042 MILLING, SCARIFICATION/PROFILE	208,522.000	SYS
14	306-08043 MILLING, TRANSITION	3,615.000	SYS
15	306-08432 MILLING, APPROACH	13,395.000	SYS
16	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
17	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	17,203.000	TON
18	402-07451 HMA WEDGE AND LEVEL, TYPE B	400.000	TON
19	406-05520 ASPHALT FOR TACK COAT	62.000	TON
20	610-07487 HMA FOR APPROACHES, TYPE B	1,105.000	TON
21	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	2.000	EACH
22	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
23	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
24	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	9,904.000	LFT
25	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,904.000	LFT
26	801-06640 CONSTRUCTION SIGN, A	51.000	EACH
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	808-04097 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (AHEAD)	2.000	EACH
29	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	9,001.000	LFT
30	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	142,704.000	LFT
31	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	89,784.000	LFT
32	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	320.000	LFT
33	808-75072 TRANSVERSE MARKINGS, PAINT, SOLID, WHITE, CROSSHATCH LINE,	80.000	LFT
34	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	90.000	LFT
35	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,575.000	EACH
36	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,581.000	EACH
37	808-94435 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (STOP)	2.000	EACH
38	808-97323 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	288.000	LFT

CALL ORDER : 571
 LETTING DATE :

CONTRACT ID : RS-30214-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-07039 FIELD OFFICE, B	9.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	9.000	MOS
6	105-08523 RADIO SERVICE	18.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	105-09198 LAPTOP COMPUTER SYSTEM	27.000	MOS
9	105-09199 FIELD OFFICE INTERNET SERVICE	9.000	MOS
10	109-08359 LIQUIDATED DAMAGES	1.000	DOL
11	109-08360 CONTRACT LIENS	1.000	DOL
12	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
13	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
14	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
15	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
16	202-02241 GUARDRAIL, REMOVE	50.000	LFT
17	202-93741 GUARD RAIL END TREATMENT, REMOVE	1.000	EACH
18	303-01180 COMPACTED AGGREGATE, NO. 53	4,500.000	TON
19	304-07783 HMA PATCHING, TYPE D	2,825.000	TON
20	306-08034 MILLING, ASPHALT, 1 1/2 IN.	13,967.000	SYS
21	306-08036 MILLING, ASPHALT, 2 IN.	3,397.830	SYS
22	306-08038 MILLING, ASPHALT, 4 IN.	26,108.450	SYS
23	306-08042 MILLING, SCARIFICATION/PROFILE	334,029.000	SYS
24	306-08043 MILLING, TRANSITION	3,840.000	SYS
25	306-08432 MILLING, APPROACH	9,254.160	SYS
26	401-05467 MILLED HMA CORRUGATIONS	161,494.000	LFT
27	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
28	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	25,820.000	TON
29	401-07338 QC/QA-HMA, 1, 64, SURFACE, 12.5 mm	10,782.000	TON
30	401-09126 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm-PWL	42,461.000	TON
31	406-05520 ASPHALT FOR TACK COAT	182.190	TON
32	601-92948 GUARDRAIL, ADJUST HEIGHT	8,692.000	LFT
33	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
34	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	50.000	LFT
35	610-07788 HMA FOR APPROACHES, TYPE D	4,133.000	TON
36	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	13.000	TON
37	612-60410 DRILLED HOLE FOR UNDERSEAL	220.000	EACH
38	615-06505 MONUMENT, B	10.000	EACH
39	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	11.000	EACH
40	720-44000 CASTING, ADJUST TO GRADE	11.000	EACH
41	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
42	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
43	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	91,960.000	LFT
44	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	91,960.000	LFT
45	801-06640 CONSTRUCTION SIGN, A	49.000	EACH
46	801-06710 FLASHING ARROW SIGN	300.000	DAY
47	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
48	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN.	393.000	LFT

CALL ORDER : 571
 LETTING DATE :

CONTRACT ID : RS-30214-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	805-05905 ATR STATION- 4 LANE	1.000	EACH
50	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	4,676.000	LFT
51	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	4,676.000	LFT
52	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	160.000	LFT
53	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	816.000	LFT
54	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	606.000	LFT
55	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	4.000	EACH
56	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	22,250.000	LFT
57	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	101,835.000	LFT
58	808-06716 LINE, REMOVE	1,582.000	LFT
59	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	1.000	EACH
60	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	1.000	EACH
61	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	90,819.000	LFT
62	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
63	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH
64	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,330.000	EACH

CALL ORDER : 581
 LETTING DATE :

CONTRACT ID : B -26680-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	9.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	9.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	9.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	3,519.000	CYS
14	203-02070 BORROW	5,527.000	CYS
15	203-51223 EXCAVATION, WATERWAY	970.000	CYS
16	205-06936 TEMPORARY SEDIMENT TRAP	127.000	TON
17	205-06937 TEMPORARY SILT FENCE	1,381.000	LFT
18	205-06938 TEMPORARY SLOPE DRAIN	60.000	LFT
19	207-08266 SUBGRADE TREATMENT, TYPE III	2,245.000	SYS
20	211-06467 AGGREGATE FOR END BENT BACKFILL	105.700	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	497.000	TON
22	302-07455 DENSE GRADED SUBBASE	30.000	CYS
23	303-07449 COMPACTED AGGREGATE, NO. 73	278.000	TON
24	402-07432 HMA SURFACE, TYPE A	124.000	TON
25	402-07435 HMA INTERMEDIATE, TYPE A	218.000	TON
26	402-07440 HMA BASE, TYPE A	200.000	TON
27	406-05521 ASPHALT FOR TACK COAT	2,780.000	SYS
28	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
29	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
30	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,175.000	LFT
31	603-06040 FENCE, FARM FIELD, 47 IN.	1,405.000	LFT
32	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	178.000	SYS
33	616-02320 GEOTEXTILES	3,341.000	SYS
34	616-05688 RIPRAP, CLASS 1	2,527.000	TON
35	616-06405 RIPRAP, REVETMENT	375.000	TON
36	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
37	621-02356 SEEDING, WETLAND	10.000	LBS
38	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	2,614.000	SYS
39	621-02770 EROSION CONTROL BLANKET	2,390.700	SYS
40	621-06545 FERTILIZER	0.080	TON
41	621-06559 MULCHED SEEDING, R	2,614.000	SYS
42	621-06565 MULCHING MATERIAL	0.420	TON
43	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
44	622-91786 SEEDLING	378.000	EACH
45	701-51195 PILE, STEEL H, HP 12 X 53	1,047.000	LFT
46	701-93633 OVERSIZED PREDRILLED PILE HOLES	185.000	LFT
47	703-51030 REINFORCING STEEL	483.000	LBS
48	703-51032 REINFORCING STEEL, EPOXY COATED	37,372.000	LBS

CALL ORDER : 581
 LETTING DATE :

CONTRACT ID : B -26680-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	704-51002 CONCRETE, C, SUPERSTRUCTURE	221.600	CYS
50	706-06344 RAILING, TS-1	237.500	LFT
51	707-08476 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	520.250	LFT
52	709-51821 SURFACE SEAL	LUMP	LUMP
53	715-05407 PIPE, END BENT DRAIN, 6 IN.	181.000	LFT
54	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
55	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
56	801-06625 DETOUR ROUTE MARKER ASSEMBLY	9.000	EACH
57	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
58	801-07118 BARRICADE, III-A	48.000	LFT
59	801-07119 BARRICADE, III-B	24.000	LFT
60	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	9.000	SFT
61	802-76065 SIGN POST, B	24.000	LFT
62	804-06770 DELINEATOR POST	2.000	EACH

CALL ORDER : 601
 LETTING DATE :

CONTRACT ID : B -27185-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	12.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	12.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02278 CURB, CONCRETE, REMOVE	150.000	LFT
13	202-02279 CURB AND GUTTER, REMOVE	78.000	LFT
14	202-52710 SIDEWALK, CONCRETE, REMOVE	100.000	SYS
15	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
16	203-02000 EXCAVATION, COMMON	1,189.000	CYS
17	203-02070 BORROW	177.000	CYS
18	204-02290 SETTLEMENT PLATE	4.000	EACH
19	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
20	205-06937 TEMPORARY SILT FENCE	2,290.000	LFT
21	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	571.000	CYS
22	210-07811 FIBER	LUMP	LUMP
23	211-09264 STRUCTURE BACKFILL, TYPE 1	3,985.000	CYS
24	303-01180 COMPACTED AGGREGATE, NO. 53	750.000	TON
25	303-07449 COMPACTED AGGREGATE, NO. 73	10.000	TON
26	304-07489 HMA PATCHING, TYPE A	34.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN.	540.000	SYS
28	402-07432 HMA SURFACE, TYPE A	190.000	TON
29	402-07435 HMA INTERMEDIATE, TYPE A	240.000	TON
30	404-05514 SEAL COAT, 5	25.000	SYS
31	406-05521 ASPHALT FOR TACK COAT	2,285.000	SYS
32	601-95344 HANDRAIL, PEDESTRIAN	1,502.000	LFT
33	601-95344 HANDRAIL, PEDESTRIAN	401.000	LFT
34	603-02736 FENCE, WOOD, REMOVE AND RESET	1,125.000	LFT
35	604-07569 PAVERS	196.000	SYS
36	604-91531 SIDEWALK, CONCRETE, 4 IN.	55.000	SYS
37	605-04742 WALL	LUMP	LUMP
38	605-06140 CURB AND GUTTER, CONCRETE	78.000	LFT
39	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	31.400	SYS
40	616-02320 GEOTEXTILES	29.000	SYS
41	616-06405 RIPRAP, REVETMENT	14.000	TON
42	621-02770 EROSION CONTROL BLANKET	240.000	SYS
43	621-06560 MULCHED SEEDING, U	5,610.000	SYS
44	621-06575 SODDING, NURSERY	1,541.000	SYS
45	622-05605 PLANT, ANNUAL	2.000	EACH
46	622-05654 PLANT, PERENNIAL	28.000	EACH
47	701-93575 PILE, STEEL H, HP 14 X 73	4,726.000	LFT
48	701-93633 OVERSIZED PREDRILLED PILE HOLES	2,432.000	LFT

CALL ORDER : 601
 LETTING DATE :

CONTRACT ID : B -27185-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE CONSTRUCTION		
49	701-98647 PILE, CONCRETE, STEEL SHELL ENCASED, 0.203 IN., 14 IN.	1,305.000	LFT
50	702-51005 CONCRETE, A, SUBSTRUCTURE	180.000	CYS
51	702-51015 CONCRETE, B, FOOTINGS	211.600	CYS
52	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	1,288.000	LBS
53	703-06029 REINFORCING BARS, EPOXY COATED	39,236.000	LBS
54	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	30.000	EACH
55	704-51002 CONCRETE, C, SUPERSTRUCTURE	41.600	CYS
56	709-51821 SURFACE SEAL	LUMP	LUMP
57	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP
58	711-51038 STRUCTURAL STEEL	LUMP	LUMP
59	711-91981 TIE ROD	272.000	EACH
60	712-03812 BENCH	8.000	EACH
61	714-44240 CONCRETE, A, STRUCTURES	4.900	CYS
62	715-05136 PIPE, TYPE 1, CIRCULAR, 72 IN.	36.000	LFT
63	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	156.000	LFT
64	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	110.000	LFT
65	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	36.500	LFT
66	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	191.000	LFT
67	715-09191 PIPE, TYPE 2, DEFORMED, MIN. AREA 7.4 SFT.	48.000	LFT
68	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
69	715-46010 PIPE END SECTION, 18 IN.	1.000	EACH
70	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
71	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
72	720-45235 CATCH BASIN, E7	2.000	EACH
73	720-94612 MANHOLE, K4	1.000	EACH
74	724-51885 STRUCTURAL EXPANSION JOINT, BS6	29.800	LFT
75	726-92406 BEARING ASSEMBLY, ELASTOMERIC	6.000	EACH
76	728-98377 MASONRY COATING	LUMP	LUMP
77	731-93945 FACE PANELS, CONCRETE	16,028.500	SFT
78	731-93946 WALL ERECTION	16,028.500	SFT
79	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
80	801-06640 CONSTRUCTION SIGN, A	9.000	EACH
81	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
82	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
83	801-07118 BARRICADE, III-A	48.000	LFT
84	801-07119 BARRICADE, III-B	48.000	LFT
85	802-91122 SIGN, GROUND MOUNTED, RESET	6.000	EACH
86	807-04962 LIGHT	4.000	EACH
87	807-86810 SERVICE POINT, II	1.000	EACH
88	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	45.000	LFT
89	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	1,675.000	LFT
90	808-06716 LINE, REMOVE	138.000	LFT
91	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	833.000	LFT
92	808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	194.000	LFT

CALL ORDER : 605
 LETTING DATE :

CONTRACT ID : B -28681-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	15.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	30.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	30.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	15.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
17	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
18	203-02000 EXCAVATION, COMMON	1,380.000	CYS
19	203-02070 BORROW	4,360.000	CYS
20	203-51223 EXCAVATION, WATERWAY	20.000	CYS
21	205-06932 TEMPORARY CHECK DAM, STRAW BALES	224.000	LFT
22	205-06936 TEMPORARY SEDIMENT TRAP	36.000	TON
23	205-06937 TEMPORARY SILT FENCE	1,800.000	LFT
24	206-51215 EXCAVATION, X	71.000	CYS
25	206-51220 EXCAVATION, WET	200.000	CYS
26	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	445.000	CYS
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,470.000	SYS
28	211-06467 AGGREGATE FOR END BENT BACKFILL	246.000	CYS
29	211-07454 STRUCTURE BACKFILL	6.000	CYS
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,480.000	TON
31	302-07455 DENSE GRADED SUBBASE	112.000	CYS
32	402-07432 HMA SURFACE, TYPE A	270.000	TON
33	402-07435 HMA INTERMEDIATE, TYPE A	445.000	TON
34	406-05521 ASPHALT FOR TACK COAT	3,130.000	SYS
35	601-01854 GUARDRAIL TRANSITION, 12 FT. 6 IN. LONG	8.000	EACH
36	601-06037 GUARDRAIL END TREATMENT, I	8.000	EACH
37	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	500.000	LFT
38	603-06040 FENCE, FARM FIELD, 47 IN.	1,436.000	LFT
39	603-91748 FENCE GATE, FARM FIELD, 47 IN. X 16 FT.	2.000	EACH
40	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	323.000	SYS
41	610-07486 HMA FOR APPROACHES, TYPE A	20.000	TON
42	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	2.000	EACH
43	615-06505 MONUMENT, B	4.000	EACH
44	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
45	616-02320 GEOTEXTILES	1,690.000	SYS
46	616-05688 RIPRAP, CLASS 1	1,260.000	TON
47	616-06405 RIPRAP, REVETMENT	134.000	TON
48	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH

CALL ORDER : 605
 LETTING DATE :

CONTRACT ID : B -28681-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	621-02770 EROSION CONTROL BLANKET	1,690.000	SYS
50	621-03787 SEED MIXTURE, D	5.000	LBS
51	621-06545 FERTILIZER	0.600	TON
52	621-06553 SEED MIXTURE, R	235.000	LBS
53	621-06557 SEED MIXTURE, T	205.000	LBS
54	621-06565 MULCHING MATERIAL	3.200	TON
55	621-06567 WATER	2.000	KGAL
56	621-06574 SODDING	507.000	SYS
57	622-52436 SIGN, DO NOT MOW OR SPRAY	2.000	EACH
58	622-91786 SEEDLING	50.000	EACH
59	702-51005 CONCRETE, A, SUBSTRUCTURE	119.000	CYS
60	702-51015 CONCRETE, B, FOOTINGS	63.700	CYS
61	703-51030 REINFORCING STEEL	21,950.000	LBS
62	703-51032 REINFORCING STEEL, EPOXY COATED	25,300.000	LBS
63	704-51002 CONCRETE, C, SUPERSTRUCTURE	79.700	CYS
64	706-91957 BRIDGE RAILING, THRIE BEAM	281.250	LFT
65	707-05972 CB 21, 21 IN X 36 IN	572.000	SFT
66	707-05973 STRUCTURAL MEMBERS, CONCRETE BOX BEAM, CB, 27 IN. X 36 IN.	625.000	SFT
67	709-51821 SURFACE SEAL	LUMP	LUMP
68	709-51821 SURFACE SEAL	LUMP	LUMP
69	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	44.000	LFT
70	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN.	48.000	LFT
71	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
72	715-46010 PIPE END SECTION, 18 IN.	2.000	EACH
73	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
74	801-06625 DETOUR ROUTE MARKER ASSEMBLY	3.000	EACH
75	801-06640 CONSTRUCTION SIGN, A	7.000	EACH
76	801-07118 BARRICADE, III-A	108.000	LFT
77	801-07119 BARRICADE, III-B	48.000	LFT
78	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	18.900	SFT
79	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	8.000	SFT
80	802-76055 SIGN POST, A	96.000	LFT

CALL ORDER : 611
 LETTING DATE :

CONTRACT ID : B -29058-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-07038 FIELD OFFICE, A	6.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
6	105-08523 RADIO SERVICE	6.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
9	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
10	109-08359 LIQUIDATED DAMAGES	1.000	DOL
11	109-08360 CONTRACT LIENS	1.000	DOL
12	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
13	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-02189 BRIDGE IDENTIFICATION MARKERS, REMOVE AND RESET	1.000	EACH
17	202-02241 GUARDRAIL, REMOVE	415.000	LFT
18	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
19	203-02000 EXCAVATION, COMMON	254.000	CYS
20	205-06932 TEMPORARY CHECK DAM, STRAW BALES	50.000	LFT
21	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
22	207-08265 SUBGRADE TREATMENT, TYPE IIA	1,347.900	SYS
23	211-02050 B BORROW	5.200	CYS
24	211-09268 STRUCTURE BACKFILL, TYPE 5	411.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	552.000	TON
26	306-08036 MILLING, ASPHALT, 2 IN.	1,808.000	SYS
27	306-08043 MILLING, TRANSITION	320.000	SYS
28	402-07433 HMA SURFACE, TYPE B	257.600	TON
29	402-07438 HMA INTERMEDIATE, TYPE B	399.100	TON
30	402-07441 HMA BASE, TYPE B	472.200	TON
31	406-05520 ASPHALT FOR TACK COAT	1.610	TON
32	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
33	601-02800 GUARDRAIL TRANSITION, TGT	4.000	EACH
34	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
36	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	525.000	LFT
37	610-07486 HMA FOR APPROACHES, TYPE A	43.400	TON
38	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
39	616-02320 GEOTEXTILES	526.000	SYS
40	616-05688 RIPRAP, CLASS 1	526.000	TON
41	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
42	621-06559 MULCHED SEEDING, R	975.000	SYS
43	622-91786 SEEDLING	85.000	EACH
44	706-08352 RAILING, CF-1	66.000	LFT
45	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN.	30.000	LFT
46	715-06471 PIPE END SECTION, MIN. AREA 3.3 SQ. FT.	2.000	EACH
47	715-08243 PIPE, TYPE 3, DEFORMED, MIN. AREA 3.3 SQ. FT.	41.500	LFT
48	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH

CALL ORDER : 611
 LETTING DATE :

CONTRACT ID : B -29058-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	723-08608 WINGWALL	834.000	SFT
50	723-09333 STRUCTURE, PRECAST THREE-SIDED,	50.400	LFT
51	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
52	801-06625 DETOUR ROUTE MARKER ASSEMBLY	24.000	EACH
53	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
54	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
55	801-07119 BARRICADE, III-B	96.000	LFT
56	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,776.000	LFT
57	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	222.000	LFT
58	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,652.000	LFT
59	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	20.000	EACH
60	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	20.000	EACH

CALL ORDER : 621
 LETTING DATE :

CONTRACT ID : B -29079-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REHABILITATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	6.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02240 PAVEMENT REMOVAL	216.000	SYS
16	202-02241 GUARDRAIL, REMOVE	324.000	LFT
17	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
18	203-02000 EXCAVATION, COMMON	24.000	CYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	97.000	SYS
20	211-07454 STRUCTURE BACKFILL	2.000	CYS
21	302-07455 DENSE GRADED SUBBASE	36.000	CYS
22	306-08043 MILLING, TRANSITION	880.000	SYS
23	406-05521 ASPHALT FOR TACK COAT	1,075.000	SYS
24	601-01128 GUARDRAIL TRANSITION TYPE WGB	2.000	EACH
25	601-01128 GUARDRAIL TRANSITION TYPE WGB	2.000	EACH
26	601-06234 IMPACT ATTENUATOR, R1, W1, TL-2	3.000	EACH
27	601-09238 HAND DIG GUARDRAIL POST HOLES	5.000	EACH
28	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
29	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	212.500	LFT
30	602-06729 BARRIER DELINEATOR	4.000	EACH
31	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	216.000	SYS
32	610-07487 HMA FOR APPROACHES, TYPE B	107.000	TON
33	616-02320 GEOTEXTILES	138.000	SYS
34	616-06405 RIPRAP, REVETMENT	130.000	TON
35	619-93790 CLEAN AND EPOXY COAT EXISTING PILES	LUMP	LUMP
36	621-06574 SODDING	24.000	SYS
37	621-06575 SODDING, NURSERY	54.000	SYS
38	702-04433 FLOOR DRAIN, PVC, 6 IN.	6.000	EACH
39	702-51863 FIELD DRILLED HOLE IN CONCRETE	92.000	EACH
40	703-06029 REINFORCING BARS, EPOXY COATED	29,142.000	LBS
41	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	68.000	EACH
42	704-51002 CONCRETE, C, SUPERSTRUCTURE	50.000	CYS
43	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	4.000	EACH
44	706-51020 CONCRETE, C, RAILING	10.600	CYS
45	709-51821 SURFACE SEAL	LUMP	LUMP
46	714-44240 CONCRETE, A, STRUCTURES	1.100	CYS
47	715-05597 PIPE EXTENSION, CIRCULAR, 24 IN.	10.000	LFT
48	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	60.000	SFT

SCHEDULE OF PAY ITEMS

CALL ORDER : 621
 LETTING DATE :

CONTRACT ID : B -29079-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
49	722-51842 BRIDGE DECK OVERLAY	418.000	SYS
50	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	9.200	CYS
51	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	160.000	SFT
52	722-60824 SURFACE MILLING	347.000	SYS
53	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
54	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
55	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,576.000	LFT
56	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	24.000	LFT
57	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
58	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
59	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
60	801-07119 BARRICADE, III-B	60.000	LFT
61	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	209.000	LFT
62	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	268.000	LFT
63	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	352.000	LFT
64	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,408.000	LFT
65	808-06716 LINE, REMOVE	1,078.000	LFT

CALL ORDER : 631
 LETTING DATE :

CONTRACT ID : B -29169-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHAB		
1	105-07040 FIELD OFFICE, C	12.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	105-09198 LAPTOP COMPUTER SYSTEM	24.000	MOS
6	105-09199 FIELD OFFICE INTERNET SERVICE	12.000	MOS
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-02240 PAVEMENT REMOVAL	109.000	SYS
15	202-02241 GUARDRAIL, REMOVE	138.000	LFT
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	203-08607 LINEAR GRADING	200.000	LFT
18	213-08058 FLOWABLE BACKFILL	10.000	CYS
19	302-07455 DENSE GRADED SUBBASE	16.000	CYS
20	402-07450 HMA WEDGE AND LEVEL, TYPE A	22.000	TON
21	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
22	601-06035 GUARDRAIL, RESET	100.000	LFT
23	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	38.000	LFT
24	603-06040 FENCE, FARM FIELD, 47 IN.	12.000	LFT
25	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	121.000	SYS
26	615-06520 MONUMENT, RE-ESTABLISH	1.000	EACH
27	616-02320 GEOTEXTILES	108.000	SYS
28	616-02842 RIPRAP, DITCH	61.000	TON
29	616-51367 SLOPEWALL, CONCRETE, 4 IN.	4.000	SYS
30	616-93772 INSPECTION HOLE	4.000	EACH
31	621-06559 MULCHED SEEDING, R	1,100.000	SYS
32	702-51005 CONCRETE, A, SUBSTRUCTURE	2.000	CYS
33	702-51863 FIELD DRILLED HOLE IN CONCRETE	690.000	EACH
34	703-51032 REINFORCING STEEL, EPOXY COATED	19,926.000	LBS
35	704-51002 CONCRETE, C, SUPERSTRUCTURE	17.000	CYS
36	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
37	706-51025 CONCRETE, C, RAILING	423.000	LFT
38	709-51821 SURFACE SEAL	LUMP	LUMP
39	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	254.000	SFT
40	722-51842 BRIDGE DECK OVERLAY	623.000	SYS
41	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	5.000	CYS
42	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	1,269.000	SFT
43	722-60824 SURFACE MILLING	564.000	SYS
44	724-03276 EXPANSION JOINT SEALING SYSTEM	60.000	LFT
45	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
46	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
47	801-06625 DETOUR ROUTE MARKER ASSEMBLY	14.000	EACH
48	801-06640 CONSTRUCTION SIGN, A	12.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 631
 LETTING DATE :

CONTRACT ID : B -29169-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHAB		
49 801-06710	FLASHING ARROW SIGN	15.000	DAY
50 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
51 801-07118	BARRICADE, III-A	56.000	LFT
52 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	752.000	LFT
53 808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	752.000	LFT

CALL ORDER : 641
 LETTING DATE :

CONTRACT ID : B -29288-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	4.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	105-09198 LAPTOP COMPUTER SYSTEM	4.000	MOS
6	105-09291 MOBILE BROADBAND ACCESS	4.000	MOS
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	80.000	SYS
14	202-02241 GUARDRAIL, REMOVE	526.000	LFT
15	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
16	203-02000 EXCAVATION, COMMON	105.000	CYS
17	203-02070 BORROW	540.000	CYS
18	205-06932 TEMPORARY CHECK DAM, STRAW BALES	88.000	LFT
19	205-06937 TEMPORARY SILT FENCE	627.000	LFT
20	207-08263 SUBGRADE TREATMENT, TYPE IA	730.400	SYS
21	211-02050 B BORROW	41.000	CYS
22	211-09268 STRUCTURE BACKFILL, TYPE 5	500.000	CYS
23	303-01180 COMPACTED AGGREGATE, NO. 53	261.000	TON
24	306-08043 MILLING, TRANSITION	560.000	SYS
25	402-07434 HMA SURFACE, TYPE C	147.000	TON
26	402-07439 HMA INTERMEDIATE, TYPE C	178.000	TON
27	402-07442 HMA BASE, TYPE C	207.000	TON
28	406-05520 ASPHALT FOR TACK COAT	0.760	TON
29	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
30	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
31	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	87.500	LFT
32	615-06490 RIGHT OF WAY MARKER	8.000	EACH
33	615-06500 MONUMENT, A	3.000	EACH
34	616-02320 GEOTEXTILES	272.000	SYS
35	616-05688 RIPRAP, CLASS 1	293.000	TON
36	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
37	621-06559 MULCHED SEEDING, R	1,032.000	SYS
38	723-06660 WINGWALL	99.000	SYS
39	723-07593 STRUCTURE, PRECAST THREE-SIDED, 240 IN. X 124 IN.	50.000	LFT
40	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
41	801-06625 DETOUR ROUTE MARKER ASSEMBLY	30.000	EACH
42	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	801-07118 BARRICADE, III-A	48.000	LFT
45	801-07119 BARRICADE, III-B	48.000	LFT
46	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	936.000	LFT
47	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	936.000	LFT
48	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	12.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 641
LETTING DATE :

CONTRACT ID : B -29288-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
49 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	11.000	EACH

CALL ORDER : 651
 LETTING DATE :

CONTRACT ID : B -29307-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	18.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	36.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	18.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	18.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-02189 BRIDGE IDENTIFICATION MARKERS, REMOVE AND RESET	1.000	EACH
17	202-02240 PAVEMENT REMOVAL	2,650.000	SYS
18	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
19	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
20	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
21	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
22	202-96133 PIPE, REMOVE	200.000	LFT
23	203-02000 EXCAVATION, COMMON	26,692.000	CYS
24	203-02010 EXCAVATION, ROCK	5,626.000	CYS
25	203-02070 BORROW	26,700.000	CYS
26	203-51223 EXCAVATION, WATERWAY	275.000	CYS
27	205-03371 SEDIMENT, REMOVE	36.000	CYS
28	205-04931 SEDIMENT TRAP	4.000	EACH
29	205-06930 SPLASHPAD, RIPRAP	23.000	TON
30	205-06937 TEMPORARY SILT FENCE	500.000	LFT
31	205-06938 TEMPORARY SLOPE DRAIN	900.000	LFT
32	206-51215 EXCAVATION, X	91.000	CYS
33	207-08263 SUBGRADE TREATMENT, TYPE IA	5,317.000	SYS
34	207-08266 SUBGRADE TREATMENT, TYPE III	7,319.000	SYS
35	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,735.000	SYS
36	211-06467 AGGREGATE FOR END BENT BACKFILL	44.000	CYS
37	211-07454 STRUCTURE BACKFILL	12.000	CYS
38	213-52830 FLOWABLE MORTAR	13.000	CYS
39	302-07455 DENSE GRADED SUBBASE	36.000	CYS
40	303-01180 COMPACTED AGGREGATE, NO. 53	1,252.000	TON
41	306-08034 MILLING, ASPHALT, 1 1/2 IN.	330.000	SYS
42	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	343.000	TON
43	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	572.000	TON
44	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	2,772.000	TON
45	402-07432 HMA SURFACE, TYPE A	865.000	TON
46	402-07433 HMA SURFACE, TYPE B	24.000	TON
47	402-07435 HMA INTERMEDIATE, TYPE A	1,039.000	TON
48	402-07438 HMA INTERMEDIATE, TYPE B	56.000	TON

CALL ORDER : 651
 LETTING DATE :

CONTRACT ID : B -29307-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	402-07440 HMA BASE, TYPE A	3,814.000	TON
50	402-07450 HMA WEDGE AND LEVEL, TYPE A	15.000	TON
51	402-07451 HMA WEDGE AND LEVEL, TYPE B	80.000	TON
52	404-05511 SEAL COAT, 2	2,914.000	SYS
53	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
54	601-01626 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 2	1.000	EACH
55	601-02206 TEMPORARY GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	3,430.000	LFT
56	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
57	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
58	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	375.000	LFT
59	602-06729 BARRIER DELINEATOR	10.000	EACH
60	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	227.000	SYS
61	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
62	611-08233 MAILBOX ASSEMBLY, DOUBLE, RESET	1.000	EACH
63	615-06490 RIGHT OF WAY MARKER	23.000	EACH
64	615-06505 MONUMENT, B	3.000	EACH
65	616-02320 GEOTEXTILES	3,559.000	SYS
66	616-02842 RIPRAP, DITCH	1,032.000	TON
67	616-05688 RIPRAP, CLASS 1	1,600.000	TON
68	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
69	621-06553 SEED MIXTURE, R	1,250.000	LBS
70	621-06557 SEED MIXTURE, T	600.000	LBS
71	621-06574 SODDING	598.000	SYS
72	621-52448 SIGN, DO NOT SPRAY	4.000	EACH
73	622-91786 SEEDLING	220.000	EACH
74	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
75	701-51195 PILE, STEEL H, HP 12 X 53	260.000	LFT
76	701-91792 PILE TIP, STEEL H	10.000	EACH
77	702-51015 CONCRETE, B, FOOTINGS	42.000	CYS
78	702-92857 CONCRETE, C, SUBSTRUCTURE	207.000	CYS
79	703-51030 REINFORCING STEEL	33,580.000	LBS
80	703-51032 REINFORCING STEEL, EPOXY COATED	101,315.000	LBS
81	704-51002 CONCRETE, C, SUPERSTRUCTURE	275.000	CYS
82	704-51106 DECK DRAIN	2.000	EACH
83	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
84	706-51020 CONCRETE, C, RAILING	38.000	CYS
85	707-07605 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 54 IN. X 48 IN.	975.000	LFT
86	709-51821 SURFACE SEAL	LUMP	LUMP
87	711-51035 STRUCTURAL STEEL	608.000	LBS
88	711-95290 FIELD WELDING	52.000	LFT
89	713-51335 TEMPORARY BRIDGE AND APPROACHES	LUMP	LUMP
90	714-26703 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 6 FT. X 4 FT.	105.000	LFT
91	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	4.000	EACH
92	715-03584 SAFETY METAL END SECTION, 4:1, 18 IN.	2.000	EACH
93	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	80.000	LFT
94	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN.	40.000	LFT
95	715-05407 PIPE, END BENT DRAIN, 6 IN.	150.000	LFT
96	801-03290 CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 651
 LETTING DATE :

CONTRACT ID : B -29307-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
97	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
98	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
99	801-06645 CONSTRUCTION SIGN, B	14.000	EACH
100	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
101	801-07118 BARRICADE, III-A	68.000	LFT
102	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	1.000	EACH
103	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	2,000.000	LFT
104	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	9,930.000	LFT
105	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	5,960.000	LFT
106	808-75994 PRISMATIC REFLECTOR	25.000	EACH
107	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	45.000	EACH
108	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	25.000	EACH

CALL ORDER : 661
 LETTING DATE :

CONTRACT ID : B -29559-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ARCH RECONSTRUCTION OR REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	8.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	16.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	8.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-51133 RAILING, REMOVE	118.500	LFT
13	203-02000 EXCAVATION, COMMON	65.000	CYS
14	205-06937 TEMPORARY SILT FENCE	240.000	LFT
15	303-01180 COMPACTED AGGREGATE, NO. 53	55.000	TON
16	303-09309 SYNTHETIC SUBSURFACE DRAINAGE LAYER	165.000	SYS
17	404-05508 ASPHALT FOR SEAL COAT	0.200	TON
18	603-03692 FENCE, WOOD	173.000	LFT
19	616-02320 GEOTEXTILES	50.000	SYS
20	616-06405 RIPRAP, REVETMENT	16.000	TON
21	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
22	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	240.000	SYS
23	621-06559 MULCHED SEEDING, R	240.000	SYS
24	702-51863 FIELD DRILLED HOLE IN CONCRETE	112.000	EACH
25	703-51030 REINFORCING STEEL	300.000	LBS
26	703-51032 REINFORCING STEEL, EPOXY COATED	2,570.000	LBS
27	704-51002 CONCRETE, C, SUPERSTRUCTURE	28.100	CYS
28	708-51813 PNEUMATICALLY PLACED MORTAR	1,015.000	SFT
29	708-51814 WELDED STEEL WIRE FABRIC	900.000	SFT
30	709-51821 SURFACE SEAL	LUMP	LUMP
31	711-91996 REPAIR EXISTING STRUCTURE	LUMP	LUMP
32	715-91361 PIPE, PVC, 6 IN.	16.000	LFT
33	715-92037 PIPE, PVC, 4 IN.	200.000	LFT
34	715-92537 PIPE, PVC, 8 IN.	78.000	LFT
35	727-90308 EPOXY INJECTION, CRACK PREPARATION	130.000	LFT
36	727-90309 EPOXY INJECTION, EPOXY MATERIAL	14.000	GAL
37	727-93560 EPOXY INJECTION, FURNISHING EQUIPMENT	LUMP	LUMP
38	801-07118 BARRICADE, III-A	48.000	LFT

CALL ORDER : 671
 LETTING DATE :

CONTRACT ID : B -29601-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	10.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	10.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-51133 RAILING, REMOVE	240.000	m
15	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
16	203-02000 EXCAVATION, COMMON	42.000	m3
17	203-02070 BORROW	1,068.000	m3
18	205-03371 SEDIMENT REMOVE	2.000	m3
19	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	4.400	Mg
20	205-06937 TEMPORARY SILT FENCE	230.000	m
21	206-51817 SHEET PILING, STEEL	45.000	m2
22	207-08268 SUBGRADE TREATMENT, TYPE IV	850.000	m2
23	210-07256 RETROFIT	1.000	EACH
24	210-07256 RETROFIT	1.000	EACH
25	210-08047 RIVET	1,118.000	EACH
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	453.000	Mg
27	402-07432 HMA SURFACE, TYPE A	14.000	Mg
28	402-07435 HMA INTERMEDIATE, TYPE A	23.000	Mg
29	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 1.905 m SPACING	9.500	m
30	601-02800 GUARDRAIL TRANSITION, TGT	4.000	EACH
31	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
32	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	49.500	m
33	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
34	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
35	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
36	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
37	621-06559 MULCHED SEEDING, R	2,026.500	m2
38	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
39	622-91786 SEEDLING	40.000	EACH
40	706-06347 RAILING, CF-1	232.000	m
41	710-51870 REPOINTING MASONRY IN STRUCTURES	216.000	m2
42	711-04297 STRUCTURAL STEEL, FIELD CUT	50,000.000	mm2
43	711-51038 STRUCTURAL STEEL	LUMP	LUMP
44	711-51866 RIVET, REMOVE	1,118.000	EACH
45	711-91149 STRAIGHTEN STEEL BEAM	LUMP	LUMP
46	711-95290 FIELD WELDING	4.000	m
47	711-96479 BOLT, REMOVE	25.000	EACH
48	712-06386 PLANK FLOORS, SINGLE PLY	550.000	m2

CALL ORDER : 671
 LETTING DATE :

CONTRACT ID : B -29601-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
49	712-94725 STRUCTURAL TIMBER	0.300	m3
50	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
51	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
52	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
53	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
54	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
55	801-07118 BARRICADE, III-A	15.000	m
56	801-07119 BARRICADE, III-B	12.000	m
57	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	26.000	m
58	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	0.900	m2
59	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	2.700	m2

CALL ORDER : 681
 LETTING DATE :

CONTRACT ID : B -29604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	11.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	11.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	11.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	11.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	203-02000 EXCAVATION, COMMON	429.000	CYS
18	203-02070 BORROW	10,403.000	CYS
19	203-51223 EXCAVATION, WATERWAY	593.000	CYS
20	204-02290 SETTLEMENT PLATE	2.000	EACH
21	204-08396 STANDPIPE PIEZOMETER	2.000	EACH
22	204-08397 WATER MONITORING BOREHOLE	2.000	EACH
23	204-08415 STAKES, SETTLEMENT	4.000	EACH
24	205-03371 SEDIMENT, REMOVE	75.000	CYS
25	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
26	205-06937 TEMPORARY SILT FENCE	1,397.000	LFT
27	205-06938 TEMPORARY SLOPE DRAIN	180.000	LFT
28	206-51220 EXCAVATION, WET	213.200	CYS
29	206-51235 COFFERDAM	LUMP	LUMP
30	207-08266 SUBGRADE TREATMENT, TYPE III	1,808.000	SYS
31	210-07006 RESET	LUMP	LUMP
32	211-06467 AGGREGATE FOR END BENT BACKFILL	67.000	CYS
33	211-07454 STRUCTURE BACKFILL	155.300	CYS
34	213-52830 FLOWABLE MORTAR	15.000	CYS
35	214-07203 GEOGRID, II	3,818.000	SYS
36	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,119.000	TON
37	302-07455 DENSE GRADED SUBBASE	39.100	CYS
38	303-01180 COMPACTED AGGREGATE, NO. 53	240.000	TON
39	303-07449 COMPACTED AGGREGATE, NO. 73	60.000	TON
40	402-07432 HMA SURFACE, TYPE A	185.300	TON
41	402-07435 HMA INTERMEDIATE, TYPE A	179.000	TON
42	404-05514 SEAL COAT, 5	784.000	SYS
43	406-05521 ASPHALT FOR TACK COAT	1,957.000	SYS
44	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
45	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
46	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	381.250	LFT
47	602-06729 BARRIER DELINEATOR	12.000	EACH
48	605-06145 CURB AND GUTTER, B, CONCRETE	250.000	LFT

CALL ORDER : 681
 LETTING DATE :

CONTRACT ID : B -29604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	610-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	235.000	SYS
50	610-08446 PCCP FOR APPROACHES, 6 IN.	35.200	SYS
51	615-06490 RIGHT OF WAY MARKER	8.000	EACH
52	615-06505 MONUMENT, B	4.000	EACH
53	616-02320 GEOTEXTILES	1,901.000	SYS
54	616-05688 RIPRAP, CLASS 1	798.000	TON
55	616-06395 RIPRAP	858.000	SYS
56	616-06405 RIPRAP, REVETMENT	99.000	TON
57	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
58	619-51860 PAINT STEEL BRIDGE, PARTIAL	LUMP	LUMP
59	619-60999 CLEAN STEEL BRIDGE, PARTIAL	LUMP	LUMP
60	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
61	621-06545 FERTILIZER	0.050	TON
62	621-06553 SEED MIXTURE, R	85.000	LBS
63	621-06557 SEED MIXTURE, T	40.000	LBS
64	621-06565 MULCHING MATERIAL	1.000	TON
65	621-06567 WATER	0.220	KGAL
66	621-06574 SODDING	61.000	SYS
67	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	100.000	EACH
68	622-52436 SIGN, DO NOT MOW OR SPRAY	3.000	EACH
69	701-05569 CORED HOLE IN ROCK	36.000	LFT
70	701-51195 PILE, STEEL H, HP 12 X 53	1,505.000	LFT
71	701-91792 PILE TIP, STEEL H	40.000	EACH
72	702-51005 CONCRETE, A, SUBSTRUCTURE	265.500	CYS
73	702-51015 CONCRETE, B, FOOTINGS	11.300	CYS
74	703-06028 REINFORCING BARS	34,424.000	LBS
75	703-06029 REINFORCING BARS, EPOXY COATED	108,201.000	LBS
76	704-51002 CONCRETE, C, SUPERSTRUCTURE	327.300	CYS
77	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
78	706-51020 CONCRETE, C, RAILING	41.400	CYS
79	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 45 IN. X 16 IN.	1,064.000	LFT
80	709-51821 SURFACE SEAL	LUMP	LUMP
81	710-51864 FIELD DRILLED HOLE	96.000	EACH
82	711-51035 STRUCTURAL STEEL	6,364.000	LBS
83	711-51866 RIVET, REMOVE	330.000	EACH
84	711-51867 STRUCTURAL STEEL CUTTING	223.000	SQIN
85	711-93754 JACKING AND SUPPORTING TRUSS AND STEEL BEAMS	LUMP	LUMP
86	711-96899 BEAMS, RESET	LUMP	LUMP
87	712-95676 LUMBER AND TIMBER, TREATED	2.700	MFBM
88	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	37.000	LFT
89	715-05407 PIPE, END BENT DRAIN, 6 IN.	116.000	LFT
90	715-46005 PIPE END SECTION, 15 IN.	1.000	EACH
91	720-45235 CATCH BASIN, E7	1.000	EACH
92	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
93	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
94	801-06625 DETOUR ROUTE MARKER ASSEMBLY	8.000	EACH
95	801-06640 CONSTRUCTION SIGN, A	3.000	EACH
96	801-06645 CONSTRUCTION SIGN, B	2.000	EACH

CALL ORDER : 681
 LETTING DATE :

CONTRACT ID : B -29604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
97	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
98	801-07118 BARRICADE, III-A	96.000	LFT
99	801-07119 BARRICADE, III-B	72.000	LFT
100	802-03896 BOLLARD	6.000	EACH
101	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	1.000	EACH
102	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	17.500	SFT
103	802-76055 SIGN POST, A	40.000	LFT
104	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,647.000	LFT
105	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	2,847.000	LFT

CALL ORDER : 691
 LETTING DATE :

CONTRACT ID : B -30274-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02240 PAVEMENT REMOVAL	200.400	SYS
8	302-07455 DENSE GRADED SUBBASE	33.400	CYS
9	306-08043 MILLING, TRANSITION	320.000	SYS
10	402-07433 HMA SURFACE, TYPE B	75.000	TON
11	402-07438 HMA INTERMEDIATE, TYPE B	133.000	TON
12	601-06035 GUARDRAIL, RESET	100.000	LFT
13	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	200.400	SYS
14	702-51863 FIELD DRILLED HOLE IN CONCRETE	88.000	EACH
15	703-51032 REINFORCING STEEL, EPOXY COATED	7,696.200	LBS
16	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	93.000	SFT
17	724-03276 EXPANSION JOINT SEALING SYSTEM	97.000	LFT
18	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
19	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
20	801-06625 DETOUR ROUTE MARKER ASSEMBLY	33.000	EACH
21	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
22	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
23	801-07118 BARRICADE, III-A	96.000	LFT
24	801-07119 BARRICADE, III-B	96.000	LFT
25	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	96.000	LFT
26	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	96.000	LFT

CALL ORDER : 701
 LETTING DATE :

CONTRACT ID : M -30039-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	6.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	304-07783 HMA PATCHING, TYPE D	79.000	TON
14	306-08033 MILLING, ASPHALT, 1 IN.	51,016.000	SYS
15	306-08034 MILLING, ASPHALT, 1 1/2 IN.	4,348.000	SYS
16	306-08038 MILLING, ASPHALT, 4 IN.	2,573.000	SYS
17	402-07784 HMA SURFACE, TYPE D	4,780.000	TON
18	402-07785 HMA INTERMEDIATE, TYPE D	354.000	TON
19	406-05520 ASPHALT FOR TACK COAT	14.600	TON
20	506-06333 PCCP PATCHING, FULL DEPTH	1,097.000	SYS
21	506-06334 PCCP PATCHING, PARTIAL DEPTH	24.000	SYS
22	801-03290 CONSTRUCTION SIGN, C	13.000	EACH
23	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
25	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	600.000	LFT
26	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	1,640.000	LFT
27	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	27,436.000	LFT
28	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	25,836.000	LFT
29	808-75256 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	100.000	LFT
30	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	84.000	LFT
31	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	12.000	EACH
32	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	12.000	EACH
33	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	826.000	EACH

CALL ORDER : 711
 LETTING DATE :

CONTRACT ID : M -30238-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PIPE LINNING		
1	105-07039 FIELD OFFICE, B	4.000	MOS
2	105-09198 LAPTOP COMPUTER SYSTEM	4.000	MOS
3	105-09199 FIELD OFFICE INTERNET SERVICE	4.000	MOS
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	206-51235 COFFERDAM	LUMP	LUMP
11	725-06858 PIPE LINER, THERMOPLASTIC, 36 IN.	1,125.000	LFT
12	725-06859 PIPE LINER, THERMOPLASTIC, 48 IN.	167.000	LFT
13	725-08079 PIPE LINER, THERMOPLASTIC, AREA 14.7 SFT.	75.000	LFT
14	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 721
 LETTING DATE :

CONTRACT ID : M -30277-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PCCP PATCHING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	303-01180 COMPACTED AGGREGATE, NO. 53	200.000	TON
15	501-05240 CONTRACTION JOINT, D1	5,000.000	LFT
16	506-06333 PCCP PATCHING, FULL DEPTH	10,430.000	SYS
17	506-06334 PCCP PATCHING, PARTIAL DEPTH	200.000	SYS
18	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
20	801-06710 FLASHING ARROW SIGN	180.000	DAY
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
23	805-01836 SIGNAL CABLE DETECTOR, 2C 16GA., SHIELDED, LEAD IN	4,500.000	LFT
24	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	450.000	LFT
25	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,440.000	LFT
26	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	6,938.000	LFT
27	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	35,500.000	LFT
28	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	27,750.000	LFT
29	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	20.000	EACH
30	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	10.000	EACH
31	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	300.000	LFT
32	808-75140 PAVEMENT MESSAGE MARKINGS, PAINT, WORD RXR	4.000	EACH
33	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	350.000	EACH
34	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	350.000	EACH

CALL ORDER : 731
 LETTING DATE :

CONTRACT ID : M -30388-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PCCP PATCHING			
1	105-07039 FIELD OFFICE, B	5.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	105-09198 LAPTOP COMPUTER SYSTEM	10.000	MOS
6	105-09199 FIELD OFFICE INTERNET SERVICE	5.000	MOS
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-90277 DETECTOR HOUSING, REMOVE	2.000	EACH
13	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	100.000	TON
14	306-08034 MILLING, ASPHALT, 1 1/2 IN.	3,500.000	SYS
15	402-07784 HMA SURFACE, TYPE D	290.000	TON
16	406-05520 ASPHALT FOR TACK COAT	0.900	TON
17	503-05240 D-1 CONTRACTION JOINT	230.000	LFT
18	506-06333 PCCP PATCHING, FULL DEPTH	2,010.000	SYS
19	507-07480 PCCP PROFILING	1,500.000	SYS
20	605-06090 CURB, INTEGRAL, CONCRETE	900.000	LFT
21	621-06567 WATER	1.200	KGAL
22	621-06575 SODDING, NURSERY	300.000	SYS
23	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
24	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
25	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
26	801-03291 CONSTRUCTION SIGN, D	4.000	EACH
27	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	500.000	LFT
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	500.000	LFT
29	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	70.000	LFT
30	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	120.000	LFT
31	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	95.000	LFT
32	801-06586 TEMPORARY PAVEMENT MARKING, 8 IN.	120.000	LFT
33	801-06640 CONSTRUCTION SIGN, A	36.000	EACH
34	801-06710 FLASHING ARROW SIGN	250.000	DAY
35	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
36	801-92448 CONSTRUCTION SIGNS, MOBILE	1,500.000	DAY
37	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,000.000	LFT
38	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
39	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	350.000	LFT
40	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	6.000	EACH
41	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	5.000	EACH
42	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	570.000	LFT
43	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,300.000	LFT
44	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	1,300.000	LFT
45	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	120.000	LFT
46	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	95.000	LFT

CALL ORDER : 741
 LETTING DATE :

CONTRACT ID : M -30389-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PCCP PATCHING		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	105-09198 LAPTOP COMPUTER SYSTEM	6.000	MOS
5	105-09291 MOBILE BROADBAND ACCESS	6.000	MOS
6	109-08359 LIQUIDATED DAMAGES	1.000	DOL
7	109-08360 CONTRACT LIENS	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-90277 DETECTOR HOUSING, REMOVE	2.000	EACH
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	30.000	TON
13	306-08043 MILLING, TRANSITION	1,717.000	SYS
14	402-07787 HMA WEDGE AND LEVEL, TYPE D	174.000	TON
15	406-05520 ASPHALT FOR TACK COAT	0.600	TON
16	503-05240 D-1 CONTRACTION JOINT	600.000	LFT
17	503-05310 TERMINAL JOINT	1,266.000	LFT
18	506-06333 PCCP PATCHING, FULL DEPTH	2,181.000	SYS
19	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
20	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
21	801-06640 CONSTRUCTION SIGN, A	38.000	EACH
22	801-06710 FLASHING ARROW SIGN	400.000	DAY
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
24	801-92448 CONSTRUCTION SIGNS, MOBILE	800.000	DAY
25	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	725.000	LFT
26	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
27	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	246.000	LFT
28	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,052.000	LFT
29	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	200.000	LFT
30	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	29.000	LFT
31	808-75001 LINE, PAINT, BROKEN, WHITE, 5 IN.	200.000	LFT

CALL ORDER : 751
 LETTING DATE :

CONTRACT ID : M -30390-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	WEDGE AND LEVEL		
1	105-09198 LAPTOP COMPUTER SYSTEM	6.000	MOS
2	105-09291 MOBILE BROADBAND ACCESS	6.000	MOS
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	210-05873 TESTING	LUMP	LUMP
9	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,137.000	TON
10	303-07449 COMPACTED AGGREGATE, NO. 73	559.000	TON
11	304-07490 HMA PATCHING, TYPE B	5.000	TON
12	304-07490 HMA PATCHING, TYPE B	189.000	TON
13	304-07491 HMA PATCHING, TYPE C	232.000	TON
14	306-08034 MILLING, ASPHALT, 1 1/2 IN.	10,396.000	SYS
15	306-08043 MILLING, TRANSITION	8,520.000	SYS
16	306-08432 MILLING, APPROACH	2,480.000	SYS
17	402-07451 HMA WEDGE AND LEVEL, TYPE B	3,468.000	TON
18	402-07452 HMA WEDGE AND LEVEL, TYPE C	11.000	TON
19	406-05520 ASPHALT FOR TACK COAT	15.000	TON
20	610-07486 HMA FOR APPROACHES, TYPE A	742.000	TON
21	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
22	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
23	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
24	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	180.000	LFT
25	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,632.000	LFT
26	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
27	801-06710 FLASHING ARROW SIGN	10.000	DAY
28	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
29	801-92448 CONSTRUCTION SIGNS, MOBILE	60.000	DAY
30	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	2,086.000	LFT
31	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	29,040.000	LFT
32	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	17,741.000	LFT
33	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	9.000	EACH
34	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	9.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 761
 LETTING DATE :

CONTRACT ID : M -30413-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHAB		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	100.000	LFT
7	602-02476 BARRIER, CONCRETE, MODIFIED	100.000	LFT
8	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	300.000	SFT
9	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	882.000	SFT
10	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
11	801-06640 CONSTRUCTION SIGN, A	50.000	EACH
12	801-06710 FLASHING ARROW SIGN	30.000	DAY
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
14	801-08403 TEMPORARY TRAFFIC BARRIER, TYPE 4	5,116.000	LFT
15	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	3.000	EACH

CALL ORDER : 771
 LETTING DATE :

CONTRACT ID : M -30414-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6 722-51401	BRIDGE DECK PATCHING, FULL DEPTH	350.000	SFT
7 722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	971.000	SFT
8 801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
9 801-06710	FLASHING ARROW SIGN	30.000	DAY
10 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
11 801-08403	TEMPORARY TRAFFIC BARRIER, TYPE 4	2,085.000	LFT
12 801-09133	TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH

CALL ORDER : 781
 LETTING DATE :

CONTRACT ID : M -30469-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PCCP PATCHING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	306-08034 MILLING, ASPHALT, 1 1/2 IN.	2,000.000	SYS
12	306-08041 MILLING, PCCP	40.000	SYS
13	306-08043 MILLING, TRANSITION	2,000.000	SYS
14	402-07452 HMA WEDGE AND LEVEL, TYPE C	500.000	TON
15	406-05521 ASPHALT FOR TACK COAT	4,032.000	SYS
16	501-05240 CONTRACTION JOINT, D1	200.000	LFT
17	506-06333 PCCP PATCHING, FULL DEPTH	874.000	SYS
18	506-06334 PCCP PATCHING, PARTIAL DEPTH	100.000	SYS
19	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
20	801-06640 CONSTRUCTION SIGN, A	37.000	EACH
21	801-06710 FLASHING ARROW SIGN	60.000	DAY
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
24	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	200.000	LFT
25	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	550.000	LFT
26	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	100.000	LFT
27	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	10.000	EACH
28	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	10.000	EACH

CALL ORDER : 791
 LETTING DATE :

CONTRACT ID : M -30470-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INSTITUTION AND PARK ROAD MAINTENANCE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-07025 MOBILIZATION AND DEMOBILIZATION	4.000	EACH
10	203-02000 EXCAVATION, COMMON	682.000	CYS
11	303-01180 COMPACTED AGGREGATE, NO. 53	1,252.000	TON
12	304-07489 HMA PATCHING, TYPE A	24.000	TON
13	306-08034 MILLING, ASPHALT, 1 1/2 IN.	13,893.000	SYS
14	402-07432 HMA SURFACE, TYPE A	1,281.000	TON
15	402-07435 HMA INTERMEDIATE, TYPE A	405.000	TON
16	405-05517 ASPHALT FOR PRIME COAT	3.600	TON
17	406-05520 ASPHALT FOR TACK COAT	4.100	TON
18	411-08438 MICRO-SURFACING, WARRANTED	13,333.000	SYS
19	610-06460 COMPACTED AGGREGATE, O	64.000	TON
20	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
21	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
22	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
23	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	4,220.000	LFT
24	808-75056 TRANSVERSE MARKINGS, PAINT, SOLID, WHITE, CROSSHATCH LINE,	67.000	LFT
25	808-97222 PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	2.000	EACH

CALL ORDER : 801
 LETTING DATE :

CONTRACT ID : M -30557-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09198 LAPTOP COMPUTER SYSTEM	3.000	MOS
3	105-09291 MOBILE BROADBAND ACCESS	3.000	MOS
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-93741 GUARD RAIL END TREATMENT, REMOVE	2.000	EACH
11	203-08607 LINEAR GRADING	5,820.000	LFT
12	303-52308 COMPACTED AGGREGATE, 0, 53	570.000	TON
13	306-08034 MILLING, ASPHALT, 1 1/2 IN.	18,137.000	SYS
14	306-08043 MILLING, TRANSITION	200.000	SYS
15	401-07353 QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	2,095.000	TON
16	406-05520 ASPHALT FOR TACK COAT	10.000	TON
17	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
18	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	2.000	EACH
19	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
20	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,332.000	LFT
21	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,112.000	LFT
22	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
23	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	2,636.000	LFT
24	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	10,544.000	LFT
25	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	10,544.000	LFT
26	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	270.000	EACH
27	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	270.000	EACH

CALL ORDER : 811
 LETTING DATE :

CONTRACT ID : M -30558-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	WEDGE AND LEVEL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-07449 COMPACTED AGGREGATE, NO. 73	908.000	TON
8	306-08034 MILLING, ASPHALT, 1 1/2 IN.	28,917.000	SYS
9	402-07452 HMA WEDGE AND LEVEL, TYPE C	3,181.000	TON
10	406-05520 ASPHALT FOR TACK COAT	14.500	TON
11	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
12	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	3,549.000	LFT
13	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	17,745.000	LFT
14	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	2,098.000	LFT
17	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	16,784.000	LFT
18	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	3,403.000	LFT
19	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	210.000	EACH

CALL ORDER : 821
 LETTING DATE :

CONTRACT ID : M -30587-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	WEDGE AND LEVEL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	303-07449 COMPACTED AGGREGATE, NO. 73	1,100.000	TON
9	306-08042 MILLING, SCARIFICATION/PROFILE	40,411.000	SYS
10	306-08043 MILLING, TRANSITION	1,680.000	SYS
11	306-08432 MILLING, APPROACH	300.000	SYS
12	402-07451 HMA WEDGE AND LEVEL, TYPE B	3,800.000	TON
13	406-05520 ASPHALT FOR TACK COAT	12.000	TON
14	610-07487 HMA FOR APPROACHES, TYPE B	90.000	TON
15	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
16	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,804.000	LFT
17	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,804.000	LFT
18	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
20	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	4,000.000	LFT
21	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	35,558.000	LFT
22	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	6,308.000	LFT
23	808-75097 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	25.000	LFT

CALL ORDER : 831
 LETTING DATE :

CONTRACT ID : M -30588-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-07449 COMPACTED AGGREGATE, NO. 73	2,460.000	TON
8	306-08034 MILLING, ASPHALT, 1 1/2 IN.	5,024.000	SYS
9	306-08043 MILLING, TRANSITION	7,920.000	SYS
10	402-07451 HMA WEDGE AND LEVEL, TYPE B	5,400.000	TON
11	406-05520 ASPHALT FOR TACK COAT	15.000	TON
12	610-07487 HMA FOR APPROACHES, TYPE B	160.000	TON
13	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
14	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	560.000	LFT
15	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,466.000	LFT
16	801-06640 CONSTRUCTION SIGN, A	37.000	EACH
17	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
18	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	6,030.000	LFT
19	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	49,320.000	LFT
20	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	650.000	LFT

CALL ORDER : 861
 LETTING DATE :

CONTRACT ID : T -29199-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW SIGNAL INSTALLATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	4.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	8.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	4.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-01874 SHEET SIGN AND POST, REMOVE	2.000	EACH
11	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
12	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
13	801-06710 FLASHING ARROW SIGN	90.000	DAY
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
15	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	24.000	LFT
16	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	58.500	SFT
17	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
18	805-01842 HANDHOLE, SIGNAL	9.000	EACH
19	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	1,500.000	LFT
20	805-01879 SIGNAL SERVICE, INSTALL	1.000	EACH
21	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	1.000	EACH
22	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
23	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000	EACH
24	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
25	805-78420 DISCONNECT HANGER	4.000	EACH
26	805-78467 SIGNAL CABLE, 3C 8GA.	60.000	LFT
27	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	5,000.000	LFT
28	805-78485 SIGNAL CABLE, 5C 14GA.	500.000	LFT
29	805-78490 SIGNAL CABLE, 7C 14GA.	600.000	LFT
30	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,000.000	LFT
31	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
32	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,600.000	LFT
33	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
34	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	4.000	EACH
35	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	6.000	EACH
36	808-02157 PAVEMENT MESSAGE MARKINGS, REMOVE	2.000	EACH
37	808-06716 LINE, REMOVE	50.000	LFT
38	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	122.000	LFT
39	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	2.000	EACH
40	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH

CALL ORDER : 871
 LETTING DATE :

CONTRACT ID : T -29804-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZED			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09198 LAPTOP COMPUTER SYSTEM	4.000	MOS
3	105-09199 FIELD OFFICE INTERNET SERVICE	3.000	MOS
4	105-09291 MOBILE BROADBAND ACCESS	4.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	2.000	EACH
11	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
12	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
14	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	96.000	LFT
15	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	2.000	EACH
16	802-76020 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.080 IN. THICKNESS	37.500	SFT
17	802-76030 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.100 IN. THICKNESS	122.000	SFT
18	802-76040 SIGN,SHEET,ENCLOSED LENS WITH LEGEND (0.125 IN. THICKNESS)	58.500	SFT
19	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
20	805-01820 SIGNAL STRAIN POLE, STEEL, INSTALL	4.000	EACH
21	805-01825 DISCONNECT HANGER, INSTALL	3.000	EACH
22	805-01842 HANDHOLE, SIGNAL	7.000	EACH
23	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	1,060.000	LFT
24	805-02658 CABLE, COAXIAL	350.000	LFT
25	805-08466 RADIO ANTENNA, 9db, YAGI	1.000	EACH
26	805-08487 TRAFFIC SIGNAL BACKPLATE	5.000	EACH
27	805-08493 RADIO SYSTEM TESTING INTERCONNECT	LUMP	LUMP
28	805-08494 RADIO SPREAD SPECTRUM	1.000	EACH
29	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
30	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	4.000	EACH
31	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	3.000	EACH
32	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
33	805-78445 SIGNAL SERVICE	1.000	EACH
34	805-78467 SIGNAL CABLE, 3C 8GA.	50.000	LFT
35	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,490.000	LFT
36	805-78485 SIGNAL CABLE, 5C 14GA.	360.000	LFT
37	805-78490 SIGNAL CABLE, 7C 14GA.	630.000	LFT
38	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,780.000	LFT
39	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
40	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	650.000	LFT
41	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
42	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
43	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	8.000	EACH
44	808-06716 LINE, REMOVE	50.000	LFT
45	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	170.000	LFT
46	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	82.000	LFT
47	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
48	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH

CALL ORDER : 881
 LETTING DATE :

CONTRACT ID : T -29827-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	6.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	6.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-04089 SIGN, SHEET, REMOVE	5.000	EACH
11	601-01115 GUARDRAIL, W BEAM, 1 FT. 6.75 IN. SPACING	207.000	LFT
12	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
13	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	7.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	80.000	LFT
17	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	2.000	EACH
18	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	4.000	EACH
19	802-76020 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.080 IN. THICKNESS	30.000	SFT
20	802-76030 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.100 IN. THICKNESS	44.500	SFT
21	802-76040 SIGN,SHEET,ENCLOSED LENS WITH LEGEND (0.125 IN. THICKNESS)	69.000	SFT
22	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	5.000	EACH
23	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	3.000	EACH
24	805-01820 SIGNAL STRAIN POLE, STEEL, INSTALL	8.000	EACH
25	805-01842 HANDHOLE, SIGNAL	17.000	EACH
26	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	2,570.000	LFT
27	805-02328 SIGNAL CABLE, 1C 14GA.	1,170.000	LFT
28	805-08487 TRAFFIC SIGNAL BACKPLATE	9.000	EACH
29	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	2.000	EACH
30	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	10.000	EACH
31	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	3.000	EACH
32	805-78415 SPAN, CATENARY, AND TETHER	6.000	EACH
33	805-78420 DISCONNECT HANGER	6.000	EACH
34	805-78445 SIGNAL SERVICE	2.000	EACH
35	805-78467 SIGNAL CABLE, 3C 8GA.	120.000	LFT
36	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,600.000	LFT
37	805-78485 SIGNAL CABLE, 5C 14GA.	570.000	LFT
38	805-78490 SIGNAL CABLE, 7C 14GA.	1,420.000	LFT
39	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	5,370.000	LFT
40	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
41	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,210.000	LFT
42	805-78925 CONTROLLER CABINET FOUNDATION, P1	2.000	EACH
43	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
44	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	14.000	EACH
45	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	150.000	LFT
46	808-06716 LINE, REMOVE	160.000	LFT
47	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	60.000	LFT
48	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	3.000	EACH

CALL ORDER : 881
 LETTING DATE :

CONTRACT ID : T -29827-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
49 808-74808	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	3.000	EACH
50 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	58.000	LFT
51 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	6.000	EACH
52 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000	EACH

CALL ORDER : 891
 LETTING DATE :

CONTRACT ID : TM-30085-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MAINTENANCE		
1	106-03285 FAILED MATERIAL	1.000	DOL
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	202-52710 SIDEWALK, CONCRETE, REMOVE	10.000	SYS
7	604-06070 SIDEWALK, CONCRETE	10.000	SYS
8	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
9	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
10	805-01842 HANDHOLE, SIGNAL	2.000	EACH
11	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	2.000	EACH
12	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	50.000	LFT
13	805-06897 SIGNAL CABLE DETECTOR, LEAD IN	7,500.000	LFT
14	805-07212 SPLICE KIT, SPIDER	5.000	EACH
15	805-07214 CONNECTOR, ST	5.000	EACH
16	805-78415 SPAN, CATENARY, AND TETHER	2.000	EACH
17	805-78746 PREFORMED LOOP DETECTORS	160.000	LFT
18	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
19	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	7,500.000	LFT
20	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	3.000	EACH
21	805-94971 FIBER OPTICS CABLE	500.000	LFT

CALL ORDER : 901
 LETTING DATE :

CONTRACT ID : TM-30240-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	50.000	LFT
11	202-86946 HANDHOLE, REMOVE	2.000	EACH
12	202-93741 GUARD RAIL END TREATMENT, REMOVE	1.000	EACH
13	202-95579 SERVICE POINT, REMOVE	1.000	EACH
14	601-01740 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 4	1.000	EACH
15	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
16	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	50.000	LFT
17	616-02320 GEOTEXTILES	360.000	SYS
18	616-05689 RIPRAP, CLASS 2	342.000	TON
19	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
20	801-06640 CONSTRUCTION SIGN, A	9.000	EACH
21	801-06710 FLASHING ARROW SIGN	30.000	DAY
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	802-07060 SIGN, SHEET, RELOCATE	4.000	EACH
24	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	741.000	LFT
25	805-86890 POLE CIRCUIT CABLE, 1C NO. 10 THW OR TW STRANDED COPPER	975.000	LFT
26	805-87485 INSULATING LINK, FURNISH	14.000	EACH
27	805-87490 INSULATING LINK, WATER PROOFED, FURNISH	20.000	EACH
28	807-02191 HANDHOLE, LIGHTING	5.000	EACH
29	807-02428 CONCRETE FOUNDATION WITH GROUNDING, 30 IN. X 30 IN. X 96 IN.	7.000	EACH
30	807-03934 LIGHT STRUCTURE, REMOVE	7.000	EACH
31	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1,514.000	LFT
32	807-84764 LIGHT POLE, 40 FT. E.M.H., 16.0 FT. MAST ARM, TRANSFORMER	1.000	EACH
33	807-84768 LIGHT POLE, 40 FT. E.M.H., 18.0 FT. MAST ARM, TRANSFORMER	1.000	EACH
34	807-84816 LIGHT POLE, 42 FT. E.M.H., 16.0 FT. MAST ARM, TRANSFORMER	3.000	EACH
35	807-84820 LIGHT POLE, 42 FT. E.M.H., 18.0 FT. MAST ARM, BREAKAWAY BASE	2.000	EACH
36	807-86805 SERVICE POINT, I	1.000	EACH
37	807-86910 CONNECTOR KIT, UNFUSED	7.000	EACH
38	807-86915 CONNECTOR KIT, FUSED	7.000	EACH
39	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	9.000	EACH
40	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.000	EACH
41	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	7.000	EACH
42	807-86955 CABLE DUCT MARKER	6.000	EACH
43	807-87205 LUMINAIRE ROADWAY, HIGH PRESSURE SODIUM, 400 WATT, FURNISH	7.000	EACH

