

CALL ORDER : 205

CONTRACT ID : R -28780-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
10	202-02278 CURB, CONCRETE, REMOVE	1,381.000	LFT
11	202-52710 SIDEWALK, CONCRETE, REMOVE	229.000	SYS
12	202-91385 INLET, REMOVE	2.000	EACH
13	202-93047 MANHOLE, REMOVE	1.000	EACH
14	202-96133 PIPE, REMOVE	112.000	LFT
15	203-02000 EXCAVATION, COMMON	1,242.000	CYS
16	205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	9.000	EACH
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	113.000	SYS
18	207-08268 SUBGRADE TREATMENT, TYPE IV	907.000	SYS
19	213-08058 FLOWABLE BACKFILL	276.000	CYS
20	304-07490 HMA PATCHING, TYPE B	163.000	TON
21	306-08034 MILLING, ASPHALT, 1 1/2 IN.	913.000	SYS
22	306-08041 MILLING, PCCP	389.000	SYS
23	306-08042 MILLING, SCARIFICATION/PROFILE	223.000	SYS
24	306-08043 MILLING, TRANSITION	684.000	SYS
25	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	316.000	TON
26	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	64.000	TON
27	401-07413 QC/QA-HMA, 3, 70, BASE, 25.0 mm	312.000	TON
28	402-07450 HMA WEDGE AND LEVEL, TYPE A	259.000	TON
29	406-05520 ASPHALT FOR TACK COAT	2.500	TON
30	502-06999 PCCP, 8 IN.	24.000	SYS
31	604-07896 CURB RAMP, CONCRETE, B	59.000	SYS
32	604-91531 SIDEWALK, CONCRETE, 4 IN.	605.000	SYS
33	605-06140 CURB AND GUTTER, CONCRETE	1,589.000	LFT
34	605-06250 CENTER CURB, C, CONCRETE	53.000	SYS
35	610-08446 PCCP FOR APPROACHES, 6 IN.	83.000	SYS
36	621-06567 WATER	22.000	kgAL
37	621-06575 SODDING, NURSERY	1,200.000	SYS
38	628-09401 FIELD OFFICE, A	8.000	MOS
39	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	373.000	LFT
40	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	16.000	LFT
41	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	128.000	LFT
42	715-08283 PCCP FOR STRUCTURE INSTALLATION	91.000	SYS
43	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	56.000	TON
44	715-09064 VIDEO INSPECTION FOR PIPE	517.000	LFT
45	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
46	720-45410 MANHOLE, C4	1.000	EACH
47	720-98174 INLET, B15	4.000	EACH
48	720-98555 INLET, C15	5.000	EACH
49	801-03290 CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 205

CONTRACT ID : R -28780-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
51	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,800.000	LFT
52	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	900.000	LFT
53	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	120.000	LFT
54	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	130.000	LFT
55	801-06625 DETOUR ROUTE MARKER ASSEMBLY	12.000	EACH
56	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
57	801-06645 CONSTRUCTION SIGN, B	7.000	EACH
58	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
59	801-07118 BARRICADE, III-A	130.000	LFT
60	801-07119 BARRICADE, III-B	40.000	LFT
61	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	10.500	LFT
62	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	57.000	SFT
63	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	4.000	EACH
64	805-01842 HANDHOLE, SIGNAL	3.000	EACH
65	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	672.000	LFT
66	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	4.000	EACH
67	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
68	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	8.000	EACH
69	805-02202 SIGNAL DETECTOR HOUSING, DOUBLE	4.000	EACH
70	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
71	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	4.000	EACH
72	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	4.000	EACH
73	805-78445 SIGNAL SERVICE	1.000	EACH
74	805-78467 SIGNAL CABLE, 3C 8GA.	50.000	LFT
75	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	3,592.000	LFT
76	805-78480 SIGNAL CABLE, 3C 14GA.	486.000	LFT
77	805-78485 SIGNAL CABLE, 5C 14GA.	1,156.000	LFT
78	805-78490 SIGNAL CABLE, 7C 14GA.	702.000	LFT
79	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	836.000	LFT
80	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	877.000	LFT
81	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	4.000	EACH
82	805-96121 PEDESTRIAN PUSH BUTTON AND SIGN	8.000	EACH
83	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	208.000	LFT
84	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	400.000	LFT
85	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	304.000	LFT
86	808-07310 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW,	148.000	LFT
87	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	2.000	EACH
88	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	2.000	EACH
89	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	280.000	LFT
90	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	177.000	LFT
91	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	131.000	LFT
92	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	442.000	LFT
93	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	3.000	EACH
94	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
95	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1,035.000	LFT
96	808-95933 CURB PAINTING, YELLOW	238.000	LFT
97	808-98000 LINE, EPOXY, SOLID, YELLOW, 8 IN.	902.000	LFT

