

CALL ORDER : 120

CONTRACT ID : IB-29520-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02271 HEADWALL, REMOVE	2.000	EACH
12	203-02000 EXCAVATION, COMMON	25,161.000	CYS
13	203-02070 BORROW	121,106.000	CYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	165.000	TON
15	205-06933 TEMPORARY DITCH INLET PROTECTION	13.000	EACH
16	205-06934 TEMPORARY MULCHING	14.000	TON
17	205-06937 TEMPORARY SILT FENCE	1,175.000	LFT
18	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	105.000	CYS
19	207-08264 SUBGRADE TREATMENT, TYPE II	20,200.000	SYS
20	211-02050 B BORROW	4,846.000	CYS
21	211-06467 AGGREGATE FOR END BENT BACKFILL	72.000	CYS
22	211-09264 STRUCTURE BACKFILL, TYPE 1	944.000	CYS
23	211-09266 STRUCTURE BACKFILL, TYPE 3	5,017.000	CYS
24	214-07202 GEOGRID, I	1,914.000	SYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	10,441.000	TON
26	302-07455 DENSE GRADED SUBBASE	79.000	CYS
27	306-08043 MILLING, TRANSITION	355.000	SYS
28	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,442.000	TON
29	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	3,336.000	TON
30	404-05511 SEAL COAT, 2	6,700.000	SYS
31	406-05520 ASPHALT FOR TACK COAT	4.600	TON
32	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
33	601-05999 CURVED TERMINAL END	2.000	EACH
34	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	2.000	EACH
35	601-06454 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R2, W1, TL-3	1.000	EACH
36	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
37	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
38	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	712.500	LFT
39	602-06729 BARRIER DELINEATOR	16.000	EACH
40	603-06040 FENCE, FARM FIELD, 47 IN.	1,900.000	LFT
41	605-06090 CURB, INTEGRAL, CONCRETE	15.400	LFT
42	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	100.000	LFT
43	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	225.500	SYS
44	610-07486 HMA FOR APPROACHES, TYPE A	190.000	TON
45	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
46	615-06490 RIGHT OF WAY MARKER	69.000	EACH
47	615-06505 MONUMENT, B	11.000	EACH
48	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
49	616-02320 GEOTEXTILES	1,055.000	SYS

CALL ORDER : 120

CONTRACT ID : IB-29520-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE CONSTRUCTION		
50	616-06451 RIPRAP, UNIFORM	377.000	TON
51	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
52	621-06545 FERTILIZER	4.400	TON
53	621-06553 SEED MIXTURE, R	1,850.000	LBS
54	621-06557 SEED MIXTURE, T	825.000	LBS
55	621-06565 MULCHING MATERIAL	21.800	TON
56	621-06567 WATER	150.000	KGAL
57	621-06574 SODDING	2,948.000	SYS
58	628-09402 FIELD OFFICE, B	15.000	MOS
59	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	15.000	MOS
60	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
61	701-06012 TEST PILE, RESTRIKE	2.000	EACH
62	701-06027 TEST PILE	2.000	EACH
63	701-91792 PILE TIP, STEEL H	35.000	EACH
64	701-95780 PILE, STEEL H, HP 12 X 74	3,318.000	LFT
65	702-51005 CONCRETE, A, SUBSTRUCTURE	101.400	CYS
66	702-51015 CONCRETE, B, FOOTINGS	47.200	CYS
67	702-92857 CONCRETE, C, SUBSTRUCTURE	29.900	CYS
68	703-51030 REINFORCING STEEL	17,065.000	LBS
69	703-51032 REINFORCING STEEL, EPOXY COATED	125,998.000	LBS
70	704-51002 CONCRETE, C, SUPERSTRUCTURE	394.400	CYS
71	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
72	706-51020 CONCRETE, C, RAILING	40.700	CYS
73	707-08476 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	842.300	LFT
74	709-51821 SURFACE SEAL	LUMP	LUMP
75	715-02629 SAFETY METAL END SECTION, 6:1, 18 IN.	1.000	EACH
76	715-03584 SAFETY METAL END SECTION, 4:1, 18 IN.	2.000	EACH
77	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	51.000	LFT
78	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	155.000	LFT
79	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	240.000	LFT
80	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	924.000	LFT
81	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	25.000	LFT
82	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	85.000	LFT
83	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN.	100.000	LFT
84	715-05407 PIPE, END BENT DRAIN, 6 IN.	189.000	LFT
85	715-26764 GRATED BOX END SECTION, II, 10:1, 18 IN.	1.000	EACH
86	715-46000 PIPE END SECTION, 12 IN.	4.000	EACH
87	715-46005 PIPE END SECTION, 15 IN.	4.000	EACH
88	715-46020 PIPE END SECTION, 24 IN.	6.000	EACH
89	720-45275 PIPE CATCH BASIN, 24 IN.	4.000	EACH
90	731-93945 FACE PANELS, CONCRETE	7,505.000	SFT
91	731-93946 WALL ERECTION	7,505.000	SFT
92	731-93947 LEVELING PAD, CONCRETE	431.000	LFT
93	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
94	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
95	801-06625 DETOUR ROUTE MARKER ASSEMBLY	45.000	EACH
96	801-06640 CONSTRUCTION SIGN, A	52.000	EACH
97	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
98	801-06710 FLASHING ARROW SIGN	360.000	DAY

CALL ORDER : 120

CONTRACT ID : IB-29520-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE CONSTRUCTION		
99	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
100	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH
101	801-07118 BARRICADE, III-A	72.000	LFT
102	801-07119 BARRICADE, III-B	192.000	LFT
103	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	200.000	LFT
104	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
105	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	125.000	LFT
106	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	63.750	SFT
107	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	16.000	SFT
108	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	555.000	LFT
109	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	555.000	LFT
110	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	9,605.000	LFT
111	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	9,475.000	LFT
112	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	30.000	LFT
113	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	124.000	EACH

CALL ORDER : 150

CONTRACT ID : IR-29885-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNS, SIGNALS, LIGHTING AND MARKINGS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	78.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.000	EACH
15	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
19	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
20	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
21	203-02000 EXCAVATION, COMMON	71,582.000	CYS
22	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	4.000	TON
23	205-06932 TEMPORARY CHECK DAM, STRAW BALES	392.000	LFT
24	205-06933 TEMPORARY DITCH INLET PROTECTION	29.000	EACH
25	205-06936 TEMPORARY SEDIMENT TRAP	8.000	TON
26	205-06937 TEMPORARY SILT FENCE	11,135.000	LFT
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	7,471.000	SYS
28	207-08268 SUBGRADE TREATMENT, TYPE IV	122,245.000	SYS
29	211-07454 STRUCTURE BACKFILL	32,033.000	CYS
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	423.000	TON
31	303-01180 COMPACTED AGGREGATE, NO. 53	812.000	TON
32	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
33	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	8,601.000	TON
34	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	101.000	TON
35	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	14,288.000	TON
36	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	2,822.000	TON
37	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	44,579.000	TON
38	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	22,647.000	TON
39	402-07433 HMA SURFACE, TYPE B	51.000	TON
40	402-07438 HMA INTERMEDIATE, TYPE B	171.000	TON
41	406-05520 ASPHALT FOR TACK COAT	113.000	TON
42	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
43	601-01740 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 4	1.000	EACH
44	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	250.000	LFT
45	605-06145 CURB AND GUTTER, B, CONCRETE	29,820.000	LFT
46	610-07487 HMA FOR APPROACHES, TYPE B	1,997.000	TON
47	610-08446 PCCP FOR APPROACHES, 6 IN.	1,582.000	SYS
48	610-09108 PCCP FOR APPROACHES, 9 IN.	5,711.000	SYS
49	611-06497 MAILBOX ASSEMBLY, SINGLE	77.000	EACH

CALL ORDER : 150

CONTRACT ID : IR-29885-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGNS, SIGNALS, LIGHTING AND MARKINGS			
50	611-06498 MAILBOX ASSEMBLY, DOUBLE	16.000	EACH
51	615-06490 RIGHT OF WAY MARKER	129.000	EACH
52	615-06505 MONUMENT, B	20.000	EACH
53	615-06510 MONUMENT, C	1.000	EACH
54	616-02320 GEOTEXTILES	1,250.000	SYS
55	616-06405 RIPRAP, REVETMENT	697.000	TON
56	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
57	621-06545 FERTILIZER	5.100	TON
58	621-06554 SEED MIXTURE, U	1,917.000	LBS
59	621-06565 MULCHING MATERIAL	26.000	TON
60	621-06567 WATER	86.000	KGAL
61	621-06574 SODDING	1,188.000	SYS
62	621-06575 SODDING, NURSERY	22,454.000	SYS
63	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	64.000	EACH
64	622-52436 SIGN, DO NOT MOW OR SPRAY	8.000	EACH
65	622-91786 SEEDLING	300.000	EACH
66	628-09401 FIELD OFFICE, A	26.000	MOS
67	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	26.000	MOS
68	714-01634 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 7 FT. X 4 FT.	130.000	LFT
69	714-01764 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 7 FT. X 5 FT.	128.000	LFT
70	714-07773 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 10 FT. X 3 FT.	216.000	LFT
71	714-26703 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 6 FT. X 4 FT.	115.000	LFT
72	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	794.000	LFT
73	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	20,018.000	LFT
74	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	367.000	LFT
75	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	11,597.000	LFT
76	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	3,730.000	LFT
77	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	4,471.000	LFT
78	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	4,187.000	LFT
79	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	4,702.000	LFT
80	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	42.000	LFT
81	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	467.000	LFT
82	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN.	45.000	LFT
83	715-05428 PIPE, SLOTTED VANE DRAIN, 12 IN.	40.000	LFT
84	715-05998 PIPE, TYPE 3, CIRCULAR, 8 IN.	2.000	LFT
85	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
86	715-46005 PIPE END SECTION, 15 IN.	11.000	EACH
87	715-46010 PIPE END SECTION, 18 IN.	6.000	EACH
88	715-46020 PIPE END SECTION, 24 IN.	3.000	EACH
89	715-46030 PIPE END SECTION, 30 IN.	1.000	EACH
90	715-46040 PIPE END SECTION, 36 IN.	3.000	EACH
91	718-06528 OUTLET PROTECTOR, 1	8.000	EACH
92	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
93	718-52610 AGGREGATE FOR UNDERDRAINS	1,459.000	CYS
94	718-99153 GEOTEXTILES FOR UNDERDRAIN	20,834.000	SYS
95	720-44000 CASTING, ADJUST TO GRADE	19.000	EACH
96	720-45030 INLET, E7	2.000	EACH
97	720-45080 INLET, S14	133.000	EACH
98	720-45085 INLET, T14	72.000	EACH

CALL ORDER : 150

CONTRACT ID : IR-29885-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGNS, SIGNALS, LIGHTING AND MARKINGS			
99	720-45235 CATCH BASIN, E7	1.000	EACH
100	720-45265 PIPE CATCH BASIN, 15 IN.	26.000	EACH
101	720-45275 PIPE CATCH BASIN, 24 IN.	2.000	EACH
102	720-45410 MANHOLE, C4	72.000	EACH
103	720-45415 MANHOLE, D4	29.000	EACH
104	720-45510 MANHOLE, C4, MODIFIED	27.000	EACH
105	720-45515 MANHOLE, D4, MODIFIED	6.000	EACH
106	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	44.000	LFT
107	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
108	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
109	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	115,484.000	LFT
110	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
111	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
112	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
113	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
114	801-07119 BARRICADE, III-B	324.000	LFT
115	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN.	303.000	LFT
116	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	854.000	LFT
117	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	218.000	LFT
118	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	271.000	SFT
119	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	646.000	SFT
120	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	111.000	SFT
121	805-01842 HANDHOLE, SIGNAL	12.000	EACH
122	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	4,284.000	LFT
123	805-05870 SIGNAL SUPPORT FOUNDATION	4.000	EACH
124	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,986.000	LFT
125	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
126	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
127	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. AMBER	4.000	EACH
128	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. RED	2.000	EACH
129	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	3.000	EACH
130	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	5.000	EACH
131	805-78415 SPAN, CATENARY, AND TETHER	5.000	EACH
132	805-78420 DISCONNECT HANGER	5.000	EACH
133	805-78445 SIGNAL SERVICE	2.000	EACH
134	805-78467 SIGNAL CABLE, 3C 8GA.	30.000	LFT
135	805-78480 SIGNAL CABLE, 3C 14GA.	183.000	LFT
136	805-78485 SIGNAL CABLE, 5C 14GA.	509.000	LFT
137	805-78490 SIGNAL CABLE, 7C 14GA.	578.000	LFT
138	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	3,859.000	LFT
139	805-78520 MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	LUMP	LUMP
140	805-78785 SIGNAL DETECTOR HOUSING	14.000	EACH
141	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	3,060.000	LFT
142	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
143	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000	EACH
144	805-96014 SAW CUT, FULL DEPTH	430.000	LFT
145	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	6,613.000	LFT
146	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	33,976.000	LFT
147	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	4,611.000	LFT

CALL ORDER : 150

CONTRACT ID : IR-29885-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNS, SIGNALS, LIGHTING AND MARKINGS		
148 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	30,571.000	LFT
149 808-75290	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	97.000	LFT
150 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	567.000	LFT
151 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	45.000	EACH
152 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	45.000	EACH
153 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1,130.000	EACH
154 808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1,718.000	LFT

CALL ORDER : 160

CONTRACT ID : IR-30114-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	63.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
9	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
13	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-96133 PIPE, REMOVE	40.000	LFT
19	203-02000 EXCAVATION, COMMON	720,935.000	CYS
20	203-02070 BORROW	285,222.100	CYS
21	203-02100 EXCAVATION, PEAT	301,540.000	CYS
22	205-03371 SEDIMENT, REMOVE	17,325.000	CYS
23	205-06930 SPLASHPAD, RIPRAP	68.000	TON
24	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,731.000	TON
25	205-06933 TEMPORARY DITCH INLET PROTECTION	28.000	EACH
26	205-06936 TEMPORARY SEDIMENT TRAP	1,580.000	TON
27	205-06937 TEMPORARY SILT FENCE	12,253.000	LFT
28	205-06938 TEMPORARY SLOPE DRAIN	1,431.000	LFT
29	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	2,581.500	CYS
30	207-08266 SUBGRADE TREATMENT, TYPE III	18,854.000	SYS
31	207-08267 SUBGRADE TREATMENT, TYPE IIIA	439.000	SYS
32	211-02050 B BORROW	98,005.000	CYS
33	211-06467 AGGREGATE FOR END BENT BACKFILL	198.400	CYS
34	211-09264 STRUCTURE BACKFILL, TYPE 1	2,897.400	CYS
35	211-09265 STRUCTURE BACKFILL, TYPE 2	1,423.000	CYS
36	211-09394 SHREDDED TIRE	12,349.000	CYS
37	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	8,980.000	TON
38	302-07455 DENSE GRADED SUBBASE	70.800	CYS
39	303-02051 STONE, NO 2	400.000	TON
40	402-07432 HMA SURFACE, TYPE A	1,564.000	TON
41	402-07435 HMA INTERMEDIATE, TYPE A	5,324.000	TON
42	406-05520 ASPHALT FOR TACK COAT	6.100	TON
43	602-06729 BARRIER DELINEATOR	154.000	EACH
44	603-06040 FENCE, FARM FIELD, 47 IN.	58,425.000	LFT
45	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	424.600	SYS
46	610-07487 HMA FOR APPROACHES, TYPE B	121.000	TON
47	615-06490 RIGHT OF WAY MARKER	37.000	EACH
48	615-06505 MONUMENT, B	22.000	EACH
49	615-06510 MONUMENT, C	41.000	EACH

CALL ORDER : 160

CONTRACT ID : IR-30114-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	615-06527 MONUMENT, SECTION CORNER	16.000	EACH
51	615-06530 POST, BENCHMARK	3.000	EACH
52	616-02320 GEOTEXTILES	31,037.100	SYS
53	616-05688 RIPRAP, CLASS 1	173.000	TON
54	616-06405 RIPRAP, REVETMENT	1,006.700	TON
55	616-09395 GEOMEMBRANE	8,922.000	SYS
56	617-02029 EXPANSION JOINT, M, 5.6 IN. MOVEMENT	47.000	LFT
57	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.000	EACH
58	621-02770 EROSION CONTROL BLANKET	82,455.000	SYS
59	621-06545 FERTILIZER	66.080	TON
60	621-06553 SEED MIXTURE, R	17,591.000	LBS
61	621-06555 SEED MIXTURE, P	7,785.000	LBS
62	621-06557 SEED MIXTURE, T	7,376.000	LBS
63	621-06565 MULCHING MATERIAL	208.400	TON
64	621-06567 WATER	108.000	KGAL
65	621-06570 TOP SOIL	2,873.000	CYS
66	621-06574 SODDING	31.200	SYS
67	621-06575 SODDING, NURSERY	25,882.000	SYS
68	628-09402 FIELD OFFICE, B	21.000	MOS
69	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	42.000	MOS
70	701-06011 DYNAMIC PILE LOAD TEST	11.000	EACH
71	701-06012 TEST PILE, RESTRIKE	11.000	EACH
72	701-06027 TEST PILE	11.000	EACH
73	701-08386 PILE, CONCRETE, STEEL SHELL ENCASED,	21,195.000	LFT
74	701-09415 PILE, CONCRETE, STEEL SHELL ENCASED,	17,698.000	LFT
75	702-51005 CONCRETE, A, SUBSTRUCTURE	1,312.500	CYS
76	702-51015 CONCRETE, B, FOOTINGS	841.400	CYS
77	702-51100 DRAIN PIPE, CAST IRON, 6 IN.	6,274.000	LBS
78	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	18,136.000	LBS
79	703-06028 REINFORCING BARS	193,835.000	LBS
80	703-06029 REINFORCING BARS, EPOXY COATED	1,589,623.000	LBS
81	704-51002 CONCRETE, C, SUPERSTRUCTURE	3,616.400	CYS
82	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	8.000	EACH
83	706-51020 CONCRETE, C, RAILING	668.860	CYS
84	707-06404 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM	2,399.300	LFT
85	707-06404 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM	2,539.300	LFT
86	707-06404 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM	5,947.500	LFT
87	709-51821 SURFACE SEAL	LUMP	LUMP
88	709-51821 SURFACE SEAL	LUMP	LUMP
89	709-51821 SURFACE SEAL	LUMP	LUMP
90	709-51821 SURFACE SEAL	LUMP	LUMP
91	714-04854 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 7 FT. X 3 FT.	232.000	LFT
92	714-06688 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 5 FT. X 2 FT.	55.000	LFT
93	714-07892 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 9 FT. X 3 FT.	237.000	LFT
94	714-09361 CULVERT, PRECAST BOX, REINFORCED	227.000	LFT
95	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	160.000	LFT
96	715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN.	252.000	LFT
97	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	1,075.000	LFT
98	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	2,369.000	LFT

CALL ORDER : 160

CONTRACT ID : IR-30114-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
99	715-05188 PIPE, TYPE 3, CIRCULAR, 60 IN.	60.000	LFT
100	715-05407 PIPE, END BENT DRAIN, 6 IN.	243.000	LFT
101	715-05440 PIPE, DRAINTILE TERMINAL SECTION, 8 IN	150.000	LFT
102	715-05442 PIPE, DRAINTILE TERMINAL SECTION, 10 IN	150.000	LFT
103	715-05443 PIPE, DRAINTILE TERMINAL SECTION, 12 IN	150.000	LFT
104	715-05841 CONCRETE ANCHOR, 60 IN.	2.000	EACH
105	715-08162 PIPE, TYPE 1, DEFORMED, MIN. AREA 8.8 SFT.	707.000	LFT
106	715-08163 PIPE END SECTION, MIN. AREA 8.8 SFT.	6.000	EACH
107	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	36.000	TON
108	715-09064 VIDEO INSPECTION FOR PIPE	4,562.000	LFT
109	715-09388 PIPE, DRAINTILE, 15 IN.	150.000	LFT
110	715-09389 PIPE, DRAINTILE, 10 IN.	150.000	LFT
111	715-09390 PIPE, DRAINTILE, 18 IN.	150.000	LFT
112	715-46000 PIPE END SECTION, 12 IN.	34.000	EACH
113	715-46010 PIPE END SECTION, 18 IN.	24.000	EACH
114	715-46030 PIPE END SECTION, 30 IN.	4.000	EACH
115	715-46040 PIPE END SECTION, 36 IN.	2.000	EACH
116	715-90832 PIPE, DRAINTILE, 6 IN	440.000	LFT
117	715-90833 PIPE, DRAINTILE, 8 IN	150.000	LFT
118	715-90834 PIPE, DRAINTILE, 12 IN.	150.000	LFT
119	719-09391 PIPE, DRAIN TILE TERMINAL SECTION, 16 IN	440.000	LFT
120	719-09392 PIPE, DRAIN TILE TERMINAL SECTION, 15 IN.	150.000	LFT
121	719-09393 PIPE, DRAIN TILE TERMINAL SECTION, 18 IN.	150.000	LFT
122	720-45065 INLET, N12	28.000	EACH
123	720-45130 INLET, E7, MODIFIED	30.000	EACH
124	724-51925 STRUCTURAL EXPANSION JOINT, SS	140.000	LFT
125	724-51927 STRUCTURAL EXPANSION JOINT, M	93.000	LFT
126	801-04308 ROAD CLOSURE SIGN ASSEMBLY	20.000	EACH
127	801-06640 CONSTRUCTION SIGN, A	32.000	EACH
128	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
129	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
130	801-07118 BARRICADE, III-A	264.000	LFT
131	801-07119 BARRICADE, III-B	216.000	LFT
132	801-07120 BARRICADE, III, PERMANENT	96.000	LFT
133	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	212.000	LFT
134	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	83.000	SFT

CALL ORDER : 166

CONTRACT ID : IR-30844-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW BRIDGE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
14	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
15	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
16	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
17	203-02000 EXCAVATION, COMMON	5,284.000	CYS
18	203-02070 BORROW	714,637.000	CYS
19	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	3.000	EACH
20	205-02770 EROSION CONTROL BLANKET	315.000	SYS
21	205-03371 SEDIMENT, REMOVE	600.000	CYS
22	205-06930 SPLASHPAD, RIPRAP	26.000	TON
23	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	280.000	TON
24	205-06936 TEMPORARY SEDIMENT TRAP	200.000	TON
25	205-06937 TEMPORARY SILT FENCE	4,830.000	LFT
26	205-06938 TEMPORARY SLOPE DRAIN	424.000	LFT
27	205-08517 ROCK FILTER BERM	20.000	TON
28	207-08262 SUBGRADE TREATMENT, TYPE I	40,322.000	SYS
29	211-02050 B BORROW	26,345.000	CYS
30	211-09264 STRUCTURE BACKFILL, TYPE 1	870.000	CYS
31	211-09266 STRUCTURE BACKFILL, TYPE 3	34,400.000	CYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5,905.000	TON
33	302-06464 SUBBASE FOR PCCP	5,311.000	CYS
34	302-07455 DENSE GRADED SUBBASE	210.000	CYS
35	302-08562 COARSE AGGREGATE, 8	135.000	TON
36	303-02051 STONE, NO 2	100.000	TON
37	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	726.000	TON
38	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,474.000	TON
39	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	2,104.000	TON
40	406-05520 ASPHALT FOR TACK COAT	5.000	TON
41	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
42	501-06322 QC/QA-PCCP, 11 IN.	18,980.000	SYS
43	503-05240 D-1 CONTRACTION JOINT	12,334.000	LFT
44	503-05310 TERMINAL JOINT	386.000	LFT
45	601-01522 GUARDRAIL TRANSITION TYPE TGB	8.000	EACH
46	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
47	601-94690 GUARDRAIL END TREATMENT, MS	3.000	EACH
48	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	750.000	LFT
49	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	750.000	LFT

CALL ORDER : 166

CONTRACT ID : IR-30844-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
50	602-06729 BARRIER DELINEATOR	52.000	EACH
51	603-06040 FENCE, FARM FIELD, 47 IN.	6,414.000	LFT
52	606-07484 MILLED HMA SHOULDER CORRUGATIONS	6,938.000	LFT
53	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	1,356.000	SYS
54	615-06490 RIGHT OF WAY MARKER	11.000	EACH
55	615-06510 MONUMENT, C	6.000	EACH
56	616-02320 GEOTEXTILES	608.000	SYS
57	616-06405 RIPRAP, REVETMENT	572.000	TON
58	616-06451 RIPRAP, UNIFORM	4.000	TON
59	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
60	621-06545 FERTILIZER	7.000	TON
61	621-06553 SEED MIXTURE, R	2,873.000	LBS
62	621-06557 SEED MIXTURE, T	1,352.000	LBS
63	621-06565 MULCHING MATERIAL	34.000	TON
64	621-06565 MULCHING MATERIAL	42.000	TON
65	621-06574 SODDING	5,896.000	SYS
66	628-09403 FIELD OFFICE, C	24.000	MOS
67	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	24.000	MOS
68	701-03921 PILE, STEEL H, HP 14 X 102	2,175.000	LFT
69	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
70	701-06012 TEST PILE, RESTRIKE	4.000	EACH
71	701-06027 TEST PILE	4.000	EACH
72	701-08152 STATIC PILE LOAD TEST	1.000	EACH
73	701-91792 PILE TIP, STEEL H	42.000	EACH
74	701-95780 PILE, STEEL H, HP 12 X 74	1,650.000	LFT
75	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	644.000	LBS
76	703-51032 REINFORCING STEEL, EPOXY COATED	340,430.000	LBS
77	704-51002 CONCRETE, C, SUPERSTRUCTURE	896.200	CYS
78	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	16.000	EACH
79	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN.	423.700	SYS
80	706-51020 CONCRETE, C, RAILING	115.100	CYS
81	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 45 IN. X 16 IN.	550.000	LFT
82	707-05997 STRUCTURAL MEMBERS, CONCRETE BULB-T	1,369.000	LFT
83	709-51821 SURFACE SEAL	LUMP	LUMP
84	714-08514 WINGWALL	152.000	SFT
85	714-26708 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 8 FT. X 4 FT.	280.000	LFT
86	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN.	1.000	EACH
87	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	12,136.000	LFT
88	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	300.000	LFT
89	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	300.000	LFT
90	715-05052 PIPE, TYPE 4, CIRCULAR, 12 IN.	300.000	LFT
91	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	1,128.000	LFT
92	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	472.000	LFT
93	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
94	715-91361 PIPE, PVC, 6 IN.	80.000	LFT
95	718-06529 OUTLET PROTECTOR, 2	39.000	EACH
96	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
97	718-52610 AGGREGATE FOR UNDERDRAINS	1,091.000	CYS
98	718-99153 GEOTEXTILES FOR UNDERDRAIN	10,000.000	SYS

CALL ORDER : 166

CONTRACT ID : IR-30844-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
99	720-45065 INLET, N12	3.000	EACH
100	731-93945 FACE PANELS, CONCRETE	36,985.000	SFT
101	731-93946 WALL ERECTION	36,985.000	SFT
102	731-93947 LEVELING PAD, CONCRETE	1,351.000	LFT
103	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
104	801-06625 DETOUR ROUTE MARKER ASSEMBLY	10.000	EACH
105	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
106	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
107	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
108	801-07118 BARRICADE, III-A	204.000	LFT
109	801-07119 BARRICADE, III-B	48.000	LFT
110	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	50.000	LFT
111	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	14.000	LFT
112	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	4.000	SFT
113	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	25.000	SFT
114	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	1,728.000	LFT
115	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	7,585.000	LFT
116	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	6,912.000	LFT
117	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	3.000	EACH
118	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	2.000	EACH

CALL ORDER : 170

CONTRACT ID : IR-30992-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HOUSES AND BUILDINGS, REMOVE		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
5 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
6 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
7 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
8 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
9 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
10 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
11 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
12 202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	328.000	SFT
13 202-03729	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	40.000	LFT
14 205-06934	TEMPORARY MULCHING	2.100	TON
15 205-06937	TEMPORARY SILT FENCE	1,600.000	LFT
16 621-06560	MULCHED SEEDING, U	4,000.000	SYS

CALL ORDER : 180

CONTRACT ID : IR-30993-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
5	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
6	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
7	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
8	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
9	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
11	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	1,494.000	SFT
12	202-03729 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	30.000	LFT
13	205-06937 TEMPORARY SILT FENCE	1,400.000	LFT
14	621-06560 MULCHED SEEDING, U	3,500.000	SYS

CALL ORDER : 200

CONTRACT ID : R -28102-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	11,500.000	SYS
11	202-02241 GUARDRAIL, REMOVE	40.000	LFT
12	202-02278 CURB, CONCRETE, REMOVE	6,000.000	LFT
13	202-91385 INLET, REMOVE	15.000	EACH
14	202-93047 MANHOLE, REMOVE	6.000	EACH
15	203-02000 EXCAVATION, COMMON	12,000.000	CYS
16	203-02010 EXCAVATION, ROCK	540.000	CYS
17	205-06933 TEMPORARY DITCH INLET PROTECTION	11.000	EACH
18	205-06937 TEMPORARY SILT FENCE	684.000	LFT
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	4,200.000	SYS
20	207-08268 SUBGRADE TREATMENT, TYPE IV	19,790.000	SYS
21	211-09264 STRUCTURE BACKFILL, TYPE 1	18,408.000	CYS
22	211-09265 STRUCTURE BACKFILL, TYPE 2	2,511.000	CYS
23	211-09267 STRUCTURE BACKFILL, TYPE 4	771.000	CYS
24	303-01180 COMPACTED AGGREGATE, NO. 53	500.000	TON
25	303-07449 COMPACTED AGGREGATE, NO. 73	220.000	TON
26	304-07493 WIDENING WITH HMA, TYPE B	20.000	TON
27	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	900.000	TON
28	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	1,500.000	TON
29	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	4,500.000	TON
30	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	2,100.000	TON
31	406-05520 ASPHALT FOR TACK COAT	30.000	TON
32	603-92636 FENCE, CHAIN LINK, 72 IN.	70.000	LFT
33	604-07896 CURB RAMP, CONCRETE, B	8.000	SYS
34	604-07898 CURB RAMP, CONCRETE, D	12.000	SYS
35	604-07900 CURB RAMP, CONCRETE, F	29.000	SYS
36	604-07901 CURB RAMP, CONCRETE, G	6.000	SYS
37	604-07902 CURB RAMP, CONCRETE, H	43.000	SYS
38	604-07903 CURB RAMP, CONCRETE, K	21.000	SYS
39	604-44251 STEPS, CONCRETE	20.000	CYS
40	604-91531 SIDEWALK, CONCRETE, 4 IN.	2,240.000	SYS
41	605-06120 CURB, CONCRETE	950.000	LFT
42	605-06140 CURB AND GUTTER, CONCRETE	6,700.000	LFT
43	610-07487 HMA FOR APPROACHES, TYPE B	2,350.000	TON
44	610-08446 PCCP FOR APPROACHES, 6 IN.	210.000	SYS
45	610-08510 PCCP FOR APPROACHES	300.000	SYS
46	610-09108 PCCP FOR APPROACHES, 9 IN.	3,580.000	SYS
47	616-02320 GEOTEXTILES	286.000	SYS
48	616-05688 RIPRAP, CLASS 1	290.000	TON
49	616-06451 RIPRAP, UNIFORM	26.000	TON

CALL ORDER : 200

CONTRACT ID : R -28102-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PAVEMENT REHABILITATION			
50	621-06575 SODDING, NURSERY	11,420.000	SYS
51	628-09402 FIELD OFFICE, B	16.000	MOS
52	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	16.000	MOS
53	702-90915 CONCRETE, A	30.000	CYS
54	703-51030 REINFORCING STEEL	1,780.000	LBS
55	706-01268 HANDRAIL, ALUMINUM	20.000	LFT
56	714-05562 RETAINING WALL	360.000	SFT
57	714-26703 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 6 FT. X 4 FT.	1,001.000	LFT
58	714-93641 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 4 FT. X 3 FT.	30.000	LFT
59	715-02181 SANITARY SEWER SERVICE ADJUSTMENT	400.000	LFT
60	715-04612 PIPE	4,052.000	LFT
61	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	930.000	LFT
62	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	9,260.000	LFT
63	715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN.	19.000	LFT
64	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	2,250.000	LFT
65	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	83.000	LFT
66	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	820.000	LFT
67	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	880.000	LFT
68	715-05159 PIPE, TYPE 2, CIRCULAR, 42 IN.	211.000	LFT
69	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN.	390.000	LFT
70	715-05162 PIPE, TYPE 2, CIRCULAR, 54 IN.	520.000	LFT
71	715-05163 PIPE, TYPE 2, CIRCULAR, 60 IN.	890.000	LFT
72	715-05408 PIPE, SANITARY SEWER, 8 IN.	47.000	LFT
73	715-05428 PIPE, SLOTTED VANE DRAIN, 12 IN.	160.000	LFT
74	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	120.000	TON
75	718-52610 AGGREGATE FOR UNDERDRAINS	620.000	CYS
76	718-99153 GEOTEXTILES FOR UNDERDRAIN	7,050.000	SYS
77	720-01092 MANHOLE, J15, MODIFIED	1.000	EACH
78	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	10.000	EACH
79	720-03194 MANHOLE	1.000	EACH
80	720-03194 MANHOLE	1.000	EACH
81	720-06607 SLOTTED DRAIN CLEANOUT	4.000	EACH
82	720-07301 INLET TYPE HA	13.000	EACH
83	720-08242 MANHOLE, L15, MODIFIED	1.000	EACH
84	720-09078 MANHOLE, M5, MODIFIED	1.000	EACH
85	720-44000 CASTING, ADJUST TO GRADE	26.000	EACH
86	720-44000 CASTING, ADJUST TO GRADE	31.000	EACH
87	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000	EACH
88	720-45005 INLET, A2	2.000	EACH
89	720-45045 INLET, J10	36.000	EACH
90	720-45055 INLET, M10	20.000	EACH
91	720-45260 PIPE CATCH BASIN, 12 IN.	3.000	EACH
92	720-45270 PIPE CATCH BASIN, 18 IN.	5.000	EACH
93	720-45410 MANHOLE, C4	8.000	EACH
94	720-45425 MANHOLE, F4	1.000	EACH
95	720-93501 MANHOLE, L4	7.000	EACH
96	720-94612 MANHOLE, K4	8.000	EACH
97	720-95335 MANHOLE, M4	2.000	EACH
98	720-95422 MANHOLE, J4	10.000	EACH

CALL ORDER : 200

CONTRACT ID : R -28102-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REHABILITATION		
99	720-98174 INLET, B15	7.000	EACH
100	720-98555 INLET, C15	5.000	EACH
101	732-04926 VALVE	19.000	EACH
102	732-04987 CONNECTION	1.000	EACH
103	732-04987 CONNECTION	4.000	EACH
104	732-04987 CONNECTION	7.000	EACH
105	732-07653 COARSE AGGREGATE, NO. 8	47.000	TON
106	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
107	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
108	801-06625 DETOUR ROUTE MARKER ASSEMBLY	21.000	EACH
109	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
110	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
111	801-07118 BARRICADE, III-A	272.000	LFT
112	801-07119 BARRICADE, III-B	120.000	LFT
113	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	408.000	LFT
114	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	146.000	SFT
115	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	62.000	SFT
116	802-97059 SIGN AND SUPPORTS, WIDE FLANGE, RESET	1.000	EACH
117	805-90267 CONDUIT, STEEL, GALVANIZED, 3 IN.	662.000	LFT
118	807-02191 HANDHOLE, LIGHTING	18.000	EACH
119	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	7,600.000	LFT
120	807-08469 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING,	53.000	EACH
121	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	120.000	LFT
122	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8,550.000	LFT
123	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	310.000	LFT
124	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	430.000	LFT

CALL ORDER : 230

CONTRACT ID : R -29623-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	4,888.000	CYS
10	205-02770 EROSION CONTROL BLANKET	3,183.000	SYS
11	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	324.000	TON
12	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
13	205-06937 TEMPORARY SILT FENCE	6,081.000	LFT
14	210-04181 BICYCLE RACK	6.000	EACH
15	211-09264 STRUCTURE BACKFILL, TYPE 1	40.000	CYS
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,820.000	TON
17	303-04853 COMPACTED AGGREGATE	378.000	TON
18	402-07432 HMA SURFACE, TYPE A	400.000	TON
19	402-07435 HMA INTERMEDIATE, TYPE A	842.000	TON
20	601-03970 RAILING, WOOD, 4 FT. 6 IN.	1,400.000	LFT
21	604-04740 PAVERS	3,864.000	SFT
22	604-07903 CURB RAMP, CONCRETE, K	1.000	SYS
23	604-44251 STEPS, CONCRETE	10.000	CYS
24	604-91531 SIDEWALK, CONCRETE, 4 IN.	260.000	SYS
25	605-06090 CURB, INTEGRAL, CONCRETE	105.000	LFT
26	605-06121 CURB, CONCRETE, B	652.000	LFT
27	610-08510 PCCP FOR APPROACHES	712.000	SYS
28	611-03671 TRASH RECEPTACLE	4.000	EACH
29	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
30	621-04317 MULCHED SEEDING	4,291.000	SYS
31	621-06545 FERTILIZER	0.200	TON
32	621-06557 SEED MIXTURE, T	113.000	LBS
33	621-06565 MULCHING MATERIAL	3.000	TON
34	621-06570 TOP SOIL	929.100	CYS
35	621-06575 SODDING, NURSERY	1,357.000	SYS
36	621-06748 SEEDING	1,164.000	SYS
37	621-98038 MULCH, HARDWOOD SHREDDED BARK	120.000	CYS
38	622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN.	593.000	EACH
39	622-05647 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 120 IN.	3.000	EACH
40	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	51.000	EACH
41	622-05654 PLANT, PERENNIAL	922.000	EACH
42	622-05654 PLANT, PERENNIAL	3,766.000	EACH
43	628-09402 FIELD OFFICE, B	9.000	MOS
44	706-01268 HANDRAIL, ALUMINUM	94.200	LFT
45	712-03812 BENCH	4.000	EACH
46	715-04555 PIPE END SECTION, MIN. AREA 5.1 SQ. FT.	2.000	EACH
47	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	105.000	LFT
48	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	31.000	LFT
49	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	128.000	LFT

CALL ORDER : 230

CONTRACT ID : R -29623-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BIKE/PEDESTRIAN FACILITY			
50	715-05335 PIPE, TYPE 2, DEFORMED, MIN. AREA 5.1 SFT.	42.000	LFT
51	715-46000 PIPE END SECTION, 12 IN.	1.000	EACH
52	715-46005 PIPE END SECTION, 15 IN.	5.000	EACH
53	718-06531 OUTLET PROTECTOR, 3	1.000	EACH
54	720-45030 INLET, E7	1.000	EACH
55	720-90984 MANHOLE, C2	1.000	EACH
56	720-91051 INLET, A	2.000	EACH
57	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
58	802-03821 SIGN, SHEET WITH LEGEND	62.000	EACH
59	802-04314 SIGN	1.000	EACH
60	802-04314 SIGN	1.000	EACH
61	802-04314 SIGN	4.000	EACH
62	802-04314 SIGN	2.000	EACH
63	802-04314 SIGN	12.000	EACH
64	802-76055 SIGN POST, A	38.000	LFT
65	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	2.000	EACH
66	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	2.000	EACH
67	805-02262 FLASHER INSTALLATION	LUMP	LUMP
68	805-02262 FLASHER INSTALLATION	LUMP	LUMP
69	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. AMBER	8.000	EACH
70	805-78445 SIGNAL SERVICE	2.000	EACH
71	805-78467 SIGNAL CABLE, 3C 8GA.	64.000	LFT
72	805-78485 SIGNAL CABLE, 5C 14GA.	320.000	LFT
73	805-86810 SERVICE POINT, II	1.000	EACH
74	805-94069 CONDUIT, STEEL, GALVANIZED, 1 IN.	30.000	LFT
75	805-98335 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C	329.000	LFT
76	805-98336 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	85.000	LFT
77	807-03051 LIGHT CABLE, 1C 10GA.	118.000	LFT
78	807-03802 LIGHT STANDARDS	4.000	EACH
79	807-03950 LUMINAIRE, ORNAMENTAL	4.000	EACH
80	807-04653 LIGHTING FOUNDATION	4.000	EACH
81	807-86910 CONNECTOR KIT, UNFUSED	4.000	EACH
82	807-86915 CONNECTOR KIT, FUSED	4.000	EACH
83	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.000	EACH
84	807-86930 INSULATION LINK, NONWATERPROOFED	17.000	EACH
85	808-03114 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, (XING) 8 FT.	4.000	EACH
86	808-04767 LINE	120.000	LFT
87	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	240.000	LFT
88	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	180.000	LFT
89	808-75330 PAVEMENT MESSAGE MARKINGS THERMOPLASTIC, WORD (PEDX)	4.000	EACH
90	808-97222 PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	2.000	EACH

CALL ORDER : 240

CONTRACT ID : R -29627-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT W/ ADDED TURN LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02241 GUARDRAIL, REMOVE	185.000	LFT
10	202-02273 CENTER CURB, CONCRETE, REMOVE	5.000	SYS
11	202-02279 CURB AND GUTTER, REMOVE	261.000	LFT
12	202-91385 INLET, REMOVE	4.000	EACH
13	202-96133 PIPE, REMOVE	378.000	LFT
14	203-02000 EXCAVATION, COMMON	2,326.000	CYS
15	207-08263 SUBGRADE TREATMENT, TYPE IA	6,650.000	SYS
16	207-08266 SUBGRADE TREATMENT, TYPE III	1,750.000	SYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,358.000	SYS
18	211-09264 STRUCTURE BACKFILL, TYPE 1	784.000	CYS
19	306-08043 MILLING, TRANSITION	965.000	SYS
20	402-07433 HMA SURFACE, TYPE B	889.000	TON
21	402-07438 HMA INTERMEDIATE, TYPE B	1,314.000	TON
22	402-07441 HMA BASE, TYPE B	2,890.000	TON
23	402-07453 HMA FOR TEMPORARY PAVEMENT	385.000	TON
24	404-05514 SEAL COAT, 5	788.000	SYS
25	406-05520 ASPHALT FOR TACK COAT	4.300	TON
26	605-06140 CURB AND GUTTER, CONCRETE	1,627.000	LFT
27	605-06145 CURB AND GUTTER, B, CONCRETE	193.000	LFT
28	605-94811 CURB TURNOUT	1.000	EACH
29	610-07487 HMA FOR APPROACHES, TYPE B	355.000	TON
30	610-08446 PCCP FOR APPROACHES, 6 IN.	70.000	SYS
31	610-09108 PCCP FOR APPROACHES, 9 IN.	585.000	SYS
32	611-06497 MAILBOX ASSEMBLY, SINGLE	6.000	EACH
33	615-06505 MONUMENT, B	2.000	EACH
34	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
36	621-06545 FERTILIZER	0.100	TON
37	621-06557 SEED MIXTURE, T	82.000	LBS
38	621-06560 MULCHED SEEDING, U	451.000	SYS
39	621-06565 MULCHING MATERIAL	2.000	TON
40	621-06567 WATER	52.000	KGAL
41	621-06574 SODDING	149.000	SYS
42	621-06575 SODDING, NURSERY	4,450.000	SYS
43	628-09402 FIELD OFFICE, B	8.000	MOS
44	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	4.000	EACH
45	715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN.	9.000	LFT
46	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	940.000	LFT
47	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	25.000	LFT
48	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	403.000	LFT
49	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	483.000	LFT

CALL ORDER : 240

CONTRACT ID : R -29627-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT W/ ADDED TURN LANES		
50	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	168.000	LFT
51	715-05361 PIPE, TYPE 3, DEFORMED, MIN. AREA 1.1 SQ. FT.	61.000	LFT
52	715-08484 SAFETY METAL END SECTION, 6:1, MIN. AREA 0.15 m2	2.000	EACH
53	715-09064 VIDEO INSPECTION FOR PIPE	2,141.000	LFT
54	715-46000 PIPE END SECTION, 12 IN.	1.000	EACH
55	715-46005 PIPE END SECTION, 15 IN.	4.000	EACH
56	715-46045 PIPE END SECTION, MIN. AREA 1.1 SQ. FT.	2.000	EACH
57	720-45030 INLET, E7	1.000	EACH
58	720-45035 INLET, F7	6.000	EACH
59	720-45410 MANHOLE, C4	5.000	EACH
60	720-90984 MANHOLE, C2	1.000	EACH
61	720-98555 INLET, C15	9.000	EACH
62	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
63	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
64	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	16,247.000	LFT
65	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	72.000	LFT
66	801-06625 DETOUR ROUTE MARKER ASSEMBLY	4.000	EACH
67	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
68	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
69	801-07118 BARRICADE, III-A	48.000	LFT
70	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	28.000	SFT
71	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
72	805-01842 HANDHOLE, SIGNAL	4.000	EACH
73	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	333.000	LFT
74	805-01879 SIGNAL SERVICE, INSTALL	1.000	EACH
75	805-02328 SIGNAL CABLE, 1C 14GA.	3,964.000	LFT
76	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
77	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	7.000	EACH
78	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	1.000	EACH
79	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
80	805-78420 DISCONNECT HANGER	4.000	EACH
81	805-78467 SIGNAL CABLE, 3C 8GA.	44.000	LFT
82	805-78485 SIGNAL CABLE, 5C 14GA.	105.000	LFT
83	805-78490 SIGNAL CABLE, 7C 14GA.	473.000	LFT
84	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	734.000	LFT
85	805-78785 SIGNAL DETECTOR HOUSING	8.000	EACH
86	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,305.000	LFT
87	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
88	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	3.000	EACH
89	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	1.000	EACH
90	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,781.000	LFT
91	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	950.000	LFT
92	808-06716 LINE, REMOVE	5,307.000	LFT
93	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,352.000	LFT
94	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	118.000	LFT
95	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	5.000	EACH
96	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	5.000	EACH
97	808-96016 LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN.	232.000	LFT

CALL ORDER : 250

CONTRACT ID : R -29783-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	36.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	5,955.000	SYS
13	202-02241 GUARDRAIL, REMOVE	1,875.000	LFT
14	202-96133 PIPE, REMOVE	77.000	LFT
15	203-02000 EXCAVATION, COMMON	1,220.000	CYS
16	205-03371 SEDIMENT, REMOVE	600.000	CYS
17	205-06937 TEMPORARY SILT FENCE	2,000.000	LFT
18	207-08263 SUBGRADE TREATMENT, TYPE IA	11,050.000	SYS
19	211-02050 B BORROW	5,400.000	CYS
20	211-09266 STRUCTURE BACKFILL, TYPE 3	390.000	CYS
21	303-07449 COMPACTED AGGREGATE, NO. 73	480.000	TON
22	306-08034 MILLING, ASPHALT, 1 1/2 IN.	3,550.000	SYS
23	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
24	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,078.000	TON
25	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1,400.000	TON
26	401-07413 QC/QA-HMA, 3, 70, BASE, 25.0 mm	4,940.000	TON
27	406-05520 ASPHALT FOR TACK COAT	14.000	TON
28	601-01128 GUARDRAIL TRANSITION TYPE WGB	1.000	EACH
29	601-01322 GUARDRAIL END TREATMENT, OS, RESET	1.000	LFT
30	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	2.000	EACH
31	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	125.000	LFT
32	601-06035 GUARDRAIL, RESET	125.000	LFT
33	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,625.000	LFT
34	610-07488 HMA FOR APPROACHES, TYPE C	250.000	TON
35	615-01323 MONUMENT. IDOT CENTERLINE, INSTALL	5.000	EACH
36	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
37	616-07210 FIBER ROLL	2,000.000	LFT
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
39	621-06559 MULCHED SEEDING, R	1,400.000	SYS
40	628-09402 FIELD OFFICE, B	12.000	MOS
41	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
42	714-05562 RETAINING WALL	22,550.000	SFT
43	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	108.000	LFT
44	715-05136 PIPE, TYPE 1, CIRCULAR, 72 IN.	90.000	LFT
45	715-46000 PIPE END SECTION, 12 IN.	4.000	EACH
46	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
47	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
48	801-06625 DETOUR ROUTE MARKER ASSEMBLY	42.000	EACH
49	801-06640 CONSTRUCTION SIGN, A	40.000	EACH

CALL ORDER : 250

CONTRACT ID : R -29783-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
51	801-07118 BARRICADE, III-A	120.000	LFT
52	801-07119 BARRICADE, III-B	150.000	LFT
53	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
54	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,837.000	LFT
55	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6,000.000	LFT
56	808-75282 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID YELLOW, CROSSHATCH	360.000	LFT
57	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	200.000	LFT
58	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
59	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH
60	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	90.000	EACH
61	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	50.000	EACH

CALL ORDER : 260

CONTRACT ID : R -29923-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	80.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02241 GUARDRAIL, REMOVE	242.000	LFT
14	203-02000 EXCAVATION, COMMON	8,695.000	CYS
15	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	988.000	SYS
17	207-08268 SUBGRADE TREATMENT, TYPE IV	18,960.000	SYS
18	211-09264 STRUCTURE BACKFILL, TYPE 1	3,739.100	CYS
19	211-09268 STRUCTURE BACKFILL, TYPE 5	223.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	176.000	TON
21	303-07449 COMPACTED AGGREGATE, NO. 73	60.000	TON
22	304-07489 HMA PATCHING, TYPE A	243.000	TON
23	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	1,347.000	TON
24	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	2,277.000	TON
25	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	6,212.000	TON
26	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	2,477.000	TON
27	406-05520 ASPHALT FOR TACK COAT	17.000	TON
28	601-02800 GUARDRAIL TRANSITION, TGT	2.000	EACH
29	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
30	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	112.500	LFT
31	603-03398 FENCE, RELOCATE	196.000	LFT
32	604-07900 CURB RAMP, CONCRETE, F	231.000	SYS
33	604-07901 CURB RAMP, CONCRETE, G	297.000	SYS
34	604-07902 CURB RAMP, CONCRETE, H	7.000	SYS
35	604-07903 CURB RAMP, CONCRETE, K	16.000	SYS
36	604-44251 STEPS, CONCRETE	41.000	CYS
37	604-91531 SIDEWALK, CONCRETE, 4 IN.	2,586.000	SYS
38	605-06120 CURB, CONCRETE	483.000	LFT
39	605-06125 CURB, CONCRETE, MODIFIED	36.000	LFT
40	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	5,410.000	LFT
41	610-07486 HMA FOR APPROACHES, TYPE A	91.000	TON
42	610-08446 PCCP FOR APPROACHES, 6 IN.	337.000	SYS
43	610-09108 PCCP FOR APPROACHES, 9 IN.	405.000	SYS
44	615-06490 RIGHT OF WAY MARKER	147.000	EACH
45	615-06505 MONUMENT, B	5.000	EACH
46	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
47	616-02320 GEOTEXTILES	34.000	SYS
48	616-06405 RIPRAP, REVETMENT	52.000	TON
49	621-06567 WATER	26.200	KGAL

CALL ORDER : 260

CONTRACT ID : R -29923-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
50	621-06575 SODDING, NURSERY	6,549.000	SYS
51	628-09402 FIELD OFFICE, B	20.000	MOS
52	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	20.000	MOS
53	703-51030 REINFORCING STEEL	1,190.000	LBS
54	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	6,114.000	LFT
55	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	31.000	LFT
56	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	602.000	LFT
57	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	579.000	LFT
58	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	1,843.500	LFT
59	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	1,392.000	LFT
60	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	356.000	LFT
61	715-09064 VIDEO INSPECTION FOR PIPE	4,772.500	LFT
62	715-46010 PIPE END SECTION, 18 IN.	1.000	EACH
63	715-46030 PIPE END SECTION, 30 IN.	1.000	EACH
64	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
65	718-52610 AGGREGATE FOR UNDERDRAINS	490.000	CYS
66	718-99153 GEOTEXTILES FOR UNDERDRAIN	2,052.000	SYS
67	720-04666 CATCH BASIN	1.000	EACH
68	720-04666 CATCH BASIN	1.000	EACH
69	720-04790 CASTING	1.000	EACH
70	720-45030 INLET, E7	2.000	EACH
71	720-45045 INLET, J10	2.000	EACH
72	720-45250 CATCH BASIN, K10	15.000	EACH
73	720-45265 PIPE CATCH BASIN, 15 IN.	1.000	EACH
74	720-45410 MANHOLE, C4	21.000	EACH
75	720-95422 MANHOLE, J4	4.000	EACH
76	720-98687 CATCH BASIN, M10	4.000	EACH
77	720-99416 CATCH BASIN, B15	1.000	EACH
78	732-08419 MODULAR BLOCK WALL	186.000	SYS
79	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	178.000	SYS
80	732-08421 MODULAR BLOCK WALL ERECTION	364.000	SYS
81	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
82	801-06625 DETOUR ROUTE MARKER ASSEMBLY	27.000	EACH
83	801-06640 CONSTRUCTION SIGN, A	52.000	EACH
84	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
85	801-07119 BARRICADE, III-B	396.000	LFT
86	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	1,447.000	LFT
87	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	89.000	EACH
88	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	565.000	SFT
89	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	12.000	SFT
90	808-03114 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, (XING) 8 FT.	2.000	EACH
91	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	60.000	LFT
92	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	625.000	LFT
93	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,934.000	LFT
94	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6,656.000	LFT
95	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	395.000	LFT
96	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	2,293.000	LFT
97	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	18.000	EACH
98	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	17.000	EACH

CALL ORDER : 260

CONTRACT ID : R -29923-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
99 808-75330	PAVEMENT MESSAGE MARKINGS THERMOPLASTIC, WORD (PEDX)	2.000	EACH
100 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	103.000	EACH

CALL ORDER : 280

CONTRACT ID : R -31016-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6 202-02255	TREE, 18 IN., REMOVE	6.000	EACH
7 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
8 205-06937	TEMPORARY SILT FENCE	1,300.000	LFT
9 621-06559	MULCHED SEEDING, R	1,227.000	SYS
10 801-06640	CONSTRUCTION SIGN, A	3.000	EACH

CALL ORDER : 290

CONTRACT ID : R -31066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, BIKE/PEDESTRIAN FACILITY			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
3	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
4	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
5	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
6	202-02240 PAVEMENT REMOVAL	4,474.000	SYS
7	202-02241 GUARDRAIL, REMOVE	1,253.000	LFT
8	202-02278 CURB, CONCRETE, REMOVE	6,140.000	LFT
9	202-04089 SIGN, SHEET, REMOVE	23.000	EACH
10	202-52710 SIDEWALK, CONCRETE, REMOVE	4,050.000	SYS
11	202-91385 INLET, REMOVE	21.000	EACH
12	202-93047 MANHOLE, REMOVE	3.000	EACH
13	202-96133 PIPE, REMOVE	406.000	LFT
14	203-02000 EXCAVATION, COMMON	2,745.000	CYS
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	494.000	SYS
16	207-08268 SUBGRADE TREATMENT, TYPE IV	2,448.000	SYS
17	210-04181 BICYCLE RACK	19.000	EACH
18	210-07644 CONDUIT	30.000	EACH
19	210-08138 RECEPTACLE	37.000	EACH
20	210-09449 CURB RAMP, CONCRETE	20.310	SYS
21	210-09449 CURB RAMP, CONCRETE	80.750	SYS
22	210-09449 CURB RAMP, CONCRETE	42.700	SYS
23	210-09449 CURB RAMP, CONCRETE	15.390	SYS
24	210-09449 CURB RAMP, CONCRETE	167.000	SYS
25	210-09449 CURB RAMP, CONCRETE	13.000	SYS
26	210-09449 CURB RAMP, CONCRETE	63.420	SYS
27	210-09450 CROSSWALK	3,153.490	SFT
28	211-09264 STRUCTURE BACKFILL, TYPE 1	782.000	CYS
29	303-01180 COMPACTED AGGREGATE, NO. 53	3,061.480	TON
30	304-07490 HMA PATCHING, TYPE B	277.000	TON
31	304-07493 WIDENING WITH HMA, TYPE B	4.500	TON
32	306-08034 MILLING, ASPHALT, 1 1/2 IN.	7,869.000	SYS
33	402-07433 HMA SURFACE, TYPE B	650.000	TON
34	406-05520 ASPHALT FOR TACK COAT	2.000	TON
35	502-06327 PCCP, 10 IN.	2,282.000	SYS
36	603-03398 FENCE, RELOCATE	86.000	LFT
37	603-03692 FENCE, WOOD	14.670	LFT
38	604-04740 PAVERS	4,766.250	SFT
39	604-04740 PAVERS	31,600.270	SFT
40	604-04740 PAVERS	4,079.380	SFT
41	604-04740 PAVERS	8,248.640	SFT
42	604-04740 PAVERS	1,176.660	SFT
43	604-04740 PAVERS	11,633.810	SFT
44	604-04740 PAVERS	884.860	SFT
45	604-04740 PAVERS	7,310.160	SFT
46	604-04740 PAVERS	1,217.600	SFT
47	604-04740 PAVERS	3,548.640	SFT
48	604-04740 PAVERS	845.620	SFT
49	604-04740 PAVERS	1,645.660	SFT

CALL ORDER : 290

CONTRACT ID : R -31066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, BIKE/PEDESTRIAN FACILITY			
50	604-04740 PAVERS	14.670	SFT
51	604-04805 PAVER	8,714.900	LFT
52	604-06070 SIDEWALK, CONCRETE	60.540	SYS
53	604-07483 HMA FOR SIDEWALK	116.000	TON
54	604-07894 CURB RAMP, CONCRETE, A	137.000	SYS
55	604-07898 CURB RAMP, CONCRETE, D	6.000	SYS
56	604-07901 CURB RAMP, CONCRETE, G	23.060	SYS
57	604-07903 CURB RAMP, CONCRETE, K	64.000	SYS
58	604-91531 SIDEWALK, CONCRETE, 4 IN.	1,653.000	SYS
59	604-91531 SIDEWALK, CONCRETE, 4 IN.	6,843.940	SYS
60	605-06090 CURB, INTEGRAL, CONCRETE	1,680.000	LFT
61	605-06120 CURB, CONCRETE	3,857.000	LFT
62	605-06120 CURB, CONCRETE	258.770	LFT
63	605-06121 CURB, CONCRETE, B	68.000	LFT
64	605-06125 CURB, CONCRETE, MODIFIED	983.000	LFT
65	610-07487 HMA FOR APPROACHES, TYPE B	106.000	TON
66	610-08446 PCCP FOR APPROACHES, 6 IN.	128.000	SYS
67	610-08446 PCCP FOR APPROACHES, 6 IN.	1,304.870	SYS
68	610-08510 PCCP FOR APPROACHES	20.030	SYS
69	610-09108 PCCP FOR APPROACHES, 9 IN.	366.000	SYS
70	611-03671 TRASH RECEPTACLE	5.000	EACH
71	615-06505 MONUMENT, B	12.000	EACH
72	615-06515 MONUMENT, D	6.000	EACH
73	621-06570 TOP SOIL	980.190	CYS
74	621-06570 TOP SOIL	78.160	CYS
75	621-06570 TOP SOIL	330.490	CYS
76	621-06575 SODDING, NURSERY	584.000	SYS
77	621-98038 MULCH, HARDWOOD SHREDDED BARK	265.380	CYS
78	622-04992 DRAIN	11.000	EACH
79	622-04992 DRAIN	2.000	EACH
80	622-05616 PLANT, BROADLEAF EVERGREEN, GLOBE, DWARF, OVER 18 TO 24 IN.	614.000	EACH
81	622-05634 PLANT, CONIFEROUS EVERGREEN, PROSTRATE, BROAD SPREADING,	180.000	EACH
82	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	329.000	EACH
83	622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	282.000	EACH
84	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.	34.000	EACH
85	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	46.000	EACH
86	622-05653 PLANT, GROUND COVER	5,787.000	EACH
87	622-05654 PLANT, PERENNIAL	12,238.000	EACH
88	622-05654 PLANT, PERENNIAL	790.000	EACH
89	622-05654 PLANT, PERENNIAL	589.000	EACH
90	622-06573 IRRIGATION	1.000	EACH
91	702-51005 CONCRETE, A, SUBSTRUCTURE	6.560	CYS
92	702-51007 CONCRETE, A, ENCASEMENT	9.000	CYS
93	703-06028 REINFORCING BARS	1,959.000	LBS
94	706-04683 RAILING	18.000	LFT
95	711-51035 STRUCTURAL STEEL	96.000	LBS
96	712-03812 BENCH	7.000	EACH
97	715-05032 PIPE, TYPE 2, CIRCULAR, 15 IN.	2.000	LFT
98	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	987.000	LFT

CALL ORDER : 290

CONTRACT ID : R -31066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN FACILITY		
99 715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	4.000	LFT
100 715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	3,276.000	LFT
101 715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	2.000	LFT
102 715-09064	VIDEO INSPECTION FOR PIPE	6,083.000	LFT
103 715-90714	PIPE, PVC, 12 IN.	27.000	LFT
104 715-91361	PIPE, PVC, 6 IN.	1,777.000	LFT
105 715-96960	PIPE, PVC, 15 IN.	2.000	LFT
106 718-52610	AGGREGATE FOR UNDERDRAINS	30.000	CYS
107 718-99153	GEOTEXTILES FOR UNDERDRAIN	612.000	SYS
108 720-01894	CASTING, FURNISH AND ADJUST TO GRADE	7.000	EACH
109 720-02442	PIPE, PLUG EXISTING	3.000	EACH
110 720-04682	INLET,	49.000	EACH
111 720-44000	CASTING, ADJUST TO GRADE	28.000	EACH
112 720-45045	INLET, J10	9.000	EACH
113 720-45055	INLET, M10	9.000	EACH
114 720-45145	INLET, J10, MODIFIED	3.000	EACH
115 720-45235	CATCH BASIN, E7	1.000	EACH
116 720-45250	CATCH BASIN, K10	23.000	EACH
117 720-45410	MANHOLE, C4	11.000	EACH
118 720-45415	MANHOLE, D4	1.000	EACH
119 720-45510	MANHOLE, C4, MODIFIED	8.000	EACH
120 720-45515	MANHOLE, D4, MODIFIED	3.000	EACH
121 720-98687	CATCH BASIN, M10	15.000	EACH
122 732-04994	METER	10.000	EACH
123 801-03290	CONSTRUCTION SIGN, C	10.000	EACH
124 801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	15,383.000	LFT
125 801-06218	TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	57.000	LFT
126 801-06640	CONSTRUCTION SIGN, A	41.000	EACH
127 801-06645	CONSTRUCTION SIGN, B	31.000	EACH
128 801-06710	FLASHING ARROW SIGN	900.000	DAY
129 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
130 801-07119	BARRICADE, III-B	350.000	LFT
131 802-03896	BOLLARD	13.000	EACH
132 802-03896	BOLLARD	34.000	EACH
133 802-03896	BOLLARD	16.000	EACH
134 802-04314	SIGN	6.000	EACH
135 802-04314	SIGN	20.000	EACH
136 802-04314	SIGN	26.000	EACH
137 802-04314	SIGN	5.000	EACH
138 802-04314	SIGN	15.000	EACH
139 802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	186.000	LFT
140 802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	30.000	EACH
141 802-07060	SIGN, SHEET, RELOCATE	2.000	EACH
142 802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	324.000	SFT
143 802-93494	POST, ROUND, GALVANIZED	395.000	LFT
144 802-96248	POST, WOOD, 4 IN. X 4 IN.	40.000	LFT
145 805-01842	HANDHOLE, SIGNAL	26.000	EACH
146 805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	4.000	EACH
147 805-02036	SIGNAL CANTILEVER STRUCTURE, 15 FT. ARM	1.000	EACH

CALL ORDER : 290

CONTRACT ID : R -31066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, BIKE/PEDESTRIAN FACILITY			
148	805-02037 SIGNAL CANTILEVER STRUCTURE, 20 FT. ARM	2.000	EACH
149	805-02069 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM	1.000	EACH
150	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	1.000	EACH
151	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	1.000	EACH
152	805-02077 SIGNAL CANTILEVER STRUCTURE, 40 FT. ARM	1.000	EACH
153	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
154	805-02150 PEDESTRIAN SIGNAL HEAD, 18 IN.	26.000	EACH
155	805-02328 SIGNAL CABLE, 1C 14GA.	440.000	LFT
156	805-02373 INTERCONNECT CABLE, FIBER OPTIC	1,838.000	LFT
157	805-02855 SIGNAL SUPPORT FOUNDATION, 2 FT. 6 IN. X 2 FT. 6 IN. X 6 FT.	6.000	EACH
158	805-04133 SIGNAL PEDESTAL, 12 FT.	2.000	EACH
159	805-04808 PEDESTRIAN SIGNAL	1.000	EACH
160	805-04974 SIGNAL CONTROLLER	1.000	EACH
161	805-05405 SIGNAL PEDESTAL, 4 FT.	1.000	EACH
162	805-05870 SIGNAL SUPPORT FOUNDATION	4.000	EACH
163	805-06101 FOUNDATION	57.000	EACH
164	805-06101 FOUNDATION	32.000	EACH
165	805-06101 FOUNDATION	4.000	EACH
166	805-06362 SIGNAL AND LIGHTING COMBINATION POLE	1.000	EACH
167	805-06362 SIGNAL AND LIGHTING COMBINATION POLE	1.000	EACH
168	805-06362 SIGNAL AND LIGHTING COMBINATION POLE	1.000	EACH
169	805-06483 CONTROLLER	1.000	EACH
170	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	5,071.000	LFT
171	805-08102 DECORATIVE	3,153.490	EACH
172	805-08129 SIGNAL CABLE	196.000	LFT
173	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
174	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	2.000	EACH
175	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. AMBER	6.000	EACH
176	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	29.000	EACH
177	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000	EACH
178	805-78370 PEDESTRIAN PUSH BUTTON	16.000	EACH
179	805-78445 SIGNAL SERVICE	4.000	EACH
180	805-78465 SIGNAL CABLE, 2C 8GA.	545.000	LFT
181	805-78480 SIGNAL CABLE, 3C 14GA.	48.000	LFT
182	805-78485 SIGNAL CABLE, 5C 14GA.	10,629.000	LFT
183	805-78490 SIGNAL CABLE, 7C 14GA.	465.000	LFT
184	805-78495 SIGNAL CABLE, 9C 14GA.	1,505.000	LFT
185	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	208.000	LFT
186	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
187	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	180.000	LFT
188	805-78900 PEDESTAL FOUNDATION, A	5.000	EACH
189	805-78900 PEDESTAL FOUNDATION, A	15.000	EACH
190	805-78925 CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
191	805-90005 SIGNAL PEDESTAL, 10 FT.	2.000	EACH
192	805-90005 SIGNAL PEDESTAL, 10 FT.	15.000	EACH
193	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	1.000	EACH
194	805-95568 CONDUIT, PVC, 4 IN.	520.000	LFT
195	807-02191 HANDHOLE, LIGHTING	9.000	EACH
196	807-02191 HANDHOLE, LIGHTING	1.000	EACH

CALL ORDER : 290

CONTRACT ID : R -31066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, BIKE/PEDESTRIAN FACILITY			
197	807-04651 WIRE	900.000	LFT
198	807-04651 WIRE	2,400.000	LFT
199	807-04651 WIRE	1,800.000	LFT
200	807-04651 WIRE	1,400.000	LFT
201	807-04652 SERVICE POINT	8.000	EACH
202	807-04866 LUMINAIRE	32.000	EACH
203	807-04866 LUMINAIRE	4.000	EACH
204	807-04866 LUMINAIRE	4.000	EACH
205	807-04866 LUMINAIRE	8.000	EACH
206	807-04866 LUMINAIRE	4.000	EACH
207	807-04866 LUMINAIRE	57.000	EACH
208	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE	3.000	EACH
209	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	749.000	LFT
210	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	13.000	SYS
211	808-06368 TRANSVERSE MARKING, REMOVE	50.000	LFT
212	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	86.000	LFT
213	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	358.000	LFT
214	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	70.000	LFT
215	808-06716 LINE, REMOVE	5,699.000	LFT
216	808-08258 TRANSVERSE MARKINGS	68.000	LFT
217	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	610.000	LFT
218	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	835.000	LFT
219	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	280.000	LFT
220	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,098.000	LFT
221	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	330.000	LFT
222	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	5.000	EACH
223	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
224	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	13.000	EACH
225	808-97664 PAVEMENT MESSAGE MARKINGS THERMOPLASTIC, HANDICAP SYMBOL	2.000	EACH
226	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
227	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
228	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
229	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
230	109-08359 LIQUIDATED DAMAGES	1.000	DOL
231	109-08360 CONTRACT LIENS	1.000	DOL

CALL ORDER : 320

CONTRACT ID : RS-28853-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08523 RADIO SERVICE	12.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	202-02241 GUARDRAIL, REMOVE	5,540.000	LFT
15	202-02278 CURB, CONCRETE, REMOVE	339.000	LFT
16	202-52710 SIDEWALK, CONCRETE, REMOVE	202.000	SYS
17	202-93741 GUARD RAIL END TREATMENT, REMOVE	28.000	EACH
18	203-02070 BORROW	860.000	CYS
19	203-08607 LINEAR GRADING	38,066.000	LFT
20	303-01180 COMPACTED AGGREGATE, NO. 53	540.000	TON
21	304-07491 HMA PATCHING, TYPE C	1,500.000	TON
22	306-08033 MILLING, ASPHALT, 1 IN.	114,282.000	SYS
23	306-08034 MILLING, ASPHALT, 1 1/2 IN.	20,580.000	SYS
24	306-08043 MILLING, TRANSITION	4,199.000	SYS
25	306-08432 MILLING, APPROACH	9,740.000	SYS
26	401-06264 PROFILEGRAPH, HMA	LUMP	LUMP
27	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	11,473.000	TON
28	401-07379 QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	13,057.000	TON
29	406-05520 ASPHALT FOR TACK COAT	67.470	TON
30	601-01322 GUARDRAIL END TREATMENT, OS, RESET	2.000	LFT
31	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	1.000	EACH
32	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
33	601-05586 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 9	1.000	EACH
34	601-06035 GUARDRAIL, RESET	300.000	LFT
35	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	25.000	EACH
37	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	6,910.000	LFT
38	604-06070 SIDEWALK, CONCRETE	15.280	SYS
39	604-07894 CURB RAMP, CONCRETE, A	4.310	SYS
40	604-07896 CURB RAMP, CONCRETE, B	120.800	SYS
41	604-07901 CURB RAMP, CONCRETE, G	62.790	SYS
42	610-07488 HMA FOR APPROACHES, TYPE C	1,088.000	TON
43	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	10.800	TON
44	612-60410 DRILLED HOLE FOR UNDERSEAL	180.000	EACH
45	615-06505 MONUMENT, B	4.000	EACH
46	628-09402 FIELD OFFICE, B	12.000	MOS
47	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
48	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
49	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,861.000	LFT

CALL ORDER : 320

CONTRACT ID : RS-28853-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,160.000	LFT
51	801-06640 CONSTRUCTION SIGN, A	45.000	EACH
52	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
53	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	75,100.000	LFT
54	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	940.000	LFT
55	808-75215 LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	84.000	LFT
56	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	5,821.000	LFT
57	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	47,314.000	LFT
58	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	319.000	LFT
59	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	980.000	LFT
60	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	907.000	EACH

CALL ORDER : 360

CONTRACT ID : B -29014-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENVIRONMENTAL MITIGATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	600.000	LFT
13	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
14	203-02000 EXCAVATION, COMMON	16,613.000	CYS
15	203-02070 BORROW	8,247.000	CYS
16	203-51223 EXCAVATION, WATERWAY	1,200.000	CYS
17	205-03371 SEDIMENT, REMOVE	100.000	CYS
18	205-06936 TEMPORARY SEDIMENT TRAP	63.000	TON
19	205-06937 TEMPORARY SILT FENCE	1,175.000	LFT
20	205-06938 TEMPORARY SLOPE DRAIN	150.000	LFT
21	207-08265 SUBGRADE TREATMENT, TYPE IIA	6,126.000	SYS
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	110.000	SYS
23	211-09264 STRUCTURE BACKFILL, TYPE 1	8.000	CYS
24	211-09265 STRUCTURE BACKFILL, TYPE 2	1,058.000	CYS
25	212-06282 STOCKPILED SELECTED MATERIAL, SALVAGED	100.000	CYS
26	303-52308 COMPACTED AGGREGATE, 0, 53	2,543.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN.	489.000	SYS
28	402-07433 HMA SURFACE, TYPE B	591.000	TON
29	402-07438 HMA INTERMEDIATE, TYPE B	650.000	TON
30	404-05511 SEAL COAT, 2	1,688.000	SYS
31	406-05520 ASPHALT FOR TACK COAT	0.880	TON
32	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
33	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	919.000	LFT
34	610-07487 HMA FOR APPROACHES, TYPE B	30.000	TON
35	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
36	615-06490 RIGHT OF WAY MARKER	17.000	EACH
37	615-06505 MONUMENT, B	4.000	EACH
38	615-06510 MONUMENT, C	1.000	EACH
39	616-02320 GEOTEXTILES	2,134.000	SYS
40	616-05688 RIPRAP, CLASS 1	500.000	TON
41	616-06405 RIPRAP, REVETMENT	1,142.000	TON
42	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
43	621-02770 EROSION CONTROL BLANKET	3,011.000	SYS
44	621-04978 SEED MIXTURE	3,011.000	SYS
45	621-06545 FERTILIZER	1.370	TON
46	621-06553 SEED MIXTURE, R	581.000	LBS
47	621-06557 SEED MIXTURE, T	1,026.000	LBS
48	621-06565 MULCHING MATERIAL	6.840	TON
49	621-06567 WATER	6.300	KGAL

CALL ORDER : 360

CONTRACT ID : B -29014-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENVIRONMENTAL MITIGATION		
50	621-06574 SODDING	1,580.000	SYS
51	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	56.000	EACH
52	622-05643 PLANT, DECIDUOUS TREE, MULTI-STEM, 48 IN. OR UNDER	112.000	EACH
53	622-05654 PLANT, PERENNIAL	1,500.000	EACH
54	622-52436 SIGN, DO NOT MOW OR SPRAY	15.000	EACH
55	622-91786 SEEDLING	1,320.000	EACH
56	628-09402 FIELD OFFICE, B	12.000	MOS
57	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
58	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	10.000	LFT
59	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	50.000	LFT
60	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	36.000	LFT
61	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
62	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
63	720-45410 MANHOLE, C4	1.000	EACH
64	723-07807 STRUCTURE, PRECAST THREE-SIDED, 264 IN. X 96 IN.	126.000	LFT
65	723-08608 WINGWALL	416.000	SFT
66	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
67	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
68	801-06625 DETOUR ROUTE MARKER ASSEMBLY	13.000	EACH
69	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
70	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
71	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
72	801-07118 BARRICADE, III-A	60.000	LFT
73	801-07119 BARRICADE, III-B	80.000	LFT
74	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	36.000	LFT
75	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	30.750	SFT
76	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	2,986.000	LFT
77	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,986.000	LFT
78	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	76.000	EACH

CALL ORDER : 370

CONTRACT ID : B -29072-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
5	105-08523 RADIO SERVICE	10.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02240 PAVEMENT REMOVAL	471.000	SYS
16	202-02241 GUARDRAIL, REMOVE	921.000	LFT
17	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
18	202-51822 BRIDGE DECK OVERLAY, REMOVE	1,976.000	SYS
19	202-93741 GUARD RAIL END TREATMENT, REMOVE	4.000	EACH
20	203-02000 EXCAVATION, COMMON	385.000	CYS
21	203-02070 BORROW	9.000	CYS
22	205-06937 TEMPORARY SILT FENCE	450.000	LFT
23	211-06467 AGGREGATE FOR END BENT BACKFILL	21.000	CYS
24	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	8.000	CYS
25	302-07455 DENSE GRADED SUBBASE	78.500	CYS
26	306-08043 MILLING, TRANSITION	240.000	SYS
27	402-07433 HMA SURFACE, TYPE B	80.000	TON
28	402-07438 HMA INTERMEDIATE, TYPE B	133.000	TON
29	402-07441 HMA BASE, TYPE B	558.000	TON
30	402-07451 HMA WEDGE AND LEVEL, TYPE B	20.000	TON
31	406-05520 ASPHALT FOR TACK COAT	0.800	TON
32	502-06329 PCCP, 12 IN.	183.000	SYS
33	503-03489 RETROFITTED TIE BARS	72.000	EACH
34	503-05310 TERMINAL JOINT	72.000	LFT
35	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
36	601-05999 CURVED TERMINAL END	1.000	EACH
37	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
38	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
39	601-94690 GUARDRAIL END TREATMENT, MS	2.000	EACH
40	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	744.000	LFT
41	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	157.000	LFT
42	602-06729 BARRIER DELINEATOR	26.000	EACH
43	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	289.000	SYS
44	616-02320 GEOTEXTILES	350.000	SYS
45	616-06405 RIPRAP, REVETMENT	136.000	TON
46	616-51367 SLOPEWALL, CONCRETE, 4 IN.	2.000	SYS
47	616-93772 INSPECTION HOLE	2.000	EACH
48	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
49	621-06559 MULCHED SEEDING, R	1,200.000	SYS

CALL ORDER : 370

CONTRACT ID : B -29072-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
50	621-06567 WATER	1.000	KGAL
51	621-06574 SODDING	91.000	SYS
52	628-09401 FIELD OFFICE, A	10.000	MOS
53	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	10.000	MOS
54	702-51005 CONCRETE, A, SUBSTRUCTURE	6.100	CYS
55	702-51863 FIELD DRILLED HOLE IN CONCRETE	1,242.000	EACH
56	702-92857 CONCRETE, C, SUBSTRUCTURE	15.300	CYS
57	703-06029 REINFORCING BARS, EPOXY COATED	32,220.000	LBS
58	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	132.000	EACH
59	704-51002 CONCRETE, C, SUPERSTRUCTURE	12.900	CYS
60	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
61	706-51020 CONCRETE, C, RAILING	128.000	CYS
62	709-51821 SURFACE SEAL	LUMP	LUMP
63	711-04121 ANCHOR BOLT, AB1	36.000	EACH
64	711-51035 STRUCTURAL STEEL	6,237.000	LBS
65	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
66	711-61500 DIAPHRAGM	16.000	EACH
67	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	889.000	SFT
68	722-51842 BRIDGE DECK OVERLAY	1,976.000	SYS
69	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	20.000	CYS
70	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	1,778.000	SFT
71	722-60824 SURFACE MILLING	1,976.000	SYS
72	724-03276 EXPANSION JOINT SEALING SYSTEM	56.000	LFT
73	724-51925 STRUCTURAL EXPANSION JOINT, SS	112.000	LFT
74	726-92406 BEARING ASSEMBLY, ELASTOMERIC	2.000	EACH
75	726-92406 BEARING ASSEMBLY, ELASTOMERIC	7.000	EACH
76	726-97941 BEARING ASSEMBLY, TFE ELASTOMERIC	2.000	EACH
77	726-97941 BEARING ASSEMBLY, TFE ELASTOMERIC	7.000	EACH
78	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
79	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
80	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,079.000	LFT
81	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	2.000	EACH
82	801-06640 CONSTRUCTION SIGN, A	77.000	EACH
83	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
84	801-06710 FLASHING ARROW SIGN	600.000	DAY
85	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
86	801-07118 BARRICADE, III-A	60.000	LFT
87	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	720.000	LFT
88	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	1,480.000	LFT
89	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
90	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	5.000	SYS
91	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	5,274.000	LFT
92	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,437.000	LFT
93	808-06716 LINE, REMOVE	2,827.000	LFT
94	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,437.000	LFT
95	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
96	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	44.000	EACH
97	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	44.000	EACH

CALL ORDER : 380

CONTRACT ID : B -29475-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	6,550.000	CYS
14	203-02070 BORROW	9,520.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	53.000	TON
16	205-06932 TEMPORARY CHECK DAM, STRAW BALES	234.000	LFT
17	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
18	205-06937 TEMPORARY SILT FENCE	2,755.000	LFT
19	206-51215 EXCAVATION, X	20.800	CYS
20	206-51220 EXCAVATION, WET	490.600	CYS
21	211-02050 B BORROW	98.000	CYS
22	211-06467 AGGREGATE FOR END BENT BACKFILL	77.600	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,600.000	TON
24	303-07449 COMPACTED AGGREGATE, NO. 73	207.000	TON
25	402-07432 HMA SURFACE, TYPE A	432.000	TON
26	402-07435 HMA INTERMEDIATE, TYPE A	736.000	TON
27	406-05521 ASPHALT FOR TACK COAT	6,761.000	SYS
28	601-06037 GUARDRAIL END TREATMENT, I	8.000	EACH
29	601-06374 GUARDRAIL TRANSITION, TGS-1	8.000	EACH
30	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	481.250	LFT
31	603-04847 FENCE GATE	1.000	EACH
32	603-06040 FENCE, FARM FIELD, 47 IN.	322.000	LFT
33	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	139.000	SYS
34	609-08229 REINFORCED CONCRETE BRIDGE APPROACH	183.100	SYS
35	610-07486 HMA FOR APPROACHES, TYPE A	312.000	TON
36	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
37	615-06505 MONUMENT, B	5.000	EACH
38	616-02320 GEOTEXTILES	3,418.000	SYS
39	616-05688 RIPRAP, CLASS 1	1,025.000	TON
40	616-06405 RIPRAP, REVETMENT	1,241.000	TON
41	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
42	621-01956 SEED MIXTURE, LEGUME, 1	740.000	LBS
43	621-02468 SEED MIXTURE, GRASS, 1	760.000	LBS
44	621-06545 FERTILIZER	1.600	TON
45	621-06565 MULCHING MATERIAL	8.000	TON
46	621-06567 WATER	8.000	KGAL
47	621-06574 SODDING	1,999.000	SYS
48	621-06575 SODDING, NURSERY	347.000	SYS
49	622-52436 SIGN, DO NOT MOW OR SPRAY	8.000	EACH

CALL ORDER : 380

CONTRACT ID : B -29475-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	622-98200 SIGN, DO NOT DISTURB	8.000	EACH
51	628-09402 FIELD OFFICE, B	14.000	MOS
52	701-91792 PILE TIP, STEEL H	64.000	EACH
53	701-93658 PILE, STEEL H, HP 12 X 63	1,303.000	LFT
54	702-51015 CONCRETE, B, FOOTINGS	123.500	CYS
55	702-90915 CONCRETE, A	208.400	CYS
56	703-51030 REINFORCING STEEL	36,647.000	LBS
57	703-51032 REINFORCING STEEL, EPOXY COATED	126,371.000	LBS
58	704-51002 CONCRETE, C, SUPERSTRUCTURE	464.800	CYS
59	706-06344 RAILING, TS-1	887.500	LFT
60	707-05980 STRUCTURAL MEMBER, CONCRETE BOX BEAM, CB, 33 IN. X 48 IN.	1,382.700	LFT
61	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 45 IN. X 16 IN.	1,140.000	LFT
62	709-51821 SURFACE SEAL	LUMP	LUMP
63	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	7.000	EACH
64	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	72.000	LFT
65	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	358.000	LFT
66	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	154.000	LFT
67	715-05407 PIPE, END BENT DRAIN, 6 IN.	177.000	LFT
68	726-93526 BEARING ASSEMBLY, III	10.000	EACH
69	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
70	801-06625 DETOUR ROUTE MARKER ASSEMBLY	15.000	EACH
71	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
72	801-07118 BARRICADE, III-A	108.000	LFT
73	801-07119 BARRICADE, III-B	40.000	LFT
74	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	56.250	SFT
75	802-76055 SIGN POST, A	126.000	LFT
76	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,928.000	LFT
77	808-75215 LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	48.000	LFT

CALL ORDER : 390

CONTRACT ID : B -29595-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
5	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	36.000	SYS
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	2,713.000	CYS
11	203-02070 BORROW	4,387.000	CYS
12	204-02290 SETTLEMENT PLATE	4.000	EACH
13	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	12.000	EACH
14	205-03371 SEDIMENT, REMOVE	51.000	CYS
15	205-06932 TEMPORARY CHECK DAM, STRAW BALES	54.000	LFT
16	205-06933 TEMPORARY DITCH INLET PROTECTION	5.000	EACH
17	205-06937 TEMPORARY SILT FENCE	2,710.000	LFT
18	207-08266 SUBGRADE TREATMENT, TYPE III	4,640.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	717.000	SYS
20	211-02050 B BORROW	2,083.000	CYS
21	211-06467 AGGREGATE FOR END BENT BACKFILL	40.000	CYS
22	211-09264 STRUCTURE BACKFILL, TYPE 1	778.000	CYS
23	211-09266 STRUCTURE BACKFILL, TYPE 3	3,071.000	CYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,716.000	TON
25	302-07455 DENSE GRADED SUBBASE	38.000	CYS
26	402-07432 HMA SURFACE, TYPE A	313.000	TON
27	402-07435 HMA INTERMEDIATE, TYPE A	535.000	TON
28	406-05521 ASPHALT FOR TACK COAT	4,511.000	SYS
29	601-01128 GUARDRAIL TRANSITION TYPE WGB	4.000	EACH
30	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
31	601-01740 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 4	1.000	EACH
32	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	100.000	LFT
33	601-06037 GUARDRAIL END TREATMENT, I	2.000	EACH
34	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	247.500	LFT
35	602-06729 BARRIER DELINEATOR	6.000	EACH
36	604-91531 SIDEWALK, CONCRETE, 4 IN.	18.000	SYS
37	607-06335 PAVED SIDE DITCH, A	113.000	LFT
38	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	224.000	SYS
39	610-07487 HMA FOR APPROACHES, TYPE B	200.000	TON
40	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
41	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
42	615-06490 RIGHT OF WAY MARKER	22.000	EACH
43	615-06505 MONUMENT, B	4.000	EACH
44	616-02320 GEOTEXTILES	314.000	SYS
45	616-06405 RIPRAP, REVETMENT	217.000	TON
46	616-06451 RIPRAP, UNIFORM	27.000	TON
47	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
48	621-06545 FERTILIZER	0.600	TON
49	621-06553 SEED MIXTURE, R	0.100	LBS

CALL ORDER : 390

CONTRACT ID : B -29595-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06557 SEED MIXTURE, T	92.000	LBS
51	621-06565 MULCHING MATERIAL	4.600	TON
52	621-06567 WATER	0.700	KGAL
53	621-06574 SODDING	190.000	SYS
54	628-09402 FIELD OFFICE, B	10.000	MOS
55	701-51195 PILE, STEEL H, HP 12 X 53	520.000	LFT
56	701-91792 PILE TIP, STEEL H	10.000	EACH
57	703-06029 REINFORCING BARS, EPOXY COATED	48,488.000	LBS
58	704-51002 CONCRETE, C, SUPERSTRUCTURE	128.400	CYS
59	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	4.000	EACH
60	706-51020 CONCRETE, C, RAILING	15.400	CYS
61	709-51821 SURFACE SEAL	LUMP	LUMP
62	711-51038 STRUCTURAL STEEL	LUMP	LUMP
63	711-51070 ANCHOR PLATE, AP 1	16.000	EACH
64	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	156.000	LFT
65	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	31.000	LFT
66	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	785.000	LFT
67	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	208.000	LFT
68	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	30.000	LFT
69	715-05422 PIPE, SLOTTED DRAIN, 12 IN.	29.000	LFT
70	715-46005 PIPE END SECTION, 15 IN.	3.000	EACH
71	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
72	715-46040 PIPE END SECTION, 36 IN.	2.000	EACH
73	715-91361 PIPE, PVC, 6 IN.	11.000	LFT
74	715-93910 WATER SERVICE LINE, ADJUST	4.000	EACH
75	720-45035 INLET, F7	9.000	EACH
76	720-45235 CATCH BASIN, E7	1.000	EACH
77	720-94612 MANHOLE, K4	1.000	EACH
78	720-97958 MANHOLE, K2	2.000	EACH
79	731-93945 FACE PANELS, CONCRETE	5,579.000	SFT
80	731-93946 WALL ERECTION	5,579.000	SFT
81	731-93947 LEVELING PAD, CONCRETE	331.000	LFT
82	732-90578 WATER METER, RELOCATE	4.000	EACH
83	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
84	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
85	801-06625 DETOUR ROUTE MARKER ASSEMBLY	7.000	EACH
86	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
87	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
88	801-07118 BARRICADE, III-A	96.000	LFT
89	801-07119 BARRICADE, III-B	96.000	LFT
90	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	55.000	LFT
91	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	36.000	SFT
92	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	2,673.000	LFT
93	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	2,632.000	LFT
94	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	97.000	LFT

CALL ORDER : 400

CONTRACT ID : B -30195-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	202-96133 PIPE, REMOVE	90.000	LFT
12	203-02000 EXCAVATION, COMMON	949.000	CYS
13	203-02070 BORROW	6,239.000	CYS
14	203-51223 EXCAVATION, WATERWAY	1,085.000	CYS
15	204-02290 SETTLEMENT PLATE	5.000	EACH
16	205-06932 TEMPORARY CHECK DAM, STRAW BALES	64.000	LFT
17	205-06937 TEMPORARY SILT FENCE	2,300.000	LFT
18	207-08266 SUBGRADE TREATMENT, TYPE III	2,262.000	SYS
19	211-06467 AGGREGATE FOR END BENT BACKFILL	54.400	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,031.000	TON
21	302-07455 DENSE GRADED SUBBASE	26.300	CYS
22	303-07449 COMPACTED AGGREGATE, NO. 73	318.600	TON
23	402-07432 HMA SURFACE, TYPE A	155.000	TON
24	402-07440 HMA BASE, TYPE A	259.000	TON
25	404-05514 SEAL COAT, 5	1,250.000	SYS
26	405-05518 ASPHALT FOR PRIME COAT	1,882.000	SYS
27	406-05521 ASPHALT FOR TACK COAT	1,882.000	SYS
28	601-01128 GUARDRAIL TRANSITION TYPE WGB	4.000	EACH
29	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	4.000	EACH
30	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	143.750	LFT
31	602-06729 BARRIER DELINEATOR	6.000	EACH
32	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	157.600	SYS
33	615-06490 RIGHT OF WAY MARKER	21.000	EACH
34	616-02320 GEOTEXTILES	1,288.000	SYS
35	616-06405 RIPRAP, REVETMENT	842.000	TON
36	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
37	621-06545 FERTILIZER	0.550	TON
38	621-06553 SEED MIXTURE, R	190.000	LBS
39	621-06557 SEED MIXTURE, T	88.000	LBS
40	621-06565 MULCHING MATERIAL	4.400	TON
41	621-06574 SODDING	48.000	SYS
42	622-52436 SIGN, DO NOT MOW OR SPRAY	3.000	EACH
43	622-91786 SEEDLING	60.000	EACH
44	628-09401 FIELD OFFICE, A	10.000	MOS
45	701-98647 PILE, CONCRETE, STEEL SHELL ENCASED, 0.203 IN., 14 IN.	664.000	LFT
46	701-99086 PILE TIP, STEEL SHELL	18.000	EACH
47	703-06029 REINFORCING BARS, EPOXY COATED	39,755.000	LBS
48	704-51002 CONCRETE, C, SUPERSTRUCTURE	168.700	CYS
49	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	4.000	EACH

CALL ORDER : 400

CONTRACT ID : B -30195-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	706-51020 CONCRETE, C, RAILING	15.200	CYS
51	707-06831 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 54 IN. X 42 IN.	384.000	LFT
52	709-51821 SURFACE SEAL	LUMP	LUMP
53	711-51070 ANCHOR PLATE, AP 1	16.000	EACH
54	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	52.000	LFT
55	715-05175 PIPE, TYPE 3, CIRCULAR, 30 IN.	60.000	LFT
56	715-05407 PIPE, END BENT DRAIN, 6 IN.	110.000	LFT
57	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
58	715-46030 PIPE END SECTION, 30 IN.	2.000	EACH
59	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
60	801-06625 DETOUR ROUTE MARKER ASSEMBLY	9.000	EACH
61	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
62	801-07118 BARRICADE, III-A	48.000	LFT
63	801-07119 BARRICADE, III-B	48.000	LFT
64	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	22.000	LFT
65	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	10.000	SFT
66	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	2,000.000	LFT
67	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	2,000.000	LFT

CALL ORDER : 420

CONTRACT ID : B -30979-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
14	202-96133 PIPE, REMOVE	36.100	LFT
15	203-02000 EXCAVATION, COMMON	14,806.000	CYS
16	203-02020 EXCAVATION, UNCLASSIFIED	31,488.000	CYS
17	203-02070 BORROW	25,350.000	CYS
18	204-02290 SETTLEMENT PLATE	5.000	EACH
19	205-03371 SEDIMENT, REMOVE	236.000	CYS
20	205-06930 SPLASHPAD, RIPRAP	5.200	TON
21	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	133.000	TON
22	205-06934 TEMPORARY MULCHING	12.500	TON
23	205-06937 TEMPORARY SILT FENCE	8,170.000	LFT
24	205-06938 TEMPORARY SLOPE DRAIN	46.000	LFT
25	205-08594 FILTER SOCK	6,978.300	LFT
26	206-51220 EXCAVATION, WET	388.000	CYS
27	206-51225 EXCAVATION, DRY	403.000	CYS
28	207-08264 SUBGRADE TREATMENT, TYPE II	17,301.000	SYS
29	211-02050 B BORROW	12,898.000	CYS
30	211-06467 AGGREGATE FOR END BENT BACKFILL	70.000	CYS
31	211-07454 STRUCTURE BACKFILL	911.000	CYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,063.000	TON
33	302-07455 DENSE GRADED SUBBASE	36.000	CYS
34	303-07662 STONE	50.000	TON
35	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,037.000	TON
36	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	3,174.000	TON
37	405-05517 ASPHALT FOR PRIME COAT	20.000	TON
38	406-05520 ASPHALT FOR TACK COAT	4.000	TON
39	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
40	601-01740 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 4	1.000	EACH
41	601-94689 GUARDRAIL END TREATMENT, OS	7.000	EACH
42	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,797.500	LFT
43	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	212.000	SYS
44	610-07486 HMA FOR APPROACHES, TYPE A	84.000	TON
45	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
46	616-02320 GEOTEXTILES	1,922.000	SYS
47	616-05689 RIPRAP, CLASS 2	189.000	TON
48	616-06405 RIPRAP, REVETMENT	1,037.000	TON
49	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH

CALL ORDER : 420

CONTRACT ID : B -30979-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-02318 SEED MIXTURE, PRAIRIE GRASS	62.730	LBS
51	621-02468 SEED MIXTURE, GRASS, 1	1,334.460	LBS
52	621-02770 EROSION CONTROL BLANKET	59.800	SYS
53	621-06545 FERTILIZER	7.350	TON
54	621-06553 SEED MIXTURE, R	801.000	LBS
55	621-06557 SEED MIXTURE, T	716.000	LBS
56	621-06565 MULCHING MATERIAL	53.380	TON
57	621-06567 WATER	7,504.000	KGAL
58	621-06574 SODDING	921.000	SYS
59	621-06575 SODDING, NURSERY	264.000	SYS
60	621-52448 SIGN, DO NOT SPRAY	11.000	EACH
61	622-91786 SEEDLING	3,500.000	EACH
62	622-91786 SEEDLING	10,325.000	EACH
63	624-92647 HERBICIDE TREATMENT	10.850	ACRE
64	628-09402 FIELD OFFICE, B	20.000	MOS
65	701-51195 PILE, STEEL H, HP 12 X 53	1,660.000	LFT
66	701-91792 PILE TIP, STEEL H	50.000	EACH
67	702-51005 CONCRETE, A, SUBSTRUCTURE	240.000	CYS
68	702-51015 CONCRETE, B, FOOTINGS	102.000	CYS
69	703-51030 REINFORCING STEEL	44,530.000	LBS
70	703-51032 REINFORCING STEEL, EPOXY COATED	86,778.000	LBS
71	704-51002 CONCRETE, C, SUPERSTRUCTURE	213.000	CYS
72	706-06341 RAILING, PF-2	430.000	LFT
73	706-06352 CONCRETE BRIDGE RAILING TRANSITION, TPF-2	4.000	EACH
74	706-51020 CONCRETE, C, RAILING	20.000	CYS
75	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 45 IN. X 16 IN.	800.000	LFT
76	709-51821 SURFACE SEAL	LUMP	LUMP
77	714-07022 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 20 FT. X 6 FT.	195.000	LFT
78	714-93637 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 6 FT. X 2 FT.6 IN	30.000	LFT
79	715-02246 PIPE END SECTION, 48 IN.	2.000	EACH
80	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	308.000	LFT
81	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	65.000	LFT
82	715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN.	43.000	LFT
83	715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN.	110.000	LFT
84	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	100.000	LFT
85	715-05407 PIPE, END BENT DRAIN, 6 IN.	124.000	LFT
86	715-05439 PIPE, DRAINTILE TERMINAL SECTION, 6 IN	200.000	LFT
87	715-05440 PIPE, DRAINTILE TERMINAL SECTION, 8 IN	200.000	LFT
88	715-05442 PIPE, DRAINTILE TERMINAL SECTION, 10 IN	200.000	LFT
89	715-46005 PIPE END SECTION, 15 IN.	4.000	EACH
90	715-46010 PIPE END SECTION, 18 IN.	14.000	EACH
91	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
92	715-46030 PIPE END SECTION, 30 IN.	2.000	EACH
93	724-51925 STRUCTURAL EXPANSION JOINT, SS	80.000	LFT
94	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
95	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
96	801-07118 BARRICADE, III-A	30.000	LFT
97	804-06770 DELINEATOR POST	136.000	EACH
98	807-04988 BOX	17.000	EACH

CALL ORDER : 420

CONTRACT ID : B -30979-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
99 808-03631	LINE, EPOXY, SOLID, WHITE, 4 IN.	538.000	LFT
100 808-03632	LINE, EPOXY, SOLID, YELLOW, 4 IN.	538.000	LFT
101 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	9,662.000	LFT
102 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	9,662.000	LFT

CALL ORDER : 450

CONTRACT ID : M -30675-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REHABILITATION		
1 105-08520	CELLULAR TELEPHONE/RADIO	1.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	9.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 109-08359	LIQUIDATED DAMAGES	1.000	DOL
5 109-08360	CONTRACT LIENS	1.000	DOL
6 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9 201-52370	CLEARING RIGHT OF WAY	LUMP	LUMP
10 201-90788	DEBRIS, REMOVE	LUMP	LUMP
11 213-08058	FLOWABLE BACKFILL	8.000	CYS
12 616-06405	RIPRAP, REVETMENT	40.000	TON
13 628-09408	MOBILE LAPTOP COMPUTER SYSTEM	9.000	MOS
14 628-09409	MOBILE INTERNET SERVICE	9.000	MOS
15 801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.000	EACH
16 801-03290	CONSTRUCTION SIGN, C	4.000	EACH
17 801-06640	CONSTRUCTION SIGN, A	6.000	EACH
18 801-06710	FLASHING ARROW SIGN	120.000	DAY
19 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 460

CONTRACT ID : M -31097-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	WEDGE AND LEVEL		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-07449 COMPACTED AGGREGATE, NO. 73	1,000.000	TON
8	304-07490 HMA PATCHING, TYPE B	300.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	1,566.000	SYS
10	306-08042 MILLING, SCARIFICATION/PROFILE	38,208.000	SYS
11	306-08043 MILLING, TRANSITION	2,880.000	SYS
12	402-07451 HMA WEDGE AND LEVEL, TYPE B	3,800.000	TON
13	406-05520 ASPHALT FOR TACK COAT	14.000	TON
14	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
15	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	400.000	LFT
16	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	400.000	LFT
17	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
18	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
19	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	3,945.000	LFT
20	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	31,972.000	LFT
21	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	2,164.000	LFT
22	808-75097 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	24.000	LFT

CALL ORDER : 470

CONTRACT ID : M -31116-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-94749 CURB, ASPHALT, REMOVE	525.000	LFT
8	304-07490 HMA PATCHING, TYPE B	100.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	26,850.000	SYS
10	306-08043 MILLING, TRANSITION	100.000	SYS
11	306-08432 MILLING, APPROACH	340.000	SYS
12	402-07433 HMA SURFACE, TYPE B	3,228.000	TON
13	406-05520 ASPHALT FOR TACK COAT	10.400	TON
14	605-05523 CURB, HMA	650.000	LFT
15	615-97768 PARKING BARRIER, RESET	40.000	EACH
16	628-09401 FIELD OFFICE, A	4.000	MOS
17	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	2.000	MOS
18	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
19	801-03290 CONSTRUCTION SIGN, C	20.000	EACH
20	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	100.000	LFT
21	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	100.000	LFT
22	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
24	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	500.000	LFT
25	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	50.000	LFT
26	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	160.000	LFT
27	808-05929 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 8 IN.	44.000	LFT
28	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	6,485.000	LFT
29	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	785.000	LFT
30	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN.	1,650.000	LFT
31	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	82.000	LFT
32	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	12.000	EACH
33	808-97222 PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	38.000	EACH

CALL ORDER : 500

CONTRACT ID : T -29389-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNAL MAINTENANCE			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	17.000	EACH
8	202-02278 CURB, CONCRETE, REMOVE	499.000	LFT
9	202-52710 SIDEWALK, CONCRETE, REMOVE	467.000	SYS
10	203-02000 EXCAVATION, COMMON	207.000	CYS
11	211-02050 B BORROW	24.000	CYS
12	402-07433 HMA SURFACE, TYPE B	16.000	TON
13	604-07894 CURB RAMP, CONCRETE, A	39.000	SYS
14	604-07896 CURB RAMP, CONCRETE, B	29.000	SYS
15	604-07898 CURB RAMP, CONCRETE, D	62.000	SYS
16	604-07900 CURB RAMP, CONCRETE, F	82.000	SYS
17	604-07901 CURB RAMP, CONCRETE, G	53.000	SYS
18	604-07902 CURB RAMP, CONCRETE, H	16.000	SYS
19	604-07903 CURB RAMP, CONCRETE, K	20.000	SYS
20	604-91531 SIDEWALK, CONCRETE, 4 IN.	371.000	SYS
21	605-06120 CURB, CONCRETE	650.000	LFT
22	610-07487 HMA FOR APPROACHES, TYPE B	15.000	TON
23	621-06570 TOP SOIL	24.000	CYS
24	621-06574 SODDING	143.000	SYS
25	628-09401 FIELD OFFICE, A	12.000	MOS
26	715-06690 PIPE, RCP, III, D0.01=1500, 12 IN.	34.000	LFT
27	720-44015 CASTING, 2, FURNISH AND ADJUST TO GRADE	1.000	EACH
28	720-45005 INLET, A2	1.000	EACH
29	720-45265 PIPE CATCH BASIN, 15 IN.	1.000	EACH
30	722-60824 SURFACE MILLING	190.000	SYS
31	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
32	801-06640 CONSTRUCTION SIGN, A	66.000	EACH
33	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
34	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	11.000	EACH
35	805-01842 HANDHOLE, SIGNAL	48.000	EACH
36	805-01879 SIGNAL SERVICE, INSTALL	17.000	EACH
37	805-02036 SIGNAL CANTILEVER STRUCTURE, 15 FT. ARM	2.000	EACH
38	805-02037 SIGNAL CANTILEVER STRUCTURE, 20 FT. ARM	1.000	EACH
39	805-02037 SIGNAL CANTILEVER STRUCTURE, 20 FT. ARM	1.000	EACH
40	805-02037 SIGNAL CANTILEVER STRUCTURE, 20 FT. ARM	1.000	EACH
41	805-02069 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM	3.000	EACH
42	805-02069 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM	1.000	EACH
43	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	4.000	EACH
44	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	3.000	EACH
45	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	1.000	EACH
46	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
47	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	38.000	EACH
48	805-02439 CONDUIT RISER, GALVANIZED, 2 IN.	10.000	EACH
49	805-02457 LOOP DETECTOR, QUADRAPOLE, 6 FT. X 20 FT.	113.000	EACH

CALL ORDER : 500

CONTRACT ID : T -29389-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MAINTENANCE		
50	805-02650 LOOP DETECTOR, 6 FT. X 6 FT.	11.000	EACH
51	805-02660 TRAFFIC SIGNAL HEAD, OPTICALLY PROGRAMMED, 5 FACE, 12 IN.	2.000	EACH
52	805-02855 SIGNAL SUPPORT FOUNDATION, 2 FT. 6 IN. X 2 FT. 6 IN. X 6 FT.	6.000	EACH
53	805-03978 EMERGENCY VEHICLE LIGHT DETECTOR, SINGLE CHANNEL, ONE	22.000	EACH
54	805-03979 EMERGENCY VEHICLE LIGHT DETECTOR, TWO CHANNEL, TWO	22.000	EACH
55	805-03980 EMERGENCY VEHICLE CONFIRMATION LIGHT KIT	44.000	EACH
56	805-03983 PHASE SELECTORS	17.000	EACH
57	805-04956 PANEL FOR FIBER OPTICS	19.000	EACH
58	805-04982 CABLE	8,007.000	LFT
59	805-05405 SIGNAL PEDESTAL, 4 FT.	5.000	EACH
60	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	9,202.000	LFT
61	805-08464 RADIO, INTERCONNECT	8.000	EACH
62	805-09366 SIGNAL SUPPORT FOUNDATION,	18.000	EACH
63	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	3.000	EACH
64	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	14.000	EACH
65	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	135.000	EACH
66	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	12.000	EACH
67	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	11.000	EACH
68	805-78245 TRAFFIC SIGNAL HEAD, OPTICALLY PROGRAMMED, 3 FACE, 12 IN.	4.000	EACH
69	805-78370 PEDESTRIAN PUSH BUTTON	34.000	EACH
70	805-78412 SIGNAL PEDESTAL, 9 FT.	1.000	EACH
71	805-78415 SPAN, CATENARY, AND TETHER	43.000	EACH
72	805-78420 DISCONNECT HANGER	20.000	EACH
73	805-78465 SIGNAL CABLE, 2C 8GA.	768.000	LFT
74	805-78480 SIGNAL CABLE, 3C 14GA.	8,007.000	LFT
75	805-78485 SIGNAL CABLE, 5C 14GA.	6,791.000	LFT
76	805-78490 SIGNAL CABLE, 7C 14GA.	7,848.000	LFT
77	805-78495 SIGNAL CABLE, 9C 14GA.	2,612.000	LFT
78	805-78500 SIGNAL CABLE, 11C 14GA.	3,113.000	LFT
79	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	18,520.000	LFT
80	805-78785 SIGNAL DETECTOR HOUSING	61.000	EACH
81	805-78900 PEDESTAL FOUNDATION, A	6.000	EACH
82	805-78925 CONTROLLER CABINET FOUNDATION, P1	8.000	EACH
83	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	18.000	EACH
84	805-90736 TELEPHONE MODEM	3.000	EACH
85	805-90737 TELEPHONE SERVICE	3.000	EACH
86	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	59.000	EACH
87	805-96260 FIBER OPTICS CABLE, IN CONDUIT	4,521.000	LFT
88	805-96261 FIBER OPTICS CABLE, AERIAL	18,679.000	LFT
89	807-01617 HANDHOLE COVER AND RING	9.000	EACH
90	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	6.000	EACH
91	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	6.000	EACH
92	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	60.000	SYS
93	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	56.000	SYS
94	808-06368 TRANSVERSE MARKING, REMOVE	2,320.000	LFT
95	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	60.000	LFT
96	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	119.000	LFT
97	808-06716 LINE, REMOVE	240.000	LFT
98	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	150.000	LFT

CALL ORDER : 500

CONTRACT ID : T -29389-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MAINTENANCE		
99 808-75069	TRANSVERSE MARKINGS, PREFORMED PLASTIC, CROSSWALK LINE,	680.000	LFT
100 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	180.000	LFT
101 808-75260	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	41.000	LFT
102 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	2,056.000	LFT
103 808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,626.000	LFT
104 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	54.000	EACH
105 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	50.000	EACH
106 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	4.000	EACH

CALL ORDER : 510

CONTRACT ID : T -29517-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INSTALL NEW GUARDRAIL			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	30.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	203-02070 BORROW	1,400.000	CYS
11	601-05057 SPARE PARTS PACKAGE	2.000	EACH
12	601-08424 WIRE ROPE TERMINAL, TYPE II	40.000	EACH
13	601-08425 WIRE ROPE SAFETY BARRIER, TL-4	104,000.000	LFT
14	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
15	621-06545 FERTILIZER	0.500	TON
16	621-06553 SEED MIXTURE, R	90.000	LBS
17	621-06565 MULCHING MATERIAL	1.000	TON
18	628-09403 FIELD OFFICE, C	10.000	MOS
19	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	10.000	MOS
20	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
21	801-03290 CONSTRUCTION SIGN, C	48.000	EACH
22	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
23	801-06710 FLASHING ARROW SIGN	1,500.000	DAY
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 520

CONTRACT ID : T -29651-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	44.000	EACH
8	202-93995 SIGNAL POLE FOUNDATION, REMOVE	5.000	EACH
9	202-93999 SIGNAL POLE, REMOVE	9.000	EACH
10	628-09401 FIELD OFFICE, A	10.000	MOS
11	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
12	802-03706 SIGN PANEL, INSTALL	71.000	EACH
13	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	24.000	LFT
14	802-90623 SIGN BRACKET FOR STREET NAME	238.000	EACH
15	802-97812 STREET NAME IDENTIFICATION SIGN	191.000	EACH
16	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	7.000	EACH
17	805-01842 HANDHOLE, SIGNAL	5.000	EACH
18	805-02069 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM	7.000	EACH
19	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	4.000	EACH
20	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
21	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	320.000	EACH
22	805-02266 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN.	177.000	EACH
23	805-02266 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN.	18.000	EACH
24	805-02266 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN.	177.000	EACH
25	805-02266 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN.	18.000	EACH
26	805-02266 LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN.	181.000	EACH
27	805-03593 ROTATE EXISTING SIGNAL MAST ARM	1.000	EACH
28	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	411.000	LFT
29	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	34.000	EACH
30	805-06886 VIDEO VEHICLE DETECTOR SYSTEM WITH 4 CAMERAS	2.000	EACH
31	805-09094 SIGNAL CONTROLLER, TS2, TYPE 1	14.000	EACH
32	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	207.000	EACH
33	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	28.000	EACH
34	805-78245 TRAFFIC SIGNAL HEAD, OPTICALLY PROGRAMMED, 3 FACE, 12 IN.	8.000	EACH
35	805-78370 PEDESTRIAN PUSH BUTTON	320.000	EACH
36	805-78412 SIGNAL PEDESTAL, 9 FT.	7.000	EACH
37	805-78445 SIGNAL SERVICE	36.000	EACH
38	805-78467 SIGNAL CABLE, 3C 8GA.	167.000	LFT
39	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	5,601.000	LFT
40	805-78480 SIGNAL CABLE, 3C 14GA.	1,156.000	LFT
41	805-78485 SIGNAL CABLE, 5C 14GA.	1,835.000	LFT
42	805-78490 SIGNAL CABLE, 7C 14GA.	2,551.000	LFT
43	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,735.000	LFT
44	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
45	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	980.000	LFT
46	805-90734 TRAFFIC RESPONSIVE SYSTEM MASTER	3.000	EACH
47	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	110.000	EACH
48	805-97509 MODIFY M FOUNDATION TO P1 FOUNDATION	26.000	EACH
49	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	25.000	SYS

CALL ORDER : 520

CONTRACT ID : T -29651-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
50 808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1,450.000	LFT
51 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	700.000	LFT
52 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,943.000	LFT
53 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	2,126.000	LFT
54 808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	7,698.000	LFT
55 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	19.000	EACH
56 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	10.000	EACH
57 808-95933	CURB PAINTING, YELLOW	880.000	LFT

CALL ORDER : 530

CONTRACT ID : T -29788-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW SIGNAL INSTALLATION			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
7	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
8	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
9	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	44.000	LFT
10	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	36.000	SFT
11	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
12	805-01842 HANDHOLE, SIGNAL	12.000	EACH
13	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	1,405.000	LFT
14	805-04736 SIGNAL CABLE, 4C 18GA.	885.000	LFT
15	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
16	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
17	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
18	805-78420 DISCONNECT HANGER	4.000	EACH
19	805-78445 SIGNAL SERVICE	1.000	EACH
20	805-78467 SIGNAL CABLE, 3C 8GA.	100.000	LFT
21	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	810.000	LFT
22	805-78480 SIGNAL CABLE, 3C 14GA.	315.000	LFT
23	805-78485 SIGNAL CABLE, 5C 14GA.	345.000	LFT
24	805-78490 SIGNAL CABLE, 7C 14GA.	705.000	LFT
25	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,805.000	LFT
26	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
27	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	225.000	LFT
28	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
29	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	4.000	EACH
30	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	1.000	EACH
31	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000	EACH
32	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000	EACH
33	805-92512 MICROLOOP DETECTOR	6.000	EACH
34	808-06368 TRANSVERSE MARKING, REMOVE	25.000	LFT
35	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	80.000	LFT

CALL ORDER : 540

CONTRACT ID : T -29918-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ITS TRAFFIC MANAGEMENT SYSTEM		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	36.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	1,027.000	SYS
13	202-02241 GUARDRAIL, REMOVE	394.000	LFT
14	202-74085 OVERHEAD SIGN STRUCTURE, TWIN CANTILEVER, REMOVE	5.000	EACH
15	202-86946 HANDHOLE, REMOVE	2.000	EACH
16	202-94747 POST, REMOVE	2.000	EACH
17	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	605.000	LFT
18	202-94954 BARRIER WALL, CONCRETE, REMOVE	44.000	LFT
19	202-95027 IMPACT ATTENUATOR, REMOVE	2.000	EACH
20	202-95579 SERVICE POINT, REMOVE	1.000	EACH
21	202-96022 CONCRETE FOUNDATION, REMOVE	2.000	EACH
22	202-99626 FOUNDATION FOR SIGNING, REMOVE	2.000	EACH
23	203-08607 LINEAR GRADING	5,798.000	LFT
24	205-06937 TEMPORARY SILT FENCE	8,000.000	LFT
25	207-08268 SUBGRADE TREATMENT, TYPE IV	4,433.000	SYS
26	302-06464 SUBBASE FOR PCCP	79.000	CYS
27	303-01180 COMPACTED AGGREGATE, NO. 53	3,556.000	TON
28	304-07783 HMA PATCHING, TYPE D	542.000	TON
29	304-07789 WIDENING WITH HMA, TYPE D	483.000	TON
30	501-05240 CONTRACTION JOINT, D1	62.000	LFT
31	502-06329 PCCP, 12 IN.	137.000	SYS
32	503-03489 RETROFITTED TIE BARS	410.000	EACH
33	506-06333 PCCP PATCHING, FULL DEPTH	180.000	SYS
34	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	8.000	EACH
35	601-06854 GUARDRAIL, W-BEAM, NESTED	1.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	10.000	EACH
37	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	3,075.000	LFT
38	602-06729 BARRIER DELINEATOR	48.000	EACH
39	602-91266 MEDIAN BARRIER, CONCRETE, MODIFIED	341.000	LFT
40	621-03867 MULCHED SEEDING, A	12,916.000	SYS
41	621-06570 TOP SOIL	1,613.000	CYS
42	628-09402 FIELD OFFICE, B	18.000	MOS
43	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	18.000	MOS
44	718-08308 UNDERDRAIN, PATCHING	1,264.000	LFT
45	801-03290 CONSTRUCTION SIGN, C	12.000	EACH
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	4.000	EACH
48	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	1.000	EACH
49	802-07061 OVERHEAD DMS STRUCTURE, BOX TRUSS	17.000	EACH

CALL ORDER : 540

CONTRACT ID : T -29918-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ITS TRAFFIC MANAGEMENT SYSTEM			
50	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	2.000	EACH
51	802-09206 BOX TRUSS SIGN STRUCTURE FOUNDATION,	3.000	EACH
52	802-09207 BOX TRUSS SIGN STRUCTURE FOUNDATION,	11.000	EACH
53	802-09208 BOX TRUSS SIGN STRUCTURE FOUNDATION,	20.000	EACH
54	802-09483 DMS	5.000	EACH
55	802-09483 DMS	12.000	EACH
56	802-09483 DMS	8.000	EACH
57	802-09483 DMS	8.000	EACH
58	802-09483 DMS	23.000	EACH
59	802-76095 STRUCTURAL STEEL, BREAKAWAY	352.000	LBS
60	805-02383 CONDUIT, STEEL, GALVANIZED, 2.5 IN.	640.000	LFT
61	807-02191 HANDHOLE, LIGHTING	27.000	EACH
62	807-03965 CONDUIT, PVC, 2.50 IN., SCHEDULE 80, FOR ELECTRIC	2,000.000	LFT
63	807-04651 WIRE	3,170.000	LFT
64	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	2,770.000	LFT
65	807-95492 SERVICE POINT, II, BREAKER ENCLOSURE	12.000	EACH

CALL ORDER : 550

CONTRACT ID : T -30575-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW FLASHER INSTALLATION		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	8.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	628-09402 FIELD OFFICE, B	8.000	MOS
11	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
12	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
13	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	16.000	SFT
14	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
15	805-01842 HANDHOLE, SIGNAL	2.000	EACH
16	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	150.000	LFT
17	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	4.000	EACH
18	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. AMBER	12.000	EACH
19	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. RED	6.000	EACH
20	805-78415 SPAN, CATENARY, AND TETHER	2.000	EACH
21	805-78420 DISCONNECT HANGER	2.000	EACH
22	805-78445 SIGNAL SERVICE	4.000	EACH
23	805-78467 SIGNAL CABLE, 3C 8GA.	280.000	LFT
24	805-78480 SIGNAL CABLE, 3C 14GA.	470.000	LFT
25	805-78485 SIGNAL CABLE, 5C 14GA.	170.000	LFT
26	805-78900 PEDESTAL FOUNDATION, A	2.000	EACH
27	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000	EACH
28	805-95064 PEDESTAL AND BASE, 10 FT.	2.000	EACH
29	807-97042 POLE, WOOD, 5, 35 FT.	2.000	EACH

CALL ORDER : 560

CONTRACT ID : T -30577-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW FLASHER INSTALLATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	1.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	13.000	EACH
12	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	1.000	MOS
13	628-09409 MOBILE INTERNET SERVICE	1.000	MOS
14	801-03290 CONSTRUCTION SIGN, C	10.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
16	801-06645 CONSTRUCTION SIGN, B	9.000	EACH
17	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
18	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	66.000	LFT
19	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	42.000	SFT
20	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	34.500	SFT
21	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
22	805-01842 HANDHOLE, SIGNAL	8.000	EACH
23	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	1,020.000	LFT
24	805-02262 FLASHER INSTALLATION	LUMP	LUMP
25	805-04736 SIGNAL CABLE, 4C 18GA.	525.000	LFT
26	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	160.000	LFT
27	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	4.000	EACH
28	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
29	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. AMBER	6.000	EACH
30	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. AMBER	2.000	EACH
31	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	6.000	EACH
32	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
33	805-78420 DISCONNECT HANGER	3.000	EACH
34	805-78445 SIGNAL SERVICE	4.000	EACH
35	805-78445 SIGNAL SERVICE	1.000	EACH
36	805-78467 SIGNAL CABLE, 3C 8GA.	525.000	LFT
37	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	790.000	LFT
38	805-78485 SIGNAL CABLE, 5C 14GA.	445.000	LFT
39	805-78490 SIGNAL CABLE, 7C 14GA.	515.000	LFT
40	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	720.000	LFT
41	805-78785 SIGNAL DETECTOR HOUSING	3.000	EACH
42	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	255.000	LFT
43	805-78900 PEDESTAL FOUNDATION, A	5.000	EACH
44	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
45	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	4.000	EACH
46	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000	EACH
47	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	1.000	EACH
48	805-92512 MICROLOOP DETECTOR	2.000	EACH
49	805-94069 CONDUIT, STEEL, GALVANIZED, 1 IN.	80.000	LFT

CALL ORDER : 560

CONTRACT ID : T -30577-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW FLASHER INSTALLATION			
50	805-99162 SIGNAL PEDESTAL, 11 FT.	4.000	EACH
51	808-06368 TRANSVERSE MARKING, REMOVE	293.000	LFT
52	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	263.000	LFT
53	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	55.000	LFT

