

CALL ORDER : 311

CONTRACT ID : R -31982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
12	202-02240 PAVEMENT REMOVAL	7,690.000	SYS
13	202-02241 GUARDRAIL, REMOVE	546.000	LFT
14	202-02273 CENTER CURB, CONCRETE, REMOVE	139.000	SYS
15	202-02278 CURB, CONCRETE, REMOVE	1,447.000	LFT
16	202-03783 SIGN, PANEL, REMOVE	1.000	EACH
17	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
18	202-51368 SLOPEWALL, REMOVE	20.000	SYS
19	202-74035 SIGN, REMOVE	1.000	EACH
20	202-74050 SIGN, OVERHEAD, REMOVE	13.000	EACH
21	202-74055 OVERHEAD SIGN STRUCTURE, BOX TRUSS, REMOVE	1.000	EACH
22	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	10.000	EACH
23	202-96133 PIPE, REMOVE	34.000	LFT
24	203-02000 EXCAVATION, COMMON	5,615.000	CYS
25	205-06932 TEMPORARY CHECK DAM, STRAW BALES	30.000	LFT
26	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
27	205-06937 TEMPORARY SILT FENCE	4,722.000	LFT
28	206-51225 EXCAVATION, DRY	99.000	CYS
29	207-08262 SUBGRADE TREATMENT, TYPE I	16,020.000	SYS
30	211-02050 B BORROW	375.000	CYS
31	211-06467 AGGREGATE FOR END BENT BACKFILL	16.000	CYS
32	211-09194 B BORROW	56.000	TON
33	211-09264 STRUCTURE BACKFILL, TYPE 1	17.600	CYS
34	211-09266 STRUCTURE BACKFILL, TYPE 3	710.000	CYS
35	302-07455 DENSE GRADED SUBBASE	24.000	CYS
36	303-01180 COMPACTED AGGREGATE, NO. 53	1,250.000	TON
37	306-08043 MILLING, TRANSITION	475.000	SYS
38	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	1,470.000	TON
39	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	1,995.000	TON
40	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	7,110.000	TON
41	402-07453 HMA FOR TEMPORARY PAVEMENT	859.000	TON
42	406-05520 ASPHALT FOR TACK COAT	13.500	TON
43	601-01522 GUARDRAIL TRANSITION TYPE TGB	2.000	EACH
44	601-06224 IMPACT ATTENUATOR, CR, W1, TL-2	1.000	EACH
45	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	1.000	EACH
46	601-06407 IMPACT ATTENUATOR SPARE PARTS PACKAGE, CR, W1, TL-2	1.000	EACH
47	601-06454 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R2, W1, TL-3	1.000	EACH
48	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
49	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH

CALL ORDER : 311

CONTRACT ID : R -31982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE RECONSTRUCTION		
50	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	682.000	LFT
51	601-99123 GUARDRAIL TRANSITION, GP	1.000	EACH
52	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	1.000	EACH
53	602-02099 MEDIAN BARRIER RAIL TRANSITION, MODIFIED	1.000	EACH
54	602-02099 MEDIAN BARRIER RAIL TRANSITION, MODIFIED	1.000	EACH
55	602-06646 TEMPORARY CONCRETE BARRIER	1,335.000	LFT
56	602-06646 TEMPORARY CONCRETE BARRIER	1,160.000	LFT
57	602-06729 BARRIER DELINEATOR	12.000	EACH
58	602-06976 BARRIER, CONCRETE, 45 IN., MODIFIED	150.000	LFT
59	602-06976 BARRIER, CONCRETE, 45 IN., MODIFIED	175.000	LFT
60	602-06976 BARRIER, CONCRETE, 45 IN., MODIFIED	115.000	LFT
61	602-08605 CONCRETE BARRIER, 33 IN.	94.500	LFT
62	602-91266 MEDIAN BARRIER, CONCRETE, MODIFIED	228.000	LFT
63	603-06045 FENCE, CHAIN LINK, 48 IN.	233.000	LFT
64	605-06120 CURB, CONCRETE	1,226.000	LFT
65	605-06150 CURB AND GUTTER, C, CONCRETE	321.000	LFT
66	605-06255 CENTER CURB, D, CONCRETE	127.000	SYS
67	607-06335 PAVED SIDE DITCH, A	440.000	LFT
68	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	145.000	SYS
69	615-06500 MONUMENT, A	1.000	EACH
70	615-06505 MONUMENT, B	8.000	EACH
71	615-06515 MONUMENT, D	1.000	EACH
72	616-02320 GEOTEXTILES	46.000	SYS
73	616-51367 SLOPEWALL, CONCRETE, 4 IN.	196.000	SYS
74	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
75	621-06545 FERTILIZER	0.800	TON
76	621-06554 SEED MIXTURE, U	200.000	LBS
77	621-06557 SEED MIXTURE, T	196.000	LBS
78	621-06565 MULCHING MATERIAL	7.600	TON
79	621-06567 WATER	4.300	KGAL
80	621-06570 TOP SOIL	597.000	CYS
81	621-06575 SODDING, NURSERY	5,373.000	SYS
82	628-09402 FIELD OFFICE, B	12.000	MOS
83	701-51195 PILE, STEEL H, HP 12" X 53	1,810.000	LFT
84	701-91792 PILE TIP, STEEL H	16.000	EACH
85	702-51005 CONCRETE, A, SUBSTRUCTURE	101.300	CYS
86	702-51015 CONCRETE, B, FOOTINGS	8.500	CYS
87	702-51863 FIELD DRILLED HOLE IN CONCRETE	114.000	EACH
88	703-06028 REINFORCING BARS	2,335.000	LBS
89	703-06029 REINFORCING BARS, EPOXY COATED	46,334.000	LBS
90	704-51002 CONCRETE, C, SUPERSTRUCTURE	108.700	CYS
91	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	2.000	EACH
92	706-51020 CONCRETE, C, RAILING	23.500	CYS
93	707-05979 STRUCTURAL MEMBERS, CONCRETE BOX BEAM, CB, 27 IN. X 48 IN.	700.000	SFT
94	709-51821 SURFACE SEAL	LUMP	LUMP
95	710-51864 FIELD DRILLED HOLE	30.000	EACH
96	711-04121 ANCHOR BOLT, AB1	28.000	EACH
97	711-51038 STRUCTURAL STEEL	LUMP	LUMP
98	711-51075 ANCHOR PLATE, AP 2	2.000	EACH

CALL ORDER : 311

CONTRACT ID : R -31982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE RECONSTRUCTION		
99	711-51080 ANCHOR PLATE, AP 3	4.000	EACH
100	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	12.000	LFT
101	715-05407 PIPE, END BENT DRAIN, 6 IN.	61.000	LFT
102	715-46015 PIPE END SECTION, 21 IN.	1.000	EACH
103	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
104	720-44080 CASTING, 15, FURNISH AND ADJUST TO GRADE	1.000	EACH
105	724-03276 EXPANSION JOINT SEALING SYSTEM	34.000	LFT
106	724-04163 STRUCTURAL EXPANSION JOINT SEAL, REPLACE	91.000	LFT
107	731-93945 FACE PANELS, CONCRETE	1,800.000	SFT
108	731-93946 WALL ERECTION	1,800.000	SFT
109	731-93947 LEVELING PAD, CONCRETE	175.000	LFT
110	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	3.000	EACH
111	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	10.000	EACH
112	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
113	801-04746 ENERGY ABSORBING TERMINAL, CZ	1.000	EACH
114	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	29,355.000	LFT
115	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	33.000	LFT
116	801-06640 CONSTRUCTION SIGN, A	47.000	EACH
117	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
118	801-06710 FLASHING ARROW SIGN	200.000	DAY
119	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
120	801-07118 BARRICADE, III-A	192.000	LFT
121	801-07119 BARRICADE, III-B	72.000	LFT
122	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	540.000	LFT
123	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	1.000	EACH
124	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	108.100	LFT
125	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	19.700	LFT
126	802-07057 SIGN, PANEL, WITH LEGEND	4,647.000	SFT
127	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	10.000	EACH
128	802-07153 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	5.000	EACH
129	802-07271 BOX TRUSS SIGN FOUNDATION, V-A	1.000	EACH
130	802-07275 BOX TRUSS SIGN FOUNDATION, V-C	2.000	EACH
131	802-07278 BOX TRUSS SIGN FOUNDATION, V-D	1.000	EACH
132	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	23.000	SFT
133	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	132.900	SFT
134	802-76095 STRUCTURAL STEEL, BREAKAWAY	3,500.000	LBS
135	802-76110 SPAN OVERHEAD SIGN STRUCTURE, BOX TRUSS	2.000	EACH
136	804-06770 DELINEATOR POST	2.000	EACH
137	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	960.000	LFT
138	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	745.000	LFT
139	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	1.000	EACH
140	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	1.000	EACH
141	805-78485 SIGNAL CABLE, 5C 14GA.	25.000	LFT
142	805-78490 SIGNAL CABLE, 7C 14GA.	12.000	LFT
143	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	280.000	LFT
144	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
145	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	320.000	LFT
146	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	1,360.000	LFT
147	805-98336 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	445.000	LFT

CALL ORDER : 311

CONTRACT ID : R -31982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE RECONSTRUCTION		
148	807-02191 HANDHOLE, LIGHTING	6.000	EACH
149	807-02428 CONCRETE FOUNDATION WITH GROUNDING, 30 IN. X 30 IN. X 96 IN.	10.000	EACH
150	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	2,395.000	LFT
151	807-82005 SIGN CIRCUIT INSTALLATION, BOX TRUSS, 6 LUMINAIRES	1.000	EACH
152	807-83866 LIGHT POLE, 44 FT. E.M.H., 15.0 FT. MAST ARM, ANCHOR BASE	1.000	EACH
153	807-83918 LIGHT POLE, 46 FT. E.M.H., 15.0 FT. MAST ARM, ANCHOR BASE	1.000	EACH
154	807-85762 LIGHT POLE, 40 FT. E.M.H., 15.0 FT. MAST ARM, BREAKAWAY BASE	3.000	EACH
155	807-85816 LIGHT POLE, 42 FT. E.M.H., 16.0 FT. MAST ARM, BREAKAWAY BASE	5.000	EACH
156	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE	10.000	EACH
157	807-86810 SERVICE POINT, II	1.000	EACH
158	807-86910 CONNECTOR KIT, UNFUSED	12.000	EACH
159	807-86915 CONNECTOR KIT, FUSED	14.000	EACH
160	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	21.000	EACH
161	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	24.000	EACH
162	807-86930 INSULATION LINK, NONWATERPROOFED	23.000	EACH
163	807-86935 INSULATION LINK, WATERPROOFED	24.000	EACH
164	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	344.000	LFT
165	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	6,120.000	LFT
166	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,400.000	LFT
167	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	1,117.000	LFT
168	808-75272 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	180.000	LFT
169	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	24.000	LFT
170	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	7.000	EACH
171	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	5.000	EACH

