

CALL ORDER : 229

CONTRACT ID : R -29912-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	AUXILLARY LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02279 CURB AND GUTTER, REMOVE	1,133.000	LFT
11	202-91385 INLET, REMOVE	7.000	EACH
12	202-96133 PIPE, REMOVE	4,591.000	LFT
13	202-96133 PIPE, REMOVE	7,627.000	LFT
14	203-02000 EXCAVATION, COMMON	25,566.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	98.000	TON
16	205-06933 TEMPORARY DITCH INLET PROTECTION	41.000	EACH
17	205-06937 TEMPORARY SILT FENCE	1,840.000	LFT
18	205-06938 TEMPORARY SLOPE DRAIN	14.000	LFT
19	207-08263 SUBGRADE TREATMENT, TYPE IA	41,837.000	SYS
20	207-08266 SUBGRADE TREATMENT, TYPE III	4,552.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	7,104.000	SYS
22	210-09534 PROTECTIVE	18.000	EACH
23	211-09264 STRUCTURE BACKFILL, TYPE 1	7,468.000	CYS
24	211-09265 STRUCTURE BACKFILL, TYPE 2	1,356.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	400.000	TON
26	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	169.000	TON
27	304-07489 HMA PATCHING, TYPE A	218.000	TON
28	304-07492 WIDENING WITH HMA, TYPE A	1,720.000	TON
29	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2,927.000	TON
30	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	4,877.000	TON
31	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	13,026.000	TON
32	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	5,554.000	TON
33	402-07432 HMA SURFACE, TYPE A	73.000	TON
34	402-07435 HMA INTERMEDIATE, TYPE A	121.000	TON
35	406-05520 ASPHALT FOR TACK COAT	48.000	TON
36	604-07902 CURB RAMP, CONCRETE, H	126.000	SYS
37	605-06140 CURB AND GUTTER, CONCRETE	13,530.000	LFT
38	610-07487 HMA FOR APPROACHES, TYPE B	63.000	TON
39	610-08446 PCCP FOR APPROACHES, 6 IN.	871.000	SYS
40	610-09108 PCCP FOR APPROACHES, 9 IN.	5,950.000	SYS
41	611-06497 MAILBOX ASSEMBLY, SINGLE	4.000	EACH
42	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
43	615-06490 RIGHT OF WAY MARKER	100.000	EACH
44	615-06505 MONUMENT, B	53.000	EACH
45	616-02320 GEOTEXTILES	524.000	SYS
46	616-05688 RIPRAP, CLASS 1	196.000	TON
47	616-06405 RIPRAP, REVETMENT	320.000	TON
48	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
49	621-06545 FERTILIZER	2.200	TON

CALL ORDER : 229

CONTRACT ID : R -29912-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	AUXILLARY LANES		
50	621-06554 SEED MIXTURE, U	643.000	LBS
51	621-06557 SEED MIXTURE, T	184.000	LBS
52	621-06565 MULCHING MATERIAL	11.000	TON
53	621-06567 WATER	10.000	KGAL
54	621-06574 SODDING	2,763.000	SYS
55	628-09403 FIELD OFFICE, C	18.000	MOS
56	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	36.000	MOS
57	702-90915 CONCRETE, A	2.000	CYS
58	714-08514 WINGWALL	89.000	SFT
59	714-26722 CULVERT, PRECAST, REINFORCED CONCRETE BOX, 10' X 8'	136.000	LFT
60	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	2,402.000	LFT
61	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	16,328.000	LFT
62	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	272.000	LFT
63	715-05133 PIPE, TYPE 1, CIRCULAR, 60 IN.	85.000	LFT
64	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	2,721.000	LFT
65	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	832.000	LFT
66	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	571.000	LFT
67	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	1,558.000	LFT
68	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	1,880.000	LFT
69	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	48.000	LFT
70	715-05711 PIPE, SANITARY SEWER, 6 IN.	774.000	LFT
71	715-05841 CONCRETE ANCHOR, 60 IN.	2.000	EACH
72	715-07794 WATER MAIN CONNECTIONS	15.000	EACH
73	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
74	715-46010 PIPE END SECTION, 18 IN.	4.000	EACH
75	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
76	715-46030 PIPE END SECTION, 30 IN.	2.000	EACH
77	715-46040 PIPE END SECTION, 36 IN.	2.000	EACH
78	715-91738 WATER MAIN, DUCTILE IRON, 6 IN.	411.000	LFT
79	715-91739 WATER MAIN, DUCTILE IRON, 8 IN.	173.000	LFT
80	715-92544 WATER MAIN, DUCTILE IRON, 12 IN.	7,804.000	LFT
81	715-94533 ADJUST WATER SERVICE LINE, COMMERCIAL	10.000	EACH
82	715-94534 ADJUST WATER SERVICE LINE, RESIDENTIAL	4.000	EACH
83	715-98265 WATER MAIN, DUCTILE IRON, 4 IN.	271.000	LFT
84	716-07634 PIPE INSTALLATION, TRENCHLESS, 30 IN.	271.000	LFT
85	716-07635 PIPE INSTALLATION, TRENCHLESS, 36 IN.	106.000	LFT
86	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
87	718-52610 AGGREGATE FOR UNDERDRAINS	1,469.000	CYS
88	718-99153 GEOTEXTILES FOR UNDERDRAIN	17,084.000	SYS
89	720-01092 MANHOLE, J15, MODIFIED	18.000	EACH
90	720-08559 BEST MANAGEMENT PRACITICES	4.000	EACH
91	720-44000 CASTING, ADJUST TO GRADE	15.000	EACH
92	720-45030 INLET, E7	34.000	EACH
93	720-45035 INLET, F7	6.000	EACH
94	720-45041 INLET, H5	5.000	EACH
95	720-45410 MANHOLE, C4	6.000	EACH
96	720-93501 MANHOLE, L4	1.000	EACH
97	720-94612 MANHOLE, K4	3.000	EACH
98	720-95422 MANHOLE, J4	20.000	EACH

CALL ORDER : 229

CONTRACT ID : R -29912-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	AUXILLARY LANES		
99	720-96999 FIRE HYDRANT ASSEMBLY	15.000	EACH
100	720-98174 INLET, B15	12.000	EACH
101	720-98555 INLET, C15	16.000	EACH
102	732-01898 WATER MAIN, DUCTILE IRON, 10 IN.	74.000	LFT
103	732-02433 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 12 IN.	33.000	EACH
104	732-02531 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON 6 IN.	6.000	EACH
105	732-02532 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 8 IN.	3.000	EACH
106	732-09197 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE	3.000	EACH
107	732-09202 VALVE WITH BOX, RESTRAINED, GATE,	1.000	EACH
108	732-97009 FIRE HYDRANT ASSEMBLY, REMOVE	8.000	EACH
109	801-01506 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (RXR)	3.000	EACH
110	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
111	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
112	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	32,070.000	LFT
113	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	32,070.000	LFT
114	801-06213 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (RXR)	5.000	EACH
115	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	12.000	LFT
116	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	24.000	LFT
117	801-06625 DETOUR ROUTE MARKER ASSEMBLY	30.000	EACH
118	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
119	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
120	801-07118 BARRICADE, III-A	108.000	LFT
121	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	300.000	LFT
122	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	7.000	EACH
123	802-07060 SIGN, SHEET, RELOCATE	22.000	EACH
124	802-07125 SIGN, DOUBLE FACED, SHEET, ENCAPSULATED LENS, WITH LEGEND,	39.550	SFT
125	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	179.500	SFT
126	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	70.400	SFT
127	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	4.000	EACH
128	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	723.000	LFT
129	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2,910.000	LFT
130	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	18,250.000	LFT
131	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	291.000	LFT
132	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	213.000	LFT
133	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	40.000	EACH
134	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	35.000	EACH
135	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	389.000	EACH

