

CALL ORDER : 148

CONTRACT ID : SR -31989-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
12	202-02240 PAVEMENT REMOVAL	1,214.000	SYS
13	202-86946 HANDHOLE, REMOVE	3.000	EACH
14	202-91385 INLET, REMOVE	5.000	EACH
15	202-93995 SIGNAL POLE FOUNDATION, REMOVE	4.000	EACH
16	203-02000 EXCAVATION, COMMON	818.000	CYS
17	203-02070 BORROW	806.000	CYS
18	207-08266 SUBGRADE TREATMENT, TYPE III	4,277.000	SYS
19	211-07454 STRUCTURE BACKFILL	369.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	518.000	TON
21	303-07449 COMPACTED AGGREGATE, NO. 73	18.000	TON
22	306-08034 MILLING, ASPHALT, 1 1/2 IN.	9,339.000	SYS
23	402-07433 HMA SURFACE, TYPE B	864.000	TON
24	402-07438 HMA INTERMEDIATE, TYPE B	3,334.000	TON
25	402-07441 HMA BASE, TYPE B	1,332.000	TON
26	406-05521 ASPHALT FOR TACK COAT	26,680.000	SYS
27	502-06457 PCCP, 9 IN.	1,554.000	SYS
28	605-06120 CURB, CONCRETE	233.000	LFT
29	605-06140 CURB AND GUTTER, CONCRETE	4,779.000	LFT
30	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
31	621-06560 MULCHED SEEDING, U	5,041.000	SYS
32	628-09402 FIELD OFFICE, B	6.000	MOS
33	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	426.000	LFT
34	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	186.000	LFT
35	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	318.000	LFT
36	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	4.000	LFT
37	720-44000 CASTING, ADJUST TO GRADE	12.000	EACH
38	720-45215 CATCH BASIN, A8	6.000	EACH
39	720-45235 CATCH BASIN, E7	1.000	EACH
40	720-45240 CATCH BASIN, J10	3.000	EACH
41	720-45250 CATCH BASIN, K10	7.000	EACH
42	720-45410 MANHOLE, C4	6.000	EACH
43	720-90984 MANHOLE, C2	2.000	EACH
44	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	4.000	EACH
45	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
46	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,137.000	LFT
47	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	200.000	LFT
48	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
49	801-06710 FLASHING ARROW SIGN	240.000	DAY

CALL ORDER : 148

CONTRACT ID : SR -31989-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
51	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	112.000	LFT
52	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	50.000	SFT
53	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	27.720	SFT
54	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
55	805-01842 HANDHOLE, SIGNAL	8.000	EACH
56	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
57	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,376.000	LFT
58	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
59	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	4.000	EACH
60	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	4.000	EACH
61	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
62	805-78420 DISCONNECT HANGER	4.000	EACH
63	805-78445 SIGNAL SERVICE	1.000	EACH
64	805-78467 SIGNAL CABLE, 3C 8GA.	15.000	LFT
65	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,804.000	LFT
66	805-78485 SIGNAL CABLE, 5C 14GA.	144.000	LFT
67	805-78490 SIGNAL CABLE, 7C 14GA.	543.000	LFT
68	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,358.000	LFT
69	805-78785 SIGNAL DETECTOR HOUSING	8.000	EACH
70	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	820.000	LFT
71	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
72	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000	EACH
73	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	2,417.000	LFT
74	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,670.000	LFT
75	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	428.000	LFT
76	808-06716 LINE, REMOVE	50.000	LFT
77	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4,498.000	LFT
78	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	108.000	LFT
79	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	201.000	LFT
80	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	120.000	LFT
81	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	10.000	EACH

CALL ORDER : 166

CONTRACT ID : SR -32257-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	304-07489 HMA PATCHING, TYPE A	500.000	TON
8	306-08033 MILLING, ASPHALT, 1 IN.	47,508.000	SYS
9	306-08043 MILLING, TRANSITION	184.000	SYS
10	306-08432 MILLING, APPROACH	720.000	SYS
11	402-07432 HMA SURFACE, TYPE A	5,552.000	TON
12	402-07450 HMA WEDGE AND LEVEL, TYPE A	626.000	TON
13	406-05520 ASPHALT FOR TACK COAT	21.000	TON
14	610-07486 HMA FOR APPROACHES, TYPE A	84.000	TON
15	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
16	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
17	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
18	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
20	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	37,432.000	LFT
21	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2,000.000	LFT
22	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	32,912.000	LFT
23	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	92.000	LFT
24	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH

CALL ORDER : 178

CONTRACT ID : SR -32429-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	304-07489 HMA PATCHING, TYPE A	1,763.000	TON
9	306-08033 MILLING, ASPHALT, 1 IN.	101,773.000	SYS
10	306-08043 MILLING, TRANSITION	1,008.000	SYS
11	306-08432 MILLING, APPROACH	5,467.000	SYS
12	402-07432 HMA SURFACE, TYPE A	11,824.000	TON
13	402-07450 HMA WEDGE AND LEVEL, TYPE A	1,763.000	TON
14	406-05520 ASPHALT FOR TACK COAT	47.000	TON
15	610-07486 HMA FOR APPROACHES, TYPE A	602.000	TON
16	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
17	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
18	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	36.000	EACH
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
21	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	76,330.000	LFT
22	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	49.000	LFT
23	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	73,904.000	LFT
24	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	368.000	LFT

CALL ORDER : 218

CONTRACT ID : SR -32507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT/ SIDEWALK/STREETSCAPE IMPROVEMENTS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02240 PAVEMENT REMOVAL	438.000	SYS
8	202-02278 CURB, CONCRETE, REMOVE	392.000	LFT
9	202-52710 SIDEWALK, CONCRETE, REMOVE	2,118.000	SYS
10	202-93996 PEDESTAL BASE, REMOVE	1.000	EACH
11	203-02000 EXCAVATION, COMMON	92.000	CYS
12	203-02070 BORROW	33.000	CYS
13	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	5.000	EACH
14	205-06937 TEMPORARY SILT FENCE	560.000	LFT
15	604-07897 CURB RAMP, CONCRETE, C	3.900	SYS
16	604-07900 CURB RAMP, CONCRETE, F	22.600	SYS
17	604-07901 CURB RAMP, CONCRETE, G	98.600	SYS
18	604-07902 CURB RAMP, CONCRETE, H	19.800	SYS
19	604-07903 CURB RAMP, CONCRETE, K	20.300	SYS
20	604-91531 SIDEWALK, CONCRETE, 4 IN.	3,254.000	SYS
21	605-06120 CURB, CONCRETE	293.000	LFT
22	610-09108 PCCP FOR APPROACHES, 9 IN.	438.000	SYS
23	611-03671 TRASH RECEPTACLE	4.000	EACH
24	621-06567 WATER	11.000	KGAL
25	621-06575 SODDING, NURSERY	3,675.000	SYS
26	628-09402 FIELD OFFICE, B	8.000	MOS
27	702-90915 CONCRETE, A	4.500	CYS
28	703-51030 REINFORCING STEEL	32.000	LBS
29	712-03812 BENCH	4.000	EACH
30	720-44000 CASTING, ADJUST TO GRADE	7.000	EACH
31	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
32	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
33	801-06710 FLASHING ARROW SIGN	264.000	DAY
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	802-07060 SIGN, SHEET, RELOCATE	19.000	EACH
36	805-01842 HANDHOLE, SIGNAL	1.000	EACH
37	805-02151 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 12 IN.	16.000	EACH
38	805-05405 SIGNAL PEDESTAL, 4 FT.	8.000	EACH
39	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,706.000	LFT
40	805-78370 PEDESTRIAN PUSH BUTTON	16.000	EACH
41	805-78480 SIGNAL CABLE, 3C 14GA.	1,736.000	LFT
42	805-78485 SIGNAL CABLE, 5C 14GA.	563.000	LFT
43	805-78490 SIGNAL CABLE, 7C 14GA.	541.000	LFT
44	805-78900 PEDESTAL FOUNDATION, A	8.000	EACH
45	805-86890 POLE CIRCUIT CABLE, 1C NO. 10 THW OR TW STRANDED COPPER	2,520.000	LFT
46	805-96014 SAW CUT, FULL DEPTH	1,551.000	LFT
47	805-97237 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	6,564.000	LFT
48	807-02191 HANDHOLE, LIGHTING	2.000	EACH
49	807-03738 LIGHT POLE ASSEMBLY, STREET	42.000	EACH

CALL ORDER : 218

CONTRACT ID : SR -32507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT/ SIDEWALK/STREETScape IMPROVEMENTS		
50	807-03738 LIGHT POLE ASSEMBLY, STREET	2.000	EACH
51	807-03950 LUMINAIRE, ORNAMENTAL	42.000	EACH
52	807-03950 LUMINAIRE, ORNAMENTAL	2.000	EACH
53	807-04443 CONDUIT	5,076.000	LFT
54	807-04779 CONCRETE FOUNDATION WITH GROUNDING	42.000	EACH
55	807-06935 INSULATING LINK, WATERPROOFED	16.000	EACH
56	807-86810 SERVICE POINT, II	1.000	EACH
57	807-86910 CONNECTOR KIT, UNFUSED	84.000	EACH
58	807-86915 CONNECTOR KIT, FUSED	84.000	EACH
59	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	198.000	EACH
60	807-86930 INSULATION LINK, NONWATERPROOFED	84.000	EACH
61	808-06368 TRANSVERSE MARKING, REMOVE	688.000	LFT
62	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	351.000	LFT
63	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	2,237.000	LFT

CALL ORDER : 230

CONTRACT ID : SR -32593-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIDEWALK IMPROVEMENTS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02245 TREE, 6 IN., REMOVE	5.000	EACH
9	202-02250 TREE, 10 IN., REMOVE	1.000	EACH
10	202-02255 TREE, 18 IN., REMOVE	6.000	EACH
11	202-02260 TREE, 30 IN., REMOVE	21.000	EACH
12	202-02264 TREE, 42 IN., REMOVE	5.000	EACH
13	202-02270 TREE, 60 IN., REMOVE	1.000	EACH
14	202-04089 SIGN, SHEET, REMOVE	2.000	EACH
15	202-52710 SIDEWALK, CONCRETE, REMOVE	9.000	SYS
16	203-02000 EXCAVATION, COMMON	23.000	CYS
17	203-02070 BORROW	300.000	CYS
18	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	24.000	EACH
19	205-02770 EROSION CONTROL BLANKET	798.000	SYS
20	205-06937 TEMPORARY SILT FENCE	692.000	LFT
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	10.000	TON
22	304-07489 HMA PATCHING, TYPE A	29.000	TON
23	406-05520 ASPHALT FOR TACK COAT	0.050	TON
24	601-95344 HANDRAIL, PEDESTRIAN	595.000	LFT
25	604-07896 CURB RAMP, CONCRETE, B	16.000	SYS
26	604-07897 CURB RAMP, CONCRETE, C	44.000	SYS
27	604-07901 CURB RAMP, CONCRETE, G	45.000	SYS
28	604-90256 SIDEWALK, CONCRETE, 6 IN.	422.000	SYS
29	604-91531 SIDEWALK, CONCRETE, 4 IN.	3,216.000	SYS
30	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
31	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
32	621-06559 MULCHED SEEDING, R	6,025.000	SYS
33	628-09401 FIELD OFFICE, A	4.000	MOS
34	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	27.000	LFT
35	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
36	715-92537 PIPE, PVC, 8 IN.	4.000	LFT
37	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
38	720-45260 PIPE CATCH BASIN, 12 IN.	1.000	EACH
39	720-45275 PIPE CATCH BASIN, 24 IN.	1.000	EACH
40	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
41	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
42	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	801-07119 BARRICADE, III-B	72.000	LFT
45	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	192.000	LFT
46	802-07060 SIGN, SHEET, RELOCATE	5.000	EACH
47	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	32.000	SFT
48	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	144.000	SFT
49	805-02262 FLASHER INSTALLATION	LUMP	LUMP

CALL ORDER : 230

CONTRACT ID : SR -32593-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIDEWALK IMPROVEMENTS		
50 808-03439	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	495.000	LFT
51 808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	113.000	LFT

CALL ORDER : 242

CONTRACT ID : SR -32665-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-01180 COMPACTED AGGREGATE, NO. 53	30.000	TON
8	304-07491 HMA PATCHING, TYPE C	89.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	66,735.000	SYS
10	402-07434 HMA SURFACE, TYPE C	5,507.000	TON
11	406-05520 ASPHALT FOR TACK COAT	16.100	TON
12	503-03489 RETROFITTED TIE BARS	124.000	EACH
13	503-05240 D-1 CONTRACTION JOINT	60.000	LFT
14	506-06333 PCCP PATCHING, FULL DEPTH	1,619.000	SYS
15	628-09401 FIELD OFFICE, A	4.000	MOS
16	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	12.000	EACH
17	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
18	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,000.000	LFT
19	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
21	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	600.000	LFT
22	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	100.000	LFT
23	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	240.000	LFT
24	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	4,597.000	LFT
25	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	20,886.000	LFT
26	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	18,086.000	LFT
27	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	12.000	EACH
28	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	11.000	EACH
29	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	275.000	EACH
30	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	275.000	EACH

CALL ORDER : 248

CONTRACT ID : SR -32696-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT BIKE/PEDESTRIAN FACILITY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	1,172.000	CYS
12	203-08607 LINEAR GRADING	82,305.000	LFT
13	205-06937 TEMPORARY SILT FENCE	3,000.000	LFT
14	207-08266 SUBGRADE TREATMENT, TYPE III	133,912.000	SYS
15	210-07572 TABLE	2.000	EACH
16	210-08157 BICYCLE LOOP	3.000	EACH
17	214-07202 GEOGRID, I	500.000	SYS
18	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	22,977.000	TON
19	303-07449 COMPACTED AGGREGATE, NO. 73	6,097.000	TON
20	402-07432 HMA SURFACE, TYPE A	5,158.000	TON
21	402-07435 HMA INTERMEDIATE, TYPE A	10,794.000	TON
22	406-05520 ASPHALT FOR TACK COAT	24.500	TON
23	601-95344 HANDRAIL, PEDESTRIAN	636.000	LFT
24	601-95344 HANDRAIL, PEDESTRIAN	536.000	LFT
25	603-03692 FENCE, WOOD	860.000	LFT
26	604-91531 SIDEWALK, CONCRETE, 4 IN.	128.000	SYS
27	605-06120 CURB, CONCRETE	536.000	LFT
28	615-03866 MILE MARKER	32.000	EACH
29	615-06496 PARKING BARRIER	7.000	EACH
30	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
31	621-03909 SEED MIXTURE, NATIVE	0.270	LBS
32	621-04258 SEED MIXTURE	1.500	LBS
33	621-04317 MULCHED SEEDING	1,829.000	SYS
34	621-06574 SODDING	288.000	SYS
35	622-05644 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 48 TO 72 IN.	2.000	EACH
36	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	5.000	EACH
37	628-09401 FIELD OFFICE, A	10.000	MOS
38	711-91996 REPAIR EXISTING STRUCTURE	LUMP	LUMP
39	712-03812 BENCH	13.000	EACH
40	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
41	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
42	801-07119 BARRICADE, III-B	60.000	LFT
43	801-92448 CONSTRUCTION SIGNS, MOBILE	480.000	DAY
44	802-03821 SIGN, SHEET WITH LEGEND	7.000	EACH
45	802-03896 BOLLARD	45.000	EACH
46	802-03896 BOLLARD	1.000	EACH
47	802-04250 SIGN, TRAIL INFORMATION	2.000	EACH
48	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	1,540.000	LFT
49	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	660.700	SFT

CALL ORDER : 248

CONTRACT ID : SR -32696-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT BIKE/PEDESTRIAN FACILITY		
50 808-02976	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, (HWY), 4 FT.	2.000	EACH
51 808-02977	TRANSVERSE MARKING, THERMOPLASTIC, BIKE SYMBOL	2.000	EACH
52 808-03114	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, (XING) 8 FT.	2.000	EACH
53 808-03115	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (XING), 4 FT.	2.000	EACH
54 808-75015	LINE, PAINT, SOLID, WHITE, 12 IN.	2,150.000	LFT
55 808-75215	LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	1,114.000	LFT
56 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	450.000	LFT
57 808-75272	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	1,665.000	LFT

CALL ORDER : 254

CONTRACT ID : SR -32711-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	26.000	TON
8	303-01180 COMPACTED AGGREGATE, NO. 53	246.000	TON
9	304-07490 HMA PATCHING, TYPE B	26.000	TON
10	306-08034 MILLING, ASPHALT, 1 1/2 IN.	16,217.000	SYS
11	402-07433 HMA SURFACE, TYPE B	1,338.000	TON
12	402-07451 HMA WEDGE AND LEVEL, TYPE B	134.000	TON
13	406-05520 ASPHALT FOR TACK COAT	4.500	TON
14	628-09401 FIELD OFFICE, A	4.000	MOS
15	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
16	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,720.000	LFT
17	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,720.000	LFT
18	801-06640 CONSTRUCTION SIGN, A	9.000	EACH
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
20	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	13,588.000	LFT
21	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	170.000	LFT
22	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	12,229.000	LFT

CALL ORDER : 260

CONTRACT ID : SR -32725-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIDEWALK REMOVAL AND REPLACEMENT		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	202-02260 TREE, 30 IN., REMOVE	3.000	EACH
6	202-02279 CURB AND GUTTER, REMOVE	35.000	LFT
7	202-02771 CONCRETE APRON, REMOVE	410.000	EACH
8	202-52710 SIDEWALK, CONCRETE, REMOVE	4,753.000	SYS
9	604-07894 CURB RAMP, CONCRETE, A	71.000	SYS
10	604-07896 CURB RAMP, CONCRETE, B	117.000	SYS
11	604-07897 CURB RAMP, CONCRETE, C	159.000	SYS
12	604-07903 CURB RAMP, CONCRETE, K	31.000	SYS
13	604-90256 SIDEWALK, CONCRETE, 6 IN.	266.000	SYS
14	604-91404 SIDEWALK, CONCRETE, 5 IN.	4,236.000	SYS
15	605-06140 CURB AND GUTTER, CONCRETE	35.000	LFT
16	610-08446 PCCP FOR APPROACHES, 6 IN.	272.000	SYS
17	621-06570 TOP SOIL	160.000	CYS
18	621-06574 SODDING	1,436.000	SYS
19	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
20	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
21	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	808-75100 TRANSVERSE MARKINGS, PAINT, CROSSWALK LINE, 6 IN.	815.000	LFT

CALL ORDER : 266

CONTRACT ID : SR -32761-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	RIVERBANK STABILIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	108-09241 STORMWATER POLLUTION PREVENTION PLAN,	LUMP	LUMP
6	109-08359 LIQUIDATED DAMAGES	1.000	DOL
7	109-08360 CONTRACT LIENS	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	203-02020 EXCAVATION, UNCLASSIFIED	689.000	CYS
13	203-02070 BORROW	883.000	CYS
14	203-51223 EXCAVATION, WATERWAY	342.000	CYS
15	205-06937 TEMPORARY SILT FENCE	400.000	LFT
16	206-51817 SHEET PILING, STEEL	8,790.000	SFT
17	603-97461 TEMPORARY FENCE	400.000	LFT
18	604-06080 SIDEWALK, CONCRETE, RECONSTRUCTED	239.000	SYS
19	616-02320 GEOTEXTILES	415.000	SYS
20	616-05688 RIPRAP, CLASS 1	514.000	TON
21	616-94426 GEOGRID	1,812.000	SYS
22	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
23	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	1,900.000	SYS
24	621-06560 MULCHED SEEDING, U	1,900.000	SYS
25	622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN.	37.000	EACH
26	628-09401 FIELD OFFICE, A	12.000	MOS
27	706-91664 PIPE RAILING	221.000	LFT
28	714-04802 CONCRETE MODULAR BLOCK WALL	155.000	SYS
29	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	180.000	LFT
30	715-05203 PIPE, TYPE 4, CIRCULAR, 4 IN.	475.000	LFT
31	718-06531 OUTLET PROTECTOR, 3	18.000	EACH
32	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
33	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	801-07119 BARRICADE, III-B	40.000	LFT
36	807-02370 LIGHT STRUCTURE, REMOVE AND RESET	6.000	EACH

CALL ORDER : 278

CONTRACT ID : SR -32818-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	9.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	270.000	SYS
12	202-02279 CURB AND GUTTER, REMOVE	130.000	LFT
13	202-93047 MANHOLE, REMOVE	1.000	EACH
14	202-96133 PIPE, REMOVE	19.000	LFT
15	203-02000 EXCAVATION, COMMON	229.000	CYS
16	203-02070 BORROW	1,373.000	CYS
17	203-02070 BORROW	200.000	CYS
18	205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	13.000	EACH
19	205-06933 TEMPORARY DITCH INLET PROTECTION	11.000	EACH
20	205-06937 TEMPORARY SILT FENCE	1,646.000	LFT
21	205-09543 NO 2 STONE	100.000	TON
22	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	280.000	CYS
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	135.000	SYS
24	211-02050 B BORROW	200.000	CYS
25	211-07454 STRUCTURE BACKFILL	477.000	CYS
26	211-09264 STRUCTURE BACKFILL, TYPE 1	10.000	CYS
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	859.000	TON
28	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	120.000	TON
29	306-08034 MILLING, ASPHALT, 1 1/2 IN.	661.000	SYS
30	402-07432 HMA SURFACE, TYPE A	135.000	TON
31	402-07433 HMA SURFACE, TYPE B	87.000	TON
32	402-07435 HMA INTERMEDIATE, TYPE A	270.000	TON
33	402-07438 HMA INTERMEDIATE, TYPE B	7.000	TON
34	406-05521 ASPHALT FOR TACK COAT	0.650	SYS
35	502-08202 PCCP, 10.5 IN.	360.000	SYS
36	604-07901 CURB RAMP, CONCRETE, G	65.000	SYS
37	604-91531 SIDEWALK, CONCRETE, 4 IN.	76.000	SYS
38	605-06120 CURB, CONCRETE	1,850.000	LFT
39	607-92907 GUTTER TURNOUT, CONCRETE	150.000	LFT
40	610-08446 PCCP FOR APPROACHES, 6 IN.	100.000	SYS
41	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
42	616-02320 GEOTEXTILES	77.000	SYS
43	616-06405 RIPRAP, REVETMENT	49.000	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
45	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
46	621-06560 MULCHED SEEDING, U	2,430.000	SYS
47	621-06560 MULCHED SEEDING, U	2,430.000	SYS
48	621-06570 TOP SOIL	400.000	CYS
49	621-06575 SODDING, NURSERY	225.000	SYS

CALL ORDER : 278

CONTRACT ID : SR -32818-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
50	628-09402 FIELD OFFICE, B	9.000	MOS
51	702-51005 CONCRETE, A, SUBSTRUCTURE	32.500	CYS
52	702-51015 CONCRETE, B, FOOTINGS	5.200	CYS
53	703-06028 REINFORCING BARS	2,792.000	LBS
54	703-06029 REINFORCING BARS, EPOXY COATED	933.000	LBS
55	704-51002 CONCRETE, C, SUPERSTRUCTURE	5.000	CYS
56	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP
57	715-02181 SANITARY SEWER SERVICE ADJUSTMENT	1.000	LFT
58	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	1,185.000	LFT
59	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	28.000	LFT
60	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	16.000	LFT
61	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
62	715-90714 PIPE, PVC, 12 IN.	137.000	LFT
63	720-04721 MANHOLE, K	1.000	EACH
64	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
65	720-44015 CASTING, 2, FURNISH AND ADJUST TO GRADE	3.000	EACH
66	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	6.000	EACH
67	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	10.000	EACH
68	720-45035 INLET, F7	2.000	EACH
69	720-90017 INLET, J	6.000	EACH
70	720-91051 INLET, A	4.000	EACH
71	720-94157 MANHOLE, C	9.000	EACH
72	731-93946 WALL ERECTION	82.000	SFT
73	732-08419 MODULAR BLOCK WALL	32.000	SYS
74	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	50.000	SYS
75	732-09163 TEST	1.000	EACH
76	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
77	801-06640 CONSTRUCTION SIGN, A	17.000	EACH
78	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
79	802-03896 BOLLARD	2.000	EACH
80	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	165.000	LFT
81	802-91122 SIGN, GROUND MOUNTED, RESET	11.000	EACH
82	805-96014 SAW CUT, FULL DEPTH	880.000	LFT
83	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	24.000	LFT
84	808-94435 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (STOP)	3.000	EACH
85	808-99077 LINE, PREFORMED PLASTIC, SOLID, WHITE, 24 IN.	155.000	LFT

CALL ORDER : 284

CONTRACT ID : SR -32819-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	4,216.000	CYS
12	205-06937 TEMPORARY SILT FENCE	2,191.000	LFT
13	205-09543 NO 2 STONE	130.000	TON
14	207-08266 SUBGRADE TREATMENT, TYPE III	15,004.000	SYS
15	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5,001.000	TON
16	303-07449 COMPACTED AGGREGATE, NO. 73	400.000	TON
17	402-07432 HMA SURFACE, TYPE A	852.000	TON
18	402-07435 HMA INTERMEDIATE, TYPE A	1,406.000	TON
19	406-05520 ASPHALT FOR TACK COAT	3.200	TON
20	604-06070 SIDEWALK, CONCRETE	11.000	SYS
21	604-07897 CURB RAMP, CONCRETE, C	25.000	SYS
22	616-02320 GEOTEXTILES	78.000	SYS
23	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
24	621-02318 SEED MIXTURE, PRAIRIE GRASS	265.000	LBS
25	621-04317 MULCHED SEEDING	9,603.000	SYS
26	628-09401 FIELD OFFICE, A	6.000	MOS
27	712-03812 BENCH	1.000	EACH
28	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
29	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
30	801-07119 BARRICADE, III-B	60.000	LFT
31	802-03896 BOLLARD	10.000	EACH
32	802-03896 BOLLARD	5.000	EACH
33	802-03896 BOLLARD	1.000	EACH
34	802-03896 BOLLARD	2.000	EACH
35	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	180.000	LFT
36	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
37	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	84.400	SFT
38	808-04767 LINE	20.000	LFT
39	808-08258 TRANSVERSE MARKINGS	80.000	LFT
40	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,160.000	LFT

CALL ORDER : 342

CONTRACT ID : SR -32939-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, LANDSCAPING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-85996 LIGHT STANDARD AND MAST ARM, REMOVE	6.000	EACH
12	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	2.000	EACH
13	202-96391 MAST ARM, REMOVE	32.000	EACH
14	202-98370 POLE, REMOVE	32.000	EACH
15	203-02000 EXCAVATION, COMMON	494.000	CYS
16	603-03829 FENCE	1,700.000	LFT
17	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
18	621-04317 MULCHED SEEDING	2,960.000	SYS
19	621-06570 TOP SOIL	494.000	CYS
20	621-98038 MULCH, HARDWOOD SHREDDED BARK	142.000	CYS
21	622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 72 TO	4.000	EACH
22	622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	316.000	EACH
23	622-05654 PLANT, PERENNIAL	1,076.000	EACH
24	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
25	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	802-04314 SIGN	2.000	EACH
28	805-02657 CAMERA	1.000	EACH
29	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	320.000	LFT
30	805-98336 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	360.000	LFT
31	807-02191 HANDHOLE, LIGHTING	7.000	EACH
32	807-02193 LIGHT STANDARD FOUNDATION, 3 FT. DIA. X 8 FT.	28.000	EACH
33	807-03950 LUMINAIRE, ORNAMENTAL	2.000	EACH
34	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	5,250.000	LFT
35	807-83752 LIGHT POLE, 40 FT. E.M.H., 10.0 FT. MAST ARM, ANCHOR BASE	6.000	EACH
36	807-85752 LIGHT POLE, 40 FT. E.M.H., 10.0 FT. MAST ARM, BREAKAWAY BASE	28.000	EACH
37	807-86615 LUMINAIRE, ROADWAY, 250 WATT, HIGH PRESSURE SODIUM	34.000	EACH
38	807-86805 SERVICE POINT, I	1.000	EACH
39	807-86910 CONNECTOR KIT, UNFUSED	34.000	EACH
40	807-86915 CONNECTOR KIT, FUSED	34.000	EACH
41	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	102.000	EACH
42	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	4.000	EACH
43	807-86930 INSULATION LINK, NONWATERPROOFED	86.000	EACH
44	807-86935 INSULATION LINK, WATERPROOFED	28.000	EACH
45	807-87556 WIRE, THW OR TW, NO. 10 COPPER STRANDED	3,400.000	LFT

CALL ORDER : 348

CONTRACT ID : SR -32940-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, LANDSCAPING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	4.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	53.000	CYS
11	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
12	621-06570 TOP SOIL	53.000	CYS
13	621-98038 MULCH, HARDWOOD SHREDDED BARK	53.000	CYS
14	622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 72 TO	7.000	EACH
15	622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	180.000	EACH
16	622-05645 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 72 TO 96 IN.	45.000	EACH
17	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	12.000	EACH
18	622-05654 PLANT, PERENNIAL	1,000.000	EACH
19	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
20	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 354

CONTRACT ID : SR -32942-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BIKE/PEDESTRIAN FACILITIES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
11	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
12	702-51863 FIELD DRILLED HOLE IN CONCRETE	242.000	EACH
13	706-92237 HANDRAIL, STEEL	1,043.000	LFT
14	706-92237 HANDRAIL, STEEL	123.000	LFT
15	706-92237 HANDRAIL, STEEL	15.000	LFT
16	712-06386 PLANK FLOORS, SINGLE PLY	12,240.000	SFT
17	712-95676 LUMBER AND TIMBER, TREATED	2.753	MFBM
18	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
20	801-06710 FLASHING ARROW SIGN	14.000	DAY
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	801-07119 BARRICADE, III-B	72.000	LFT

CALL ORDER : 384

CONTRACT ID : SRS-32370-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02278 CURB, CONCRETE, REMOVE	251.000	LFT
8	202-02279 CURB AND GUTTER, REMOVE	55.000	LFT
9	202-52710 SIDEWALK, CONCRETE, REMOVE	80.500	SYS
10	304-07490 HMA PATCHING, TYPE B	88.000	TON
11	306-08034 MILLING, ASPHALT, 1 1/2 IN.	24,045.000	SYS
12	402-07433 HMA SURFACE, TYPE B	1,984.000	TON
13	402-07451 HMA WEDGE AND LEVEL, TYPE B	13.000	TON
14	406-05520 ASPHALT FOR TACK COAT	6.100	TON
15	604-06070 SIDEWALK, CONCRETE	14.500	SYS
16	604-07896 CURB RAMP, CONCRETE, B	5.500	SYS
17	604-07900 CURB RAMP, CONCRETE, F	14.500	SYS
18	604-07901 CURB RAMP, CONCRETE, G	4.000	SYS
19	604-07902 CURB RAMP, CONCRETE, H	42.000	SYS
20	605-06120 CURB, CONCRETE	251.000	LFT
21	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	55.000	LFT
22	621-06575 SODDING, NURSERY	33.000	SYS
23	628-09401 FIELD OFFICE, A	5.000	MOS
24	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	13.000	EACH
25	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
26	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	11,500.000	LFT
27	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,400.000	LFT
28	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	360.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	9,540.000	LFT
32	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	3,180.000	LFT
33	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1,165.000	LFT
34	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8,300.000	LFT
35	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	300.000	LFT
36	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7,770.000	LFT
37	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	305.000	LFT
38	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	360.000	LFT
39	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	465.000	LFT
40	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	13.000	EACH
41	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	10.000	EACH
42	808-98796 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN., 2 FT. LINE, 4 FT.	35.000	LFT

CALL ORDER : 400

CONTRACT ID : SRS-32378-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-01180 COMPACTED AGGREGATE, NO. 53	20.000	TON
8	304-07490 HMA PATCHING, TYPE B	310.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	4,929.000	SYS
10	306-08042 MILLING, SCARIFICATION/PROFILE	23,783.000	SYS
11	306-08043 MILLING, TRANSITION	3,673.000	SYS
12	306-08432 MILLING, APPROACH	286.000	SYS
13	402-07433 HMA SURFACE, TYPE B	2,672.000	TON
14	406-05520 ASPHALT FOR TACK COAT	8.300	TON
15	610-07487 HMA FOR APPROACHES, TYPE B	24.000	TON
16	628-09401 FIELD OFFICE, A	5.000	MOS
17	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
18	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
20	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	575.000	LFT
21	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	18,623.000	LFT
22	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	17,506.000	LFT
23	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	313.000	LFT
24	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	130.000	LFT
25	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	9.000	EACH
26	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	20.000	EACH
27	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	20.000	EACH
28	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1,240.000	LFT

CALL ORDER : 406

CONTRACT ID : SRS-32441-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	1.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	303-01180 COMPACTED AGGREGATE, NO. 53	3,930.000	TON
11	304-07489 HMA PATCHING, TYPE A	10.000	TON
12	306-08042 MILLING, SCARIFICATION/PROFILE	136,520.000	SYS
13	306-08043 MILLING, TRANSITION	4,070.000	SYS
14	306-08432 MILLING, APPROACH	500.000	SYS
15	402-07432 HMA SURFACE, TYPE A	11,640.000	TON
16	402-07450 HMA WEDGE AND LEVEL, TYPE A	2,300.000	TON
17	406-05520 ASPHALT FOR TACK COAT	35.400	TON
18	610-07486 HMA FOR APPROACHES, TYPE A	41.000	TON
19	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	1.000	MOS
20	628-09409 MOBILE INTERNET SERVICE	1.000	MOS
21	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
22	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
24	801-07119 BARRICADE, III-B	20.000	LFT

CALL ORDER : 442

CONTRACT ID : SRS-32537-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	306-08034 MILLING, ASPHALT, 1 1/2 IN.	27,270.000	SYS
8	306-08432 MILLING, APPROACH	590.000	SYS
9	402-07433 HMA SURFACE, TYPE B	2,250.000	TON
10	402-07451 HMA WEDGE AND LEVEL, TYPE B	445.000	TON
11	406-05520 ASPHALT FOR TACK COAT	8.000	TON
12	610-07487 HMA FOR APPROACHES, TYPE B	50.000	TON
13	628-09401 FIELD OFFICE, A	2.000	MOS
14	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	210.000	LFT
18	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	15.000	EACH
19	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	75.000	SFT
20	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	980.000	LFT
21	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	325.000	LFT
22	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	13,470.000	LFT
23	808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	170.000	LFT
24	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	13,440.000	LFT
25	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	30.000	LFT
26	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH

CALL ORDER : 454

CONTRACT ID : SRS-32615-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	50.000	TON
9	304-07490 HMA PATCHING, TYPE B	186.000	TON
10	306-08042 MILLING, SCARIFICATION/PROFILE	26,992.000	SYS
11	306-08043 MILLING, TRANSITION	1,260.000	SYS
12	306-08432 MILLING, APPROACH	429.000	SYS
13	402-07433 HMA SURFACE, TYPE B	2,227.000	TON
14	402-07451 HMA WEDGE AND LEVEL, TYPE B	112.000	TON
15	406-05520 ASPHALT FOR TACK COAT	6.000	TON
16	408-07504 CRACKS AND JOINTS IN ASPHALT PAVEMENT, SEAL	5.000	TON
17	610-07487 HMA FOR APPROACHES, TYPE B	46.000	TON
18	615-06520 MONUMENT, RE-ESTABLISH	3.000	EACH
19	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
20	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
21	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
22	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 466

CONTRACT ID : SRS-32664-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-01180 COMPACTED AGGREGATE, NO. 53	2.000	TON
8	304-07490 HMA PATCHING, TYPE B	1,516.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	49,856.000	SYS
10	306-08432 MILLING, APPROACH	739.000	SYS
11	402-07433 HMA SURFACE, TYPE B	4,330.000	TON
12	402-07451 HMA WEDGE AND LEVEL, TYPE B	100.000	TON
13	406-05520 ASPHALT FOR TACK COAT	16.000	TON
14	610-07487 HMA FOR APPROACHES, TYPE B	70.000	TON
15	628-09403 FIELD OFFICE, C	4.000	MOS
16	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
17	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	906.000	LFT
18	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
20	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	215.000	LFT
21	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	60.000	LFT
22	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	20.000	EACH
23	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	114.000	SFT
24	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	42.000	SFT
25	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	67.000	LFT
26	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	19,649.000	LFT
27	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,126.000	LFT
28	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	9,116.000	LFT
29	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	203.000	EACH
30	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	203.000	EACH

CALL ORDER : 506

CONTRACT ID : SRS-32749-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	303-07449 COMPACTED AGGREGATE, NO. 73	64.000	TON
9	304-07490 HMA PATCHING, TYPE B	891.000	TON
10	304-07491 HMA PATCHING, TYPE C	1,023.000	TON
11	304-07491 HMA PATCHING, TYPE C	526.000	TON
12	306-08034 MILLING, ASPHALT, 1 1/2 IN.	51,316.000	SYS
13	306-08432 MILLING, APPROACH	2,440.000	SYS
14	402-07433 HMA SURFACE, TYPE B	2,391.000	TON
15	402-07434 HMA SURFACE, TYPE C	1,843.000	TON
16	402-07451 HMA WEDGE AND LEVEL, TYPE B	455.000	TON
17	402-07452 HMA WEDGE AND LEVEL, TYPE C	212.000	TON
18	406-05520 ASPHALT FOR TACK COAT	20.000	TON
19	610-07487 HMA FOR APPROACHES, TYPE B	152.000	TON
20	610-07488 HMA FOR APPROACHES, TYPE C	78.000	TON
21	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	4.000	EACH
22	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
23	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
24	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
25	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,672.000	LFT
26	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,672.000	LFT
27	801-06640 CONSTRUCTION SIGN, A	34.000	EACH
28	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
29	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	150.000	LFT
30	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	50.000	LFT
31	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	1.000	EACH
32	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8,459.000	LFT
33	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	2,619.000	LFT
34	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	22,606.000	LFT
35	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	4,782.000	LFT
36	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	543.000	LFT
37	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4,656.000	LFT
38	808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	192.000	LFT
39	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	43.000	LFT
40	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	6.000	EACH
41	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH

CALL ORDER : 518

CONTRACT ID : SRS-32751-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	1,146.000	SYS
11	202-02278 CURB, CONCRETE, REMOVE	6,282.000	LFT
12	202-52710 SIDEWALK, CONCRETE, REMOVE	1,750.000	SYS
13	203-02000 EXCAVATION, COMMON	157.000	CYS
14	203-02070 BORROW	150.000	CYS
15	205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	72.000	EACH
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,415.000	TON
17	304-07491 HMA PATCHING, TYPE C	545.000	TON
18	306-08034 MILLING, ASPHALT, 1 1/2 IN.	15,202.000	SYS
19	306-08037 MILLING, ASPHALT, 3 IN.	19,906.000	SYS
20	306-08041 MILLING, PCCP	823.000	SYS
21	306-08043 MILLING, TRANSITION	360.000	SYS
22	306-08432 MILLING, APPROACH	6,058.000	SYS
23	402-07434 HMA SURFACE, TYPE C	2,926.000	TON
24	402-07452 HMA WEDGE AND LEVEL, TYPE C	439.000	TON
25	406-05520 ASPHALT FOR TACK COAT	13.000	TON
26	408-07504 CRACKS AND JOINTS IN ASPHALT PAVEMENT, SEAL	4.000	TON
27	604-06070 SIDEWALK, CONCRETE	1,607.000	SYS
28	604-07894 CURB RAMP, CONCRETE, A	72.000	SYS
29	604-07897 CURB RAMP, CONCRETE, C	73.000	SYS
30	604-07898 CURB RAMP, CONCRETE, D	9.000	SYS
31	604-07899 CURB RAMP, CONCRETE, E	29.000	SYS
32	604-07901 CURB RAMP, CONCRETE, G	102.000	SYS
33	604-07902 CURB RAMP, CONCRETE, H	76.000	SYS
34	604-07903 CURB RAMP, CONCRETE, K	130.000	SYS
35	605-06120 CURB, CONCRETE	6,603.000	LFT
36	605-06140 CURB AND GUTTER, CONCRETE	1,700.000	LFT
37	610-07488 HMA FOR APPROACHES, TYPE C	512.000	TON
38	610-08446 PCCP FOR APPROACHES, 6 IN.	261.000	SYS
39	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
40	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	553.000	SYS
41	621-06570 TOP SOIL	93.000	CYS
42	621-06575 SODDING, NURSERY	553.000	SYS
43	628-09401 FIELD OFFICE, A	12.000	MOS
44	720-44000 CASTING, ADJUST TO GRADE	26.000	EACH
45	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	10.000	LFT
46	720-45615 STRUCTURE, INLET, RECONSTRUCT	10.000	LFT
47	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
48	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,468.000	LFT
49	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,468.000	LFT

CALL ORDER : 518

CONTRACT ID : SRS-32751-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	ASPHALT RESURFACE			
50	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	309.000	LFT
51	801-06218	TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	309.000	LFT
52	801-06640	CONSTRUCTION SIGN, A	39.000	EACH
53	801-06710	FLASHING ARROW SIGN	60.000	DAY
54	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
55	805-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	160.000	LFT
56	805-78470	SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	8,000.000	LFT
57	805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	900.000	LFT
58	805-78785	SIGNAL DETECTOR HOUSING	4.000	EACH
59	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	2,560.000	LFT

CALL ORDER : 530

CONTRACT ID : SRS-32769-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	2.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	306-08034 MILLING, ASPHALT, 1 1/2 IN.	34,388.000	SYS
11	306-08432 MILLING, APPROACH	1,146.000	SYS
12	402-07433 HMA SURFACE, TYPE B	800.000	TON
13	402-07784 HMA SURFACE, TYPE D	2,038.000	TON
14	406-05520 ASPHALT FOR TACK COAT	9.000	TON
15	610-07487 HMA FOR APPROACHES, TYPE B	95.000	TON
16	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	2.000	MOS
17	628-09409 MOBILE INTERNET SERVICE	2.000	MOS
18	720-44000 CASTING, ADJUST TO GRADE	6.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	17.000	EACH
20	801-06645 CONSTRUCTION SIGN, B	11.000	EACH
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	805-02328 SIGNAL CABLE, 1C 14GA.	1,950.000	LFT
23	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	675.000	LFT
24	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	2,310.000	LFT
25	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,692.000	LFT
26	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	240.000	LFT
27	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	12,550.000	LFT
28	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	514.000	LFT
29	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,102.000	LFT
30	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	10.000	EACH
31	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	10.000	EACH
32	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	4.000	EACH

CALL ORDER : 536

CONTRACT ID : SRS-32770-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	2.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02274 CURB, CONCRETE, INTEGRAL, REMOVE	228.000	LFT
11	202-02279 CURB AND GUTTER, REMOVE	356.000	LFT
12	202-52710 SIDEWALK, CONCRETE, REMOVE	372.000	SYS
13	203-02000 EXCAVATION, COMMON	28.000	CYS
14	306-08034 MILLING, ASPHALT, 1 1/2 IN.	31,680.000	SYS
15	306-08432 MILLING, APPROACH	2,841.000	SYS
16	402-07433 HMA SURFACE, TYPE B	2,614.000	TON
17	406-05520 ASPHALT FOR TACK COAT	9.000	TON
18	604-07900 CURB RAMP, CONCRETE, F	93.000	SYS
19	604-07901 CURB RAMP, CONCRETE, G	167.000	SYS
20	604-07902 CURB RAMP, CONCRETE, H	171.000	SYS
21	604-91531 SIDEWALK, CONCRETE, 4 IN.	91.000	SYS
22	605-06090 CURB, INTEGRAL, CONCRETE	228.000	LFT
23	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	505.000	LFT
24	610-07487 HMA FOR APPROACHES, TYPE B	235.000	TON
25	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	2.000	MOS
26	628-09409 MOBILE INTERNET SERVICE	2.000	MOS
27	720-44000 CASTING, ADJUST TO GRADE	21.000	EACH
28	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
29	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
30	801-06645 CONSTRUCTION SIGN, B	21.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	13,612.000	LFT
33	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	640.000	LFT
34	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2,695.000	LFT
35	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	14,092.000	LFT
36	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	271.000	LFT
37	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	483.000	LFT
38	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,500.000	LFT
39	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	34.000	EACH
40	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	34.000	EACH

CALL ORDER : 542

CONTRACT ID : SRS-32778-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	50.000	TON
8	304-07490 HMA PATCHING, TYPE B	134.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	500.000	SYS
10	306-08037 MILLING, ASPHALT, 3 IN.	230.000	SYS
11	306-08042 MILLING, SCARIFICATION/PROFILE	12,328.000	SYS
12	306-08043 MILLING, TRANSITION	948.000	SYS
13	306-08432 MILLING, APPROACH	203.000	SYS
14	402-07433 HMA SURFACE, TYPE B	1,115.000	TON
15	402-07438 HMA INTERMEDIATE, TYPE B	38.000	TON
16	402-07451 HMA WEDGE AND LEVEL, TYPE B	45.000	TON
17	406-05521 ASPHALT FOR TACK COAT	4.000	SYS
18	408-07504 CRACKS AND JOINTS IN ASPHALT PAVEMENT, SEAL	2.000	TON
19	610-07487 HMA FOR APPROACHES, TYPE B	65.000	TON
20	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
21	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
22	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
23	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	478.000	LFT
24	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	41.000	LFT
25	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,500.000	LFT
28	805-78785 SIGNAL DETECTOR HOUSING	3.000	EACH
29	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	480.000	LFT
30	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8,584.000	LFT
31	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8,270.000	LFT
32	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	59.000	LFT
33	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
34	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH

CALL ORDER : 548

CONTRACT ID : SRS-32779-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	50.000	TON
8	304-07490 HMA PATCHING, TYPE B	433.000	TON
9	306-08042 MILLING, SCARIFICATION/PROFILE	27,884.000	SYS
10	306-08043 MILLING, TRANSITION	1,233.000	SYS
11	306-08432 MILLING, APPROACH	1,065.000	SYS
12	402-07433 HMA SURFACE, TYPE B	2,403.000	TON
13	402-07451 HMA WEDGE AND LEVEL, TYPE B	36.000	TON
14	406-05521 ASPHALT FOR TACK COAT	7.000	SYS
15	408-07504 CRACKS AND JOINTS IN ASPHALT PAVEMENT, SEAL	4.000	TON
16	610-07487 HMA FOR APPROACHES, TYPE B	238.000	TON
17	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
18	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
19	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
20	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,118.000	LFT
21	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	13.000	LFT
22	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
24	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	22,075.000	LFT
25	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	21,678.000	LFT
26	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	113.000	LFT

CALL ORDER : 560

CONTRACT ID : SRS-32784-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02278 CURB, CONCRETE, REMOVE	740.000	LFT
9	202-52710 SIDEWALK, CONCRETE, REMOVE	560.000	SYS
10	303-01180 COMPACTED AGGREGATE, NO. 53	19.000	TON
11	306-08034 MILLING, ASPHALT, 1 1/2 IN.	94,110.000	SYS
12	306-08432 MILLING, APPROACH	4,600.000	SYS
13	402-07433 HMA SURFACE, TYPE B	8,160.000	TON
14	402-07451 HMA WEDGE AND LEVEL, TYPE B	1,553.000	TON
15	406-05520 ASPHALT FOR TACK COAT	16.000	TON
16	406-05521 ASPHALT FOR TACK COAT	8.000	SYS
17	604-07896 CURB RAMP, CONCRETE, B	75.000	SYS
18	604-07901 CURB RAMP, CONCRETE, G	165.000	SYS
19	604-07902 CURB RAMP, CONCRETE, H	20.000	SYS
20	604-91531 SIDEWALK, CONCRETE, 4 IN.	270.000	SYS
21	610-07487 HMA FOR APPROACHES, TYPE B	400.000	TON
22	628-09401 FIELD OFFICE, A	2.000	MOS
23	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
24	801-06640 CONSTRUCTION SIGN, A	94.000	EACH
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	1,630.000	LFT
27	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	118.000	EACH
28	802-07060 SIGN, SHEET, RELOCATE	15.000	EACH
29	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	560.000	SFT
30	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	150.000	SFT
31	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	12,570.000	LFT
32	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	3,970.000	LFT
33	805-90015 POLE BANDS, STEEL	5.000	EACH
34	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	55.000	EACH
35	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	32.000	EACH
36	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	1.000	EACH
37	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	4,170.000	LFT
38	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	14,800.000	LFT
39	808-74815 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 12 IN.	2,430.000	LFT
40	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,030.000	LFT
41	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	42,570.000	LFT
42	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	2,340.000	LFT
43	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	530.000	LFT
44	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,140.000	LFT
45	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	4.000	EACH
46	808-75350 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (SCHOOL)	4.000	EACH

CALL ORDER : 566

CONTRACT ID : SRS-32785-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	306-08034 MILLING, ASPHALT, 1 1/2 IN.	43,910.000	SYS
9	306-08043 MILLING, TRANSITION	550.000	SYS
10	306-08432 MILLING, APPROACH	1,750.000	SYS
11	402-07433 HMA SURFACE, TYPE B	4,440.000	TON
12	402-07451 HMA WEDGE AND LEVEL, TYPE B	578.000	TON
13	406-05520 ASPHALT FOR TACK COAT	12.000	TON
14	610-07487 HMA FOR APPROACHES, TYPE B	160.000	TON
15	628-09401 FIELD OFFICE, A	2.000	MOS
16	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
17	801-06640 CONSTRUCTION SIGN, A	61.000	EACH
18	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
19	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	850.000	LFT
20	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	55.000	EACH
21	802-07060 SIGN, SHEET, RELOCATE	5.000	EACH
22	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	270.000	SFT
23	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	130.000	SFT
24	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	285.000	LFT
25	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	260.000	LFT
26	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	21,880.000	LFT
27	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	28,650.000	LFT
28	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	1,505.000	LFT
29	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	175.000	LFT
30	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	335.000	LFT
31	808-75350 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (SCHOOL)	4.000	EACH

CALL ORDER : 578

CONTRACT ID : SRS-32789-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT BIKE/PEDESTRIAN FACILITY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02255 TREE, 18 IN., REMOVE	1.000	EACH
8	202-52710 SIDEWALK, CONCRETE, REMOVE	55.000	SYS
9	202-91922 STUMP, REMOVE	2.000	EACH
10	203-02000 EXCAVATION, COMMON	869.000	CYS
11	203-02070 BORROW	500.000	CYS
12	205-06933 TEMPORARY DITCH INLET PROTECTION	18.000	EACH
13	205-06937 TEMPORARY SILT FENCE	3,644.000	LFT
14	303-01180 COMPACTED AGGREGATE, NO. 53	1,161.000	TON
15	402-07433 HMA SURFACE, TYPE B	495.000	TON
16	604-07901 CURB RAMP, CONCRETE, G	71.000	SYS
17	604-07901 CURB RAMP, CONCRETE, G	140.000	SYS
18	604-91531 SIDEWALK, CONCRETE, 4 IN.	377.000	SYS
19	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
20	621-06560 MULCHED SEEDING, U	2,000.000	SYS
21	628-09401 FIELD OFFICE, A	4.000	MOS
22	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	2.000	EACH
23	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
24	801-06640 CONSTRUCTION SIGN, A	37.000	EACH
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	19.000	LFT
27	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	7.000	SFT
28	808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	836.000	LFT

CALL ORDER : 584

CONTRACT ID : SRS-32791-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-52710 SIDEWALK, CONCRETE, REMOVE	11.000	SYS
9	306-08037 MILLING, ASPHALT, 3 IN.	2,573.000	SYS
10	306-08041 MILLING, PCCP	14,610.000	SYS
11	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,418.000	TON
12	401-07362 QC/QA-HMA, 3, 70, INTERMEDIATE, 9.5 mm	1,418.000	TON
13	406-05520 ASPHALT FOR TACK COAT	9.000	TON
14	506-06333 PCCP PATCHING, FULL DEPTH	210.000	SYS
15	604-07897 CURB RAMP, CONCRETE, C	8.000	SYS
16	604-91531 SIDEWALK, CONCRETE, 4 IN.	4.000	SYS
17	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
18	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
19	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
20	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
21	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
22	801-06710 FLASHING ARROW SIGN	20.000	DAY
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
24	801-07117 TEMPORARY WORKSITE FLASHING LIGHT SIGN ASSEMBLY	1.000	EACH
25	805-02328 SIGNAL CABLE, 1C 14GA.	5,980.000	LFT
26	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,600.000	LFT
27	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	16.000	EACH
28	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1,432.000	LFT
29	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,741.000	LFT
30	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,594.000	LFT
31	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	184.000	LFT
32	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	3.000	EACH
33	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000	EACH

CALL ORDER : 600

CONTRACT ID : SRS-32792-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	306-08034 MILLING, ASPHALT, 1 1/2 IN.	25,588.000	SYS
9	306-08039 MILLING, ASPHALT REMOVAL	95,082.000	SYS
10	306-08043 MILLING, TRANSITION	311.000	SYS
11	306-08432 MILLING, APPROACH	4,433.000	SYS
12	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
13	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	9,955.000	TON
14	401-07372 QC/QA-HMA, 3, 64, INTERMEDIATE, 12.5 mm	15,689.000	TON
15	406-05520 ASPHALT FOR TACK COAT	61.000	TON
16	506-06333 PCCP PATCHING, FULL DEPTH	404.000	SYS
17	610-07487 HMA FOR APPROACHES, TYPE B	732.000	TON
18	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	53.000	EACH
19	611-08233 MAILBOX ASSEMBLY, DOUBLE, RESET	4.000	EACH
20	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	60.000	TON
21	612-60410 DRILLED HOLE FOR UNDERSEAL	1,061.000	EACH
22	628-09402 FIELD OFFICE, B	12.000	MOS
23	720-44000 CASTING, ADJUST TO GRADE	12.000	EACH
24	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
25	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
26	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,978.000	LFT
27	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
28	801-06645 CONSTRUCTION SIGN, B	24.000	EACH
29	801-06710 FLASHING ARROW SIGN	40.000	DAY
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	801-07117 TEMPORARY WORKSITE FLASHING LIGHT SIGN ASSEMBLY	4.000	EACH
32	802-76005 SIGN, SHEET, ENCLOSED LENS, WITH LEGEND	870.000	SFT
33	802-76055 SIGN POST, A	1,260.000	LFT
34	808-06609 PAVEMENT MESSAGE MARKING	120.000	EACH
35	808-06609 PAVEMENT MESSAGE MARKING	13.000	EACH
36	808-06609 PAVEMENT MESSAGE MARKING	119.000	EACH
37	808-06609 PAVEMENT MESSAGE MARKING	120.000	EACH
38	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	9,228.000	LFT
39	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	72,070.000	LFT
40	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	36,684.000	LFT
41	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	198.000	LFT
42	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	15.000	EACH
43	808-98796 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN., 2 FT. LINE, 4 FT.	332.000	LFT

CALL ORDER : 606

CONTRACT ID : SRS-32793-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	304-07490 HMA PATCHING, TYPE B	100.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	10,502.000	SYS
10	306-08043 MILLING, TRANSITION	970.000	SYS
11	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	946.000	TON
12	401-07356 QC/QA-HMA, 2, 64, INTERMEDIATE, 9.5 mm	866.000	TON
13	406-05520 ASPHALT FOR TACK COAT	6.000	TON
14	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	50.000	EACH
15	611-08233 MAILBOX ASSEMBLY, DOUBLE, RESET	7.000	EACH
16	628-09402 FIELD OFFICE, B	12.000	MOS
17	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
18	720-44000 CASTING, ADJUST TO GRADE	11.000	EACH
19	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
20	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
21	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
22	801-06645 CONSTRUCTION SIGN, B	13.000	EACH
23	801-06710 FLASHING ARROW SIGN	10.000	DAY
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
25	801-07117 TEMPORARY WORKSITE FLASHING LIGHT SIGN ASSEMBLY	4.000	EACH
26	805-02328 SIGNAL CABLE, 1C 14GA.	920.000	LFT
27	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	400.000	LFT
28	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	2.000	EACH
29	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5,737.000	LFT
30	808-09038 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE,	90.000	LFT
31	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,481.000	LFT
32	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	86.000	LFT
33	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
34	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH
35	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	4.000	EACH

CALL ORDER : 630

CONTRACT ID : SRS-32808-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-74035 SIGN, REMOVE	21.000	EACH
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	32,820.000	SYS
10	402-07433 HMA SURFACE, TYPE B	2,708.000	TON
11	402-07451 HMA WEDGE AND LEVEL, TYPE B	538.000	TON
12	406-05520 ASPHALT FOR TACK COAT	8.300	TON
13	628-09401 FIELD OFFICE, A	1.000	MOS
14	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	105.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	214.000	LFT
18	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	107.500	SFT
19	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	8.000	SFT
20	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	20,660.000	LFT
21	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2,215.000	LFT
22	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	16,270.000	LFT
23	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	56.000	LFT

CALL ORDER : 642

CONTRACT ID : SRS-32811-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	3.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	303-01180 COMPACTED AGGREGATE, NO. 53	19.000	TON
11	304-07490 HMA PATCHING, TYPE B	150.000	TON
12	306-08034 MILLING, ASPHALT, 1 1/2 IN.	21,704.000	SYS
13	306-08432 MILLING, APPROACH	1,474.000	SYS
14	402-07433 HMA SURFACE, TYPE B	1,800.000	TON
15	402-07451 HMA WEDGE AND LEVEL, TYPE B	460.000	TON
16	406-05521 ASPHALT FOR TACK COAT	7.000	SYS
17	408-07504 CRACKS AND JOINTS IN ASPHALT PAVEMENT, SEAL	50.000	TON
18	610-07487 HMA FOR APPROACHES, TYPE B	122.000	TON
19	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
20	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
21	715-94530 ADJUST WATER VALVE TO GRADE	2.000	EACH
22	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
23	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
24	801-03291 CONSTRUCTION SIGN, D	15.000	EACH
25	801-06640 CONSTRUCTION SIGN, A	33.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	564.000	LFT
28	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	252.300	SFT
29	805-96014 SAW CUT, FULL DEPTH	500.000	LFT
30	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,000.000	LFT
31	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	18,278.000	LFT
32	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	180.000	LFT

CALL ORDER : 648

CONTRACT ID : SRS-32813-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	1.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	282.500	SYS
11	202-52710 SIDEWALK, CONCRETE, REMOVE	734.000	SYS
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	282.750	TON
13	306-08034 MILLING, ASPHALT, 1 1/2 IN.	39,780.000	SYS
14	402-07432 HMA SURFACE, TYPE A	3,349.000	TON
15	402-07450 HMA WEDGE AND LEVEL, TYPE A	490.000	TON
16	406-05520 ASPHALT FOR TACK COAT	21.000	TON
17	502-06329 PCCP, 12 IN.	271.000	SYS
18	604-07894 CURB RAMP, CONCRETE, A	1,036.700	SYS
19	604-07896 CURB RAMP, CONCRETE, B	31.600	SYS
20	604-07902 CURB RAMP, CONCRETE, H	43.600	SYS
21	604-91531 SIDEWALK, CONCRETE, 4 IN.	76.330	SYS
22	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	1.000	MOS
23	628-09409 MOBILE INTERNET SERVICE	1.000	MOS
24	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	39.000	EACH
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 672

CONTRACT ID : SRS-32847-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	689.000	TON
7	304-07490 HMA PATCHING, TYPE B	689.000	TON
8	306-08034 MILLING, ASPHALT, 1 1/2 IN.	12,100.000	SYS
9	306-08043 MILLING, TRANSITION	600.000	SYS
10	306-08432 MILLING, APPROACH	1,492.000	SYS
11	402-07433 HMA SURFACE, TYPE B	1,121.000	TON
12	402-07451 HMA WEDGE AND LEVEL, TYPE B	18.000	TON
13	406-05521 ASPHALT FOR TACK COAT	12,356.000	SYS
14	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
15	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
16	720-01355 CLEAN EXISTING INLET	2.000	EACH
17	720-44000 CASTING, ADJUST TO GRADE	16.000	EACH
18	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
21	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8,750.000	LFT
22	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	105.000	LFT
23	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8,540.000	LFT

CALL ORDER : 678

CONTRACT ID : SRS-32849-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	408-07504 CRACKS AND JOINTS IN ASPHALT PAVEMENT, SEAL	130.000	TON
9	628-09401 FIELD OFFICE, A	2.000	MOS
10	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
11	801-03291 CONSTRUCTION SIGN, D	8.000	EACH
12	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 700

CONTRACT ID : SRS-32859-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-07449 COMPACTED AGGREGATE, NO. 73	22.000	TON
8	304-07490 HMA PATCHING, TYPE B	664.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN.	8,837.000	SYS
10	306-08432 MILLING, APPROACH	279.000	SYS
11	402-07433 HMA SURFACE, TYPE B	729.000	TON
12	402-07451 HMA WEDGE AND LEVEL, TYPE B	142.000	TON
13	406-05520 ASPHALT FOR TACK COAT	3.000	TON
14	610-07487 HMA FOR APPROACHES, TYPE B	26.000	TON
15	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
16	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
17	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
18	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	361.000	LFT
19	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	361.000	LFT
20	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	508.000	LFT
23	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	7,220.000	LFT
24	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	4,801.000	LFT
25	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	12.000	LFT

CALL ORDER : 706

CONTRACT ID : SRS-32884-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	306-08034 MILLING, ASPHALT, 1 1/2 IN.	11,660.000	SYS
9	402-07433 HMA SURFACE, TYPE B	1,020.000	TON
10	402-07451 HMA WEDGE AND LEVEL, TYPE B	190.000	TON
11	406-05520 ASPHALT FOR TACK COAT	3.000	TON
12	628-09401 FIELD OFFICE, A	2.000	MOS
13	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	44.000	LFT
17	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	3.000	EACH
18	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	18.000	SFT
19	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,770.000	LFT
20	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7,770.000	LFT
21	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	15.000	LFT

CALL ORDER : 754

CONTRACT ID : SB -31224-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	202-96430 FENCE AND POSTS, REMOVE	LUMP	LUMP
14	203-02000 EXCAVATION, COMMON	109.000	CYS
15	203-02070 BORROW	269.000	CYS
16	203-02100 EXCAVATION, PEAT	2,212.000	CYS
17	203-09753 GRANULAR SOILS	1,104.000	TON
18	203-09754 COHESIVE ENCASEMENT MATERIAL	62.000	CYS
19	205-02770 EROSION CONTROL BLANKET	358.000	SYS
20	205-03371 SEDIMENT, REMOVE	16.000	CYS
21	205-06932 TEMPORARY CHECK DAM, STRAW BALES	12.000	LFT
22	205-06934 TEMPORARY MULCHING	0.300	TON
23	205-06936 TEMPORARY SEDIMENT TRAP	3.300	TON
24	205-06937 TEMPORARY SILT FENCE	1,146.000	LFT
25	205-09543 NO 2 STONE	100.000	TON
26	207-08263 SUBGRADE TREATMENT, TYPE IA	1,032.000	SYS
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	60.000	SYS
28	211-02050 B BORROW	560.000	CYS
29	211-09265 STRUCTURE BACKFILL, TYPE 2	237.000	CYS
30	211-09774 SHREDDED TIRE, MODIFIED	230.000	TON
31	214-07202 GEOGRID, I	2,717.000	SYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	220.000	TON
33	303-01180 COMPACTED AGGREGATE, NO. 53	433.000	TON
34	306-08043 MILLING, TRANSITION	267.000	SYS
35	402-07434 HMA SURFACE, TYPE C	178.000	TON
36	402-07439 HMA INTERMEDIATE, TYPE C	178.000	TON
37	402-07442 HMA BASE, TYPE C	259.000	TON
38	406-05520 ASPHALT FOR TACK COAT	1.000	TON
39	601-01701 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 2	1.000	EACH
40	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
41	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
42	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	218.800	LFT
43	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
44	615-06490 RIGHT OF WAY MARKER	24.000	EACH
45	615-06505 MONUMENT, B	2.000	EACH
46	616-02320 GEOTEXTILES	5,035.000	SYS
47	616-06405 RIPRAP, REVETMENT	91.000	TON
48	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH

49 621-06545

FERTILIZER

0.100

TON

CALL ORDER : 754

CONTRACT ID : SB -31224-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	621-06553 SEED MIXTURE, R	22.000	LBS
51	621-06557 SEED MIXTURE, T	5.000	LBS
52	621-06565 MULCHING MATERIAL	0.100	TON
53	621-06567 WATER	1.000	KGAL
54	621-06575 SODDING, NURSERY	380.000	SYS
55	628-09401 FIELD OFFICE, A	5.000	MOS
56	714-26718 CULVERT, PRECAST, REINFORCED CONCRETE BOX, 10' X 6'	88.000	LFT
57	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN.	1.000	EACH
58	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	45.000	LFT
59	715-46005 PIPE END SECTION, 15 IN.	1.000	EACH
60	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
61	801-06625 DETOUR ROUTE MARKER ASSEMBLY	34.000	EACH
62	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
63	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
64	801-07118 BARRICADE, III-A	48.000	LFT
65	801-07119 BARRICADE, III-B	64.000	LFT
66	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,025.000	LFT
67	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	128.000	LFT

CALL ORDER : 766

CONTRACT ID : SB -32816-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DESIN BUILD, BRIDGE DECK REPLACEMENT		
1	104-05404 DESIGN/BUILD	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	20.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	628-09402 FIELD OFFICE, B	10.000	MOS
10	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	10.000	MOS

