

CALL ORDER : 141

CONTRACT ID : R -29931-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	36.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
14	202-02278 CURB, CONCRETE, REMOVE	1,197.000	LFT
15	202-02279 CURB AND GUTTER, REMOVE	609.000	LFT
16	202-02772 CASTING, REMOVE	1.000	EACH
17	202-02928 CATCH BASIN, REMOVE	3.000	EACH
18	202-52710 SIDEWALK, CONCRETE, REMOVE	3,725.000	SYS
19	202-91385 INLET, REMOVE	37.000	EACH
20	202-93047 MANHOLE, REMOVE	17.000	EACH
21	202-96133 PIPE, REMOVE	6,776.000	LFT
22	203-02000 EXCAVATION, COMMON	19,990.000	CYS
23	205-03371 SEDIMENT, REMOVE	15.000	CYS
24	205-06933 TEMPORARY DITCH INLET PROTECTION	75.000	EACH
25	205-06937 TEMPORARY SILT FENCE	341.000	LFT
26	205-09543 NO 2 STONE	100.000	TON
27	207-08263 SUBGRADE TREATMENT, TYPE IA	39,510.000	SYS
28	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,860.000	SYS
29	211-02050 B BORROW	3,385.000	CYS
30	211-09264 STRUCTURE BACKFILL, TYPE 1	10,396.000	CYS
31	303-01180 COMPACTED AGGREGATE, NO. 53	0.600	TON
32	304-07491 HMA PATCHING, TYPE C	59.200	TON
33	306-08043 MILLING, TRANSITION	1,004.000	SYS
34	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2,484.000	TON
35	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	4,006.000	TON
36	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	14,373.000	TON
37	406-05520 ASPHALT FOR TACK COAT	22.700	TON
38	604-07894 CURB RAMP, CONCRETE, A	4.700	SYS
39	604-07896 CURB RAMP, CONCRETE, B	10.200	SYS
40	604-07897 CURB RAMP, CONCRETE, C	47.800	SYS
41	604-07900 CURB RAMP, CONCRETE, F	121.800	SYS
42	604-07901 CURB RAMP, CONCRETE, G	210.100	SYS
43	604-07902 CURB RAMP, CONCRETE, H	94.100	SYS
44	604-91531 SIDEWALK, CONCRETE, 4 IN.	7,459.000	SYS
45	605-06150 CURB AND GUTTER, C, CONCRETE	13,666.000	LFT
46	610-08446 PCCP FOR APPROACHES, 6 IN.	2,161.000	SYS
47	610-09108 PCCP FOR APPROACHES, 9 IN.	1,700.000	SYS
48	611-06497 MAILBOX ASSEMBLY, SINGLE	64.000	EACH
49	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH

CALL ORDER : 141

CONTRACT ID : R -29931-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION		
50	615-06505 MONUMENT, B	9.000	EACH
51	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
52	616-02320 GEOTEXTILES	5.200	SYS
53	621-06567 WATER	58.600	KGAL
54	621-06575 SODDING, NURSERY	14,631.000	SYS
55	628-09402 FIELD OFFICE, B	18.000	MOS
56	703-06028 REINFORCING BARS	29.000	LBS
57	714-44240 CONCRETE, A, STRUCTURES	7.000	CYS
58	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	1,062.000	LFT
59	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	5,334.000	LFT
60	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	720.000	LFT
61	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	402.000	LFT
62	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	668.000	LFT
63	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	2,209.000	LFT
64	715-05159 PIPE, TYPE 2, CIRCULAR, 42 IN.	710.000	LFT
65	715-05428 PIPE, SLOTTED VANE DRAIN, 12 IN.	180.000	LFT
66	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	26.300	TON
67	715-09064 VIDEO INSPECTION FOR PIPE	4,978.000	LFT
68	715-09550 PIPE, SANITARY SEWER, 27 IN.	11.000	LFT
69	715-91738 WATER MAIN, DUCTILE IRON, 6 IN.	3,536.000	LFT
70	715-91739 WATER MAIN, DUCTILE IRON, 8 IN.	419.000	LFT
71	715-93910 WATER SERVICE LINE, ADJUST	20.000	EACH
72	720-08628 SLOTTED DRAIN PIPE CLEANOUT PORT, TYPE II	1.000	EACH
73	720-44000 CASTING, ADJUST TO GRADE	44.000	EACH
74	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000	EACH
75	720-44296 CAP INLET	1.000	EACH
76	720-45030 INLET, E7	7.000	EACH
77	720-45075 INLET, R13	2.000	EACH
78	720-45205 CATCH BASIN, A2	1.000	EACH
79	720-45375 PIPE CATCH BASIN, 24 IN., MODIFIED	53.000	EACH
80	720-45410 MANHOLE, C4	16.000	EACH
81	720-90984 MANHOLE, C2	3.000	EACH
82	720-94612 MANHOLE, K4	6.000	EACH
83	720-95335 MANHOLE, M4	1.000	EACH
84	720-95422 MANHOLE, J4	31.000	EACH
85	720-96999 FIRE HYDRANT ASSEMBLY	5.000	EACH
86	720-98174 INLET, B15	30.000	EACH
87	720-98555 INLET, C15	33.000	EACH
88	720-99416 CATCH BASIN, B15	30.000	EACH
89	720-99417 CATCH BASIN, C15	42.000	EACH
90	732-02531 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON 6 IN.	20.000	EACH
91	732-02532 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 8 IN.	2.000	EACH
92	732-90578 WATER METER, RELOCATE	3.000	EACH
93	801-04308 ROAD CLOSURE SIGN ASSEMBLY	15.000	EACH
94	801-06625 DETOUR ROUTE MARKER ASSEMBLY	67.000	EACH
95	801-06640 CONSTRUCTION SIGN, A	25.000	EACH
96	801-06710 FLASHING ARROW SIGN	28.000	DAY
97	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
98	801-07118 BARRICADE, III-A	192.000	LFT

CALL ORDER : 141

CONTRACT ID : R -29931-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION		
99	801-07119 BARRICADE, III-B	144.000	LFT
100	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	870.700	LFT
101	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	85.000	EACH
102	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
103	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	628.300	SFT
104	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	25.500	SFT
105	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	90.000	SFT
106	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
107	805-01842 HANDHOLE, SIGNAL	5.000	EACH
108	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	8.000	EACH
109	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,042.000	LFT
110	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
111	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	3.000	EACH
112	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	5.000	EACH
113	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
114	805-78420 DISCONNECT HANGER	4.000	EACH
115	805-78467 SIGNAL CABLE, 3C 8GA.	39.000	LFT
116	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	4,780.000	LFT
117	805-78485 SIGNAL CABLE, 5C 14GA.	827.000	LFT
118	805-78490 SIGNAL CABLE, 7C 14GA.	1,787.000	LFT
119	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,633.000	LFT
120	805-78785 SIGNAL DETECTOR HOUSING	9.000	EACH
121	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,460.000	LFT
122	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
123	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000	EACH
124	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	5.000	EACH
125	805-96121 PEDESTRIAN PUSH BUTTON AND SIGN	8.000	EACH
126	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,122.000	LFT
127	808-06716 LINE, REMOVE	632.000	LFT
128	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	460.000	LFT
129	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	16,171.000	LFT
130	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	592.000	LFT
131	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	3,112.700	LFT
132	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	16.000	EACH
133	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	16.000	EACH
134	808-75350 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (SCHOOL)	2.000	EACH
135	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	104.000	EACH
136	808-98796 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN., 2 FT. LINE, 4 FT.	37.000	LFT

CALL ORDER : 151

CONTRACT ID : R -30256-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIDEWALK REHABILITATION AND CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-52710 SIDEWALK, CONCRETE, REMOVE	58.000	SYS
10	203-02000 EXCAVATION, COMMON	10.000	CYS
11	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	8.000	EACH
12	205-06937 TEMPORARY SILT FENCE	395.000	LFT
13	211-09266 STRUCTURE BACKFILL, TYPE 3	3.000	CYS
14	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	18.000	TON
15	304-07489 HMA PATCHING, TYPE A	54.000	TON
16	406-05520 ASPHALT FOR TACK COAT	0.050	TON
17	604-07897 CURB RAMP, CONCRETE, C	66.000	SYS
18	604-07901 CURB RAMP, CONCRETE, G	65.000	SYS
19	604-44251 STEPS, CONCRETE	0.500	CYS
20	604-90256 SIDEWALK, CONCRETE, 6 IN.	220.000	SYS
21	604-91531 SIDEWALK, CONCRETE, 4 IN.	1,914.000	SYS
22	605-06120 CURB, CONCRETE	278.000	LFT
23	610-08446 PCCP FOR APPROACHES, 6 IN.	60.000	SYS
24	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
25	621-06559 MULCHED SEEDING, R	3,062.000	SYS
26	628-09401 FIELD OFFICE, A	6.000	MOS
27	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	70.000	LFT
28	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
29	732-08419 MODULAR BLOCK WALL	16.000	SYS
30	732-08421 MODULAR BLOCK WALL ERECTION	16.000	SYS
31	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
32	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
33	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	801-07119 BARRICADE, III-B	72.000	LFT
36	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	216.000	LFT
37	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
38	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	36.000	SFT
39	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	162.000	SFT
40	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	510.000	LFT
41	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	385.000	LFT

CALL ORDER : 171

CONTRACT ID : B -29668-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
6	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-01261 TESTING FOR ASBESTOS	3.000	EACH
13	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
14	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
16	202-07003 REMOVE	LUMP	LUMP
17	203-02000 EXCAVATION, COMMON	3,940.000	CYS
18	203-02070 BORROW	14,425.000	CYS
19	205-03371 SEDIMENT, REMOVE	12.000	CYS
20	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	41.000	TON
21	205-06936 TEMPORARY SEDIMENT TRAP	59.000	TON
22	205-06937 TEMPORARY SILT FENCE	2,815.000	LFT
23	205-09543 NO 2 STONE	100.000	TON
24	207-08264 SUBGRADE TREATMENT, TYPE II	5,033.000	SYS
25	211-09265 STRUCTURE BACKFILL, TYPE 2	156.000	CYS
26	216-06392 CELLULAR CONCRETE FILL, II	27,730.000	CYS
27	216-06394 CELLULAR CONCRETE FILL, IV	2,372.000	CYS
28	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,663.000	TON
29	302-06464 SUBBASE FOR PCCP	1,012.000	CYS
30	302-07455 DENSE GRADED SUBBASE	39.000	CYS
31	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	178.000	TON
32	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	762.000	TON
33	406-05520 ASPHALT FOR TACK COAT	1.000	TON
34	501-06321 QC/QA-PCCP, 10 IN.	4,411.000	SYS
35	503-05240 D-1 CONTRACTION JOINT	2,330.000	LFT
36	503-05310 TERMINAL JOINT	71.000	LFT
37	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
38	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
39	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,244.000	LFT
40	602-06729 BARRIER DELINEATOR	18.000	EACH
41	603-97461 TEMPORARY FENCE	2,260.000	LFT
42	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	232.200	SYS
43	615-06510 MONUMENT, C	1.000	EACH
44	615-06515 MONUMENT, D	1.000	EACH
45	616-02320 GEOTEXTILES	8,224.000	SYS
46	616-06405 RIPRAP, REVETMENT	7,031.000	TON
47	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
48	621-06545 FERTILIZER	2.000	TON
49	621-06553 SEED MIXTURE, R	685.000	LBS

CALL ORDER : 171

CONTRACT ID : B -29668-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE CONSTRUCTION		
50	621-06565 MULCHING MATERIAL	8.000	TON
51	621-06567 WATER	3.000	KGAL
52	621-06575 SODDING, NURSERY	604.000	SYS
53	622-52436 SIGN, DO NOT MOW OR SPRAY	12.000	EACH
54	622-98200 SIGN, DO NOT DISTURB	12.000	EACH
55	628-09402 FIELD OFFICE, B	15.000	MOS
56	701-05561 DRILLED SHAFT	930.000	LFT
57	701-05671 PERMANENT CASING	508.000	LFT
58	701-05784 TRIAL SHAFT HOLES	55.000	LFT
59	701-05785 EXPLORATION (SHAFT EXCAVATION)	930.000	LFT
60	702-51005 CONCRETE, A, SUBSTRUCTURE	299.800	CYS
61	702-51100 DRAIN PIPE, CAST IRON, 6 IN.	904.000	LBS
62	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	2,576.000	LBS
63	703-06028 REINFORCING BARS	147,453.000	LBS
64	703-06029 REINFORCING BARS, EPOXY COATED	187,855.000	LBS
65	704-51002 CONCRETE, C, SUPERSTRUCTURE	383.400	CYS
66	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
67	706-51020 CONCRETE, C, RAILING	65.000	CYS
68	707-08512 STRUCTURAL MEMBERS, CONCRETE BOX BEAM,	1,224.000	LFT
69	707-09316 STRUCTURALMEMBERS, CONCRETE BULB-T BEAM,	1,020.000	LFT
70	709-51821 SURFACE SEAL	LUMP	LUMP
71	714-93638 CULVERT, PRECAST, REINFORCED CONCRETE BOX, 5' X 4'	118.000	LFT
72	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	1,620.000	LFT
73	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	169.000	LFT
74	718-06528 OUTLET PROTECTOR, 1	3.000	EACH
75	718-06531 OUTLET PROTECTOR, 3	5.000	EACH
76	718-52610 AGGREGATE FOR UNDERDRAINS	152.000	CYS
77	718-99153 GEOTEXTILES FOR UNDERDRAIN	2,157.000	SYS
78	724-51925 STRUCTURAL EXPANSION JOINT, SS	154.000	LFT
79	801-04308 ROAD CLOSURE SIGN ASSEMBLY	1.000	EACH
80	801-06640 CONSTRUCTION SIGN, A	3.000	EACH
81	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
82	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
83	801-07118 BARRICADE, III-A	48.000	LFT
84	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	47.000	LFT
85	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	24.000	SFT
86	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	6.000	SFT
87	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	4,231.000	LFT
88	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	1,742.000	LFT
89	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	142.000	LFT
90	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	34.000	LFT
91	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
92	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH

CALL ORDER : 181

CONTRACT ID : B -31480-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	262.000	CYS
10	304-07492 WIDENING WITH HMA, TYPE A	518.000	TON
11	619-09429 CLEAN STEEL BRIDGE, PARTIAL, TYPE 1, QP-2	23,966.000	SFT
12	619-09429 CLEAN STEEL BRIDGE, PARTIAL, TYPE 1, QP-2	23,966.000	SFT
13	619-09437 PAINT STEEL BRIDGE, PARTIAL, TYPE 1	23,966.000	SFT
14	619-09437 PAINT STEEL BRIDGE, PARTIAL, TYPE 1	23,966.000	SFT
15	628-09402 FIELD OFFICE, B	5.000	MOS
16	711-51035 STRUCTURAL STEEL	2,117.000	LBS
17	711-51864 DRILLED HOLE	641.000	EACH
18	711-51866 RIVET, REMOVE	160.000	EACH
19	711-96479 BOLT, REMOVE	96.000	EACH
20	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	9.000	EACH
21	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
22	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	22,400.000	LFT
23	801-06640 CONSTRUCTION SIGN, A	41.000	EACH
24	801-06710 FLASHING ARROW SIGN	120.000	DAY
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	801-08507 TEMPORARY TRAFFIC BARRIER, TYPE 1, ANCHORED	2,616.000	LFT
27	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
28	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	1,300.000	LFT
29	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	3,340.000	LFT
30	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	3,340.000	LFT
31	808-06716 LINE, REMOVE	7,980.000	LFT

