

CALL ORDER : 140

CONTRACT ID : IB-30838-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	34.000	MOS
5	105-08523 RADIO SERVICE	34.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
17	203-02000 EXCAVATION, COMMON	13,996.000	CYS
18	203-02070 BORROW	180,524.000	CYS
19	204-02290 SETTLEMENT PLATE	11.000	EACH
20	204-08415 STAKES, SETTLEMENT	11.000	EACH
21	205-03371 SEDIMENT, REMOVE	100.000	CYS
22	205-06930 SPLASHPAD, RIPRAP	20.400	TON
23	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	250.000	TON
24	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
25	205-06936 TEMPORARY SEDIMENT TRAP	40.000	TON
26	205-06937 TEMPORARY SILT FENCE	2,440.000	LFT
27	205-06938 TEMPORARY SLOPE DRAIN	326.000	LFT
28	205-09543 NO 2 STONE	100.000	TON
29	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	170.000	CYS
30	207-08263 SUBGRADE TREATMENT, TYPE IA	16,037.000	SYS
31	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,027.000	SYS
32	211-02050 B BORROW	3,570.000	CYS
33	211-09264 STRUCTURE BACKFILL, TYPE 1	1,546.000	CYS
34	211-09266 STRUCTURE BACKFILL, TYPE 3	3,365.000	CYS
35	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,822.000	TON
36	302-07455 DENSE GRADED SUBBASE	44.000	CYS
37	302-08562 COARSE AGGREGATE, 8	53.000	TON
38	306-08043 MILLING, TRANSITION	90.000	SYS
39	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	4,206.000	TON
40	402-07432 HMA SURFACE, TYPE A	430.000	TON
41	402-07433 HMA SURFACE, TYPE B	757.000	TON
42	402-07435 HMA INTERMEDIATE, TYPE A	307.000	TON
43	402-07438 HMA INTERMEDIATE, TYPE B	1,270.000	TON
44	402-07440 HMA BASE, TYPE A	1,749.000	TON
45	406-05520 ASPHALT FOR TACK COAT	8.310	TON
46	503-05240 D-1 CONTRACTION JOINT	94.000	LFT
47	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
48	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
49	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	550.000	LFT

CALL ORDER : 140

CONTRACT ID : IB-30838-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
50	602-06729 BARRIER DELINEATOR	22.000	EACH
51	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	262.000	SYS
52	610-07486 HMA FOR APPROACHES, TYPE A	283.500	TON
53	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
54	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
55	615-06505 MONUMENT, B	8.000	EACH
56	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
57	616-02320 GEOTEXTILES	988.000	SYS
58	616-05689 RIPRAP, CLASS 2	30.000	TON
59	616-06405 RIPRAP, REVETMENT	607.000	TON
60	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
61	621-02770 EROSION CONTROL BLANKET	245.000	SYS
62	621-03787 SEED MIXTURE, D	2.000	LBS
63	621-06545 FERTILIZER	7.000	TON
64	621-06553 SEED MIXTURE, R	2,380.000	LBS
65	621-06557 SEED MIXTURE, T	1,120.000	LBS
66	621-06557 SEED MIXTURE, T	12.000	LBS
67	621-06565 MULCHING MATERIAL	56.000	TON
68	621-06567 WATER	21.000	KGAL
69	621-06574 SODDING	7,412.000	SYS
70	621-92968 SEED MIXTURE, WILD FLOWER	0.500	LBS
71	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	102.000	EACH
72	622-05648 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	112.000	EACH
73	622-52436 SIGN, DO NOT MOW OR SPRAY	6.000	EACH
74	628-09402 FIELD OFFICE, B	17.000	MOS
75	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	17.000	MOS
76	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
77	701-06012 TEST PILE, RESTRIKE	2.000	EACH
78	701-06027 TEST PILE	2.000	EACH
79	701-08253 PILE SLEEVES	18.000	EACH
80	701-91792 PILE TIP, STEEL H	44.000	EACH
81	701-95780 PILE, STEEL H, HP 12" X 74	3,535.000	LFT
82	702-51005 CONCRETE, A, SUBSTRUCTURE	290.500	CYS
83	703-51030 REINFORCING STEEL	24,230.000	LBS
84	703-51032 REINFORCING STEEL, EPOXY COATED	231,827.000	LBS
85	704-51002 CONCRETE, C, SUPERSTRUCTURE	527.500	CYS
86	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
87	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN.	154.000	SYS
88	706-51020 CONCRETE, C, RAILING	81.700	CYS
89	707-09183 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	1,675.000	LFT
90	709-51821 SURFACE SEAL	LUMP	LUMP
91	714-08514 WINGWALL	152.000	SFT
92	714-26718 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 10 FT. X 6 FT.	85.000	LFT
93	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	300.000	LFT
94	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	300.000	LFT
95	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	300.000	LFT
96	715-05052 PIPE, TYPE 4, CIRCULAR, 12 IN.	300.000	LFT
97	715-05133 PIPE, TYPE 1, CIRCULAR, 60 IN.	160.000	LFT
98	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	50.000	LFT

CALL ORDER : 140

CONTRACT ID : IB-30838-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
99	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	400.000	LFT
100	715-05239 PIPE, TYPE 1, DEFORMED, MIN AREA 7.4 SQ. FT.	380.000	LFT
101	715-05372 PIPE, TYPE 3, DEFORMED, MIN. AREA 7.4 SFT.	66.000	LFT
102	715-05841 CONCRETE ANCHOR, 60 IN.	2.000	EACH
103	715-46005 PIPE END SECTION, 15 IN.	21.000	EACH
104	715-97804 PIPE END SECTION, MIN. AREA 7.4 SQ. FT.	8.000	EACH
105	720-45030 INLET, E7	1.000	EACH
106	731-93945 FACE PANELS, CONCRETE	7,400.000	SFT
107	731-93946 WALL ERECTION	7,400.000	SFT
108	731-93947 LEVELING PAD, CONCRETE	356.000	LFT
109	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
110	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
111	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
112	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
113	801-07119 BARRICADE, III-B	48.000	LFT
114	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	42.000	LFT
115	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	22.500	SFT
116	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	6,700.000	LFT
117	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	778.000	LFT
118	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6,868.000	LFT
119	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	11.000	LFT

CALL ORDER : 170

CONTRACT ID : IR-28976-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	5.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	120.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
6	109-08359 LIQUIDATED DAMAGES	1.000	DOL
7	109-08360 CONTRACT LIENS	1.000	DOL
8	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02240 PAVEMENT REMOVAL	138.000	m2
16	203-02000 EXCAVATION, COMMON	61,335.000	m3
17	205-03371 SEDIMENT REMOVE	650.250	m3
18	205-06930 SPLASHPAD, RIPRAP	29.280	Mg
19	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	629.700	Mg
20	205-06933 TEMPORARY DITCH INLET PROTECTION	28.000	EACH
21	205-06936 TEMPORARY SEDIMENT TRAP	467.800	Mg
22	205-06937 TEMPORARY SILT FENCE	10,153.000	m
23	205-06938 TEMPORARY SLOPE DRAIN	1,075.000	m
24	207-08263 SUBGRADE TREATMENT, TYPE IA	129,788.000	m2
25	211-06467 AGGREGATE FOR END BENT BACKFILL	61.000	m3
26	211-09264 STRUCTURE BACKFILL, TYPE 1	406.000	m3
27	211-09265 STRUCTURE BACKFILL, TYPE 2	179.400	m3
28	211-09268 STRUCTURE BACKFILL, TYPE 5	326.200	m3
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	14,171.000	Mg
30	302-07455 DENSE GRADED SUBBASE	343.000	m3
31	303-01180 COMPACTED AGGREGATE, NO. 53	12,732.000	Mg
32	306-08037 MILLING, ASPHALT, 75 mm	16,778.000	m2
33	401-06264 PROFIOGRAPH, HMA	LUMP	LUMP
34	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,292.000	Mg
35	401-07333 QC/QA-HMA, 2, 76, SURFACE, 9.5 mm	1,151.000	Mg
36	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	9,840.000	Mg
37	401-07402 QC/QA-HMA, 2, 76, INTERMEDIATE, 19.0 mm	1,923.000	Mg
38	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	16,523.000	Mg
39	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 MM	3,924.000	Mg
40	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	6,296.000	Mg
41	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	45,700.000	Mg
42	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	17,898.000	Mg
43	406-05521 ASPHALT FOR TACK COAT	533,256.000	m2
44	601-01522 GUARDRAIL TRANSITION TYPE TGB	24.000	EACH
45	601-05999 CURVED TERMINAL END	4.000	EACH
46	601-06035 GUARDRAIL, RESET	9.120	m
47	601-06238 IMPACT ATTENUATOR, R1, W1, TL-3	1.000	EACH
48	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	1.000	EACH
49	601-09149 IMPACT ATTENUATOR, CR1, W1, TL-3	3.000	EACH

CALL ORDER : 170

CONTRACT ID : IR-28976-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	601-94689 GUARDRAIL END TREATMENT, OS	10.000	EACH
51	601-94690 GUARDRAIL END TREATMENT, MS	10.000	EACH
52	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	1,328.236	m
53	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 1.905 m SPACING	1,030.605	m
54	602-06729 BARRIER DELINEATOR	240.000	EACH
55	602-08605 CONCRETE BARRIER, 840 mm	1,080.000	m
56	603-06040 FENCE, FARM FIELD, 1190 mm	772.000	m
57	603-06045 FENCE, CHAIN LINK, 1220 mm	56.000	m
58	606-07484 MILLED HMA SHOULDER CORRUGATIONS	23,796.000	m
59	607-06375 PAVED SIDE DITCH, J	332.300	m
60	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	2,359.000	m2
61	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
62	615-06490 RIGHT OF WAY MARKER	7.000	EACH
63	615-06505 MONUMENT, B	58.000	EACH
64	615-06510 MONUMENT, C	27.000	EACH
65	616-02320 GEOTEXTILES	3,491.300	m2
66	616-05688 RIPRAP, CLASS 1	25.100	Mg
67	616-05689 RIPRAP, CLASS 2	87.110	Mg
68	616-06405 RIPRAP, REVETMENT	1,703.300	Mg
69	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
70	621-06545 FERTILIZER	20.100	Mg
71	621-06553 SEED MIXTURE, R	2,818.000	kg
72	621-06557 SEED MIXTURE, T	1,223.000	kg
73	621-06565 MULCHING MATERIAL	100.200	Mg
74	621-06567 WATER	93.000	kL
75	621-06574 SODDING	5,137.000	m2
76	628-09403 FIELD OFFICE, C	24.000	MOS
77	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	24.000	MOS
78	702-93722 CONCRETE, C	40.000	m3
79	703-51032 REINFORCING STEEL, EPOXY COATED	61,501.000	kg
80	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	40.000	EACH
81	709-51821 SURFACE SEAL	LUMP	LUMP
82	714-08514 WINGWALL	13.750	m2
83	714-99348 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1500 mm x 900 mm	53.600	m
84	715-02397 SAFETY METAL END SECTION, 4:1, 900 mm	2.000	EACH
85	715-02407 SAFETY METAL END SECTION, 4:1, 1200 mm	2.000	EACH
86	715-03475 SAFETY METAL END SECTION, 4:1, 375 mm	4.000	EACH
87	715-03584 SAFETY METAL END SECTION, 4:1, 450 mm	2.000	EACH
88	715-05019 PIPE, TYPE 1, CIRCULAR, 900 mm	16.500	m
89	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	19,361.900	m
90	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	3,319.000	m
91	715-05123 PIPE, TYPE 1, CIRCULAR, 600 mm	20.500	m
92	715-05128 PIPE, TYPE 1, CIRCULAR, 1200 mm	21.600	m
93	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	223.500	m
94	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	52.400	m
95	715-05407 PIPE, END BENT DRAIN, 150 mm	100.000	m
96	715-08283 PCCP FOR STRUCTURE INSTALLATION	138.000	m2
97	715-08307 HMA FOR STRUCTURE INSTALLATION, TYPE D	51.000	Mg
98	718-06528 OUTLET PROTECTOR, 1	137.000	EACH

CALL ORDER : 170

CONTRACT ID : IR-28976-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
99	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	2,000.000	m
100	718-52610 AGGREGATE FOR UNDERDRAINS	3,814.000	m3
101	718-99153 GEOTEXTILES FOR UNDERDRAIN	35,820.000	m2
102	720-45041 INLET, H5	8.000	EACH
103	720-45065 INLET, N12	1.000	EACH
104	720-45069 INLET, P12	1.000	EACH
105	720-45070 INLET, P12A	1.000	EACH
106	720-45075 INLET, R13	2.000	EACH
107	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
108	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	6,544.000	m
109	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
110	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
111	802-04893 REFERENCE POST	11.000	EACH
112	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	115.900	m
113	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	42.700	m
114	802-07137 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	2.000	EACH
115	802-07138 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, IX	10.000	EACH
116	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	8.000	EACH
117	802-07153 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	2.000	EACH
118	802-07158 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, I	1.000	EACH
119	802-07271 BOX TRUSS SIGN FOUNDATION, V-A	4.000	EACH
120	802-09221 BOX TRUSS SIGN STRUCTURE, TYPE A	2.000	EACH
121	802-76015 SIGN,PANEL,ENCAPSULATED LENS WITH LEGEND	221.202	m2
122	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	4.650	m2
123	802-76030 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 2.54 mm THICKNESS	64.170	m2
124	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	1.620	m2
125	802-76095 STRUCTURAL STEEL, BREAKAWAY	2,167.260	kg
126	802-76140 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM	1.000	EACH
127	805-06592 CONDUIT, STEEL, GALVANIZED, 50 mm	332.000	m
128	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	810.000	m
129	805-98335 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C	1,772.000	m
130	805-98336 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	332.000	m
131	807-02191 HANDHOLE, LIGHTING	7.000	EACH
132	807-02193 LIGHT STANDARD FOUNDATION, 915 mm DIA. X 2450 mm	24.000	EACH
133	807-82440 LIGHT POLE, HIGH MAST, 40 m E.M.H.	5.000	EACH
134	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	24.000	EACH
135	807-86665 LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM	30.000	EACH
136	807-86810 SERVICE POINT, II	5.000	EACH
137	807-86910 CONNECTOR KIT, UNFUSED	29.000	EACH
138	807-86915 CONNECTOR KIT, FUSED	29.000	EACH
139	807-86920 MULTIPLE COMPRESSION FITTING, NOT WATERPROOFED	51.000	EACH
140	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.000	EACH
141	807-86930 INSULATION LINK, NONWATERPROOFED	58.000	EACH
142	807-86935 INSULATING LINK, WATERPROOFED	28.000	EACH
143	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	29.000	EACH
144	807-86955 CABLE DUCT MARKER	3.000	EACH
145	807-95709 PHOTOCELLS	10.000	EACH
146	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 125 mm	9,030.000	m
147	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	12,845.000	m

CALL ORDER : 170

CONTRACT ID : IR-28976-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
148 808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 200 mm	1,565.000	m
149 808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 600 mm	125.000	m
150 808-75215	LINE, THERMOPLASTIC, SOLID, WHITE, 300 mm	93.000	m
151 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	12,800.000	m
152 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	14.000	m
153 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	2.000	EACH
154 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH
155 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	836.000	EACH

CALL ORDER : 180

CONTRACT ID : IR-30115-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	20.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	4.000	EACH
15	203-02000 EXCAVATION, COMMON	16,956.340	CYS
16	203-02070 BORROW	52,182.010	CYS
17	205-03371 SEDIMENT, REMOVE	522.500	CYS
18	205-06930 SPLASHPAD, RIPRAP	11.400	TON
19	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	219.200	TON
20	205-06933 TEMPORARY DITCH INLET PROTECTION	10.000	EACH
21	205-06935 TEMPORARY SEDIMENT BASIN	1.000	EACH
22	205-06936 TEMPORARY SEDIMENT TRAP	126.500	TON
23	205-06937 TEMPORARY SILT FENCE	500.000	LFT
24	205-06938 TEMPORARY SLOPE DRAIN	137.000	LFT
25	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	210.100	CYS
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	14,950.590	SYS
27	211-02050 B BORROW	53.100	CYS
28	211-09264 STRUCTURE BACKFILL, TYPE 1	62.800	CYS
29	211-09265 STRUCTURE BACKFILL, TYPE 2	30.000	CYS
30	211-09266 STRUCTURE BACKFILL, TYPE 3	2,374.500	CYS
31	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	11.800	TON
32	302-07455 DENSE GRADED SUBBASE	26.900	CYS
33	302-08562 COARSE AGGREGATE, 8	19.000	TON
34	303-01180 COMPACTED AGGREGATE, NO. 53	665.130	TON
35	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	242.280	TON
36	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,050.140	TON
37	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,765.230	TON
38	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	5,910.960	TON
39	406-05520 ASPHALT FOR TACK COAT	10.030	TON
40	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
41	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
42	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	4.000	EACH
43	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	237.500	LFT
44	602-06729 BARRIER DELINEATOR	18.000	EACH
45	603-06060 FENCE, FARM FIELD, RESET	1,950.000	LFT
46	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	161.200	SYS
47	610-07487 HMA FOR APPROACHES, TYPE B	62.980	TON
48	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
49	615-06490 RIGHT OF WAY MARKER	39.000	EACH

CALL ORDER : 180

CONTRACT ID : IR-30115-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	615-06505 MONUMENT, B	15.000	EACH
51	615-06510 MONUMENT, C	4.000	EACH
52	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
53	616-02320 GEOTEXTILES	776.000	SYS
54	616-05688 RIPRAP, CLASS 1	14.800	TON
55	616-06405 RIPRAP, REVETMENT	566.500	TON
56	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
57	621-06545 FERTILIZER	3.290	TON
58	621-06553 SEED MIXTURE, R	1,079.680	LBS
59	621-06557 SEED MIXTURE, T	1,127.740	LBS
60	621-06565 MULCHING MATERIAL	27.740	TON
61	621-06567 WATER	19.000	KGAL
62	621-06570 TOP SOIL	6,064.730	CYS
63	621-06574 SODDING	1,039.000	SYS
64	621-06575 SODDING, NURSERY	4,726.000	SYS
65	628-09402 FIELD OFFICE, B	10.000	MOS
66	701-06011 DYNAMIC PILE LOAD TEST	3.000	EACH
67	701-06012 TEST PILE, RESTRIKE	3.000	EACH
68	701-06027 TEST PILE	3.000	EACH
69	701-51195 PILE, STEEL H, HP 12" X 53	2,681.000	LFT
70	702-51005 CONCRETE, A, SUBSTRUCTURE	118.000	CYS
71	702-51015 CONCRETE, B, FOOTINGS	29.000	CYS
72	703-06028 REINFORCING BARS	14,487.000	LBS
73	703-06029 REINFORCING BARS, EPOXY COATED	93,836.000	LBS
74	704-51002 CONCRETE, C, SUPERSTRUCTURE	257.600	CYS
75	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
76	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN.	32.000	SYS
77	706-51020 CONCRETE, C, RAILING	46.300	CYS
78	707-07605 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 54 IN. X 48 IN.	818.000	LFT
79	709-51821 SURFACE SEAL	LUMP	LUMP
80	714-94664 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3 FT. X 3 FT.	127.000	LFT
81	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	44.000	LFT
82	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	130.000	LFT
83	715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN.	216.000	LFT
84	715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN.	311.000	LFT
85	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	114.000	LFT
86	715-06004 CONCRETE ANCHOR, 48 IN.	4.000	EACH
87	715-46005 PIPE END SECTION, 15 IN.	8.000	EACH
88	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
89	715-46030 PIPE END SECTION, 30 IN.	4.000	EACH
90	731-93945 FACE PANELS, CONCRETE	3,510.000	SFT
91	731-93946 WALL ERECTION	3,510.000	SFT
92	731-93947 LEVELING PAD, CONCRETE	227.000	LFT
93	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
94	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
95	801-06625 DETOUR ROUTE MARKER ASSEMBLY	29.000	EACH
96	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
97	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
98	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 180

CONTRACT ID : IR-30115-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
99 801-07119	BARRICADE, III-B	192.000	LFT
100 802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	143.500	LFT
101 802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	62.500	SFT
102 802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	19.000	SFT
103 808-03631	LINE, EPOXY, SOLID, WHITE, 4 IN.	8,605.150	LFT
104 808-03632	LINE, EPOXY, SOLID, YELLOW, 4 IN.	13,823.000	LFT
105 808-04896	LINE, EPOXY, BROKEN, YELLOW, 4 IN.	100.000	LFT
106 808-06716	LINE, REMOVE	2,775.000	LFT
107 808-74805	TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	26.000	LFT

CALL ORDER : 190

CONTRACT ID : IR-30156-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6 202-02255	TREE, 18 IN., REMOVE	10.000	EACH
7 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
8 202-03729	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	15.000	LFT
9 205-06937	TEMPORARY SILT FENCE	500.000	LFT
10 621-06560	MULCHED SEEDING, U	2,300.000	SYS
11 801-03290	CONSTRUCTION SIGN, C	2.000	EACH
12 801-06640	CONSTRUCTION SIGN, A	2.000	EACH

CALL ORDER : 200

CONTRACT ID : IR-30160-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	6.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	6.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	216.000	MOS
5	105-08523 RADIO SERVICE	216.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
12	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
13	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
14	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
15	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
16	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
17	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
19	203-02000 EXCAVATION, COMMON	312,750.000	CYS
20	203-02070 BORROW	1,760,623.000	CYS
21	204-02290 SETTLEMENT PLATE	122.000	EACH
22	205-06930 SPLASHPAD, RIPRAP	62.400	TON
23	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,555.000	TON
24	205-06932 TEMPORARY CHECK DAM, STRAW BALES	648.000	LFT
25	205-06933 TEMPORARY DITCH INLET PROTECTION	15.000	EACH
26	205-06934 TEMPORARY MULCHING	230.400	TON
27	205-06936 TEMPORARY SEDIMENT TRAP	226.400	TON
28	205-06937 TEMPORARY SILT FENCE	1,720.000	LFT
29	205-06938 TEMPORARY SLOPE DRAIN	2,020.000	LFT
30	210-05873 TESTING	LUMP	LUMP
31	210-07314 FORCE MAIN	815.000	LFT
32	210-07314 FORCE MAIN	130.000	LFT
33	211-02050 B BORROW	26,506.000	CYS
34	211-04712 BACKFILL	4,900.000	CYS
35	211-06467 AGGREGATE FOR END BENT BACKFILL	225.000	CYS
36	211-07454 STRUCTURE BACKFILL	5,943.000	CYS
37	211-09264 STRUCTURE BACKFILL, TYPE 1	6,881.000	CYS
38	211-09266 STRUCTURE BACKFILL, TYPE 3	23,729.000	CYS
39	215-07043 CHEMICAL MODIFICATION, SOILS	215,687.000	SYS
40	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	27,429.000	TON
41	302-06464 SUBBASE FOR PCCP	29,441.000	CYS
42	302-07455 DENSE GRADED SUBBASE	353.000	CYS
43	302-08562 COARSE AGGREGATE, 8	367.000	TON
44	303-01180 COMPACTED AGGREGATE, NO. 53	31,287.000	TON
45	303-02051 STONE, NO 2	13.800	TON
46	303-04489 COMPACTED CRUSHED AGGREGATE, 8	346.000	TON
47	303-07449 COMPACTED AGGREGATE, NO. 73	56.000	TON
48	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
49	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	4,871.000	TON

CALL ORDER : 200

CONTRACT ID : IR-30160-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	9,937.000	TON
51	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	14,197.000	TON
52	402-07432 HMA SURFACE, TYPE A	2,505.000	TON
53	402-07433 HMA SURFACE, TYPE B	1,214.000	TON
54	402-07435 HMA INTERMEDIATE, TYPE A	1,637.000	TON
55	402-07438 HMA INTERMEDIATE, TYPE B	2,073.000	TON
56	402-07440 HMA BASE, TYPE A	67.000	TON
57	402-07441 HMA BASE, TYPE B	3,222.000	TON
58	406-05520 ASPHALT FOR TACK COAT	36.600	TON
59	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
60	501-08196 QC/QA-PCCP, 12.5 IN.	105,771.000	SYS
61	503-05240 D-1 CONTRACTION JOINT	63,461.000	LFT
62	503-05310 TERMINAL JOINT	544.000	LFT
63	601-01522 GUARDRAIL TRANSITION TYPE TGB	18.000	EACH
64	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
65	601-06416 IMPACT ATTENUATOR SPARE PARTS PACKAGE, ED, W1, TL-3	2.000	EACH
66	601-94689 GUARDRAIL END TREATMENT, OS	22.000	EACH
67	601-94690 GUARDRAIL END TREATMENT, MS	6.000	EACH
68	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	22.000	EACH
69	601-97803 GUARDRAIL END TREATMENT, MS, SPARE PARTS PACKAGE	6.000	EACH
70	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	7,156.250	LFT
71	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	1,362.500	LFT
72	602-06729 BARRIER DELINEATOR	52.000	EACH
73	603-06040 FENCE, FARM FIELD, 47 IN.	37,964.000	LFT
74	605-06095 CURB, INTEGRAL, B, CONCRETE	50.000	LFT
75	606-07484 MILLED HMA SHOULDER CORRUGATIONS	73,210.000	LFT
76	607-06370 PAVED SIDE DITCH, H	80.000	LFT
77	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	522.800	SYS
78	609-09231 REINFORCED CONCRETE BRIDGE APPROACH,	1,644.000	SYS
79	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
80	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
81	615-06490 RIGHT OF WAY MARKER	26.000	EACH
82	615-06505 MONUMENT, B	4.000	EACH
83	615-06510 MONUMENT, C	10.000	EACH
84	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
85	616-02320 GEOTEXTILES	3,195.000	SYS
86	616-06405 RIPRAP, REVETMENT	1,135.600	TON
87	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
88	621-06545 FERTILIZER	32.800	TON
89	621-06553 SEED MIXTURE, R	13,936.000	LBS
90	621-06557 SEED MIXTURE, T	13,816.000	LBS
91	621-06565 MULCHING MATERIAL	164.000	TON
92	621-06567 WATER	2,405.000	kgAL
93	621-06574 SODDING	48,106.500	SYS
94	621-06575 SODDING, NURSERY	2,210.000	SYS
95	621-96948 GATE VALVE, 8 IN.	2.000	EACH
96	628-09403 FIELD OFFICE, C	36.000	MOS
97	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	108.000	MOS
98	701-05569 CORED HOLE IN ROCK	88.000	LFT

CALL ORDER : 200

CONTRACT ID : IR-30160-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
99	701-06011 DYNAMIC PILE LOAD TEST	10.000	EACH
100	701-06012 TEST PILE, RESTRIKE	10.000	EACH
101	701-06027 TEST PILE	10.000	EACH
102	701-90386 TEMPORARY SHEET PILING	LUMP	LUMP
103	701-91792 PILE TIP, STEEL H	78.000	EACH
104	701-93575 PILE, STEEL H, HP 14" X 73	6,746.000	LFT
105	702-51005 CONCRETE, A, SUBSTRUCTURE	82.500	CYS
106	702-51015 CONCRETE, B, FOOTINGS	38.500	CYS
107	702-90915 CONCRETE, A	2.000	CYS
108	702-90915 CONCRETE, A	1.500	CYS
109	702-92857 CONCRETE, C, SUBSTRUCTURE	136.000	CYS
110	702-94656 CONCRETE, B	236.000	CYS
111	703-06028 REINFORCING BARS	31,085.000	LBS
112	703-06029 REINFORCING BARS, EPOXY COATED	376,648.000	LBS
113	703-51032 REINFORCING STEEL, EPOXY COATED	103,406.000	LBS
114	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,472.000	CYS
115	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
116	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	24.000	EACH
117	706-51020 CONCRETE, C, RAILING	107.160	CYS
118	706-51025 CONCRETE, C, RAILING	465.500	LFT
119	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 45 IN. X 16 IN.	772.000	LFT
120	707-07605 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 54 IN. X 48 IN.	1,625.000	LFT
121	707-08643 STRUCTURAL MEMBERS, CONCRETE BULB-T	1,130.000	LFT
122	709-51821 SURFACE SEAL	LUMP	LUMP
123	709-51821 SURFACE SEAL	LUMP	LUMP
124	709-51821 SURFACE SEAL	LUMP	LUMP
125	709-51821 SURFACE SEAL	LUMP	LUMP
126	709-51821 SURFACE SEAL	LUMP	LUMP
127	709-51821 SURFACE SEAL	LUMP	LUMP
128	711-51035 STRUCTURAL STEEL	1,485.000	LBS
129	711-95290 FIELD WELDING	51.000	LFT
130	715-01336 GATE VALVE, 12 IN.	2.000	EACH
131	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	1,206.000	LFT
132	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	72,954.000	LFT
133	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	18,856.000	LFT
134	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	516.000	LFT
135	715-05127 PIPE, TYPE 1, CURCULAR, 42 IN.	202.000	LFT
136	715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN.	202.000	LFT
137	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	495.000	LFT
138	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	1,231.000	LFT
139	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	55.000	LFT
140	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	208.000	LFT
141	715-05428 PIPE, SLOTTED VANE DRAIN, 12 IN.	14.000	LFT
142	715-05438 PIPE, DRAIN TILE TERMINAL SECTION, 4 IN.	3,047.000	LFT
143	715-05439 PIPE, DRAINTILE TERMINAL SECTION, 6 IN	9,141.000	LFT
144	715-05440 PIPE, DRAINTILE TERMINAL SECTION, 8 IN	3,047.000	LFT
145	715-05443 PIPE, DRAINTILE TERMINAL SECTION, 12 IN	12,188.000	LFT
146	715-05445 PIPE, DRAIN TILE, TERMINAL SECTION, 18 IN.	930.000	LFT
147	715-09552 ORIFICE PLATE	16.000	EACH

CALL ORDER : 200

CONTRACT ID : IR-30160-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
148	715-09554 PIPE, TYPE 1, DEFORMED, MIN. AREA 209.45 SQ. FT.	508.000	LFT
149	715-09555 PIPE, TYPE 1, DEFORMED, MIN. AREA 97.13 SQ. FT.	404.000	LFT
150	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
151	715-46005 PIPE END SECTION, 15 IN.	8.000	EACH
152	715-46040 PIPE END SECTION, 36 IN.	16.000	EACH
153	715-97405 GRATED BOX END SECTION, I, 4:1, 18 IN.	1.000	EACH
154	715-97406 GRATED BOX END SECTION, I, 3:1, 18 IN.	12.000	EACH
155	715-97408 GRATED BOX END SECTION, I, 3:1, 42 IN.	2.000	EACH
156	715-97557 GRATED BOX END SECTION, I, 6:1, 18 IN.	11.000	EACH
157	715-97559 GRATED BOX END SECTION, II, 10:1, 12 IN.	2.000	EACH
158	715-97695 GRATED BOX END SECTION, I, 3:1, 48 IN.	2.000	EACH
159	715-97755 GRATED BOX END SECTION, I, 3:1, 12 IN.	1.000	EACH
160	715-98769 GRATED BOX END SECTION, I, 4:1, 12 IN.	1.000	EACH
161	718-06531 OUTLET PROTECTOR, 3	101.000	EACH
162	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	6,500.000	LFT
163	718-52610 AGGREGATE FOR UNDERDRAINS	6,568.000	CYS
164	718-99153 GEOTEXTILES FOR UNDERDRAIN	50,012.000	SYS
165	719-09505 TILE INTERCEPT TRENCH EXCAVATION AND LOCATION	30,470.000	LFT
166	720-45235 CATCH BASIN, E7	1.000	EACH
167	720-96999 FIRE HYDRANT ASSEMBLY	1.000	EACH
168	731-93945 FACE PANELS, CONCRETE	43,707.000	SFT
169	731-93946 WALL ERECTION	43,707.000	SFT
170	731-93947 LEVELING PAD, CONCRETE	2,062.000	LFT
171	732-04837 PLUG	2.000	EACH
172	732-04837 PLUG	2.000	EACH
173	732-04964 WATER MAIN	125.000	LFT
174	732-04964 WATER MAIN	815.000	LFT
175	732-05538 TESTING AND DISINFECTION	LUMP	LUMP
176	801-04308 ROAD CLOSURE SIGN ASSEMBLY	16.000	EACH
177	801-06625 DETOUR ROUTE MARKER ASSEMBLY	25.000	EACH
178	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
179	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
180	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
181	801-07118 BARRICADE, III-A	192.000	LFT
182	801-07119 BARRICADE, III-B	192.000	LFT
183	802-01749 SIGN BRACKET, WALL MOUNTED	8.000	EACH
184	802-04893 REFERENCE POST	20.000	EACH
185	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	150.400	LFT
186	802-05703 SIGN POST, SQUARE, 3, REINFORCED ANCHOR BASE	70.400	LFT
187	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	8.000	EACH
188	802-76015 SIGN,PANEL,ENCAPSULATED LENS WITH LEGEND	108.000	SFT
189	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	37.500	SFT
190	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	83.500	SFT
191	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	54.000	SFT
192	802-76095 STRUCTURAL STEEL, BREAKAWAY	1,043.700	LBS
193	802-94674 BRIDGE BRACKET ASSEMBLY, CROSSROAD IDENTIFICATION	2.000	EACH
194	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	37,500.000	LFT
195	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	37,500.000	LFT
196	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	14,046.000	LFT

CALL ORDER : 200

CONTRACT ID : IR-30160-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
197 808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	13,874.000	LFT
198 808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	9,376.000	LFT
199 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	51.000	LFT
200 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	470.000	EACH

CALL ORDER : 210

CONTRACT ID : IR-30294-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	6.000	EACH
12	202-02240 PAVEMENT REMOVAL	84,056.000	SYS
13	202-02241 GUARDRAIL, REMOVE	70.000	LFT
14	202-02271 HEADWALL, REMOVE	1.000	EACH
15	202-02928 CATCH BASIN, REMOVE	5.000	EACH
16	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
19	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
20	202-04345 UNDERGROUND STORAGE TANK, LIQUID WASTE DISPOSAL, A	70,000.000	GAL
21	202-05545 REGULATED MATERIALS, DISPOSE, C	200.000	CYS
22	202-05550 REGULATED MATERIALS, REMOVE, C	200.000	CYS
23	202-05555 REGULATED MATERIALS, TRANSPORT, C	200.000	CYS
24	202-05825 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE,	3.000	EACH
25	202-05826 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE,	3.000	EACH
26	202-07603 TESTING FOR WASTE, C	32.000	EACH
27	202-09106 TESTING FOR CONTAMINATED MATERIALS, MTBE AND	20.000	EACH
28	202-52710 SIDEWALK, CONCRETE, REMOVE	156.000	SYS
29	202-74025 FENCE, REMOVE	257.000	LFT
30	202-74035 SIGN, REMOVE	2.000	EACH
31	202-91385 INLET, REMOVE	89.000	EACH
32	202-92222 TESTING FOR CONTAMINATED MATERIALS, TPH	60.000	EACH
33	202-93047 MANHOLE, REMOVE	16.000	EACH
34	202-93615 CONCRETE, REMOVE	862.000	SYS
35	202-98370 POLE, REMOVE	9.000	EACH
36	203-02000 EXCAVATION, COMMON	137,247.000	CYS
37	203-02070 BORROW	20,857.000	CYS
38	205-06933 TEMPORARY DITCH INLET PROTECTION	44.000	EACH
39	205-06937 TEMPORARY SILT FENCE	6,955.000	LFT
40	207-08267 SUBGRADE TREATMENT, TYPE IIIA	39,595.000	SYS
41	207-08268 SUBGRADE TREATMENT, TYPE IV	227,586.000	SYS
42	211-09264 STRUCTURE BACKFILL, TYPE 1	58,845.000	CYS
43	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	14,617.000	TON
44	303-07449 COMPACTED AGGREGATE, NO. 73	287.000	TON
45	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	300.000	TON
46	306-08033 MILLING, ASPHALT, 1 IN.	11,214.000	SYS
47	306-08034 MILLING, ASPHALT, 1 1/2 IN.	14,688.000	SYS
48	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	18,489.000	TON
49	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	29,454.000	TON

CALL ORDER : 210

CONTRACT ID : IR-30294-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
50 401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	14,492.000	TON
51 401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	59,686.000	TON
52 401-07429	QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	27,607.000	TON
53 402-07432	HMA SURFACE, TYPE A	139.000	TON
54 402-07435	HMA INTERMEDIATE, TYPE A	231.000	TON
55 402-07453	HMA FOR TEMPORARY PAVEMENT	4,045.000	TON
56 402-07784	HMA SURFACE, TYPE D	139.000	TON
57 402-07785	HMA INTERMEDIATE, TYPE D	231.000	TON
58 406-05520	ASPHALT FOR TACK COAT	200.000	TON
59 601-05585	GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 8	1.000	EACH
60 601-99105	GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	82.000	LFT
61 604-06070	SIDEWALK, CONCRETE	19,991.100	SYS
62 604-07894	CURB RAMP, CONCRETE, A	90.600	SYS
63 604-07897	CURB RAMP, CONCRETE, C	13.500	SYS
64 604-07901	CURB RAMP, CONCRETE, G	762.800	SYS
65 604-07902	CURB RAMP, CONCRETE, H	11.000	SYS
66 605-02493	CURB ISLAND, CONCRETE	16,839.000	SYS
67 605-06120	CURB, CONCRETE	1,362.000	LFT
68 605-06140	CURB AND GUTTER, CONCRETE	33,173.000	LFT
69 605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	31,520.000	LFT
70 605-06160	CURB AND GUTTER, B, CONCRETE, MODIFIED	125.000	LFT
71 605-06235	CENTER CURB, D, CONCRETE, MODIFIED	268.000	LFT
72 605-97937	CURB AND GUTTER, CONCRETE, ROLL	851.000	LFT
73 610-07487	HMA FOR APPROACHES, TYPE B	1,020.000	TON
74 610-08446	PCCP FOR APPROACHES, 6 IN.	3,192.000	SYS
75 610-09108	PCCP FOR APPROACHES, 9 IN.	6,218.000	SYS
76 611-06497	MAILBOX ASSEMBLY, SINGLE	68.000	EACH
77 611-06498	MAILBOX ASSEMBLY, DOUBLE	27.000	EACH
78 615-06490	RIGHT OF WAY MARKER	111.000	EACH
79 615-06495	RIGHT OF WAY MARKER, RESET	78.000	EACH
80 615-06505	MONUMENT, B	30.000	EACH
81 615-06505	MONUMENT, B	2.000	EACH
82 615-06515	MONUMENT, D	2.000	EACH
83 615-06527	MONUMENT, SECTION CORNER	4.000	EACH
84 616-02320	GEOTEXTILES	334.000	SYS
85 616-05688	RIPRAP, CLASS 1	250.000	TON
86 616-06405	RIPRAP, REVETMENT	125.000	TON
87 621-06545	FERTILIZER	0.670	TON
88 621-06557	SEED MIXTURE, T	536.000	LBS
89 621-06559	MULCHED SEEDING, R	5,550.000	SYS
90 621-06560	MULCHED SEEDING, U	4,546.000	SYS
91 621-06575	SODDING, NURSERY	64,864.000	SYS
92 621-98503	MULCH MATERIAL	13.400	TON
93 628-09402	FIELD OFFICE, B	24.000	MOS
94 628-09407	FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	24.000	MOS
95 703-51030	REINFORCING STEEL	3,210.000	LBS
96 714-26712	CULVERT, PRECAST BOX, REINFORCED CONCRETE, 8 FT. X 6 FT.	329.000	LFT
97 714-26718	CULVERT, PRECAST BOX, REINFORCED CONCRETE, 10 FT. X 6 FT.	170.000	LFT
98 714-44240	CONCRETE, A, STRUCTURES	38.000	CYS

CALL ORDER : 210

CONTRACT ID : IR-30294-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
99	715-04611 SAFETY METAL END SECTION, 4:1, 12 IN.	1.000	EACH
100	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	6,996.000	LFT
101	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	59,015.000	LFT
102	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	100.000	LFT
103	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	100.000	LFT
104	715-05052 PIPE, TYPE 4, CIRCULAR, 12 IN.	100.000	LFT
105	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	227.000	LFT
106	715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN.	34.000	LFT
107	715-05147 PIPE, TYPE 2, CIRCULAR, 8 IN.	100.000	LFT
108	715-05148 PIPE, TYPE 2, CIRCULAR, 10 IN.	18.000	LFT
109	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	11,849.000	LFT
110	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	5,617.000	LFT
111	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	4,775.000	LFT
112	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	4,376.000	LFT
113	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	5,698.000	LFT
114	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN.	2,702.000	LFT
115	715-05165 PIPE, TYPE 2, CIRCULAR, 72 IN.	212.000	LFT
116	715-06923 PIPE, TYPE 2, CIRCULAR, 84 IN.	208.000	LFT
117	715-09064 VIDEO INSPECTION FOR PIPE	42,038.000	LFT
118	715-46000 PIPE END SECTION, 12 IN.	1.000	EACH
119	715-46005 PIPE END SECTION, 15 IN.	6.000	EACH
120	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	20,000.000	LFT
121	718-52610 AGGREGATE FOR UNDERDRAINS	5,301.100	CYS
122	720-08239 MANHOLE, J7, MODIFIED	1.000	EACH
123	720-44000 CASTING, ADJUST TO GRADE	37.000	EACH
124	720-45005 INLET, A2	2.000	EACH
125	720-45030 INLET, E7	1.000	EACH
126	720-45035 INLET, F7	8.000	EACH
127	720-45045 INLET, J10	113.000	EACH
128	720-45055 INLET, M10	17.000	EACH
129	720-45075 INLET, R13	1.000	EACH
130	720-45141 INLET, H5, MODIFIED	9.000	EACH
131	720-45270 PIPE CATCH BASIN, 18 IN.	23.000	EACH
132	720-45275 PIPE CATCH BASIN, 24 IN.	9.000	EACH
133	720-45410 MANHOLE, C4	88.000	EACH
134	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	14.600	LFT
135	720-91110 MANHOLE, N4	3.000	EACH
136	720-93501 MANHOLE, L4	2.000	EACH
137	720-94612 MANHOLE, K4	13.000	EACH
138	720-95409 MANHOLE, J4, MODIFIED	1.000	EACH
139	720-95422 MANHOLE, J4	64.000	EACH
140	720-98174 INLET, B15	95.000	EACH
141	720-98555 INLET, C15	28.000	EACH
142	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
143	801-04308 ROAD CLOSURE SIGN ASSEMBLY	37.000	EACH
144	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	87,750.000	LFT
145	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	77.000	EACH
146	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (ONLY)	72.000	EACH
147	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	2,024.000	LFT

CALL ORDER : 210

CONTRACT ID : IR-30294-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
148	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	20,907.000	LFT
149	801-06640 CONSTRUCTION SIGN, A	197.000	EACH
150	801-06645 CONSTRUCTION SIGN, B	59.000	EACH
151	801-06710 FLASHING ARROW SIGN	1,440.000	DAY
152	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
153	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	4.000	EACH
154	801-07119 BARRICADE, III-B	2,688.000	LFT
155	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	1,300.000	LFT
156	801-94295 SIGNAL HEAD, RELOCATE	177.000	EACH
157	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	2,321.000	LFT
158	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	437.000	SFT
159	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	1,623.000	SFT
160	805-01579 MISCELLANEOUS EQUIPMENT FOR SYSTEM LOOP AND INTERCONNECT	LUMP	LUMP
161	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	24.000	EACH
162	805-01842 HANDHOLE, SIGNAL	74.000	EACH
163	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
164	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	20.000	EACH
165	805-02328 SIGNAL CABLE, 1C 14GA.	470.000	LFT
166	805-02658 CABLE, COAXIAL	360.000	LFT
167	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	11,062.000	LFT
168	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	6.000	EACH
169	805-08466 RADIO ANTENNA, 9db, YAGI	6.000	EACH
170	805-08493 RADIO SYSTEM TESTING INTERCONNECT	LUMP	LUMP
171	805-08494 RADIO SPREAD SPECTRUM	6.000	EACH
172	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	64.000	EACH
173	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	30.000	EACH
174	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	1.000	EACH
175	805-78370 PEDESTRIAN PUSH BUTTON	20.000	EACH
176	805-78415 SPAN, CATENARY, AND TETHER	24.000	EACH
177	805-78420 DISCONNECT HANGER	24.000	EACH
178	805-78445 SIGNAL SERVICE	6.000	EACH
179	805-78467 SIGNAL CABLE, 3C 8GA.	374.000	LFT
180	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	29,652.000	LFT
181	805-78480 SIGNAL CABLE, 3C 14GA.	5,873.000	LFT
182	805-78485 SIGNAL CABLE, 5C 14GA.	12,864.000	LFT
183	805-78490 SIGNAL CABLE, 7C 14GA.	4,698.000	LFT
184	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	50,909.000	LFT
185	805-78785 SIGNAL DETECTOR HOUSING	58.000	EACH
186	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	7,045.000	LFT
187	805-78925 CONTROLLER CABINET FOUNDATION, P1	6.000	EACH
188	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	24.000	EACH
189	805-90193 SIGNAL CABLE, INTERCONNECT, 50C/22	470.000	LFT
190	805-90458 SIGNAL HEAD BACK PLATES FOR 3-SECTION 12 IN.	94.000	EACH
191	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	56.000	EACH
192	805-92512 MICROLOOP DETECTOR	48.000	EACH
193	805-96014 SAW CUT, FULL DEPTH	4,892.000	LFT
194	808-01045 LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN., 2 FT. LINE,	496.000	LFT
195	808-06694 LINE, PAINT, SOLID, YELLOW, 8 IN.	13,875.000	LFT
196	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	15,970.000	LFT

CALL ORDER : 210

CONTRACT ID : IR-30294-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
197	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	50,775.000	LFT
198	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	1,130.000	LFT
199	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	42,478.000	LFT
200	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	19,122.000	LFT
201	808-06716 LINE, REMOVE	51,724.000	LFT
202	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	50.000	EACH
203	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	51.000	EACH
204	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	824.000	LFT
205	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	570.000	LFT
206	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	15,179.000	LFT
207	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	1,037.000	LFT
208	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	2,346.000	LFT
209	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	6,877.000	LFT
210	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	133.000	EACH
211	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	133.000	EACH
212	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	800.000	EACH
213	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,408.000	EACH
214	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	4,351.000	LFT
215	808-98796 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN., 2 FT. LINE, 4 FT.	582.000	LFT

CALL ORDER : 220

CONTRACT ID : IR-30304-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENVIRONMENTAL MITIGATION		
1 105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
2 109-08359	LIQUIDATED DAMAGES	1.000	DOL
3 109-08360	CONTRACT LIENS	1.000	DOL
4 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5 203-02000	EXCAVATION, COMMON	12,171.000	CYS
6 203-02000	EXCAVATION, COMMON	14,591.000	CYS
7 205-06932	TEMPORARY CHECK DAM, STRAW BALES	72.000	LFT
8 205-06934	TEMPORARY MULCHING	219.800	TON
9 205-06937	TEMPORARY SILT FENCE	1,853.000	LFT
10 303-02051	STONE, NO 2	100.000	TON
11 616-06405	RIPRAP, REVETMENT	317.000	TON
12 621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
13 621-02770	EROSION CONTROL BLANKET	48,884.000	SYS
14 621-04258	SEED MIXTURE	606.000	LBS
15 621-04258	SEED MIXTURE	185.000	LBS
16 621-04258	SEED MIXTURE	192.000	LBS
17 621-04258	SEED MIXTURE	9,962.000	LBS
18 621-06545	FERTILIZER	49.600	TON
19 621-06557	SEED MIXTURE, T	13,200.000	LBS
20 621-06565	MULCHING MATERIAL	482.200	TON
21 622-05654	PLANT, PERENNIAL	1,210.000	EACH
22 622-52436	SIGN, DO NOT MOW OR SPRAY	13.000	EACH
23 622-91786	SEEDLING	79,266.000	EACH
24 622-91786	SEEDLING	7,596.000	EACH
25 622-91786	SEEDLING	25,048.000	EACH
26 802-04314	SIGN	2.000	EACH
27 804-06770	DELINEATOR POST	349.000	EACH
28 805-08093	POLE	2.000	EACH

CALL ORDER : 230

CONTRACT ID : IR-30351-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENVIRONMENTAL MITIGATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	40.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-90788 DEBRIS, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	5,768.000	CYS
11	203-02000 EXCAVATION, COMMON	6,327.000	CYS
12	205-06934 TEMPORARY MULCHING	184.300	TON
13	205-06937 TEMPORARY SILT FENCE	5,183.000	LFT
14	303-02051 STONE, NO 2	200.000	TON
15	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
16	621-02770 EROSION CONTROL BLANKET	20,330.000	SYS
17	621-04258 SEED MIXTURE	120.000	LBS
18	621-04258 SEED MIXTURE	1,248.000	LBS
19	621-04258 SEED MIXTURE	80.000	LBS
20	621-04258 SEED MIXTURE	67.000	LBS
21	621-04258 SEED MIXTURE	35.300	LBS
22	621-04258 SEED MIXTURE	48.000	LBS
23	621-04258 SEED MIXTURE	55.000	LBS
24	621-04258 SEED MIXTURE	2,820.000	LBS
25	621-04258 SEED MIXTURE	4,658.000	LBS
26	621-06545 FERTILIZER	22.380	TON
27	621-06545 FERTILIZER	19.620	TON
28	621-06557 SEED MIXTURE, T	11,045.000	LBS
29	621-06565 MULCHING MATERIAL	220.000	TON
30	621-06565 MULCHING MATERIAL	192.800	TON
31	622-91786 SEEDLING	41,415.000	EACH
32	622-91786 SEEDLING	37,550.000	EACH
33	622-91786 SEEDLING	2,494.000	EACH
34	622-91786 SEEDLING	1,580.000	EACH
35	628-09401 FIELD OFFICE, A	20.000	MOS
36	802-04314 SIGN	4.000	EACH
37	804-06770 DELINEATOR POST	272.000	EACH
38	805-08093 POLE	3.000	EACH

CALL ORDER : 240

CONTRACT ID : IR-30354-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENVIRONMENTAL MITIGATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-90788 DEBRIS, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	66.000	CYS
11	203-02000 EXCAVATION, COMMON	1,970.000	CYS
12	205-06934 TEMPORARY MULCHING	10.600	TON
13	205-06937 TEMPORARY SILT FENCE	1,350.000	LFT
14	205-09543 NO 2 STONE	100.000	TON
15	603-04244 GATE	3.000	EACH
16	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
17	621-02770 EROSION CONTROL BLANKET	1,080.000	SYS
18	621-04258 SEED MIXTURE	13.900	LBS
19	621-04258 SEED MIXTURE	518.800	LBS
20	621-04258 SEED MIXTURE	12.700	LBS
21	621-06545 FERTILIZER	2.410	TON
22	621-06557 SEED MIXTURE, T	635.000	LBS
23	621-06565 MULCHING MATERIAL	24.100	TON
24	622-52436 SIGN, DO NOT MOW OR SPRAY	13.000	EACH
25	622-91786 SEEDLING	6,335.000	EACH
26	628-09401 FIELD OFFICE, A	12.000	MOS
27	715-05177 PIPE, TYPE 3, CIRCULAR, 36 IN.	24.000	LFT
28	805-08093 POLE	1.000	EACH

CALL ORDER : 260

CONTRACT ID : IR-30412-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	7.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02637 PIPE, ABANDON AND GROUT FILL	107.000	LFT
14	202-93995 SIGNAL POLE FOUNDATION, REMOVE	2.000	EACH
15	202-93999 SIGNAL POLE, REMOVE	2.000	EACH
16	202-96133 PIPE, REMOVE	239.000	LFT
17	203-02000 EXCAVATION, COMMON	4,980.000	CYS
18	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	351.000	TON
19	205-06937 TEMPORARY SILT FENCE	510.000	LFT
20	205-09543 NO 2 STONE	100.000	TON
21	207-08263 SUBGRADE TREATMENT, TYPE IA	7,091.000	SYS
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,485.000	SYS
23	211-09264 STRUCTURE BACKFILL, TYPE 1	177.000	CYS
24	214-07202 GEOGRID, I	2,258.000	SYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,290.000	TON
26	303-01180 COMPACTED AGGREGATE, NO. 53	1,444.000	TON
27	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	462.000	TON
28	303-93506 AGGREGATE, 2	90.000	CYS
29	304-07491 HMA PATCHING, TYPE C	80.000	TON
30	306-08038 MILLING, ASPHALT, 4 IN.	9,265.000	SYS
31	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
32	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	292.000	TON
33	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	980.000	TON
34	401-07379 QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	1,635.000	TON
35	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	875.000	TON
36	402-07433 HMA SURFACE, TYPE B	75.000	TON
37	402-07438 HMA INTERMEDIATE, TYPE B	143.000	TON
38	402-07441 HMA BASE, TYPE B	171.000	TON
39	402-07442 HMA BASE, TYPE C	1,430.000	TON
40	406-05520 ASPHALT FOR TACK COAT	7.500	TON
41	606-07484 MILLED HMA SHOULDER CORRUGATIONS	2,236.000	LFT
42	610-09108 PCCP FOR APPROACHES, 9 IN.	593.000	SYS
43	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
44	611-06498 MAILBOX ASSEMBLY, DOUBLE	3.000	EACH
45	615-06490 RIGHT OF WAY MARKER	31.000	EACH
46	615-06505 MONUMENT, B	5.000	EACH
47	616-02320 GEOTEXTILES	1,164.000	SYS
48	616-05688 RIPRAP, CLASS 1	165.000	TON
49	616-06405 RIPRAP, REVETMENT	569.000	TON

CALL ORDER : 260

CONTRACT ID : IR-30412-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT WITH ADDED TURN LANES		
50	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
51	621-06545 FERTILIZER	1,815.000	TON
52	621-06553 SEED MIXTURE, R	386.000	LBS
53	621-06557 SEED MIXTURE, T	182.000	LBS
54	621-06565 MULCHING MATERIAL	4.500	TON
55	621-06567 WATER	396.000	KGAL
56	621-06574 SODDING	1,470.000	SYS
57	621-06575 SODDING, NURSERY	2,257.000	SYS
58	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	7.000	MOS
59	628-09409 MOBILE INTERNET SERVICE	7.000	MOS
60	715-04694 PIPE END SECTION, MIN AREA 6.5 SF	2.000	EACH
61	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	196.000	LFT
62	715-05237 PIPE, TYPE 1, DEFORMED, MIN. AREA 6.4 SQ. FT.	107.000	LFT
63	715-05365 PIPE, TYPE 3, DEFORMED, MIN AREA 2.9 SF	46.000	LFT
64	715-08162 PIPE, TYPE 1, DEFORMED, MIN. AREA 8.8 SFT.	89.000	LFT
65	715-08163 PIPE END SECTION, MIN. AREA 8.8 SFT.	2.000	EACH
66	715-46005 PIPE END SECTION, 15 IN.	16.000	EACH
67	715-46065 PIPE END SECTION, MIN. AREA 2.9 SQ. FT.	4.000	EACH
68	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
69	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
70	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	13,690.000	LFT
71	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
72	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
73	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
74	801-07119 BARRICADE, III-B	48.000	LFT
75	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN.	75.000	LFT
76	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	85.000	LFT
77	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	245.000	LFT
78	802-76020 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.080 IN. THICKNESS	188.000	SFT
79	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	32.000	SFT
80	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	2.000	EACH
81	805-01842 HANDHOLE, SIGNAL	10.000	EACH
82	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	215.000	LFT
83	805-02328 SIGNAL CABLE, 1C 14GA.	3,906.000	LFT
84	805-03793 DETECTOR CARD RACK AND DETECTOR MODULES	2.000	EACH
85	805-08487 TRAFFIC SIGNAL BACKPLATE	8.000	EACH
86	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	4.000	EACH
87	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	4.000	EACH
88	805-78415 SPAN, CATENARY, AND TETHER	6.000	EACH
89	805-78420 DISCONNECT HANGER	4.000	EACH
90	805-78485 SIGNAL CABLE, 5C 14GA.	223.000	LFT
91	805-78490 SIGNAL CABLE, 7C 14GA.	922.000	LFT
92	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	5,912.000	LFT
93	805-78785 SIGNAL DETECTOR HOUSING	13.000	EACH
94	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,640.000	LFT
95	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	2.000	EACH
96	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,210.000	LFT
97	808-06716 LINE, REMOVE	11,520.000	LFT
98	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,150.000	LFT

CALL ORDER : 260

CONTRACT ID : IR-30412-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT WITH ADDED TURN LANES		
99 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	160.000	LFT
100 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	9.000	EACH
101 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	6.000	EACH
102 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	58.000	EACH
103 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	73.000	EACH

CALL ORDER : 270

CONTRACT ID : IR-30437-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	914.000	CYS
11	203-02070 BORROW	9,335.000	CYS
12	203-51223 EXCAVATION, WATERWAY	96.300	CYS
13	205-02770 EROSION CONTROL BLANKET	257.000	SYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	16.000	TON
15	205-06932 TEMPORARY CHECK DAM, STRAW BALES	48.000	LFT
16	205-06937 TEMPORARY SILT FENCE	618.000	LFT
17	205-09543 NO 2 STONE	100.000	TON
18	206-51220 EXCAVATION, WET	501.000	CYS
19	207-08262 SUBGRADE TREATMENT, TYPE I	2,682.000	SYS
20	210-06750 INSTALL	LUMP	LUMP
21	211-09265 STRUCTURE BACKFILL, TYPE 2	1,096.200	CYS
22	211-09268 STRUCTURE BACKFILL, TYPE 5	94.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,330.000	TON
24	303-07449 COMPACTED AGGREGATE, NO. 73	51.000	TON
25	402-07432 HMA SURFACE, TYPE A	240.600	TON
26	402-07435 HMA INTERMEDIATE, TYPE A	369.000	TON
27	406-05520 ASPHALT FOR TACK COAT	0.600	TON
28	601-04793 GUARDRAIL	162.500	LFT
29	601-06053 GUARDRAIL	4.000	EACH
30	605-06120 CURB, CONCRETE	368.000	LFT
31	610-07486 HMA FOR APPROACHES, TYPE A	12.000	TON
32	615-06490 RIGHT OF WAY MARKER	21.000	EACH
33	615-06510 MONUMENT, C	1.000	EACH
34	615-06515 MONUMENT, D	6.000	EACH
35	616-02320 GEOTEXTILES	759.000	SYS
36	616-05688 RIPRAP, CLASS 1	660.000	TON
37	616-06405 RIPRAP, REVETMENT	28.000	TON
38	621-06560 MULCHED SEEDING, U	3,882.000	SYS
39	621-06567 WATER	15.000	KGAL
40	621-06574 SODDING	753.000	SYS
41	628-09401 FIELD OFFICE, A	6.000	MOS
42	702-51005 CONCRETE, A, SUBSTRUCTURE	102.100	CYS
43	702-51015 CONCRETE, B, FOOTINGS	109.600	CYS
44	703-51030 REINFORCING STEEL	23,901.000	LBS
45	709-51821 SURFACE SEAL	LUMP	LUMP
46	712-08257 PREFABRICATED	LUMP	LUMP
47	714-07773 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 10 FT. X 3 FT.	48.000	LFT
48	714-08514 WINGWALL	144.000	SFT
49	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	116.000	LFT

CALL ORDER : 270

CONTRACT ID : IR-30437-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	715-05407 PIPE, END BENT DRAIN, 6 IN.	176.000	LFT
51	715-46005 PIPE END SECTION, 15 IN.	4.000	EACH
52	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
53	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,508.000	LFT
54	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
55	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
56	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	29.500	LFT
57	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	16.300	SFT
58	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,253.000	LFT
59	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,527.000	LFT
60	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	1,387.000	LFT
61	808-06716 LINE, REMOVE	1,254.000	LFT
62	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	2.000	EACH
63	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	2.000	EACH
64	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	30.000	LFT
65	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,254.000	LFT

CALL ORDER : 330

CONTRACT ID : R -29095-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	45.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
15	202-02240 PAVEMENT REMOVAL	16.000	SYS
16	202-02241 GUARDRAIL, REMOVE	332.000	LFT
17	202-02274 CURB, CONCRETE, INTEGRAL, REMOVE	845.000	LFT
18	202-86946 HANDHOLE, REMOVE	8.000	EACH
19	202-90277 DETECTOR HOUSING, REMOVE	10.000	EACH
20	203-02000 EXCAVATION, COMMON	5,340.000	CYS
21	205-03371 SEDIMENT, REMOVE	156.000	CYS
22	205-06932 TEMPORARY CHECK DAM, STRAW BALES	541.000	LFT
23	205-06933 TEMPORARY DITCH INLET PROTECTION	17.000	EACH
24	205-06937 TEMPORARY SILT FENCE	880.000	LFT
25	205-09543 NO 2 STONE	100.000	TON
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,564.000	SYS
27	207-08268 SUBGRADE TREATMENT, TYPE IV	12,476.000	SYS
28	211-09264 STRUCTURE BACKFILL, TYPE 1	2,123.000	CYS
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,981.000	TON
30	306-08033 MILLING, ASPHALT, 1 IN.	6,581.000	SYS
31	306-08034 MILLING, ASPHALT, 1 1/2 IN.	7,799.000	SYS
32	306-08036 MILLING, ASPHALT, 2 IN.	2,555.000	SYS
33	306-08043 MILLING, TRANSITION	2,009.000	SYS
34	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	2,170.000	TON
35	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	3,608.000	TON
36	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	1,116.000	TON
37	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	3,066.000	TON
38	402-07432 HMA SURFACE, TYPE A	372.000	TON
39	406-05520 ASPHALT FOR TACK COAT	11.000	TON
40	605-06145 CURB AND GUTTER, B, CONCRETE	595.000	LFT
41	610-07487 HMA FOR APPROACHES, TYPE B	1,400.000	TON
42	610-09108 PCCP FOR APPROACHES, 9 IN.	364.000	SYS
43	611-02825 MAILBOX ASSEMBLY, TRIPLE	1.000	EACH
44	611-06497 MAILBOX ASSEMBLY, SINGLE	6.000	EACH
45	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
46	615-06490 RIGHT OF WAY MARKER	43.000	EACH
47	615-06500 MONUMENT, A	5.000	EACH
48	616-02320 GEOTEXTILES	79.000	SYS
49	616-06405 RIPRAP, REVETMENT	45.000	TON

CALL ORDER : 330

CONTRACT ID : R -29095-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
50	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
51	621-06545 FERTILIZER	0.200	TON
52	621-06557 SEED MIXTURE, T	110.000	LBS
53	621-06560 MULCHED SEEDING, U	1,068.000	SYS
54	621-06565 MULCHING MATERIAL	3.000	TON
55	621-06567 WATER	44.000	KGAL
56	621-06575 SODDING, NURSERY	12,256.000	SYS
57	628-09402 FIELD OFFICE, B	15.000	MOS
58	702-90915 CONCRETE, A	3.000	CYS
59	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN.	1.000	EACH
60	715-03476 SAFETY METAL END SECTION, 4:1, 24 IN.	2.000	EACH
61	715-04612 PIPE	185.000	LFT
62	715-04612 PIPE	85.000	LFT
63	715-04612 PIPE	117.000	LFT
64	715-04612 PIPE	242.000	LFT
65	715-04612 PIPE	142.000	LFT
66	715-04612 PIPE	137.000	LFT
67	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	30.000	LFT
68	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	109.000	LFT
69	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	137.000	LFT
70	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	355.000	LFT
71	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	338.000	LFT
72	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	333.000	LFT
73	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN.	6.000	LFT
74	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	70.000	LFT
75	715-05423 PIPE SLOTTED DRAIN, 15 IN.	80.000	LFT
76	715-08283 PCCP FOR STRUCTURE INSTALLATION	235.000	SYS
77	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	63.000	TON
78	715-46005 PIPE END SECTION, 15 IN.	10.000	EACH
79	715-46010 PIPE END SECTION, 18 IN.	2.000	EACH
80	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
81	715-99384 PIPE, REINFORCED CONCRETE, 15 IN.	114.000	LFT
82	720-03194 MANHOLE	2.000	EACH
83	720-04682 INLET,	1.000	EACH
84	720-04682 INLET,	1.000	EACH
85	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
86	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	3.000	EACH
87	720-45030 INLET, E7	2.000	EACH
88	720-45075 INLET, R13	1.000	EACH
89	720-45130 INLET, E7, MODIFIED	1.000	EACH
90	720-45140 INLET, G7, MODIFIED	3.000	EACH
91	720-45235 CATCH BASIN, E7	3.000	EACH
92	720-45275 PIPE CATCH BASIN, 24 IN.	2.000	EACH
93	720-45410 MANHOLE, C4	2.000	EACH
94	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	5.000	LFT
95	720-91973 MANHOLE, H4	1.000	EACH
96	720-93409 INLET, B15, MODIFIED	2.000	EACH
97	720-93411 INLET, C15, MODIFIED	2.000	EACH
98	720-94208 MANHOLE, C10	1.000	EACH

CALL ORDER : 330

CONTRACT ID : R -29095-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
99 720-94612	MANHOLE, K4	1.000	EACH
100 801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	16.000	EACH
101 801-01505	TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (ONLY)	7.000	EACH
102 801-01506	TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (RXR)	2.000	EACH
103 801-02595	CONTROLLER, RESET TIMING	2.000	EACH
104 801-03290	CONSTRUCTION SIGN, C	4.000	EACH
105 801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.000	EACH
106 801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	14,203.000	LFT
107 801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12,856.000	LFT
108 801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	10.000	EACH
109 801-06212	TEMPORARY PAVEMENT MESSAGE MARKING, WORD (ONLY)	5.000	EACH
110 801-06213	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (RXR)	2.000	EACH
111 801-06218	TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	197.000	LFT
112 801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	1,561.000	LFT
113 801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	LUMP	LUMP
114 801-06586	TEMPORARY PAVEMENT MARKING, 8 IN.	1,131.000	LFT
115 801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.000	EACH
116 801-06640	CONSTRUCTION SIGN, A	62.000	EACH
117 801-06645	CONSTRUCTION SIGN, B	18.000	EACH
118 801-06710	FLASHING ARROW SIGN	150.000	DAY
119 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
120 801-07118	BARRICADE, III-A	192.000	LFT
121 801-07119	BARRICADE, III-B	156.000	LFT
122 801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	275.000	LFT
123 801-94295	SIGNAL HEAD, RELOCATE	18.000	EACH
124 802-04893	REFERENCE POST	2.000	EACH
125 802-05704	SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	25.000	LFT
126 802-05705	SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	367.000	LFT
127 802-05706	SIGN POST, SQUARE, 3, UNREINFORCED ANCHOR BASE	47.000	LFT
128 802-07060	SIGN, SHEET, RELOCATE	3.000	EACH
129 802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	239.000	SFT
130 802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	74.000	SFT
131 802-76045	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	38.000	SFT
132 805-01815	SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
133 805-01842	HANDHOLE, SIGNAL	13.000	EACH
134 805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	2,340.000	LFT
135 805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
136 805-78100	CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
137 805-78205	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	3.000	EACH
138 805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	7.000	EACH
139 805-78415	SPAN, CATENARY, AND TETHER	4.000	EACH
140 805-78420	DISCONNECT HANGER	4.000	EACH
141 805-78445	SIGNAL SERVICE	1.000	EACH
142 805-78470	SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	4,400.000	LFT
143 805-78485	SIGNAL CABLE, 5C 14GA.	230.000	LFT
144 805-78490	SIGNAL CABLE, 7C 14GA.	1,350.000	LFT
145 805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	6,660.000	LFT
146 805-78785	SIGNAL DETECTOR HOUSING	14.000	EACH
147 805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	1,430.000	LFT

CALL ORDER : 330

CONTRACT ID : R -29095-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
148	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
149	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	4.000	EACH
150	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	7.000	EACH
151	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	3.000	EACH
152	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	52.000	SYS
153	808-06368 TRANSVERSE MARKING, REMOVE	145.000	LFT
154	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1,787.000	LFT
155	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	9,878.000	LFT
156	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	200.000	LFT
157	808-06716 LINE, REMOVE	3,570.000	LFT
158	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4,548.000	LFT
159	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	16.000	LFT
160	808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	207.000	LFT
161	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	390.000	LFT
162	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	18.000	EACH
163	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	9.000	EACH
164	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	174.000	EACH
165	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	289.000	EACH
166	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	2,462.000	LFT

CALL ORDER : 340

CONTRACT ID : R -29234-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02279 CURB AND GUTTER, REMOVE	10.000	m
10	202-52710 SIDEWALK, CONCRETE, REMOVE	14.500	m2
11	202-91840 FENCE, CHAIN LINK, REMOVE	33.000	m
12	203-02070 BORROW	230.000	m3
13	205-06937 TEMPORARY SILT FENCE	1,602.000	m
14	207-08267 SUBGRADE TREATMENT, TYPE IIIA	33.000	m2
15	210-08379 STEEL	6.000	EACH
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	716.500	Mg
17	402-07432 HMA SURFACE, TYPE A	181.800	Mg
18	402-07435 HMA INTERMEDIATE, TYPE A	363.600	Mg
19	406-05521 ASPHALT FOR TACK COAT	3,030.000	m2
20	603-03829 FENCE	188.000	m
21	604-07902 CURB RAMP, CONCRETE, H	7.400	m2
22	610-08446 PCCP FOR APPROACHES, 150 mm	33.000	m2
23	621-06560 MULCHED SEEDING, U	3,050.000	m2
24	621-06570 TOP SOIL	235.000	m3
25	628-09401 FIELD OFFICE, A	5.000	MOS
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	39.280	m
28	802-76020 SIGN, SHEET, ENCLOSED LENS WITH LEGEND 2.03 mm THICKNESS	5.730	m2
29	808-75060 TRANSVERSE MARKINGS, PAINT, SOLID, WHITE, CROSSHATCH LINE,	170.000	m

CALL ORDER : 350

CONTRACT ID : R -29270-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-91385 INLET, REMOVE	1.000	EACH
14	202-96133 PIPE, REMOVE	401.000	LFT
15	203-02000 EXCAVATION, COMMON	4,173.000	CYS
16	203-02070 BORROW	10,150.000	CYS
17	205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	1.000	EACH
18	205-06932 TEMPORARY CHECK DAM, STRAW BALES	48.000	LFT
19	205-06934 TEMPORARY MULCHING	11.000	TON
20	205-06937 TEMPORARY SILT FENCE	7,491.000	LFT
21	205-09543 NO 2 STONE	100.000	TON
22	207-08263 SUBGRADE TREATMENT, TYPE IA	12,217.000	SYS
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	5,638.000	SYS
24	211-09264 STRUCTURE BACKFILL, TYPE 1	1,259.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,278.000	TON
26	303-01180 COMPACTED AGGREGATE, NO. 53	2,125.000	TON
27	304-07494 WIDENING WITH HMA, TYPE C	396.000	TON
28	306-08036 MILLING, ASPHALT, 2 IN.	4,428.000	SYS
29	306-08039 MILLING, ASPHALT REMOVAL	8,567.000	SYS
30	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	1,327.000	TON
31	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	2,289.000	TON
32	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	5,215.000	TON
33	402-07432 HMA SURFACE, TYPE A	470.000	TON
34	402-07435 HMA INTERMEDIATE, TYPE A	1,560.000	TON
35	406-05520 ASPHALT FOR TACK COAT	1.000	TON
36	601-06239 IMPACT ATTENUATOR, R1, W2, TL-3	5.000	EACH
37	610-07488 HMA FOR APPROACHES, TYPE C	420.000	TON
38	610-08446 PCCP FOR APPROACHES, 6 IN.	76.000	SYS
39	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	5.000	EACH
40	615-06490 RIGHT OF WAY MARKER	22.000	EACH
41	615-06505 MONUMENT, B	9.000	EACH
42	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
43	616-02320 GEOTEXTILES	2,611.000	SYS
44	616-05688 RIPRAP, CLASS 1	136.000	TON
45	616-06451 RIPRAP, UNIFORM	414.000	TON
46	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	10,625.000	SYS
47	621-06545 FERTILIZER	2.000	TON
48	621-06557 SEED MIXTURE, T	112.000	LBS
49	621-06559 MULCHED SEEDING, R	264.000	SYS

CALL ORDER : 350

CONTRACT ID : R -29270-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	621-06564 MULCHED SEEDING, CV	112.000	SYS
51	621-06567 WATER	328.000	KGAL
52	621-06574 SODDING	9,814.000	SYS
53	621-06575 SODDING, NURSERY	20,783.000	SYS
54	628-09402 FIELD OFFICE, B	12.000	MOS
55	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
56	714-01633 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 9 FT X 5 FT	106.000	LFT
57	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	39.000	LFT
58	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	112.000	LFT
59	715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN.	158.000	LFT
60	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	146.000	LFT
61	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	128.000	LFT
62	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN.	71.000	LFT
63	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN.	68.000	LFT
64	715-05175 PIPE, TYPE 3, CIRCULAR, 30 IN.	40.000	LFT
65	715-05177 PIPE, TYPE 3, CIRCULAR, 36 IN.	214.000	LFT
66	715-08282 HMA FOR STRUCTURE INSTALLATION, TYPE A	5.000	TON
67	715-46000 PIPE END SECTION, 12 IN.	3.000	EACH
68	715-46005 PIPE END SECTION, 15 IN.	10.000	EACH
69	715-46010 PIPE END SECTION, 18 IN.	4.000	EACH
70	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
71	715-46030 PIPE END SECTION, 30 IN.	4.000	EACH
72	715-46040 PIPE END SECTION, 36 IN.	3.000	EACH
73	720-45410 MANHOLE, C4	2.000	EACH
74	720-95422 MANHOLE, J4	3.000	EACH
75	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
76	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
77	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7,953.000	LFT
78	801-06539 TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	LUMP	LUMP
79	801-06625 DETOUR ROUTE MARKER ASSEMBLY	9.000	EACH
80	801-06640 CONSTRUCTION SIGN, A	46.000	EACH
81	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
82	801-07119 BARRICADE, III-B	180.000	LFT
83	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	824.000	LFT
84	802-02158 SIGN, PANEL, REMOVE AND REINSTALL	2.000	EACH
85	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	480.000	LFT
86	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	143.000	SFT
87	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	95.000	SFT
88	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	62.000	SFT
89	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	6,245.000	LFT
90	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7,071.000	LFT
91	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	210.000	LFT
92	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
93	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
94	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
95	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	108.000	EACH

CALL ORDER : 360

CONTRACT ID : R -29400-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	40.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-74035 SIGN, REMOVE	7.000	EACH
14	202-96133 PIPE, REMOVE	675.000	LFT
15	203-02000 EXCAVATION, COMMON	10,327.000	CYS
16	203-02070 BORROW	22,280.000	CYS
17	205-03371 SEDIMENT, REMOVE	34.000	CYS
18	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	11.000	TON
19	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
20	205-06936 TEMPORARY SEDIMENT TRAP	131.000	TON
21	207-08262 SUBGRADE TREATMENT, TYPE I	37,433.000	SYS
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	952.000	SYS
23	211-09264 STRUCTURE BACKFILL, TYPE 1	511.000	CYS
24	211-09265 STRUCTURE BACKFILL, TYPE 2	618.000	CYS
25	211-09268 STRUCTURE BACKFILL, TYPE 5	138.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,095.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN.	247.000	SYS
28	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
29	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	2,779.000	TON
30	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	4,632.000	TON
31	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	15,041.000	TON
32	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	6,098.000	TON
33	406-05520 ASPHALT FOR TACK COAT	44.400	TON
34	605-06120 CURB, CONCRETE	1,266.000	LFT
35	605-06140 CURB AND GUTTER, CONCRETE	9,278.000	LFT
36	605-06215 CENTER CURB, D, CONCRETE	800.000	LFT
37	610-07486 HMA FOR APPROACHES, TYPE A	513.000	TON
38	610-08446 PCCP FOR APPROACHES, 6 IN.	479.000	SYS
39	610-09108 PCCP FOR APPROACHES, 9 IN.	473.000	SYS
40	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
41	615-06490 RIGHT OF WAY MARKER	43.000	EACH
42	615-06505 MONUMENT, B	9.000	EACH
43	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
44	616-02320 GEOTEXTILES	1,172.000	SYS
45	616-06405 RIPRAP, REVETMENT	871.000	TON
46	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
47	621-06545 FERTILIZER	2.000	TON
48	621-06554 SEED MIXTURE, U	715.000	LBS
49	621-06565 MULCHING MATERIAL	9.500	TON

CALL ORDER : 360

CONTRACT ID : R -29400-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
50	621-06567 WATER	28.000	kGAL
51	621-06575 SODDING, NURSERY	6,896.000	SYS
52	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	235.000	EACH
53	622-98200 SIGN, DO NOT DISTURB	4.000	EACH
54	628-09402 FIELD OFFICE, B	20.000	MOS
55	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	20.000	MOS
56	714-06279 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 8 FT. X 3 FT.	280.000	LFT
57	714-06688 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 5 FT. X 2 FT.	230.000	LFT
58	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	9,145.000	LFT
59	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	16.000	LFT
60	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	78.000	LFT
61	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	37.000	LFT
62	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	1,133.500	LFT
63	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	96.000	LFT
64	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	171.000	LFT
65	715-46005 PIPE END SECTION, 15 IN.	27.000	EACH
66	715-46010 PIPE END SECTION, 18 IN.	4.000	EACH
67	718-06529 OUTLET PROTECTOR, 2	1.000	EACH
68	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
69	718-52610 AGGREGATE FOR UNDERDRAINS	823.000	CYS
70	718-99153 GEOTEXTILES FOR UNDERDRAIN	9,572.000	SYS
71	720-45030 INLET, E7	1.000	EACH
72	720-98174 INLET, B15	15.000	EACH
73	720-98555 INLET, C15	21.000	EACH
74	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
75	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
76	801-06625 DETOUR ROUTE MARKER ASSEMBLY	26.000	EACH
77	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
78	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
79	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
80	801-07119 BARRICADE, III-B	48.000	LFT
81	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	145.000	LFT
82	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	67.500	SFT
83	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	100.000	LFT
84	805-02389 SIGNAL CABLE, 2C/14	100.000	LFT
85	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,000.000	LFT
86	805-78785 SIGNAL DETECTOR HOUSING	3.000	EACH
87	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	400.000	LFT
88	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	2,270.000	LFT
89	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,732.000	LFT
90	808-06716 LINE, REMOVE	945.000	LFT
91	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	862.000	LFT
92	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	9,449.000	LFT
93	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	172.000	LFT
94	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	22.000	EACH
95	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	15.000	EACH
96	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	165.000	EACH

CALL ORDER : 370

CONTRACT ID : R -29777-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE AND PEDESTRIAN PATH, ENHANCEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02236 SURFACE, REMOVE	1,600.000	SYS
9	202-02245 TREE, 6 IN., REMOVE	5.000	EACH
10	202-02250 TREE, 10 IN., REMOVE	8.000	EACH
11	202-02255 TREE, 18 IN., REMOVE	31.000	EACH
12	202-02260 TREE, 30 IN., REMOVE	21.000	EACH
13	202-02278 CURB, CONCRETE, REMOVE	500.000	LFT
14	202-52710 SIDEWALK, CONCRETE, REMOVE	5,300.000	SYS
15	202-91922 STUMP, REMOVE	9.000	EACH
16	211-02050 B BORROW	100.000	CYS
17	303-04470 CRUSHED STONE, 11	650.000	TON
18	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	1,500.000	TON
19	304-07492 WIDENING WITH HMA, TYPE A	270.000	TON
20	603-06065 FENCE, CHAIN LINK, RESET	125.000	LFT
21	604-06070 SIDEWALK, CONCRETE	7,500.000	SYS
22	604-07897 CURB RAMP, CONCRETE, C	700.000	SYS
23	610-08446 PCCP FOR APPROACHES, 6 IN.	3,020.000	SYS
24	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	2.000	EACH
25	621-06560 MULCHED SEEDING, U	7,500.000	SYS
26	628-09401 FIELD OFFICE, A	10.000	MOS
27	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	30.000	LFT
28	732-91742 FIRE HYDRANT	6.000	EACH
29	732-94780 WATER SERVICE CONNECTION	26.000	EACH
30	802-91122 SIGN, GROUND MOUNTED, RESET	27.000	EACH
31	808-75256 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	2,380.000	LFT

CALL ORDER : 380

CONTRACT ID : R -30256-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIDEWALK REHABILITATION AND CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-52710 SIDEWALK, CONCRETE, REMOVE	61.000	SYS
10	203-02000 EXCAVATION, COMMON	10.000	CYS
11	203-02070 BORROW	49.000	CYS
12	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	9.000	EACH
13	205-06937 TEMPORARY SILT FENCE	875.000	LFT
14	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	18.000	TON
15	304-07489 HMA PATCHING, TYPE A	54.000	TON
16	406-05520 ASPHALT FOR TACK COAT	0.050	TON
17	604-07897 CURB RAMP, CONCRETE, C	71.000	SYS
18	604-07901 CURB RAMP, CONCRETE, G	80.000	SYS
19	604-44251 STEPS, CONCRETE	0.500	CYS
20	604-90256 SIDEWALK, CONCRETE, 6 IN.	271.000	SYS
21	604-91531 SIDEWALK, CONCRETE, 4 IN.	2,904.000	SYS
22	605-06120 CURB, CONCRETE	278.000	LFT
23	610-08446 PCCP FOR APPROACHES, 6 IN.	60.000	SYS
24	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
25	621-02770 EROSION CONTROL BLANKET	125.000	SYS
26	621-06559 MULCHED SEEDING, R	4,646.000	SYS
27	628-09401 FIELD OFFICE, A	6.000	MOS
28	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
29	732-08419 MODULAR BLOCK WALL	16.000	SYS
30	732-08421 MODULAR BLOCK WALL ERECTION	16.000	SYS
31	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
32	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
33	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	801-07119 BARRICADE, III-B	72.000	LFT
36	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	216.000	LFT
37	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
38	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	36.000	SFT
39	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	162.000	SFT
40	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	510.000	LFT
41	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	474.000	LFT

CALL ORDER : 390

CONTRACT ID : R -30295-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
1 105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
2 105-06899	RADIO	2.000	EACH
3 105-08520	CELLULAR TELEPHONE/RADIO	2.000	EACH
4 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	48.000	MOS
5 105-08523	RADIO SERVICE	48.000	MOS
6 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7 109-08359	LIQUIDATED DAMAGES	1.000	DOL
8 109-08360	CONTRACT LIENS	1.000	DOL
9 109-08440	QUALITY ADJUSTMENTS, HMA	1.000	DOL
10 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12 109-08463	PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
13 109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
14 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15 201-52370	CLEARING RIGHT OF WAY	LUMP	LUMP
16 202-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
17 202-02240	PAVEMENT REMOVAL	362.200	m2
18 202-02286	PRESENT STRUCTURE, REMOVE	1.000	EACH
19 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
20 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
21 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
22 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
23 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
24 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
25 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
26 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
27 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
28 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
29 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
30 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
31 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
32 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
33 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
34 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
35 202-74035	SIGN, REMOVE	139.000	EACH
36 202-91385	INLET, REMOVE	12.000	EACH
37 202-93995	SIGNAL POLE FOUNDATION, REMOVE	1.000	EACH
38 202-96133	PIPE, REMOVE	1,262.400	m
39 203-02000	EXCAVATION, COMMON	98,930.000	m3
40 205-06931	TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,655.000	Mg
41 205-06933	TEMPORARY DITCH INLET PROTECTION	53.000	EACH
42 205-06937	TEMPORARY SILT FENCE	2,053.000	m
43 206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	60.000	m3
44 207-08263	SUBGRADE TREATMENT, TYPE IA	142,335.200	m2
45 207-08267	SUBGRADE TREATMENT, TYPE IIIA	10,280.000	m2
46 211-06467	AGGREGATE FOR END BENT BACKFILL	48.000	m3
47 211-09264	STRUCTURE BACKFILL, TYPE 1	6,231.300	m3
48 211-09265	STRUCTURE BACKFILL, TYPE 2	1,210.800	m3
49 211-09266	STRUCTURE BACKFILL, TYPE 3	11.200	m3

CALL ORDER : 390

CONTRACT ID : R -30295-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
50	211-09268 STRUCTURE BACKFILL, TYPE 5	323.000	m3
51	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	23,949.600	Mg
52	302-07455 DENSE GRADED SUBBASE	84.000	m3
53	303-06959 AGGREGATE	100.000	Mg
54	304-07491 HMA PATCHING, TYPE C	64.400	Mg
55	304-07494 WIDENING WITH HMA, TYPE C	3,386.300	Mg
56	306-08034 MILLING, ASPHALT, 38 mm	9,340.000	m2
57	306-08042 MILLING, SCARIFICATION/PROFILE	16,752.000	m2
58	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
59	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	9,796.800	Mg
60	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	2,114.200	Mg
61	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	11,814.000	Mg
62	401-07399 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	3,523.700	Mg
63	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	34,778.000	Mg
64	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	15,504.000	Mg
65	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	16,628.000	Mg
66	402-07432 HMA SURFACE, TYPE A	1,349.000	Mg
67	402-07440 HMA BASE, TYPE A	4,304.000	Mg
68	406-05520 ASPHALT FOR TACK COAT	91.000	Mg
69	601-01128 GUARDRAIL TRANSITION TYPE WGB	4.000	EACH
70	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
71	601-01627 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 3	2.000	EACH
72	601-05071 GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, 7	1.000	EACH
73	601-94689 GUARDRAIL END TREATMENT, OS	28.000	EACH
74	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	1,447.800	m
75	602-06729 BARRIER DELINEATOR	10.000	EACH
76	604-07894 CURB RAMP, CONCRETE, A	17.600	m2
77	604-07902 CURB RAMP, CONCRETE, H	63.200	m2
78	604-07903 CURB RAMP, CONCRETE, K	18.800	m2
79	604-90256 SIDEWALK, CONCRETE, 150 mm	3,567.200	m2
80	605-06120 CURB, CONCRETE	109.000	m
81	605-06140 CURB AND GUTTER, CONCRETE	2,935.600	m
82	605-09131 CURB AND GUTTER TURNOUT, CONCRETE	8.400	m
83	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	623.800	m2
84	610-07487 HMA FOR APPROACHES, TYPE B	2,192.900	Mg
85	610-07488 HMA FOR APPROACHES, TYPE C	5,870.400	Mg
86	610-08446 PCCP FOR APPROACHES, 150 mm	2,464.800	m2
87	610-09108 PCCP FOR APPROACHES, 225 mm	920.000	m2
88	615-06490 RIGHT OF WAY MARKER	275.000	EACH
89	615-06505 MONUMENT, B	56.000	EACH
90	616-02320 GEOTEXTILES	9,932.700	m2
91	616-06405 RIPRAP, REVETMENT	6,121.000	Mg
92	616-06451 RIPRAP, UNIFORM	25.000	Mg
93	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
94	621-06545 FERTILIZER	13.000	Mg
95	621-06560 MULCHED SEEDING, U	145,172.000	m2
96	621-06565 MULCHING MATERIAL	65.300	Mg
97	621-06567 WATER	159.400	kL
98	621-06574 SODDING	20,412.000	m2

CALL ORDER : 390

CONTRACT ID : R -30295-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
99 621-06575	SODDING, NURSERY	19,455.000	m2
100 628-09403	FIELD OFFICE, C	24.000	MOS
101 628-09407	FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	48.000	MOS
102 701-01849	PILE, CONCRETE, STEEL SHELL ENCASED, 7.92 mm, 356 mm	198.900	m
103 701-99086	PILE TIP, STEEL SHELL	18.000	EACH
104 702-51863	FIELD DRILLED HOLE IN CONCRETE	12.000	EACH
105 702-92857	CONCRETE, C, SUBSTRUCTURE	31.700	m3
106 703-51032	REINFORCING STEEL, EPOXY COATED	30,534.000	kg
107 704-51002	CONCRETE, C, SUPERSTRUCTURE	117.100	m3
108 706-05733	CONCRETE BRIDGE RAILING TRANSITION, WBC	4.000	EACH
109 706-51025	CONCRETE, C, RAILING	29.600	m
110 707-05979	STRUCTURAL MEMBERS, CONCRETE BOX BEAM, CB, 686 mm X 1219 mm	166.600	m2
111 709-51821	SURFACE SEAL	LUMP	LUMP
112 709-51821	SURFACE SEAL	LUMP	LUMP
113 714-04802	CONCRETE MODULAR BLOCK WALL	52.300	m2
114 714-26703	CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1800 mm x 1200 mm	24.000	m
115 714-26712	CULVERT, PRECAST BOX, REINFORCED CONCRETE, 2400 mm x 1800 mm	24.000	m
116 714-26722	CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3000 mm x 2400 mm	26.500	m
117 714-26724	CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3600 mm x 1200 mm	22.000	m
118 714-99348	CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1500 mm x 900 mm	9.000	m
119 715-04855	PIPE END SECTION, 1050 mm	1.000	EACH
120 715-05019	PIPE, TYPE 1, CIRCULAR, 900 mm	28.000	m
121 715-05048	PIPE, TYPE 4, CIRCULAR, 150 mm	14,874.000	m
122 715-05053	PIPE, UNDERDRAIN OUTLET, 150 mm	645.500	m
123 715-05121	PIPE, TYPE 1, CIRCULAR, 450 mm	60.000	m
124 715-05123	PIPE, TYPE 1, CIRCULAR, 600 mm	157.000	m
125 715-05149	PIPE, TYPE 2, CIRCULAR, 300 mm	913.600	m
126 715-05151	PIPE, TYPE 2, CIRCULAR, 375 mm	1,054.300	m
127 715-05152	PIPE, TYPE 2, CIRCULAR, 450 mm	480.500	m
128 715-05154	PIPE, TYPE 2, CIRCULAR, 600 mm	402.000	m
129 715-05156	PIPE, TYPE 2, CIRCULAR, 750 mm	3.500	m
130 715-05159	PIPE, TYPE 2, CIRCULAR, 1050 mm	165.000	m
131 715-05169	PIPE, TYPE 3, CIRCULAR, 375 mm	321.000	m
132 715-05171	PIPE, TYPE 3, CIRCULAR, 450 mm	66.500	m
133 715-05173	PIPE, TYPE 3, CIRCULAR, 600 mm	14.000	m
134 715-05407	PIPE, END BENT DRAIN, 150 mm	48.000	m
135 715-05422	PIPE, SLOTTED DRAIN, 300 mm	17.000	m
136 715-07667	CONCRETE ANCHOR, 900 mm	2.000	EACH
137 715-26750	GRATED BOX END SECTION, II, 4:1, 1050 mm x 725 mm	1.000	EACH
138 715-46000	PIPE END SECTION, 300 mm	3.000	EACH
139 715-46005	PIPE END SECTION, 375 mm	61.000	EACH
140 715-46010	PIPE END SECTION, 450 mm	23.000	EACH
141 715-46020	PIPE END SECTION, 600 mm	19.000	EACH
142 715-46030	PIPE END SECTION, 750 mm	1.000	EACH
143 718-06529	OUTLET PROTECTOR, 2	69.000	EACH
144 718-06532	VIDEO INSPECTION FOR UNDERDRAINS	2,000.000	m
145 718-52610	AGGREGATE FOR UNDERDRAINS	3,729.000	m3
146 718-99153	GEOTEXTILES FOR UNDERDRAIN	27,387.100	m2
147 720-45005	INLET, A2	2.000	EACH

CALL ORDER : 390

CONTRACT ID : R -30295-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
148	720-45030 INLET, E7	35.000	EACH
149	720-45035 INLET, F7	18.000	EACH
150	720-45410 MANHOLE, C4	20.000	EACH
151	720-45415 MANHOLE, D4	1.000	EACH
152	720-98174 INLET, B15	21.000	EACH
153	720-98555 INLET, C15	48.000	EACH
154	722-51842 BRIDGE DECK OVERLAY	266.000	m2
155	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	2.000	m3
156	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	28.000	m2
157	722-60824 SURFACE MILLING	266.000	m2
158	723-08050 STRUCTURE, PRECAST THREE-SIDED, 5480 mm x 2440 mm	24.600	m
159	727-90308 EPOXY INJECTION, CRACK PREPARATION	62.000	m
160	727-90309 EPOXY INJECTION, EPOXY MATERIAL	142.000	L
161	727-93560 EPOXY INJECTION, FURNISHING EQUIPMENT	LUMP	LUMP
162	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
163	801-06625 DETOUR ROUTE MARKER ASSEMBLY	35.000	EACH
164	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
165	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
166	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
167	801-07119 BARRICADE, III-B	16.000	m
168	802-04893 REFERENCE POST	2.000	EACH
169	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	509.700	m
170	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	50.100	m2
171	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	32.580	m2
172	805-01816 SIGNAL SUPPORT FOUNDATION, 900 mm X 900 mm X 2500 mm	3.000	EACH
173	805-01842 HANDHOLE, SIGNAL	2.000	EACH
174	805-01844 CONDUIT, STEEL, GALVANIZED, 50 mm, UNDERGROUND	42.000	m
175	805-01879 SIGNAL SERVICE, INSTALL	1.000	EACH
176	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	337.000	m
177	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
178	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	8.000	EACH
179	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
180	805-78420 DISCONNECT HANGER	4.000	EACH
181	805-78467 SIGNAL CABLE, 3C 8GA.	16.000	m
182	805-78485 SIGNAL CABLE, 5C 14GA.	111.000	m
183	805-78490 SIGNAL CABLE, 7C 14GA.	159.000	m
184	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	101.000	m
185	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	169.000	m
186	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
187	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	3.000	EACH
188	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	3.000	EACH
189	808-03002 LINE, EPOXY, BROKEN, WHITE, 100 mm	7.000	m
190	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	395.800	m
191	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	395.800	m
192	808-04896 LINE, EPOXY, BROKEN, YELLOW, 100 mm	14.800	m
193	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	429.000	m
194	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	20,066.400	m
195	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	495.700	m
196	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	13,547.000	m

CALL ORDER : 390

CONTRACT ID : R -30295-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
197 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	20.000	m
198 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	36.000	EACH
199 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	13.000	EACH
200 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	961.000	EACH

CALL ORDER : 400

CONTRACT ID : R -30385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	19,275.000	SYS
11	202-04089 SIGN, SHEET, REMOVE	32.000	EACH
12	202-52710 SIDEWALK, CONCRETE, REMOVE	195.000	SYS
13	203-02000 EXCAVATION, COMMON	70,806.000	CYS
14	205-06933 TEMPORARY DITCH INLET PROTECTION	6.000	EACH
15	205-06934 TEMPORARY MULCHING	2.000	TON
16	205-06937 TEMPORARY SILT FENCE	13,248.000	LFT
17	205-09543 NO 2 STONE	750.000	TON
18	207-08263 SUBGRADE TREATMENT, TYPE IA	67,000.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	7,900.000	SYS
20	211-02050 B BORROW	95.000	CYS
21	211-07454 STRUCTURE BACKFILL	6,445.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,458.000	TON
23	302-06464 SUBBASE FOR PCCP	13,566.000	CYS
24	303-01180 COMPACTED AGGREGATE, NO. 53	2,376.000	TON
25	306-08034 MILLING, ASPHALT, 1 1/2 IN.	80.000	SYS
26	402-07434 HMA SURFACE, TYPE C	283.000	TON
27	402-07439 HMA INTERMEDIATE, TYPE C	460.000	TON
28	402-07442 HMA BASE, TYPE C	1,607.000	TON
29	402-07453 HMA FOR TEMPORARY PAVEMENT	2,871.000	TON
30	406-05520 ASPHALT FOR TACK COAT	7.100	TON
31	501-08193 QC/QA-PCCP, 10.5 IN.	54,266.000	SYS
32	503-05240 D-1 CONTRACTION JOINT	25,940.000	LFT
33	604-07900 CURB RAMP, CONCRETE, F	265.000	SYS
34	604-91531 SIDEWALK, CONCRETE, 4 IN.	7,200.000	SYS
35	605-06090 CURB, INTEGRAL, CONCRETE	9,190.000	LFT
36	610-07486 HMA FOR APPROACHES, TYPE A	298.000	TON
37	610-07712 PCCP FOR APPROACHES, 6 IN.	2,741.000	SYS
38	610-09108 PCCP FOR APPROACHES, 9 IN.	971.000	SYS
39	611-06497 MAILBOX ASSEMBLY, SINGLE	62.000	EACH
40	615-06490 RIGHT OF WAY MARKER	78.000	EACH
41	615-06515 MONUMENT, D	9.000	EACH
42	621-06557 SEED MIXTURE, T	97.000	LBS
43	621-06567 WATER	350.000	kgAL
44	621-06575 SODDING, NURSERY	6,900.000	SYS
45	628-09402 FIELD OFFICE, B	8.000	MOS
46	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	2,484.000	LFT
47	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	13,145.000	LFT
48	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	4,519.000	LFT
49	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	635.000	LFT

CALL ORDER : 400

CONTRACT ID : R -30385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
50	715-05159 PIPE, TYPE 2, CIRCULAR, 42 IN.	2,975.000	LFT
51	718-52610 AGGREGATE FOR UNDERDRAINS	1,619.000	CYS
52	718-99153 GEOTEXTILES FOR UNDERDRAIN	40,833.000	SYS
53	720-01092 MANHOLE, J15, MODIFIED	25.000	EACH
54	720-03194 MANHOLE	24.000	EACH
55	720-08660 MANHOLE, J5, MODIFIED	4.000	EACH
56	720-08661 MANHOLE, K5, MODIFIED	2.000	EACH
57	720-44080 CASTING, 15, FURNISH AND ADJUST TO GRADE	1.000	EACH
58	720-45265 PIPE CATCH BASIN, 15 IN.	7.000	EACH
59	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	5.000	LFT
60	720-93409 INLET, B15, MODIFIED	2.000	EACH
61	720-93411 INLET, C15, MODIFIED	19.000	EACH
62	720-95409 MANHOLE, J4, MODIFIED	1.000	EACH
63	720-98174 INLET, B15	41.000	EACH
64	732-08419 MODULAR BLOCK WALL	18.000	SYS
65	732-08421 MODULAR BLOCK WALL ERECTION	18.000	SYS
66	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
67	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
68	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	27,440.000	LFT
69	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	49,800.000	LFT
70	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	2.000	EACH
71	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
72	801-06645 CONSTRUCTION SIGN, B	9.000	EACH
73	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
74	801-07119 BARRICADE, III-B	552.000	LFT
75	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	2,063.000	LFT
76	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
77	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	21.000	LFT
78	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	209.000	LFT
79	802-07135 CABLE SPAN SIGN STRUCTURE FOUNDATION, IV	10.000	EACH
80	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	192.000	SFT
81	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	102.000	SFT
82	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	44.000	SFT
83	802-76125 SPAN OVERHEAD SIGN STRUCTURE, CABLESPAN	5.000	EACH
84	802-91122 SIGN, GROUND MOUNTED, RESET	1.000	EACH
85	805-01842 HANDHOLE, SIGNAL	30.000	EACH
86	805-01879 SIGNAL SERVICE, INSTALL	1.000	EACH
87	805-02151 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 12 IN.	8.000	EACH
88	805-04982 CABLE	675.000	LFT
89	805-04989 POWER SUPPLY	1.000	EACH
90	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	7,255.000	LFT
91	805-06921 INTEGRATED VIDEO VEHICLE DETECTOR SYSTEM	4.000	EACH
92	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
93	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	5.000	EACH
94	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	3.000	EACH
95	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
96	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
97	805-78420 DISCONNECT HANGER	4.000	EACH
98	805-78467 SIGNAL CABLE, 3C 8GA.	50.000	LFT

CALL ORDER : 400

CONTRACT ID : R -30385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
99 805-78480	SIGNAL CABLE, 3C 14GA.	620.000	LFT
100 805-78485	SIGNAL CABLE, 5C 14GA.	880.000	LFT
101 805-78490	SIGNAL CABLE, 7C 14GA.	475.000	LFT
102 805-78925	CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
103 805-81060	SIGNAL STRAIN POLE, STEEL, 36 FT.	4.000	EACH
104 805-98540	FOUNDATION AND ANCHOR BOLTS FOR STRAIN POLE	4.000	EACH
105 807-02785	LUMINAIRE MAST ARM, 25 FT.	4.000	EACH
106 808-03002	LINE, EPOXY, BROKEN, WHITE, 4 IN.	3,680.000	LFT
107 808-03631	LINE, EPOXY, SOLID, WHITE, 4 IN.	1,410.000	LFT
108 808-03632	LINE, EPOXY, SOLID, YELLOW, 4 IN.	17,070.000	LFT
109 808-04896	LINE, EPOXY, BROKEN, YELLOW, 4 IN.	10,330.000	LFT
110 808-06716	LINE, REMOVE	23,550.000	LFT
111 808-74805	TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	290.000	LFT
112 808-74807	PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	31.000	EACH
113 808-74808	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	31.000	EACH
114 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	95.000	EACH
115 808-94455	TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 6 IN.	1,570.000	LFT

CALL ORDER : 410

CONTRACT ID : R -30711-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
13	202-02273 CENTER CURB, CONCRETE, REMOVE	352.000	m2
14	202-02279 CURB AND GUTTER, REMOVE	176.240	m
15	202-02928 CATCH BASIN, REMOVE	2.000	EACH
16	202-91922 STUMP, REMOVE	1.000	EACH
17	202-93047 MANHOLE, REMOVE	1.000	EACH
18	202-94425 APRON, REMOVE	390.814	m2
19	202-96022 CONCRETE FOUNDATION, REMOVE	1.000	EACH
20	203-02000 EXCAVATION, COMMON	6,338.980	m3
21	203-02100 EXCAVATION, PEAT	100.000	m3
22	203-02131 EXPLORATORY EXCAVATION	440.000	m3
23	205-03371 SEDIMENT REMOVE	20.000	m3
24	205-06937 TEMPORARY SILT FENCE	427.000	m
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	490.904	m2
26	207-08268 SUBGRADE TREATMENT, TYPE IV	11,514.173	m2
27	211-09264 STRUCTURE BACKFILL, TYPE 1	1,379.402	m3
28	213-09270 FLOWABLE BACKFILL, REMOVEABLE	61.875	m3
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	213.179	Mg
30	302-06464 SUBBASE FOR PCCP	2,590.690	m3
31	303-02172 TEMPORARY AGGREGATE	191.200	Mg
32	304-07489 HMA PATCHING, TYPE A	75.000	Mg
33	304-07494 WIDENING WITH HMA, TYPE C	60.000	Mg
34	501-06324 QC/QA-PCCP, 325 mm	9,976.086	m2
35	502-06330 PCCP, 325 mm	448.238	m2
36	503-05240 D-1 CONTRACTION JOINT	2,357.470	m
37	604-07092 BED COURSE MATERIAL	56.601	Mg
38	604-07902 CURB RAMP, CONCRETE, H	47.807	m2
39	604-91404 SIDEWALK, CONCRETE, 125 mm	508.928	m2
40	605-06090 CURB, INTEGRAL, CONCRETE	10.000	m
41	605-06150 CURB AND GUTTER, C, CONCRETE	150.000	m
42	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	330.000	m
43	605-06210 CENTER CURB, C, CONCRETE	118.328	m
44	610-09108 PCCP FOR APPROACHES, 225 mm	452.255	m2
45	621-06567 WATER	28.300	kL
46	621-06570 TOP SOIL	157.320	m3
47	621-06574 SODDING	1,573.242	m2
48	628-09402 FIELD OFFICE, B	12.000	MOS
49	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	773.316	m

CALL ORDER : 410

CONTRACT ID : R -30711-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	13.000	m
51	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	170.566	m
52	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	159.739	m
53	715-09064 VIDEO INSPECTION FOR PIPE	340.000	m
54	718-06529 OUTLET PROTECTOR, 2	2.000	EACH
55	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	270.000	m
56	718-52610 AGGREGATE FOR UNDERDRAINS	264.474	m3
57	718-99153 GEOTEXTILES FOR UNDERDRAIN	3,402.590	m2
58	720-44000 CASTING, ADJUST TO GRADE	9.000	EACH
59	720-45045 INLET, J10	8.000	EACH
60	720-45250 CATCH BASIN, K10	8.000	EACH
61	720-45410 MANHOLE, C4	5.000	EACH
62	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
63	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	5,540.774	m
64	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	30.000	m
65	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
66	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
67	801-06710 FLASHING ARROW SIGN	450.000	DAY
68	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
69	801-07119 BARRICADE, III-B	72.000	m
70	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	5.800	m
71	802-07135 CABLE SPAN SIGN STRUCTURE FOUNDATION, IV	4.000	EACH
72	802-07158 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, I	1.000	EACH
73	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	0.900	m2
74	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	10.010	m2
75	802-76125 SPAN OVERHEAD SIGN STRUCTURE, CABLESPAN	2.000	EACH
76	802-76135 OVERHEAD SIGN STRUCTURE, CANTILEVER SINGLE ARM	1.000	EACH
77	805-01844 CONDUIT, STEEL, GALVANIZED, 50 mm, UNDERGROUND	500.000	m
78	805-01893 MAINTAINING TRAFFIC SIGNAL	LUMP	LUMP
79	805-02445 CONTROLLER CABINET, P1	1.000	EACH
80	805-02595 CONTROLLER, RESET TIMING	4.000	EACH
81	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	1.000	EACH
82	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
83	805-86898 CONDUIT, STEEL, GALVANIZED, 19 mm	100.000	m
84	805-95890 WIRE, NO. 12 COPPER, 1/C	252.000	m
85	807-02191 HANDHOLE, LIGHTING	2.000	EACH
86	807-02428 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING,	23.000	EACH
87	807-03051 LIGHT CABLE, 1C 10GA.	810.000	m
88	807-04651 WIRE	140.000	m
89	807-04651 WIRE	300.000	m
90	807-04651 WIRE	800.000	m
91	807-85502 LIGHT POLE, 9.1 m E.M.H., 4.6 m MAST ARM, BREAKAWAY BASE	23.000	EACH
92	807-86615 LUMINAIRE, ROADWAY, 250 WATT, HIGH PRESSURE SODIUM	23.000	EACH
93	807-86805 SERVICE POINT, I	1.000	EACH
94	807-86910 CONNECTOR KIT, UNFUSED	23.000	EACH
95	807-86915 CONNECTOR KIT, FUSED	23.000	EACH
96	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.000	EACH
97	807-86930 INSULATION LINK, NONWATERPROOFED	46.000	EACH
98	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	23.000	EACH

CALL ORDER : 410

CONTRACT ID : R -30711-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
99 807-98690	HANDHOLE ADJUSTED TO GRADE	2.000	EACH
100 808-03002	LINE, EPOXY, BROKEN, WHITE, 100 mm	570.398	m
101 808-03631	LINE, EPOXY, SOLID, WHITE, 100 mm	569.062	m
102 808-03632	LINE, EPOXY, SOLID, YELLOW, 100 mm	1,770.404	m
103 808-04896	LINE, EPOXY, BROKEN, YELLOW, 100 mm	604.250	m
104 808-06716	LINE, REMOVE	3,392.808	m
105 808-74805	TRANSVERSE MARKINGS, EPOXY, STOP LINE, 600 mm	44.890	m
106 808-74807	PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	10.000	EACH
107 808-74808	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	10.000	EACH

CALL ORDER : 420

CONTRACT ID : R -30920-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
11	202-02240 PAVEMENT REMOVAL	538.000	m2
12	202-02278 CURB, CONCRETE, REMOVE	1,314.000	m
13	202-02928 CATCH BASIN, REMOVE	20.000	EACH
14	202-52710 SIDEWALK, CONCRETE, REMOVE	887.000	m2
15	202-93047 MANHOLE, REMOVE	2.000	EACH
16	202-96133 PIPE, REMOVE	74.000	m
17	203-02000 EXCAVATION, COMMON	2,443.000	m3
18	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	3.000	EACH
19	205-06933 TEMPORARY DITCH INLET PROTECTION	22.000	EACH
20	205-06937 TEMPORARY SILT FENCE	667.000	m
21	207-08266 SUBGRADE TREATMENT, TYPE III	1,771.000	m2
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,293.000	m2
23	211-07454 STRUCTURE BACKFILL	386.000	m3
24	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	2,911.000	Mg
25	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	4,908.000	Mg
26	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	828.000	Mg
27	406-05520 ASPHALT FOR TACK COAT	21.000	Mg
28	604-07894 CURB RAMP, CONCRETE, A	346.000	m2
29	604-07896 CURB RAMP, CONCRETE, B	41.000	m2
30	604-07900 CURB RAMP, CONCRETE, F	60.000	m2
31	604-07901 CURB RAMP, CONCRETE, G	33.000	m2
32	604-91531 SIDEWALK, CONCRETE, 100 mm	2,102.000	m2
33	605-06120 CURB, CONCRETE	1,922.000	m
34	610-07488 HMA FOR APPROACHES, TYPE C	536.000	Mg
35	610-08446 PCCP FOR APPROACHES, 150 mm	164.000	m2
36	610-09108 PCCP FOR APPROACHES, 225 mm	1,607.000	m2
37	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
39	621-06575 SODDING, NURSERY	3,606.000	m2
40	628-09403 FIELD OFFICE, C	7.000	MOS
41	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	163.000	m
42	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	1.000	m
43	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	177.000	Mg
44	720-44000 CASTING, ADJUST TO GRADE	48.000	EACH
45	720-45410 MANHOLE, C4	1.000	EACH
46	720-98174 INLET, B15	16.000	EACH
47	720-98555 INLET, C15	6.000	EACH
48	722-60824 SURFACE MILLING	32,472.000	m2
49	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	1.000	EACH

CALL ORDER : 420

CONTRACT ID : R -30920-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
50	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
51	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	4,895.000	m
52	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 200 mm	509.000	m
53	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 600 mm	41.000	m
54	801-06640 CONSTRUCTION SIGN, A	35.000	EACH
55	801-06645 CONSTRUCTION SIGN, B	25.000	EACH
56	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
57	801-09087 TEMPORARY PAVEMENT MARKING, REMOVABLE, 300 mm	130.000	m
58	802-07060 SIGN, SHEET, RELOCATE	11.000	EACH
59	802-91122 SIGN, GROUND MOUNTED, RESET	21.000	EACH
60	805-01842 HANDHOLE, SIGNAL	8.000	EACH
61	805-02069 SIGNAL CANTILEVER STRUCTURE, 7.6 m	1.000	EACH
62	805-02073 SIGNAL CANTILEVER STRUCTURE, 10.7 m ARM	7.000	EACH
63	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
64	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 450mm	16.000	EACH
65	805-02373 INTERCONNECT CABLE, FIBER OPTIC	2,214.200	m
66	805-05698 SIGNAL SUPPORT FOUNDATION, 750 mm X 750 mm X 2100 mm	8.000	EACH
67	805-06592 CONDUIT, STEEL, GALVANIZED, 50 mm	514.600	m
68	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	2.000	EACH
69	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	12.000	EACH
70	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	4.000	EACH
71	805-78370 PEDESTRIAN PUSH BUTTON	16.000	EACH
72	805-78445 SIGNAL SERVICE	2.000	EACH
73	805-78465 SIGNAL CABLE, 2C 8GA.	27.900	m
74	805-78485 SIGNAL CABLE, 5C 14GA.	283.200	m
75	805-78490 SIGNAL CABLE, 7C 14GA.	298.400	m
76	805-78495 SIGNAL CABLE, 9C 14GA.	228.900	m
77	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	296.100	m
78	805-78746 PREFORMED LOOP DETECTORS	2,949.600	m
79	805-78785 SIGNAL DETECTOR HOUSING	14.000	EACH
80	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	700.900	m
81	805-78925 CONTROLLER CABINET FOUNDATION, P1	2.000	EACH
82	808-03114 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, (XING) 2.4 m	3.000	EACH
83	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	855.000	m
84	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	324.000	m
85	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 200 mm	482.000	m
86	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	215.000	m
87	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	2,963.000	m
88	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	266.000	m
89	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	22.000	EACH
90	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	21.000	EACH
91	808-75330 PAVEMENT MESSAGE MARKINGS THERMOPLASTIC, WORD (PEDX)	3.000	EACH
92	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	340.000	EACH
93	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	1,073.000	m
94	808-96016 LINE, THERMOPLASTIC, SOLID, YELLOW, 300 mm	244.000	m

CALL ORDER : 430

CONTRACT ID : R -31819-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	MICROSURFACING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	304-07490 HMA PATCHING, TYPE B	200.000	TON
12	402-07451 HMA WEDGE AND LEVEL, TYPE B	175.000	TON
13	406-05520 ASPHALT FOR TACK COAT	1.000	TON
14	411-08438 MICRO-SURFACING, WARRANTED	154,800.000	SYS
15	628-09402 FIELD OFFICE, B	6.000	MOS
16	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
17	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
18	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	6,630.000	LFT
19	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,630.000	LFT
20	801-06640 CONSTRUCTION SIGN, A	45.000	EACH
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	808-02066 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID WHITE CROSSHATCH	50.000	LFT
23	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
24	808-04723 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 4 IN.	200.000	LFT
25	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	9,061.000	LFT
26	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	132,810.000	LFT
27	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	96,567.000	LFT
28	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	24.000	LFT
29	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	45.000	LFT
30	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,374.000	EACH
31	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,343.000	EACH

CALL ORDER : 440

CONTRACT ID : R -31834-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SLIDE CORRECTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	203-02000 EXCAVATION, COMMON	6,608.000	CYS
9	205-09543 NO 2 STONE	431.000	TON
10	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	381.000	TON
11	303-04470 CRUSHED STONE, 11	1,374.000	TON
12	404-05514 SEAL COAT, 5	2,592.000	SYS
13	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
14	616-06405 RIPRAP, REVETMENT	10,784.000	TON
15	628-09401 FIELD OFFICE, A	4.000	MOS
16	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	50.000	LFT
17	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	20.000	LFT
18	718-52610 AGGREGATE FOR UNDERDRAINS	11.100	CYS
19	718-99153 GEOTEXTILES FOR UNDERDRAIN	61.100	SYS
20	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
21	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
22	801-06625 DETOUR ROUTE MARKER ASSEMBLY	21.000	EACH
23	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
25	801-07119 BARRICADE, III-B	48.000	LFT

CALL ORDER : 470

CONTRACT ID : RS-28233-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	AUXILARY LANES, PASSING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	560.000	CYS
10	205-03371 SEDIMENT, REMOVE	10.000	CYS
11	205-06937 TEMPORARY SILT FENCE	900.000	LFT
12	205-09235 TEMPORARY FILTER BAG	14.000	DAY
13	205-09543 NO 2 STONE	40.000	TON
14	207-08263 SUBGRADE TREATMENT, TYPE IA	1,437.000	SYS
15	211-02050 B BORROW	255.000	CYS
16	211-09265 STRUCTURE BACKFILL, TYPE 2	3.000	CYS
17	214-07202 GEOGRID, I	720.000	SYS
18	303-01180 COMPACTED AGGREGATE, NO. 53	480.000	TON
19	303-07449 COMPACTED AGGREGATE, NO. 73	260.000	TON
20	304-07494 WIDENING WITH HMA, TYPE C	260.000	TON
21	402-07434 HMA SURFACE, TYPE C	77.000	TON
22	402-07439 HMA INTERMEDIATE, TYPE C	130.000	TON
23	402-07442 HMA BASE, TYPE C	575.000	TON
24	406-05520 ASPHALT FOR TACK COAT	1.000	TON
25	615-06490 RIGHT OF WAY MARKER	2.000	EACH
26	615-06505 MONUMENT, B	2.000	EACH
27	616-07266 COIR ROLL	20.000	LFT
28	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
29	621-06557 SEED MIXTURE, T	135.000	LBS
30	621-06559 MULCHED SEEDING, R	786.000	SYS
31	621-06567 WATER	1.000	KGAL
32	621-06575 SODDING, NURSERY	48.000	SYS
33	622-98200 SIGN, DO NOT DISTURB	2.000	EACH
34	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
35	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
36	714-09420 CONCRETE CULVERT EXTENSION, PRECAST REINFORCED	6.000	LFT
37	715-97921 GRATED BOX END SECTION, I, 4:1, 57 IN. X 38 IN.	1.000	EACH
38	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
39	801-03291 CONSTRUCTION SIGN, D	2.000	EACH
40	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,933.000	LFT
41	801-06640 CONSTRUCTION SIGN, A	19.000	EACH
42	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	1,210.000	LFT
45	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	48.000	LFT
46	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	25.000	LFT
47	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
48	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,495.000	LFT
49	808-06716 LINE, REMOVE	4,875.000	LFT

CALL ORDER : 470

CONTRACT ID : RS-28233-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	AUXILARY LANES, PASSING		
50 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	469.000	LFT
51 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,456.000	LFT
52 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	44.000	EACH
53 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	44.000	EACH

CALL ORDER : 480

CONTRACT ID : RS-30278-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-02241 GUARDRAIL, REMOVE	3,197.000	LFT
15	202-02278 CURB, CONCRETE, REMOVE	350.000	LFT
16	202-02676 TRANSPORTATION OF SALVAGEABLE MILLED MATERIAL	1,500.000	TON
17	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
18	202-52710 SIDEWALK, CONCRETE, REMOVE	246.000	SYS
19	202-93741 GUARD RAIL END TREATMENT, REMOVE	21.000	EACH
20	203-02000 EXCAVATION, COMMON	6,000.000	CYS
21	203-02070 BORROW	2,451.000	CYS
22	205-03371 SEDIMENT, REMOVE	321.000	CYS
23	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	20.000	TON
24	205-06936 TEMPORARY SEDIMENT TRAP	108.000	TON
25	205-06937 TEMPORARY SILT FENCE	3,700.000	LFT
26	205-09543 NO 2 STONE	40.000	TON
27	207-08263 SUBGRADE TREATMENT, TYPE IA	5,041.000	SYS
28	210-07095 TEMPORARY	LUMP	LUMP
29	211-09264 STRUCTURE BACKFILL, TYPE 1	4.000	CYS
30	211-09268 STRUCTURE BACKFILL, TYPE 5	1,112.000	CYS
31	214-07202 GEOGRID, I	3,233.000	SYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,489.000	TON
33	303-01180 COMPACTED AGGREGATE, NO. 53	2,234.000	TON
34	304-07490 HMA PATCHING, TYPE B	4,930.000	TON
35	306-08033 MILLING, ASPHALT, 1 IN.	212,275.000	SYS
36	306-08034 MILLING, ASPHALT, 1 1/2 IN.	138.000	SYS
37	306-08043 MILLING, TRANSITION	1,147.000	SYS
38	306-08432 MILLING, APPROACH	10,437.000	SYS
39	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
40	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	17,500.000	TON
41	402-07433 HMA SURFACE, TYPE B	463.000	TON
42	402-07438 HMA INTERMEDIATE, TYPE B	491.000	TON
43	402-07441 HMA BASE, TYPE B	1,557.000	TON
44	402-07451 HMA WEDGE AND LEVEL, TYPE B	3,681.000	TON
45	402-07453 HMA FOR TEMPORARY PAVEMENT	322.000	TON
46	404-05511 SEAL COAT, 2	1,651.000	SYS
47	406-05520 ASPHALT FOR TACK COAT	206.240	TON
48	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
49	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	2.000	EACH

CALL ORDER : 480

CONTRACT ID : RS-30278-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	601-06854 GUARDRAIL, W-BEAM, NESTED	9.000	EACH
51	601-94689 GUARDRAIL END TREATMENT, OS	32.000	EACH
52	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	2,479.000	LFT
53	604-07894 CURB RAMP, CONCRETE, A	65.000	SYS
54	604-07897 CURB RAMP, CONCRETE, C	15.000	SYS
55	604-07901 CURB RAMP, CONCRETE, G	13.000	SYS
56	604-07902 CURB RAMP, CONCRETE, H	32.000	SYS
57	604-07903 CURB RAMP, CONCRETE, K	19.000	SYS
58	604-91531 SIDEWALK, CONCRETE, 4 IN.	55.000	SYS
59	605-06120 CURB, CONCRETE	330.000	LFT
60	610-07487 HMA FOR APPROACHES, TYPE B	883.000	TON
61	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	3.760	TON
62	612-60410 DRILLED HOLE FOR UNDERSEAL	64.000	EACH
63	615-06490 RIGHT OF WAY MARKER	24.000	EACH
64	615-06505 MONUMENT, B	6.000	EACH
65	616-02320 GEOTEXTILES	1,535.000	SYS
66	616-06405 RIPRAP, REVETMENT	287.000	TON
67	616-06451 RIPRAP, UNIFORM	760.000	TON
68	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.000	EACH
69	621-02770 EROSION CONTROL BLANKET	780.000	SYS
70	621-06545 FERTILIZER	2.180	TON
71	621-06553 SEED MIXTURE, R	561.000	LBS
72	621-06557 SEED MIXTURE, T	487.000	LBS
73	621-06559 MULCHED SEEDING, R	1,524.000	SYS
74	621-06565 MULCHING MATERIAL	7.930	TON
75	621-06567 WATER	2.680	KGAL
76	621-06574 SODDING	524.000	SYS
77	621-06575 SODDING, NURSERY	100.000	SYS
78	622-52436 SIGN, DO NOT MOW OR SPRAY	9.000	EACH
79	622-91786 SEEDLING	178.000	EACH
80	622-98200 SIGN, DO NOT DISTURB	12.000	EACH
81	628-09402 FIELD OFFICE, B	12.000	MOS
82	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
83	706-08188 RAILING, TR	156.000	LFT
84	714-08514 WINGWALL	211.000	SFT
85	714-09185 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 18 FT. X 10 FT.	48.000	LFT
86	714-09524 CULVERT, PRECAST BOX, REINFORCED CONCRETE,	70.000	LFT
87	714-26718 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 10 FT. X 6 FT.	56.000	LFT
88	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	5.000	LFT
89	715-05052 PIPE, TYPE 4, CIRCULAR, 12 IN.	5.000	LFT
90	715-05208 PIPE, TYPE 4, CIRCULAR, 15 IN.	10.000	LFT
91	715-46000 PIPE END SECTION, 12 IN.	1.000	EACH
92	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
93	715-90325 PIPE END SECTION, 10 IN.	1.000	EACH
94	723-08608 WINGWALL	1,426.100	SFT
95	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
96	801-02617 TEMPORARY POLE, WOOD, WITH DOWN GUYS AND ANCHORS	19.000	EACH
97	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
98	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH

CALL ORDER : 480

CONTRACT ID : RS-30278-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SMALL STRUCTURE REPLACEMENT			
99	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	12,950.000 LFT
100	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	18,151.000 LFT
101	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	60.000 LFT
102	801-06640	CONSTRUCTION SIGN, A	107.000 EACH
103	801-06645	CONSTRUCTION SIGN, B	10.000 EACH
104	801-06775	MAINTAINING TRAFFIC	LUMP LUMP
105	801-07119	BARRICADE, III-B	40.000 LFT
106	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3,863.000 LFT
107	801-08508	TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	155.000 LFT
108	801-53072	TEMPORARY TRAFFIC SIGNAL	LUMP LUMP
109	802-05702	SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	33.000 LFT
110	802-07060	SIGN, SHEET, RELOCATE	2.000 EACH
111	804-06770	DELINEATOR POST	9.000 EACH
112	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	13,392.000 LFT
113	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	131,766.000 LFT
114	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	45,375.000 LFT
115	808-06716	LINE, REMOVE	644.000 LFT
116	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	380.000 LFT
117	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	50.000 LFT
118	808-75340	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	4.000 EACH
119	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,158.000 EACH
120	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1,188.000 EACH

CALL ORDER : 520

CONTRACT ID : B -29211-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE, OTHER		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
10	203-02000 EXCAVATION, COMMON	400.000	m3
11	203-02070 BORROW	100.000	m3
12	205-03371 SEDIMENT REMOVE	75.000	m3
13	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	17.700	Mg
14	207-08263 SUBGRADE TREATMENT, TYPE IA	1,649.000	m2
15	211-09266 STRUCTURE BACKFILL, TYPE 3	125.000	m3
16	211-09267 STRUCTURE BACKFILL, TYPE 4	75.000	m3
17	211-09268 STRUCTURE BACKFILL, TYPE 5	180.000	m3
18	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,010.000	Mg
19	402-07434 HMA SURFACE, TYPE C	126.000	Mg
20	402-07439 HMA INTERMEDIATE, TYPE C	33.000	Mg
21	402-07442 HMA BASE, TYPE C	456.000	Mg
22	406-05520 ASPHALT FOR TACK COAT	0.500	Mg
23	601-06854 GUARDRAIL, W-BEAM, NESTED	61.340	EACH
24	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
25	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	4.000	EACH
26	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	194.310	m
27	615-06490 RIGHT OF WAY MARKER	6.000	EACH
28	616-02320 GEOTEXTILES	491.000	m2
29	616-06405 RIPRAP, REVETMENT	682.000	Mg
30	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
31	621-02770 EROSION CONTROL BLANKET	1,014.000	m2
32	621-06545 FERTILIZER	0.560	Mg
33	621-06554 SEED MIXTURE, U	81.000	kg
34	621-06557 SEED MIXTURE, T	50.000	kg
35	621-06565 MULCHING MATERIAL	5.000	Mg
36	621-06567 WATER	11.000	kL
37	621-06574 SODDING	31.000	m2
38	628-09401 FIELD OFFICE, A	6.000	MOS
39	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
40	714-08514 WINGWALL	54.820	m2
41	723-08119 STRUCTURE, PRECAST THREE-SIDED, 7310 mm X 2740 mm	22.900	m
42	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
43	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
44	801-06625 DETOUR ROUTE MARKER ASSEMBLY	22.000	EACH
45	801-06640 CONSTRUCTION SIGN, A	29.000	EACH
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	801-07118 BARRICADE, III-A	16.000	m
48	801-07119 BARRICADE, III-B	75.000	m
49	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	560.000	m

SCHEDULE OF PAY ITEMS

CALL ORDER : 520

CONTRACT ID : B -29211-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE, OTHER		
50 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	560.000	m

CALL ORDER : 530

CONTRACT ID : B -29290-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	9.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	900.000	LFT
13	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
14	203-02000 EXCAVATION, COMMON	1,606.000	CYS
15	203-02070 BORROW	4,769.000	CYS
16	203-51223 EXCAVATION, WATERWAY	133.000	CYS
17	205-03371 SEDIMENT, REMOVE	96.000	CYS
18	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	31.000	TON
19	205-06936 TEMPORARY SEDIMENT TRAP	87.000	TON
20	205-06937 TEMPORARY SILT FENCE	1,615.000	LFT
21	205-06938 TEMPORARY SLOPE DRAIN	98.000	LFT
22	205-09543 NO 2 STONE	100.000	TON
23	206-51220 EXCAVATION, WET	36.000	CYS
24	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	26.000	CYS
25	206-51817 SHEET PILING, STEEL	1,900.000	SFT
26	207-08263 SUBGRADE TREATMENT, TYPE IA	3,875.000	SYS
27	211-06467 AGGREGATE FOR END BENT BACKFILL	92.000	CYS
28	211-09264 STRUCTURE BACKFILL, TYPE 1	101.000	CYS
29	211-09266 STRUCTURE BACKFILL, TYPE 3	248.000	CYS
30	302-07455 DENSE GRADED SUBBASE	33.000	CYS
31	303-52308 COMPACTED AGGREGATE, O, 53	2,125.000	TON
32	306-08043 MILLING, TRANSITION	267.000	SYS
33	402-07433 HMA SURFACE, TYPE B	306.000	TON
34	402-07438 HMA INTERMEDIATE, TYPE B	401.000	TON
35	402-07441 HMA BASE, TYPE B	777.000	TON
36	406-05520 ASPHALT FOR TACK COAT	0.940	TON
37	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
38	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
39	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	668.750	LFT
40	602-06729 BARRIER DELINEATOR	10.000	EACH
41	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	336.000	SYS
42	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
43	615-06490 RIGHT OF WAY MARKER	19.000	EACH
44	615-06505 MONUMENT, B	2.000	EACH
45	616-02320 GEOTEXTILES	2,562.000	SYS
46	616-03472 RIPRAP, REVEMENT 18 IN.	504.000	TON
47	616-05688 RIPRAP, CLASS 1	77.000	TON
48	616-06451 RIPRAP, UNIFORM	1,167.000	TON
49	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH

CALL ORDER : 530

CONTRACT ID : B -29290-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06545 FERTILIZER	0.400	TON
51	621-06553 SEED MIXTURE, R	143.000	LBS
52	621-06565 MULCHING MATERIAL	1.680	TON
53	621-06567 WATER	4.000	kGAL
54	621-06574 SODDING	914.000	SYS
55	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
56	622-91786 SEEDLING	147.000	EACH
57	628-09402 FIELD OFFICE, B	9.000	MOS
58	701-02139 PILE, STEEL SHELL, 0.375 IN, 14 IN	2,350.000	LFT
59	701-09526 PILE, REINFORCED CONCRETE, STEEL SHELL ENCASED,	189.000	LFT
60	702-92857 CONCRETE, C, SUBSTRUCTURE	53.000	CYS
61	703-06028 REINFORCING BARS	13,036.000	LBS
62	703-06029 REINFORCING BARS, EPOXY COATED	85,731.000	LBS
63	704-51002 CONCRETE, C, SUPERSTRUCTURE	356.000	CYS
64	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
65	706-51020 CONCRETE, C, RAILING	34.000	CYS
66	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 45 IN. X 16 IN.	850.000	LFT
67	709-51821 SURFACE SEAL	LUMP	LUMP
68	715-02630 SAFETY METAL END SECTION, 6:1, 24 IN.	6.000	EACH
69	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	96.000	LFT
70	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN.	171.000	LFT
71	715-05407 PIPE, END BENT DRAIN, 6 IN.	203.000	LFT
72	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
73	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
74	801-06625 DETOUR ROUTE MARKER ASSEMBLY	50.000	EACH
75	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
76	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
77	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
78	801-07118 BARRICADE, III-A	96.000	LFT
79	801-07119 BARRICADE, III-B	96.000	LFT
80	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	44.000	LFT
81	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	4.000	EACH
82	802-07060 SIGN, SHEET, RELOCATE	6.000	EACH
83	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	5,030.000	LFT
84	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	5,030.000	LFT
85	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	28.000	EACH
86	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	28.000	EACH

CALL ORDER : 540

CONTRACT ID : B -29293-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
5	105-08523 RADIO SERVICE	12.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-02240 PAVEMENT REMOVAL	163.300	SYS
15	202-02241 GUARDRAIL, REMOVE	1,216.000	LFT
16	202-02277 GUTTER, LIP, REMOVE	1,320.000	LFT
17	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
18	202-74095 BRIDGE BRACKET ASSEMBLY, REMOVE	2.000	EACH
19	202-90413 SLOPEWALL, CONCRETE, 4 IN., REMOVE	41.000	SYS
20	202-94810 CURB TURNOUT, REMOVE	4.000	EACH
21	202-95027 IMPACT ATTENUATOR, REMOVE	2.000	EACH
22	203-02000 EXCAVATION, COMMON	54.000	CYS
23	211-06467 AGGREGATE FOR END BENT BACKFILL	55.600	CYS
24	213-04324 FLOWABLE FILL	9.400	CYS
25	302-07455 DENSE GRADED SUBBASE	24.900	CYS
26	304-07494 WIDENING WITH HMA, TYPE C	12.000	TON
27	306-08043 MILLING, TRANSITION	178.000	SYS
28	402-07452 HMA WEDGE AND LEVEL, TYPE C	288.000	TON
29	406-05521 ASPHALT FOR TACK COAT	1,556.000	SYS
30	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
31	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
32	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	940.000	LFT
33	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	4.000	EACH
34	602-06729 BARRIER DELINEATOR	16.000	EACH
35	603-06040 FENCE, FARM FIELD, 47 IN.	40.000	LFT
36	607-06335 PAVED SIDE DITCH, A	1,320.000	LFT
37	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	163.300	SYS
38	616-02320 GEOTEXTILES	158.000	SYS
39	616-06405 RIPRAP, REVETMENT	12.000	TON
40	616-51367 SLOPEWALL, CONCRETE, 4 IN.	56.800	SYS
41	619-09429 CLEAN STEEL BRIDGE, PARTIAL, TYPE 1, QP-2	310.000	SFT
42	619-09437 PAINT STEEL BRIDGE, PARTIAL, TYPE 1	310.000	SFT
43	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
44	621-06559 MULCHED SEEDING, R	3,867.000	SYS
45	621-06567 WATER	0.500	KGAL
46	621-06574 SODDING	147.000	SYS
47	628-09402 FIELD OFFICE, B	12.000	MOS
48	702-51005 CONCRETE, A, SUBSTRUCTURE	3.000	CYS
49	702-51863 FIELD DRILLED HOLE IN CONCRETE	196.000	EACH

CALL ORDER : 540

CONTRACT ID : B -29293-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
50	703-06028 REINFORCING BARS	434.000	LBS
51	703-06029 REINFORCING BARS, EPOXY COATED	68,102.000	LBS
52	704-51002 CONCRETE, C, SUPERSTRUCTURE	218.600	CYS
53	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
54	706-51020 CONCRETE, C, RAILING	43.700	CYS
55	709-51821 SURFACE SEAL	LUMP	LUMP
56	711-04121 ANCHOR BOLT, AB1	20.000	EACH
57	711-51035 STRUCTURAL STEEL	5,884.000	LBS
58	711-51864 DRILLED HOLE	600.000	EACH
59	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
60	711-96526 FIELD WELDED STUD, 0.875 IN. DIA.	891.000	EACH
61	715-05407 PIPE, END BENT DRAIN, 6 IN.	76.000	LFT
62	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
63	726-92406 BEARING ASSEMBLY, ELASTOMERIC	10.000	EACH
64	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
65	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
66	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
67	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
68	801-06640 CONSTRUCTION SIGN, A	36.000	EACH
69	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
70	801-06710 FLASHING ARROW SIGN	90.000	DAY
71	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
72	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH
73	801-07118 BARRICADE, III-A	48.000	LFT
74	801-07119 BARRICADE, III-B	48.000	LFT
75	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	1,160.000	LFT
76	802-07057 SIGN, PANEL, WITH LEGEND	28.000	SFT
77	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	4.000	EACH
78	802-76095 STRUCTURAL STEEL, BREAKAWAY	548.000	LBS
79	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	560.000	LFT
80	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	560.000	LFT
81	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,320.000	LFT
82	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,320.000	LFT

CALL ORDER : 550

CONTRACT ID : B -29355-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-01261 TESTING FOR ASBESTOS	1.000	EACH
10	202-02240 PAVEMENT REMOVAL	279.000	SYS
11	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	278.000	CYS
13	205-06937 TEMPORARY SILT FENCE	1,080.000	LFT
14	207-08263 SUBGRADE TREATMENT, TYPE IA	988.000	SYS
15	211-09265 STRUCTURE BACKFILL, TYPE 2	130.000	CYS
16	211-09268 STRUCTURE BACKFILL, TYPE 5	138.000	CYS
17	303-01180 COMPACTED AGGREGATE, NO. 53	446.000	TON
18	306-08036 MILLING, ASPHALT, 2 IN.	2,658.000	SYS
19	402-07432 HMA SURFACE, TYPE A	58.000	TON
20	402-07440 HMA BASE, TYPE A	129.000	TON
21	402-07784 HMA SURFACE, TYPE D	291.000	TON
22	402-07785 HMA INTERMEDIATE, TYPE D	263.000	TON
23	402-07786 HMA BASE, TYPE D	177.000	TON
24	406-05521 ASPHALT FOR TACK COAT	5,843.000	SYS
25	601-02800 GUARDRAIL TRANSITION, TGT	4.000	EACH
26	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
27	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	587.500	LFT
28	615-06505 MONUMENT, B	2.000	EACH
29	616-02320 GEOTEXTILES	389.000	SYS
30	616-06405 RIPRAP, REVETMENT	332.000	TON
31	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
32	621-06559 MULCHED SEEDING, R	908.000	SYS
33	628-09402 FIELD OFFICE, B	5.000	MOS
34	706-06347 RAILING, CF-1	239.000	LFT
35	714-04733 CULVERT, PRECAST, 3 SIDED, REINFORCED CONCRETE,	39.000	LFT
36	723-08608 WINGWALL	2,192.000	SFT
37	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
38	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
39	801-06625 DETOUR ROUTE MARKER ASSEMBLY	41.000	EACH
40	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
41	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
42	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
43	801-07119 BARRICADE, III-B	108.000	LFT
44	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	2,049.000	LFT
45	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	1,664.000	LFT
46	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	21.000	EACH
47	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	21.000	EACH

CALL ORDER : 560

CONTRACT ID : B -29625-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-01261 TESTING FOR ASBESTOS	1.000	EACH
13	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
14	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	34.000	SFT
15	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
16	203-02000 EXCAVATION, COMMON	2,470.000	CYS
17	203-02070 BORROW	1,860.000	CYS
18	203-51223 EXCAVATION, WATERWAY	744.000	CYS
19	205-02770 EROSION CONTROL BLANKET	2,120.000	SYS
20	205-06937 TEMPORARY SILT FENCE	731.000	LFT
21	205-08511 EROSION CONTROL	76.000	LFT
22	207-08264 SUBGRADE TREATMENT, TYPE II	4,517.000	SYS
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	735.000	SYS
24	211-06467 AGGREGATE FOR END BENT BACKFILL	106.000	CYS
25	211-09264 STRUCTURE BACKFILL, TYPE 1	889.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	701.000	TON
27	302-07455 DENSE GRADED SUBBASE	34.000	CYS
28	402-07433 HMA SURFACE, TYPE B	361.000	TON
29	402-07438 HMA INTERMEDIATE, TYPE B	407.000	TON
30	402-07441 HMA BASE, TYPE B	1,350.000	TON
31	406-05521 ASPHALT FOR TACK COAT	9,631.000	SYS
32	601-01128 GUARDRAIL TRANSITION TYPE WGB	4.000	EACH
33	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
34	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
36	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	150.000	LFT
37	602-06729 BARRIER DELINEATOR	6.000	EACH
38	603-06040 FENCE, FARM FIELD, 47 IN.	600.000	LFT
39	603-96042 FENCE GATE, FARM FIELD, 47 IN. X 24 FT.	1.000	EACH
40	605-06140 CURB AND GUTTER, CONCRETE	708.000	LFT
41	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	202.000	SYS
42	610-07487 HMA FOR APPROACHES, TYPE B	206.000	TON
43	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
44	616-02320 GEOTEXTILES	869.000	SYS
45	616-05688 RIPRAP, CLASS 1	72.000	TON
46	616-06405 RIPRAP, REVETMENT	446.000	TON
47	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
48	621-04978 SEED MIXTURE	2.000	SYS
49	621-04978 SEED MIXTURE	7.000	SYS

CALL ORDER : 560

CONTRACT ID : B -29625-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-04978 SEED MIXTURE	1.000	SYS
51	621-04978 SEED MIXTURE	1.000	SYS
52	621-06545 FERTILIZER	0.060	TON
53	621-06557 SEED MIXTURE, T	39.000	LBS
54	621-06560 MULCHED SEEDING, U	995.000	SYS
55	621-06565 MULCHING MATERIAL	2.000	TON
56	621-06567 WATER	6.000	KGAL
57	621-06574 SODDING	104.000	SYS
58	621-06575 SODDING, NURSERY	1,314.000	SYS
59	621-09528 OPEN CELL ARTICULATE BLOCK	73.000	SYS
60	622-91786 SEEDLING	105.000	EACH
61	622-98200 SIGN, DO NOT DISTURB	3.000	EACH
62	628-09402 FIELD OFFICE, B	12.000	MOS
63	701-01849 PILE, CONCRETE, STEEL SHELL ENCASED, 0.312 IN., 14 IN.	840.000	LFT
64	702-51100 DRAIN PIPE, CAST IRON, 6 IN.	190.000	LBS
65	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	644.000	LBS
66	702-92857 CONCRETE, C, SUBSTRUCTURE	28.400	CYS
67	703-06029 REINFORCING BARS, EPOXY COATED	48,349.000	LBS
68	704-51002 CONCRETE, C, SUPERSTRUCTURE	148.500	CYS
69	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	4.000	EACH
70	706-51020 CONCRETE, C, RAILING	10.500	CYS
71	707-07605 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 54 IN. X 48 IN.	267.000	LFT
72	709-51821 SURFACE SEAL	LUMP	LUMP
73	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	28.000	LFT
74	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	1,140.000	LFT
75	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	115.000	LFT
76	715-05407 PIPE, END BENT DRAIN, 6 IN.	100.000	LFT
77	715-46000 PIPE END SECTION, 12 IN.	3.000	EACH
78	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
79	720-45045 INLET, J10	3.000	EACH
80	720-45155 INLET, M10, MODIFIED	1.000	EACH
81	720-45265 PIPE CATCH BASIN, 15 IN.	2.000	EACH
82	720-45270 PIPE CATCH BASIN, 18 IN.	1.000	EACH
83	720-45340 CATCH BASIN, J10, MODIFIED	1.000	EACH
84	720-45410 MANHOLE, C4	4.000	EACH
85	720-45510 MANHOLE, C4, MODIFIED	1.000	EACH
86	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
87	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
88	801-06625 DETOUR ROUTE MARKER ASSEMBLY	8.000	EACH
89	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
90	801-07118 BARRICADE, III-A	86.000	LFT
91	801-07119 BARRICADE, III-B	132.000	LFT
92	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	6.250	SFT
93	802-76055 SIGN POST, A	13.000	LFT

CALL ORDER : 580

CONTRACT ID : B -30463-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PIPE LINER		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
9	205-03371 SEDIMENT, REMOVE	1.000	CYS
10	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
11	621-06559 MULCHED SEEDING, R	1,000.000	SYS
12	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
13	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
14	725-09071 PIPE LINER, THERMOPLASTIC, 90 IN.	215.000	LFT
15	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
16	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
17	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 640

CONTRACT ID : M -31658-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INSTITUTION AND PARK ROAD MAINTENANCE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	303-01180 COMPACTED AGGREGATE, NO. 53	123.000	TON
9	304-07489 HMA PATCHING, TYPE A	50.000	TON
10	306-08043 MILLING, TRANSITION	1,200.000	SYS
11	402-07432 HMA SURFACE, TYPE A	1,950.000	TON
12	402-07450 HMA WEDGE AND LEVEL, TYPE A	100.000	TON
13	406-05520 ASPHALT FOR TACK COAT	6.000	TON
14	610-07486 HMA FOR APPROACHES, TYPE A	7.000	TON
15	628-09402 FIELD OFFICE, B	6.000	MOS
16	720-44000 CASTING, ADJUST TO GRADE	15.000	EACH
17	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
18	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
20	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	6,828.000	LFT
21	808-75056 TRANSVERSE MARKINGS, PAINT, SOLID, WHITE, CROSSHATCH LINE,	2,036.000	LFT
22	808-97222 PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	14.000	EACH

CALL ORDER : 650

CONTRACT ID : M -31753-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 Patoka State Wildlife Area			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	303-07449 COMPACTED AGGREGATE, NO. 73	200.000	TON
9	304-07489 HMA PATCHING, TYPE A	75.000	TON
10	402-07450 HMA WEDGE AND LEVEL, TYPE A	3,650.000	TON
11	406-05520 ASPHALT FOR TACK COAT	11.000	TON
12	615-97768 PARKING BARRIER, RESET	175.000	EACH
13	628-09401 FIELD OFFICE, A	4.000	MOS
14	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	808-04723 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 4 IN.	132.000	LFT
18	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	21,110.000	LFT
19	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	26,286.000	LFT

CALL ORDER : 660

CONTRACT ID : M -31772-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO. 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO. 2	1.000	CYCL
5 623-04886	MOWING, CYCLE NO. 3	1.000	CYCL

