

CALL ORDER : 130

CONTRACT ID : IR-30710-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	48.000	MOS
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	201-90788 DEBRIS, REMOVE	LUMP	LUMP
15	201-90788 DEBRIS, REMOVE	LUMP	LUMP
16	202-01261 TESTING FOR ASBESTOS	3.000	EACH
17	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.000	EACH
18	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
19	202-02240 PAVEMENT REMOVAL	160,261.800	SYS
20	202-02241 GUARDRAIL, REMOVE	13,460.000	LFT
21	202-02278 CURB, CONCRETE, REMOVE	144.000	LFT
22	202-02279 CURB AND GUTTER, REMOVE	453.000	LFT
23	202-02286 PRESENT STRUCTURE, REMOVE	8.000	EACH
24	202-02286 PRESENT STRUCTURE, REMOVE	2.000	EACH
25	202-02637 PIPE, ABANDON AND GROUT FILL	244.000	LFT
26	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
27	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
28	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
29	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	6,700.000	SFT
30	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
31	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
32	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
33	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
34	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
35	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
36	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
37	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
38	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
39	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
40	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
41	202-51368 SLOPEWALL, REMOVE	669.000	SYS
42	202-52710 SIDEWALK, CONCRETE, REMOVE	177.000	SYS
43	202-74085 OVERHEAD SIGN STRUCTURE, TWIN CANTILEVER, REMOVE	3.000	EACH
44	202-91840 FENCE, CHAIN LINK, REMOVE	12,580.000	LFT
45	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	35.000	EACH
46	202-93974 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM, REMOVE	1.000	EACH
47	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	18,898.000	LFT
48	202-95027 IMPACT ATTENUATOR, REMOVE	2.000	EACH
49	202-96133 PIPE, REMOVE	8,935.700	LFT

CALL ORDER : 130

CONTRACT ID : IR-30710-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	202-96531 FENCE, RIGHT-OF-WAY, REMOVE	3,046.000	LFT
51	203-02000 EXCAVATION, COMMON	232,420.000	CYS
52	204-08415 STAKES, SETTLEMENT	20.000	EACH
53	205-02770 EROSION CONTROL BLANKET	2,900.000	SYS
54	205-03371 SEDIMENT, REMOVE	11,660.000	CYS
55	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	475.610	TON
56	205-06933 TEMPORARY DITCH INLET PROTECTION	17.000	EACH
57	205-06936 TEMPORARY SEDIMENT TRAP	1,089.000	TON
58	205-06937 TEMPORARY SILT FENCE	21,635.000	LFT
59	205-06938 TEMPORARY SLOPE DRAIN	64.000	LFT
60	205-09543 NO 2 STONE	1,160.000	TON
61	206-51220 EXCAVATION, WET	6,157.000	CYS
62	206-51225 EXCAVATION, DRY	775.800	CYS
63	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	2,319.700	CYS
64	206-51235 COFFERDAM	LUMP	LUMP
65	206-51235 COFFERDAM	LUMP	LUMP
66	206-51235 COFFERDAM	LUMP	LUMP
67	206-51235 COFFERDAM	LUMP	LUMP
68	207-08263 SUBGRADE TREATMENT, TYPE IA	374,365.000	SYS
69	207-08267 SUBGRADE TREATMENT, TYPE IIIA	108,789.000	SYS
70	211-02050 B BORROW	25,494.000	CYS
71	211-06467 AGGREGATE FOR END BENT BACKFILL	653.600	CYS
72	211-09264 STRUCTURE BACKFILL, TYPE 1	22,444.000	CYS
73	211-09265 STRUCTURE BACKFILL, TYPE 2	17,000.000	CYS
74	211-09266 STRUCTURE BACKFILL, TYPE 3	41,806.000	CYS
75	211-09267 STRUCTURE BACKFILL, TYPE 4	170.000	CYS
76	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	121.000	CYS
77	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	9,000.000	TON
78	302-06464 SUBBASE FOR PCCP	84,736.000	CYS
79	302-07455 DENSE GRADED SUBBASE	880.400	CYS
80	302-08562 COARSE AGGREGATE, 8	269.400	TON
81	303-01180 COMPACTED AGGREGATE, NO. 53	24,309.000	TON
82	306-08034 MILLING, ASPHALT, 1 1/2 IN.	1,167.000	SYS
83	306-08042 MILLING, SCARIFICATION/PROFILE	9,544.000	SYS
84	306-08043 MILLING, TRANSITION	2,396.000	SYS
85	306-08595 MILLING ASPHALT, 3 1/2 IN.	1,781.000	SYS
86	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	8,889.000	TON
87	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	14,902.000	TON
88	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	47,839.000	TON
89	402-07432 HMA SURFACE, TYPE A	166.000	TON
90	402-07433 HMA SURFACE, TYPE B	640.000	TON
91	402-07434 HMA SURFACE, TYPE C	1,043.000	TON
92	402-07438 HMA INTERMEDIATE, TYPE B	836.000	TON
93	402-07439 HMA INTERMEDIATE, TYPE C	1,057.000	TON
94	402-07441 HMA BASE, TYPE B	1,561.000	TON
95	402-07451 HMA WEDGE AND LEVEL, TYPE B	28.000	TON
96	406-05520 ASPHALT FOR TACK COAT	89.500	TON
97	406-05521 ASPHALT FOR TACK COAT	3,080.000	SYS

SCHEDULE OF PAY ITEMS

CALL ORDER : 130

CONTRACT ID : IR-30710-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
99	501-06324 QC/QA-PCCP, 13 IN.	337,524.000	SYS
100	502-06329 PCCP, 12 IN.	668.000	SYS
101	502-08201 PCCP, 9.5 IN.	1,420.000	SYS
102	503-05240 D-1 CONTRACTION JOINT	196,502.000	LFT
103	503-05310 TERMINAL JOINT	1,451.400	LFT
104	601-01522 GUARDRAIL TRANSITION TYPE TGB	34.000	EACH
105	601-01848 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 5	1.000	EACH
106	601-05999 CURVED TERMINAL END	5.000	EACH
107	601-06035 GUARDRAIL, RESET	543.750	LFT
108	601-06234 IMPACT ATTENUATOR, R1, W1, TL-2	1.000	EACH
109	601-06243 IMPACT ATTENUATOR, R2, W2, TL-2	1.000	EACH
110	601-07050 GUARDRAIL END TREATMENT, OS, RESET	1.000	EACH
111	601-94689 GUARDRAIL END TREATMENT, OS	6.000	EACH
112	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	26,532.600	LFT
113	602-06729 BARRIER DELINEATOR	1,364.000	EACH
114	602-06944 BARRIER, CONCRETE, 33 IN.	50.000	LFT
115	602-08603 CONCRETE BARRIER, 45 IN.	14,795.000	LFT
116	602-08605 CONCRETE BARRIER, 33 IN.	2,247.000	LFT
117	602-09465 BARRIER, CONCRETE, 45 IN., DOUBLE,	2,923.000	LFT
118	603-01932 FENCE, CHAIN LINK, 96 IN.	1,287.000	LFT
119	603-06045 FENCE, CHAIN LINK, 48 IN.	14,446.000	LFT
120	605-06121 CURB, CONCRETE, B	75.000	LFT
121	605-06144 CURB AND GUTTER, A, CONCRETE	139.000	LFT
122	605-06145 CURB AND GUTTER, B, CONCRETE	892.000	LFT
123	605-06165 CURB AND GUTTER, C, CONCRETE, MODIFIED	71.000	LFT
124	605-08636 CURB AND GUTTER, TURNOUT, COMBINED	25.000	LFT
125	605-52807 CURB AND GUTTER, COMBINED	224.000	LFT
126	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	511.200	SYS
127	609-06260 REINFORCED CONCRETE BRIDGE APPROACH, 13 IN.	4,532.600	SYS
128	610-07487 HMA FOR APPROACHES, TYPE B	48.000	TON
129	615-06505 MONUMENT, B	8.000	EACH
130	615-06510 MONUMENT, C	2.000	EACH
131	615-06515 MONUMENT, D	20.000	EACH
132	616-02320 GEOTEXTILES	27,033.000	SYS
133	616-05688 RIPRAP, CLASS 1	1,290.000	TON
134	616-06405 RIPRAP, REVETMENT	18,380.000	TON
135	616-51367 SLOPEWALL, CONCRETE, 4 IN.	236.000	SYS
136	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	122,868.000	SFT
137	619-09434 PAINT STEEL BRIDGE, TYPE 1	122,868.000	SFT
138	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	11.000	EACH
139	621-02770 EROSION CONTROL BLANKET	11,871.000	SYS
140	621-06545 FERTILIZER	15.590	TON
141	621-06554 SEED MIXTURE, U	4,661.000	LBS
142	621-06557 SEED MIXTURE, T	2,955.000	LBS
143	621-06565 MULCHING MATERIAL	127.500	TON
144	621-06567 WATER	49.170	KGAL
145	621-06574 SODDING	10,558.000	SYS

146	621-06575	SODDING, NURSERY	430.000	SYS
147	622-05640	PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN.	119.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 130

CONTRACT ID : IR-30710-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
148	622-05641	PLANT, DECIDUOUS SHRUB, OVER 36 TO 48 IN.	59.000 EACH
149	622-05644	PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 48 TO 72 IN.	15.000 EACH
150	622-05647	PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 120 IN.	2.000 EACH
151	622-05654	PLANT, PERENNIAL	579.000 EACH
152	622-05654	PLANT, PERENNIAL	889.000 EACH
153	628-09403	FIELD OFFICE, C	24.000 MOS
154	701-04732	PILE	3,928.000 LFT
155	701-06011	DYNAMIC PILE LOAD TEST	40.000 EACH
156	701-06027	TEST PILE	52.000 EACH
157	701-08152	STATIC PILE LOAD TEST	1.000 EACH
158	701-08253	PILE SLEEVES	42.000 EACH
159	701-09557	TEST PILE, DYNAMIC, PRODUCTION	1,931.000 LFT
160	701-09559	TEST PILE, DYNAMIC, RESTRIKE	40.000 EACH
161	701-09662	PILE, STEEL PIPE, 0.250 IN., 14 IN.	5,414.000 LFT
162	701-09665	PILE, STEEL PIPE, 0.375 IN., 14 IN.	3,042.000 LFT
163	701-09679	CONICAL PILE TIP, 14 IN.	204.000 EACH
164	701-09683	PILE SHOE, HP 12 X 74	242.000 EACH
165	701-09739	PILE SHOE, HP 12 X 53	68.000 EACH
166	701-09765	OBSTRUCTIONS	8.000 EACH
167	701-09766	INTEGRITY	24.000 EACH
168	701-51195	PILE, STEEL H, HP 12" X 53	3,118.000 LFT
169	701-95780	PILE, STEEL H, HP 12" X 74	6,575.000 LFT
170	702-51005	CONCRETE, A, SUBSTRUCTURE	3,642.400 CYS
171	702-51015	CONCRETE, B, FOOTINGS	883.600 CYS
172	702-51046	CONCRETE, FOUNDATION SEAL	1,501.800 CYS
173	702-51100	DRAIN PIPE, CAST IRON, 6 IN.	1,440.000 LBS
174	702-51110	GRATES, BASINS, AND FITTINGS, CAST IRON	5,152.000 LBS
175	702-51863	FIELD DRILLED HOLE IN CONCRETE	3,128.000 EACH
176	702-90915	CONCRETE, A	115.200 CYS
177	703-06028	REINFORCING BARS	298,491.000 LBS
178	703-06029	REINFORCING BARS, EPOXY COATED	3,304,965.000 LBS
179	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	3,513.000 EACH
180	704-51002	CONCRETE, C, SUPERSTRUCTURE	7,261.500 CYS
181	706-05732	CONCRETE BRIDGE RAILING TRANSITION, TBC	10.000 EACH
182	706-05734	CONCRETE BRIDGE RAILING TRANSITION, TBT	16.000 EACH
183	706-05734	CONCRETE BRIDGE RAILING TRANSITION, TBT	1.000 EACH
184	706-06342	RAILING, PS-1	449.200 LFT
185	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TPS-1	4.000 EACH
186	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	642.000 SYS
187	706-08498	REINFORCED CONCRETE MOMENT SLAB, 13 IN.	10,588.000 SYS
188	706-08502	REINFORCED CONCRETE MOMENT SLAB, 15 IN.	48.700 SYS
189	706-51020	CONCRETE, C, RAILING	848.000 CYS
190	706-51025	CONCRETE, C, RAILING	6,388.000 LFT
191	706-91664	PIPE RAILING	1,588.600 LFT
192	707-05984	STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 45 IN. X 16 IN.	1,296.000 LFT
193	707-07605	STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 54 IN. X 48 IN.	5,600.000 LFT

194	707-09382	STRUCTURAL MEMBERS, CONCRETE BULB-T	810.000	LFT
195	707-09634	STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	1,057.500	LFT
196	709-07733	ANTI-GRAFFITI COAT	LUMP	LUMP

SCHEDULE OF PAY ITEMS

PAGE 5

CALL ORDER : 130

CONTRACT ID : IR-30710-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
197	709-07733 ANTI-GRAFFITI COAT	LUMP	LUMP
198	709-07733 ANTI-GRAFFITI COAT	LUMP	LUMP
199	709-07733 ANTI-GRAFFITI COAT	LUMP	LUMP
200	709-07733 ANTI-GRAFFITI COAT	LUMP	LUMP
201	709-07733 ANTI-GRAFFITI COAT	LUMP	LUMP
202	709-07733 ANTI-GRAFFITI COAT	LUMP	LUMP
203	709-07733 ANTI-GRAFFITI COAT	LUMP	LUMP
204	709-51821 SURFACE SEAL	LUMP	LUMP
205	709-51821 SURFACE SEAL	LUMP	LUMP
206	709-51821 SURFACE SEAL	LUMP	LUMP
207	709-51821 SURFACE SEAL	LUMP	LUMP
208	709-51821 SURFACE SEAL	LUMP	LUMP
209	709-51821 SURFACE SEAL	LUMP	LUMP
210	709-51821 SURFACE SEAL	LUMP	LUMP
211	709-51821 SURFACE SEAL	LUMP	LUMP
212	709-51821 SURFACE SEAL	LUMP	LUMP
213	709-51821 SURFACE SEAL	LUMP	LUMP
214	709-51821 SURFACE SEAL	LUMP	LUMP
215	709-51821 SURFACE SEAL	LUMP	LUMP
216	709-51821 SURFACE SEAL	LUMP	LUMP
217	709-51821 SURFACE SEAL	LUMP	LUMP
218	709-51821 SURFACE SEAL	LUMP	LUMP
219	709-51821 SURFACE SEAL	LUMP	LUMP
220	709-51821 SURFACE SEAL	LUMP	LUMP
221	709-51821 SURFACE SEAL	LUMP	LUMP
222	709-51821 SURFACE SEAL	LUMP	LUMP
223	709-51821 SURFACE SEAL	LUMP	LUMP
224	709-51821 SURFACE SEAL	LUMP	LUMP
225	709-51821 SURFACE SEAL	LUMP	LUMP
226	711-04121 ANCHOR BOLT, AB1	168.000	EACH
227	711-51038 STRUCTURAL STEEL	LUMP	LUMP
228	711-51038 STRUCTURAL STEEL	LUMP	LUMP
229	711-51038 STRUCTURAL STEEL	LUMP	LUMP
230	711-51038 STRUCTURAL STEEL	LUMP	LUMP
231	711-51070 ANCHOR PLATE, AP 1	50.000	EACH
232	711-51864 DRILLED HOLE	1,080.000	EACH
233	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
234	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
235	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
236	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
237	711-96800 STUD SHEAR CONNECTORS	24,066.000	EACH
238	713-51820 TEMPORARY SUPPORT	LUMP	LUMP
239	714-02930 HEADWALL	1.000	EACH
240	714-08070 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 16 FT. X 6 FT.	309.000	LFT
241	714-08514 WINGWALL	2,580.160	SFT

242	714-09725	STRUCTURE, PRECAST REINFORCED CONCRETE	167.000	LFT
243	714-26709	CULVERT, PRECAST, REINFORCED CONCRETE BOX, 8' X 5'	3,004.000	LFT
244	714-96642	TEMPORARY RETAINING WALL	LUMP	LUMP
245	714-96642	TEMPORARY RETAINING WALL	LUMP	LUMP

SCHEDULE OF PAY ITEMS

CALL ORDER : 130

CONTRACT ID : IR-30710-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
246	715-01354	CLEAN EXISTING PIPE	200.000 LFT
247	715-02629	SAFETY METAL END SECTION, 6:1, 18 IN.	1.000 EACH
248	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	559.000 LFT
249	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	2,117.000 LFT
250	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	52,668.000 LFT
251	715-05053	PIPE, UNDERDRAIN OUTLET, 6 IN.	1,501.000 LFT
252	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	36.000 LFT
253	715-05127	PIPE, TYPE 1, CURCULAR, 42 IN.	395.000 LFT
254	715-05128	PIPE, TYPE 1, CIRCULAR, 48 IN.	702.000 LFT
255	715-05129	PIPE, TYPE 1, CIRCULAR, 54 IN.	261.000 LFT
256	715-05133	PIPE, TYPE 1, CIRCULAR, 60 IN.	234.000 LFT
257	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1,917.000 LFT
258	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	3,482.000 LFT
259	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	3,147.000 LFT
260	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	2,677.000 LFT
261	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	849.000 LFT
262	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	422.000 LFT
263	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	100.000 LFT
264	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	316.000 LFT
265	715-05407	PIPE, END BENT DRAIN, 6 IN.	876.000 LFT
266	715-05411	PIPE, SANITARY SEWER, 12 IN.	360.000 LFT
267	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	505.000 LFT
268	715-05756	PIPE EXTENSION, CIRCULAR, 12 IN.	2.000 LFT
269	715-05841	CONCRETE ANCHOR, 60 IN.	2.000 EACH
270	715-05842	CONCRETE ANCHOR, 42 IN.	2.000 EACH
271	715-06004	CONCRETE ANCHOR, 48 IN.	7.000 EACH
272	715-06492	CONCRETE ANCHOR, 54 IN.	2.000 EACH
273	715-06691	CONCRETE ANCHOR, 96 IN.	3.000 EACH
274	715-06910	PIPE, TYPE 2, CIRCULAR, 96 IN.	439.000 LFT
275	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	1.000 TON
276	715-09064	VIDEO INSPECTION FOR PIPE	6,240.000 LFT
277	715-09457	PIPE, TYPE 1, CIRCULAR, 120 IN.	294.000 LFT
278	715-09764	CONCRETE ANCHOR, 126 IN.	2.000 EACH
279	715-46000	PIPE END SECTION, 12 IN.	5.000 EACH
280	715-46005	PIPE END SECTION, 15 IN.	6.000 EACH
281	715-46010	PIPE END SECTION, 18 IN.	6.000 EACH
282	715-46020	PIPE END SECTION, 24 IN.	5.000 EACH
283	715-46030	PIPE END SECTION, 30 IN.	1.000 EACH
284	715-46040	PIPE END SECTION, 36 IN.	11.000 EACH
285	716-07630	PIPE INSTALLATION, TRENCHLESS, 12 IN.	360.000 LFT
286	716-09396	PIPE INSTALLATION, TRENCHLESS, 2 IN.	500.000 LFT
287	718-06528	OUTLET PROTECTOR, 1	73.000 EACH
288	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	9,500.000 LFT
289	718-52610	AGGREGATE FOR UNDERDRAINS	4,692.000 CYS

290	718-99153	GEOTEXTILES FOR UNDERDRAIN	39,052.000	SYS
291	720-03194	MANHOLE	8.000	EACH
292	720-03194	MANHOLE	10.000	EACH
293	720-03194	MANHOLE	2.000	EACH
294	720-07299	INLET TYPE H	11.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 130

CONTRACT ID : IR-30710-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
295	720-07300	INLET TYPE H, WITH SLOTTED DRAIN	4.000 EACH
296	720-07301	INLET TYPE HA	39.000 EACH
297	720-07302	INLET TYPE HA, WITH SLOTTED DRAIN	38.000 EACH
298	720-08628	SLOTTED DRAIN PIPE CLEANOUT PORT, TYPE II	1.000 EACH
299	720-08659	MANHOLE, C5	14.000 EACH
300	720-08659	MANHOLE, C5	9.000 EACH
301	720-08660	MANHOLE, J5, MODIFIED	7.000 EACH
302	720-08660	MANHOLE, J5, MODIFIED	7.000 EACH
303	720-08661	MANHOLE, K5, MODIFIED	2.000 EACH
304	720-08661	MANHOLE, K5, MODIFIED	4.000 EACH
305	720-08662	MANHOLE, L5, MODIFIED	1.000 EACH
306	720-09078	MANHOLE, M5, MODIFIED	1.000 EACH
307	720-09079	INLET, HA5, MODIFIED	5.000 EACH
308	720-44000	CASTING, ADJUST TO GRADE	7.000 EACH
309	720-45030	INLET, E7	1.000 EACH
310	720-45035	INLET, F7	1.000 EACH
311	720-45075	INLET, R13	1.000 EACH
312	720-45080	INLET, S14	1.000 EACH
313	720-45085	INLET, T14	1.000 EACH
314	720-45140	INLET, G7, MODIFIED	1.000 EACH
315	720-45155	INLET, M10, MODIFIED	1.000 EACH
316	720-45410	MANHOLE, C4	5.000 EACH
317	720-98174	INLET, B15	1.000 EACH
318	720-98555	INLET, C15	2.000 EACH
319	721-43235	AUTOMATIC DRAINAGE GATE, 96" X 96"	1.000 EACH
320	723-08311	STRUCTURE, PRECAST THREE-SIDED, 240 IN. X 144 IN.	238.500 LFT
321	731-93945	FACE PANELS, CONCRETE	104,401.000 SFT
322	731-93946	WALL ERECTION	104,401.000 SFT
323	731-93947	LEVELING PAD, CONCRETE	8,660.000 LFT
324	732-07653	COARSE AGGREGATE, NO. 8	5,891.000 TON
325	801-02595	CONTROLLER, RESET TIMING	12.000 EACH
326	801-03290	CONSTRUCTION SIGN, C	29.000 EACH
327	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.000 EACH
328	801-06202	TEMPORARY PANEL SIGN SUPPORTS	332.000 LFT
329	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	216,777.000 LFT
330	801-06204	TEMPORARY PAVEMENT MARKING, 5 IN.	44,425.000 LFT
331	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	128,777.000 LFT
332	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN	28,170.000 LFT
333	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	12.000 EACH
334	801-06212	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (ONLY)	4.000 EACH
335	801-06218	TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	148.000 LFT
336	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	8,475.000 LFT
337	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	LUMP LUMP

338	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	618.000	LFT
339	801-06625	DETOUR ROUTE MARKER ASSEMBLY	78.000	EACH
340	801-06640	CONSTRUCTION SIGN, A	158.000	EACH
341	801-06645	CONSTRUCTION SIGN, B	12.000	EACH
342	801-06710	FLASHING ARROW SIGN	100.000	DAY
343	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

SCHEDULE OF PAY ITEMS

CALL ORDER : 130

CONTRACT ID : IR-30710-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	BRIDGE REPLACEMENT		
344	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.000 EACH
345	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	18.000 EACH
346	801-07118	BARRICADE, III-A	244.000 LFT
347	801-07119	BARRICADE, III-B	144.000 LFT
348	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	43,480.000 LFT
349	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1,296.000 LFT
350	801-08402	TEMPORARY TRAFFIC BARRIER, TYPE 3	2,772.000 LFT
351	801-08507	TEMPORARY TRAFFIC BARRIER, TYPE 1, ANCHORED	6,908.000 LFT
352	801-08508	TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	867.000 LFT
353	801-08509	TEMPORARY TRAFFIC BARRIER, TYPE 3, ANCHORED	1,008.000 LFT
354	801-09133	TEMPORARY CHANGEABLE MESSAGE SIGN	9.000 EACH
355	801-09133	TEMPORARY CHANGEABLE MESSAGE SIGN	1.000 EACH
356	801-09282	TEMPORARY PANEL SIGNS	6,095.000 SFT
357	802-03811	OVERHEAD SIGN STRUCTURE, BOX TRUSS, RESET	6.000 EACH
358	802-04893	REFERENCE POST	36.000 EACH
359	802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	235.000 LFT
360	802-05702	SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	488.000 LFT
361	802-07057	SIGN, PANEL, WITH LEGEND	844.000 SFT
362	802-07151	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	16.000 EACH
363	802-07152	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, X	2.000 EACH
364	802-07154	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XII	2.000 EACH
365	802-08479	OVERHEAD SIGN STRUCTURE, BOX TRUSS	2.000 EACH
366	802-09459	DYNAMIC MESSAGE SIGN, STRUCTURE,	4.000 EACH
367	802-09570	SIGN, SHEET, SHEETING TYPE IX, WITH	54.000 SFT
368	802-09572	SIGN, PANEL, SHEETING TYPE IX, WITH LEGEND	3,020.000 SFT
369	802-09578	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	4.000 EACH
370	802-09580	CANTILEVER SIGN SUPPORT	2.000 EACH
371	802-09581	CANTILEVER SIGN SUPPORT FOUNDATION,	4.000 EACH
372	802-09710	BOX TRUSS SIGN STRUCTURE FOUNDATION,	6.000 EACH
373	802-09711	BOX TRUSS SIGN STRUCTURE FOUNDATION,	6.000 EACH
374	802-09712	OVERHEAD SIGN STRUCTURE, A	5.000 EACH
375	802-09713	OVERHEAD SIGN STRUCTURE, B	1.000 EACH
376	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	60.380 SFT
377	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	432.000 SFT
378	802-76045	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	40.250 SFT
379	802-76095	STRUCTURAL STEEL, BREAKAWAY	4,557.000 LBS
380	802-93388	BARRIER WALL SIGN BRACKET ASSEMBLY, MEDIAN	2.000 EACH
381	802-93389	BARRIER WALL SIGN BRACKET, SHOULDER	4.000 EACH
382	804-06725	DELINEATOR WITH POST, D1, 3 IN. DIA.	153.000 EACH
383	805-01842	HANDHOLE, SIGNAL	4.000 EACH
384	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP
385	805-04443	CONDUIT	72.500 EACH

386	805-04443	CONDUIT	293.000	EACH
387	805-04973	CONDUIT	2,509.250	LFT
388	805-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	19,208.000	LFT
389	805-06595	CONDUIT, PVC, 2 IN.	710.000	LFT
390	805-09042	POLE CIRCUIT CABLE	2,520.000	LFT
391	805-09240	TRANSPORTATION OF SALVAGEABLE	1.000	EACH
392	805-78205	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	5.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 130

CONTRACT ID : IR-30710-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
393	805-78215	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000 EACH
394	805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	1.000 EACH
395	805-78415	SPAN, CATENARY, AND TETHER	3.000 EACH
396	805-78420	DISCONNECT HANGER	3.000 EACH
397	805-78467	SIGNAL CABLE, 3C 8GA.	20.000 LFT
398	805-78470	SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,797.000 LFT
399	805-78485	SIGNAL CABLE, 5C 14GA.	709.000 LFT
400	805-78490	SIGNAL CABLE, 7C 14GA.	239.000 LFT
401	805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	1,095.000 LFT
402	805-78785	SIGNAL DETECTOR HOUSING	4.000 EACH
403	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	1,677.000 LFT
404	805-81032	SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000 EACH
405	805-87780	CIRCUIT BREAKER	10.000 EACH
406	805-95209	TRUCK, TOW	2,920.000 DAY
407	805-95296	SIGNAL HEADS, TEMPORARY, INSTALL	LUMP LUMP
408	805-97237	WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	18,171.000 LFT
409	805-98540	FOUNDATION AND ANCHOR BOLTS FOR STRAIN POLE	4.000 EACH
410	807-02191	HANDHOLE, LIGHTING	27.000 EACH
411	807-04654	LIGHT POLE	63.000 EACH
412	807-04866	LUMINAIRE	15.000 EACH
413	807-07580	WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	3,424.000 LFT
414	807-08469	LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING,	63.000 EACH
415	807-82053	UNDERPASS CIRCUIT INSTALLATION, 3 LUMINAIRES	2.000 EACH
416	807-86620	LUMINAIRE, ROADWAY, HIGH PRESSURE	119.000 EACH
417	807-86750	LUMINAIRE UNDERPASS, WALL MOUNTED, HIGH PRESSURE SODIUM, 150	6.000 EACH
418	807-86810	SERVICE POINT, II	5.000 EACH
419	807-86910	CONNECTOR KIT, UNFUSED	63.000 EACH
420	807-86915	CONNECTOR KIT, FUSED	63.000 EACH
421	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	273.000 EACH
422	807-86935	INSULATION LINK, WATERPROOFED	234.000 EACH
423	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	84.000 EACH
424	807-91507	UNDERPASS CIRCUIT INSTALLATION	LUMP LUMP
425	808-01045	LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN., 2 FT. LINE,	26.000 LFT
426	808-03178	PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	6.000 EACH
427	808-03179	PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	6.000 EACH
428	808-03631	LINE, EPOXY, SOLID, WHITE, 4 IN.	28,641.000 LFT
429	808-03632	LINE, EPOXY, SOLID, YELLOW, 4 IN.	38,294.000 LFT
430	808-05534	LINE, EPOXY, SOLID, WHITE, 8 IN.	5,212.000 LFT
431	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	392.000 LFT
432	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	3,041.000 LFT
433	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	14,180.000 LFT

434	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	4,172.000	LFT
435	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	180.000	LFT
436	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	13,158.000	LFT
437	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	4,878.000	LFT
438	808-06716	LINE, REMOVE	279,247.000	LFT
439	808-74811	LINE, EPOXY, BROKEN, WHITE, 5 IN.	33,804.000	LFT
440	808-75008	LINE, PAINT, SOLID, WHITE, 8 IN.	1,103.000	LFT
441	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	260.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 10

CALL ORDER : 130

CONTRACT ID : IR-30710-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
442	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	10,376.000 LFT
443	808-75278	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	70.000 LFT
444	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	216.000 LFT
445	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	3.000 EACH
446	808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000 EACH
447	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2,539.000 EACH
448	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1,770.000 EACH
449	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	383.000 LFT
450	808-98796	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN., 2 FT. LINE, 4 FT.	72.000 LFT

SCHEDULE OF PAY ITEMS

PAGE 11

CALL ORDER : 140

CONTRACT ID : IR-32543-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW BRIDGE			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP LUMP
2	109-08359	LIQUIDATED DAMAGES	1.000 DOL
3	109-08360	CONTRACT LIENS	1.000 DOL
4	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000 DOL
5	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000 DOL
6	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.000 DOL
7	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000 DOL
8	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP LUMP
9	201-52370	CLEARING RIGHT OF WAY	LUMP LUMP
10	203-02000	EXCAVATION, COMMON	40,790.000 CYS
11	203-02070	BORROW	830,896.000 CYS
12	203-08668	STRIP DRAIN, 12 IN.	140,000.000 LFT
13	204-08552	VIBRATING WIRE SETTLEMENT SYSTEM	7.000 EACH
14	204-08553	DATA LOGGING	7.000 EACH
15	204-08554	HAND HELD VW READOUT	2.000 EACH
16	205-03371	SEDIMENT, REMOVE	100.000 CYS
17	205-06930	SPLASHPAD, RIPRAP	54.000 TON
18	205-06931	TEMPORARY CHECK DAM, REVETMENT RIPRAP	147.000 TON
19	205-06936	TEMPORARY SEDIMENT TRAP	345.000 TON
20	205-06937	TEMPORARY SILT FENCE	9,335.000 LFT

21	205-06938	TEMPORARY SLOPE DRAIN	1,607.000	LFT
22	205-09543	NO 2 STONE	300.000	TON
23	206-51225	EXCAVATION, DRY	310.000	CYS
24	211-02050	B BORROW	94,150.000	CYS
25	211-09264	STRUCTURE BACKFILL, TYPE 1	1,711.000	CYS
26	211-09266	STRUCTURE BACKFILL, TYPE 3	114,789.000	CYS
27	215-07043	CHEMICAL MODIFICATION, SOILS	85,000.000	SYS
28	302-07455	DENSE GRADED SUBBASE	274.000	CYS
29	303-01180	COMPACTED AGGREGATE, NO. 53	475.000	TON
30	402-07453	HMA FOR TEMPORARY PAVEMENT	627.000	TON
31	602-06729	BARRIER DELINEATOR	59.000	EACH
32	607-06335	PAVED SIDE DITCH, A	1,041.000	LFT
33	609-06259	REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	1,679.000	SYS
34	616-02320	GEOTEXTILES	1,728.000	SYS
35	616-05688	RIPRAP, CLASS 1	21.000	TON
36	616-06405	RIPRAP, REVETMENT	1,369.000	TON
37	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
38	621-06557	SEED MIXTURE, T	5,850.000	LBS
39	621-06565	MULCHING MATERIAL	78.000	TON
40	628-09402	FIELD OFFICE, B	15.000	MOS
41	628-09407	FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	30.000	MOS
42	701-06011	DYNAMIC PILE LOAD TEST	5.000	EACH
43	701-09557	TEST PILE, DYNAMIC, PRODUCTION	440.000	LFT
44	701-09559	TEST PILE, DYNAMIC, RESTRIKE	5.000	EACH
45	701-09683	PILE SHOE, HP 12 X 74	150.000	EACH
46	701-95780	PILE, STEEL H, HP 12" X 74	10,210.000	LFT
47	702-51005	CONCRETE, A, SUBSTRUCTURE	902.000	CYS
48	702-51015	CONCRETE, B, FOOTINGS	145.300	CYS
49	702-92857	CONCRETE, C, SUBSTRUCTURE	1,946.000	CYS

SCHEDULE OF PAY ITEMS

PAGE 12

CALL ORDER : 140

CONTRACT ID : IR-32543-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	NEW BRIDGE			
50	703-06028	REINFORCING BARS	353,147.000	LBS
51	703-06029	REINFORCING BARS, EPOXY COATED	531,881.000	LBS
52	704-51002	CONCRETE, C, SUPERSTRUCTURE	1,309.100	CYS
53	706-05732	CONCRETE BRIDGE RAILING TRANSITION, TBC	12.000	EACH
54	706-51020	CONCRETE, C, RAILING	163.800	CYS
55	707-09286	STRUCTURAL MEMBERS, CONCRETE BULB-T	1,881.000	LFT
56	707-09598	STRUCTURAL MEMBERS, CONCRETE, BULB-T	1,277.000	LFT
57	709-51821	SURFACE SEAL	LUMP	LUMP
58	709-51821	SURFACE SEAL	LUMP	LUMP
59	709-51821	SURFACE SEAL	LUMP	LUMP
60	709-51821	SURFACE SEAL	LUMP	LUMP
61	709-51821	SURFACE SEAL	LUMP	LUMP
62	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	157.000	LFT
63	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	300.000	LFT
64	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	300.000	LFT
65	715-05051	PIPE, TYPE 4, CIRCULAR, 10 IN.	300.000	LFT
66	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	300.000	LFT
67	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	109.000	LFT
68	715-05133	PIPE, TYPE 1, CIRCULAR, 60 IN.	316.000	LFT

69	715-05141	PIPE, TYPE 1, CIRCULAR, 84 IN.	314.000	LFT
70	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	502.000	LFT
71	715-05841	CONCRETE ANCHOR, 60 IN.	2.000	EACH
72	715-05842	CONCRETE ANCHOR, 42 IN.	2.000	EACH
73	715-07150	CONCRETE ANCHOR, 84 IN.	2.000	EACH
74	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	6.000	TON
75	715-09064	VIDEO INSPECTION FOR PIPE	1,398.000	LFT
76	715-46020	PIPE END SECTION, 24 IN.	2.000	EACH
77	715-46040	PIPE END SECTION, 36 IN.	2.000	EACH
78	720-95422	MANHOLE, J4	2.000	EACH
79	724-51925	STRUCTURAL EXPANSION JOINT, SS	326.000	LFT
80	731-07016	FACE PANELS, WIRE	19,818.000	SFT
81	731-93945	FACE PANELS, CONCRETE	133,543.000	SFT
82	731-93946	WALL ERECTION	133,543.000	SFT
83	731-93947	LEVELING PAD, CONCRETE	6,052.000	LFT
84	801-03290	CONSTRUCTION SIGN, C	5.000	EACH
85	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
86	801-06625	DETOUR ROUTE MARKER ASSEMBLY	18.000	EACH
87	801-06640	CONSTRUCTION SIGN, A	20.000	EACH
88	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
89	801-07118	BARRICADE, III-A	72.000	LFT
90	801-07119	BARRICADE, III-B	48.000	LFT
91	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1,642.000	LFT
92	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3,204.000	LFT
93	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	3,204.000	LFT
94	808-06716	LINE, REMOVE	3,200.000	LFT
95	203-09747	RAMMED AGGREGATE PIER	LUMP	LUMP
96	701-04732	PILE	1,872.000	LFT
97	608-09748	PREFABRICATED VERTICAL DRAIN	776,355.000	LFT
98	207-08267	SUBGRADE TREATMENT, TYPE IIIA	1,425.000	SYS

SCHEDULE OF PAY ITEMS

PAGE 13

CALL ORDER : 210

CONTRACT ID : R -29483-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
2	105-08520	CELLULAR TELEPHONE/RADIO	1.000 EACH
3	105-08521	CELLULAR TELEPHONE/RADIO SERVICE	15.000 MOS
4	105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000 DOL
5	108-09241	STORMWATER POLLUTION PREVENTION PLAN,	LUMP
6	109-08359	LIQUIDATED DAMAGES	1.000 DOL
7	109-08360	CONTRACT LIENS	1.000 DOL
8	109-08440	QUALITY ADJUSTMENTS, HMA	1.000 DOL
9	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000 DOL
10	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000 DOL
11	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000 DOL
12	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
13	201-01015	CLEARING AND GRUBBING	LUMP
14	201-52370	CLEARING RIGHT OF WAY	LUMP
15	202-02240	PAVEMENT REMOVAL	772.000 SYS
16	202-02278	CURB, CONCRETE, REMOVE	501.000 LFT
17	202-04089	SIGN, SHEET, REMOVE	30.000 EACH
18	202-52710	SIDEWALK, CONCRETE, REMOVE	1,276.000 SYS

19	202-93047	MANHOLE, REMOVE	1.000	EACH
20	203-02000	EXCAVATION, COMMON	4,372.000	CYS
21	203-02070	BORROW	1,138.000	CYS
22	205-02237	TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	43.000	EACH
23	205-03371	SEDIMENT, REMOVE	10.000	CYS
24	205-06933	TEMPORARY DITCH INLET PROTECTION	51.000	EACH
25	205-06937	TEMPORARY SILT FENCE	1,250.000	LFT
26	207-08265	SUBGRADE TREATMENT, TYPE IIA	12,277.000	SYS
27	211-02050	B BORROW	600.000	CYS
28	211-09264	STRUCTURE BACKFILL, TYPE 1	1,582.000	CYS
29	211-09268	STRUCTURE BACKFILL, TYPE 5	11.000	CYS
30	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	63.000	CYS
31	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	1,625.000	TON
32	303-08210	COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	50.000	TON
33	304-07489	HMA PATCHING, TYPE A	50.000	TON
34	304-07492	WIDENING WITH HMA, TYPE A	2,358.000	TON
35	306-08033	MILLING, ASPHALT, 1 IN.	1,150.000	SYS
36	306-08036	MILLING, ASPHALT, 2 IN.	901.000	SYS
37	306-08038	MILLING, ASPHALT, 4 IN.	2,919.000	SYS
38	306-08042	MILLING, SCARIFICATION/PROFILE	5,734.000	SYS
39	306-08043	MILLING, TRANSITION	213.000	SYS
40	401-07320	QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,232.000	TON
41	401-07389	QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	2,053.000	TON
42	402-07440	HMA BASE, TYPE A	1,357.000	TON
43	402-07450	HMA WEDGE AND LEVEL, TYPE A	349.000	TON
44	402-07453	HMA FOR TEMPORARY PAVEMENT	107.000	TON
45	406-05521	ASPHALT FOR TACK COAT	30,513.000	SYS
46	603-03398	FENCE, RELOCATE	466.000	LFT
47	603-97461	TEMPORARY FENCE	1,600.000	LFT
48	604-02007	SIDEWALK, CONCRETE, RECONSTRUCT	43.000	SYS
49	604-06070	SIDEWALK, CONCRETE	2,220.000	SYS

SCHEDULE OF PAY ITEMS

PAGE 14

CALL ORDER : 210

CONTRACT ID : R -29483-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	ROAD REHABILITATION			
50	604-07897	CURB RAMP, CONCRETE, C	13.600	SYS
51	604-07900	CURB RAMP, CONCRETE, F	14.300	SYS
52	604-07901	CURB RAMP, CONCRETE, G	76.500	SYS
53	605-06140	CURB AND GUTTER, CONCRETE	8,887.000	LFT
54	610-07486	HMA FOR APPROACHES, TYPE A	338.000	TON
55	610-08446	PCCP FOR APPROACHES, 6 IN.	2,376.000	SYS
56	610-09108	PCCP FOR APPROACHES, 9 IN.	1,211.000	SYS
57	611-02825	MAILBOX ASSEMBLY, TRIPLE	2.000	EACH
58	611-06497	MAILBOX ASSEMBLY, SINGLE	5.000	EACH
59	611-08232	MAILBOX ASSEMBLY, SINGLE, RESET	27.000	EACH
60	611-08233	MAILBOX ASSEMBLY, DOUBLE, RESET	4.000	EACH
61	614-92148	RAILROAD TRACK	150.000	LFT
62	615-97768	PARKING BARRIER, RESET	15.000	EACH
63	616-02320	GEOTEXTILES	67.000	SYS
64	616-05689	RIPRAP, CLASS 2	4.000	TON
65	616-06405	RIPRAP, REVETMENT	12.000	TON
66	616-06451	RIPRAP, UNIFORM	16.000	TON

67	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
68	621-02363	MULCHED SEEDING, T, CONVENTIONAL MIX	8,000.000	SYS
69	621-02770	EROSION CONTROL BLANKET	223.000	SYS
70	621-06560	MULCHED SEEDING, U	7,167.000	SYS
71	621-06575	SODDING, NURSERY	1,919.000	SYS
72	622-05625	PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 48 TO	13.000	EACH
73	622-05639	PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	3.000	EACH
74	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.	3.000	EACH
75	628-09401	FIELD OFFICE, A	15.000	MOS
76	715-02628	SAFETY METAL END SECTION, 6:1, 15 IN.	1.000	EACH
77	715-02629	SAFETY METAL END SECTION, 6:1, 18 IN.	1.000	EACH
78	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	132.000	LFT
79	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	12.000	LFT
80	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	733.000	LFT
81	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	340.000	LFT
82	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	2,244.000	LFT
83	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	1,051.000	LFT
84	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	543.000	LFT
85	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	361.000	LFT
86	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	185.000	LFT
87	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	338.000	LFT
88	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	48.000	LFT
89	715-05428	PIPE, SLOTTED VANE DRAIN, 12 IN.	64.000	LFT
90	715-08282	HMA FOR STRUCTURE INSTALLATION, TYPE A	184.000	TON
91	715-08627	PIPE, TYPE 2, CIRCULAR, 4 IN.	200.000	LFT
92	715-09064	VIDEO INSPECTION FOR PIPE	7,103.000	LFT
93	715-09455	PIPE, TYPE 2, CIRCULAR, 16 IN.	1,508.000	LFT
94	715-46000	PIPE END SECTION, 12 IN.	6.000	EACH
95	715-46005	PIPE END SECTION, 15 IN.	8.000	EACH
96	715-46010	PIPE END SECTION, 18 IN.	5.000	EACH
97	715-46020	PIPE END SECTION, 24 IN.	1.000	EACH
98	715-93910	WATER SERVICE LINE, ADJUST	60.000	EACH

SCHEDULE OF PAY ITEMS

PAGE 15

CALL ORDER : 210

CONTRACT ID : R -29483-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
99	720-44000	CASTING, ADJUST TO GRADE	13.000 EACH
100	720-45030	INLET, E7	8.000 EACH
101	720-45035	INLET, F7	40.000 EACH
102	720-45040	INLET, G7	3.000 EACH
103	720-45045	INLET, J10	12.000 EACH
104	720-45055	INLET, M10	9.000 EACH
105	720-45130	INLET, E7, MODIFIED	1.000 EACH
106	720-45145	INLET, J10, MODIFIED	1.000 EACH
107	720-45155	INLET, M10, MODIFIED	6.000 EACH
108	720-45410	MANHOLE, C4	6.000 EACH
109	720-45520	MANHOLE, E4, MODIFIED	1.000 EACH
110	720-45605	STRUCTURE, MANHOLE, RECONSTRUCT	3.000 LFT
111	720-92025	MANHOLE, D2	1.000 EACH
112	720-93409	INLET, B15, MODIFIED	1.000 EACH
113	720-93411	INLET, C15, MODIFIED	1.000 EACH

114	720-98174	INLET, B15	3.000	EACH
115	720-98555	INLET, C15	7.000	EACH
116	731-93946	WALL ERECTION	45.000	SFT
117	801-03290	CONSTRUCTION SIGN, C	4.000	EACH
118	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
119	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	19,800.000	LFT
120	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	110.000	LFT
121	801-06640	CONSTRUCTION SIGN, A	29.000	EACH
122	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
123	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000	EACH
124	801-07119	BARRICADE, III-B	168.000	LFT
125	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	290.000	LFT
126	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	20.000	LFT
127	802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	293.000	LFT
128	802-07060	SIGN, SHEET, RELOCATE	23.000	EACH
129	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	197.000	SFT
130	802-76055	SIGN POST, A	318.000	LFT
131	802-90623	SIGN BRACKET FOR STREET NAME	11.000	EACH
132	802-90623	SIGN BRACKET FOR STREET NAME	3.000	EACH
133	802-97812	STREET NAME IDENTIFICATION SIGN	14.000	EACH
134	807-03594	RELOCATE EXISTING LIGHT	2.000	EACH
135	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	279.000	LFT
136	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	273.000	LFT
137	808-07845	TRANSVERSE MARKINGS	16.000	EACH
138	808-74815	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 12 IN.	566.000	LFT
139	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	9,500.000	LFT
140	808-75278	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	19.000	LFT
141	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	183.000	LFT
142	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
143	808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
144	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	201.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 16

CALL ORDER : 220

CONTRACT ID : R -30139-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 DRAINAGE DITCH CORRECTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	51.600	SYS
13	202-02278 CURB, CONCRETE, REMOVE	16.000	LFT
14	202-02279 CURB AND GUTTER, REMOVE	101.000	LFT
15	202-52710 SIDEWALK, CONCRETE, REMOVE	30.000	SYS
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	306.200	SYS
17	210-07224 VIDEO	1.000	EACH

18	210-07314	FORCE MAIN	295.000	LFT
19	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	136.000	TON
20	303-01180	COMPACTED AGGREGATE, NO. 53	17.600	TON
21	402-07433	HMA SURFACE, TYPE B	33.300	TON
22	402-07441	HMA BASE, TYPE B	99.800	TON
23	604-91531	SIDEWALK, CONCRETE, 4 IN.	46.900	SYS
24	605-06120	CURB, CONCRETE	16.000	LFT
25	605-06140	CURB AND GUTTER, CONCRETE	101.000	LFT
26	616-02320	GEOTEXTILES	235.300	SYS
27	616-94213	RIPRAP, GROUTED	139.800	SYS
28	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
29	621-06560	MULCHED SEEDING, U	2,116.000	SYS
30	628-09403	FIELD OFFICE, C	10.000	MOS
31	714-02930	HEADWALL	1.000	EACH
32	715-04612	PIPE	60.000	LFT
33	715-07317	CHECK VALVE	1.000	EACH
34	715-07317	CHECK VALVE	1.000	EACH
35	715-46020	PIPE END SECTION, 24 IN.	2.000	EACH
36	715-90052	LIFT STATION	LUMP	LUMP
37	716-01382	AIR RELEASE VALVE	1.000	EACH
38	716-07633	PIPE INSTALLATION, TRENCHLESS, 24 IN.	268.000	LFT
39	801-03290	CONSTRUCTION SIGN, C	2.000	EACH
40	801-06640	CONSTRUCTION SIGN, A	7.000	EACH
41	801-06710	FLASHING ARROW SIGN	120.000	DAY
42	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
43	801-07119	BARRICADE, III-B	40.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 17

CALL ORDER : 232

CONTRACT ID : R -30440-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	BIKE AND PEDESTRIAN		
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
2	109-08359	LIQUIDATED DAMAGES	1.000 DOL
3	109-08360	CONTRACT LIENS	1.000 DOL
4	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000 DOL
5	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000 DOL
6	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000 DOL
7	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
8	201-52370	CLEARING RIGHT OF WAY	LUMP
9	202-02240	PAVEMENT REMOVAL	66.000 SYS
10	202-02241	GUARDRAIL, REMOVE	100.000 LFT
11	202-04089	SIGN, SHEET, REMOVE	11.000 EACH
12	203-02000	EXCAVATION, COMMON	2,629.000 CYS
13	203-02070	BORROW	100.000 CYS
14	205-06931	TEMPORARY CHECK DAM, REVETMENT RIPRAP	3.000 TON
15	205-06933	TEMPORARY DITCH INLET PROTECTION	4.000 EACH
16	205-06937	TEMPORARY SILT FENCE	1,850.000 LFT
17	205-09543	NO 2 STONE	30.000 TON
18	206-51220	EXCAVATION, WET	520.000 CYS
19	206-51225	EXCAVATION, DRY	770.000 CYS
20	206-51817	SHEET PILING, STEEL	18,620.000 SFT
21	207-08267	SUBGRADE TREATMENT, TYPE IIIA	1,780.000 SYS
22	211-09264	STRUCTURE BACKFILL, TYPE 1	8.000 CYS

23	211-09265	STRUCTURE BACKFILL, TYPE 2	172.000	CYS
24	211-09266	STRUCTURE BACKFILL, TYPE 3	295.000	CYS
25	302-07455	DENSE GRADED SUBBASE	53.500	CYS
26	303-01180	COMPACTED AGGREGATE, NO. 53	685.000	TON
27	303-09527	COARSE AGGREGATE, 12	850.000	TON
28	402-07432	HMA SURFACE, TYPE A	155.000	TON
29	402-07433	HMA SURFACE, TYPE B	16.000	TON
30	402-07435	HMA INTERMEDIATE, TYPE A	240.000	TON
31	402-07438	HMA INTERMEDIATE, TYPE B	45.000	TON
32	402-07441	HMA BASE, TYPE B	12.000	TON
33	406-05520	ASPHALT FOR TACK COAT	1.000	TON
34	502-06329	PCCP, 12 IN.	122.000	SYS
35	503-05240	D-1 CONTRACTION JOINT	78.000	LFT
36	503-05310	TERMINAL JOINT	42.000	LFT
37	601-01522	GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
38	601-06854	GUARDRAIL, W-BEAM, NESTED	1.000	EACH
39	601-94689	GUARDRAIL END TREATMENT, OS	1.000	EACH
40	601-99105	GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	25.000	LFT
41	609-06259	REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	195.100	SYS
42	615-06520	MONUMENT, RE-ESTABLISH	2.000	EACH
43	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
44	621-06560	MULCHED SEEDING, U	4,850.000	SYS
45	621-06570	TOP SOIL	550.000	CYS
46	621-06574	SODDING	66.000	SYS
47	628-09402	FIELD OFFICE, B	10.000	MOS
48	702-52376	CONCRETE, C, STRUCTURES	191.900	CYS
49	703-06029	REINFORCING BARS, EPOXY COATED	51,744.000	LBS

SCHEDULE OF PAY ITEMS

PAGE 18

CALL ORDER : 232

CONTRACT ID : R -30440-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001 BIKE AND PEDESTRIAN				
50	706-01268	HANDRAIL, ALUMINUM	868.000	LFT
51	709-51821	SURFACE SEAL	LUMP	LUMP
52	712-03812	BENCH	4.000	EACH
53	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	763.000	LFT
54	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	320.000	LFT
55	715-05162	PIPE, TYPE 2, CIRCULAR, 54 IN.	10.000	LFT
56	718-52610	AGGREGATE FOR UNDERDRAINS	175.000	CYS
57	720-02485	TRENCH DRAIN	2.000	EACH
58	720-45235	CATCH BASIN, E7	4.000	EACH
59	720-45605	STRUCTURE, MANHOLE, RECONSTRUCT	5.000	LFT
60	720-95101	MANHOLE, L2	1.000	EACH
61	720-97359	WATER METER AND LINE, RELOCATE	1.000	EACH
62	801-03290	CONSTRUCTION SIGN, C	8.000	EACH
63	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
64	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	500.000	LFT
65	801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.000	EACH
66	801-06640	CONSTRUCTION SIGN, A	9.000	EACH
67	801-06645	CONSTRUCTION SIGN, B	2.000	EACH
68	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
69	801-07119	BARRICADE, III-B	120.000	LFT
70	802-05704	SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	123.600	LFT

71	802-07060	SIGN, SHEET, RELOCATE	6.000	EACH
72	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	35.300	SFT
73	805-03083	CONDUIT, RIGID, P.V.C., 1.50 IN.	50.000	LFT
74	805-90187	CONDUIT, STEEL, GALVANIZED, 4 IN.	100.000	LFT
75	805-95890	WIRE, NO. 12 COPPER, 1/C	4,252.000	LFT
76	807-02194	SERVICE POINT, II, MODIFIED	1.000	EACH
77	807-03802	LIGHT STANDARDS	12.000	EACH
78	807-03802	LIGHT STANDARDS	5.000	EACH
79	807-03968	CONDUIT, PVC, 1 IN., SCHEDULE 80, FOR ELECTRIC	1,075.000	LFT
80	807-94480	LIGHT STANDARD, INSTALL	4.000	EACH
81	808-03631	LINE, EPOXY, SOLID, WHITE, 4 IN.	240.000	LFT
82	808-03632	LINE, EPOXY, SOLID, YELLOW, 4 IN.	320.000	LFT
83	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	3.000	SYS
84	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	136.000	LFT
85	808-06716	LINE, REMOVE	200.000	LFT
86	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,200.000	LFT
87	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	61.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 19

CALL ORDER : 234

CONTRACT ID : R -30476-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, RIVERFRONT REVITALIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	14.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	105-08634 ADMINISTRATION OF UTILITY RELOCATION	LUMP	LUMP
6	109-08359 LIQUIDATED DAMAGES	1.000	DOL
7	109-08360 CONTRACT LIENS	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	203-02020 EXCAVATION, UNCLASSIFIED	1,935.000	CYS
14	203-02070 BORROW	5,385.000	CYS
15	205-03371 SEDIMENT, REMOVE	50.000	CYS
16	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
17	205-06937 TEMPORARY SILT FENCE	1,275.000	LFT
18	207-08262 SUBGRADE TREATMENT, TYPE I	3,238.000	SYS
19	210-03828 RECEPTACLE, TRASH	4.000	EACH
20	210-05533 GRATE	1.000	EACH
21	210-06752 INSTALL	4.000	EACH
22	211-09264 STRUCTURE BACKFILL, TYPE 1	240.000	CYS
23	402-07433 HMA SURFACE, TYPE B	243.000	TON
24	402-07438 HMA INTERMEDIATE, TYPE B	405.000	TON
25	402-07441 HMA BASE, TYPE B	1,296.000	TON
26	406-05520 ASPHALT FOR TACK COAT	2.300	TON
27	604-07894 CURB RAMP, CONCRETE, A	55.000	SYS
28	604-07903 CURB RAMP, CONCRETE, K	40.000	SYS
29	604-91404 SIDEWALK, CONCRETE, 5 IN.	2,333.130	SYS
30	605-04742 WALL	LUMP	LUMP
31	605-06120 CURB, CONCRETE	1,064.000	LFT

32	616-06395	RIPRAP	8.000	SYS
33	621-06570	TOP SOIL	2,119.000	CYS
34	621-07762	COMPOST AMENDED SOIL	117.000	CYS
35	622-05616	PLANT, BROADLEAF EVERGREEN, GLOBE, DWARF, OVER 18 TO 24 IN.	32.000	EACH
36	622-05654	PLANT, PERENNIAL	974.000	EACH
37	622-05654	PLANT, PERENNIAL	1,073.000	EACH
38	628-09402	FIELD OFFICE, B	14.000	MOS
39	701-09556	PILE, HELICAL	121.000	EACH
40	702-90915	CONCRETE, A	341.130	CYS
41	709-07733	ANTI-GRAFFITI COAT	LUMP	LUMP
42	712-03812	BENCH	7.000	EACH
43	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	395.000	LFT
44	720-09079	INLET, HA5, MODIFIED	1.000	EACH
45	720-45275	PIPE CATCH BASIN, 24 IN.	1.000	EACH
46	720-45410	MANHOLE, C4	2.000	EACH
47	732-04458	QUICK COUPLER WITH BOX	6.000	EACH
48	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
49	802-04314	SIGN	4.000	EACH

SCHEDULE OF PAY ITEMS

PAGE 20

CALL ORDER : 234

CONTRACT ID : R -30476-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, RIVERFRONT REVITALIZATION			
50	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	557.000	LFT
51	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	257.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 21

CALL ORDER : 240

CONTRACT ID : R -30586-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 Category Number 0001			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	13,364.000	m2
11	202-02245 TREE, 150 mm, REMOVE	11.000	EACH
12	202-02250 TREE, 250 mm, REMOVE	102.000	EACH
13	202-02255 TREE, 460 mm, REMOVE	31.000	EACH
14	202-02260 TREE, 760 mm, REMOVE	7.000	EACH
15	202-02265 TREE, 1220 mm, REMOVE	1.000	EACH
16	202-02271 HEADWALL, REMOVE	5.000	EACH
17	202-02278 CURB, CONCRETE, REMOVE	483.200	m

18	202-52710	SIDEWALK, CONCRETE, REMOVE	361.000	m2
19	202-91385	INLET, REMOVE	13.000	EACH
20	202-93994	SIGNAL MAST ARM AND POLE, REMOVE	2.000	EACH
21	202-93995	SIGNAL POLE FOUNDATION, REMOVE	2.000	EACH
22	202-96133	PIPE, REMOVE	810.000	m
23	203-02000	EXCAVATION, COMMON	16,275.000	m3
24	205-06933	TEMPORARY DITCH INLET PROTECTION	14.000	EACH
25	205-06937	TEMPORARY SILT FENCE	3,433.000	m
26	205-09543	NO 2 STONE	100.000	Mg
27	207-08263	SUBGRADE TREATMENT, TYPE IA	30,432.000	m2
28	207-08267	SUBGRADE TREATMENT, TYPE IIIA	2,622.300	m2
29	211-09264	STRUCTURE BACKFILL, TYPE 1	15,203.000	m3
30	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	208.000	Mg
31	302-06464	SUBBASE FOR PCCP	6,307.000	m3
32	302-07455	DENSE GRADED SUBBASE	183.400	m3
33	306-08034	MILLING, ASPHALT, 38 mm	1,367.000	m2
34	402-07433	HMA SURFACE, TYPE B	73.300	Mg
35	402-07434	HMA SURFACE, TYPE C	22.200	Mg
36	402-07438	HMA INTERMEDIATE, TYPE B	122.200	Mg
37	402-07439	HMA INTERMEDIATE, TYPE C	29.600	Mg
38	402-07441	HMA BASE, TYPE B	455.400	Mg
39	402-07442	HMA BASE, TYPE C	153.300	Mg
40	402-07451	HMA WEDGE AND LEVEL, TYPE B	55.000	Mg
41	402-07452	HMA WEDGE AND LEVEL, TYPE C	26.300	Mg
42	402-07453	HMA FOR TEMPORARY PAVEMENT	141.000	Mg
43	406-05521	ASPHALT FOR TACK COAT	6,746.000	m2
44	501-09107	QC/QA-PCCP, 225 mm	25,307.400	m2
45	503-05240	D-1 CONTRACTION JOINT	5,490.000	m
46	604-07901	CURB RAMP, CONCRETE, G	95.000	m2
47	604-91531	SIDEWALK, CONCRETE, 100 mm	4,465.000	m2
48	605-06090	CURB, INTEGRAL, CONCRETE	2,916.000	m
49	605-06140	CURB AND GUTTER, CONCRETE	450.000	m

SCHEDULE OF PAY ITEMS

PAGE 22

CALL ORDER : 240

CONTRACT ID : R -30586-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	Category Number 0001			
50	610-07487	HMA FOR APPROACHES, TYPE B	390.500	Mg
51	610-08446	PCCP FOR APPROACHES, 150 mm	1,954.000	m2
52	610-09108	PCCP FOR APPROACHES, 225 mm	1,356.000	m2
53	611-06497	MAILBOX ASSEMBLY, SINGLE	56.000	EACH
54	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
55	621-06545	FERTILIZER	0.740	Mg
56	621-06557	SEED MIXTURE, T	100.000	kg
57	621-06565	MULCHING MATERIAL	4.950	Mg
58	621-06567	WATER	198.100	kL
59	621-06574	SODDING	11,004.000	m2
60	628-09401	FIELD OFFICE, A	12.000	MOS
61	715-05024	PIPE, TYPE 2, CIRCULAR, 900 mm	175.000	m
62	715-05048	PIPE, TYPE 4, CIRCULAR, 150 mm	3,378.000	m
63	715-05149	PIPE, TYPE 2, CIRCULAR, 300 mm	968.000	m
64	715-05151	PIPE, TYPE 2, CIRCULAR, 375 mm	327.000	m
65	715-05152	PIPE, TYPE 2, CIRCULAR, 450 mm	207.000	m

66	715-05153	PIPE, TYPE 2, CIRCULAR, 525 mm	166.000	m
67	715-05154	PIPE, TYPE 2, CIRCULAR, 600 mm	154.000	m
68	715-05155	PIPE, TYPE 2, CIRCULAR, 675 mm	295.000	m
69	715-05156	PIPE, TYPE 2, CIRCULAR, 750 mm	179.000	m
70	715-05159	PIPE, TYPE 2, CIRCULAR, 1050 mm	31.000	m
71	715-94530	ADJUST WATER VALVE TO GRADE	15.000	EACH
72	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3,378.000	m
73	718-52610	AGGREGATE FOR UNDERDRAINS	902.000	m3
74	718-99153	GEOTEXTILES FOR UNDERDRAIN	15,438.000	m2
75	720-44000	CASTING, ADJUST TO GRADE	3.000	EACH
76	720-45130	INLET, E7, MODIFIED	12.000	EACH
77	720-45130	INLET, E7, MODIFIED	2.000	EACH
78	720-45410	MANHOLE, C4	28.000	EACH
79	720-90579	HYDRANT SETTING, RELOCATE	1.000	EACH
80	720-93409	INLET, B15, MODIFIED	12.000	EACH
81	720-93409	INLET, B15, MODIFIED	50.000	EACH
82	720-93411	INLET, C15, MODIFIED	8.000	EACH
83	720-94840	CASTING, ADJUST TO GRADE, WATER VALVE	3.000	EACH
84	720-95422	MANHOLE, J4	15.000	EACH
85	732-04596	WATER SERVICE	1.000	EACH
86	732-94780	WATER SERVICE CONNECTION	1.000	EACH
87	801-03290	CONSTRUCTION SIGN, C	20.000	EACH
88	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.000	EACH
89	801-06625	DETOUR ROUTE MARKER ASSEMBLY	50.000	EACH
90	801-06640	CONSTRUCTION SIGN, A	37.000	EACH
91	801-06645	CONSTRUCTION SIGN, B	5.000	EACH
92	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
93	801-07119	BARRICADE, III-B	118.800	m
94	801-94295	SIGNAL HEAD, RELOCATE	3.000	EACH
95	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	22.000	m2
96	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	6.000	m2
97	802-76055	SIGN POST, A	113.000	m
98	804-06770	DELINEATOR POST	2.000	EACH

SCHEDULE OF PAY ITEMS

PAGE 23

CALL ORDER : 240

CONTRACT ID : R -30586-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Category Number 0001		
99	805-01842	HANDHOLE, SIGNAL	21.000 EACH
100	805-02032	PEDESTRIAN SIGNAL HEAD, 305 mm, RELOCATE	2.000 EACH
101	805-02072	SIGNAL CANTILEVER STRUCTURE, 9.1 m ARM	2.000 EACH
102	805-02151	PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 305 mm	2.000 EACH
103	805-02328	SIGNAL CABLE, 1C 14GA.	55.000 m
104	805-02572	SIGNAL SUPPORT FOUNDATION, A	2.000 EACH
105	805-06592	CONDUIT, STEEL, GALVANIZED, 50 mm	1,671.000 m
106	805-08129	SIGNAL CABLE	43.000 m
107	805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	1.000 EACH
108	805-78485	SIGNAL CABLE, 5C 14GA.	253.000 m
109	805-78490	SIGNAL CABLE, 7C 14GA.	128.000 m
110	805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	135.000 m
111	805-78785	SIGNAL DETECTOR HOUSING	1.000 EACH
112	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	12.000 m
113	805-96121	PEDESTRIAN PUSH BUTTON AND SIGN	4.000 EACH

114	807-01878	LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	28.000	EACH
115	807-02191	HANDHOLE, LIGHTING	14.000	EACH
116	807-02782	LUMINAIRE MAST ARM, 3.7 m	1.000	EACH
117	807-07580	WIRE, NO. 4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	2,848.000	m
118	807-08317	CIRCUIT INSTALLATION, STR. NO.	4.000	EACH
119	807-08469	LIGHTING FOUNDATION CONCRETE WITH GROUNDING,	27.000	EACH
120	807-85752	LIGHT POLE, 12.2 m E.M.H., 3.1 m MAST ARM, BREAKAWAY BASE	27.000	EACH
121	807-86810	SERVICE POINT, II	2.000	EACH
122	807-86955	CABLE DUCT MARKER	15.000	EACH
123	807-87556	WIRE, THW OR TW, NO. 10 COPPER STRANDED	270.000	m
124	808-03002	LINE, EPOXY, BROKEN, WHITE, 100 mm	760.000	m
125	808-03631	LINE, EPOXY, SOLID, WHITE, 100 mm	3,200.000	m
126	808-03632	LINE, EPOXY, SOLID, YELLOW, 100 mm	3,392.000	m
127	808-07591	LINE, EPOXY, SOLID, WHITE, 600 mm	78.000	m
128	808-74807	PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	6.000	EACH
129	808-74808	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	6.000	EACH

SCHEDULE OF PAY ITEMS

PAGE 24

CALL ORDER : 250

CONTRACT ID : R -30646-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-74025 FENCE, REMOVE	2,047.000	LFT
11	202-74035 SIGN, REMOVE	17.000	EACH
12	203-02000 EXCAVATION, COMMON	99,082.000	CYS
13	204-08415 STAKES, SETTLEMENT	34.000	EACH
14	205-02770 EROSION CONTROL BLANKET	636.000	SYS
15	205-03371 SEDIMENT, REMOVE	1,000.000	CYS
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,138.000	TON
17	205-06932 TEMPORARY CHECK DAM, STRAW BALES	1,457.000	LFT
18	205-06933 TEMPORARY DITCH INLET PROTECTION	49.000	EACH
19	205-08511 EROSION CONTROL	19,352.000	LFT
20	205-09543 NO 2 STONE	750.000	TON
21	207-08263 SUBGRADE TREATMENT, TYPE IA	13,736.000	SYS
22	207-08264 SUBGRADE TREATMENT, TYPE II	29,764.000	SYS
23	207-08265 SUBGRADE TREATMENT, TYPE IIA	34,084.000	SYS
24	211-09264 STRUCTURE BACKFILL, TYPE 1	10,328.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	7,746.000	TON
26	304-07490 HMA PATCHING, TYPE B	149.000	TON
27	304-07494 WIDENING WITH HMA, TYPE C	126.000	TON
28	306-08034 MILLING, ASPHALT, 1 1/2 IN.	690.000	SYS
29	306-08043 MILLING, TRANSITION	220.000	SYS
30	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
31	401-07333 QC/QA-HMA, 2, 76, SURFACE, 9.5 mm	4,684.000	TON
32	401-07402 QC/QA-HMA, 2, 76, INTERMEDIATE, 19.0 mm	7,681.000	TON

33	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	16,810.000	TON
34	401-07429	QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	6,369.000	TON
35	402-07433	HMA SURFACE, TYPE B	1,251.000	TON
36	402-07441	HMA BASE, TYPE B	3,755.000	TON
37	406-05520	ASPHALT FOR TACK COAT	19.000	TON
38	601-01700	GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
39	601-61390	GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE,	1.000	EACH
40	601-99105	GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	581.250	LFT
41	605-06140	CURB AND GUTTER, CONCRETE	1,540.000	LFT
42	605-06210	CENTER CURB, C, CONCRETE	44.000	LFT
43	607-06385	PAVED SIDE DITCH, L	321.000	LFT
44	610-07487	HMA FOR APPROACHES, TYPE B	1,191.000	TON
45	611-06497	MAILBOX ASSEMBLY, SINGLE	5.000	EACH
46	611-06498	MAILBOX ASSEMBLY, DOUBLE	5.000	EACH
47	611-08232	MAILBOX ASSEMBLY, SINGLE, RESET	7.000	EACH
48	615-06490	RIGHT OF WAY MARKER	23.000	EACH
49	615-06505	MONUMENT, B	10.000	EACH

SCHEDULE OF PAY ITEMS

PAGE 25

CALL ORDER : 250

CONTRACT ID : R -30646-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	615-06510	MONUMENT, C	1.000 EACH
51	616-02320	GEOTEXTILES	1,123.000 SYS
52	616-05688	RIPRAP, CLASS 1	27.000 TON
53	616-06405	RIPRAP, REVETMENT	400.000 TON
54	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000 EACH
55	621-02356	SEEDING, WETLAND	656.000 LBS
56	621-06545	FERTILIZER	14.000 TON
57	621-06553	SEED MIXTURE, R	3,269.000 LBS
58	621-06557	SEED MIXTURE, T	1,981.000 LBS
59	621-06565	MULCHING MATERIAL	68.000 TON
60	621-06567	WATER	285.000 KGAL
61	621-06575	SODDING, NURSERY	8,168.000 SYS
62	628-09402	FIELD OFFICE, B	18.000 MOS
63	628-09407	FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	18.000 MOS
64	715-03475	SAFETY METAL END SECTION, 4:1, 15 IN.	4.000 EACH
65	715-04611	SAFETY METAL END SECTION, 4:1, 12 IN.	1.000 EACH
66	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	699.000 LFT
67	715-05028	PIPE, TYPE 2, CIRCULAR, 12 IN.	827.000 LFT
68	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	25,802.000 LFT
69	715-05053	PIPE, UNDERDRAIN OUTLET, 6 IN.	1,910.000 LFT
70	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	80.000 LFT
71	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	175.000 LFT
72	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	144.000 LFT
73	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	2,609.000 LFT
74	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	803.000 LFT
75	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	160.000 LFT
76	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	821.000 LFT
77	715-05820	PIPE, REINFORCED CONCRETE	77.000 LFT
78	715-09064	VIDEO INSPECTION FOR PIPE	6,395.000 LFT
79	715-46000	PIPE END SECTION, 12 IN.	2.000 EACH
80	715-46005	PIPE END SECTION, 15 IN.	25.000 EACH

81	715-46010	PIPE END SECTION, 18 IN.	7.000	EACH
82	715-46020	PIPE END SECTION, 24 IN.	2.000	EACH
83	715-46040	PIPE END SECTION, 36 IN.	11.000	EACH
84	718-06528	OUTLET PROTECTOR, 1	41.000	EACH
85	718-06529	OUTLET PROTECTOR, 2	1.000	EACH
86	718-06531	OUTLET PROTECTOR, 3	5.000	EACH
87	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	25,802.000	LFT
88	718-52610	AGGREGATE FOR UNDERDRAINS	3,013.000	CYS
89	718-99153	GEOTEXTILES FOR UNDERDRAIN	20,068.000	SYS
90	720-45030	INLET, E7	3.000	EACH
91	720-45130	INLET, E7, MODIFIED	3.000	EACH
92	720-45410	MANHOLE, C4	18.000	EACH
93	720-94840	CASTING, ADJUST TO GRADE, WATER VALVE	1.000	EACH
94	720-98555	INLET, C15	4.000	EACH
95	732-07653	COARSE AGGREGATE, NO. 8	9,482.000	TON
96	801-03290	CONSTRUCTION SIGN, C	4.000	EACH
97	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.000	EACH
98	801-06625	DETOUR ROUTE MARKER ASSEMBLY	32.000	EACH

SCHEDULE OF PAY ITEMS

PAGE 26

CALL ORDER : 250

CONTRACT ID : R -30646-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 NEW ROAD CONSTRUCTION			
99	801-06640	CONSTRUCTION SIGN, A	12.000 EACH
100	801-06645	CONSTRUCTION SIGN, B	4.000 EACH
101	801-06775	MAINTAINING TRAFFIC	LUMP LUMP
102	801-07118	BARRICADE, III-A	252.000 LFT
103	801-07119	BARRICADE, III-B	12.000 LFT
104	802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	553.500 LFT
105	802-07060	SIGN, SHEET, RELOCATE	7.000 EACH
106	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	197.640 SFT
107	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	138.000 SFT
108	802-76045	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	24.580 SFT
109	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	27,348.000 LFT
110	808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	344.000 LFT
111	808-74809	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (R X R)	2.000 EACH
112	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2,000.000 LFT
113	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	23,050.000 LFT
114	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	29.000 EACH
115	808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	26.000 EACH
116	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	5,460.000 LFT
117	808-96016	LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN.	524.000 LFT
118	808-99176	LINE, THERMOPLASTIC, SOLID, YELLOW, 24 IN.	465.000 LFT

SCHEDULE OF PAY ITEMS

PAGE 27

CALL ORDER : 260

CONTRACT ID : R -30654-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 NEW ROAD CONSTRUCTION			

1	105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
3	105-08520	CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521	CELLULAR TELEPHONE/RADIO SERVICE	36.000	MOS
5	105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08359	LIQUIDATED DAMAGES	1.000	DOL
7	109-08360	CONTRACT LIENS	1.000	DOL
8	109-08440	QUALITY ADJUSTMENTS, HMA	1.000	DOL
9	109-08441	QUALITY ADJUSTMENTS, PCCP	1.000	DOL
10	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	201-52370	CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-01261	TESTING FOR ASBESTOS	1.000	EACH
17	202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-05823	UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, UNDER 3000 GAL	1.000	EACH
19	202-99187	FENCE, FARM FIELD, REMOVE	281.000	LFT
20	203-02000	EXCAVATION, COMMON	276,375.000	CYS
21	203-02000	EXCAVATION, COMMON	9,080.000	CYS
22	204-02290	SETTLEMENT PLATE	12.000	EACH
23	204-08414	STAKES, LATERAL	48.000	EACH
24	204-08415	STAKES, SETTLEMENT	24.000	EACH
25	205-03371	SEDIMENT, REMOVE	106.000	CYS
26	205-06930	SPLASHPAD, RIPRAP	11.000	TON
27	205-06931	TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,569.000	TON
28	205-06931	TEMPORARY CHECK DAM, REVETMENT RIPRAP	7.000	TON
29	205-06932	TEMPORARY CHECK DAM, STRAW BALES	1,188.000	LFT
30	205-06933	TEMPORARY DITCH INLET PROTECTION	10.000	EACH
31	205-06934	TEMPORARY MULCHING	125.000	TON
32	205-06934	TEMPORARY MULCHING	16.000	TON
33	205-06936	TEMPORARY SEDIMENT TRAP	278.000	TON
34	205-06937	TEMPORARY SILT FENCE	525.000	LFT
35	205-06937	TEMPORARY SILT FENCE	4,200.000	LFT
36	205-06938	TEMPORARY SLOPE DRAIN	203.000	LFT
37	205-09543	NO 2 STONE	100.000	TON
38	205-09543	NO 2 STONE	100.000	TON
39	207-08262	SUBGRADE TREATMENT, TYPE I	64,133.000	SYS
40	207-08263	SUBGRADE TREATMENT, TYPE IA	2,472.000	SYS
41	207-08267	SUBGRADE TREATMENT, TYPE IIIA	462.000	SYS
42	211-02050	B BORROW	5,165.000	CYS
43	211-09264	STRUCTURE BACKFILL, TYPE 1	1,171.000	CYS
44	211-09265	STRUCTURE BACKFILL, TYPE 2	997.000	CYS
45	211-09268	STRUCTURE BACKFILL, TYPE 5	14.000	CYS
46	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	8,341.000	TON
47	302-06464	SUBBASE FOR PCCP	12,380.000	CYS
48	401-07320	QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,416.000	TON
49	401-07389	QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	2,921.000	TON

SCHEDULE OF PAY ITEMS

PAGE 28

CALL ORDER : 260

CONTRACT ID : R -30654-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
----------	-------------	----------	-------

SECTION NO. 0001 NEW ROAD CONSTRUCTION

50	401-07406	QC/QA-HMA, 1, 64, BASE, 25.0 mm	3,333.000	TON
51	406-05520	ASPHALT FOR TACK COAT	10.000	TON
52	501-06266	PROFILOGRAPH, PCCP	LUMP	LUMP
53	501-06321	QC/QA-PCCP, 10 IN.	40,768.000	SYS
54	501-06727	CORING, PCCP	LUMP	LUMP
55	503-03489	RETROFITTED TIE BARS	70.000	EACH
56	503-05240	D-1 CONTRACTION JOINT	20,397.000	LFT
57	603-06040	FENCE, FARM FIELD, 47 IN.	15,354.000	LFT
58	603-06045	FENCE, CHAIN LINK, 48 IN.	943.000	LFT
59	610-07487	HMA FOR APPROACHES, TYPE B	2,015.000	TON
60	611-06497	MAILBOX ASSEMBLY, SINGLE	1.000	EACH
61	615-06505	MONUMENT, B	3.000	EACH
62	615-06510	MONUMENT, C	10.000	EACH
63	616-02320	GEOTEXTILES	11,860.000	SYS
64	616-05688	RIPRAP, CLASS 1	157.000	TON
65	616-06405	RIPRAP, REVETMENT	4,783.000	TON
66	616-06405	RIPRAP, REVETMENT	219.000	TON
67	616-06451	RIPRAP, UNIFORM	152.000	TON
68	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
69	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
70	621-02770	EROSION CONTROL BLANKET	286.000	SYS
71	621-02770	EROSION CONTROL BLANKET	3,800.000	SYS
72	621-04258	SEED MIXTURE	15.000	LBS
73	621-04258	SEED MIXTURE	430.000	LBS
74	621-04258	SEED MIXTURE	29.000	LBS
75	621-06545	FERTILIZER	18.000	TON
76	621-06545	FERTILIZER	1.000	TON
77	621-06553	SEED MIXTURE, R	6,987.000	LBS
78	621-06555	SEED MIXTURE, P	482.000	LBS
79	621-06557	SEED MIXTURE, T	7,500.000	LBS
80	621-06557	SEED MIXTURE, T	931.000	LBS
81	621-06565	MULCHING MATERIAL	92.000	TON
82	621-06565	MULCHING MATERIAL	39.000	TON
83	621-06567	WATER	90.000	KGAL
84	621-06567	WATER	3,900.000	KGAL
85	621-06574	SODDING	21,202.000	SYS
86	621-06575	SODDING, NURSERY	1,138.000	SYS
87	621-93073	UNDERGROUND STORAGE TANK, LIQUID WASTE DISPOSAL, C	100.000	GAL
88	622-05654	PLANT, PERENNIAL	80.000	EACH
89	622-52436	SIGN, DO NOT MOW OR SPRAY	6.000	EACH
90	622-52436	SIGN, DO NOT MOW OR SPRAY	14.000	EACH
91	622-91786	SEEDLING	242.000	EACH
92	622-91786	SEEDLING	7,005.000	EACH
93	628-09402	FIELD OFFICE, B	18.000	MOS
94	703-51030	REINFORCING STEEL	530.000	LBS
95	714-09636	CULVERT, PRECAST, REINFORCED CONCRETE BOX, 14' X 12'	300.000	LFT
96	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	895.000	LFT
97	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	26,460.000	LFT
98	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	100.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 29

CALL ORDER : 260

CONTRACT ID : R -30654-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
----------	-------------	----------	-------

SECTION NO. 0001

NEW ROAD CONSTRUCTION

99	715-05051	PIPE, TYPE 4, CIRCULAR, 10 IN.	100.000	LFT
100	715-05053	PIPE, UNDERDRAIN OUTLET, 6 IN.	4,116.000	LFT
101	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	84.000	LFT
102	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	68.000	LFT
103	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	264.000	LFT
104	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	230.000	LFT
105	715-05218	PIPE, TYPE 5, CIRCULAR, 15 IN.	540.000	LFT
106	715-09064	VIDEO INSPECTION FOR PIPE	1,851.000	LFT
107	715-46000	PIPE END SECTION, 12 IN.	1.000	EACH
108	715-46005	PIPE END SECTION, 15 IN.	18.000	EACH
109	715-46040	PIPE END SECTION, 36 IN.	8.000	EACH
110	715-92537	PIPE, PVC, 8 IN.	1,039.000	LFT
111	718-06529	OUTLET PROTECTOR, 2	22.000	EACH
112	718-06531	OUTLET PROTECTOR, 3	14.000	EACH
113	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
114	718-52610	AGGREGATE FOR UNDERDRAINS	2,375.000	CYS
115	718-99153	GEOTEXTILES FOR UNDERDRAIN	23,251.000	SYS
116	719-09505	TILE INTERCEPT TRENCH EXCAVATION AND LOCATION	630.000	LFT
117	720-45070	INLET, P12A	8.000	EACH
118	720-45275	PIPE CATCH BASIN, 24 IN.	1.000	EACH
119	732-04749	CASING	520.000	LFT
120	801-03290	CONSTRUCTION SIGN, C	5.000	EACH
121	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
122	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	1,500.000	LFT
123	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,500.000	LFT
124	801-06640	CONSTRUCTION SIGN, A	12.000	EACH
125	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
126	801-07118	BARRICADE, III-A	384.000	LFT
127	801-07119	BARRICADE, III-B	32.000	LFT
128	802-04314	SIGN	1.000	EACH
129	802-04314	SIGN	1.000	EACH
130	802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	231.000	LFT
131	802-05702	SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	358.000	LFT
132	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	2.000	EACH
133	802-07060	SIGN, SHEET, RELOCATE	7.000	EACH
134	802-07127	SIGN, DOUBLE FACED, SHEET, ENCAPSULATED LENS, WITH LEGEND,	27.000	SFT
135	802-09757	SIGN, DOUBLE FACED, SHEET, ENCAPSULATED LENS,	5.000	SFT
136	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	9.000	SFT
137	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	199.000	SFT
138	802-76045	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	9.000	SFT
139	804-06770	DELINEATOR POST	24.000	EACH
140	804-06771	DELINEATOR POST, FLEXIBLE	62.000	EACH
141	808-03002	LINE, EPOXY, BROKEN, WHITE, 4 IN.	3,520.000	LFT
142	808-03631	LINE, EPOXY, SOLID, WHITE, 4 IN.	13,651.000	LFT
143	808-03632	LINE, EPOXY, SOLID, YELLOW, 4 IN.	13,570.000	LFT
144	808-06368	TRANSVERSE MARKING, REMOVE	36.000	LFT
145	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,188.000	LFT
146	808-06716	LINE, REMOVE	628.000	LFT
147	808-74805	TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	33.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 30

CALL ORDER : 260

CONTRACT ID : R -30654-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
----------	-------------	----------	-------

SECTION NO. 0001 NEW ROAD CONSTRUCTION

148	808-74807	PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	4.000	EACH
149	808-74808	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	4.000	EACH
150	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	816.000	LFT
151	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	70.000	LFT
152	808-75994	PRISMATIC REFLECTOR	14.000	EACH
153	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	175.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 300

CONTRACT ID : R -31752-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
2	105-06899	RADIO	4.000 EACH
3	105-08520	CELLULAR TELEPHONE/RADIO	4.000 EACH
4	105-08521	CELLULAR TELEPHONE/RADIO SERVICE	144.000 MOS
5	105-08523	RADIO SERVICE	144.000 MOS
6	105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000 DOL
7	108-01614	PARTNERING OVERHEAD	LUMP
8	109-08359	LIQUIDATED DAMAGES	1.000 DOL
9	109-08360	CONTRACT LIENS	1.000 DOL
10	109-08440	QUALITY ADJUSTMENTS, HMA	1.000 DOL
11	109-08441	QUALITY ADJUSTMENTS, PCCP	1.000 DOL
12	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000 DOL
13	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000 DOL
14	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.000 DOL
15	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000 DOL
16	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
17	201-52370	CLEARING RIGHT OF WAY	LUMP
18	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP
19	202-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000 EACH
20	202-02240	PAVEMENT REMOVAL	2,246.000 SYS
21	202-02273	CENTER CURB, CONCRETE, REMOVE	73.000 SYS
22	202-02637	PIPE, ABANDON AND GROUT FILL	16.420 LFT
23	202-02637	PIPE, ABANDON AND GROUT FILL	1,035.000 LFT
24	202-02637	PIPE, ABANDON AND GROUT FILL	650.000 LFT
25	202-02637	PIPE, ABANDON AND GROUT FILL	910.000 LFT
26	202-02637	PIPE, ABANDON AND GROUT FILL	962.000 LFT
27	202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP
28	202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP
29	202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP
30	202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP
31	202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP
32	202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP
33	202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP
34	202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP
35	202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP
36	202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	90.000 SFT
37	202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	1,680.000 SFT
38	202-03729	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	210.000 LFT

39	202-06580	CONTAMINATED SOIL, REMOVE	337.000	CYS
40	202-91385	INLET, REMOVE	2.000	EACH
41	202-93047	MANHOLE, REMOVE	8.000	EACH
42	203-02000	EXCAVATION, COMMON	50,597.000	CYS
43	203-02020	EXCAVATION, UNCLASSIFIED	118,519.000	CYS
44	203-02070	BORROW	406,007.000	CYS
45	204-02290	SETTLEMENT PLATE	30.000	EACH
46	205-06931	TEMPORARY CHECK DAM, REVETMENT RIPRAP	59.000	TON
47	205-06933	TEMPORARY DITCH INLET PROTECTION	12.000	EACH
48	205-06936	TEMPORARY SEDIMENT TRAP	18.000	TON
49	205-06937	TEMPORARY SILT FENCE	13,425.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 32

CALL ORDER : 300

CONTRACT ID : R -31752-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001 NEW ROAD CONSTRUCTION				
50	206-51220	EXCAVATION, WET	1,281.000	CYS
51	206-51225	EXCAVATION, DRY	1,224.000	CYS
52	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	9,552.000	CYS
53	206-51235	COFFERDAM	LUMP	LUMP
54	207-08262	SUBGRADE TREATMENT, TYPE I	51,988.000	SYS
55	207-08267	SUBGRADE TREATMENT, TYPE IIIA	2,763.000	SYS
56	210-07779	MULCH	1,782.000	CYS
57	210-08390	WATER	LUMP	LUMP
58	210-09777	JOINT	63.000	LFT
59	210-09778	SCREEN	4,040.000	LFT
60	211-02050	B BORROW	37,078.000	CYS
61	211-06467	AGGREGATE FOR END BENT BACKFILL	260.000	CYS
62	211-07454	STRUCTURE BACKFILL	2,512.000	CYS
63	211-09264	STRUCTURE BACKFILL, TYPE 1	14,589.000	CYS
64	211-09266	STRUCTURE BACKFILL, TYPE 3	56,129.000	CYS
65	214-07202	GEOGRID, I	4,991.000	SYS
66	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	6,969.000	TON
67	302-06464	SUBBASE FOR PCCP	11,258.000	CYS
68	302-07455	DENSE GRADED SUBBASE	294.000	CYS
69	302-08562	COARSE AGGREGATE, 8	1,102.000	TON
70	303-01180	COMPACTED AGGREGATE, NO. 53	2,078.000	TON
71	304-07489	HMA PATCHING, TYPE A	19.000	TON
72	304-07493	WIDENING WITH HMA, TYPE B	71.000	TON
73	306-08034	MILLING, ASPHALT, 1 1/2 IN.	5,782.000	SYS
74	401-07323	QC/QA-HMA, 4, 64, SURFACE, 9.5 mm	1,631.000	TON
75	401-07393	QC/QA-HMA, 4, 64, INTERMEDIATE, 19.0 mm	1,733.000	TON
76	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	2,368.000	TON
77	401-08338	QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm	801.000	TON
78	402-07450	HMA WEDGE AND LEVEL, TYPE A	319.000	TON
79	406-05520	ASPHALT FOR TACK COAT	12.000	TON
80	501-06322	QC/QA-PCCP, 11 IN.	43,258.000	SYS
81	501-51112	ANCHOR BOLT	44.000	EACH
82	503-05240	D-1 CONTRACTION JOINT	23,929.000	LFT
83	503-05310	TERMINAL JOINT	302.000	LFT
84	506-06333	PCCP PATCHING, FULL DEPTH	73.000	SYS
85	601-01522	GUARDRAIL TRANSITION TYPE TGB	9.000	EACH
86	601-06854	GUARDRAIL, W-BEAM, NESTED	2.000	EACH

87	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	18.000	EACH
88	601-61390	GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE,	3.000	EACH
89	601-94689	GUARDRAIL END TREATMENT, OS	6.000	EACH
90	601-95344	HANDRAIL, PEDESTRIAN	1,137.000	LFT
91	601-99105	GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,947.000	LFT
92	602-06729	BARRIER DELINEATOR	112.000	EACH
93	603-01932	FENCE, CHAIN LINK, 96 IN.	5,454.000	LFT
94	603-03829	FENCE	2,039.000	LFT
95	603-96521	FENCE GATE, CHAIN LINK, RESET	1.000	EACH
96	604-07901	CURB RAMP, CONCRETE, G	84.000	SYS
97	604-90256	SIDEWALK, CONCRETE, 6 IN.	1,185.000	SYS
98	604-91531	SIDEWALK, CONCRETE, 4 IN.	4,885.000	SYS

SCHEDULE OF PAY ITEMS

PAGE 33

CALL ORDER : 300

CONTRACT ID : R -31752-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
99	605-06095	CURB, INTEGRAL, B, CONCRETE	2,310.000 LFT
100	605-06100	CURB, INTEGRAL, C, CONCRETE	9,300.000 LFT
101	607-06335	PAVED SIDE DITCH, A	101.000 LFT
102	608-05741	WICK DRAIN	481,586.000 LFT
103	609-06259	REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	1,143.000 SYS
104	610-07487	HMA FOR APPROACHES, TYPE B	754.000 TON
105	610-08446	PCCP FOR APPROACHES, 6 IN.	89.000 SYS
106	610-09108	PCCP FOR APPROACHES, 9 IN.	862.000 SYS
107	611-02825	MAILBOX ASSEMBLY, TRIPLE	1.000 EACH
108	611-06497	MAILBOX ASSEMBLY, SINGLE	2.000 EACH
109	611-06498	MAILBOX ASSEMBLY, DOUBLE	5.000 EACH
110	616-02320	GEOTEXTILES	5,795.000 SYS
111	616-06405	RIPRAP, REVETMENT	3,221.000 TON
112	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000 EACH
113	621-02770	EROSION CONTROL BLANKET	1,147.000 SYS
114	621-04978	SEED MIXTURE	17,842.000 SYS
115	621-04978	SEED MIXTURE	14,634.000 SYS
116	621-06557	SEED MIXTURE, T	2,634.000 LBS
117	621-06560	MULCHED SEEDING, U	94,480.000 SYS
118	621-06570	TOP SOIL	5,345.000 CYS
119	621-06574	SODDING	3,220.000 SYS
120	621-06626	MULCHED SEEDING, D	3,556.000 SYS
121	622-05625	PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 48 TO	20.000 EACH
122	622-05639	PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	83.000 EACH
123	622-05640	PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN.	638.000 EACH
124	622-05641	PLANT, DECIDUOUS SHRUB, OVER 36 TO 48 IN.	38.000 EACH
125	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.	49.000 EACH
126	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	139.000 EACH
127	622-05654	PLANT, PERENNIAL	132.000 EACH
128	628-09402	FIELD OFFICE, B	36.000 MOS
129	628-09407	FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	72.000 MOS
130	701-06011	DYNAMIC PILE LOAD TEST	9.000 EACH
131	701-09557	TEST PILE, DYNAMIC, PRODUCTION	661.000 LFT
132	701-09559	TEST PILE, DYNAMIC, RESTRIKE	9.000 EACH
133	701-09683	PILE SHOE, HP 12 X 74	513.000 EACH
134	701-95780	PILE, STEEL H, HP 12" X 74	25,923.000 LFT

135	702-03607	CORED HOLE IN CONCRETE	3.000	EACH
136	702-51005	CONCRETE, A, SUBSTRUCTURE	3,377.100	CYS
137	702-51015	CONCRETE, B, FOOTINGS	1,033.800	CYS
138	702-51110	GRATES, BASINS, AND FITTINGS, CAST IRON	11,636.000	LBS
139	702-90915	CONCRETE, A	369.000	CYS
140	703-06028	REINFORCING BARS	291,954.000	LBS
141	703-06029	REINFORCING BARS, EPOXY COATED	1,436,863.000	LBS
142	704-51002	CONCRETE, C, SUPERSTRUCTURE	4,583.900	CYS
143	706-06339	RAILING, PF-1	4,507.000	LFT
144	706-06339	RAILING, PF-1	1,075.000	LFT
145	706-06343	RAILING, PS-2	937.000	LFT
146	706-06343	RAILING, PS-2	1,016.000	LFT
147	706-06343	RAILING, PS-2	108.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 34

CALL ORDER : 300

CONTRACT ID : R -31752-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	NEW ROAD CONSTRUCTION		
148	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	7.000 EACH
149	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TPS-1	1.000 EACH
150	706-06354	CONCRETE BRIDGE RAILING TRANSITION, TPS-2	4.000 EACH
151	706-08344	REINFORCED CONCRETE MOMENT SLAB	2,558.000 SYS
152	706-51020	CONCRETE, C, RAILING	469.800 CYS
153	706-92612	RAILING, CONCRETE, C, MODIFIED	1,791.000 LFT
154	707-08476	STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	11,547.000 LFT
155	707-08643	STRUCTURAL MEMBERS, CONCRETE BULB-T	761.000 LFT
156	709-51821	SURFACE SEAL	LUMP LUMP
157	709-51821	SURFACE SEAL	LUMP LUMP
158	709-51821	SURFACE SEAL	LUMP LUMP
159	711-51070	ANCHOR PLATE, AP 1	32.000 EACH
160	715-03025	SANITARY MANHOLE	9.000 EACH
161	715-03025	SANITARY MANHOLE	4.000 EACH
162	715-04612	PIPE	135.000 LFT
163	715-04612	PIPE	733.000 LFT
164	715-04612	PIPE	261.000 LFT
165	715-04612	PIPE	100.000 LFT
166	715-04664	PIPE, DUCTILE IRON, 20 IN.	840.000 LFT
167	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	3,748.000 LFT
168	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	14,369.000 LFT
169	715-05053	PIPE, UNDERDRAIN OUTLET, 6 IN.	297.000 LFT
170	715-05062	WATER SERVICE LINE	LUMP LUMP
171	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	2,777.000 LFT
172	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	1,534.000 LFT
173	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	1,261.000 LFT
174	715-05153	PIPE, TYPE 2, CIRCULAR, 21 IN.	1,117.000 LFT
175	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	262.000 LFT
176	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	646.000 LFT
177	715-05162	PIPE, TYPE 2, CIRCULAR, 54 IN.	330.000 LFT
178	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	53.000 LFT
179	715-05177	PIPE, TYPE 3, CIRCULAR, 36 IN.	106.000 LFT
180	715-05361	PIPE, TYPE 3, DEFORMED, MIN. AREA 1.1 SQ. FT.	195.000 LFT
181	715-05407	PIPE, END BENT DRAIN, 6 IN.	200.000 LFT
182	715-05408	PIPE, SANITARY SEWER, 8 IN.	287.000 LFT

183	715-05411	PIPE, SANITARY SEWER, 12 IN.	266.000	LFT
184	715-05412	PIPE, SANITARY SEWER, 15 IN.	242.000	LFT
185	715-05413	PIPE, SANITARY SEWER, 18 IN.	400.000	LFT
186	715-08048	STORMWATER TREATMENT SYSTEM	2.000	EACH
187	715-08250	PIPE, DUCTILE IRON, 12 IN.	586.000	LFT
188	715-08282	HMA FOR STRUCTURE INSTALLATION, TYPE A	776.000	TON
189	715-46000	PIPE END SECTION, 12 IN.	39.000	EACH
190	715-46005	PIPE END SECTION, 15 IN.	3.000	EACH
191	715-46015	PIPE END SECTION, 21 IN.	2.000	EACH
192	715-46040	PIPE END SECTION, 36 IN.	6.000	EACH
193	715-46045	PIPE END SECTION, MIN. AREA 1.1 SQ. FT.	8.000	EACH
194	715-90714	PIPE, PVC, 12 IN.	103.000	LFT
195	715-91361	PIPE, PVC, 6 IN.	769.000	LFT
196	715-91738	WATER MAIN, DUCTILE IRON, 6 IN.	35.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 35

CALL ORDER : 300

CONTRACT ID : R -31752-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	NEW ROAD CONSTRUCTION		
197	715-91739	WATER MAIN, DUCTILE IRON, 8 IN.	902.000 LFT
198	715-92537	PIPE, PVC, 8 IN.	1,058.000 LFT
199	715-92544	WATER MAIN, DUCTILE IRON, 12 IN.	1,244.000 LFT
200	715-96669	WATER MAIN, DUCTILE IRON, 16 IN.	3,950.000 LFT
201	715-96881	PIPE END SECTION, 54 IN.	1.000 EACH
202	716-01382	AIR RELEASE VALVE	3.000 EACH
203	716-07633	PIPE INSTALLATION, TRENCHLESS, 24 IN.	250.000 LFT
204	716-07634	PIPE INSTALLATION, TRENCHLESS, 30 IN.	598.000 LFT
205	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	299.000 LFT
206	716-09551	PIPE INSTALLATION, TRENCHLESS, 20 IN.	110.000 LFT
207	718-06528	OUTLET PROTECTOR, 1	8.000 EACH
208	718-52610	AGGREGATE FOR UNDERDRAINS	1,295.000 CYS
209	718-99153	GEOTEXTILES FOR UNDERDRAIN	15,303.000 SYS
210	720-01092	MANHOLE, J15, MODIFIED	2.000 EACH
211	720-02367	MANHOLE, J10	1.000 EACH
212	720-03988	MANHOLE, J4, DROP	2.000 EACH
213	720-44000	CASTING, ADJUST TO GRADE	4.000 EACH
214	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000 EACH
215	720-45030	INLET, E7	8.000 EACH
216	720-45041	INLET, H5	9.000 EACH
217	720-45045	INLET, J10	47.000 EACH
218	720-45055	INLET, M10	22.000 EACH
219	720-45065	INLET, N12	1.000 EACH
220	720-45155	INLET, M10, MODIFIED	1.000 EACH
221	720-45410	MANHOLE, C4	21.000 EACH
222	720-90129	MANHOLE, J2	2.000 EACH
223	720-93501	MANHOLE, L4	2.000 EACH
224	720-94612	MANHOLE, K4	1.000 EACH
225	720-95101	MANHOLE, L2	1.000 EACH
226	720-95422	MANHOLE, J4	18.000 EACH
227	720-96999	FIRE HYDRANT ASSEMBLY	8.000 EACH
228	720-98174	INLET, B15	3.000 EACH
229	720-98555	INLET, C15	1.000 EACH
230	721-43010	AUTOMATIC DRAINAGE GATE, 18 IN.	2.000 EACH

231	723-08311	STRUCTURE, PRECAST THREE-SIDED, 240 IN. X 144 IN.	90.000	LFT
232	723-08608	WINGWALL	1,548.000	SFT
233	724-51925	STRUCTURAL EXPANSION JOINT, SS	319.000	LFT
234	731-07016	FACE PANELS, WIRE	2,748.000	SFT
235	731-93945	FACE PANELS, CONCRETE	82,896.000	SFT
236	731-93946	WALL ERECTION	82,896.000	SFT
237	731-93947	LEVELING PAD, CONCRETE	2,632.000	LFT
238	732-02433	VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 12 IN.	2.000	EACH
239	732-02531	VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON 6 IN.	1.000	EACH
240	732-02532	VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 8 IN.	3.000	EACH
241	732-04926	VALVE	1.000	EACH
242	732-04926	VALVE	1.000	EACH
243	732-04926	VALVE	8.000	EACH
244	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	4.000	EACH
245	801-01505	TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (ONLY)	4.000	EACH

SCHEDULE OF PAY ITEMS

PAGE 36

CALL ORDER : 300

CONTRACT ID : R -31752-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
246	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.000 EACH
247	801-06196	DETOUR ROUTE MARKER ASSEMBLY, MULTIPLE ROUTES	53.000 EACH
248	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8,673.000 LFT
249	801-06640	CONSTRUCTION SIGN, A	22.000 EACH
250	801-06710	FLASHING ARROW SIGN	400.000 DAY
251	801-06775	MAINTAINING TRAFFIC	LUMP
252	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000 EACH
253	801-07118	BARRICADE, III-A	96.000 LFT
254	801-07119	BARRICADE, III-B	36.000 LFT
255	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	995.000 LFT
256	801-08508	TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	150.000 LFT
257	802-05704	SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	262.000 LFT
258	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	285.000 SFT
259	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	65.000 SFT
260	802-76045	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	214.000 SFT
261	805-01815	SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	8.000 EACH
262	805-01815	SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	2.000 EACH
263	805-01842	HANDHOLE, SIGNAL	26.000 EACH
264	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	4,160.000 LFT
265	805-01879	SIGNAL SERVICE, INSTALL	3.000 EACH
266	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP
267	805-02373	INTERCONNECT CABLE, FIBER OPTIC	5,000.000 LFT
268	805-02639	SIGNAL POLE, MAST ARM 20 FT.	1.000 EACH
269	805-04757	SIGNAL	1.000 EACH
270	805-04940	MAST ARM	2.000 EACH
271	805-07767	SIGNAL CABLE, 12C 14GA	1,612.000 LFT
272	805-09344	WIRELESS	2.000 EACH
273	805-09344	WIRELESS	2.000 EACH
274	805-09344	WIRELESS	1.000 EACH
275	805-09344	WIRELESS	19.000 EACH
276	805-78109	CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	3.000 EACH
277	805-78205	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	14.000 EACH

278	805-78215	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	3.000	EACH
279	805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	8.000	EACH
280	805-78415	SPAN, CATENARY, AND TETHER	9.000	EACH
281	805-78420	DISCONNECT HANGER	11.000	EACH
282	805-78467	SIGNAL CABLE, 3C 8GA.	47.000	LFT
283	805-78470	SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	11,183.000	LFT
284	805-78485	SIGNAL CABLE, 5C 14GA.	751.000	LFT
285	805-78490	SIGNAL CABLE, 7C 14GA.	389.000	LFT
286	805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	8,883.000	LFT
287	805-78785	SIGNAL DETECTOR HOUSING	24.000	EACH
288	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	3,550.000	LFT
289	805-78925	CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
290	805-81032	SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000	EACH
291	805-81060	SIGNAL STRAIN POLE, STEEL, 36 FT.	10.000	EACH
292	805-86890	POLE CIRCUIT CABLE, 1C NO. 10 THW OR TW STRANDED COPPER	5,065.000	LFT
293	805-86900	JUNCTION BOX	8.000	EACH
294	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	27.000	EACH

SCHEDULE OF PAY ITEMS

PAGE 37

CALL ORDER : 300

CONTRACT ID : R -31752-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
295	807-01878	LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	53.000 EACH
296	807-02106	LUMINAIRE, UNDERPASS, WALL MOUNTED, HIGH PRESSURE SODIUM,	14.000 EACH
297	807-02191	HANDHOLE, LIGHTING	6.000 EACH
298	807-02193	LIGHT STANDARD FOUNDATION, 3 FT. DIA. X 8 FT.	37.000 EACH
299	807-04651	WIRE	3,070.000 LFT
300	807-04651	WIRE	2,210.000 LFT
301	807-04653	LIGHTING FOUNDATION	16.000 EACH
302	807-04654	LIGHT POLE	16.000 EACH
303	807-04654	LIGHT POLE	37.000 EACH
304	807-07580	WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	7,464.000 LFT
305	807-08214	CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	3,070.000 LFT
306	807-82051	UNDERPASS CIRCUIT INSTALLATION, 1 LUMINAIRE	2.000 EACH
307	807-82052	UNDERPASS CIRCUIT INSTALLATION, 2 LUMINAIRES	6.000 EACH
308	807-86805	SERVICE POINT, I	1.000 EACH
309	807-86810	SERVICE POINT, II	2.000 EACH
310	807-86905	TRANSITION FITTINGS, GALVANIZED STEEL CONDUIT TO PLASTIC	2.000 EACH
311	807-86910	CONNECTOR KIT, UNFUSED	53.000 EACH
312	807-86915	CONNECTOR KIT, FUSED	53.000 EACH
313	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	132.000 EACH
314	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	16.000 EACH
315	807-86930	INSULATION LINK, NONWATERPROOFED	106.000 EACH
316	807-86935	INSULATION LINK, WATERPROOFED	24.000 EACH
317	807-86955	CABLE DUCT MARKER	8.000 EACH
318	808-03002	LINE, EPOXY, BROKEN, WHITE, 4 IN.	3,226.000 LFT
319	808-03631	LINE, EPOXY, SOLID, WHITE, 4 IN.	22,207.000 LFT
320	808-03632	LINE, EPOXY, SOLID, YELLOW, 4 IN.	18,583.000 LFT
321	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	448.000 LFT
322	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	6,169.000 LFT
323	808-06716	LINE, REMOVE	5,973.000 LFT
324	808-06800	TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW, CROSSHATCH LINE,	303.000 LFT
325	808-74805	TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	327.000 LFT

326	808-74807	PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	18.000	EACH
327	808-74808	PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	8.000	EACH
328	808-75067	TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	157.000	LFT
329	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	326.000	LFT
330	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6,056.000	LFT
331	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	106.000	LFT
332	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	19.000	EACH
333	808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH
334	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1,062.000	LFT
335	808-94455	TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 6 IN.	166.000	LFT
336	808-98000	LINE, EPOXY, SOLID, YELLOW, 8 IN.	2,624.000	LFT

SCHEDULE OF PAY ITEMS

CALL ORDER : 310

CONTRACT ID : R -31957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
2	109-08359	LIQUIDATED DAMAGES	1.000 DOL
3	109-08360	CONTRACT LIENS	1.000 DOL
4	109-08440	QUALITY ADJUSTMENTS, HMA	1.000 DOL
5	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000 DOL
6	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000 DOL
7	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.000 DOL
8	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000 DOL
9	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
10	201-52370	CLEARING RIGHT OF WAY	LUMP
11	202-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000 EACH
12	202-02772	CASTING, REMOVE	1.000 EACH
13	202-96133	PIPE, REMOVE	785.000 LFT
14	203-02000	EXCAVATION, COMMON	91,806.000 CYS
15	203-02070	BORROW	268,975.000 CYS
16	203-51223	EXCAVATION, WATERWAY	4,592.000 CYS
17	204-08415	STAKES, SETTLEMENT	16.000 EACH
18	205-02770	EROSION CONTROL BLANKET	19,240.000 SYS
19	205-03371	SEDIMENT, REMOVE	10.000 CYS
20	205-06930	SPLASHPAD, RIPRAP	9.000 TON
21	205-06931	TEMPORARY CHECK DAM, REVETMENT RIPRAP	273.000 TON
22	205-06932	TEMPORARY CHECK DAM, STRAW BALES	204.000 LFT
23	205-06937	TEMPORARY SILT FENCE	5,440.000 LFT
24	205-06938	TEMPORARY SLOPE DRAIN	460.000 LFT
25	205-09543	NO 2 STONE	594.000 TON
26	206-04301	SHEET PILING, STEEL, S=18.1	3,476.000 SFT
27	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	2,628.000 CYS
28	207-08262	SUBGRADE TREATMENT, TYPE I	56,830.000 SYS
29	207-08266	SUBGRADE TREATMENT, TYPE III	1,460.000 SYS
30	207-08267	SUBGRADE TREATMENT, TYPE IIIA	3,413.000 SYS
31	211-02050	B BORROW	1,113.000 CYS
32	211-06467	AGGREGATE FOR END BENT BACKFILL	182.600 CYS
33	211-09264	STRUCTURE BACKFILL, TYPE 1	1,656.000 CYS
34	211-09266	STRUCTURE BACKFILL, TYPE 3	1,383.000 CYS
35	211-09268	STRUCTURE BACKFILL, TYPE 5	3,141.000 CYS
36	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	21,570.000 TON
37	302-07455	DENSE GRADED SUBBASE	59.000 CYS

38	303-01180	COMPACTED AGGREGATE, NO. 53	352.000	TON
39	303-08210	COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	330.000	TON
40	306-08033	MILLING, ASPHALT, 1 IN.	4,355.000	SYS
41	401-06264	PROFILOGRAPH, HMA	LUMP	LUMP
42	401-07320	QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	827.000	TON
43	401-07334	QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	328.000	TON
44	401-07334	QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	4,402.000	TON
45	401-07403	QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	6,014.000	TON
46	401-07422	QC/QA-HMA, 1, 64, BASE, 19.0 mm	2,737.000	TON
47	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	14,261.000	TON
48	401-07429	QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	5,801.000	TON
49	406-05520	ASPHALT FOR TACK COAT	50.000	TON

SCHEDULE OF PAY ITEMS

PAGE 39

CALL ORDER : 310

CONTRACT ID : R -31957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
50	601-01522	GUARDRAIL TRANSITION TYPE TGB	4.000 EACH
51	601-02103	GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	88.000 LFT
52	601-06854	GUARDRAIL, W-BEAM, NESTED	4.000 EACH
53	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	3.000 EACH
54	601-94689	GUARDRAIL END TREATMENT, OS	13.000 EACH
55	601-99105	GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	907.000 LFT
56	602-06729	BARRIER DELINEATOR	28.000 EACH
57	603-03829	FENCE	1,127.000 LFT
58	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	317.000 LFT
59	605-06200	CENTER CURB, A, CONCRETE	70.000 LFT
60	605-06235	CENTER CURB, D, CONCRETE, MODIFIED	734.000 LFT
61	607-06335	PAVED SIDE DITCH, A	157.000 LFT
62	609-06259	REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	353.800 SYS
63	610-07487	HMA FOR APPROACHES, TYPE B	1,616.000 TON
64	610-08446	PCCP FOR APPROACHES, 6 IN.	215.000 SYS
65	615-06490	RIGHT OF WAY MARKER	39.000 EACH
66	615-06505	MONUMENT, B	12.000 EACH
67	615-06510	MONUMENT, C	2.000 EACH
68	616-02320	GEOTEXTILES	10,238.000 SYS
69	616-05688	RIPRAP, CLASS 1	1,114.000 TON
70	616-06405	RIPRAP, REVETMENT	4,665.000 TON
71	616-07266	COIR ROLL	1,338.000 LFT
72	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000 EACH
73	621-01597	EROSION CONTROL, MAT	971.000 SYS
74	621-02318	SEED MIXTURE, PRAIRIE GRASS	32.000 LBS
75	621-02356	SEEDING, WETLAND	99.000 LBS
76	621-02356	SEEDING, WETLAND	5.000 LBS
77	621-02770	EROSION CONTROL BLANKET	4,889.000 SYS
78	621-02770	EROSION CONTROL BLANKET	909.000 SYS
79	621-06545	FERTILIZER	8.000 TON
80	621-06554	SEED MIXTURE, U	2,972.000 LBS
81	621-06557	SEED MIXTURE, T	1,000.000 LBS
82	621-06565	MULCHING MATERIAL	48.000 TON
83	621-06567	WATER	237.000 KGAL
84	621-06574	SODDING	3,613.000 SYS
85	621-06575	SODDING, NURSERY	4,262.000 SYS

86	621-08161	PERMANENT TURF REINFORCEMENT MAT	2,723.000	SYS
87	621-09399	SEED MIXTURE, WET MESIC	32.000	LBS
88	622-05639	PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	413.000	EACH
89	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	44.000	EACH
90	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.	28.000	EACH
91	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	14.000	EACH
92	622-52436	SIGN, DO NOT MOW OR SPRAY	12.000	EACH
93	622-91786	SEEDLING	882.000	EACH
94	622-98200	SIGN, DO NOT DISTURB	1.000	EACH
95	628-09402	FIELD OFFICE, B	36.000	MOS
96	628-09407	FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	31.000	MOS
97	701-05779	FURNISHING DRILLED SHAFT DRILLING EQUIPMENT	LUMP	LUMP
98	701-05780	DRILLED SHAFT CONCRETE	275.500	CYS

SCHEDULE OF PAY ITEMS

PAGE 40

CALL ORDER : 310

CONTRACT ID : R -31957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	NEW ROAD CONSTRUCTION			
99	701-05781	UNCLASSIFIED SHAFT EXCAVATION	275.500	CYS
100	701-05782	UNCLASSIFIED EXTRA DEPTH EXCAVATION	22.000	CYS
101	701-05783	OBSTRUCTIONS	8.000	HRS
102	701-05787	INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION	LUMP	LUMP
103	701-06011	DYNAMIC PILE LOAD TEST	2.000	EACH
104	701-09557	TEST PILE, DYNAMIC, PRODUCTION	118.000	LFT
105	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
106	701-09739	PILE SHOE, HP 12 X 53	42.000	EACH
107	701-51195	PILE, STEEL H, HP 12" X 53	1,960.000	LFT
108	701-93633	OVERSIZED PREDRILLED PILE HOLES	2,058.000	LFT
109	702-51005	CONCRETE, A, SUBSTRUCTURE	1,066.400	CYS
110	702-51100	DRAIN PIPE, CAST IRON, 6 IN.	434.000	LBS
111	702-51110	GRATES, BASINS, AND FITTINGS, CAST IRON	1,288.000	LBS
112	702-93722	CONCRETE, C	3.000	CYS
113	703-51030	REINFORCING STEEL	149,038.000	LBS
114	703-51032	REINFORCING STEEL, EPOXY COATED	418,755.000	LBS
115	704-51002	CONCRETE, C, SUPERSTRUCTURE	1,521.700	CYS
116	706-05732	CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
117	706-51020	CONCRETE, C, RAILING	110.800	CYS
118	707-09633	STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	4,509.000	LFT
119	709-51821	SURFACE SEAL	LUMP	LUMP
120	712-04131	STRUCTURE	LUMP	LUMP
121	714-05760	CULVERT, PRECAST, REINFORCED CONCRETE BOX, 12' X 5'	100.000	LFT
122	714-08514	WINGWALL	1,698.000	SFT
123	715-03475	SAFETY METAL END SECTION, 4:1, 15 IN.	24.000	EACH
124	715-03476	SAFETY METAL END SECTION, 4:1, 24 IN.	2.000	EACH
125	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	11,875.000	LFT
126	715-05053	PIPE, UNDERDRAIN OUTLET, 6 IN.	1,698.000	LFT
127	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	76.000	LFT
128	715-05127	PIPE, TYPE 1, CURCULAR, 42 IN.	20.000	LFT
129	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	20.000	LFT
130	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	378.000	LFT
131	715-05407	PIPE, END BENT DRAIN, 6 IN.	180.000	LFT
132	715-05411	PIPE, SANITARY SEWER, 12 IN.	1,060.000	LFT
133	715-05842	CONCRETE ANCHOR, 42 IN.	1.000	EACH

134	715-09064	VIDEO INSPECTION FOR PIPE	1,060.000	LFT
135	715-92874	PIPE ENCASEMENT	147.000	LFT
136	718-06531	OUTLET PROTECTOR, 3	45.000	EACH
137	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
138	718-52610	AGGREGATE FOR UNDERDRAINS	1,069.000	CYS
139	720-03194	MANHOLE	3.000	EACH
140	720-44070	CASTING, 13, FURNISH AND ADJUST TO GRADE	1.000	EACH
141	720-45025	INLET, D6	2.000	EACH
142	720-45605	STRUCTURE, MANHOLE, RECONSTRUCT	3.000	LFT
143	723-06912	STRUCTURE, PRECAST THREE-SIDED, 240 IN. X 96 IN.	100.000	LFT
144	723-07105	STRUCTURE, PRECAST THREE-SIDED, 240 IN. X 120 IN.	152.000	LFT
145	723-08608	WINGWALL	1,135.000	SFT
146	724-03276	EXPANSION JOINT SEALING SYSTEM	157.000	LFT
147	731-93945	FACE PANELS, CONCRETE	2,882.000	SFT

SCHEDULE OF PAY ITEMS

PAGE 41

CALL ORDER : 310

CONTRACT ID : R -31957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	NEW ROAD CONSTRUCTION		
148	731-93946	WALL ERECTION	2,882.000 SFT
149	731-93947	LEVELING PAD, CONCRETE	156.000 LFT
150	801-03290	CONSTRUCTION SIGN, C	4.000 EACH
151	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.000 EACH
152	801-06625	DETOUR ROUTE MARKER ASSEMBLY	8.000 EACH
153	801-06640	CONSTRUCTION SIGN, A	21.000 EACH
154	801-06775	MAINTAINING TRAFFIC	LUMP
155	801-07119	BARRICADE, III-B	300.000 LFT
156	802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	162.000 LFT
157	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	140.000 SFT
158	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	35.000 SFT
159	802-76045	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	20.000 SFT
160	804-06770	DELINEATOR POST	32.000 EACH
161	805-01815	SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	1.000 EACH
162	805-01842	HANDHOLE, SIGNAL	5.000 EACH
163	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP
164	805-02328	SIGNAL CABLE, 1C 14GA.	1,140.000 LFT
165	805-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	940.000 LFT
166	805-78205	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	5.000 EACH
167	805-78215	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000 EACH
168	805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	2.000 EACH
169	805-78415	SPAN, CATENARY, AND TETHER	2.000 EACH
170	805-78420	DISCONNECT HANGER	2.000 EACH
171	805-78467	SIGNAL CABLE, 3C 8GA.	30.000 LFT
172	805-78485	SIGNAL CABLE, 5C 14GA.	535.000 LFT
173	805-78490	SIGNAL CABLE, 7C 14GA.	1,175.000 LFT
174	805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	1,535.000 LFT
175	805-78785	SIGNAL DETECTOR HOUSING	7.000 EACH
176	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	414.000 LFT
177	805-81032	SIGNAL STRAIN POLE, STEEL, 30 FT.	1.000 EACH
178	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000 EACH
179	805-96014	SAW CUT, FULL DEPTH	1,549.000 LFT
180	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	2,150.000 LFT
181	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	14,636.000 LFT

182	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	4,074.000	LFT
183	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	1,216.000	LFT
184	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	1,216.000	LFT
185	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	300.000	LFT
186	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	10,844.000	LFT
187	808-75260	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	1,670.000	LFT
188	808-75278	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	650.000	LFT
189	808-75290	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	600.000	LFT
190	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	168.000	LFT
191	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	18.000	EACH
192	808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	14.000	EACH
193	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	449.000	EACH

SCHEDULE OF PAY ITEMS

PAGE 42

CALL ORDER : 350

CONTRACT ID : R -32737-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SAFE ROUTES TO SCHOOL			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
2	105-08520	CELLULAR TELEPHONE/RADIO	1.000 EACH
3	105-08521	CELLULAR TELEPHONE/RADIO SERVICE	7.000 MOS
4	105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000 DOL
5	109-08359	LIQUIDATED DAMAGES	1.000 DOL
6	109-08360	CONTRACT LIENS	1.000 DOL
7	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000 DOL
8	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000 DOL
9	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000 DOL
10	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
11	201-52370	CLEARING RIGHT OF WAY	LUMP
12	202-52710	SIDEWALK, CONCRETE, REMOVE	706.000 SYS
13	202-91010	TREE, 24 IN., REMOVE	3.000 EACH
14	202-91922	STUMP, REMOVE	2.000 EACH
15	203-02000	EXCAVATION, COMMON	149.000 CYS
16	205-03371	SEDIMENT, REMOVE	2.000 CYS
17	205-06933	TEMPORARY DITCH INLET PROTECTION	1.000 EACH
18	205-06937	TEMPORARY SILT FENCE	3,305.000 LFT
19	205-09543	NO 2 STONE	100.000 TON
20	207-08267	SUBGRADE TREATMENT, TYPE IIIA	208.000 SYS
21	211-09265	STRUCTURE BACKFILL, TYPE 2	27.000 CYS
22	213-04324	FLOWABLE FILL	16.000 CYS
23	304-07489	HMA PATCHING, TYPE A	21.000 TON
24	406-05520	ASPHALT FOR TACK COAT	1.000 TON
25	604-90256	SIDEWALK, CONCRETE, 6 IN.	52.000 SYS
26	604-91531	SIDEWALK, CONCRETE, 4 IN.	1,787.000 SYS
27	610-08446	PCCP FOR APPROACHES, 6 IN.	208.000 SYS
28	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000 EACH
29	621-02770	EROSION CONTROL BLANKET	128.000 SYS
30	621-06545	FERTILIZER	1.000 TON
31	621-06554	SEED MIXTURE, U	35.000 LBS
32	621-06557	SEED MIXTURE, T	40.000 LBS
33	621-06565	MULCHING MATERIAL	1.000 TON
34	628-09402	FIELD OFFICE, B	7.000 MOS
35	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	56.000 LFT
36	715-06696	PIPE, PVC, 10 IN.	29.000 LFT

37	720-44000	CASTING, ADJUST TO GRADE	1.000	EACH
38	801-03290	CONSTRUCTION SIGN, C	2.000	EACH
39	801-06640	CONSTRUCTION SIGN, A	9.000	EACH
40	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
41	802-07060	SIGN, SHEET, RELOCATE	6.000	EACH
42	808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	265.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 43

CALL ORDER : 500

CONTRACT ID : B -29452-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	370.000	CYS
11	203-02070 BORROW	4,070.000	CYS
12	203-51223 EXCAVATION, WATERWAY	703.000	CYS
13	205-06932 TEMPORARY CHECK DAM, STRAW BALES	171.000	LFT
14	205-06937 TEMPORARY SILT FENCE	1,435.000	LFT
15	205-09543 NO 2 STONE	100.000	TON
16	206-51215 EXCAVATION, X	60.900	CYS
17	206-51220 EXCAVATION, WET	395.800	CYS
18	207-08262 SUBGRADE TREATMENT, TYPE I	2,241.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	121.000	SYS
20	211-06467 AGGREGATE FOR END BENT BACKFILL	32.000	CYS
21	211-07454 STRUCTURE BACKFILL	2.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,155.000	TON
23	302-07455 DENSE GRADED SUBBASE	36.000	CYS
24	402-07432 HMA SURFACE, TYPE A	158.000	TON
25	402-07433 HMA SURFACE, TYPE B	9.000	TON
26	402-07435 HMA INTERMEDIATE, TYPE A	268.000	TON
27	402-07438 HMA INTERMEDIATE, TYPE B	22.000	TON
28	406-05521 ASPHALT FOR TACK COAT	2,015.000	SYS
29	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	3.000	EACH
30	601-06037 GUARDRAIL END TREATMENT, I	3.000	EACH
31	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
32	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	400.000	LFT
33	608-04395 AGGREGATE FOR SHOULDER DRAINS	5.100	TON
34	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	220.000	SYS
35	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
36	616-02320 GEOTEXTILES	1,245.000	SYS
37	616-06405 RIPRAP, REVETMENT	895.000	TON
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
39	621-06545 FERTILIZER	0.600	TON
40	621-06553 SEED MIXTURE, R	170.000	LBS
41	621-06557 SEED MIXTURE, T	85.000	LBS
42	621-06565 MULCHING MATERIAL	4.000	TON

43	621-06575	SODDING, NURSERY	487.000	SYS
44	628-09402	FIELD OFFICE, B	12.000	MOS
45	701-09739	PILE SHOE, HP 12 X 53	10.000	EACH
46	701-51195	PILE, STEEL H, HP 12" X 53	300.000	LFT
47	702-51005	CONCRETE, A, SUBSTRUCTURE	150.100	CYS
48	702-51015	CONCRETE, B, FOOTINGS	60.800	CYS
49	703-51030	REINFORCING STEEL	23,581.000	LBS

SCHEDULE OF PAY ITEMS

PAGE 44

CALL ORDER : 500

CONTRACT ID : B -29452-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
50	703-51032	REINFORCING STEEL, EPOXY COATED	43,732.000 LBS
51	704-51002	CONCRETE, C, SUPERSTRUCTURE	159.900 CYS
52	706-06344	RAILING, TS-1	275.000 LFT
53	707-05983	STRUCTURAL MEMBERS, CONCRETE I-BEAM, II, 36 IN. X 12 IN.	700.000 LFT
54	709-51821	SURFACE SEAL	LUMP
55	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	74.000 LFT
56	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	140.000 LFT
57	715-05407	PIPE, END BENT DRAIN, 6 IN.	132.000 LFT
58	715-09064	VIDEO INSPECTION FOR PIPE	132.000 LFT
59	715-46005	PIPE END SECTION, 15 IN.	2.000 EACH
60	715-46010	PIPE END SECTION, 18 IN.	2.000 EACH
61	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.000 EACH
62	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.000 EACH
63	801-06640	CONSTRUCTION SIGN, A	12.000 EACH
64	801-07118	BARRICADE, III-A	64.000 LFT
65	801-07119	BARRICADE, III-B	16.000 LFT

SCHEDULE OF PAY ITEMS

PAGE 45

CALL ORDER : 510

CONTRACT ID : B -29616-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
1	105-06845	CONSTRUCTION ENGINEERING	LUMP
2	105-08520	CELLULAR TELEPHONE/RADIO	1.000 EACH
3	105-08521	CELLULAR TELEPHONE/RADIO SERVICE	15.000 MOS
4	105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000 DOL
5	109-08359	LIQUIDATED DAMAGES	1.000 DOL
6	109-08360	CONTRACT LIENS	1.000 DOL
7	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000 DOL
8	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000 DOL
9	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000 DOL
10	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP
11	201-52370	CLEARING RIGHT OF WAY	LUMP
12	202-51330	PRESENT STRUCTURE, REMOVE	LUMP
13	203-02000	EXCAVATION, COMMON	1,635.000 CYS
14	203-02070	BORROW	723.000 CYS

15	203-51223	EXCAVATION, WATERWAY	252.000	CYS
16	205-03371	SEDIMENT, REMOVE	15.000	CYS
17	205-06931	TEMPORARY CHECK DAM, REVETMENT RIPRAP	66.000	TON
18	205-06937	TEMPORARY SILT FENCE	1,650.000	LFT
19	206-51220	EXCAVATION, WET	150.000	CYS
20	206-51235	COFFERDAM	LUMP	LUMP
21	207-08267	SUBGRADE TREATMENT, TYPE IIIA	2,766.000	SYS
22	211-09264	STRUCTURE BACKFILL, TYPE 1	104.400	CYS
23	211-09267	STRUCTURE BACKFILL, TYPE 4	28.000	CYS
24	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	1,513.000	TON
25	302-07455	DENSE GRADED SUBBASE	29.800	CYS
26	303-07449	COMPACTED AGGREGATE, NO. 73	374.000	TON
27	402-07432	HMA SURFACE, TYPE A	19.000	TON
28	402-07435	HMA INTERMEDIATE, TYPE A	32.000	TON
29	404-05514	SEAL COAT, 5	93.000	SYS
30	406-05521	ASPHALT FOR TACK COAT	226.000	SYS
31	601-01522	GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
32	601-01700	GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
33	601-06037	GUARDRAIL END TREATMENT, I	3.000	EACH
34	601-99105	GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	106.300	LFT
35	602-06729	BARRIER DELINEATOR	8.000	EACH
36	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	179.000	SYS
37	615-06490	RIGHT OF WAY MARKER	18.000	EACH
38	616-02320	GEOTEXTILES	779.000	SYS
39	616-06405	RIPRAP, REVETMENT	547.000	TON
40	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
41	621-02770	EROSION CONTROL BLANKET	2,445.000	SYS
42	621-06545	FERTILIZER	0.100	TON
43	621-06557	SEED MIXTURE, T	58.000	LBS
44	621-06559	MULCHED SEEDING, R	3,271.000	SYS
45	621-06565	MULCHING MATERIAL	2.000	TON
46	621-06567	WATER	1.000	KGAL
47	621-06574	SODDING	219.000	SYS
48	621-08161	PERMANENT TURF REINFORCEMENT MAT	44.000	SYS
49	622-91786	SEEDLING	44.000	EACH

SCHEDULE OF PAY ITEMS

PAGE 46

CALL ORDER : 510

CONTRACT ID : B -29616-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
50	622-98200	SIGN, DO NOT DISTURB	4.000 EACH
51	628-09402	FIELD OFFICE, B	15.000 MOS
52	701-51195	PILE, STEEL H, HP 12" X 53	760.000 LFT
53	701-91792	PILE TIP, STEEL H	26.000 EACH
54	701-95780	PILE, STEEL H, HP 12" X 74	912.000 LFT
55	702-04433	FLOOR DRAIN, PVC, 6 IN.	40.000 EACH
56	702-51005	CONCRETE, A, SUBSTRUCTURE	144.000 CYS
57	702-51015	CONCRETE, B, FOOTINGS	12.000 CYS
58	703-06028	REINFORCING BARS	30,377.000 LBS
59	703-06029	REINFORCING BARS, EPOXY COATED	80,178.000 LBS
60	704-51002	CONCRETE, C, SUPERSTRUCTURE	353.800 CYS
61	706-05732	CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000 EACH
62	706-51020	CONCRETE, C, RAILING	23.000 CYS

63	709-51821	SURFACE SEAL	LUMP	LUMP
64	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	50.000	LFT
65	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	112.000	LFT
66	715-46020	PIPE END SECTION, 24 IN.	4.000	EACH
67	715-46040	PIPE END SECTION, 36 IN.	2.000	EACH
68	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
69	801-06625	DETOUR ROUTE MARKER ASSEMBLY	12.000	EACH
70	801-06640	CONSTRUCTION SIGN, A	3.000	EACH
71	801-07118	BARRICADE, III-A	24.000	LFT
72	801-07119	BARRICADE, III-B	24.000	LFT
73	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	537.000	LFT
74	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	537.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 47

CALL ORDER : 520

CONTRACT ID : B -30483-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT BRIDGE RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
8	203-02000 EXCAVATION, COMMON	2,500.000	CYS
9	205-06932 TEMPORARY CHECK DAM, STRAW BALES	264.000	LFT
10	205-06937 TEMPORARY SILT FENCE	2,150.000	LFT
11	206-51220 EXCAVATION, WET	476.000	CYS
12	206-51235 COFFERDAM	LUMP	LUMP
13	207-08266 SUBGRADE TREATMENT, TYPE III	1,125.000	SYS
14	210-05794 MISCELLANEOUS PLANTINGS	LUMP	LUMP
15	211-07454 STRUCTURE BACKFILL	126.000	CYS
16	303-01180 COMPACTED AGGREGATE, NO. 53	740.000	TON
17	402-07432 HMA SURFACE, TYPE A	390.000	TON
18	402-07435 HMA INTERMEDIATE, TYPE A	670.000	TON
19	406-05521 ASPHALT FOR TACK COAT	4,600.000	SYS
20	601-05399 GUARDRAIL	LUMP	LUMP
21	601-05399 GUARDRAIL	LUMP	LUMP
22	616-02320 GEOTEXTILES	538.000	SYS
23	616-05688 RIPRAP, CLASS 1	36.000	TON
24	616-06405 RIPRAP, REVETMENT	164.000	TON
25	619-09427 CLEAN STEEL BRIDGE, TYPE 3, QP-2	5,765.000	SFT
26	619-09439 PAINT STEEL BRIDGE, PARTIAL, TYPE 3	5,765.000	SFT
27	621-01597 EROSION CONTROL, MAT	50.000	SYS
28	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	7,850.000	SYS
29	621-06748 SEEDING	3,800.000	SYS
30	628-09401 FIELD OFFICE, A	14.000	MOS
31	701-51195 PILE, STEEL H, HP 12" X 53	504.000	LFT
32	701-98647 PILE, CONCRETE, STEEL SHELL ENCASED, 0.203 IN., 14 IN.	750.000	LFT
33	702-51005 CONCRETE, A, SUBSTRUCTURE	257.800	CYS
34	702-51015 CONCRETE, B, FOOTINGS	66.100	CYS
35	702-90915 CONCRETE, A	36.600	CYS
36	703-51030 REINFORCING STEEL	17,837.000	LBS

37	708-05394	REPAIR	LUMP	LUMP
38	708-05394	REPAIR	LUMP	LUMP
39	711-05396	REPLACE	LUMP	LUMP
40	711-05396	REPLACE	LUMP	LUMP
41	711-05396	REPLACE	LUMP	LUMP
42	711-05396	REPLACE	LUMP	LUMP
43	712-04960	RELOCATE	LUMP	LUMP
44	712-04960	RELOCATE	LUMP	LUMP
45	715-05407	PIPE, END BENT DRAIN, 6 IN.	64.000	LFT
46	802-04993	SIGN	LUMP	LUMP

SCHEDULE OF PAY ITEMS

CALL ORDER : 560

CONTRACT ID : T -30911-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001 SIGNAL MODERNIZATION				
1	105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359	LIQUIDATED DAMAGES	1.000	DOL
3	109-08360	CONTRACT LIENS	1.000	DOL
4	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	5.000	EACH
9	202-74070	OVERHEAD SIGN STRUCTURE, CABLE SPAN, REMOVE	1.000	EACH
10	202-86946	HANDHOLE, REMOVE	10.000	EACH
11	202-93763	LIGHT STANDARD AND FOUNDATION, REMOVE	1.000	EACH
12	202-99626	FOUNDATION FOR SIGNING, REMOVE	1.000	EACH
13	203-02020	EXCAVATION, UNCLASSIFIED	548.000	CYS
14	205-02237	TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	1.000	EACH
15	205-06937	TEMPORARY SILT FENCE	1,465.000	LFT
16	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	36.200	TON
17	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	140.400	TON
18	304-07489	HMA PATCHING, TYPE A	4.000	TON
19	304-07491	HMA PATCHING, TYPE C	78.000	TON
20	305-07465	PCC BASE PATCHING, 10 IN.	353.500	SYS
21	406-05520	ASPHALT FOR TACK COAT	0.500	TON
22	604-07899	CURB RAMP, CONCRETE, E	79.000	SYS
23	604-07900	CURB RAMP, CONCRETE, F	98.200	SYS
24	604-07902	CURB RAMP, CONCRETE, H	152.600	SYS
25	604-91531	SIDEWALK, CONCRETE, 4 IN.	1,835.700	SYS
26	605-06165	CURB AND GUTTER, C, CONCRETE, MODIFIED	1,515.000	LFT
27	610-07487	HMA FOR APPROACHES, TYPE B	48.000	TON
28	611-95728	CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 8 IN.	472.200	SYS
29	621-02363	MULCHED SEEDING, T, CONVENTIONAL MIX	863.000	SYS
30	621-06570	TOP SOIL	59.300	CYS
31	621-06575	SODDING, NURSERY	533.300	SYS
32	628-09403	FIELD OFFICE, C	9.000	MOS
33	720-90105	INLET, REPAIR	2.000	EACH
34	801-03290	CONSTRUCTION SIGN, C	60.000	EACH
35	801-06640	CONSTRUCTION SIGN, A	204.000	EACH
36	801-06710	FLASHING ARROW SIGN	135.000	DAY
37	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
38	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	209.000	SFT

39	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	60.000	SFT
40	802-76045	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	279.000	SFT
41	805-01579	MISCELLANEOUS EQUIPMENT FOR SYSTEM LOOP AND INTERCONNECT	LUMP	LUMP
42	805-01815	SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	6.000	EACH
43	805-01816	SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	12.000	EACH
44	805-01820	SIGNAL STRAIN POLE, STEEL	1.000	EACH
45	805-01842	HANDHOLE, SIGNAL	43.000	EACH
46	805-02072	SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	3.000	EACH
47	805-02073	SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	1.000	EACH
48	805-02077	SIGNAL CANTILEVER STRUCTURE, 40 FT. ARM	9.000	EACH
49	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP

SCHEDULE OF PAY ITEMS

PAGE 49

CALL ORDER : 560

CONTRACT ID : T -30911-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNAL MODERNIZATION		
50	805-02152	PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	34.000 EACH
51	805-02572	SIGNAL SUPPORT FOUNDATION, A	2.000 EACH
52	805-03708	SIGNAL CANTILEVER STRUCTURE,	1.000 EACH
53	805-03708	SIGNAL CANTILEVER STRUCTURE,	1.000 EACH
54	805-03708	SIGNAL CANTILEVER STRUCTURE,	1.000 EACH
55	805-04133	SIGNAL PEDESTAL, 12 FT.	3.000 EACH
56	805-04148	STRAIN POLE, RELOCATE	1.000 EACH
57	805-04980	FLASHING BEACON	2.000 EACH
58	805-05870	SIGNAL SUPPORT FOUNDATION	2.000 EACH
59	805-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	7,350.000 LFT
60	805-06886	VIDEO VEHICLE DETECTOR SYSTEM WITH 4 CAMERAS	5.000 EACH
61	805-06892	VIDEO SIGNAL CABLE	4,050.000 LFT
62	805-07115	ITS VIDEO SURVEILLANCE	LUMP LUMP
63	805-07115	ITS VIDEO SURVEILLANCE	LUMP LUMP
64	805-78106	CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000 EACH
65	805-78109	CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	4.000 EACH
66	805-78205	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	37.000 EACH
67	805-78215	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	15.000 EACH
68	805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	5.000 EACH
69	805-78370	PEDESTRIAN PUSH BUTTON	34.000 EACH
70	805-78415	SPAN, CATENARY, AND TETHER	4.000 EACH
71	805-78420	DISCONNECT HANGER	4.000 EACH
72	805-78445	SIGNAL SERVICE	5.000 EACH
73	805-78467	SIGNAL CABLE, 3C 8GA.	365.000 LFT
74	805-78470	SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,530.000 LFT
75	805-78480	SIGNAL CABLE, 3C 14GA.	3,935.000 LFT
76	805-78485	SIGNAL CABLE, 5C 14GA.	6,675.000 LFT
77	805-78490	SIGNAL CABLE, 7C 14GA.	2,890.000 LFT
78	805-78500	SIGNAL CABLE, 11C 14GA.	210.000 LFT
79	805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	2,070.000 LFT
80	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	465.000 LFT
81	805-78925	CONTROLLER CABINET FOUNDATION, P1	5.000 EACH
82	805-81060	SIGNAL STRAIN POLE, STEEL, 36 FT.	3.000 EACH
83	805-91615	EMERGENCY PRE-EMPTOR	1.000 EACH
84	805-91615	EMERGENCY PRE-EMPTOR	3.000 EACH
85	805-91615	EMERGENCY PRE-EMPTOR	2.000 EACH
86	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	6.000 EACH

87	805-96014	SAW CUT, FULL DEPTH	1,915.700	LFT
88	805-96260	FIBER OPTICS CABLE, IN CONDUIT	6,225.000	LFT
89	805-97114	CABLE, INTERCONNECT, 6 PAIR 19	340.000	LFT
90	807-02193	LIGHT STANDARD FOUNDATION, 3 FT. DIA. X 8 FT.	1.000	EACH
91	807-02603	LIGHT STANDARD, RELOCATE	1.000	EACH
92	808-06368	TRANSVERSE MARKING, REMOVE	2,130.000	LFT
93	808-06716	LINE, REMOVE	451.000	LFT
94	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	585.000	LFT
95	808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	2,265.000	LFT
96	808-98796	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN., 2 FT. LINE, 4 FT.	115.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 50

CALL ORDER : 580

CONTRACT ID : T -31789-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ITS TRAFFIC MANAGEMENT SYSTEM			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	8.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
11	202-02250 TREE, 10 IN., REMOVE	2.000	EACH
12	628-09402 FIELD OFFICE, B	8.000	MOS
13	801-03290 CONSTRUCTION SIGN, C	9.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
15	801-06710 FLASHING ARROW SIGN	180.000	DAY
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	802-07057 SIGN, PANEL, WITH LEGEND	160.000	SFT
18	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	6.000	EACH
19	802-76095 STRUCTURAL STEEL, BREAKAWAY	608.040	LBS
20	805-01842 HANDHOLE, SIGNAL	8.000	EACH
21	805-02618 WIRE, NO. 2 COPPER, 3 1C	1,135.000	LFT
22	805-06101 FOUNDATION	1.000	EACH
23	805-06101 FOUNDATION	1.000	EACH
24	805-09343 ITS	2.000	EACH
25	805-09344 WIRELESS	2.000	EACH
26	805-78445 SIGNAL SERVICE	2.000	EACH
27	805-92155 WIRE, XHHW, NO. 6 COPPER, 1/C	1,135.000	LFT
28	807-04443 CONDUIT	1,180.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 51

CALL ORDER : 660

CONTRACT ID : TM-31547-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			

1	105-06845	CONSTRUCTION ENGINEERING	LUMP		LUMP
2	105-08520	CELLULAR TELEPHONE/RADIO		2.000	EACH
3	105-08521	CELLULAR TELEPHONE/RADIO SERVICE		16.000	MOS
4	105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL		1.000	DOL
5	109-08359	LIQUIDATED DAMAGES		1.000	DOL
6	109-08360	CONTRACT LIENS		1.000	DOL
7	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC		1.000	DOL
8	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS		1.000	DOL
9	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER		1.000	DOL
10	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP		LUMP
11	202-02273	CENTER CURB, CONCRETE, REMOVE		172.000	SYS
12	202-52710	SIDEWALK, CONCRETE, REMOVE		12.000	SYS
13	207-08263	SUBGRADE TREATMENT, TYPE IA		172.000	SYS
14	304-07491	HMA PATCHING, TYPE C		103.000	TON
15	306-08036	MILLING, ASPHALT, 2 IN.		465.000	SYS
16	402-07434	HMA SURFACE, TYPE C		35.000	TON
17	402-07439	HMA INTERMEDIATE, TYPE C		47.000	TON
18	406-05520	ASPHALT FOR TACK COAT		1.000	TON
19	604-07903	CURB RAMP, CONCRETE, K		12.000	SYS
20	604-90256	SIDEWALK, CONCRETE, 6 IN.		2.000	SYS
21	605-06215	CENTER CURB, D, CONCRETE		387.000	LFT
22	628-09402	FIELD OFFICE, B		8.000	MOS
23	720-44000	CASTING, ADJUST TO GRADE		1.000	EACH
24	801-03290	CONSTRUCTION SIGN, C		4.000	EACH
25	801-06640	CONSTRUCTION SIGN, A		15.000	EACH
26	801-06775	MAINTAINING TRAFFIC	LUMP		LUMP
27	802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE		25.000	LFT
28	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.		4.200	SFT
29	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.		18.000	SFT
30	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND		90.000	LFT
31	805-02152	PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.		8.000	EACH
32	805-02645	SIGNAL PEDESTAL FOUNDATION, A		1.000	EACH
33	805-09451	SIGNAL PEDESTAL, 15 FT.		1.000	EACH
34	805-78480	SIGNAL CABLE, 3C 14GA.		1,365.000	LFT
35	805-78485	SIGNAL CABLE, 5C 14GA.		1,405.000	LFT
36	805-96121	PEDESTRIAN PUSH BUTTON AND SIGN		6.000	EACH
37	808-75205	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.		311.000	LFT
38	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.		776.000	LFT
39	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.		57.000	LFT
40	808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.		885.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 52

CALL ORDER : 670

CONTRACT ID : TM-32760-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MAINTENANCE		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	210-07224 VIDEO	10.000	EACH
7	702-76240 CONCRETE	4.000	CYS

8	801-03290	CONSTRUCTION SIGN, C	4.000	EACH
9	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
10	805-01523	MAST ARM, INSTALL	1.000	EACH
11	805-01815	SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	1.000	EACH
12	805-01816	SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	1.000	EACH
13	805-01820	SIGNAL STRAIN POLE, STEEL	1.000	EACH
14	805-01821	SIGNAL CANTILEVER STRUCTURE, INSTALL	1.000	EACH
15	805-01822	SPAN, CATENARY AND TETHER, INSTALL	5.000	EACH
16	805-01823	TETHER CABLE, INSTALL	5.000	EACH
17	805-01824	SPAN, CATENARY, AND TETHER, TIGHTEN	5.000	EACH
18	805-01825	DISCONNECT HANGER, INSTALL	5.000	EACH
19	805-01827	TRAFFIC SIGNAL HEAD, INSTALL	20.000	EACH
20	805-01829	SIGN, INSTALL	10.000	EACH
21	805-01830	CONFLICT MONITOR CHANGEOUT	218.000	EACH
22	805-01833	LOOP SYSTEM CHECK	120.000	EACH
23	805-01835	TRAFFIC SIGNAL HEAD, REPAIR	50.000	EACH
24	805-01842	HANDHOLE, SIGNAL	2.000	EACH
25	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	2.000	EACH
26	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	200.000	LFT
27	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	180.000	LFT
28	805-02266	LENS REPLACEMENT, TRAFFIC SIGNAL, 12 IN.	50.000	EACH
29	805-03690	SIGNAL CABLE, INSTALL	3,000.000	LFT
30	805-05707	PRE-WARNING FLASHER, BULB REPLACEMENT, GROUND INSPECTION	7.000	EACH
31	805-06363	FIBER OPTIC ST TERMINATION	14.000	EACH
32	805-06364	FIBER OPTIC BREAKOUT KIT	1.000	EACH
33	805-06891	VIDEO CAMERA DETECTOR, INSTALL	4.000	EACH
34	805-06892	VIDEO SIGNAL CABLE	160.000	LFT
35	805-06893	VIDEO CABLE CONNECTOR	3.000	EACH
36	805-06894	VIDEO CABLE JUNCTION BOX, INSTALL	1.000	EACH
37	805-09072	AERIAL INSPECTION	100.000	EACH
38	805-09073	TRUCK, SERVICE	10.000	HRS
39	805-78370	PEDESTRIAN PUSH BUTTON	5.000	EACH
40	805-78445	SIGNAL SERVICE	5.000	EACH
41	805-78470	SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	3,000.000	LFT
42	805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	500.000	LFT
43	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	2,000.000	LFT
44	805-78800	SIGNAL DETECTOR HOUSING INSTALL	4.000	EACH
45	805-78900	PEDESTAL FOUNDATION, A	1.000	EACH
46	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
47	805-87068	TRUCK, BUCKET	10.000	HRS
48	805-87076	TRUCK, PICKUP	10.000	HRS
49	805-87090	LABOR, SKILLED, OVERTIME	10.000	HRS

SCHEDULE OF PAY ITEMS

PAGE 53

CALL ORDER : 670

CONTRACT ID : TM-32760-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MAINTENANCE		
50	805-87092	LABOR, SKILLED, STRAIGHT TIME	20.000 HRS
51	805-87093	LABOR, SKILLED, DOUBLETIME	5.000 HRS
52	805-91706	ANCHOR BOLT, REPAIR	2.000 EACH
53	805-92327	SIGNAL PEDESTAL, INSTALL	2.000 EACH
54	805-92336	SIGNAL POLE, WOOD, INSTALL	1.000 EACH
55	805-92951	SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	2.000 EACH

56	805-92983	TRAFFIC SIGNAL CONTROLLER AND CABINET, INSTALL	2.000	EACH
57	805-94636	SIGNAL CABINET FOUNDATION EXPANSION	1.000	EACH
58	805-94677	EMERGENCY RESPONSE MAINTENANCE OF DIGITAL CONTROLLER	2,616.000	MOS
59	805-94680	EMERGENCY RESPONSE MAINTENANCE OF FLASHER CONTROLLER	228.000	MOS
60	805-94682	LOOP TESTING	204.000	EACH
61	805-94687	LOCATE UNDERGROUND SIGNAL FACILITIES	5.000	EACH
62	805-94721	SIGNAL BULB REPLACEMENT, AERIAL INSPECTION	128.000	EACH
63	805-94724	FLASHER, BULB REPLACEMENT, AERIAL INSPECTION	8.000	EACH
64	805-94971	FIBER OPTICS CABLE	330.000	LFT
65	805-95695	EXPANSION ANCHOR BOLT (PEDESTAL AND CONTROLLER ONLY)	3.000	EACH
66	805-97042	SIGNAL POLE, WOOD, 5, 35 FT.	1.000	EACH