

CALL ORDER : 250

CONTRACT ID : R -29629-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW SIGNAL INSTALLATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-05936 CROSSOVER, REMOVE	LUMP	LUMP
12	202-05936 CROSSOVER, REMOVE	LUMP	LUMP
13	202-05936 CROSSOVER, REMOVE	LUMP	LUMP
14	202-74035 SIGN, REMOVE	4.000	EACH
15	203-02000 EXCAVATION, COMMON	9,780.000	CYS
16	205-03371 SEDIMENT, REMOVE	25.000	CYS
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	50.000	TON
18	205-06933 TEMPORARY DITCH INLET PROTECTION	6.000	EACH
19	205-06937 TEMPORARY SILT FENCE	2,431.000	LFT
20	205-09543 NO 2 STONE	100.000	TON
21	207-08263 SUBGRADE TREATMENT, TYPE IA	15,353.000	SYS
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,293.000	SYS
23	211-09264 STRUCTURE BACKFILL, TYPE 1	2,040.000	CYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	285.000	TON
25	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	814.000	TON
26	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,356.000	TON
27	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	3,892.000	TON
28	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	2,085.000	TON
29	406-05520 ASPHALT FOR TACK COAT	12.000	TON
30	605-06120 CURB, CONCRETE	119.000	LFT
31	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	6,890.000	LFT
32	605-09131 CURB AND GUTTER TURNOUT CONCRETE	4.000	LFT
33	610-07487 HMA FOR APPROACHES, TYPE B	3,113.000	TON
34	610-09108 PCCP FOR APPROACHES, 9 IN.	1,139.000	SYS
35	615-06505 MONUMENT, B	21.000	EACH
36	616-02320 GEOTEXTILES	45.000	SYS
37	616-06405 RIPRAP, REVETMENT	21.000	TON
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
39	621-06545 FERTILIZER	2.000	TON
40	621-06554 SEED MIXTURE, U	542.000	LBS
41	621-06557 SEED MIXTURE, T	353.000	LBS
42	621-06565 MULCHING MATERIAL	16.000	TON
43	621-06567 WATER	14.000	KGAL
44	621-06575 SODDING, NURSERY	4,709.000	SYS
45	628-09402 FIELD OFFICE, B	12.000	MOS
46	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	581.000	LFT
47	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	6,952.000	LFT
48	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	2,445.000	LFT
49	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	192.000	LFT

CALL ORDER : 250

CONTRACT ID : R -29629-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW SIGNAL INSTALLATION		
50	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	1,416.000	LFT
51	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	163.000	LFT
52	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	20.000	LFT
53	715-46005 PIPE END SECTION, 15 IN.	4.000	EACH
54	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
55	715-46040 PIPE END SECTION, 36 IN.	1.000	EACH
56	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
57	718-52610 AGGREGATE FOR UNDERDRAINS	626.000	CYS
58	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
59	720-45030 INLET, E7	4.000	EACH
60	720-45035 INLET, F7	2.000	EACH
61	720-45410 MANHOLE, C4	13.000	EACH
62	720-90129 MANHOLE, J2	1.000	EACH
63	720-91051 INLET, A	15.000	EACH
64	720-94157 MANHOLE, C	2.000	EACH
65	720-94612 MANHOLE, K4	3.000	EACH
66	720-95422 MANHOLE, J4	5.000	EACH
67	720-96422 INLET, A, MODIFIED	21.000	EACH
68	720-96851 INLET, J13	1.000	EACH
69	720-98013 INLET, M	2.000	EACH
70	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	13.000	EACH
71	801-01505 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (ONLY)	3.000	EACH
72	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
73	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
74	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	5,947.000	LFT
75	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	146.000	LFT
76	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
77	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
78	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
79	801-07119 BARRICADE, III-B	288.000	LFT
80	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	354.000	LFT
81	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	44.000	LFT
82	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	257.000	SFT
83	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	283.000	SFT
84	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	8.000	EACH
85	805-01842 HANDHOLE, SIGNAL	16.000	EACH
86	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	2,690.000	LFT
87	805-03793 DETECTOR CARD RACK AND DETECTOR MODULES	2.000	EACH
88	805-08493 RADIO SYSTEM TESTING INTERCONNECT	LUMP	LUMP
89	805-08494 RADIO SPREAD SPECTRUM	4.000	EACH
90	805-08566 RADIO ANTENNA, 9db, YAGI	4.000	EACH
91	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	2.000	EACH
92	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	18.000	EACH
93	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	4.000	EACH
94	805-78415 SPAN, CATENARY, AND TETHER	8.000	EACH
95	805-78420 DISCONNECT HANGER	8.000	EACH
96	805-78445 SIGNAL SERVICE	2.000	EACH
97	805-78467 SIGNAL CABLE, 3C 8GA.	200.000	LFT
98	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	5,020.000	LFT

CALL ORDER : 250

CONTRACT ID : R -29629-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW SIGNAL INSTALLATION		
99	805-78485 SIGNAL CABLE, 5C 14GA.	1,445.000	LFT
100	805-78490 SIGNAL CABLE, 7C 14GA.	1,120.000	LFT
101	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	8,835.000	LFT
102	805-78785 SIGNAL DETECTOR HOUSING	14.000	EACH
103	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,570.000	LFT
104	805-78925 CONTROLLER CABINET FOUNDATION, P1	2.000	EACH
105	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	8.000	EACH
106	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	12.000	EACH
107	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	3.000	EACH
108	805-94971 FIBER OPTICS CABLE	995.000	LFT
109	805-94971 FIBER OPTICS CABLE	1,240.000	LFT
110	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,145.000	LFT
111	808-06716 LINE, REMOVE	1,100.000	LFT
112	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	9,828.000	LFT
113	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	673.000	LFT
114	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	26.000	EACH
115	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	17.000	EACH
116	808-96078 LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	37.000	LFT
117	808-98875 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	277.000	LFT

CALL ORDER : 320

CONTRACT ID : R -31907-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	303-07449 COMPACTED AGGREGATE, NO. 73	1,100.000	TON
13	304-07491 HMA PATCHING, TYPE C	800.000	TON
14	306-08042 MILLING, SCARIFICATION/PROFILE	93,000.000	SYS
15	306-08043 MILLING, TRANSITION	1,680.000	SYS
16	306-08432 MILLING, APPROACH	15,450.000	SYS
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	8,100.000	TON
19	402-09731 FIBER REINFORCED ASPHALT MEMBRANE	25,900.000	SYS
20	402-09732 STRESS ABSORBING MEMBRANE INTERLAYER	25,900.000	SYS
21	406-05520 ASPHALT FOR TACK COAT	10.000	TON
22	407-05522 ASPHALT MATERIAL FOR DUST PALLIATIVE	25.000	TON
23	604-07901 CURB RAMP, CONCRETE, G	24.000	SYS
24	610-07488 HMA FOR APPROACHES, TYPE C	1,300.000	TON
25	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	28.000	TON
26	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
27	612-60410 DRILLED HOLE FOR UNDERSEAL	450.000	EACH
28	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	1.000	EACH
29	628-09402 FIELD OFFICE, B	6.000	MOS
30	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
31	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
32	720-94840 CASTING, ADJUST TO GRADE, WATER VALVE	1.000	EACH
33	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.000	EACH
34	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
35	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	3,000.000	LFT
36	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,000.000	LFT
37	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
38	801-06710 FLASHING ARROW SIGN	70.000	DAY
39	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
40	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
41	802-07125 SIGN, DOUBLE FACED, SHEET, ENCAPSULATED LENS, WITH LEGEND,	32.000	SFT
42	802-76055 SIGN POST, A	80.000	LFT
43	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
44	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	55,200.000	LFT
45	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	6,000.000	LFT
46	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	27,100.000	LFT
47	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	665.000	EACH
48	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	665.000	EACH

CALL ORDER : 390

CONTRACT ID : B -28866-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK RECONSTRUCTION & WIDENING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	48.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	24.000	SYS
14	202-02241 GUARDRAIL, REMOVE	1,891.000	LFT
15	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
16	202-86946 HANDHOLE, REMOVE	1.000	EACH
17	202-91385 INLET, REMOVE	3.000	EACH
18	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	4.000	EACH
19	202-95027 IMPACT ATTENUATOR, REMOVE	2.000	EACH
20	203-02000 EXCAVATION, COMMON	2,699.000	CYS
21	203-02070 BORROW	681.000	CYS
22	203-51196 CORED HOLE IN ROCK	32.400	LFT
23	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	16.000	TON
24	205-06934 TEMPORARY MULCHING	2.000	TON
25	205-06937 TEMPORARY SILT FENCE	2,315.000	LFT
26	205-09543 NO 2 STONE	100.000	TON
27	206-51215 EXCAVATION, X	36.000	CYS
28	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	135.000	CYS
29	207-08263 SUBGRADE TREATMENT, TYPE IA	3,358.000	SYS
30	210-05811 REPAIR	12.000	EACH
31	211-06467 AGGREGATE FOR END BENT BACKFILL	59.600	CYS
32	211-09265 STRUCTURE BACKFILL, TYPE 2	105.400	CYS
33	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	15.000	TON
34	302-07455 DENSE GRADED SUBBASE	53.000	CYS
35	303-01180 COMPACTED AGGREGATE, NO. 53	436.000	TON
36	304-07491 HMA PATCHING, TYPE C	59.900	TON
37	305-07468 PCC BASE PATCHING, 12 IN.	24.000	SYS
38	306-08034 MILLING, ASPHALT, 1 1/2 IN.	3,886.000	SYS
39	402-07434 HMA SURFACE, TYPE C	560.000	TON
40	402-07439 HMA INTERMEDIATE, TYPE C	398.000	TON
41	402-07442 HMA BASE, TYPE C	1,867.000	TON
42	406-05520 ASPHALT FOR TACK COAT	2.450	TON
43	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
44	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	500.000	LFT
45	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
46	601-06416 IMPACT ATTENUATOR SPARE PARTS PACKAGE, ED, W1, TL-3	2.000	EACH
47	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
48	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,131.250	LFT
49	601-99123 GUARDRAIL TRANSITION, GP	2.000	EACH

CALL ORDER : 390

CONTRACT ID : B -28866-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK RECONSTRUCTION & WIDENING		
50	602-06729 BARRIER DELINEATOR	12.000	EACH
51	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	317.900	SYS
52	615-06505 MONUMENT, B	6.000	EACH
53	616-02320 GEOTEXTILES	1,147.000	SYS
54	616-06405 RIPRAP, REVETMENT	730.000	TON
55	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	7,628.000	SFT
56	619-09434 PAINT STEEL BRIDGE, TYPE 1	7,628.000	SFT
57	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
58	621-02468 SEED MIXTURE, GRASS, 1	130.000	LBS
59	621-02770 EROSION CONTROL BLANKET	2,777.000	SYS
60	621-06545 FERTILIZER	0.100	TON
61	621-06557 SEED MIXTURE, T	53.000	LBS
62	621-06565 MULCHING MATERIAL	3.300	TON
63	621-06574 SODDING	38.000	SYS
64	628-09402 FIELD OFFICE, B	12.000	MOS
65	701-51190 PILE, STEEL H, HP 10" X 42	176.000	LFT
66	701-91792 PILE TIP, STEEL H	8.000	EACH
67	701-93633 OVERSIZED PREDRILLED PILE HOLES	129.000	LFT
68	702-51005 CONCRETE, A, SUBSTRUCTURE	171.500	CYS
69	702-51015 CONCRETE, B, FOOTINGS	26.200	CYS
70	702-51100 DRAIN PIPE, CAST IRON, 6 IN.	96.000	LBS
71	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	384.000	LBS
72	702-51863 FIELD DRILLED HOLE IN CONCRETE	124.000	EACH
73	702-51864 FIELD DRILLED HOLE	808.000	EACH
74	703-51032 REINFORCING STEEL, EPOXY COATED	150,510.000	LBS
75	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	781.000	EACH
76	704-51002 CONCRETE, C, SUPERSTRUCTURE	376.000	CYS
77	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
78	706-51020 CONCRETE, C, RAILING	41.000	CYS
79	709-04647 FIBER WRAP CONCRETE CASING SYSTEM	LUMP	LUMP
80	709-51821 SURFACE SEAL	LUMP	LUMP
81	711-51038 STRUCTURAL STEEL	LUMP	LUMP
82	711-51866 RIVET, REMOVE	112.000	EACH
83	711-93035 JACKING AND SUPPORTING STRUCTURAL STEEL	LUMP	LUMP
84	711-96479 BOLT, REMOVE	56.000	EACH
85	711-96800 STUD SHEAR CONNECTORS	1,743.000	EACH
86	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	14.000	LFT
87	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	33.000	LFT
88	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	8.000	LFT
89	715-05407 PIPE, END BENT DRAIN, 6 IN.	144.000	LFT
90	715-46030 PIPE END SECTION, 30 IN.	1.000	EACH
91	720-02810 INLET, B5	1.000	EACH
92	726-58789 BEARING ASSEMBLY, ELASTOMERIC, II	14.000	EACH
93	726-99095 BEARING ASSEMBLY, ELASTOMERIC, I	8.000	EACH
94	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
95	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
96	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
97	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12,103.000	LFT
98	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	162.000	LFT

CALL ORDER : 390

CONTRACT ID : B -28866-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK RECONSTRUCTION & WIDENING		
99	801-06640 CONSTRUCTION SIGN, A	65.000	EACH
100	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
101	801-06710 FLASHING ARROW SIGN	60.000	DAY
102	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
103	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000	EACH
104	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	4.000	EACH
105	801-07119 BARRICADE, III-B	120.000	LFT
106	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	1,340.000	LFT
107	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
108	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
109	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	1.000	EACH
110	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	551.000	LFT
111	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	6.000	EACH
112	802-07158 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, I	2.000	EACH
113	802-09572 SIGN, PANEL, SHEETING TYPE IX, WITH LEGEND	533.000	SFT
114	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	109.000	SFT
115	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	221.000	SFT
116	802-76095 STRUCTURAL STEEL, BREAKAWAY	947.000	LBS
117	802-76140 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM	2.000	EACH
118	805-02426 WIRE, THW, NO. 4 CU, IN PLASTIC DUCT, IN CONDUIT, 4 1C	235.000	LFT
119	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	185.000	LFT
120	805-86890 POLE CIRCUIT CABLE, 1C NO. 10 THW OR TW STRANDED COPPER	60.000	LFT
121	807-01077 EXTERNAL WINCH PAD, CONCRETE	2.000	EACH
122	807-02191 HANDHOLE, LIGHTING	3.000	EACH
123	807-04309 PORTABLE TOWER LIGHTING DRIVE SYSTEM	2.000	EACH
124	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1,870.000	LFT
125	807-08469 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING,	2.000	EACH
126	807-82160 LIGHT POLE, HIGH MAST, 95 FT. E.M.H.	2.000	EACH
127	807-84752 LIGHT POLE, 40 FT. E.M.H., 10.0 FT. MAST ARM, TRANSFORMER	2.000	EACH
128	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE	2.000	EACH
129	807-86665 LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM	8.000	EACH
130	807-86830 CONCRETE FOUNDATION WITH GROUNDING, 4 FT. DIAMETER X 20 FT.	2.000	EACH
131	807-86910 CONNECTOR KIT, UNFUSED	4.000	EACH
132	807-86915 CONNECTOR KIT, FUSED	6.000	EACH
133	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	6.000	EACH
134	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	2.000	EACH
135	807-86930 INSULATION LINK, NONWATERPROOFED	6.000	EACH
136	807-86935 INSULATION LINK, WATERPROOFED	6.000	EACH
137	807-86955 CABLE DUCT MARKER	1.000	EACH
138	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	630.000	LFT
139	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	514.000	LFT
140	808-06368 TRANSVERSE MARKING, REMOVE	286.000	LFT
141	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,749.000	LFT
142	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	2,680.000	LFT
143	808-06716 LINE, REMOVE	4,580.000	LFT
144	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	2.000	EACH
145	808-75001 LINE, PAINT, BROKEN, WHITE, 5 IN.	1,680.000	LFT
146	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	673.000	LFT
147	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	147.000	LFT

CALL ORDER : 390

CONTRACT ID : B -28866-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK RECONSTRUCTION & WIDENING		
148 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	145.000	LFT
149 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	2.000	EACH
150 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	86.000	EACH
151 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	172.000	EACH
152 808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	918.000	LFT

