

CALL ORDER : 201

CONTRACT ID : R -26792-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02279 CURB AND GUTTER, REMOVE	17.000	m
14	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
15	202-96133 PIPE, REMOVE	109.000	m
16	203-02000 EXCAVATION, COMMON	5,700.000	m3
17	203-02070 BORROW	2,500.000	m3
18	205-06932 TEMPORARY CHECK DAM, STRAW BALES	96.000	m
19	205-06933 TEMP DITCH INLET PROTECTION	1.000	EACH
20	205-06937 TEMPORARY SILT FENCE	403.000	m
21	207-08263 SUBGRADE TREATMENT, TYPE IA	9,100.000	m2
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	676.000	m2
23	211-09264 STRUCTURAL BACKFILL, TYPE 1	355.000	m3
24	211-09265 STRUCTURAL BACKFILL, TYPE 2	88.000	m3
25	304-07490 HMA PATCHING, TYPE B	61.000	Mg
26	306-08043 MILLING, TRANSITION	730.000	m2
27	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
28	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	640.000	Mg
29	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1,066.000	Mg
30	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	3,717.000	Mg
31	402-07433 HMA SURFACE, TYPE B	66.000	Mg
32	402-07438 HMA INTERMEDIATE, TYPE B	87.000	Mg
33	406-05520 ASPHALT FOR TACK COAT	5.500	Mg
34	604-07900 CURB RAMP, CONCRETE, F	33.000	m2
35	604-91531 SIDEWALK, CONCRETE, 100 mm	1,009.000	m2
36	605-06140 CURB AND GUTTER, CONCRETE	1,375.000	m
37	605-09137 CURB TURNOUT	9.000	m
38	610-09108 PCCP FOR APPROACHES, 225 mm	676.000	m2
39	616-02320 GEOTEXTILES	401.000	m2
40	616-06406 RIPRAP, REVETMENT	334.000	m2
41	621-06575 SODDING, NURSERY	5,896.000	m2
42	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, 50 TO 63 mm	62.000	EACH
43	628-09401 FIELD OFFICE, A	9.000	MOS
44	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	9.000	MOS
45	703-06028 REINFORCING BARS	3,403.000	kg
46	706-04683 RAILING	62.000	m
47	714-26708 STRUCTURE, PRECAST, RC, BOX SECTION 2400 mm X 1200 mm	20.200	m
48	714-44240 CONCRETE, A, STRUCTURES	49.000	m3
49	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	17.000	m

CALL ORDER : 201

CONTRACT ID : R -26792-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	115.000	m
51	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	30.000	m
52	715-05168 PIPE, TYPE 3, CIRCULAR, 300 mm	13.000	m
53	715-05276 PIPE, TYPE 1, DEFORMED, MIN. AREA 3.80 m2	32.000	m
54	715-46000 PIPE END SECTION, 300 mm	2.000	EACH
55	715-46005 PIPE END SECTION, 375 mm	15.000	EACH
56	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
57	720-45275 PIPE CATCH BASIN, 600 mm	1.000	EACH
58	720-96999 FIRE HYDRANT ASSEMBLY	1.000	EACH
59	720-98174 INLET, B15	8.000	EACH
60	720-98555 INLET, C15	2.000	EACH
61	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
62	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
63	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
64	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
65	801-07118 BARRICADE, III-A	30.000	m
66	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	11.430	m
67	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
68	802-09838 SIGN, SHEET, WITH LEGEND 2.03mm	7.160	m2
69	802-09840 SIGN, SHEET, WITH LEGEND 2.54mm	0.720	m2
70	802-09842 SIGN, SHEET, WITH LEGEND 3.18mm	4.320	m2
71	805-01815 SIGNAL SUPPORT FOUNDATION, 915 mm X 3658 mm	4.000	EACH
72	805-01842 HANDHOLE, SIGNAL	5.000	EACH
73	805-01844 CONDUIT STEEL GALVANIZED 50 mm, UNDERGROUND	221.000	m
74	805-01879 SIGNAL SERVICE	1.000	EACH
75	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 450 mm	4.000	EACH
76	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
77	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	6.000	EACH
78	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm	2.000	EACH
79	805-78370 PEDESTRIAN PUSH BUTTON	4.000	EACH
80	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
81	805-78467 SIGNAL CABLE, 3C 8GA	5.000	m
82	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA	377.000	m
83	805-78480 SIGNAL CABLE, 3C 14GA	297.000	m
84	805-78485 SIGNAL CABLE, 5C 14GA	414.000	m
85	805-78490 SIGNAL CABLE, 7C 14GA	299.000	m
86	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	557.000	m
87	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
88	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	438.000	m
89	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
90	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
91	805-86900 JUNCTION BOX	4.000	EACH
92	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100 mm	205.000	m
93	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100 mm	925.000	m
94	808-75278 TRANSVERSE MARKING, THERMOPLASTIC, SOLID, YELLOW,	106.000	m
95	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	57.000	m
96	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	93.000	m
97	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	7.000	EACH
98	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	4.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 201

CONTRACT ID : R -26792-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
99 808-92027	LINE, THERMO, SOLID, YELLOW, 200 mm	573.000	m

CALL ORDER : 205

CONTRACT ID : R -26831-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	200.000	SYS
14	203-02000 EXCAVATION, COMMON	2,327.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	82.000	TON
16	205-06933 TEMP DITCH INLET PROTECTION	5.000	EACH
17	205-06937 TEMPORARY SILT FENCE	3,860.000	LFT
18	207-08263 SUBGRADE TREATMENT, TYPE IA	6,303.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,111.000	SYS
20	211-09264 STRUCTURAL BACKFILL, TYPE 1	388.000	CYS
21	303-01180 COMPACTED AGGREGATE, NO. 53	659.000	TON
22	304-07493 WIDENING WITH HMA, TYPE B	325.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	5,244.000	SYS
24	402-07433 HMA SURFACE, TYPE B	806.000	TON
25	402-07438 HMA INTERMEDIATE, TYPE B	637.000	TON
26	402-07441 HMA BASE, TYPE B	2,095.000	TON
27	402-07451 HMA WEDGE AND LEVEL, TYPE B	33.000	TON
28	406-05520 ASPHALT FOR TACK COAT	5.000	TON
29	610-07487 HMA FOR APPROACHES, TYPE B	291.000	TON
30	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	3.000	EACH
31	615-06490 RIGHT OF WAY MARKER	40.000	EACH
32	615-06505 MONUMENT, B	10.000	EACH
33	615-06510 MONUMENT, C	2.000	EACH
34	616-02320 GEOTEXTILES	471.000	SYS
35	616-06405 RIPRAP, REVETMENT	86.000	TON
36	616-06451 RIPRAP, UNIFORM	239.000	TON
37	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
38	621-06559 MULCHED SEEDING, R	5,678.000	SYS
39	621-06575 SODDING, NURSERY	5,678.000	SYS
40	628-09402 FIELD OFFICE, B	6.000	MOS
41	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN	4.000	EACH
42	715-03584 SAFETY METAL END SECTION, 4:1, 18 IN	2.000	EACH
43	715-04857 SAFETY METAL END SECTION,	2.000	EACH
44	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN	62.000	LFT
45	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	696.000	LFT
46	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	17.000	LFT
47	715-05237 PIPE, TYPE 1, DEFORMED, MIN AREA 6.4 SF	77.000	LFT
48	720-45030 INLET, E7	5.000	EACH
49	801-03290 CONSTRUCTION SIGN, C	6.000	EACH

CALL ORDER : 205

CONTRACT ID : R -26831-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
50	801-04308 ROAD CLOSURE SIGN ASSEMBLY	16.000	EACH
51	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	14,310.000	LFT
52	801-06625 DETOUR ROUTE MARKER ASSEMBLY	18.000	EACH
53	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
54	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
55	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
56	801-07118 BARRICADE, III-A	168.000	LFT
57	801-07119 BARRICADE, III-B	24.000	LFT
58	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	359.000	LFT
59	802-07060 SIGN, SHEET, RELOCATE	18.000	EACH
60	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	27.000	SFT
61	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	27.000	SFT
62	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN	30.000	SFT
63	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	4.000	EACH
64	805-01842 HANDHOLE, SIGNAL	7.000	EACH
65	805-01879 SIGNAL SERVICE	1.000	EACH
66	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
67	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	4.000	EACH
68	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	2.000	EACH
69	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
70	805-78420 DISCONNECT HANGER	3.000	EACH
71	805-78467 SIGNAL CABLE, 3C 8GA	8.000	LFT
72	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA	1,590.000	LFT
73	805-78485 SIGNAL CABLE, 5C 14GA	106.000	LFT
74	805-78490 SIGNAL CABLE, 7C 14GA	410.000	LFT
75	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,195.000	LFT
76	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
77	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	526.000	LFT
78	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
79	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT	4.000	EACH
80	805-86900 JUNCTION BOX	3.000	EACH
81	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	1,010.000	LFT
82	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,835.000	LFT
83	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	9,788.000	LFT
84	808-75278 TRANSVERSE MARKING, THERMOPLASTIC, SOLID, YELLOW,	321.000	LFT
85	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	95.000	LFT
86	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	9.000	EACH
87	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	65.000	EACH
88	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	65.000	EACH
89	808-92027 LINE, THERMO, SOLID, YELLOW, 8 IN	1,420.000	LFT

CALL ORDER : 211

CONTRACT ID : R -29489-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	279.000	SYS
11	202-02271 HEADWALL, REMOVE	8.000	EACH
12	202-02279 CURB AND GUTTER, REMOVE	49.000	LFT
13	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
14	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
15	202-52710 SIDEWALK, CONCRETE, REMOVE	10.000	SYS
16	202-91385 INLET, REMOVE	1.000	EACH
17	203-02000 EXCAVATION, COMMON	25,323.000	CYS
18	203-02010 EXCAVATION, ROCK	3,659.000	CYS
19	203-02070 BORROW	11,580.000	CYS
20	203-02131 EXPLORATORY EXCAVATION	35.000	CYS
21	204-02290 SETTLEMENT PLATE	5.000	EACH
22	205-03371 SEDIMENT, REMOVE	100.000	CYS
23	205-06933 TEMP DITCH INLET PROTECTION	12.000	EACH
24	205-06937 TEMPORARY SILT FENCE	7,339.000	LFT
25	205-09543 NO 2 STONE	100.000	TON
26	207-08263 SUBGRADE TREATMENT, TYPE IA	38,669.000	SYS
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	4,582.000	SYS
28	211-02050 B BORROW	1,418.000	CYS
29	211-07454 STRUCTURAL BACKFILL	929.000	CYS
30	211-09264 STRUCTURAL BACKFILL, TYPE 1	8,658.000	CYS
31	211-09266 STRUCTURAL BACKFILL, TYPE 3	620.000	CYS
32	214-07203 GEOGRID, TYPE II	3,900.000	SYS
33	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,000.000	TON
34	303-07449 COMPACTED AGGREGATE, NO. 73	70.000	TON
35	304-07493 WIDENING WITH HMA, TYPE B	222.000	TON
36	306-08034 MILLING, ASPHALT, 1 1/2 IN	891.000	SYS
37	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	2,500.000	TON
38	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	4,004.000	TON
39	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	6,406.000	TON
40	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	5,203.000	TON
41	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	5,646.000	TON
42	402-07451 HMA WEDGE AND LEVEL, TYPE B	90.000	TON
43	406-05520 ASPHALT FOR TACK COAT	33.000	TON
44	601-02241 GUARDRAIL, REMOVE	194.000	LFT
45	603-01159 FENCE, CHAIN LINK, 42 IN	786.000	LFT
46	604-07901 CURB RAMP, CONCRETE, G	73.000	SYS
47	604-07902 CURB RAMP, CONCRETE, H	15.000	SYS
48	604-91531 SIDEWALK, CONCRETE, 4 IN	2,615.000	SYS
49	604-95344 HANDRAIL, PEDESTRIAN	983.000	LFT

CALL ORDER : 211

CONTRACT ID : R -29489-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
50	605-06090 CURB, INTEGRAL, CONCRETE	90.000	LFT
51	605-06140 CURB AND GUTTER, CONCRETE	12,584.000	LFT
52	610-07487 HMA FOR APPROACHES, TYPE B	503.000	TON
53	610-08446 PCCP FOR APPROACHES, 6 IN	2,919.000	SYS
54	610-09108 PCCP FOR APPROACHES, 9 IN	1,438.000	SYS
55	611-06497 MAILBOX ASSEMBLY, SINGLE	29.000	EACH
56	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
57	615-06505 MONUMENT, B	22.000	EACH
58	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
59	616-02320 GEOTEXTILES	1,377.000	SYS
60	616-05689 RIPRAP, CLASS 2	231.000	TON
61	616-06405 RIPRAP, REVETMENT	604.000	TON
62	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
63	621-06545 FERTILIZER	2.000	TON
64	621-06554 SEED MIXTURE, U	720.000	LBS
65	621-06557 SEED MIXTURE, T	1,415.000	LBS
66	621-06565 MULCHING MATERIAL	9.600	TON
67	621-06567 WATER	81.000	KGAL
68	621-06574 SODDING	22,397.000	SYS
69	628-09401 FIELD OFFICE, A	21.000	MOS
70	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	42.000	MOS
71	709-51821 SURFACE SEAL	LUMP	LUMP
72	714-08514 WINGWALL	292.000	SFT
73	715-04612 PIPE	431.000	LFT
74	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN	1,399.000	LFT
75	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	13,852.000	LFT
76	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	94.000	LFT
77	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	2,659.000	LFT
78	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	1,551.000	LFT
79	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN	248.000	LFT
80	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN	757.000	LFT
81	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN	271.000	LFT
82	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN	30.000	LFT
83	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	66.000	LFT
84	715-05408 PIPE, SANITARY SEWER, 8 IN	3,475.000	LFT
85	715-05409 PIPE, SANITARY SEWER, 10 IN	145.000	LFT
86	715-05711 PIPE, SANITARY SEWER, 6 IN	905.000	LFT
87	715-06004 CONCRETE ANCHOR, 48 IN	1.000	EACH
88	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	28.000	TON
89	715-46005 PIPE END SECTION, 15 IN	6.000	EACH
90	715-46010 PIPE END SECTION, 18 IN	3.000	EACH
91	715-46020 PIPE END SECTION, 24 IN	1.000	EACH
92	715-46040 PIPE END SECTION, 36 IN	1.000	EACH
93	715-90052 LIFT STATION	LUMP	LUMP
94	715-96960 PIPE, PVC, 15 IN	431.000	LFT
95	715-98961 FORCE MAIN	2,967.000	LFT
96	718-04986 CLEANOUT	25.000	EACH
97	718-06528 OUTLET PROTECTOR, 1	4.000	EACH
98	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT

CALL ORDER : 211

CONTRACT ID : R -29489-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
99	718-52610 AGGREGATE FOR UNDERDRAINS	1,249.000	CYS
100	718-99153 GEOTEXTILES FOR UNDERDRAIN	14,814.000	SYS
101	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
102	720-44296 CAP INLET	2.000	EACH
103	720-45030 INLET, E7	10.000	EACH
104	720-45035 INLET, F7	2.000	EACH
105	720-45045 INLET, J10	1.000	EACH
106	720-45055 INLET, M10	1.000	EACH
107	720-45265 PIPE CATCH BASIN, 15 IN	4.000	EACH
108	720-45410 MANHOLE, C4	27.000	EACH
109	720-45410 MANHOLE, C4	15.000	EACH
110	720-93409 INLET, B15, MODIFIED	3.000	EACH
111	720-93411 INLET, C15, MODIFIED	11.000	EACH
112	720-94157 MANHOLE, C	2.000	EACH
113	720-94612 MANHOLE, K4	1.000	EACH
114	720-95422 MANHOLE, J4	16.000	EACH
115	720-97008 FIRE HYDRANT ASSEMBLY, RELOCATE	1.000	EACH
116	720-98174 INLET, B15	27.000	EACH
117	720-98555 INLET, C15	30.000	EACH
118	720-98625 MANHOLE, C4, DROP	2.000	EACH
119	723-08477 STRUCTURE, PRECAST THREE-SIDED, 144 IN X 60 IN	106.000	LFT
120	731-08252 LEVELING PAD	234.000	LFT
121	731-93945 FACE PANELS, CONCRETE	1,840.000	SFT
122	731-93946 WALL ERECTION	1,840.000	SFT
123	732-08419 MODULAR BLOCK WALL	465.000	SYS
124	732-08421 MODULAR BLOCK WALL ERECTION	465.000	SYS
125	732-08618 RISER	8.000	EACH
126	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
127	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
128	801-06625 DETOUR ROUTE MARKER ASSEMBLY	37.000	EACH
129	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
130	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
131	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
132	801-07119 BARRICADE, III-B	100.000	LFT
133	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	186.000	LFT
134	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	21.000	LFT
135	802-07127 SIGN, DOUBLE-FACED SHEET ENCAPSULATED LENS,	38.000	SFT
136	802-07135 CABLE SPAN SIGN STRUCTURE FOUNDATION, IV	4.000	EACH
137	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	95.000	SFT
138	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	9.000	SFT
139	802-76125 OVERHEAD SIGN STRUCTURE, CABLESPAN	2.000	EACH
140	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	115.000	LFT
141	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	507.000	LFT
142	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	500.000	LFT
143	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2,138.000	LFT
144	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	16,266.000	LFT
145	808-75278 TRANSVERSE MARKING, THERMOPLASTIC, SOLID, YELLOW,	290.000	LFT
146	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	193.000	LFT
147	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	366.000	LFT



SCHEDULE OF PAY ITEMS

CALL ORDER : 211

CONTRACT ID : R -29489-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
148 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	18.000	EACH
149 808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	1.000	EACH
150 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	318.000	EACH

CALL ORDER : 225

CONTRACT ID : R -29852-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	96.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-02240 PAVEMENT REMOVAL	44,285.000	SYS
17	202-02241 GUARDRAIL, REMOVE	800.000	LFT
18	203-02000 EXCAVATION, COMMON	44,858.000	CYS
19	203-02070 BORROW	3,159.000	CYS
20	203-02070 BORROW	2,323.000	CYS
21	203-08279 EXPANDED POLYSTYRENE FILL	5,650.000	CYS
22	203-08607 LINEAR GRADING	5,070.000	LFT
23	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	11.000	EACH
24	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	543.000	TON
25	205-06934 TEMPORARY MULCHING	9.500	TON
26	205-06937 TEMPORARY SILT FENCE	930.000	LFT
27	207-08263 SUBGRADE TREATMENT, TYPE IA	82,010.000	SYS
28	210-07857 INCLINOMETER	3.000	EACH
29	211-02050 B BORROW	555.000	CYS
30	211-02050 B BORROW	2,080.000	CYS
31	211-07454 STRUCTURAL BACKFILL	117.000	CYS
32	211-09394 SHREDDED TIRE	5,190.000	CYS
33	214-07203 GEOGRID, TYPE II	1,800.000	SYS
34	303-01180 COMPACTED AGGREGATE, NO. 53	7,789.000	TON
35	304-07783 HMA PATCHING, TYPE D	3,999.000	TON
36	306-08043 MILLING, TRANSITION	170.000	SYS
37	306-08432 MILLING, APPROACH	1,937.000	SYS
38	306-08563 MILLING ASPHALT, 1 1/4 IN	629,045.000	SYS
39	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
40	401-07330 QC/QA-HMA, 5, 70, SURFACE, 9.5 mm	55,610.000	TON
41	401-07382 QC/QA-HMA, 5, 70, INTERMEDIATE, 12.5 mm	6,188.000	TON
42	401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm	35,682.000	TON
43	401-07415 QC/QA-HMA, 5, 70, BASE, 25.0 mm	1,449.000	TON
44	402-07433 HMA SURFACE, TYPE B	396.000	TON
45	402-07438 HMA INTERMEDIATE, TYPE B	661.000	TON
46	402-07441 HMA BASE, TYPE B	2,638.000	TON
47	402-07784 HMA SURFACE, TYPE D	2,795.000	TON
48	402-07785 HMA INTERMEDIATE, TYPE D	4,658.000	TON
49	402-07786 HMA BASE, TYPE D	11,178.000	TON

CALL ORDER : 225

CONTRACT ID : R -29852-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	406-05520 ASPHALT FOR TACK COAT	286.780	TON
51	502-06627 PCCP, 6 IN	700.000	SYS
52	506-06333 PCCP PATCHING, FULL DEPTH	3,200.000	SYS
53	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	800.000	LFT
54	606-07484 MILLED HMA SHOULDER CORRUGATIONS	320,554.000	LFT
55	610-07488 HMA FOR APPROACHES, TYPE C	65.000	TON
56	610-07788 HMA FOR APPROACHES, TYPE D	95.000	TON
57	616-02320 GEOTEXTILES	19,050.000	SYS
58	616-06405 RIPRAP, REVETMENT	104.000	TON
59	616-09395 GEOMEMBRANE	2,667.000	SYS
60	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
61	621-02770 EROSION CONTROL BLANKET	4,949.000	SYS
62	621-06545 FERTILIZER	2.800	TON
63	621-06553 SEED MIXTURE, R	1,001.000	LBS
64	621-06557 SEED MIXTURE, T	381.000	LBS
65	621-06565 MULCHING MATERIAL	14.700	TON
66	621-06574 SODDING	9,178.000	SYS
67	628-09402 FIELD OFFICE, B	24.000	MOS
68	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	48.000	MOS
69	701-90386 TEMPORARY SHEET PILING	LUMP	LUMP
70	706-09545 COARSE AGGREGATE, NO 8	975.000	CYS
71	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	650.000	LFT
72	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	1,626.000	LFT
73	715-05203 PIPE, TYPE 4, CIRCULAR, 4 IN	20,206.000	LFT
74	718-06528 OUTLET PROTECTOR, 1	64.000	EACH
75	718-52610 AGGREGATE FOR UNDERDRAINS	3,021.000	CYS
76	718-99153 GEOTEXTILES FOR UNDERDRAIN	18,528.000	SYS
77	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	22.000	EACH
78	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
79	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	21,340.000	LFT
80	801-06209 TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN	136,452.000	LFT
81	801-06625 DETOUR ROUTE MARKER ASSEMBLY	7.000	EACH
82	801-06640 CONSTRUCTION SIGN, A	113.000	EACH
83	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
84	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
85	801-06710 FLASHING ARROW SIGN	1,095.000	DAY
86	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
87	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	4.000	EACH
88	801-07117 TEMPORARY WORKSITE FLASHING LIGHT SIGN ASSEMBLY	6.000	EACH
89	801-07119 BARRICADE, III-B	36.000	LFT
90	801-08402 TEMPORARY TRAFFIC BARRIER, TYPE 3	9,592.000	LFT
91	801-08507 TEMP TRAFFIC BARRIER, TYPE 1, ANCHORED	1,660.000	LFT
92	801-08509 TEMP TRAFFIC BARRIER, TYPE 3, ANCHORED	3,872.000	LFT
93	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	20.000	EACH
94	805-06974 WIM STATION, 4 LANE PIEZO	LUMP	LUMP
95	805-09281 WIM STATION, QUARTZ	LUMP	LUMP
96	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	39,117.000	LFT
97	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	154,607.000	LFT
98	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	4,190.000	LFT

CALL ORDER : 225

CONTRACT ID : R -29852-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
99 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN	10,390.000	LFT
100 808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN	7,750.000	LFT
101 808-06716	LINE, REMOVE	77,852.000	LFT
102 808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN	2,242.000	LFT
103 808-75008	LINE, PAINT, SOLID, WHITE, 8 IN	1,750.000	LFT
104 808-75072	TRANSVERSE MARKING, PAINT, SOLID,	438.000	LFT
105 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	163,652.000	LFT
106 808-75272	TRANSVERSE MARKING, THERMOPLASTIC, SOLID,	1,257.000	LFT
107 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2,441.000	EACH
108 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2,441.000	EACH
109 808-97127	LINE, THERMOPLASTIC, SOLID, WHITE, 5 IN	650.000	LFT

CALL ORDER : 251

CONTRACT ID : R -31680-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	30.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	18,240.000	SYS
13	202-02637 PIPE, ABANDON AND GROUT FILL	224.000	LFT
14	202-07846 TREE	25.000	EACH
15	202-52710 SIDEWALK, CONCRETE, REMOVE	10,875.000	SYS
16	202-74080 OVERHEAD SIGN STRUCTURE,	1.000	EACH
17	202-91385 INLET, REMOVE	105.000	EACH
18	202-96133 PIPE, REMOVE	1,115.000	LFT
19	203-02000 EXCAVATION, COMMON	1,800.000	CYS
20	203-02070 BORROW	3,114.000	CYS
21	205-06937 TEMPORARY SILT FENCE	5,847.000	LFT
22	205-09543 NO 2 STONE	100.000	TON
23	207-08263 SUBGRADE TREATMENT, TYPE IA	2,511.000	SYS
24	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,928.000	SYS
25	207-08268 SUBGRADE TREATMENT, TYPE IV	565.000	SYS
26	210-06192 WALL	2,774.000	LFT
27	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,640.000	CYS
28	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,713.000	TON
29	303-01180 COMPACTED AGGREGATE, NO. 53	699.000	TON
30	305-07464 PCC BASE PATCHING, 9 IN	3,121.000	SYS
31	306-08039 MILLING, ASPHALT REMOVAL	71,748.000	SYS
32	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	6,136.000	TON
33	401-07361 QC/QA-HMA, 2, 70, INTERMEDIATE, 9.5 mm	6,136.000	TON
34	402-09873 STAMPED	9,397.000	SFT
35	406-05520 ASPHALT FOR TACK COAT	37.200	TON
36	501-03489 TIE BAR, RETROFIT	3,602.000	EACH
37	604-07894 CURB RAMP, CONCRETE, A	103.000	SYS
38	604-07896 CURB RAMP, CONCRETE, B	14.000	SYS
39	604-07897 CURB RAMP, CONCRETE, C	142.000	SYS
40	604-07900 CURB RAMP, CONCRETE, F	531.000	SYS
41	604-07901 CURB RAMP, CONCRETE, G	274.000	SYS
42	604-07902 CURB RAMP, CONCRETE, H	16.000	SYS
43	604-07903 CURB RAMP, CONCRETE, K	12.000	SYS
44	604-07904 CURB RAMP, CONCRETE, L	146.000	SYS
45	604-91531 SIDEWALK, CONCRETE, 4 IN	9,636.000	SYS
46	605-06125 CURB, CONCRETE, MODIFIED	306.000	LFT
47	605-06125 CURB, CONCRETE, MODIFIED	10,218.000	LFT
48	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	18,458.000	LFT
49	605-06215 CENTER CURB, D, CONCRETE	2,968.000	LFT

CALL ORDER : 251

CONTRACT ID : R -31680-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
50	610-08446 PCCP FOR APPROACHES, 6 IN	236.000	SYS
51	610-09108 PCCP FOR APPROACHES, 9 IN	2,693.000	SYS
52	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
53	616-02320 GEOTEXTILES	9,200.000	SYS
54	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
55	621-06545 FERTILIZER	1.000	TON
56	621-06557 SEED MIXTURE, T	126.000	LBS
57	621-06565 MULCHING MATERIAL	4.000	TON
58	621-06567 WATER	37.000	KGAL
59	621-06570 TOPSOIL	2,885.000	CYS
60	621-06575 SODDING, NURSERY	10,106.000	SYS
61	621-98038 MULCH, HARDWOOD SHREDDED BARK	433.000	CYS
62	622-05616 PLANT, BROADLEAF EVERGREEN, GLOBE, DWARF, OVER 18 TO 24 IN	113.000	EACH
63	622-05639 PLANT, DECIDUOUS SHRUB, 18 TO 24 IN	72.000	EACH
64	622-05646 PLANT, DECIDUOUS TREE, MULTI-STEM, 96 TO 120 IN	19.000	EACH
65	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	528.000	EACH
66	622-05654 PLANT, PERENNIAL	18,034.000	EACH
67	628-09402 FIELD OFFICE, B	15.000	MOS
68	704-04850 CONCRETE	265.000	SYS
69	707-09101 PRECAST	2.000	EACH
70	715-04612 PIPE	1,910.000	LFT
71	715-04612 PIPE	1,740.000	LFT
72	715-04612 PIPE	4,005.000	LFT
73	715-04612 PIPE	4,300.000	LFT
74	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	9,374.000	LFT
75	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	311.000	LFT
76	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	3,799.000	LFT
77	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	2,095.000	LFT
78	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	64.000	LFT
79	715-05428 PIPE, SLOTTED VANE DRAIN, 12 IN	1,280.000	LFT
80	715-09064 VIDEO INSPECTION FOR PIPE	3,604.000	LFT
81	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
82	718-52610 AGGREGATE FOR UNDERDRAINS	3,375.000	CYS
83	720-08628 SLOTTED DRAIN PIPE CLEANOUT PORT, TYPE II	17.000	EACH
84	720-44000 CASTING, ADJUST TO GRADE	18.000	EACH
85	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	3.000	EACH
86	720-45005 INLET, A2	1.000	EACH
87	720-45045 INLET, J10	64.000	EACH
88	720-45055 INLET, M10	36.000	EACH
89	720-45075 INLET, R13	5.000	EACH
90	720-45145 INLET, J10, MODIFIED	5.000	EACH
91	720-45155 INLET, M10, MODIFIED	12.000	EACH
92	720-45410 MANHOLE, C4	33.000	EACH
93	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	11.100	LFT
94	720-90984 MANHOLE, C2	1.000	EACH
95	720-93409 INLET, B15, MODIFIED	1.000	EACH
96	720-93411 INLET, C15, MODIFIED	6.000	EACH
97	720-98174 INLET, B15	9.000	EACH
98	720-98555 INLET, C15	12.000	EACH

CALL ORDER : 251

CONTRACT ID : R -31680-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
99	721-09874 DRIPLINE	24,500.000	LFT
100	732-03944 BACKFLOW PREVENTER	9.000	EACH
101	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	5.000	EACH
102	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
103	801-04308 ROAD CLOSURE SIGN ASSEMBLY	26.000	EACH
104	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	40,104.000	LFT
105	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	39,736.000	LFT
106	801-06577 TEMPORARY PAVEMENT MARKING	11.000	LFT
107	801-06625 DETOUR ROUTE MARKER ASSEMBLY	78.000	EACH
108	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
109	801-06645 CONSTRUCTION SIGN, B	23.000	EACH
110	801-06710 FLASHING ARROW SIGN	900.000	DAY
111	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
112	801-07118 BARRICADE, III-A	1,404.000	LFT
113	801-07119 BARRICADE, III-B	624.000	LFT
114	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	1,290.000	LFT
115	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	204.000	EACH
116	802-09837 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.080 IN	30.000	SFT
117	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	687.000	SFT
118	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN	131.000	SFT
119	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	70.000	SFT
120	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN	210.000	SFT
121	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	5.000	EACH
122	805-01746 INTERCONNECT CABLE, RELOCATE	LUMP	LUMP
123	805-01816 SIGNAL SUPPORT FOUNDATION, 36 IN X 36 IN X 96 IN	18.000	EACH
124	805-01842 HANDHOLE, SIGNAL	25.000	EACH
125	805-02069 SIGNAL CANTILEVER STRUCTURE, MAST ARM 25FT	1.000	EACH
126	805-02072 SIGNAL CANTILEVER STRUCTURE, MAST ARM 30FT	6.000	EACH
127	805-02073 SIGNAL CANTILEVER STRUCTURE, MAST ARM 35FT	5.000	EACH
128	805-02077 SIGNAL CANTILEVER STRUCTURE, MAST ARM 40FT	2.000	EACH
129	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	38.000	EACH
130	805-02373 SIGNAL INTERCONNECT CABLE, FIBER OPTIC	3,000.000	LFT
131	805-03083 CONDUIT, RIGID, PVC, 1.50 IN	4,083.000	LFT
132	805-03978 EMERGENCY VEHICLE PREEMPTION DETECTOR,	2.000	EACH
133	805-03979 EMERGENCY VEHICLE PREEMPTION DETECTOR,	9.000	EACH
134	805-03980 EMERGENCY VEHICLE CONFIRMATION LIGHT KIT	20.000	EACH
135	805-03983 PHASE SELECTORS	5.000	EACH
136	805-04973 CONDUIT	2,660.000	LFT
137	805-05673 SIGNAL AND LIGHTING COMBINATION STRUCTURE	1.000	EACH
138	805-05673 SIGNAL AND LIGHTING COMBINATION STRUCTURE	1.000	EACH
139	805-05673 SIGNAL AND LIGHTING COMBINATION STRUCTURE	1.000	EACH
140	805-05673 SIGNAL AND LIGHTING COMBINATION STRUCTURE	1.000	EACH
141	805-06483 CONTROLLER	9.000	EACH
142	805-08102 DECORATIVE	144.000	EACH
143	805-08102 DECORATIVE	18.000	EACH
144	805-08494 RADIO SPREAD SPECTRUM	5.000	EACH
145	805-09098 RADIO, YAGI ANTENNA	6.000	EACH
146	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	5.000	EACH
147	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	40.000	EACH

CALL ORDER : 251

CONTRACT ID : R -31680-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
148	805-78445 SIGNAL SERVICE	5.000	EACH
149	805-78467 SIGNAL CABLE, 3C 8GA	214.000	LFT
150	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA	7,800.000	LFT
151	805-78480 SIGNAL CABLE, 3C 14GA	5,268.000	LFT
152	805-78485 SIGNAL CABLE, 5C 14GA	7,472.000	LFT
153	805-78490 SIGNAL CABLE, 7C 14GA	2,598.000	LFT
154	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,925.000	LFT
155	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
156	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	2,600.000	LFT
157	805-78900 PEDESTAL FOUNDATION, A	7.000	EACH
158	805-78925 CONTROLLER CABINET FOUNDATION, P1	5.000	EACH
159	805-90005 SIGNAL PEDESTAL, 10 FT	7.000	EACH
160	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHAN	7.000	EACH
161	805-96121 PEDESTRIAN PUSH BUTTON AND SIGN	38.000	EACH
162	807-02191 HANDHOLE, LIGHTING	32.000	EACH
163	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	144.000	EACH
164	807-03950 LUMINAIRE, ORNAMENTAL	73.000	EACH
165	807-03950 LUMINAIRE, ORNAMENTAL	75.000	EACH
166	807-03972 CONDUIT, PVC, 1 IN, SCHEDULE 40, FOR ELECTRIC	3,439.000	LFT
167	807-04651 WIRE,	10,641.000	LFT
168	807-04654 LIGHT POLE	73.000	EACH
169	807-04654 LIGHT POLE	71.000	EACH
170	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	2,685.000	LFT
171	807-07580 WIRE #4 COPPER PLASTIC DUCT TRENCH 4, 1/C	15,283.000	LFT
172	807-86810 SERVICE POINT, II	7.000	EACH
173	807-86843 WIRE, NO 4 COPPER, 1/C	15,258.000	LFT
174	807-86905 TRANSITION FITTINGS, GALVANIZED STEEL CONDUIT TO PLASTIC	205.000	EACH
175	807-86910 CONNECTOR KIT, UNFUSED	296.000	EACH
176	807-86915 CONNECTOR KIT, FUSED	296.000	EACH
177	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	390.000	EACH
178	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	24.000	EACH
179	807-86930 INSULATION LINK, NON-WATERPROOFED	296.000	EACH
180	807-86935 INSULATION LINK, WATERPROOFED	186.000	EACH
181	807-86955 CABLE-DUCT MARKER	8.000	EACH
182	807-87556 WIRE, THW OR TW, NO. 10 COPPER STRANDED	7,337.000	LFT
183	807-95888 WIRE, NO. 8 COPPER, 1C	7,260.000	LFT
184	807-95889 WIRE, NO. 10 COPPER, 1C	6,729.000	LFT
185	807-95890 WIRE, NO. 12 COPPER, 1/C	1,476.000	LFT
186	807-97237 WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN	5,328.000	LFT
187	808-03775 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (BIKE)	44.000	EACH
188	808-03775 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (BIKE)	44.000	EACH
189	808-04096 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (LANE)	44.000	EACH
190	808-04767 LINE	38.000	LFT
191	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	4,192.000	LFT
192	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,864.000	LFT
193	808-06716 LINE, REMOVE	1,345.000	LFT
194	808-75043 LINE THERMOPLASTIC, SOLID, WHITE, 6 IN	14,828.000	LFT
195	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	17,070.000	LFT
196	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	1,214.000	LFT



CALL ORDER : 251

CONTRACT ID : R -31680-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
197 808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	8,793.000	LFT
198 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	39.000	EACH
199 808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	19.000	EACH
200 808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	4.000	EACH
201 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	304.000	EACH
202 808-98796	LINE, THERMOPLASTIC DOTTED WHITE, 4 IN, 2FT LINE, 4FT GAP	60.000	LFT

CALL ORDER : 301

CONTRACT ID : R -32795-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02278 CURB, CONCRETE, REMOVE	190.000	LFT
9	202-04089 SIGN, SHEET, REMOVE	4.000	EACH
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	202-52710 SIDEWALK, CONCRETE, REMOVE	19.000	SYS
12	203-02000 EXCAVATION, COMMON	1,253.000	CYS
13	203-02070 BORROW	200.000	CYS
14	205-02770 EROSION CONTROL BLANKET	200.000	SYS
15	205-06933 TEMP DITCH INLET PROTECTION	7.000	EACH
16	205-06937 TEMPORARY SILT FENCE	730.000	LFT
17	205-09543 NO 2 STONE	50.000	TON
18	207-08263 SUBGRADE TREATMENT, TYPE IA	2,011.000	SYS
19	211-09264 STRUCTURAL BACKFILL, TYPE 1	140.000	CYS
20	211-09265 STRUCTURAL BACKFILL, TYPE 2	2.300	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	130.000	TON
22	304-07492 WIDENING WITH HMA, TYPE A	519.000	TON
23	306-08033 MILLING, ASPHALT, 1 IN	200.000	SYS
24	306-08042 MILLING, SCARIFICATION/PROFILE	4,265.000	SYS
25	306-08043 MILLING, TRANSITION	600.000	SYS
26	402-07432 HMA SURFACE, TYPE A	58.000	TON
27	402-07433 HMA SURFACE, TYPE B	431.000	TON
28	402-07450 HMA WEDGE AND LEVEL, TYPE A	120.000	TON
29	406-05520 ASPHALT FOR TACK COAT	3.540	TON
30	604-06070 SIDEWALK, CONCRETE	591.000	SYS
31	604-07898 CURB RAMP, CONCRETE, D	4.000	SYS
32	604-07901 CURB RAMP, CONCRETE, G	29.000	SYS
33	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	1,106.000	LFT
34	610-07486 HMA FOR APPROACHES, TYPE A	64.000	TON
35	610-08446 PCCP FOR APPROACHES, 6 IN	338.000	SYS
36	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	14.000	EACH
37	616-02320 GEOTEXTILES	43.000	SYS
38	616-05688 RIPRAP, CLASS 1	35.000	TON
39	616-06451 RIPRAP, UNIFORM	2.000	TON
40	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
41	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	8,200.000	SYS
42	621-06560 MULCHED SEEDING, U	5,451.000	SYS
43	621-06575 SODDING, NURSERY	810.000	SYS
44	621-98038 MULCH, HARDWOOD SHREDDED BARK	25.000	CYS
45	628-09401 FIELD OFFICE, A	12.000	MOS
46	702-03607 CORED HOLE IN CONCRETE	1.000	EACH
47	702-90915 CONCRETE, CLASS A	6.000	CYS
48	715-02181 SANITARY SEWER SERVICE ADJUSTMENT	100.000	LFT

49 715-05149

PIPE, TYPE 2, CIRCULAR, 12 IN

117.000

LFT

CALL ORDER : 301

CONTRACT ID : R -32795-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
50	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	150.000	LFT
51	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	218.000	LFT
52	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	135.000	LFT
53	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN	332.000	LFT
54	715-05155 PIPE, TYPE 2, CIRCULAR, 27 IN	103.000	LFT
55	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN	78.000	LFT
56	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	48.000	LFT
57	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN	48.000	LFT
58	715-05428 PIPE, SLOTTED VANE DRAIN, 12 IN	114.000	LFT
59	715-05756 PIPE EXTENSION, CIRCULAR, 12 IN	15.000	LFT
60	715-06492 CONCRETE ANCHOR, 54 IN	2.000	EACH
61	715-08282 HMA FOR STRUCTURE INSTALLATION, TYPE A	22.000	TON
62	715-09455 PIPE, TYPE 2, CIRCULAR, 16 IN.	188.000	LFT
63	715-46000 PIPE END SECTION, 12 IN	4.000	EACH
64	715-46005 PIPE END SECTION, 15 IN	2.000	EACH
65	715-46010 PIPE END SECTION, 18 IN	3.000	EACH
66	715-90567 WATER MAIN, RELOCATED, 6 IN.	295.000	LFT
67	715-90832 PIPE, DRAINTILE, 6 IN	150.000	LFT
68	715-93910 WATER SERVICE LINE, ADJUST	13.000	EACH
69	718-06529 OUTLET PROTECTOR, 2	1.000	EACH
70	718-52610 AGGREGATE FOR UNDERDRAINS	9.000	CYS
71	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
72	720-45035 INLET, F7	6.000	EACH
73	720-45045 INLET, J10	6.000	EACH
74	720-45410 MANHOLE, C4	1.000	EACH
75	720-92025 MANHOLE, D2	1.000	EACH
76	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	4.000	EACH
77	720-96999 FIRE HYDRANT ASSEMBLY	1.000	EACH
78	725-06873 PIPE LINER, THERMOPLASTIC, 54 IN	93.000	LFT
79	732-02531 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON 6 IN.	1.000	EACH
80	732-90578 WATER METER, RELOCATE	1.000	EACH
81	732-97009 FIRE HYDRANT ASSEMBLY, REMOVE	1.000	EACH
82	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
83	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,200.000	LFT
84	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
85	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
86	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
87	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN	82.000	LFT
88	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	67.000	LFT
89	802-07060 SIGN, SHEET, RELOCATE	6.000	EACH
90	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	72.000	SFT
91	802-90623 SIGN BRACKET FOR STREET NAME	2.000	EACH
92	802-90623 SIGN BRACKET FOR STREET NAME	2.000	EACH
93	802-97812 STREET NAME IDENTIFICATION SIGN	10.000	EACH
94	805-01842 HANDHOLE, SIGNAL	8.000	EACH
95	805-04133 SIGNAL PEDESTAL, 12FT	8.000	EACH
96	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	2.000	EACH
97	805-78467 SIGNAL CABLE, 3C 8GA	16.000	LFT
98	805-78485 SIGNAL CABLE, 5C 14GA	715.000	LFT

CALL ORDER : 301

CONTRACT ID : R -32795-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
99 807-03965	CONDUIT, PVC, 2.50 IN, SCHEDULE 80, FOR ELECTRIC	443.000	LFT
100 807-86805	SERVICE POINT, I	2.000	EACH
101 808-01296	PAVEMENT MESSAGE MARKING, THERMOPLASTIC (STOP AHEAD)	2.000	EACH
102 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,572.000	LFT
103 808-75043	LINE THERMOPLASTIC, SOLID, WHITE, 6 IN	323.000	LFT
104 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,300.000	LFT
105 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	191.000	LFT
106 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	34.000	EACH

CALL ORDER : 371

CONTRACT ID : RS-30455-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08523 RADIO ONLY SERVICE	12.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	202-02240 PAVEMENT REMOVAL	25.000	SYS
15	202-52710 SIDEWALK, CONCRETE, REMOVE	62.000	SYS
16	202-93741 GUARDRAIL END TREATMENT, REMOVE	6.000	EACH
17	202-96133 PIPE, REMOVE	47.000	LFT
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	50.000	CYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	360.000	TON
20	303-01180 COMPACTED AGGREGATE, NO. 53	6,885.000	TON
21	304-07490 HMA PATCHING, TYPE B	675.000	TON
22	306-08033 MILLING, ASPHALT, 1 IN	7,150.000	SYS
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	88,800.000	SYS
24	306-08037 MILLING, ASPHALT, 3 IN	23,650.000	SYS
25	306-08432 MILLING, APPROACH	30,000.000	SYS
26	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
27	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	10,340.000	TON
28	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	17,225.000	TON
29	402-07451 HMA WEDGE AND LEVEL, TYPE B	2,200.000	TON
30	406-05520 ASPHALT FOR TACK COAT	73.000	TON
31	601-92948 GUARDRAIL, ADJUST HEIGHT	1,251.000	LFT
32	601-94689 GUARDRAIL END TREATMENT, OS	6.000	EACH
33	604-07896 CURB RAMP, CONCRETE, B	43.000	SYS
34	604-07901 CURB RAMP, CONCRETE, G	45.000	SYS
35	610-07487 HMA FOR APPROACHES, TYPE B	2,710.000	TON
36	615-06520 MONUMENT, RE-ESTABLISH	9.000	EACH
37	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	9.000	EACH
38	628-09402 FIELD OFFICE, B	6.000	MOS
39	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
40	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN	50.000	LFT
41	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
42	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
43	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,650.000	LFT
44	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,650.000	LFT
45	801-06640 CONSTRUCTION SIGN, A	44.000	EACH
46	801-06710 FLASHING ARROW SIGN	244.000	DAY
47	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
48	801-92448 CONSTRUCTION SIGNS, MOBILE	244.000	DAY
49	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	88,000.000	LFT

CALL ORDER : 371

CONTRACT ID : RS-30455-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	10,700.000	LFT
51 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	15,400.000	LFT
52 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	100.000	LFT
53 808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	30.000	LFT
54 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	723.000	EACH

CALL ORDER : 401

CONTRACT ID : RS-31975-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	303-07449 COMPACTED AGGREGATE, NO. 73	1,138.000	TON
10	304-07490 HMA PATCHING, TYPE B	400.000	TON
11	306-08034 MILLING, ASPHALT, 1 1/2 IN	139,412.000	SYS
12	306-08043 MILLING, TRANSITION	200.000	SYS
13	306-08432 MILLING, APPROACH	10,380.000	SYS
14	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
15	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	11,502.000	TON
16	402-07451 HMA WEDGE AND LEVEL, TYPE B	100.000	TON
17	406-05520 ASPHALT FOR TACK COAT	41.000	TON
18	610-07487 HMA FOR APPROACHES, TYPE B	856.000	TON
19	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	15.000	TON
20	612-60410 DRILLED HOLE FOR UNDERSEAL	242.000	EACH
21	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
22	615-06527 MONUMENT, SECTION CORNER	4.000	EACH
23	628-09402 FIELD OFFICE, B	6.000	MOS
24	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
25	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
26	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
27	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	11,629.000	LFT
28	801-06209 TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN	11,629.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	48.000	EACH
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA	1,750.000	LFT
32	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	175.000	LFT
33	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
34	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	560.000	LFT
35	808-01296 PAVEMENT MESSAGE MARKING, THERMOPLASTIC (STOP AHEAD)	1.000	EACH
36	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	8,848.000	LFT
37	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	90,040.000	LFT
38	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	27,810.000	LFT
39	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	47.000	LFT
40	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	2.000	EACH
41	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	1.000	EACH
42	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	862.000	EACH
43	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	862.000	EACH
44	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	9.000	EACH



CALL ORDER : 411

CONTRACT ID : RS-31981-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-90277 DETECTOR HOUSING, REMOVE	1.000	EACH
10	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	50.000	TON
11	303-07449 COMPACTED AGGREGATE, NO. 73	1,100.000	TON
12	304-07491 HMA PATCHING, TYPE C	350.000	TON
13	306-08042 MILLING, SCARIFICATION/PROFILE	125,508.000	SYS
14	306-08043 MILLING, TRANSITION	1,080.000	SYS
15	306-08432 MILLING, APPROACH	7,467.000	SYS
16	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
17	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	10,443.000	TON
18	406-05520 ASPHALT FOR TACK COAT	36.900	TON
19	610-07488 HMA FOR APPROACHES, TYPE C	616.000	TON
20	628-09401 FIELD OFFICE, A	6.000	MOS
21	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
22	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
23	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	3,754.000	LFT
24	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,754.000	LFT
25	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	805-01836 SIGNAL CABLE DETECTOR, 2C 16GA., SHIELDED, LEAD IN	138.000	LFT
28	805-02441 SIGNAL CABLE, ROADWAY LOOP, 1C 14 GA.	1,375.000	LFT
29	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
30	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	440.000	LFT
31	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	4.000	EACH
32	808-04723 LINE THERMOPLASTIC FOR BUZZ STRIPS 4 IN	480.000	LFT
33	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	8,279.000	LFT
34	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	78,425.000	LFT
35	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	24,963.000	LFT
36	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	86.000	LFT
37	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	9.000	EACH
38	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	2.000	EACH
39	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	741.000	EACH
40	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	746.000	EACH

