

CALL ORDER : 390

CONTRACT ID : RS-30800-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08523 RADIO ONLY SERVICE	12.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
13	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
14	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
15	202-02676 TRANSPORTATION OF SALVAGEABLE MILLED MATERIAL	1,000.000	TON
16	202-90277 DETECTOR HOUSING, REMOVE	2.000	EACH
17	202-93741 GUARDRAIL END TREATMENT, REMOVE	28.000	EACH
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	6,243.000	SYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	100.000	TON
20	303-07449 COMPACTED AGGREGATE, NO. 73	6,223.000	TON
21	304-07490 HMA PATCHING, TYPE B	200.000	TON
22	304-07490 HMA PATCHING, TYPE B	600.000	TON
23	306-08036 MILLING, ASPHALT, 2 IN	141,353.000	SYS
24	306-08432 MILLING, APPROACH	13,589.000	SYS
25	306-08563 MILLING ASPHALT, 1 1/4 IN	30,530.000	SYS
26	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
27	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	2,519.000	TON
28	401-07345 QC/QA-HMA, 2, 70, SURFACE, 12.5 mm	15,207.000	TON
29	402-07433 HMA SURFACE, TYPE B	343.000	TON
30	404-05511 SEAL COAT, 2	20,241.000	SYS
31	406-05520 ASPHALT FOR TACK COAT	50.000	TON
32	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	3.000	EACH
33	601-09238 HAND DIG GUARDRAIL POST HOLES	114.000	EACH
34	601-62070 GUARDRAIL, STEEL BEAM, GALVANIZED	206.000	LFT
35	601-93346 GUARDRAIL CONNECTOR, AS	3.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	25.000	EACH
37	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	150.000	LFT
38	610-07487 HMA FOR APPROACHES, TYPE B	3,011.000	TON
39	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	5.000	EACH
40	615-06520 MONUMENT, RE-ESTABLISH	26.000	EACH
41	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	4.000	EACH
42	628-09402 FIELD OFFICE, B	6.000	MOS
43	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
44	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,265.000	LFT
45	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7,265.000	LFT
46	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	239.000	LFT
47	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	239.000	LFT
48	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
49	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 390

CONTRACT ID : RS-30800-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	801-92448 CONSTRUCTION SIGNS, MOBILE	1,080.000	DAY
51	805-02441 SIGNAL CABLE, ROADWAY LOOP, 1C 14 GA.	324.000	LFT
52	805-06616 PIEZO, CLASS II	2.000	EACH
53	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	272.000	LFT
54	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
55	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	94.000	LFT
56	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	13,810.000	LFT
57	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	119,375.000	LFT
58	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	13,438.000	LFT
59	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
60	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	239.000	LFT
61	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	903.000	EACH
62	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	903.000	EACH