

CALL ORDER : 160

CONTRACT ID : IR-31121-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION HMA			
1	203-02000 EXCAVATION, COMMON	366,368.000	CYS
2	203-02070 BORROW	413,862.000	CYS
3	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	16,316.000	TON
4	303-01180 COMPACTED AGGREGATE, NO. 53	35,887.000	TON
5	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
6	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	2,750.000	TON
7	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,184.000	TON
8	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	10,581.000	TON
9	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	4,212.000	TON
10	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	17,625.000	TON
11	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	8,217.000	TON
12	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	2,423.000	TON
13	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	3,422.000	TON
14	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	19,348.000	TON
15	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	49,481.000	TON
16	406-05520 ASPHALT FOR TACK COAT	190.000	TON
17	606-07484 MILLED HMA SHOULDER CORRUGATIONS	66,887.000	LFT
SECTION NO. 0002 NEW ROAD CONSTRUCTION PCCP			
18	203-02000 EXCAVATION, COMMON	369,705.000	CYS
19	203-02070 BORROW	394,197.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	10,097.000	TON
21	302-06464 SUBBASE FOR PCCP	36,993.000	CYS
22	303-01180 COMPACTED AGGREGATE, NO. 53	26,842.000	TON
23	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	4,052.000	TON
24	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	718.000	TON
25	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	9,615.000	TON
26	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,679.000	TON
27	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	10,529.000	TON
28	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	2,423.000	TON
29	406-05520 ASPHALT FOR TACK COAT	38.000	TON
30	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
31	501-06322 QC/QA-PCCP, 11 IN	111,292.000	SYS
32	501-06727 CORING, PCCP	LUMP	LUMP
33	501-09107 QC/QA-PCCP, 9 IN	17,778.000	SYS
34	503-05240 D-1 CONTRACTION JOINT	68,270.000	LFT
35	503-05310 TERMINAL JOINT	180.000	LFT
36	606-07484 MILLED HMA SHOULDER CORRUGATIONS	35,520.000	LFT
37	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	33,322.000	LFT
SECTION NO. 0003 NEW BRIDGE CONSTRUCTION			
38	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
39	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
40	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
41	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
42	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
43	202-74045 SIGN AND SUPPORTS, CHAN POSTS, REMOVE	9.000	EACH

CALL ORDER : 160

CONTRACT ID : IR-31121-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW BRIDGE CONSTRUCTION		
44	203-02000 EXCAVATION, COMMON	5,576.000	CYS
45	203-51223 EXCAVATION, WATERWAY	8,346.000	CYS
46	204-02290 SETTLEMENT PLATE	38.000	EACH
47	204-08415 STAKES, SETTLEMENT	76.000	EACH
48	205-03371 SEDIMENT, REMOVE	49,655.000	CYS
49	205-06930 SPLASHPAD, RIPRAP	88.000	TON
50	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	2,136.000	TON
51	205-06932 TEMPORARY CHECK DAM, STRAW BALES	96.000	LFT
52	205-06933 TEMPORARY DITCH INLET PROTECTION	28.000	EACH
53	205-06935 TEMPORARY SEDIMENT BASIN	30.000	EACH
54	205-06936 TEMPORARY SEDIMENT TRAP	45.000	TON
55	205-06937 TEMPORARY SILT FENCE	2,131.000	LFT
56	205-06938 TEMPORARY SLOPE DRAIN	1,702.000	LFT
57	205-09543 NO 2 STONE	100.000	TON
58	206-51220 EXCAVATION, WET	840.000	CYS
59	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	45.000	CYS
60	207-08263 SUBGRADE TREATMENT, TYPE IA	178,772.000	SYS
61	207-08265 SUBGRADE TREATMENT, TYPE IIA	8,701.000	SYS
62	207-08266 SUBGRADE TREATMENT, TYPE III	10,247.000	SYS
63	208-02046 GRADING IN GORE AREA	4.000	EACH
64	211-02050 B BORROW	21,649.000	CYS
65	211-06467 AGGREGATE FOR END BENT BACKFILL	263.100	CYS
66	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,569.000	CYS
67	211-09265 STRUCTURAL BACKFILL, TYPE 2	12,238.000	CYS
68	211-09265 STRUCTURAL BACKFILL, TYPE 2	840.000	CYS
69	211-09266 STRUCTURAL BACKFILL, TYPE 3	17,950.000	CYS
70	215-07043 CHEMICAL MODIFICATION, SOILS	5,000.000	SYS
71	302-07455 DENSE GRADED SUBBASE	414.000	CYS
72	303-07449 COMPACTED AGGREGATE, NO. 73	1,671.000	TON
73	306-08043 MILLING, TRANSITION	342.000	SYS
74	601-01522 GUARDRAIL TRANSITION TYPE TGB	26.000	EACH
75	601-01626 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 2	2.000	EACH
76	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT 3 IN SPACING	112.500	LFT
77	601-05586 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 9	1.000	EACH
78	601-05999 CURVED TERMINAL END	10.000	EACH
79	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
80	601-06854 GUARDRAIL, W-BEAM, NESTED	3.000	EACH
81	601-06855 GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	7.000	EACH
82	601-94689 GUARDRAIL END TREATMENT, OS	15.000	EACH
83	601-94690 GUARDRAIL END TREATMENT, MS	7.000	EACH
84	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	6,418.400	LFT
85	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	2,200.000	LFT
86	602-06729 BARRIER DELINEATOR	64.000	EACH
87	603-06040 FENCE, FARM FIELD, 47 IN	40,387.000	LFT
88	608-05741 WICK DRAIN	252,121.000	LFT
89	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	2,524.900	SYS
90	610-07486 HMA FOR APPROACHES, TYPE A	154.000	TON
91	610-07487 HMA FOR APPROACHES, TYPE B	15.000	TON
92	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH

CALL ORDER : 160

CONTRACT ID : IR-31121-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW BRIDGE CONSTRUCTION		
93	615-06490 RIGHT OF WAY MARKER	25.000	EACH
94	615-06505 MONUMENT, B	6.000	EACH
95	615-06510 MONUMENT, C	41.000	EACH
96	615-06515 MONUMENT, D	16.000	EACH
97	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
98	616-02320 GEOTEXTILES	15,740.000	SYS
99	616-05688 RIPRAP, CLASS 1	3,969.000	TON
100	616-05689 RIPRAP, CLASS 2	161.000	TON
101	616-06405 RIPRAP, REVETMENT	679.000	TON
102	616-06451 RIPRAP, UNIFORM	4,330.000	TON
103	616-07210 FIBER ROLL	4,385.000	LFT
104	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
105	621-02770 EROSION CONTROL BLANKET	14,562.000	SYS
106	621-04258 SEED MIXTURE	32.000	LBS
107	621-04258 SEED MIXTURE	19.000	LBS
108	621-06545 FERTILIZER	94.000	TON
109	621-06553 SEED MIXTURE, R	22,763.000	LBS
110	621-06557 SEED MIXTURE, T	15,060.000	LBS
111	621-06565 MULCHING MATERIAL	469.000	TON
112	621-06567 WATER	184.000	KGAL
113	621-06574 SODDING	50,780.000	SYS
114	621-06575 SODDING, NURSERY	335.000	SYS
115	622-52436 SIGN, DO NOT MOW OR SPRAY	12.000	EACH
116	622-91786 SEEDLING	240.000	EACH
117	622-98200 SIGN, DO NOT DISTURB	6.000	EACH
118	628-09403 FIELD OFFICE, C	24.000	MOS
119	701-06011 DYNAMIC PILE LOAD TEST	15.000	EACH
120	701-09557 TEST PILE, DYNAMIC, PRODUCTION	400.000	LFT
121	701-09557 TEST PILE, DYNAMIC, PRODUCTION	435.000	LFT
122	701-09557 TEST PILE, DYNAMIC, PRODUCTION	26.000	LFT
123	701-09559 TEST PILE, DYNAMIC, RESTRIKE	15.000	EACH
124	701-09683 PILE SHOE, HP 12 X 74	110.000	EACH
125	701-09891 PILE SHOE, HP 12 X 84	9.000	EACH
126	701-09892 PILE, STEEL H, HP 12 X 84	128.000	LFT
127	701-95780 PILE, STEEL H, HP 12 IN X 74	5,011.000	LFT
128	702-51005 CONCRETE, A, SUBSTRUCTURE	119.800	CYS
129	702-51015 CONCRETE, B, FOOTINGS	6.800	CYS
130	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	3,864.000	LBS
131	702-92857 CONCRETE, C, SUBSTRUCTURE	450.200	CYS
132	703-06028 REINFORCING BARS	12,717.000	LBS
133	703-06029 REINFORCING BARS, EPOXY COATED	614,018.000	LBS
134	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,596.600	CYS
135	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
136	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	24.000	EACH
137	706-51020 CONCRETE, C, RAILING	173.600	CYS
138	707-09634 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	910.000	LFT
139	707-09865 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	1,392.000	LFT
140	707-09921 STRUCTURAL MEMBERS, CONCRETE, BULB-T BEAM,	1,170.000	LFT
141	709-51821 SURFACE SEAL	LUMP	LUMP

CALL ORDER : 160

CONTRACT ID : IR-31121-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW BRIDGE CONSTRUCTION		
142	709-51821 SURFACE SEAL	LUMP	LUMP
143	709-51821 SURFACE SEAL	LUMP	LUMP
144	709-51821 SURFACE SEAL	LUMP	LUMP
145	709-51821 SURFACE SEAL	LUMP	LUMP
146	709-51821 SURFACE SEAL	LUMP	LUMP
147	709-51821 SURFACE SEAL	LUMP	LUMP
148	714-04854 STRUCTURE, PRECAST, RC, BOX SECTION 7FT X 3FT	428.000	LFT
149	714-06677 STRUCTURE, PRECAST, RC, BOX SECTION 18FT X 6FT	220.000	LFT
150	714-08514 WINGWALL	1,942.000	SFT
151	714-26724 STRUCTURE, PRECAST, RC, BOX SECTION 12FT X 4FT	378.000	LFT
152	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN	2.000	EACH
153	715-05032 PIPE, TYPE 2, CIRCULAR, 15 IN	804.000	LFT
154	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	86,598.000	LFT
155	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	10,176.000	LFT
156	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN	32.000	LFT
157	715-05122 PIPE, TYPE 1, CIRCULAR, 21 IN	140.000	LFT
158	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN	395.000	LFT
159	715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN	240.000	LFT
160	715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN	12.000	LFT
161	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	49.000	LFT
162	715-05218 PIPE, TYPE 5, CIRCULAR, 15 IN	2,057.000	LFT
163	715-05407 PIPE, END BENT DRAIN, 6 IN	660.000	LFT
164	715-09064 VIDEO INSPECTION FOR PIPE	3,717.000	LFT
165	715-46005 PIPE END SECTION, 15 IN	28.000	EACH
166	715-46015 PIPE END SECTION, 21 IN	4.000	EACH
167	715-46020 PIPE END SECTION, 24 IN	8.000	EACH
168	715-46030 PIPE END SECTION, 30 IN	6.000	EACH
169	718-06528 OUTLET PROTECTOR, 1	143.000	EACH
170	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	10,000.000	LFT
171	718-52610 AGGREGATE FOR UNDERDRAINS	11,749.000	CYS
172	718-99153 GEOTEXTILES FOR UNDERDRAIN	64,346.000	SYS
173	720-45070 INLET, P12A	28.000	EACH
174	722-95883 BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
175	722-95883 BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
176	722-95883 BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
177	723-06660 WINGWALL	508.000	SFT
178	723-09922 STRUCTURE, PRECAST THREE-SIDED,	288.000	LFT
179	731-93945 FACE PANELS, CONCRETE	18,964.000	SFT
180	731-93946 WALL ERECTION	18,964.000	SFT
181	731-93947 LEVELING PAD, CONCRETE	860.400	LFT
182	801-03290 CONSTRUCTION SIGN, C	20.000	EACH
183	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
184	801-06625 DETOUR ROUTE MARKER ASSEMBLY	26.000	EACH
185	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
186	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
187	801-07118 BARRICADE, III-A	224.000	LFT
188	801-07119 BARRICADE, III-B	56.000	LFT
189	801-08402 TEMPORARY TRAFFIC BARRIER, TYPE 3	456.000	LFT
190	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	503.300	LFT

CALL ORDER : 160

CONTRACT ID : IR-31121-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW BRIDGE CONSTRUCTION			
191	802-07057 SIGN, PANEL, WITH LEGEND	531.000	SFT
192	802-08456 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	4.000	EACH
193	802-09577 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E	2.000	EACH
194	802-09581 CANTILEVER SIGN SUPPORT FOUNDATION,	2.000	EACH
195	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	217.800	SFT
196	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN	14.000	SFT
197	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	60.100	SFT
198	802-76095 STRUCTURAL STEEL, BREAKAWAY	920.000	LBS
199	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,097.000	LFT
200	808-10033 LINE, MULTI-COMP, SOLID, WHITE, 4 IN	600.000	LFT
201	808-10034 LINE, MULTI-COMP, SOLID, YELLOW, 4 IN	600.000	LFT
202	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4,714.000	LFT
203	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	32.000	LFT
204	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	66.000	EACH
SECTION NO. 0004 NEW BRIDGE CONSTRUCTION			
205	109-08359 LIQUIDATED DAMAGES	1.000	DOL
206	109-08360 CONTRACT LIENS	1.000	DOL
207	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
208	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE CONCRETE	1.000	DOL
209	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
210	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
211	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL