

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-------------|-------|
| SECTION NO. 0001 | BRIDGE REPLACEMENT, CONCRETE | | |
| 1 | 109-08359 LIQUIDATED DAMAGES | 0.200 | DOL |
| 2 | 109-08360 CONTRACT LIENS | 0.200 | DOL |
| 3 | 109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE | 0.200 | DOL |
| 4 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 0.200 | DOL |
| 5 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 0.200 | DOL |
| 6 | 109-08463 PROJECT ESTIMATE ADJUSTMENT | 0.200 | DOL |
| 7 | 202-51330 PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 8 | 202-51330 PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 9 | 203-02000 EXCAVATION, COMMON | 3,403.000 | CYS |
| 10 | 211-06467 AGGREGATE FOR END BENT BACKFILL | 366.000 | CYS |
| 11 | 302-07455 DENSE GRADED SUBBASE | 251.000 | CYS |
| 12 | 503-05310 TERMINAL JOINT | 388.000 | LFT |
| 13 | 602-06729 BARRIER DELINEATOR | 44.000 | EACH |
| 14 | 609-06262 REINFORCED CONCRETE BRIDGE APPROACH, 14 IN. | 1,504.000 | SYS |
| 15 | 616-02320 GEOTEXTILES | 8,052.000 | SYS |
| 16 | 616-05688 RIPRAP, CLASS 1 | 4,048.000 | TON |
| 17 | 616-06405 RIPRAP, REVETMENT | 2,684.000 | TON |
| 18 | 701-05779 FURNISHING DRILLED SHAFT DRILLING EQUIPMENT | LUMP | LUMP |
| 19 | 701-05779 FURNISHING DRILLED SHAFT DRILLING EQUIPMENT | LUMP | LUMP |
| 20 | 701-05780 DRILLED SHAFT CONCRETE | 6,370.600 | CYS |
| 21 | 701-05781 UNCLASSIFIED SHAFT EXCAVATION | 1,688.000 | CYS |
| 22 | 701-05782 UNCLASSIFIED EXTRA DEPTH EXCAVATION | 100.000 | CYS |
| 23 | 701-05783 OBSTRUCTIONS | 60.000 | HRS |
| 24 | 701-05784 TRIAL SHAFT HOLES | 83.000 | LFT |
| 25 | 701-05785 EXPLORATION (SHAFT EXCAVATION) | 200.000 | LFT |
| 26 | 701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION | LUMP | LUMP |
| 27 | 701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION | LUMP | LUMP |
| 28 | 701-06011 DYNAMIC PILE LOAD TEST | 4.000 | EACH |
| 29 | 701-09557 TEST PILE, DYNAMIC, PRODUCTION | 274.000 | LFT |
| 30 | 701-09559 TEST PILE, DYNAMIC, RESTRIKE | 4.000 | EACH |
| 31 | 701-09770 PILE SHOE, HP 14 X 73 | 58.000 | EACH |
| 32 | 701-93575 PILE, STEEL H, HP 14" X 73 | 3,161.000 | LFT |
| 33 | 702-51005 CONCRETE, A, SUBSTRUCTURE | 1,264.500 | CYS |
| 34 | 702-51100 DRAIN PIPE, CAST IRON, 6 IN. | 2,428.000 | LBS |
| 35 | 702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON | 3,864.000 | LBS |
| 36 | 703-01540 THREADED TIE BAR ASSEMBLY | 2,106.000 | EACH |
| 37 | 703-06028 REINFORCING BARS | 487,966.000 | LBS |
| 38 | 703-06029 REINFORCING BARS, EPOXY COATED | 688,409.000 | LBS |
| 39 | 703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED | 2,724.000 | EACH |
| 40 | 704-08088 QC/QA-CONCRETE, SUPERSTRUCTURE, MODIFIED | 2,691.800 | CYS |
| 41 | 706-51020 CONCRETE, C, RAILING | 43.600 | CYS |
| 42 | 706-94947 RAILING, CONCRETE, C, MODIFIED | 171.700 | CYS |
| 43 | 707-09772 STRUCTURAL MEMBERS, CONCRETE BULB-T | 6,756.000 | LFT |
| 44 | 709-07733 ANTI-GRAFFITI COAT | LUMP | LUMP |
| 45 | 709-07733 ANTI-GRAFFITI COAT | LUMP | LUMP |
| 46 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 47 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 48 | 711-51070 ANCHOR PLATE, AP 1 | 76.000 | EACH |
| 49 | 715-05407 PIPE, END BENT DRAIN, 6 IN. | 470.000 | LFT |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-------------|-------|
| SECTION NO. 0001 | BRIDGE REPLACEMENT, CONCRETE | | |
| 50 728-98377 | MASONRY COATING | LUMP | LUMP |
| 51 728-98377 | MASONRY COATING | LUMP | LUMP |
| SECTION NO. 0002 | BRIDGE REPLACEMENT, STEEL | | |
| 52 109-08359 | LIQUIDATED DAMAGES | 0.200 | DOL |
| 53 109-08360 | CONTRACT LIENS | 0.200 | DOL |
| 54 109-08442 | QUALITY ADJUSTMENTS, SUPERSTRUCTURE | 0.200 | DOL |
| 55 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 0.200 | DOL |
| 56 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 0.200 | DOL |
| 57 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 0.200 | DOL |
| 58 202-51330 | PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 59 202-51330 | PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 60 203-02000 | EXCAVATION, COMMON | 3,198.000 | CYS |
| 61 211-06467 | AGGREGATE FOR END BENT BACKFILL | 274.000 | CYS |
| 62 302-07455 | DENSE GRADED SUBBASE | 251.000 | CYS |
| 63 503-05310 | TERMINAL JOINT | 388.000 | LFT |
| 64 602-06729 | BARRIER DELINEATOR | 44.000 | EACH |
| 65 609-06262 | REINFORCED CONCRETE BRIDGE APPROACH, 14 IN. | 1,504.000 | SYS |
| 66 616-02320 | GEOTEXTILES | 7,934.000 | SYS |
| 67 616-05688 | RIPRAP, CLASS 1 | 4,048.000 | TON |
| 68 616-06405 | RIPRAP, REVETMENT | 2,684.000 | TON |
| 69 619-09437 | PAINT STEEL BRIDGE, PARTIAL, TYPE 1 | 8,354.000 | SFT |
| 70 701-05779 | FURNISHING DRILLED SHAFT DRILLING EQUIPMENT | LUMP | LUMP |
| 71 701-05779 | FURNISHING DRILLED SHAFT DRILLING EQUIPMENT | LUMP | LUMP |
| 72 701-05780 | DRILLED SHAFT CONCRETE | 6,370.600 | CYS |
| 73 701-05781 | UNCLASSIFIED SHAFT EXCAVATION | 1,688.000 | CYS |
| 74 701-05782 | UNCLASSIFIED EXTRA DEPTH EXCAVATION | 100.000 | CYS |
| 75 701-05783 | OBSTRUCTIONS | 60.000 | HRS |
| 76 701-05784 | TRIAL SHAFT HOLES | 83.000 | LFT |
| 77 701-05785 | EXPLORATION (SHAFT EXCAVATION) | 200.000 | LFT |
| 78 701-05787 | INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION | LUMP | LUMP |
| 79 701-05787 | INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION | LUMP | LUMP |
| 80 701-06011 | DYNAMIC PILE LOAD TEST | 4.000 | EACH |
| 81 701-09557 | TEST PILE, DYNAMIC, PRODUCTION | 253.000 | LFT |
| 82 701-09559 | TEST PILE, DYNAMIC, RESTRIKE | 4.000 | EACH |
| 83 701-09770 | PILE SHOE, HP 14 X 73 | 60.000 | EACH |
| 84 701-93575 | PILE, STEEL H, HP 14" X 73 | 2,985.000 | LFT |
| 85 702-51005 | CONCRETE, A, SUBSTRUCTURE | 1,269.300 | CYS |
| 86 702-51100 | DRAIN PIPE, CAST IRON, 6 IN. | 2,428.000 | LBS |
| 87 702-51110 | GRATES, BASINS, AND FITTINGS, CAST IRON | 3,864.000 | LBS |
| 88 703-01540 | THREADED TIE BAR ASSEMBLY | 2,196.000 | EACH |
| 89 703-06028 | REINFORCING BARS | 481,945.000 | LBS |
| 90 703-06029 | REINFORCING BARS, EPOXY COATED | 774,571.000 | LBS |
| 91 703-97936 | THREADED TIE BAR ASSEMBLY, EPOXY COATED | 2,772.000 | EACH |
| 92 704-08088 | QC/QA-CONCRETE, SUPERSTRUCTURE, MODIFIED | 2,283.200 | CYS |
| 93 706-51020 | CONCRETE, C, RAILING | 42.800 | CYS |
| 94 706-94947 | RAILING, CONCRETE, C, MODIFIED | 171.700 | CYS |
| 95 709-07733 | ANTI-GRAFFITI COAT | LUMP | LUMP |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|--|--|-------------|-------|
| SECTION NO. 0002 BRIDGE REPLACEMENT, STEEL | | | |
| 96 | 709-07733 ANTI-GRAFFITI COAT | LUMP | LUMP |
| 97 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 98 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 99 | 711-51038 STRUCTURAL STEEL | LUMP | LUMP |
| 100 | 711-51038 STRUCTURAL STEEL | LUMP | LUMP |
| 101 | 715-05407 PIPE, END BENT DRAIN, 6 IN. | 471.000 | LFT |
| 102 | 728-98377 MASONRY COATING | LUMP | LUMP |
| 103 | 728-98377 MASONRY COATING | LUMP | LUMP |
| SECTION NO. 0003 ADDED TRAVEL LANES | | | |
| 104 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 105 | 105-08520 CELLULAR TELEPHONE/RADIO | 3.000 | EACH |
| 106 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 63.000 | MOS |
| 107 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 108 | 109-08359 LIQUIDATED DAMAGES | 0.800 | DOL |
| 109 | 109-08360 CONTRACT LIENS | 0.800 | DOL |
| 110 | 109-08440 QUALITY ADJUSTMENTS, HMA | 0.100 | DOL |
| 111 | 109-08441 QUALITY ADJUSTMENTS, PCCP | 0.500 | DOL |
| 112 | 109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE | 0.600 | DOL |
| 113 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 0.300 | DOL |
| 114 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 0.800 | DOL |
| 115 | 109-08463 PROJECT ESTIMATE ADJUSTMENT | 0.800 | DOL |
| 116 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 117 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 118 | 113-01614 PARTNERING OVERHEAD | LUMP | LUMP |
| 119 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 120 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 121 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 122 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 123 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 124 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 125 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 126 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 127 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 128 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 129 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 130 | 202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE | 1.000 | EACH |
| 131 | 202-02240 PAVEMENT REMOVAL | 128,504.100 | SYS |
| 132 | 202-02241 GUARDRAIL, REMOVE | 17,781.500 | LFT |
| 133 | 202-02278 CURB, CONCRETE, REMOVE | 950.000 | LFT |
| 134 | 202-02279 CURB AND GUTTER, REMOVE | 1,984.500 | LFT |
| 135 | 202-51330 PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 136 | 202-51330 PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 137 | 202-51330 PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 138 | 202-51330 PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 139 | 202-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE | 7.000 | EACH |
| 140 | 202-74050 SIGN, OVERHEAD, REMOVE | 11.000 | EACH |
| 141 | 202-74055 OVERHEAD SIGN STRUCTURE, BOX TRUSS, REMOVE | 9.000 | EACH |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-------------|-------|
| SECTION NO. 0003 | ADDED TRAVEL LANES | | |
| 142 | 202-74080 OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE | 5.000 | EACH |
| 143 | 202-82065 SIGN CIRCUITRY, BOX TRUSS, REMOVE | 1.000 | EACH |
| 144 | 202-91707 LIGHT FIXTURE AND CONDUIT, REMOVE | 8.000 | EACH |
| 145 | 202-91840 FENCE, CHAIN LINK, REMOVE | 657.000 | LFT |
| 146 | 202-93741 GUARD RAIL END TREATMENT, REMOVE | 22.000 | EACH |
| 147 | 202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE | 26.000 | EACH |
| 148 | 202-94954 BARRIER WALL, CONCRETE, REMOVE | 7,743.000 | LFT |
| 149 | 202-95027 IMPACT ATTENUATOR, REMOVE | 6.000 | EACH |
| 150 | 202-95579 SERVICE POINT, REMOVE | 1.000 | EACH |
| 151 | 202-96022 CONCRETE FOUNDATION, REMOVE | 7.000 | EACH |
| 152 | 202-96022 CONCRETE FOUNDATION, REMOVE | 1.000 | EACH |
| 153 | 202-96070 HIGH MAST TOWER, REMOVE | 9.000 | EACH |
| 154 | 203-02000 EXCAVATION, COMMON | 676,071.000 | CYS |
| 155 | 203-02046 GRADING IN GORE AREA | 6.000 | EACH |
| 156 | 203-02070 BORROW | 63,866.000 | CYS |
| 157 | 205-03371 SEDIMENT, REMOVE | 130.000 | CYS |
| 158 | 205-06930 SPLASHPAD, RIPRAP | 41.000 | TON |
| 159 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 1,938.000 | TON |
| 160 | 205-06932 TEMPORARY CHECK DAM, STRAW BALES | 13.000 | LFT |
| 161 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 30.000 | EACH |
| 162 | 205-06936 TEMPORARY SEDIMENT TRAP | 281.000 | TON |
| 163 | 205-06938 TEMPORARY SLOPE DRAIN | 851.000 | LFT |
| 164 | 205-09543 NO 2 STONE | 862.500 | TON |
| 165 | 206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED | 1,963.200 | CYS |
| 166 | 207-08262 SUBGRADE TREATMENT, TYPE I | 218,365.000 | SYS |
| 167 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 57,038.000 | SYS |
| 168 | 207-08268 SUBGRADE TREATMENT, TYPE IV | 11,774.000 | SYS |
| 169 | 210-06314 REMOVE AND REPLACE | 7.000 | EACH |
| 170 | 210-06685 LANDMARK PYLON TOWER | 7.000 | EACH |
| 171 | 210-06685 LANDMARK PYLON TOWER | 7.000 | EACH |
| 172 | 210-06685 LANDMARK PYLON TOWER | 7.000 | EACH |
| 173 | 210-06686 MEDIAN PYLON TOWER | 1.000 | EACH |
| 174 | 210-06686 MEDIAN PYLON TOWER | 1.000 | EACH |
| 175 | 210-07764 IRRIGATION SYSTEM | LUMP | LUMP |
| 176 | 211-02050 B BORROW | 57,651.000 | CYS |
| 177 | 211-06467 AGGREGATE FOR END BENT BACKFILL | 330.000 | CYS |
| 178 | 211-09264 STRUCTURE BACKFILL, TYPE 1 | 12,218.900 | CYS |
| 179 | 211-09266 STRUCTURE BACKFILL, TYPE 3 | 86,735.200 | CYS |
| 180 | 213-08068 DRILLED HOLE FOR FLOWABLE BACKFILL | 6.000 | EACH |
| 181 | 213-09269 FLOWABLE BACKFILL, NON-REMOVABLE | 578.000 | CYS |
| 182 | 302-06464 SUBBASE FOR PCCP | 19,928.100 | CYS |
| 183 | 302-06464 SUBBASE FOR PCCP | 30,573.000 | CYS |
| 184 | 302-07455 DENSE GRADED SUBBASE | 541.000 | CYS |
| 185 | 302-08562 COARSE AGGREGATE, 8 | 1,773.700 | TON |
| 186 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 13,165.000 | TON |
| 187 | 303-07449 COMPACTED AGGREGATE, NO. 73 | 812.000 | TON |
| 188 | 304-07491 HMA PATCHING, TYPE C | 2,500.000 | TON |
| 189 | 304-07494 WIDENING WITH HMA, TYPE C | 1,046.000 | TON |
| 190 | 306-08034 MILLING, ASPHALT, 1 1/2 IN. | 992.000 | SYS |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-------------|-------|
| SECTION NO. 0003 | ADDED TRAVEL LANES | | |
| 191 | 306-08432 MILLING, APPROACH | 143.000 | SYS |
| 192 | 401-06264 PROFILOGRAPH, HMA | LUMP | LUMP |
| 193 | 401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 250.000 | TON |
| 194 | 401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 1,601.000 | TON |
| 195 | 401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm | 3,084.000 | TON |
| 196 | 401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm | 1,664.800 | TON |
| 197 | 401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm | 4,934.000 | TON |
| 198 | 401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm | 6,540.600 | TON |
| 199 | 401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm | 3,911.000 | TON |
| 200 | 401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm | 4,082.000 | TON |
| 201 | 401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm | 2,500.000 | TON |
| 202 | 401-09530 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm--SMA | 987.400 | TON |
| 203 | 402-07434 HMA SURFACE, TYPE C | 94.000 | TON |
| 204 | 402-07453 HMA FOR TEMPORARY PAVEMENT | 39,602.000 | TON |
| 205 | 406-05520 ASPHALT FOR TACK COAT | 72.100 | TON |
| 206 | 501-06266 PROFILOGRAPH, PCCP | LUMP | LUMP |
| 207 | 501-06325 QC/QA-PCCP, 14 IN. | 116,819.000 | SYS |
| 208 | 501-06727 CORING, PCCP | LUMP | LUMP |
| 209 | 501-08196 QC/QA-PCCP, 12.5 IN. | 70,892.800 | SYS |
| 210 | 503-03489 RETROFITTED TIE BARS | 794.000 | EACH |
| 211 | 503-05240 D-1 CONTRACTION JOINT | 99,739.500 | LFT |
| 212 | 503-05310 TERMINAL JOINT | 775.600 | LFT |
| 213 | 601-06234 IMPACT ATTENUATOR, R1, W1, TL-2 | 6.000 | EACH |
| 214 | 601-06238 IMPACT ATTENUATOR, R1, W1, TL-3 | 13.000 | EACH |
| 215 | 601-06246 IMPACT ATTENUATOR, R2, W1, TL-3 | 4.000 | EACH |
| 216 | 601-06421 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R1, W1, TL-3 | 2.000 | EACH |
| 217 | 602-06729 BARRIER DELINEATOR | 847.000 | EACH |
| 218 | 602-06945 BARRIER, CONCRETE, 45 IN. | 646.000 | LFT |
| 219 | 602-08603 CONCRETE BARRIER, 45 IN. | 4,773.000 | LFT |
| 220 | 602-08603 CONCRETE BARRIER, 45 IN. | 1,497.000 | LFT |
| 221 | 602-09464 BARRIER, CONCRETE, 45 IN, SINGLE | 6,728.000 | LFT |
| 222 | 602-09465 BARRIER, CONCRETE, 45 IN, DOUBLE | 1,334.000 | LFT |
| 223 | 602-09466 BARRIER, CONCRETE, 54 IN., SINGLE | 143.000 | LFT |
| 224 | 602-94283 BARRIER, SINGLE FACE, CONCRETE | 2,168.000 | LFT |
| 225 | 602-98036 BARRIER MAT, WEED | 491.000 | SYS |
| 226 | 603-98225 FENCE, CHAIN LINK, BLACK VINYL COATED, 48 IN. | 12,477.000 | LFT |
| 227 | 604-07894 CURB RAMP, CONCRETE, A | 111.000 | SYS |
| 228 | 604-07901 CURB RAMP, CONCRETE, G | 66.000 | SYS |
| 229 | 604-07904 CURB RAMP, CONCRETE, L | 84.500 | SYS |
| 230 | 604-91531 SIDEWALK, CONCRETE, 4 IN. | 3,316.000 | SYS |
| 231 | 605-06121 CURB, CONCRETE, B | 239.000 | LFT |
| 232 | 605-06150 CURB AND GUTTER, C, CONCRETE | 9,670.000 | LFT |
| 233 | 607-92007 PAVED SIDE DITCH, L, MODIFIED | 545.000 | LFT |
| 234 | 609-06262 REINFORCED CONCRETE BRIDGE APPROACH, 14 IN. | 2,174.000 | SYS |
| 235 | 609-09231 REINFORCED CONCRETE BRIDGE APPROACH, | 1,472.000 | SYS |
| 236 | 610-08446 PCCP FOR APPROACHES, 6 IN. | 2,290.000 | SYS |
| 237 | 615-06505 MONUMENT, B | 18.000 | EACH |
| 238 | 615-06510 MONUMENT, C | 14.000 | EACH |
| 239 | 615-06515 MONUMENT, D | 54.000 | EACH |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0003 | ADDED TRAVEL LANES | | |
| 240 | 616-02320 GEOTEXTILES | 10,681.000 | SYS |
| 241 | 616-05688 RIPRAP, CLASS 1 | 144.000 | TON |
| 242 | 616-05689 RIPRAP, CLASS 2 | 10.000 | TON |
| 243 | 616-06405 RIPRAP, REVETMENT | 4,114.000 | TON |
| 244 | 616-51367 SLOPEWALL, CONCRETE, 4 IN. | 253.300 | SYS |
| 245 | 619-09437 PAINT STEEL BRIDGE, PARTIAL, TYPE 1 | 2,694.000 | SFT |
| 246 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 21.000 | EACH |
| 247 | 621-03787 SEED MIXTURE, D | 7.000 | LBS |
| 248 | 621-06545 FERTILIZER | 27.460 | TON |
| 249 | 621-06554 SEED MIXTURE, U | 9,341.200 | LBS |
| 250 | 621-06557 SEED MIXTURE, T | 964.000 | LBS |
| 251 | 621-06565 MULCHING MATERIAL | 124.130 | TON |
| 252 | 621-06567 WATER | 44.000 | KGAL |
| 253 | 621-06570 TOP SOIL | 2,831.020 | CYS |
| 254 | 621-06574 SODDING | 8,844.000 | SYS |
| 255 | 621-06575 SODDING, NURSERY | 5,277.000 | SYS |
| 256 | 621-07109 WATER PUMPING | LUMP | LUMP |
| 257 | 621-98038 MULCH, HARDWOOD SHREDDED BARK | 708.000 | CYS |
| 258 | 622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 72 TO | 15.000 | EACH |
| 259 | 622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN. | 858.000 | EACH |
| 260 | 622-05641 PLANT, DECIDUOUS SHRUB, OVER 36 TO 48 IN. | 364.000 | EACH |
| 261 | 622-05645 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 72 TO 96 IN. | 52.000 | EACH |
| 262 | 622-05647 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 120 IN. | 42.000 | EACH |
| 263 | 622-05647 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 120 IN. | 3.000 | EACH |
| 264 | 622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN. | 6.000 | EACH |
| 265 | 622-05654 PLANT, PERENNIAL | 10,978.000 | EACH |
| 266 | 622-05654 PLANT, PERENNIAL | 6,775.000 | EACH |
| 267 | 622-93712 PLANT, BULBS | 3,236.000 | EACH |
| 268 | 628-09403 FIELD OFFICE, C | 21.000 | MOS |
| 269 | 628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL | 21.000 | MOS |
| 270 | 701-02936 PILE, STEEL H, HP 14" X 89 | 1,370.000 | LFT |
| 271 | 701-06011 DYNAMIC PILE LOAD TEST | 19.000 | EACH |
| 272 | 701-08253 PILE SLEEVES | 50.000 | EACH |
| 273 | 701-08253 PILE SLEEVES | 71.000 | EACH |
| 274 | 701-08253 PILE SLEEVES | 22.000 | EACH |
| 275 | 701-09557 TEST PILE, DYNAMIC, PRODUCTION | 1,442.000 | LFT |
| 276 | 701-09559 TEST PILE, DYNAMIC, RESTRIKE | 19.000 | EACH |
| 277 | 701-09739 PILE SHOE, HP 12 X 53 | 66.000 | EACH |
| 278 | 701-09770 PILE SHOE, HP 14 X 73 | 239.000 | EACH |
| 279 | 701-51195 PILE, STEEL H, HP 12" X 53 | 3,301.000 | LFT |
| 280 | 701-90386 TEMPORARY SHEET PILING | LUMP | LUMP |
| 281 | 701-90386 TEMPORARY SHEET PILING | LUMP | LUMP |
| 282 | 701-93575 PILE, STEEL H, HP 14" X 73 | 11,482.000 | LFT |
| 283 | 701-93633 OVERSIZED PREDRILLED PILE HOLES | 280.000 | LFT |
| 284 | 702-01753 SOUND BARRIER PANELS, WALL MOUNTED | 24,060.400 | SFT |
| 285 | 702-01753 SOUND BARRIER PANELS, WALL MOUNTED | 6,450.000 | SFT |
| 286 | 702-01754 SOUND BARRIER PANELS, GROUND MOUNTED | 67,833.900 | SFT |
| 287 | 702-01754 SOUND BARRIER PANELS, GROUND MOUNTED | 61,742.000 | SFT |
| 288 | 702-01755 SOUND BARRIER ERECTION, WALL MOUNTED | 24,060.400 | SFT |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|-------------------------------------|---|---------------|-------|
| SECTION NO. 0003 ADDED TRAVEL LANES | | | |
| 289 | 702-01755 SOUND BARRIER ERECTION, WALL MOUNTED | 6,450.000 | SFT |
| 290 | 702-01756 SOUND BARRIER ERECTION, GROUND MOUNTED | 67,833.900 | SFT |
| 291 | 702-01756 SOUND BARRIER ERECTION, GROUND MOUNTED | 61,742.000 | SFT |
| 292 | 702-04118 SOUND BARRIER, DESIGN AND LAYOUT | LUMP | LUMP |
| 293 | 702-51005 CONCRETE, A, SUBSTRUCTURE | 1,553.300 | CYS |
| 294 | 702-51015 CONCRETE, B, FOOTINGS | 616.100 | CYS |
| 295 | 702-90915 CONCRETE, A | 14.000 | CYS |
| 296 | 702-90915 CONCRETE, A | 12.000 | CYS |
| 297 | 703-01540 THREADED TIE BAR ASSEMBLY | 112.000 | EACH |
| 298 | 703-06028 REINFORCING BARS | 360,234.000 | LBS |
| 299 | 703-06028 REINFORCING BARS | 1,580.000 | LBS |
| 300 | 703-06028 REINFORCING BARS | 1,379.000 | LBS |
| 301 | 703-06029 REINFORCING BARS, EPOXY COATED | 1,516,267.000 | LBS |
| 302 | 703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED | 411.000 | EACH |
| 303 | 704-08088 QC/QA-CONCRETE, SUPERSTRUCTURE, MODIFIED | 3,143.400 | CYS |
| 304 | 706-08497 REINFORCED CONCRETE MOMENT SLAB, 12 1/2 IN. | 6,410.300 | SYS |
| 305 | 706-08500 REINFORCED CONCRETE MOMENT SLAB, 14 IN. | 2,023.000 | SYS |
| 306 | 706-09789 REINFORCED CONCRETE MOMENT SLAB, 20 IN. | 37.000 | SYS |
| 307 | 706-51020 CONCRETE, C, RAILING | 608.700 | CYS |
| 308 | 706-51020 CONCRETE, C, RAILING | 23.400 | CYS |
| 309 | 706-94947 RAILING, CONCRETE, C, MODIFIED | 773.600 | CYS |
| 310 | 707-07605 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 54 IN. X 48 IN. | 438.000 | LFT |
| 311 | 707-09634 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, | 4,474.000 | LFT |
| 312 | 709-07733 ANTI-GRAFFITI COAT | LUMP | LUMP |
| 313 | 709-07733 ANTI-GRAFFITI COAT | LUMP | LUMP |
| 314 | 709-07733 ANTI-GRAFFITI COAT | LUMP | LUMP |
| 315 | 709-07733 ANTI-GRAFFITI COAT | LUMP | LUMP |
| 316 | 709-07733 ANTI-GRAFFITI COAT | LUMP | LUMP |
| 317 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 318 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 319 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 320 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 321 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 322 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 323 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 324 | 709-96826 CONCRETE SURFACE COATING | LUMP | LUMP |
| 325 | 709-96826 CONCRETE SURFACE COATING | LUMP | LUMP |
| 326 | 709-96826 CONCRETE SURFACE COATING | LUMP | LUMP |
| 327 | 709-96826 CONCRETE SURFACE COATING | LUMP | LUMP |
| 328 | 709-96826 CONCRETE SURFACE COATING | LUMP | LUMP |
| 329 | 710-02003 REPOINTING MASONRY IN STRUCTURES, MODIFIED | 140.000 | SFT |
| 330 | 710-02003 REPOINTING MASONRY IN STRUCTURES, MODIFIED | 130.000 | SFT |
| 331 | 711-51038 STRUCTURAL STEEL | LUMP | LUMP |
| 332 | 711-51038 STRUCTURAL STEEL | LUMP | LUMP |
| 333 | 711-51070 ANCHOR PLATE, AP 1 | 42.000 | EACH |
| 334 | 714-04875 CULVERT, PRECAST, REINFORCED CONCRETE BOX | 419.000 | LFT |
| 335 | 714-96642 TEMPORARY RETAINING WALL | LUMP | LUMP |
| 336 | 714-96642 TEMPORARY RETAINING WALL | LUMP | LUMP |
| 337 | 714-96642 TEMPORARY RETAINING WALL | LUMP | LUMP |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--------------------|---|----------------|
| SECTION NO. 0003 | ADDED TRAVEL LANES | | |
| 338 | 714-96642 | TEMPORARY RETAINING WALL | LUMP |
| 339 | 715-02048 | MISCELLANEOUS EQUIPMENT FOR WATER RELOCATION AND ADJUSTMENT | LUMP |
| 340 | 715-02246 | PIPE END SECTION, 48 IN. | 1.000 EACH |
| 341 | 715-03025 | SANITARY MANHOLE | 7.000 EACH |
| 342 | 715-04522 | PIPE END SECTION, 42 IN. | 1.000 EACH |
| 343 | 715-05019 | PIPE, TYPE 1, CIRCULAR, 36 IN. | 531.000 LFT |
| 344 | 715-05024 | PIPE, TYPE 2, CIRCULAR, 36 IN. | 167.000 LFT |
| 345 | 715-05048 | PIPE, TYPE 4, CIRCULAR, 6 IN. | 54,100.000 LFT |
| 346 | 715-05048 | PIPE, TYPE 4, CIRCULAR, 6 IN. | 15,300.000 LFT |
| 347 | 715-05053 | PIPE, UNDERDRAIN OUTLET, 6 IN. | 2,880.000 LFT |
| 348 | 715-05121 | PIPE, TYPE 1, CIRCULAR, 18 IN. | 176.000 LFT |
| 349 | 715-05123 | PIPE, TYPE 1, CIRCULAR, 24 IN. | 293.000 LFT |
| 350 | 715-05125 | PIPE, TYPE 1, CIRCULAR, 30 IN. | 208.000 LFT |
| 351 | 715-05149 | PIPE, TYPE 2, CIRCULAR, 12 IN. | 2,835.000 LFT |
| 352 | 715-05151 | PIPE, TYPE 2, CIRCULAR, 15 IN. | 4,922.000 LFT |
| 353 | 715-05152 | PIPE, TYPE 2, CIRCULAR, 18 IN. | 2,347.000 LFT |
| 354 | 715-05154 | PIPE, TYPE 2, CIRCULAR, 24 IN. | 1,282.000 LFT |
| 355 | 715-05156 | PIPE, TYPE 2, CIRCULAR, 30 IN. | 734.000 LFT |
| 356 | 715-05159 | PIPE, TYPE 2, CIRCULAR, 42 IN. | 393.000 LFT |
| 357 | 715-05411 | PIPE, SANITARY SEWER, 12 IN. | 1,226.000 LFT |
| 358 | 715-05422 | PIPE, SLOTTED DRAIN, 12 IN. | 5,980.000 LFT |
| 359 | 715-05423 | PIPE SLOTTED DRAIN, 15 IN. | 201.000 LFT |
| 360 | 715-05537 | PIPE | 300.000 LFT |
| 361 | 715-05757 | PIPE EXTENSION, CIRCULAR, 36 IN. | 14.000 LFT |
| 362 | 715-06337 | PIPE EXTENSION, CIRCULAR, 48 IN. | 12.000 LFT |
| 363 | 715-07587 | PIPE, TYPE 1, DEFORMED, 1.8 SQ. FT. | 80.000 LFT |
| 364 | 715-09064 | VIDEO INSPECTION FOR PIPE | 18,742.000 LFT |
| 365 | 715-46000 | PIPE END SECTION, 12 IN. | 12.000 EACH |
| 366 | 715-46005 | PIPE END SECTION, 15 IN. | 6.000 EACH |
| 367 | 715-46010 | PIPE END SECTION, 18 IN. | 12.000 EACH |
| 368 | 715-46020 | PIPE END SECTION, 24 IN. | 10.000 EACH |
| 369 | 715-46030 | PIPE END SECTION, 30 IN. | 7.000 EACH |
| 370 | 715-46040 | PIPE END SECTION, 36 IN. | 8.000 EACH |
| 371 | 715-46055 | PIPE END SECTION, MIN. AREA 1.8 SQ. FT. | 2.000 EACH |
| 372 | 718-06528 | OUTLET PROTECTOR, 1 | 45.000 EACH |
| 373 | 718-06529 | OUTLET PROTECTOR, 2 | 5.000 EACH |
| 374 | 718-06531 | OUTLET PROTECTOR, 3 | 6.000 EACH |
| 375 | 718-06532 | VIDEO INSPECTION FOR UNDERDRAINS | 9,500.000 LFT |
| 376 | 718-52610 | AGGREGATE FOR UNDERDRAINS | 6,465.100 CYS |
| 377 | 718-99153 | GEOTEXTILES FOR UNDERDRAIN | 50,739.000 SYS |
| 378 | 720-07302 | INLET TYPE HA, WITH SLOTTED DRAIN | 29.000 EACH |
| 379 | 720-08628 | SLOTTED DRAIN PIPE CLEANOUT PORT, TYPE II | 27.000 EACH |
| 380 | 720-08659 | MANHOLE, C5 | 7.000 EACH |
| 381 | 720-08659 | MANHOLE, C5 | 5.000 EACH |
| 382 | 720-08660 | MANHOLE, J5, MODIFIED | 1.000 EACH |
| 383 | 720-08660 | MANHOLE, J5, MODIFIED | 6.000 EACH |
| 384 | 720-09079 | INLET, HA5, MODIFIED | 6.000 EACH |
| 385 | 720-09079 | INLET, HA5, MODIFIED | 3.000 EACH |
| 386 | 720-44000 | CASTING, ADJUST TO GRADE | 19.000 EACH |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-------------|-------|
| SECTION NO. 0003 | ADDED TRAVEL LANES | | |
| 387 | 720-45030 INLET, E7 | 8.000 | EACH |
| 388 | 720-45035 INLET, F7 | 2.000 | EACH |
| 389 | 720-45041 INLET, H5 | 1.000 | EACH |
| 390 | 720-45041 INLET, H5 | 1.000 | EACH |
| 391 | 720-45042 INLET, HA5 | 10.000 | EACH |
| 392 | 720-45042 INLET, HA5 | 8.000 | EACH |
| 393 | 720-45065 INLET, N12 | 3.000 | EACH |
| 394 | 720-45141 INLET, H5, MODIFIED | 7.000 | EACH |
| 395 | 720-45141 INLET, H5, MODIFIED | 4.000 | EACH |
| 396 | 720-45410 MANHOLE, C4 | 27.000 | EACH |
| 397 | 720-45415 MANHOLE, D4 | 3.000 | EACH |
| 398 | 720-45416 MANHOLE, E4 | 2.000 | EACH |
| 399 | 720-45510 MANHOLE, C4, MODIFIED | 2.000 | EACH |
| 400 | 720-95409 MANHOLE, J4, MODIFIED | 4.000 | EACH |
| 401 | 720-95422 MANHOLE, J4 | 1.000 | EACH |
| 402 | 720-98174 INLET, B15 | 23.000 | EACH |
| 403 | 720-98555 INLET, C15 | 24.000 | EACH |
| 404 | 723-06660 WINGWALL | 40.200 | SYS |
| 405 | 724-51925 STRUCTURAL EXPANSION JOINT, SS | 140.000 | LFT |
| 406 | 724-51927 STRUCTURAL EXPANSION JOINT, M | 70.000 | LFT |
| 407 | 726-97941 BEARING ASSEMBLY, TFE ELASTOMERIC | 12.000 | EACH |
| 408 | 728-98377 MASONRY COATING | LUMP | LUMP |
| 409 | 728-98377 MASONRY COATING | LUMP | LUMP |
| 410 | 728-98377 MASONRY COATING | LUMP | LUMP |
| 411 | 728-98377 MASONRY COATING | LUMP | LUMP |
| 412 | 728-98377 MASONRY COATING | LUMP | LUMP |
| 413 | 728-98377 MASONRY COATING | LUMP | LUMP |
| 414 | 728-98377 MASONRY COATING | LUMP | LUMP |
| 415 | 731-93945 FACE PANELS, CONCRETE | 137,135.000 | SFT |
| 416 | 731-93946 WALL ERECTION | 137,135.000 | SFT |
| 417 | 731-93947 LEVELING PAD, CONCRETE | 7,727.200 | LFT |
| 418 | 732-07653 COARSE AGGREGATE, NO. 8 | 4,562.000 | TON |
| 419 | 801-03290 CONSTRUCTION SIGN, C | 31.000 | EACH |
| 420 | 801-03291 CONSTRUCTION SIGN, D | 4.000 | EACH |
| 421 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 9.000 | EACH |
| 422 | 801-06198 PATROLLER | 540.000 | DAY |
| 423 | 801-06202 TEMPORARY PANEL SIGN SUPPORTS | 54.000 | LFT |
| 424 | 801-06203 TEMPORARY PAVEMENT MARKING, 4 IN. | 93,916.000 | LFT |
| 425 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 546,149.000 | LFT |
| 426 | 801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN. | 903.000 | LFT |
| 427 | 801-06539 TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN | LUMP | LUMP |
| 428 | 801-06539 TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN | LUMP | LUMP |
| 429 | 801-06625 DETOUR ROUTE MARKER ASSEMBLY | 10.000 | EACH |
| 430 | 801-06640 CONSTRUCTION SIGN, A | 166.000 | EACH |
| 431 | 801-06645 CONSTRUCTION SIGN, B | 61.000 | EACH |
| 432 | 801-06710 FLASHING ARROW SIGN | 2,280.000 | DAY |
| 433 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 434 | 801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3 | 13.000 | EACH |
| 435 | 801-07118 BARRICADE, III-A | 444.000 | LFT |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|-------------------------------------|--|------------|-------|
| SECTION NO. 0003 ADDED TRAVEL LANES | | | |
| 436 | 801-07119 BARRICADE, III-B | 176.000 | LFT |
| 437 | 801-07606 TEMPORARY CROSSOVER DRAINAGE PIPE | 604.000 | LFT |
| 438 | 801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2 | 22,542.000 | LFT |
| 439 | 801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED | 7,844.000 | LFT |
| 440 | 801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN | 5.000 | EACH |
| 441 | 801-09282 TEMPORARY PANEL SIGNS | 152.000 | SFT |
| 442 | 801-52817 TEMPORARY CROSSOVER, B | 1.000 | EACH |
| 443 | 801-53072 TEMPORARY TRAFFIC SIGNAL | LUMP | LUMP |
| 444 | 801-53072 TEMPORARY TRAFFIC SIGNAL | LUMP | LUMP |
| 445 | 802-01749 SIGN BRACKET, WALL MOUNTED | 11.000 | EACH |
| 446 | 802-02158 SIGN, PANEL, REMOVE AND REINSTALL | 1.000 | EACH |
| 447 | 802-02475 SIGN, PANEL, REMOVE AND RELOCATE | 1.000 | EACH |
| 448 | 802-04893 REFERENCE POST | 18.000 | EACH |
| 449 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 73.000 | LFT |
| 450 | 802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE | 409.000 | LFT |
| 451 | 802-07057 SIGN, PANEL, WITH LEGEND | 8,648.000 | SFT |
| 452 | 802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE | 16.000 | EACH |
| 453 | 802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII | 15.000 | EACH |
| 454 | 802-08456 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII | 2.000 | EACH |
| 455 | 802-09536 SIGN BOX TRUSS STRUCTURE FOUNDATION AT 45 IN. | 4.000 | EACH |
| 456 | 802-09537 SIGN BOX TRUSS STRUCTURE FOUNDATION AT 36 IN. | 15.000 | EACH |
| 457 | 802-09577 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E | 1.000 | EACH |
| 458 | 802-09578 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F | 1.000 | EACH |
| 459 | 802-09580 CANTILEVER SIGN SUPPORT | 1.000 | EACH |
| 460 | 802-09581 CANTILEVER SIGN SUPPORT FOUNDATION, | 1.000 | EACH |
| 461 | 802-09711 BOX TRUSS SIGN STRUCTURE FOUNDATION, | 3.000 | EACH |
| 462 | 802-09712 OVERHEAD SIGN STRUCTURE, A | 4.000 | EACH |
| 463 | 802-09713 OVERHEAD SIGN STRUCTURE, B | 6.000 | EACH |
| 464 | 802-09714 OVERHEAD SIGN STRUCTURE, C | 2.000 | EACH |
| 465 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080 IN. | 319.000 | SFT |
| 466 | 802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN | 1,309.000 | SFT |
| 467 | 802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN | 39.000 | SFT |
| 468 | 802-76095 STRUCTURAL STEEL, BREAKAWAY | 5,029.000 | LBS |
| 469 | 802-76205 SIGN MODIFICATION (OVERHEAD) | 1.000 | EACH |
| 470 | 802-93388 BARRIER WALL SIGN BRACKET ASSEMBLY, MEDIAN | 1.000 | EACH |
| 471 | 802-93389 BARRIER WALL SIGN BRACKET, SHOULDER | 14.000 | EACH |
| 472 | 804-06725 DELINEATOR WITH POST, D1, 3 IN. DIA. | 12.000 | EACH |
| 473 | 804-06770 DELINEATOR POST | 45.000 | EACH |
| 474 | 805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT. | 4.000 | EACH |
| 475 | 805-01842 HANDHOLE, SIGNAL | 16.000 | EACH |
| 476 | 805-01885 MAST ARM, 30 FT. | 1.000 | EACH |
| 477 | 805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT | LUMP | LUMP |
| 478 | 805-02150 PEDESTRIAN SIGNAL HEAD, 18 IN. | 10.000 | EACH |
| 479 | 805-02262 FLASHER INSTALLATION | LUMP | LUMP |
| 480 | 805-04133 SIGNAL PEDESTAL, 12 FT. | 4.000 | EACH |
| 481 | 805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN. | 7,135.300 | LFT |
| 482 | 805-09344 WIRELESS | 1.000 | EACH |
| 483 | 805-09471 SIGNAL CABLE, PREFORMED PAVE-OVER LOOP | 44.000 | EACH |
| 484 | 805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, | 9.000 | EACH |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0003 | ADDED TRAVEL LANES | | |
| 485 | 805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE | 1.000 | EACH |
| 486 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN | 6.000 | EACH |
| 487 | 805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN | 4.000 | EACH |
| 488 | 805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN, | 1.000 | EACH |
| 489 | 805-78370 PEDESTRIAN PUSH BUTTON | 10.000 | EACH |
| 490 | 805-78415 SPAN, CATENARY, AND TETHER | 4.000 | EACH |
| 491 | 805-78420 DISCONNECT HANGER | 3.000 | EACH |
| 492 | 805-78445 SIGNAL SERVICE | 1.000 | EACH |
| 493 | 805-78467 SIGNAL CABLE, 3C 8GA. | 60.000 | LFT |
| 494 | 805-78480 SIGNAL CABLE, 3C 14GA. | 1,848.000 | LFT |
| 495 | 805-78485 SIGNAL CABLE, 5C 14GA. | 2,972.700 | LFT |
| 496 | 805-78490 SIGNAL CABLE, 7C 14GA. | 536.000 | LFT |
| 497 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 5,611.800 | LFT |
| 498 | 805-78900 PEDESTAL FOUNDATION, A | 4.000 | EACH |
| 499 | 805-78925 CONTROLLER CABINET FOUNDATION, P1 | 1.000 | EACH |
| 500 | 805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT. | 4.000 | EACH |
| 501 | 805-86890 POLE CIRCUIT CABLE, 1C NO. 10 THW OR TW STRANDED COPPER | 1,710.000 | LFT |
| 502 | 805-87780 CIRCUIT BREAKER | 8.000 | EACH |
| 503 | 805-90736 TELEPHONE MODEM | 1.000 | EACH |
| 504 | 805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL | 1.000 | EACH |
| 505 | 805-95209 TRUCK, TOW | 540.000 | DAY |
| 506 | 805-95663 ELECTRICAL WORK | LUMP | LUMP |
| 507 | 805-95663 ELECTRICAL WORK | LUMP | LUMP |
| 508 | 805-97237 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C | 4,728.000 | LFT |
| 509 | 807-01077 EXTERNAL WINCH PAD, CONCRETE | 6.000 | EACH |
| 510 | 807-02191 HANDHOLE, LIGHTING | 29.000 | EACH |
| 511 | 807-04654 LIGHT POLE | 15.000 | EACH |
| 512 | 807-04654 LIGHT POLE | 9.000 | EACH |
| 513 | 807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C | 10,155.000 | LFT |
| 514 | 807-08469 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, | 24.000 | EACH |
| 515 | 807-82053 UNDERPASS CIRCUIT INSTALLATION, 3 LUMINAIRES | 2.000 | EACH |
| 516 | 807-82400 LIGHT POLE, HIGH MAST, 125 FT. E.M.H. | 6.000 | EACH |
| 517 | 807-82990 TOWER LIGHTING WINCH DRIVE | 1.000 | EACH |
| 518 | 807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE | 48.000 | EACH |
| 519 | 807-86665 LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM | 36.000 | EACH |
| 520 | 807-86750 LUMINAIRE UNDERPASS, WALL MOUNTED, HIGH PRESSURE SODIUM, 150 | 6.000 | EACH |
| 521 | 807-86810 SERVICE POINT, II | 2.000 | EACH |
| 522 | 807-86832 CONCRETE FOUNDATION WITH GROUNDING, HIGH MAST TOWER | 6.000 | EACH |
| 523 | 807-86910 CONNECTOR KIT, UNFUSED | 30.000 | EACH |
| 524 | 807-86915 CONNECTOR KIT, FUSED | 30.000 | EACH |
| 525 | 807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED | 175.000 | EACH |
| 526 | 807-86935 INSULATION LINK, WATERPROOFED | 173.000 | EACH |
| 527 | 807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION | 36.000 | EACH |
| 528 | 808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN. | 2,310.000 | LFT |
| 529 | 808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN. | 55,003.000 | LFT |
| 530 | 808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN. | 47,305.000 | LFT |
| 531 | 808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN. | 12,384.000 | LFT |
| 532 | 808-05535 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, CROSSHATCH LINE, | 657.000 | LFT |
| 533 | 808-05866 PAVEMENT MESSAGE MARKING, REMOVE | 97.000 | SYS |

CALL ORDER : 141

CONTRACT ID : IR-31358-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-------------|-------|
| SECTION NO. 0003 | ADDED TRAVEL LANES | | |
| 534 | 808-06368 TRANSVERSE MARKING, REMOVE | 288.000 | LFT |
| 535 | 808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN. | 4,797.000 | LFT |
| 536 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 5,611.000 | LFT |
| 537 | 808-06716 LINE, REMOVE | 204,784.000 | LFT |
| 538 | 808-06848 LINE, EPOXY, DOTTED, WHITE, 4 IN, 24 IN LINE, 48 IN GAP | 705.000 | LFT |
| 539 | 808-09038 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, | 41.000 | LFT |
| 540 | 808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN. | 544.000 | LFT |
| 541 | 808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS | 33.000 | EACH |
| 542 | 808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY) | 17.000 | EACH |
| 543 | 808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN. | 22,007.000 | LFT |
| 544 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 4,750.000 | LFT |
| 545 | 808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 747.000 | EACH |
| 546 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 1,947.000 | EACH |
| 547 | 808-94455 TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 6 IN. | 866.000 | LFT |

CALL ORDER : 151

CONTRACT ID : IR-31944-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-------------|-------|
| SECTION NO. 0001 | HOUSE AND BUILDINGS, REMOVE | | |
| 1 109-08359 | LIQUIDATED DAMAGES | 1.000 | DOL |
| 2 109-08360 | CONTRACT LIENS | 1.000 | DOL |
| 3 110-01001 | MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 4 202-02240 | PAVEMENT REMOVAL | 7,136.000 | SYS |
| 5 202-02250 | TREE, 10 IN., REMOVE | 24.000 | EACH |
| 6 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 7 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 8 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 9 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 10 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 11 202-03135 | REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE | 130,764.000 | SFT |
| 12 202-52710 | SIDEWALK, CONCRETE, REMOVE | 686.000 | SYS |
| 13 202-74025 | FENCE, REMOVE | 221.000 | LFT |
| 14 202-93615 | CONCRETE, REMOVE | 504.000 | SYS |
| 15 205-06937 | TEMPORARY SILT FENCE | 644.000 | LFT |
| 16 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 1.000 | EACH |
| 17 621-01852 | MULCHED SEEDING, GRASS, 2 | 11,815.000 | SYS |

CALL ORDER : 161

CONTRACT ID : IR-32951-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | DEMOLITION | | |
| 1 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 2 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 3 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 4 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 5 | 202-03000 HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 6 | 202-03000 HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 7 | 202-03000 HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 8 | 202-03000 HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 9 | 202-03000 HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 10 | 202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE | 1,015.000 | SFT |
| 11 | 205-06937 TEMPORARY SILT FENCE | 1,250.000 | LFT |
| 12 | 621-06560 MULCHED SEEDING, U | 3,500.000 | SYS |
| 13 | 621-06570 TOP SOIL | 292.000 | CYS |

CALL ORDER : 171

CONTRACT ID : IR-32952-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS | | |
| 1 109-08359 | LIQUIDATED DAMAGES | 1.000 | DOL |
| 2 109-08360 | CONTRACT LIENS | 1.000 | DOL |
| 3 110-01001 | MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 4 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 5 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 6 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 7 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 8 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 9 202-03135 | REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE | 330.000 | SFT |
| 10 205-06937 | TEMPORARY SILT FENCE | 1,250.000 | LFT |
| 11 621-06560 | MULCHED SEEDING, U | 2,500.000 | SYS |
| 12 621-06570 | TOP SOIL | 210.000 | CYS |

CALL ORDER : 181

CONTRACT ID : IR-32984-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | DEMOLITION | | |
| 1 109-08359 | LIQUIDATED DAMAGES | 1.000 | DOL |
| 2 109-08360 | CONTRACT LIENS | 1.000 | DOL |
| 3 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 4 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 5 110-01001 | MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 6 201-01015 | CLEARING AND GRUBBING | LUMP | LUMP |
| 7 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 8 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 9 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 10 202-03000 | HOUSES AND BUILDINGS, REMOVE | LUMP | LUMP |
| 11 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 2.000 | EACH |
| 12 621-06560 | MULCHED SEEDING, U | 4,500.000 | SYS |
| 13 801-06775 | MAINTAINING TRAFFIC | LUMP | LUMP |

CALL ORDER : 191

CONTRACT ID : IR-33009-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|----------|-------|
| SECTION NO. 0001 | DEMOLITION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 5 | 201-09835 CLEARING RIGHT OF WAY | 22.600 | ACRE |
| 6 | 202-02245 TREE, 6 IN., REMOVE | 19.000 | EACH |
| 7 | 202-02250 TREE, 10 IN., REMOVE | 4.000 | EACH |
| 8 | 202-02255 TREE, 18 IN., REMOVE | 17.000 | EACH |
| 9 | 202-02260 TREE, 30 IN., REMOVE | 11.000 | EACH |
| 10 | 202-02265 TREE, 48 IN., REMOVE | 5.000 | EACH |
| 11 | 202-02270 TREE, 60 IN., REMOVE | 1.000 | EACH |
| 12 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 1.000 | EACH |
| 13 | 621-06545 FERTILIZER | 2.260 | TON |
| 14 | 621-06554 SEED MIXTURE, U | 847.000 | LBS |
| 15 | 621-06565 MULCHING MATERIAL | 11.000 | TON |

CALL ORDER : 241

CONTRACT ID : R -29436-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | ROAD RECONSTRUCTION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 5 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 6 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 7 | 109-08463 PROJECT ESTIMATE ADJUSTMENT | 1.000 | DOL |
| 8 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 9 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 10 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 11 | 202-01261 TESTING FOR ASBESTOS | 1.000 | EACH |
| 12 | 202-02241 GUARDRAIL, REMOVE | 25.000 | m |
| 13 | 202-02271 HEADWALL, REMOVE | 5.000 | EACH |
| 14 | 202-07553 REGULATED MATERIALS, REMOVE, TYPE Y | 100.000 | m3 |
| 15 | 202-07554 REGULATED MATERIALS, TRANSPORT, TYPE Y | 100.000 | m3 |
| 16 | 202-07555 REGULATED MATERIALS, DISPOSE, TYPE Y | 100.000 | m3 |
| 17 | 202-51330 PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 18 | 202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE | 13.000 | EACH |
| 19 | 202-91385 INLET, REMOVE | 5.000 | EACH |
| 20 | 202-96133 PIPE, REMOVE | 225.000 | m |
| 21 | 203-02000 EXCAVATION, COMMON | 2,560.000 | m3 |
| 22 | 203-02070 BORROW | 250.000 | m3 |
| 23 | 205-06930 SPLASHPAD, RIPRAP | 1.800 | Mg |
| 24 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 25.200 | Mg |
| 25 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 6.000 | EACH |
| 26 | 205-06937 TEMPORARY SILT FENCE | 314.000 | m |
| 27 | 205-06938 TEMPORARY SLOPE DRAIN | 13.000 | m |
| 28 | 206-51220 EXCAVATION, WET | 306.200 | m3 |
| 29 | 206-51225 EXCAVATION, DRY | 486.700 | m3 |
| 30 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 5,821.000 | m2 |
| 31 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 998.000 | m2 |
| 32 | 211-06467 AGGREGATE FOR END BENT BACKFILL | 351.600 | m3 |
| 33 | 211-09264 STRUCTURE BACKFILL, TYPE 1 | 2,798.000 | m3 |
| 34 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 103.600 | Mg |
| 35 | 306-08034 MILLING, ASPHALT, 38 mm | 295.000 | m2 |
| 36 | 306-08037 MILLING, ASPHALT, 75 mm | 5,176.000 | m2 |
| 37 | 401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm | 880.000 | Mg |
| 38 | 401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm | 2,294.000 | Mg |
| 39 | 401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm | 2,021.000 | Mg |
| 40 | 401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm | 1,003.000 | Mg |
| 41 | 406-05520 ASPHALT FOR TACK COAT | 12.700 | Mg |
| 42 | 601-01128 GUARDRAIL TRANSITION TYPE WGB | 1.000 | EACH |
| 43 | 601-01522 GUARDRAIL TRANSITION TYPE TGB | 1.000 | EACH |
| 44 | 601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1 | 1.000 | EACH |
| 45 | 601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 1.905 m SPACING | 19.100 | m |
| 46 | 601-05999 CURVED TERMINAL END | 3.000 | EACH |
| 47 | 601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING | 11.430 | m |
| 48 | 604-07894 CURB RAMP, CONCRETE, A | 69.000 | m2 |
| 49 | 604-07902 CURB RAMP, CONCRETE, H | 19.000 | m2 |

CALL ORDER : 241

CONTRACT ID : R -29436-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | ROAD RECONSTRUCTION | | |
| 50 | 604-91531 SIDEWALK, CONCRETE, 100 mm | 1,381.000 | m2 |
| 51 | 605-06120 CURB, CONCRETE | 55.000 | m |
| 52 | 605-06140 CURB AND GUTTER, CONCRETE | 899.000 | m |
| 53 | 605-06250 CENTER CURB, C, CONCRETE | 377.000 | m2 |
| 54 | 605-06255 CENTER CURB, D, CONCRETE | 36.000 | m2 |
| 55 | 605-92578 CURB WALK, CONCRETE | 42.000 | m2 |
| 56 | 605-92578 CURB WALK, CONCRETE | 86.300 | m2 |
| 57 | 609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm | 291.100 | m2 |
| 58 | 610-07487 HMA FOR APPROACHES, TYPE B | 568.000 | Mg |
| 59 | 610-08446 PCCP FOR APPROACHES, 150 mm | 31.000 | m2 |
| 60 | 610-09108 PCCP FOR APPROACHES, 225 mm | 671.000 | m2 |
| 61 | 611-06497 MAILBOX ASSEMBLY, SINGLE | 2.000 | EACH |
| 62 | 615-06490 RIGHT OF WAY MARKER | 30.000 | EACH |
| 63 | 615-06505 MONUMENT, B | 6.000 | EACH |
| 64 | 615-06527 MONUMENT, SECTION CORNER | 1.000 | EACH |
| 65 | 616-02320 GEOTEXTILES | 1,105.300 | m2 |
| 66 | 616-05688 RIPRAP, CLASS 1 | 577.700 | Mg |
| 67 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 2.000 | EACH |
| 68 | 621-06545 FERTILIZER | 0.200 | Mg |
| 69 | 621-06554 SEED MIXTURE, U | 14.600 | kg |
| 70 | 621-06557 SEED MIXTURE, T | 35.500 | kg |
| 71 | 621-06565 MULCHING MATERIAL | 2.200 | Mg |
| 72 | 621-06567 WATER | 55.000 | kL |
| 73 | 621-06575 SODDING, NURSERY | 3,055.000 | m2 |
| 74 | 628-09402 FIELD OFFICE, B | 12.000 | MOS |
| 75 | 628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL | 12.000 | MOS |
| 76 | 701-51195 PILE, STEEL H, HP 310mm X 79 | 276.800 | m |
| 77 | 702-51005 CONCRETE, A, SUBSTRUCTURE | 120.500 | m3 |
| 78 | 702-51015 CONCRETE, B, FOOTINGS | 51.000 | m3 |
| 79 | 703-51030 REINFORCING STEEL | 8,108.000 | kg |
| 80 | 703-51032 REINFORCING STEEL, EPOXY COATED | 31,189.000 | kg |
| 81 | 704-51002 CONCRETE, C, SUPERSTRUCTURE | 214.500 | m3 |
| 82 | 706-06349 RAILING, TX | 26.340 | m |
| 83 | 706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX | 4.000 | EACH |
| 84 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 85 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 86 | 715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm | 135.700 | m |
| 87 | 715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm | 1,071.100 | m |
| 88 | 715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm | 267.000 | m |
| 89 | 715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm | 112.700 | m |
| 90 | 715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm | 57.100 | m |
| 91 | 715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm | 222.400 | m |
| 92 | 715-05407 PIPE, END BENT DRAIN, 150 mm | 75.100 | m |
| 93 | 715-05408 PIPE, SANITARY SEWER, 200 mm | 30.000 | m |
| 94 | 715-05411 PIPE, SANITARY SEWER, 300 mm | 12.000 | m |
| 95 | 715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C | 194.000 | Mg |
| 96 | 715-46000 PIPE END SECTION, 300 mm | 1.000 | EACH |
| 97 | 715-46020 PIPE END SECTION, 600 mm | 1.000 | EACH |
| 98 | 718-52610 AGGREGATE FOR UNDERDRAINS | 243.000 | m3 |

CALL ORDER : 241

CONTRACT ID : R -29436-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | ROAD RECONSTRUCTION | | |
| 99 | 718-99153 GEOTEXTILES FOR UNDERDRAIN | 3,044.000 | m2 |
| 100 | 720-01092 MANHOLE, J15, MODIFIED | 1.000 | EACH |
| 101 | 720-44000 CASTING, ADJUST TO GRADE | 10.000 | EACH |
| 102 | 720-45030 INLET, E7 | 1.000 | EACH |
| 103 | 720-45250 CATCH BASIN, K10 | 1.000 | EACH |
| 104 | 720-45410 MANHOLE, C4 | 9.000 | EACH |
| 105 | 720-95422 MANHOLE, J4 | 4.000 | EACH |
| 106 | 720-98174 INLET, B15 | 4.000 | EACH |
| 107 | 720-98555 INLET, C15 | 3.000 | EACH |
| 108 | 720-99416 CATCH BASIN, B15 | 5.000 | EACH |
| 109 | 720-99417 CATCH BASIN, C15 | 6.000 | EACH |
| 110 | 721-09548 AUTOMATIC DRAINAGE GATE | 1.000 | EACH |
| 111 | 801-03290 CONSTRUCTION SIGN, C | 6.000 | EACH |
| 112 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 4.000 | EACH |
| 113 | 801-06203 TEMPORARY PAVEMENT MARKING, 100 mm | 2,712.000 | m |
| 114 | 801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm | 57.000 | m |
| 115 | 801-06640 CONSTRUCTION SIGN, A | 19.000 | EACH |
| 116 | 801-06645 CONSTRUCTION SIGN, B | 8.000 | EACH |
| 117 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 118 | 801-07119 BARRICADE, III-B | 64.800 | m |
| 119 | 801-94295 SIGNAL HEAD, RELOCATE | 5.000 | EACH |
| 120 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 37.200 | m |
| 121 | 802-09838 SIGN, SHEET, WITH LEGEND 2.03mm | 10.900 | m2 |
| 122 | 802-09840 SIGN, SHEET, WITH LEGEND 2.54mm | 1.400 | m2 |
| 123 | 805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m | 4.000 | EACH |
| 124 | 805-01842 HANDHOLE, SIGNAL | 4.000 | EACH |
| 125 | 805-01879 SIGNAL SERVICE, INSTALL | 1.000 | EACH |
| 126 | 805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 450mm | 8.000 | EACH |
| 127 | 805-06592 CONDUIT, STEEL, GALVANIZED, 50 mm | 303.000 | m |
| 128 | 805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE | 1.000 | EACH |
| 129 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN | 7.000 | EACH |
| 130 | 805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN, | 2.000 | EACH |
| 131 | 805-78370 PEDESTRIAN PUSH BUTTON | 8.000 | EACH |
| 132 | 805-78415 SPAN, CATENARY, AND TETHER | 4.000 | EACH |
| 133 | 805-78420 DISCONNECT HANGER | 4.000 | EACH |
| 134 | 805-78467 SIGNAL CABLE, 3C 8GA. | 20.000 | m |
| 135 | 805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA. | 2,142.000 | m |
| 136 | 805-78480 SIGNAL CABLE, 3C 14GA. | 252.000 | m |
| 137 | 805-78485 SIGNAL CABLE, 5C 14GA. | 357.000 | m |
| 138 | 805-78490 SIGNAL CABLE, 7C 14GA. | 219.000 | m |
| 139 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 1,178.000 | m |
| 140 | 805-78785 SIGNAL DETECTOR HOUSING | 16.000 | EACH |
| 141 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER | 694.000 | m |
| 142 | 805-78925 CONTROLLER CABINET FOUNDATION, P1 | 1.000 | EACH |
| 143 | 805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m | 4.000 | EACH |
| 144 | 805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL | 14.000 | EACH |
| 145 | 805-96014 SAW CUT, FULL DEPTH | 425.000 | m |
| 146 | 808-03002 LINE, EPOXY, BROKEN, WHITE, 100 mm | 13.000 | m |
| 147 | 808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm | 206.000 | m |

CALL ORDER : 241

CONTRACT ID : R -29436-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|----------|-------|
| SECTION NO. 0001 | ROAD RECONSTRUCTION | | |
| 148 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm | 598.000 | m |
| 149 | 808-06716 LINE, REMOVE | 551.000 | m |
| 150 | 808-07310 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW, | 13.000 | m |
| 151 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm | 252.000 | m |
| 152 | 808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW, | 39.000 | m |
| 153 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm | 56.000 | m |
| 154 | 808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm | 286.000 | m |
| 155 | 808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 15.000 | EACH |
| 156 | 808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 14.000 | EACH |
| 157 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 95.000 | EACH |
| 158 | 808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm | 143.000 | m |
| 159 | 808-95638 CENTER CURB PAINTING | 506.000 | m2 |
| 160 | 808-98000 LINE, EPOXY, SOLID, YELLOW, 200 mm | 52.000 | m |

CALL ORDER : 251

CONTRACT ID : R -29483-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | ROAD REHABILITATION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 15.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 5 | 108-09241 STORMWATER POLLUTION PREVENTION PLAN, | LUMP | LUMP |
| 6 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 7 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 8 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 9 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 10 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 11 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 12 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 13 | 201-01015 CLEARING AND GRUBBING | LUMP | LUMP |
| 14 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 15 | 202-02240 PAVEMENT REMOVAL | 772.000 | SYS |
| 16 | 202-02278 CURB, CONCRETE, REMOVE | 501.000 | LFT |
| 17 | 202-04089 SIGN, SHEET, REMOVE | 30.000 | EACH |
| 18 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 1,276.000 | SYS |
| 19 | 202-93047 MANHOLE, REMOVE | 1.000 | EACH |
| 20 | 203-02000 EXCAVATION, COMMON | 4,372.000 | CYS |
| 21 | 203-02070 BORROW | 1,138.000 | CYS |
| 22 | 205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET | 43.000 | EACH |
| 23 | 205-03371 SEDIMENT, REMOVE | 10.000 | CYS |
| 24 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 51.000 | EACH |
| 25 | 205-06937 TEMPORARY SILT FENCE | 1,250.000 | LFT |
| 26 | 207-08265 SUBGRADE TREATMENT, TYPE IIA | 12,277.000 | SYS |
| 27 | 211-02050 B BORROW | 600.000 | CYS |
| 28 | 211-09264 STRUCTURE BACKFILL, TYPE 1 | 1,582.000 | CYS |
| 29 | 211-09268 STRUCTURE BACKFILL, TYPE 5 | 11.000 | CYS |
| 30 | 213-09269 FLOWABLE BACKFILL, NON-REMOVABLE | 63.000 | CYS |
| 31 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 1,625.000 | TON |
| 32 | 303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS | 50.000 | TON |
| 33 | 304-07489 HMA PATCHING, TYPE A | 50.000 | TON |
| 34 | 304-07492 WIDENING WITH HMA, TYPE A | 2,358.000 | TON |
| 35 | 306-08033 MILLING, ASPHALT, 1 IN. | 1,150.000 | SYS |
| 36 | 306-08036 MILLING, ASPHALT, 2 IN. | 901.000 | SYS |
| 37 | 306-08038 MILLING, ASPHALT, 4 IN. | 2,919.000 | SYS |
| 38 | 306-08042 MILLING, SCARIFICATION/PROFILE | 5,734.000 | SYS |
| 39 | 306-08043 MILLING, TRANSITION | 213.000 | SYS |
| 40 | 401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm | 1,232.000 | TON |
| 41 | 401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm | 2,053.000 | TON |
| 42 | 402-07440 HMA BASE, TYPE A | 1,357.000 | TON |
| 43 | 402-07450 HMA WEDGE AND LEVEL, TYPE A | 349.000 | TON |
| 44 | 402-07453 HMA FOR TEMPORARY PAVEMENT | 107.000 | TON |
| 45 | 406-05521 ASPHALT FOR TACK COAT | 30,513.000 | SYS |
| 46 | 603-03398 FENCE, RELOCATE | 466.000 | LFT |
| 47 | 603-97461 TEMPORARY FENCE | 1,600.000 | LFT |
| 48 | 604-02007 SIDEWALK, CONCRETE, RECONSTRUCT | 43.000 | SYS |
| 49 | 604-06070 SIDEWALK, CONCRETE | 2,220.000 | SYS |

CALL ORDER : 251

CONTRACT ID : R -29483-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | ROAD REHABILITATION | | |
| 50 | 604-07897 CURB RAMP, CONCRETE, C | 13.600 | SYS |
| 51 | 604-07900 CURB RAMP, CONCRETE, F | 14.300 | SYS |
| 52 | 604-07901 CURB RAMP, CONCRETE, G | 76.500 | SYS |
| 53 | 605-06140 CURB AND GUTTER, CONCRETE | 8,887.000 | LFT |
| 54 | 610-07486 HMA FOR APPROACHES, TYPE A | 338.000 | TON |
| 55 | 610-08446 PCCP FOR APPROACHES, 6 IN. | 2,376.000 | SYS |
| 56 | 610-09108 PCCP FOR APPROACHES, 9 IN. | 1,211.000 | SYS |
| 57 | 611-02825 MAILBOX ASSEMBLY, TRIPLE | 2.000 | EACH |
| 58 | 611-06497 MAILBOX ASSEMBLY, SINGLE | 5.000 | EACH |
| 59 | 611-08232 MAILBOX ASSEMBLY, SINGLE, RESET | 27.000 | EACH |
| 60 | 611-08233 MAILBOX ASSEMBLY, DOUBLE, RESET | 4.000 | EACH |
| 61 | 614-92148 RAILROAD TRACK | 150.000 | LFT |
| 62 | 615-97768 PARKING BARRIER, RESET | 15.000 | EACH |
| 63 | 616-02320 GEOTEXTILES | 67.000 | SYS |
| 64 | 616-05689 RIPRAP, CLASS 2 | 4.000 | TON |
| 65 | 616-06405 RIPRAP, REVETMENT | 12.000 | TON |
| 66 | 616-06451 RIPRAP, UNIFORM | 16.000 | TON |
| 67 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 4.000 | EACH |
| 68 | 621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX | 8,000.000 | SYS |
| 69 | 621-02770 EROSION CONTROL BLANKET | 223.000 | SYS |
| 70 | 621-06560 MULCHED SEEDING, U | 7,167.000 | SYS |
| 71 | 621-06575 SODDING, NURSERY | 1,919.000 | SYS |
| 72 | 622-05625 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 48 TO | 13.000 | EACH |
| 73 | 622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN. | 3.000 | EACH |
| 74 | 622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN. | 3.000 | EACH |
| 75 | 628-09401 FIELD OFFICE, A | 15.000 | MOS |
| 76 | 715-02628 SAFETY METAL END SECTION, 6:1, 15 IN. | 1.000 | EACH |
| 77 | 715-02629 SAFETY METAL END SECTION, 6:1, 18 IN. | 1.000 | EACH |
| 78 | 715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN. | 132.000 | LFT |
| 79 | 715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN. | 12.000 | LFT |
| 80 | 715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN. | 733.000 | LFT |
| 81 | 715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN. | 340.000 | LFT |
| 82 | 715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN. | 2,244.000 | LFT |
| 83 | 715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN. | 1,051.000 | LFT |
| 84 | 715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN. | 543.000 | LFT |
| 85 | 715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN. | 361.000 | LFT |
| 86 | 715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN. | 185.000 | LFT |
| 87 | 715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN. | 338.000 | LFT |
| 88 | 715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN. | 48.000 | LFT |
| 89 | 715-05428 PIPE, SLOTTED VANE DRAIN, 12 IN. | 64.000 | LFT |
| 90 | 715-08282 HMA FOR STRUCTURE INSTALLATION, TYPE A | 184.000 | TON |
| 91 | 715-08627 PIPE, TYPE 2, CIRCULAR, 4 IN. | 200.000 | LFT |
| 92 | 715-09064 VIDEO INSPECTION FOR PIPE | 7,103.000 | LFT |
| 93 | 715-09455 PIPE, TYPE 2, CIRCULAR, 16 IN. | 1,508.000 | LFT |
| 94 | 715-46000 PIPE END SECTION, 12 IN. | 6.000 | EACH |
| 95 | 715-46005 PIPE END SECTION, 15 IN. | 8.000 | EACH |
| 96 | 715-46010 PIPE END SECTION, 18 IN. | 5.000 | EACH |
| 97 | 715-46020 PIPE END SECTION, 24 IN. | 1.000 | EACH |
| 98 | 715-93910 WATER SERVICE LINE, ADJUST | 60.000 | EACH |

CALL ORDER : 251

CONTRACT ID : R -29483-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | ROAD REHABILITATION | | |
| 99 | 720-44000 CASTING, ADJUST TO GRADE | 13.000 | EACH |
| 100 | 720-45030 INLET, E7 | 8.000 | EACH |
| 101 | 720-45035 INLET, F7 | 40.000 | EACH |
| 102 | 720-45040 INLET, G7 | 3.000 | EACH |
| 103 | 720-45045 INLET, J10 | 12.000 | EACH |
| 104 | 720-45055 INLET, M10 | 9.000 | EACH |
| 105 | 720-45130 INLET, E7, MODIFIED | 1.000 | EACH |
| 106 | 720-45145 INLET, J10, MODIFIED | 1.000 | EACH |
| 107 | 720-45155 INLET, M10, MODIFIED | 6.000 | EACH |
| 108 | 720-45410 MANHOLE, C4 | 6.000 | EACH |
| 109 | 720-45520 MANHOLE, E4, MODIFIED | 1.000 | EACH |
| 110 | 720-45605 STRUCTURE, MANHOLE, RECONSTRUCT | 3.000 | LFT |
| 111 | 720-92025 MANHOLE, D2 | 1.000 | EACH |
| 112 | 720-93409 INLET, B15, MODIFIED | 1.000 | EACH |
| 113 | 720-93411 INLET, C15, MODIFIED | 1.000 | EACH |
| 114 | 720-98174 INLET, B15 | 3.000 | EACH |
| 115 | 720-98555 INLET, C15 | 7.000 | EACH |
| 116 | 731-93946 WALL ERECTION | 45.000 | SFT |
| 117 | 801-03290 CONSTRUCTION SIGN, C | 4.000 | EACH |
| 118 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 5.000 | EACH |
| 119 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 19,800.000 | LFT |
| 120 | 801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN. | 110.000 | LFT |
| 121 | 801-06640 CONSTRUCTION SIGN, A | 29.000 | EACH |
| 122 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 123 | 801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2 | 2.000 | EACH |
| 124 | 801-07119 BARRICADE, III-B | 168.000 | LFT |
| 125 | 801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1 | 290.000 | LFT |
| 126 | 801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1 | 20.000 | LFT |
| 127 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 293.000 | LFT |
| 128 | 802-07060 SIGN, SHEET, RELOCATE | 23.000 | EACH |
| 129 | 802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN. | 197.000 | SFT |
| 130 | 802-76055 SIGN POST, A | 318.000 | LFT |
| 131 | 802-90623 SIGN BRACKET FOR STREET NAME | 11.000 | EACH |
| 132 | 802-90623 SIGN BRACKET FOR STREET NAME | 3.000 | EACH |
| 133 | 802-97812 STREET NAME IDENTIFICATION SIGN | 14.000 | EACH |
| 134 | 807-03594 RELOCATE EXISTING LIGHT | 2.000 | EACH |
| 135 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 279.000 | LFT |
| 136 | 808-06713 LINE, PAINT, SOLID, WHITE, 4 IN. | 273.000 | LFT |
| 137 | 808-07845 TRANSVERSE MARKINGS | 16.000 | EACH |
| 138 | 808-74815 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 12 IN. | 566.000 | LFT |
| 139 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 9,500.000 | LFT |
| 140 | 808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW, | 19.000 | LFT |
| 141 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 183.000 | LFT |
| 142 | 808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 4.000 | EACH |
| 143 | 808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 2.000 | EACH |
| 144 | 808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN. | 201.000 | LFT |

CALL ORDER : 271

CONTRACT ID : R -29579-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | BIKE/PEDESTRIAN FACILITY | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 5 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.500 | DOL |
| 6 | 109-08463 PROJECT ESTIMATE ADJUSTMENT | 1.000 | DOL |
| 7 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 8 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 9 | 201-06587 CLEARING AND GRUBBING | 3.480 | ACRE |
| 10 | 202-02240 PAVEMENT REMOVAL | 112.700 | SYS |
| 11 | 202-02241 GUARDRAIL, REMOVE | 807.000 | LFT |
| 12 | 202-02250 TREE, 10 IN., REMOVE | 11.000 | EACH |
| 13 | 202-02255 TREE, 18 IN., REMOVE | 2.000 | EACH |
| 14 | 202-02274 CURB, CONCRETE, INTEGRAL, REMOVE | 126.000 | LFT |
| 15 | 202-02278 CURB, CONCRETE, REMOVE | 62.000 | LFT |
| 16 | 202-04089 SIGN, SHEET, REMOVE | 1.000 | EACH |
| 17 | 202-06541 REMOVE | 2.000 | EACH |
| 18 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 26.300 | SYS |
| 19 | 202-91385 INLET, REMOVE | 3.000 | EACH |
| 20 | 202-91840 FENCE, CHAIN LINK, REMOVE | 100.000 | LFT |
| 21 | 202-91922 STUMP, REMOVE | 1.000 | EACH |
| 22 | 202-93898 TREE, 12 IN., REMOVE | 2.000 | EACH |
| 23 | 202-96133 PIPE, REMOVE | 204.000 | LFT |
| 24 | 202-96430 FENCE AND POSTS, REMOVE | LUMP | LUMP |
| 25 | 202-97188 ISLAND, CONCRETE, REMOVE | 8.000 | SYS |
| 26 | 202-99187 FENCE, FARM FIELD, REMOVE | 194.000 | LFT |
| 27 | 203-02000 EXCAVATION, COMMON | 12,361.000 | CYS |
| 28 | 203-02070 BORROW | 488.000 | CYS |
| 29 | 205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET | 2.000 | EACH |
| 30 | 205-02770 EROSION CONTROL BLANKET | 231.000 | SYS |
| 31 | 205-04948 TEMPORARY CONSTRUCTION ENTRANCE/EXIT | LUMP | LUMP |
| 32 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 49.500 | TON |
| 33 | 205-06937 TEMPORARY SILT FENCE | 3,383.000 | LFT |
| 34 | 210-07907 LANDSCAPE | 10.000 | EACH |
| 35 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 2,466.000 | TON |
| 36 | 302-08562 COARSE AGGREGATE, 8 | 116.100 | TON |
| 37 | 303-07662 STONE | 87.000 | TON |
| 38 | 402-07432 HMA SURFACE, TYPE A | 1,354.000 | TON |
| 39 | 603-06045 FENCE, CHAIN LINK, 48 IN. | 100.000 | LFT |
| 40 | 604-07894 CURB RAMP, CONCRETE, A | 26.000 | SYS |
| 41 | 604-07898 CURB RAMP, CONCRETE, D | 2.700 | SYS |
| 42 | 604-07901 CURB RAMP, CONCRETE, G | 29.400 | SYS |
| 43 | 604-07902 CURB RAMP, CONCRETE, H | 81.900 | SYS |
| 44 | 604-91531 SIDEWALK, CONCRETE, 4 IN. | 784.500 | SYS |
| 45 | 605-06100 CURB, INTEGRAL, C, CONCRETE | 427.000 | LFT |
| 46 | 610-07486 HMA FOR APPROACHES, TYPE A | 30.000 | TON |
| 47 | 611-08232 MAILBOX ASSEMBLY, SINGLE, RESET | 1.000 | EACH |
| 48 | 616-02320 GEOTEXTILES | 255.000 | SYS |
| 49 | 616-06451 RIPRAP, UNIFORM | 56.000 | TON |

CALL ORDER : 271

CONTRACT ID : R -29579-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | BIKE/PEDESTRIAN FACILITY | | |
| 50 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 1.000 | EACH |
| 51 | 621-02770 EROSION CONTROL BLANKET | 10,582.000 | SYS |
| 52 | 621-06545 FERTILIZER | 0.980 | TON |
| 53 | 621-06553 SEED MIXTURE, R | 204.000 | LBS |
| 54 | 621-06557 SEED MIXTURE, T | 193.000 | LBS |
| 55 | 621-06559 MULCHED SEEDING, R | 16,894.000 | SYS |
| 56 | 622-05640 PLANT, DECIDUOUS SHRUB, OVER 24 TO 36 IN. | 3.000 | EACH |
| 57 | 622-05641 PLANT, DECIDUOUS SHRUB, OVER 36 TO 48 IN. | 6.000 | EACH |
| 58 | 622-05644 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 48 TO 72 IN. | 2.000 | EACH |
| 59 | 622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN. | 2.000 | EACH |
| 60 | 628-09401 FIELD OFFICE, A | 10.000 | MOS |
| 61 | 628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL | 10.000 | MOS |
| 62 | 714-93978 CULVERT, PRECAST, REINFORCED CONCRETE BOX, 4' X 2' | 15.000 | LFT |
| 63 | 715-01663 PIPE CLEANING, ABOVE 48 IN. DIA. | 10.000 | LFT |
| 64 | 715-05116 PIPE, TYPE 1, CIRCULAR, 8 IN. | 8.000 | LFT |
| 65 | 715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN. | 54.000 | LFT |
| 66 | 715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN. | 132.000 | LFT |
| 67 | 715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN. | 36.000 | LFT |
| 68 | 715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN. | 298.000 | LFT |
| 69 | 715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN. | 250.000 | LFT |
| 70 | 715-05165 PIPE, TYPE 2, CIRCULAR, 72 IN. | 121.000 | LFT |
| 71 | 715-05203 PIPE, TYPE 4, CIRCULAR, 4 IN. | 160.000 | LFT |
| 72 | 715-05595 PIPE EXTENSION, CIRCULAR, 15 IN. | 8.000 | LFT |
| 73 | 715-46000 PIPE END SECTION, 12 IN. | 2.000 | EACH |
| 74 | 715-46010 PIPE END SECTION, 18 IN. | 2.000 | EACH |
| 75 | 715-46020 PIPE END SECTION, 24 IN. | 4.000 | EACH |
| 76 | 715-90836 PIPE END SECTION, 8 IN. | 2.000 | EACH |
| 77 | 720-44000 CASTING, ADJUST TO GRADE | 13.000 | EACH |
| 78 | 720-45035 INLET, F7 | 6.000 | EACH |
| 79 | 720-45045 INLET, J10 | 1.000 | EACH |
| 80 | 720-90984 MANHOLE, C2 | 1.000 | EACH |
| 81 | 732-08419 MODULAR BLOCK WALL | 81.000 | SYS |
| 82 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 83 | 802-07060 SIGN, SHEET, RELOCATE | 7.000 | EACH |
| 84 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080 IN. | 128.110 | SFT |
| 85 | 802-96248 POST, WOOD, 4 IN. X 4 IN. | 370.000 | LFT |
| 86 | 802-96248 POST, WOOD, 4 IN. X 4 IN. | 90.000 | LFT |
| 87 | 808-06609 PAVEMENT MESSAGE MARKING | 14.000 | EACH |
| 88 | 808-06609 PAVEMENT MESSAGE MARKING | 14.000 | EACH |
| 89 | 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN. | 948.000 | LFT |
| 90 | 808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN. | 850.000 | LFT |

CALL ORDER : 281

CONTRACT ID : R -29711-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | PAVEMENT REPLACEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 2.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 48.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 5 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 6 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 7 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 8 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 9 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 10 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 11 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 12 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 13 | 203-02020 EXCAVATION, UNCLASSIFIED | 3,309.000 | CYS |
| 14 | 203-02070 BORROW | 564.000 | CYS |
| 15 | 205-03371 SEDIMENT, REMOVE | 200.000 | CYS |
| 16 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 1,604.000 | TON |
| 17 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 13.000 | EACH |
| 18 | 205-06934 TEMPORARY MULCHING | 1.000 | TON |
| 19 | 205-06937 TEMPORARY SILT FENCE | 18,738.000 | LFT |
| 20 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 67,482.000 | SYS |
| 21 | 211-09264 STRUCTURE BACKFILL, TYPE 1 | 939.000 | CYS |
| 22 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 20,050.000 | TON |
| 23 | 401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm | 3,478.000 | TON |
| 24 | 401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm | 5,962.000 | TON |
| 25 | 406-05520 ASPHALT FOR TACK COAT | 12.000 | TON |
| 26 | 610-07487 HMA FOR APPROACHES, TYPE B | 1,343.000 | TON |
| 27 | 611-06497 MAILBOX ASSEMBLY, SINGLE | 8.000 | EACH |
| 28 | 611-06498 MAILBOX ASSEMBLY, DOUBLE | 2.000 | EACH |
| 29 | 616-02320 GEOTEXTILES | 14,974.000 | SYS |
| 30 | 616-06405 RIPRAP, REVETMENT | 157.000 | TON |
| 31 | 616-06451 RIPRAP, UNIFORM | 5,673.000 | TON |
| 32 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 10.000 | EACH |
| 33 | 621-01956 SEED MIXTURE, LEGUME, 1 | 713.000 | LBS |
| 34 | 621-02770 EROSION CONTROL BLANKET | 18,149.000 | SYS |
| 35 | 621-06545 FERTILIZER | 2.000 | TON |
| 36 | 621-06557 SEED MIXTURE, T | 100.000 | LBS |
| 37 | 621-06567 WATER | 5.000 | KGAL |
| 38 | 621-06575 SODDING, NURSERY | 1,271.000 | SYS |
| 39 | 621-52448 SIGN, DO NOT SPRAY | 8.000 | EACH |
| 40 | 622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 72 TO | 20.000 | EACH |
| 41 | 622-52436 SIGN, DO NOT MOW OR SPRAY | 25.000 | EACH |
| 42 | 622-91786 SEEDLING | 191.000 | EACH |
| 43 | 622-91786 SEEDLING | 200.000 | EACH |
| 44 | 628-09402 FIELD OFFICE, B | 24.000 | MOS |
| 45 | 628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL | 24.000 | MOS |
| 46 | 715-02407 SAFETY METAL END SECTION, 4:1, 48 IN. | 2.000 | EACH |
| 47 | 715-03475 SAFETY METAL END SECTION, 4:1, 15 IN. | 4.000 | EACH |
| 48 | 715-03476 SAFETY METAL END SECTION, 4:1, 24 IN. | 1.000 | EACH |
| 49 | 715-03584 SAFETY METAL END SECTION, 4:1, 18 IN. | 3.000 | EACH |

CALL ORDER : 281

CONTRACT ID : R -29711-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | PAVEMENT REPLACEMENT | | |
| 50 | 715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN. | 48.000 | LFT |
| 51 | 715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN. | 602.000 | LFT |
| 52 | 715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN. | 136.000 | LFT |
| 53 | 715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN. | 175.000 | LFT |
| 54 | 715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN. | 101.000 | LFT |
| 55 | 715-05127 PIPE, TYPE 1, CURCULAR, 42 IN. | 44.000 | LFT |
| 56 | 715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN. | 78.000 | LFT |
| 57 | 715-05136 PIPE, TYPE 1, CIRCULAR, 72 IN. | 32.000 | LFT |
| 58 | 715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN. | 427.000 | LFT |
| 59 | 715-05842 CONCRETE ANCHOR, 42 IN. | 2.000 | EACH |
| 60 | 715-06004 CONCRETE ANCHOR, 48 IN. | 2.000 | EACH |
| 61 | 715-06357 CONCRETE ANCHOR, 72 IN. | 2.000 | EACH |
| 62 | 715-09064 VIDEO INSPECTION FOR PIPE | 1,000.000 | LFT |
| 63 | 715-46005 PIPE END SECTION, 15 IN. | 49.000 | EACH |
| 64 | 715-46010 PIPE END SECTION, 18 IN. | 5.000 | EACH |
| 65 | 715-46020 PIPE END SECTION, 24 IN. | 9.000 | EACH |
| 66 | 715-46030 PIPE END SECTION, 30 IN. | 4.000 | EACH |
| 67 | 715-46040 PIPE END SECTION, 36 IN. | 4.000 | EACH |
| 68 | 720-45030 INLET, E7 | 4.000 | EACH |
| 69 | 720-45035 INLET, F7 | 1.000 | EACH |
| 70 | 801-03290 CONSTRUCTION SIGN, C | 2.000 | EACH |
| 71 | 801-06640 CONSTRUCTION SIGN, A | 31.000 | EACH |
| 72 | 801-06645 CONSTRUCTION SIGN, B | 15.000 | EACH |
| 73 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 74 | 801-07119 BARRICADE, III-B | 144.000 | LFT |
| 75 | 801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN | 3.000 | EACH |
| 76 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 210.000 | LFT |
| 77 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080 IN. | 61.000 | SFT |
| 78 | 802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN | 90.000 | SFT |
| 79 | 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN. | 9,817.000 | LFT |

CALL ORDER : 311

CONTRACT ID : R -30703-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | INTERSECTION IMPROVEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 10.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 5 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 6 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 10 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 11 | 201-01015 CLEARING AND GRUBBING | LUMP | LUMP |
| 12 | 202-02271 HEADWALL, REMOVE | 1.000 | EACH |
| 13 | 202-02278 CURB, CONCRETE, REMOVE | 65.000 | LFT |
| 14 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 102.000 | SYS |
| 15 | 202-90747 RETAINING WALL, REMOVE | 16.000 | LFT |
| 16 | 202-91385 INLET, REMOVE | 1.000 | EACH |
| 17 | 203-02000 EXCAVATION, COMMON | 1,205.000 | CYS |
| 18 | 205-03371 SEDIMENT, REMOVE | 3.000 | CYS |
| 19 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 5.000 | EACH |
| 20 | 205-06937 TEMPORARY SILT FENCE | 600.000 | LFT |
| 21 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 1,360.000 | SYS |
| 22 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 753.000 | SYS |
| 23 | 211-09264 STRUCTURE BACKFILL, TYPE 1 | 104.000 | CYS |
| 24 | 211-09265 STRUCTURE BACKFILL, TYPE 2 | 246.000 | CYS |
| 25 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 683.000 | TON |
| 26 | 306-08034 MILLING, ASPHALT, 1 1/2 IN. | 2,140.000 | SYS |
| 27 | 306-08043 MILLING, TRANSITION | 51.000 | SYS |
| 28 | 402-07433 HMA SURFACE, TYPE B | 277.000 | TON |
| 29 | 402-07438 HMA INTERMEDIATE, TYPE B | 55.000 | TON |
| 30 | 402-07441 HMA BASE, TYPE B | 336.000 | TON |
| 31 | 402-07451 HMA WEDGE AND LEVEL, TYPE B | 2.000 | TON |
| 32 | 402-07453 HMA FOR TEMPORARY PAVEMENT | 55.000 | TON |
| 33 | 406-05520 ASPHALT FOR TACK COAT | 1.000 | TON |
| 34 | 601-95344 HANDRAIL, PEDESTRIAN | 40.000 | LFT |
| 35 | 604-06070 SIDEWALK, CONCRETE | 678.000 | SYS |
| 36 | 604-07900 CURB RAMP, CONCRETE, F | 35.000 | SYS |
| 37 | 604-07903 CURB RAMP, CONCRETE, K | 11.500 | SYS |
| 38 | 604-44251 STEPS, CONCRETE | 0.250 | CYS |
| 39 | 605-02493 CURB ISLAND, CONCRETE | 20.600 | SYS |
| 40 | 605-06140 CURB AND GUTTER, CONCRETE | 940.000 | LFT |
| 41 | 605-06145 CURB AND GUTTER, B, CONCRETE | 210.000 | LFT |
| 42 | 610-08446 PCCP FOR APPROACHES, 6 IN. | 257.000 | SYS |
| 43 | 610-09108 PCCP FOR APPROACHES, 9 IN. | 497.000 | SYS |
| 44 | 616-02320 GEOTEXTILES | 33.000 | SYS |
| 45 | 616-06405 RIPRAP, REVETMENT | 17.000 | TON |
| 46 | 621-06545 FERTILIZER | 0.020 | TON |
| 47 | 621-06557 SEED MIXTURE, T | 15.000 | LBS |
| 48 | 621-06565 MULCHING MATERIAL | 0.400 | TON |
| 49 | 621-06567 WATER | 3.200 | KGAL |

CALL ORDER : 311

CONTRACT ID : R -30703-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | INTERSECTION IMPROVEMENT | | |
| 50 | 621-06570 TOP SOIL | 20.000 | CYS |
| 51 | 621-06575 SODDING, NURSERY | 821.000 | SYS |
| 52 | 628-09402 FIELD OFFICE, B | 10.000 | MOS |
| 53 | 702-51015 CONCRETE, B, FOOTINGS | 3.000 | CYS |
| 54 | 714-05562 RETAINING WALL | 90.000 | SFT |
| 55 | 715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN. | 256.000 | LFT |
| 56 | 715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN. | 75.000 | LFT |
| 57 | 715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN. | 579.000 | LFT |
| 58 | 715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN. | 249.000 | LFT |
| 59 | 715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN. | 210.000 | LFT |
| 60 | 715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B | 24.000 | TON |
| 61 | 715-09064 VIDEO INSPECTION FOR PIPE | 1,038.000 | LFT |
| 62 | 715-46020 PIPE END SECTION, 24 IN. | 1.000 | EACH |
| 63 | 718-52610 AGGREGATE FOR UNDERDRAINS | 32.000 | CYS |
| 64 | 718-99153 GEOTEXTILES FOR UNDERDRAIN | 107.000 | SYS |
| 65 | 720-44000 CASTING, ADJUST TO GRADE | 5.000 | EACH |
| 66 | 720-45005 INLET, A2 | 1.000 | EACH |
| 67 | 720-45030 INLET, E7 | 1.000 | EACH |
| 68 | 720-45040 INLET, G7 | 2.000 | EACH |
| 69 | 720-45080 INLET, S14 | 2.000 | EACH |
| 70 | 720-45270 PIPE CATCH BASIN, 18 IN. | 1.000 | EACH |
| 71 | 720-45410 MANHOLE, C4 | 7.000 | EACH |
| 72 | 720-90984 MANHOLE, C2 | 1.000 | EACH |
| 73 | 720-98174 INLET, B15 | 5.000 | EACH |
| 74 | 720-98555 INLET, C15 | 4.000 | EACH |
| 75 | 732-08419 MODULAR BLOCK WALL | 37.000 | SYS |
| 76 | 732-08421 MODULAR BLOCK WALL ERECTION | 37.000 | SYS |
| 77 | 801-03290 CONSTRUCTION SIGN, C | 1.000 | EACH |
| 78 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 6.000 | EACH |
| 79 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 5,540.000 | LFT |
| 80 | 801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN. | 30.000 | LFT |
| 81 | 801-06640 CONSTRUCTION SIGN, A | 18.000 | EACH |
| 82 | 801-06645 CONSTRUCTION SIGN, B | 4.000 | EACH |
| 83 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 84 | 801-07119 BARRICADE, III-B | 228.000 | LFT |
| 85 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 157.000 | LFT |
| 86 | 802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE | 14.000 | EACH |
| 87 | 802-07060 SIGN, SHEET, RELOCATE | 1.000 | EACH |
| 88 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080 IN. | 72.000 | SFT |
| 89 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 102.000 | LFT |
| 90 | 808-06713 LINE, PAINT, SOLID, WHITE, 4 IN. | 190.000 | LFT |
| 91 | 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN. | 670.000 | LFT |
| 92 | 808-06716 LINE, REMOVE | 4,650.000 | LFT |
| 93 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 1,284.000 | LFT |
| 94 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 65.000 | LFT |
| 95 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 20.000 | EACH |

CALL ORDER : 331

CONTRACT ID : R -31343-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | ROAD RECONSTRUCTION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 2.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 48.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 5 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 6 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 7 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 8 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 9 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 10 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 11 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 12 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 13 | 202-02245 TREE, 6 IN., REMOVE | 8.000 | EACH |
| 14 | 202-02250 TREE, 10 IN., REMOVE | 6.000 | EACH |
| 15 | 202-02928 CATCH BASIN, REMOVE | 2.000 | EACH |
| 16 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 6.000 | SYS |
| 17 | 202-93047 MANHOLE, REMOVE | 1.000 | EACH |
| 18 | 202-96133 PIPE, REMOVE | 691.000 | LFT |
| 19 | 203-02000 EXCAVATION, COMMON | 14,410.000 | CYS |
| 20 | 205-03371 SEDIMENT, REMOVE | 61.000 | CYS |
| 21 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 5.000 | TON |
| 22 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 17.000 | EACH |
| 23 | 205-06937 TEMPORARY SILT FENCE | 4,868.000 | LFT |
| 24 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 35,992.000 | SYS |
| 25 | 207-08266 SUBGRADE TREATMENT, TYPE III | 4,492.000 | SYS |
| 26 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 2,674.000 | SYS |
| 27 | 211-09264 STRUCTURE BACKFILL, TYPE 1 | 874.000 | CYS |
| 28 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 2,940.000 | TON |
| 29 | 302-08562 COARSE AGGREGATE, 8 | 450.000 | TON |
| 30 | 304-07493 WIDENING WITH HMA, TYPE B | 51.000 | TON |
| 31 | 306-08043 MILLING, TRANSITION | 516.000 | SYS |
| 32 | 401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 1,992.000 | TON |
| 33 | 401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm | 3,320.000 | TON |
| 34 | 401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm | 5,590.000 | TON |
| 35 | 401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm | 3,641.000 | TON |
| 36 | 401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm | 3,976.000 | TON |
| 37 | 402-07453 HMA FOR TEMPORARY PAVEMENT | 988.000 | TON |
| 38 | 406-05520 ASPHALT FOR TACK COAT | 25.000 | TON |
| 39 | 601-06035 GUARDRAIL, RESET | 77.000 | LFT |
| 40 | 601-07050 GUARDRAIL END TREATMENT, OS, RESET | 1.000 | EACH |
| 41 | 603-06065 FENCE, CHAIN LINK, RESET | 30.000 | LFT |
| 42 | 604-07901 CURB RAMP, CONCRETE, G | 95.000 | SYS |
| 43 | 604-91531 SIDEWALK, CONCRETE, 4 IN. | 132.000 | SYS |
| 44 | 604-91531 SIDEWALK, CONCRETE, 4 IN. | 4,501.000 | SYS |
| 45 | 605-06120 CURB, CONCRETE | 402.000 | LFT |
| 46 | 605-06140 CURB AND GUTTER, CONCRETE | 7,471.000 | LFT |
| 47 | 605-06210 CENTER CURB, C, CONCRETE | 200.000 | LFT |
| 48 | 605-94811 CURB TURNOUT | 31.000 | EACH |
| 49 | 605-96305 CURB AND GUTTER, CONCRETE, DEPRESSED | 1,236.000 | LFT |

CALL ORDER : 331

CONTRACT ID : R -31343-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | ROAD RECONSTRUCTION | | |
| 50 | 607-06175 GUTTER, CONCRETE | 192.000 | LFT |
| 51 | 610-07487 HMA FOR APPROACHES, TYPE B | 385.000 | TON |
| 52 | 610-09108 PCCP FOR APPROACHES, 9 IN. | 2,092.000 | SYS |
| 53 | 611-02825 MAILBOX ASSEMBLY, TRIPLE | 1.000 | EACH |
| 54 | 611-06497 MAILBOX ASSEMBLY, SINGLE | 3.000 | EACH |
| 55 | 611-06498 MAILBOX ASSEMBLY, DOUBLE | 1.000 | EACH |
| 56 | 615-06505 MONUMENT, B | 3.000 | EACH |
| 57 | 616-02320 GEOTEXTILES | 269.000 | SYS |
| 58 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 4.000 | EACH |
| 59 | 621-04258 SEED MIXTURE | 296.000 | LBS |
| 60 | 621-06545 FERTILIZER | 2.000 | TON |
| 61 | 621-06557 SEED MIXTURE, T | 585.000 | LBS |
| 62 | 621-06565 MULCHING MATERIAL | 12.000 | TON |
| 63 | 621-06567 WATER | 39.000 | KGAL |
| 64 | 621-06575 SODDING, NURSERY | 10,804.000 | SYS |
| 65 | 621-98038 MULCH, HARDWOOD SHREDDED BARK | 12.000 | CYS |
| 66 | 621-99173 SEED MIXTURE, S | 4.000 | LBS |
| 67 | 622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER | 312.000 | EACH |
| 68 | 622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN. | 46.000 | EACH |
| 69 | 622-05654 PLANT, PERENNIAL | 9,280.000 | EACH |
| 70 | 622-05654 PLANT, PERENNIAL | 988.000 | EACH |
| 71 | 628-09402 FIELD OFFICE, B | 24.000 | MOS |
| 72 | 715-04555 PIPE END SECTION, MIN. AREA 5.1 SQ. FT. | 2.000 | EACH |
| 73 | 715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN. | 8,231.000 | LFT |
| 74 | 715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN. | 188.000 | LFT |
| 75 | 715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN. | 1,787.000 | LFT |
| 76 | 715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN. | 146.000 | LFT |
| 77 | 715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN. | 282.000 | LFT |
| 78 | 715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN. | 156.000 | LFT |
| 79 | 715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN. | 635.000 | LFT |
| 80 | 715-09064 VIDEO INSPECTION FOR PIPE | 3,020.000 | LFT |
| 81 | 715-09769 PIPE, TYPE 3, DEFORMED, MIN. AREA 5.1 SFT. | 58.000 | LFT |
| 82 | 715-46000 PIPE END SECTION, 12 IN. | 20.000 | EACH |
| 83 | 715-46005 PIPE END SECTION, 15 IN. | 6.000 | EACH |
| 84 | 715-46010 PIPE END SECTION, 18 IN. | 3.000 | EACH |
| 85 | 715-46020 PIPE END SECTION, 24 IN. | 1.000 | EACH |
| 86 | 718-06531 OUTLET PROTECTOR, 3 | 13.000 | EACH |
| 87 | 718-06532 VIDEO INSPECTION FOR UNDERDRAINS | 3,000.000 | LFT |
| 88 | 718-52610 AGGREGATE FOR UNDERDRAINS | 854.000 | CYS |
| 89 | 718-99153 GEOTEXTILES FOR UNDERDRAIN | 13,961.000 | SYS |
| 90 | 720-09079 INLET, HA5, MODIFIED | 3.000 | EACH |
| 91 | 720-44000 CASTING, ADJUST TO GRADE | 5.000 | EACH |
| 92 | 720-45010 INLET, A3 | 6.000 | EACH |
| 93 | 720-45030 INLET, E7 | 2.000 | EACH |
| 94 | 720-45035 INLET, F7 | 1.000 | EACH |
| 95 | 720-94157 MANHOLE, C | 2.000 | EACH |
| 96 | 720-97958 MANHOLE, K2 | 2.000 | EACH |
| 97 | 720-98174 INLET, B15 | 20.000 | EACH |
| 98 | 720-98555 INLET, C15 | 7.000 | EACH |

CALL ORDER : 331

CONTRACT ID : R -31343-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | ROAD RECONSTRUCTION | | |
| 99 | 801-03290 CONSTRUCTION SIGN, C | 2.000 | EACH |
| 100 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 6.000 | EACH |
| 101 | 801-06203 TEMPORARY PAVEMENT MARKING, 4 IN. | 39,232.000 | LFT |
| 102 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 12,247.000 | LFT |
| 103 | 801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN. | 285.000 | LFT |
| 104 | 801-06625 DETOUR ROUTE MARKER ASSEMBLY | 22.000 | EACH |
| 105 | 801-06640 CONSTRUCTION SIGN, A | 4.000 | EACH |
| 106 | 801-06645 CONSTRUCTION SIGN, B | 2.000 | EACH |
| 107 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 108 | 801-07118 BARRICADE, III-A | 88.000 | LFT |
| 109 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 235.000 | LFT |
| 110 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080 IN. | 56.000 | SFT |
| 111 | 805-01842 HANDHOLE, SIGNAL | 1.000 | EACH |
| 112 | 805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND | 170.000 | LFT |
| 113 | 805-02328 SIGNAL CABLE, 1C 14GA. | 1,494.000 | LFT |
| 114 | 805-78490 SIGNAL CABLE, 7C 14GA. | 686.000 | LFT |
| 115 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 1,820.000 | LFT |
| 116 | 805-78785 SIGNAL DETECTOR HOUSING | 3.000 | EACH |
| 117 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER | 594.000 | LFT |
| 118 | 808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN. | 3,598.000 | LFT |
| 119 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 260.000 | LFT |
| 120 | 808-06716 LINE, REMOVE | 2,016.000 | LFT |
| 121 | 808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN. | 150.000 | LFT |
| 122 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 8,724.000 | LFT |
| 123 | 808-75274 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW, | 1,374.000 | LFT |
| 124 | 808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW, | 152.000 | LFT |
| 125 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 223.000 | LFT |
| 126 | 808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN. | 178.000 | LFT |
| 127 | 808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 4.000 | EACH |
| 128 | 808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 3.000 | EACH |
| 129 | 808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR | 4.000 | EACH |

CALL ORDER : 341

CONTRACT ID : R -31782-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNALS MODERNIZATION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 6.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 5 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 6 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 10 | 202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE | 62.000 | EACH |
| 11 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 113.000 | SYS |
| 12 | 203-02000 EXCAVATION, COMMON | 142.000 | CYS |
| 13 | 203-02070 BORROW | 12.000 | CYS |
| 14 | 211-02050 B BORROW | 44.000 | CYS |
| 15 | 604-91531 SIDEWALK, CONCRETE, 4 IN. | 91.000 | SYS |
| 16 | 621-06574 SODDING | 88.000 | SYS |
| 17 | 628-09408 MOBILE LAPTOP COMPUTER SYSTEM | 6.000 | MOS |
| 18 | 628-09409 MOBILE INTERNET SERVICE | 6.000 | MOS |
| 19 | 801-03290 CONSTRUCTION SIGN, C | 98.000 | EACH |
| 20 | 801-06640 CONSTRUCTION SIGN, A | 492.000 | EACH |
| 21 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 22 | 801-92448 CONSTRUCTION SIGNS, MOBILE | 780.000 | DAY |
| 23 | 805-01579 MISCELLANEOUS EQUIPMENT FOR SYSTEM LOOP AND INTERCONNECT | LUMP | LUMP |
| 24 | 805-01579 MISCELLANEOUS EQUIPMENT FOR SYSTEM LOOP AND INTERCONNECT | LUMP | LUMP |
| 25 | 805-01842 HANDHOLE, SIGNAL | 5.000 | EACH |
| 26 | 805-01842 HANDHOLE, SIGNAL | 45.000 | EACH |
| 27 | 805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND | 659.000 | LFT |
| 28 | 805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND | 11,092.000 | LFT |
| 29 | 805-01879 SIGNAL SERVICE, INSTALL | 8.000 | EACH |
| 30 | 805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT | LUMP | LUMP |
| 31 | 805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN. | 6.000 | EACH |
| 32 | 805-02373 INTERCONNECT CABLE, FIBER OPTIC | 11,445.000 | LFT |
| 33 | 805-02855 SIGNAL SUPPORT FOUNDATION, 2 FT. 6 IN. X 2 FT. 6 IN. X 6 FT. | 1.000 | EACH |
| 34 | 805-04133 SIGNAL PEDESTAL, 12 FT. | 1.000 | EACH |
| 35 | 805-09094 SIGNAL CONTROLLER, TS2, TYPE 1 | 2.000 | EACH |
| 36 | 805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE | 5.000 | EACH |
| 37 | 805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE | 1.000 | EACH |
| 38 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN | 9.000 | EACH |
| 39 | 805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN, | 1.000 | EACH |
| 40 | 805-78370 PEDESTRIAN PUSH BUTTON | 6.000 | EACH |
| 41 | 805-78467 SIGNAL CABLE, 3C 8GA. | 265.000 | LFT |
| 42 | 805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA. | 5,018.000 | LFT |
| 43 | 805-78480 SIGNAL CABLE, 3C 14GA. | 667.000 | LFT |
| 44 | 805-78485 SIGNAL CABLE, 5C 14GA. | 3,457.000 | LFT |
| 45 | 805-78490 SIGNAL CABLE, 7C 14GA. | 12,716.000 | LFT |
| 46 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 5,662.000 | LFT |
| 47 | 805-78520 MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS | LUMP | LUMP |
| 48 | 805-78785 SIGNAL DETECTOR HOUSING | 21.000 | EACH |
| 49 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER | 1,923.000 | LFT |

CALL ORDER : 341

CONTRACT ID : R -31782-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|----------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNALS MODERNIZATION | | |
| 50 805-78900 | PEDESTAL FOUNDATION, A | 1.000 | EACH |
| 51 805-78925 | CONTROLLER CABINET FOUNDATION, P1 | 5.000 | EACH |
| 52 805-92504 | LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL | 14.000 | EACH |
| 53 807-86805 | SERVICE POINT, I | 8.000 | EACH |
| 54 808-06703 | LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 187.000 | LFT |
| 55 808-06726 | TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN. | 49.000 | LFT |
| 56 808-75245 | LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 568.000 | LFT |
| 57 808-75320 | PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 8.000 | EACH |
| 58 808-75325 | PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 2.000 | EACH |

CALL ORDER : 351

CONTRACT ID : R -31829-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | ENHANCEMENT BIKE/PEDESTRIAN FACILITIES | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 11.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 5 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 6 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 10 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 11 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 12 | 203-02000 EXCAVATION, COMMON | 5,751.000 | CYS |
| 13 | 204-02290 SETTLEMENT PLATE | 2.000 | EACH |
| 14 | 205-03371 SEDIMENT, REMOVE | 25.000 | CYS |
| 15 | 205-06930 SPLASHPAD, RIPRAP | 13.000 | TON |
| 16 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 11.000 | TON |
| 17 | 205-06932 TEMPORARY CHECK DAM, STRAW BALES | 315.000 | LFT |
| 18 | 205-06934 TEMPORARY MULCHING | 18.000 | TON |
| 19 | 205-06937 TEMPORARY SILT FENCE | 2,710.000 | LFT |
| 20 | 205-09543 NO 2 STONE | 200.000 | TON |
| 21 | 207-08262 SUBGRADE TREATMENT, TYPE I | 3,472.000 | SYS |
| 22 | 210-04181 BICYCLE RACK | 2.000 | EACH |
| 23 | 210-07858 UTILITY | 1.000 | EACH |
| 24 | 210-08284 EMERGENCY | 6.000 | EACH |
| 25 | 211-09264 STRUCTURE BACKFILL, TYPE 1 | 81.000 | CYS |
| 26 | 211-09266 STRUCTURE BACKFILL, TYPE 3 | 937.000 | CYS |
| 27 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 2,849.000 | TON |
| 28 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 174.000 | TON |
| 29 | 303-07449 COMPACTED AGGREGATE, NO. 73 | 310.000 | TON |
| 30 | 402-07432 HMA SURFACE, TYPE A | 565.000 | TON |
| 31 | 402-07435 HMA INTERMEDIATE, TYPE A | 943.000 | TON |
| 32 | 406-05520 ASPHALT FOR TACK COAT | 1.700 | TON |
| 33 | 601-98352 BICYCLE RAILING | 736.000 | LFT |
| 34 | 604-91404 SIDEWALK, CONCRETE, 5 IN. | 683.000 | SYS |
| 35 | 604-91404 SIDEWALK, CONCRETE, 5 IN. | 15.000 | SYS |
| 36 | 604-91404 SIDEWALK, CONCRETE, 5 IN. | 18.000 | SYS |
| 37 | 605-06140 CURB AND GUTTER, CONCRETE | 157.000 | LFT |
| 38 | 607-06335 PAVED SIDE DITCH, A | 73.000 | LFT |
| 39 | 616-02320 GEOTEXTILES | 403.000 | SYS |
| 40 | 616-06451 RIPRAP, UNIFORM | 215.000 | TON |
| 41 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 2.000 | EACH |
| 42 | 621-02770 EROSION CONTROL BLANKET | 1,720.000 | SYS |
| 43 | 621-06545 FERTILIZER | 0.650 | TON |
| 44 | 621-06554 SEED MIXTURE, U | 405.000 | LBS |
| 45 | 621-06557 SEED MIXTURE, T | 1,080.000 | LBS |
| 46 | 621-06565 MULCHING MATERIAL | 3.250 | TON |
| 47 | 621-06567 WATER | 36.000 | KGAL |
| 48 | 621-06575 SODDING, NURSERY | 8,875.000 | SYS |
| 49 | 621-07642 SOIL PREPARATION | 168.000 | CYS |

CALL ORDER : 351

CONTRACT ID : R -31829-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | ENHANCEMENT BIKE/PEDESTRIAN FACILITIES | | |
| 50 | 621-09273 WEED BARRIER | 335.000 | SYS |
| 51 | 621-98038 MULCH, HARDWOOD SHREDDED BARK | 37.000 | CYS |
| 52 | 622-01937 PLANT | 68.000 | EACH |
| 53 | 622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN. | 89.000 | EACH |
| 54 | 622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN. | 25.000 | EACH |
| 55 | 622-05654 PLANT, PERENNIAL | 18.000 | EACH |
| 56 | 628-09402 FIELD OFFICE, B | 11.000 | MOS |
| 57 | 714-02930 HEADWALL | 5.000 | EACH |
| 58 | 715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN. | 296.000 | LFT |
| 59 | 715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN. | 31.000 | LFT |
| 60 | 715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN. | 58.000 | LFT |
| 61 | 715-46000 PIPE END SECTION, 12 IN. | 20.000 | EACH |
| 62 | 715-46005 PIPE END SECTION, 15 IN. | 4.000 | EACH |
| 63 | 715-46010 PIPE END SECTION, 18 IN. | 1.000 | EACH |
| 64 | 715-92537 PIPE, PVC, 8 IN. | 12.000 | LFT |
| 65 | 732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT | 630.000 | SYS |
| 66 | 732-08421 MODULAR BLOCK WALL ERECTION | 630.000 | SYS |
| 67 | 801-03290 CONSTRUCTION SIGN, C | 2.000 | EACH |
| 68 | 801-06640 CONSTRUCTION SIGN, A | 6.000 | EACH |
| 69 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 70 | 801-07119 BARRICADE, III-B | 60.000 | LFT |
| 71 | 802-03896 BOLLARD | 10.000 | EACH |
| 72 | 802-03896 BOLLARD | 3.000 | EACH |
| 73 | 802-04314 SIGN | 4.000 | EACH |
| 74 | 802-04314 SIGN | 1.000 | EACH |
| 75 | 802-04314 SIGN | 86.000 | EACH |
| 76 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 243.000 | LFT |
| 77 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080 IN. | 35.000 | SFT |
| 78 | 805-01419 CIRCUIT BREAKER, INSTALL | 5.000 | EACH |
| 79 | 805-01879 SIGNAL SERVICE, INSTALL | 1.000 | EACH |
| 80 | 805-02572 SIGNAL SUPPORT FOUNDATION, A | 2.000 | EACH |
| 81 | 805-02728 CONDUIT, PVC, 1 IN. | 4,000.000 | LFT |
| 82 | 805-04973 CONDUIT | 8,200.000 | LFT |
| 83 | 805-04973 CONDUIT | 3,500.000 | LFT |
| 84 | 805-04973 CONDUIT | 750.000 | LFT |
| 85 | 805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE | 1.000 | EACH |
| 86 | 805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12" AMBER | 2.000 | EACH |
| 87 | 805-78480 SIGNAL CABLE, 3C 14GA. | 152.000 | LFT |
| 88 | 805-90005 SIGNAL PEDESTAL, 10 FT. | 2.000 | EACH |
| 89 | 805-94554 PULL BOX, POLYETHYLENE | 1.000 | EACH |
| 90 | 805-95888 WIRE, NO. 8 COPPER, 1C | 6,000.000 | LFT |
| 91 | 805-95889 WIRE, NO. 10 COPPER, 1C | 4,600.000 | LFT |
| 92 | 807-04651 WIRE | 8,500.000 | LFT |
| 93 | 807-04967 CABLE | 17,000.000 | LFT |
| 94 | 807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC | 218.000 | LFT |
| 95 | 807-78590 HANDHOLE | 22.000 | EACH |
| 96 | 808-04767 LINE | 3,231.000 | LFT |

CALL ORDER : 361

CONTRACT ID : R -31892-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNAL MODERNIZATION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 6.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 5 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 6 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 10 | 202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE | 10.000 | EACH |
| 11 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 112.000 | SYS |
| 12 | 203-02000 EXCAVATION, COMMON | 140.000 | CYS |
| 13 | 203-02070 BORROW | 8.000 | CYS |
| 14 | 210-07227 POWER SUPPLY | 10.000 | EACH |
| 15 | 211-02050 B BORROW | 41.000 | CYS |
| 16 | 604-91531 SIDEWALK, CONCRETE, 4 IN. | 85.000 | SYS |
| 17 | 621-06574 SODDING | 85.000 | SYS |
| 18 | 628-09408 MOBILE LAPTOP COMPUTER SYSTEM | 6.000 | MOS |
| 19 | 628-09409 MOBILE INTERNET SERVICE | 6.000 | MOS |
| 20 | 801-03290 CONSTRUCTION SIGN, C | 134.000 | EACH |
| 21 | 801-06640 CONSTRUCTION SIGN, A | 684.000 | EACH |
| 22 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 23 | 801-92448 CONSTRUCTION SIGNS, MOBILE | 780.000 | DAY |
| 24 | 802-07060 SIGN, SHEET, RELOCATE | 5.000 | EACH |
| 25 | 805-01579 MISCELLANEOUS EQUIPMENT FOR SYSTEM LOOP AND INTERCONNECT | LUMP | LUMP |
| 26 | 805-01842 HANDHOLE, SIGNAL | 50.000 | EACH |
| 27 | 805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND | 14,129.000 | LFT |
| 28 | 805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT | LUMP | LUMP |
| 29 | 805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN. | 8.000 | EACH |
| 30 | 805-02373 INTERCONNECT CABLE, FIBER OPTIC | 20,094.000 | LFT |
| 31 | 805-09094 SIGNAL CONTROLLER, TS2, TYPE 1 | 3.000 | EACH |
| 32 | 805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE | 6.000 | EACH |
| 33 | 805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE | 1.000 | EACH |
| 34 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN | 6.000 | EACH |
| 35 | 805-78370 PEDESTRIAN PUSH BUTTON | 8.000 | EACH |
| 36 | 805-78467 SIGNAL CABLE, 3C 8GA. | 289.000 | LFT |
| 37 | 805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA. | 4,895.000 | LFT |
| 38 | 805-78485 SIGNAL CABLE, 5C 14GA. | 2,090.000 | LFT |
| 39 | 805-78490 SIGNAL CABLE, 7C 14GA. | 12,605.000 | LFT |
| 40 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 6,628.000 | LFT |
| 41 | 805-78785 SIGNAL DETECTOR HOUSING | 8.000 | EACH |
| 42 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER | 1,955.000 | LFT |
| 43 | 805-78925 CONTROLLER CABINET FOUNDATION, P1 | 4.000 | EACH |
| 44 | 805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL | 33.000 | EACH |
| 45 | 807-01603 SERVICE POINT, TYPE II | 8.000 | EACH |

CALL ORDER : 371

CONTRACT ID : R -32490-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | ROAD REHABILITATION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 5 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 6 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 7 | 109-08463 PROJECT ESTIMATE ADJUSTMENT | 1.000 | DOL |
| 8 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 9 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 10 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 11 | 202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE | 1.000 | EACH |
| 12 | 202-02240 PAVEMENT REMOVAL | 17,290.000 | SYS |
| 13 | 202-02273 CENTER CURB, CONCRETE, REMOVE | 741.000 | SYS |
| 14 | 202-86946 HANDHOLE, REMOVE | 5.000 | EACH |
| 15 | 202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE | 15.000 | EACH |
| 16 | 203-02000 EXCAVATION, COMMON | 11,937.000 | CYS |
| 17 | 205-03371 SEDIMENT, REMOVE | 5.000 | CYS |
| 18 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 1.000 | EACH |
| 19 | 205-06934 TEMPORARY MULCHING | 0.600 | TON |
| 20 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 795.000 | SYS |
| 21 | 207-08268 SUBGRADE TREATMENT, TYPE IV | 34,309.000 | SYS |
| 22 | 211-09264 STRUCTURE BACKFILL, TYPE 1 | 7,710.000 | CYS |
| 23 | 213-09269 FLOWABLE BACKFILL, NON-REMOVABLE | 1,900.000 | CYS |
| 24 | 304-07491 HMA PATCHING, TYPE C | 81.000 | TON |
| 25 | 306-08034 MILLING, ASPHALT, 1 1/2 IN. | 17,753.000 | SYS |
| 26 | 401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm | 4,391.000 | TON |
| 27 | 401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm | 4,731.000 | TON |
| 28 | 401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm | 23,132.000 | TON |
| 29 | 402-07452 HMA WEDGE AND LEVEL, TYPE C | 2,196.000 | TON |
| 30 | 406-05520 ASPHALT FOR TACK COAT | 40.000 | TON |
| 31 | 604-07897 CURB RAMP, CONCRETE, C | 9.000 | SYS |
| 32 | 604-07900 CURB RAMP, CONCRETE, F | 133.000 | SYS |
| 33 | 604-07902 CURB RAMP, CONCRETE, H | 59.000 | SYS |
| 34 | 604-07903 CURB RAMP, CONCRETE, K | 11.000 | SYS |
| 35 | 604-91404 SIDEWALK, CONCRETE, 5 IN. | 3,987.000 | SYS |
| 36 | 605-06120 CURB, CONCRETE | 192.000 | LFT |
| 37 | 605-06140 CURB AND GUTTER, CONCRETE | 5,749.000 | LFT |
| 38 | 605-06215 CENTER CURB, D, CONCRETE | 33.000 | LFT |
| 39 | 610-07487 HMA FOR APPROACHES, TYPE B | 53.000 | TON |
| 40 | 610-09108 PCCP FOR APPROACHES, 9 IN. | 679.000 | SYS |
| 41 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 2.000 | EACH |
| 42 | 621-06545 FERTILIZER | 0.200 | TON |
| 43 | 621-06557 SEED MIXTURE, T | 36.000 | LBS |
| 44 | 621-06560 MULCHED SEEDING, U | 2,300.000 | SYS |
| 45 | 621-06567 WATER | 18.000 | KGAL |
| 46 | 621-06575 SODDING, NURSERY | 2,300.000 | SYS |
| 47 | 628-09402 FIELD OFFICE, B | 18.000 | MOS |
| 48 | 628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL | 18.000 | MOS |
| 49 | 715-01902 WATER SERVICE LINE, 2 IN. | 130.000 | LFT |

CALL ORDER : 371

CONTRACT ID : R -32490-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | ROAD REHABILITATION | | |
| 50 | 715-02048 MISCELLANEOUS EQUIPMENT FOR WATER RELOCATION AND ADJUSTMENT | LUMP | LUMP |
| 51 | 715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN. | 1,445.000 | LFT |
| 52 | 715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN. | 3,176.000 | LFT |
| 53 | 715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN. | 1,544.000 | LFT |
| 54 | 715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN. | 51.000 | LFT |
| 55 | 715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN. | 1,089.000 | LFT |
| 56 | 715-05155 PIPE, TYPE 2, CIRCULAR, 27 IN. | 286.000 | LFT |
| 57 | 715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN. | 1,110.000 | LFT |
| 58 | 715-05159 PIPE, TYPE 2, CIRCULAR, 42 IN. | 163.000 | LFT |
| 59 | 715-05408 PIPE, SANITARY SEWER, 8 IN. | 270.000 | LFT |
| 60 | 715-05409 PIPE, SANITARY SEWER, 10 IN. | 125.000 | LFT |
| 61 | 715-05411 PIPE, SANITARY SEWER, 12 IN. | 1,154.000 | LFT |
| 62 | 715-05412 PIPE, SANITARY SEWER, 15 IN. | 250.000 | LFT |
| 63 | 715-05413 PIPE, SANITARY SEWER, 18 IN. | 1,186.000 | LFT |
| 64 | 715-05415 PIPE, SANITARY SEWER, 24 IN. | 3,283.000 | LFT |
| 65 | 715-05711 PIPE, SANITARY SEWER, 6 IN. | 20.000 | LFT |
| 66 | 715-09064 VIDEO INSPECTION FOR PIPE | 14,134.000 | LFT |
| 67 | 715-96629 WATER SERVICE LINE, 1 IN. | 100.000 | LFT |
| 68 | 715-96669 WATER MAIN, DUCTILE IRON, 16 IN. | 50.000 | LFT |
| 69 | 715-97419 WATER MAIN, DUCTILE IRON, 24 IN. | 25.000 | LFT |
| 70 | 720-03988 MANHOLE, J4, DROP | 1.000 | EACH |
| 71 | 720-44000 CASTING, ADJUST TO GRADE | 5.000 | EACH |
| 72 | 720-44296 CAP INLET | 1.000 | EACH |
| 73 | 720-45045 INLET, J10 | 17.000 | EACH |
| 74 | 720-45055 INLET, M10 | 6.000 | EACH |
| 75 | 720-45205 CATCH BASIN, A2 | 4.000 | EACH |
| 76 | 720-45250 CATCH BASIN, K10 | 31.000 | EACH |
| 77 | 720-45410 MANHOLE, C4 | 32.000 | EACH |
| 78 | 720-90579 HYDRANT SETTING, RELOCATE | 1.000 | EACH |
| 79 | 720-90984 MANHOLE, C2 | 1.000 | EACH |
| 80 | 720-94612 MANHOLE, K4 | 1.000 | EACH |
| 81 | 720-95422 MANHOLE, J4 | 26.000 | EACH |
| 82 | 720-96999 FIRE HYDRANT ASSEMBLY | 1.000 | EACH |
| 83 | 720-98625 MANHOLE, C4, DROP | 2.000 | EACH |
| 84 | 732-91738 WATER MAIN, DUCTILE IRON, 6 IN. | 225.000 | LFT |
| 85 | 732-91739 WATER MAIN, DUCTILE IRON, 8 IN. | 703.000 | LFT |
| 86 | 732-96670 WATER MAIN, DUCTILE IRON, 12 IN. | 50.000 | LFT |
| 87 | 732-97009 FIRE HYDRANT ASSEMBLY, REMOVE | 1.000 | EACH |
| 88 | 801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW | 21.000 | EACH |
| 89 | 801-02595 CONTROLLER, RESET TIMING | 11.000 | EACH |
| 90 | 801-03290 CONSTRUCTION SIGN, C | 4.000 | EACH |
| 91 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 4.000 | EACH |
| 92 | 801-06203 TEMPORARY PAVEMENT MARKING, 4 IN. | 65,615.000 | LFT |
| 93 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 10,000.000 | LFT |
| 94 | 801-06539 TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN | LUMP | LUMP |
| 95 | 801-06640 CONSTRUCTION SIGN, A | 39.000 | EACH |
| 96 | 801-06645 CONSTRUCTION SIGN, B | 6.000 | EACH |
| 97 | 801-06710 FLASHING ARROW SIGN | 1,320.000 | DAY |
| 98 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |

CALL ORDER : 371

CONTRACT ID : R -32490-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | ROAD REHABILITATION | | |
| 99 | 801-07119 BARRICADE, III-B | 268.000 | LFT |
| 100 | 801-07612 TEMPORARY PAVEMENT MARKING, 24 IN. | 853.000 | LFT |
| 101 | 801-94295 SIGNAL HEAD, RELOCATE | 66.000 | EACH |
| 102 | 802-01986 POLE, STEEL GALVANIZED, 2.375 IN. | 46.000 | LFT |
| 103 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 466.000 | LFT |
| 104 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080 IN. | 264.570 | SFT |
| 105 | 802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN | 114.220 | SFT |
| 106 | 802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN | 41.500 | SFT |
| 107 | 802-97812 STREET NAME IDENTIFICATION SIGN | 8.000 | EACH |
| 108 | 805-01579 MISCELLANEOUS EQUIPMENT FOR SYSTEM LOOP AND INTERCONNECT | LUMP | LUMP |
| 109 | 805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT. | 4.000 | EACH |
| 110 | 805-01842 HANDHOLE, SIGNAL | 17.000 | EACH |
| 111 | 805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN. | 10.000 | EACH |
| 112 | 805-02373 INTERCONNECT CABLE, FIBER OPTIC | 2,620.000 | LFT |
| 113 | 805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN. | 3,675.000 | LFT |
| 114 | 805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE | 1.000 | EACH |
| 115 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN | 8.000 | EACH |
| 116 | 805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN | 4.000 | EACH |
| 117 | 805-78225 TRAFFIC SIGNAL HEAD, 4 FACE, 12 IN. RED, AMBER, GREEN, GREEN | 4.000 | EACH |
| 118 | 805-78370 PEDESTRIAN PUSH BUTTON | 10.000 | EACH |
| 119 | 805-78415 SPAN, CATENARY, AND TETHER | 4.000 | EACH |
| 120 | 805-78420 DISCONNECT HANGER | 4.000 | EACH |
| 121 | 805-78445 SIGNAL SERVICE | 1.000 | EACH |
| 122 | 805-78467 SIGNAL CABLE, 3C 8GA. | 50.000 | LFT |
| 123 | 805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA. | 6,878.000 | LFT |
| 124 | 805-78480 SIGNAL CABLE, 3C 14GA. | 1,465.000 | LFT |
| 125 | 805-78485 SIGNAL CABLE, 5C 14GA. | 1,795.000 | LFT |
| 126 | 805-78500 SIGNAL CABLE, 11C 14GA. | 870.000 | LFT |
| 127 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 4,112.000 | LFT |
| 128 | 805-78785 SIGNAL DETECTOR HOUSING | 13.000 | EACH |
| 129 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER | 2,431.000 | LFT |
| 130 | 805-78925 CONTROLLER CABINET FOUNDATION, P1 | 1.000 | EACH |
| 131 | 805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT. | 4.000 | EACH |
| 132 | 805-86838 WIRE, NO. 4 COPPER IN CONDUIT, 1C | 8,300.000 | LFT |
| 133 | 805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL | 6.000 | EACH |
| 134 | 805-95598 WIRE, NO. 1 COPPER IN PLASTIC DUCTIN TRENCH, 4 1/C | 1,300.000 | LFT |
| 135 | 805-95889 WIRE, NO. 10 COPPER, 1C | 2,250.000 | LFT |
| 136 | 805-99327 CONDUIT, SPLICE | 3.000 | EACH |
| 137 | 807-02191 HANDHOLE, LIGHTING | 6.000 | EACH |
| 138 | 807-02193 LIGHT STANDARD FOUNDATION, 3 FT. DIA. X 8 FT. | 15.000 | EACH |
| 139 | 807-02603 LIGHT STANDARD, RELOCATE | 15.000 | EACH |
| 140 | 807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC | 1,000.000 | LFT |
| 141 | 807-86910 CONNECTOR KIT, UNFUSED | 15.000 | EACH |
| 142 | 807-86915 CONNECTOR KIT, FUSED | 15.000 | EACH |
| 143 | 807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED | 45.000 | EACH |
| 144 | 807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED | 16.000 | EACH |
| 145 | 807-86930 INSULATION LINK, NONWATERPROOFED | 30.000 | EACH |
| 146 | 807-86935 INSULATION LINK, WATERPROOFED | 28.000 | EACH |
| 147 | 807-86955 CABLE DUCT MARKER | 2.000 | EACH |

CALL ORDER : 371

CONTRACT ID : R -32490-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | ROAD REHABILITATION | | |
| 148 | 808-02977 TRANSVERSE MARKING, THERMOPLASTIC, BIKE SYMBOL | 4.000 | EACH |
| 149 | 808-03114 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, (XING) 8 FT. | 4.000 | EACH |
| 150 | 808-05866 PAVEMENT MESSAGE MARKING, REMOVE | 40.000 | SYS |
| 151 | 808-05929 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 8 IN. | 2,411.000 | LFT |
| 152 | 808-06368 TRANSVERSE MARKING, REMOVE | 3,000.000 | LFT |
| 153 | 808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN. | 3,536.000 | LFT |
| 154 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 2,877.000 | LFT |
| 155 | 808-06716 LINE, REMOVE | 30,720.000 | LFT |
| 156 | 808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN. | 534.000 | LFT |
| 157 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 13,812.000 | LFT |
| 158 | 808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW, | 719.000 | LFT |
| 159 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 573.000 | LFT |
| 160 | 808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 33.000 | EACH |
| 161 | 808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY) | 30.000 | EACH |

CALL ORDER : 551

CONTRACT ID : B -30380-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | BRIDGE REPLACEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 5 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 6 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 7 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 8 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 9 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 10 | 202-02278 CURB, CONCRETE, REMOVE | 2,229.000 | LFT |
| 11 | 202-51330 PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 12 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 782.000 | SYS |
| 13 | 202-90747 RETAINING WALL, REMOVE | 280.000 | LFT |
| 14 | 202-91385 INLET, REMOVE | 2.000 | EACH |
| 15 | 202-96133 PIPE, REMOVE | 311.000 | LFT |
| 16 | 203-02000 EXCAVATION, COMMON | 9,160.000 | CYS |
| 17 | 205-06934 TEMPORARY MULCHING | 4.000 | TON |
| 18 | 205-06937 TEMPORARY SILT FENCE | 1,246.000 | LFT |
| 19 | 205-09543 NO 2 STONE | 100.000 | TON |
| 20 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 3,824.000 | SYS |
| 21 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 689.000 | SYS |
| 22 | 211-02050 B BORROW | 2,743.000 | CYS |
| 23 | 211-06467 AGGREGATE FOR END BENT BACKFILL | 19.000 | CYS |
| 24 | 211-09264 STRUCTURE BACKFILL, TYPE 1 | 1,518.000 | CYS |
| 25 | 211-09266 STRUCTURE BACKFILL, TYPE 3 | 6,623.000 | CYS |
| 26 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 176.000 | TON |
| 27 | 303-07449 COMPACTED AGGREGATE, NO. 73 | 10.000 | TON |
| 28 | 306-08043 MILLING, TRANSITION | 680.000 | SYS |
| 29 | 401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm | 2,444.000 | TON |
| 30 | 402-07434 HMA SURFACE, TYPE C | 377.000 | TON |
| 31 | 402-07439 HMA INTERMEDIATE, TYPE C | 566.000 | TON |
| 32 | 406-05520 ASPHALT FOR TACK COAT | 3.000 | TON |
| 33 | 501-05240 CONTRACTION JOINT, D1 | 323.000 | LFT |
| 34 | 601-95344 HANDRAIL, PEDESTRIAN | 160.300 | LFT |
| 35 | 603-92230 FENCE, CHAIN LINK, SECURITY, 72 IN. | 233.000 | LFT |
| 36 | 603-92636 FENCE, CHAIN LINK, 72 IN. | 115.000 | LFT |
| 37 | 604-07894 CURB RAMP, CONCRETE, A | 14.000 | SYS |
| 38 | 604-44251 STEPS, CONCRETE | 12.100 | CYS |
| 39 | 604-91531 SIDEWALK, CONCRETE, 4 IN. | 693.000 | SYS |
| 40 | 605-06120 CURB, CONCRETE | 165.000 | LFT |
| 41 | 605-06150 CURB AND GUTTER, C, CONCRETE | 1,811.000 | LFT |
| 42 | 605-92578 CURB WALK, CONCRETE | 97.000 | SYS |
| 43 | 609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN. | 344.000 | SYS |
| 44 | 610-07488 HMA FOR APPROACHES, TYPE C | 30.000 | TON |
| 45 | 610-08446 PCCP FOR APPROACHES, 6 IN. | 208.000 | SYS |
| 46 | 610-09108 PCCP FOR APPROACHES, 9 IN. | 481.000 | SYS |
| 47 | 611-02825 MAILBOX ASSEMBLY, TRIPLE | 1.000 | EACH |
| 48 | 611-06497 MAILBOX ASSEMBLY, SINGLE | 5.000 | EACH |
| 49 | 611-06498 MAILBOX ASSEMBLY, DOUBLE | 1.000 | EACH |

CALL ORDER : 551

CONTRACT ID : B -30380-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | BRIDGE REPLACEMENT | | |
| 50 | 615-06490 RIGHT OF WAY MARKER | 21.000 | EACH |
| 51 | 616-02320 GEOTEXTILES | 44.000 | SYS |
| 52 | 616-06405 RIPRAP, REVETMENT | 25.000 | TON |
| 53 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 3.000 | EACH |
| 54 | 621-06545 FERTILIZER | 0.600 | TON |
| 55 | 621-06557 SEED MIXTURE, T | 220.000 | LBS |
| 56 | 621-06565 MULCHING MATERIAL | 1.500 | TON |
| 57 | 621-06567 WATER | 43.000 | KGAL |
| 58 | 621-06575 SODDING, NURSERY | 3,520.000 | SYS |
| 59 | 628-09401 FIELD OFFICE, A | 12.000 | MOS |
| 60 | 701-51195 PILE, STEEL H, HP 12" X 53 | 907.000 | LFT |
| 61 | 703-51030 REINFORCING STEEL | 450.000 | LBS |
| 62 | 703-51032 REINFORCING STEEL, EPOXY COATED | 89,898.000 | LBS |
| 63 | 704-51002 CONCRETE, C, SUPERSTRUCTURE | 194.000 | CYS |
| 64 | 706-06349 RAILING, TX | 1,062.000 | LFT |
| 65 | 706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN. | 638.000 | SYS |
| 66 | 706-09545 COARSE AGGREGATE, NO. 8 | 160.000 | CYS |
| 67 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 68 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 69 | 711-51038 STRUCTURAL STEEL | LUMP | LUMP |
| 70 | 711-51070 ANCHOR PLATE, AP 1 | 24.000 | EACH |
| 71 | 715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN. | 744.000 | LFT |
| 72 | 715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN. | 498.000 | LFT |
| 73 | 715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN. | 287.000 | LFT |
| 74 | 715-46010 PIPE END SECTION, 18 IN. | 1.000 | EACH |
| 75 | 720-45005 INLET, A2 | 2.000 | EACH |
| 76 | 720-45270 PIPE CATCH BASIN, 18 IN. | 5.000 | EACH |
| 77 | 720-45275 PIPE CATCH BASIN, 24 IN. | 2.000 | EACH |
| 78 | 720-45410 MANHOLE, C4 | 5.000 | EACH |
| 79 | 720-45605 STRUCTURE, MANHOLE, RECONSTRUCT | 5.000 | LFT |
| 80 | 720-90984 MANHOLE, C2 | 2.000 | EACH |
| 81 | 720-93411 INLET, C15, MODIFIED | 1.000 | EACH |
| 82 | 720-94713 CATCH BASIN, C15, MODIFIED | 4.000 | EACH |
| 83 | 720-98174 INLET, B15 | 2.000 | EACH |
| 84 | 720-98555 INLET, C15 | 1.000 | EACH |
| 85 | 720-99416 CATCH BASIN, B15 | 1.000 | EACH |
| 86 | 731-08252 LEVELING PAD | 1,164.000 | LFT |
| 87 | 731-93945 FACE PANELS, CONCRETE | 17,081.000 | SFT |
| 88 | 731-93946 WALL ERECTION | 17,081.000 | SFT |
| 89 | 801-03290 CONSTRUCTION SIGN, C | 2.000 | EACH |
| 90 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 5.000 | EACH |
| 91 | 801-06625 DETOUR ROUTE MARKER ASSEMBLY | 26.000 | EACH |
| 92 | 801-06640 CONSTRUCTION SIGN, A | 11.000 | EACH |
| 93 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 94 | 801-07118 BARRICADE, III-A | 72.000 | LFT |
| 95 | 801-07119 BARRICADE, III-B | 48.000 | LFT |
| 96 | 802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE | 278.000 | LFT |
| 97 | 802-07060 SIGN, SHEET, RELOCATE | 5.000 | EACH |
| 98 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080 IN. | 76.000 | SFT |

CALL ORDER : 551

CONTRACT ID : B -30380-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | BRIDGE REPLACEMENT | | |
| 99 | 802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN | 9.000 | SFT |
| 100 | 808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR) | 1.000 | EACH |
| 101 | 808-05866 PAVEMENT MESSAGE MARKING, REMOVE | 17.000 | SYS |
| 102 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 50.000 | LFT |
| 103 | 808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN. | 278.000 | LFT |
| 104 | 808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN. | 155.000 | LFT |
| 105 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 2,575.000 | LFT |
| 106 | 808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN. | 42.000 | LFT |
| 107 | 808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION | 3.000 | EACH |

CALL ORDER : 611

CONTRACT ID : M -31149-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|------------------------------|----------|-------|
| SECTION NO. 0001 | ROADSIDE MAINTENANCE, MOWING | | |
| 1 109-08359 | LIQUIDATED DAMAGES | 1.000 | DOL |
| 2 109-08360 | CONTRACT LIENS | 1.000 | DOL |
| 3 623-04884 | MOWING, CYCLE NO. 1 | 1.000 | CYCL |
| 4 623-04885 | MOWING, CYCLE NO. 2 | 1.000 | CYCL |
| 5 623-04886 | MOWING, CYCLE NO. 3 | 1.000 | CYCL |
| 6 623-04887 | MOWING, CYCLE NO. 4 | 1.000 | CYCL |
| 7 623-05684 | MOWING, CYCLE NO. 5 | 1.000 | CYCL |
| 8 623-06704 | MOWING, CYCLE NO. 6 | 1.000 | CYCL |

CALL ORDER : 621

CONTRACT ID : M -31151-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|------------------------------|----------|-------|
| SECTION NO. 0001 | ROADSIDE MAINTENANCE, MOWING | | |
| 1 109-08359 | LIQUIDATED DAMAGES | 1.000 | DOL |
| 2 109-08360 | CONTRACT LIENS | 1.000 | DOL |
| 3 623-04884 | MOWING, CYCLE NO. 1 | 1.000 | CYCL |
| 4 623-04885 | MOWING, CYCLE NO. 2 | 1.000 | CYCL |
| 5 623-04886 | MOWING, CYCLE NO. 3 | 1.000 | CYCL |
| 6 623-04887 | MOWING, CYCLE NO. 4 | 1.000 | CYCL |
| 7 623-05684 | MOWING, CYCLE NO. 5 | 1.000 | CYCL |
| 8 623-06704 | MOWING, CYCLE NO. 6 | 1.000 | CYCL |

CALL ORDER : 631

CONTRACT ID : M -31155-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | ROADSIDE MAINTENANCE | | |
| 1 | 105-08520 CELLULAR TELEPHONE/RADIO | 2.000 | EACH |
| 2 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 4.000 | MOS |
| 3 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 4 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 5 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 6 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 7 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 8 | 624-92647 HERBICIDE TREATMENT | 6,241.000 | ACRE |
| 9 | 628-09408 MOBILE LAPTOP COMPUTER SYSTEM | 3.000 | MOS |
| 10 | 628-09409 MOBILE INTERNET SERVICE | 3.000 | MOS |
| 11 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |

CALL ORDER : 641

CONTRACT ID : M -32747-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | GUARDRAIL MAINTENANCE | | |
| 1 | 105-08520 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 2 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 12.000 | MOS |
| 3 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 4 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 5 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 6 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 7 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 8 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 9 | 601-01522 GUARDRAIL TRANSITION TYPE TGB | 2.000 | EACH |
| 10 | 601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING | 120.000 | LFT |
| 11 | 601-02212 GUARDRAIL POST, BRACKET, 8.5 LBS PER FT, GALVANIZED, | 200.000 | EACH |
| 12 | 601-03443 CAT UNIT FOUNDATION TUBE, MK ST WITH SOIL PLATES, MK SP | 5.000 | EACH |
| 13 | 601-03460 GUARDRAIL, CHANNEL 6.7 LBS PER LFT., LABOR ONLY | 2.000 | LFT |
| 14 | 601-03462 GUARDRAIL, POST STEEL, 8.5 LBS PER LFT, 7 FT. 0 IN. | 300.000 | EACH |
| 15 | 601-03599 GUARDRAIL, THRIE BEAM, RAIL SECTION, 12 FT. 6 IN | 100.000 | EACH |
| 16 | 601-03683 COMBINATION ATTENUATING TERMINAL, REPAIR, LABOR ONLY | 20.000 | HRS |
| 17 | 601-06247 IMPACT ATTENUATOR, R2, W2, TL-3 | 1.000 | EACH |
| 18 | 601-06773 ENERGY ABSORBING TERMINAL, B, SPARE PARTS PACKAGE | 2.000 | EACH |
| 19 | 601-61340 GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN. | 100.000 | EACH |
| 20 | 601-61350 GUARDRAIL POST BRACKET, 15.5 LBS PER LFT., GALVANIZED, | 50.000 | EACH |
| 21 | 601-61390 GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE, | 7.000 | EACH |
| 22 | 601-62530 GUARDRAIL PIER CONNECTION, ES | 1.000 | EACH |
| 23 | 601-62540 GUARDRAIL POST, PLUMB | 500.000 | EACH |
| 24 | 601-91428 GUARDRAIL ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN | 12.000 | EACH |
| 25 | 601-91432 GUARDRAIL ATTENUATING TERMINAL, SIDE PLATE, MKSD | 25.000 | EACH |
| 26 | 601-91504 GUARDRAIL POST, W1, 10 IN X 10 IN | 7.000 | EACH |
| 27 | 601-91505 GUARDRAIL POST, W2, 8 IN. X 8 IN. | 15.000 | EACH |
| 28 | 601-91542 GUARDRAIL BLOCK, 6 IN. X 8 IN., B1 | 200.000 | EACH |
| 29 | 601-91649 GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED | 5.000 | EACH |
| 30 | 601-91653 GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED | 5.000 | EACH |
| 31 | 601-94689 GUARDRAIL END TREATMENT, OS | 15.000 | EACH |
| 32 | 601-94690 GUARDRAIL END TREATMENT, MS | 5.000 | EACH |
| 33 | 601-95972 GUARDRAIL POST (CRT), 8 IN.X 6 IN.TREATED LUMBER, | 5.000 | EACH |
| 34 | 601-96591 GUARDRAIL PANEL, STEEL BEAM | 7,500.000 | LFT |
| 35 | 601-97950 GUARDRAIL POST BRACKET, TREATED TIMBER, 6 IN. X 6 IN. | 50.000 | EACH |
| 36 | 601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING | 300.000 | LFT |
| 37 | 628-09402 FIELD OFFICE, B | 12.000 | MOS |
| 38 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |

CALL ORDER : 701

CONTRACT ID : T -32506-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|----------|-------|
| SECTION NO. 0001 | NEW FLASHER INSTALLATION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 9.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL | 1.000 | DOL |
| 5 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 6 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 109-08463 PROJECT ESTIMATE ADJUSTMENT | 1.000 | DOL |
| 10 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 11 | 202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE | 2.000 | EACH |
| 12 | 628-09408 MOBILE LAPTOP COMPUTER SYSTEM | 8.000 | MOS |
| 13 | 628-09409 MOBILE INTERNET SERVICE | 8.000 | MOS |
| 14 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 15 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080 IN. | 16.000 | SFT |
| 16 | 805-01842 HANDHOLE, SIGNAL | 6.000 | EACH |
| 17 | 805-02645 SIGNAL PEDESTAL FOUNDATION, A | 2.000 | EACH |
| 18 | 805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN. | 265.000 | LFT |
| 19 | 805-06742 SOLAR POWERED FLASHING BEACON ASSEMBLY | 2.000 | EACH |
| 20 | 805-09451 SIGNAL PEDESTAL, 15 FT. | 2.000 | EACH |
| 21 | 805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE | 2.000 | EACH |
| 22 | 805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12" AMBER | 4.000 | EACH |
| 23 | 805-78445 SIGNAL SERVICE | 3.000 | EACH |
| 24 | 805-95466 FLASHING BEACON WITH SIGNAL AHEAD SIGN, 6 IN. I BEAM AND | 2.000 | EACH |
| 25 | 805-97042 SIGNAL POLE, WOOD, 5, 35 FT. | 1.000 | EACH |
| 26 | 807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC | 415.000 | LFT |

CALL ORDER : 711

CONTRACT ID : TM-32777-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNAL MAINTENANCE | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC | 1.000 | DOL |
| 5 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 6 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 7 | 202-90277 DETECTOR HOUSING, REMOVE | 1.000 | EACH |
| 8 | 801-03290 CONSTRUCTION SIGN, C | 8.000 | EACH |
| 9 | 801-06640 CONSTRUCTION SIGN, A | 22.000 | EACH |
| 10 | 801-06645 CONSTRUCTION SIGN, B | 4.000 | EACH |
| 11 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 12 | 805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN. | 130.000 | LFT |
| 13 | 805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA. | 1,000.000 | LFT |
| 14 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 870.000 | LFT |
| 15 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER | 400.000 | LFT |

