

CALL ORDER : 221

CONTRACT ID : IR-30851-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	6.000	EACH
3	105-08523 RADIO ONLY SERVICE	108.000	MOS
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	113-01614 PARTNERING OVERHEAD	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
17	203-02000 EXCAVATION, COMMON	277,654.000	CYS
18	203-02070 BORROW	56,136.000	CYS
19	204-08552 VIBRATING WIRE SETTLEMENT SYSTEM	1.000	EACH
20	204-08553 DATA LOGGING SYSTEM	1.000	EACH
21	204-08554 HAND HELD VW READOUT	1.000	EACH
22	205-03371 SEDIMENT, REMOVE	100.000	CYS
23	205-06930 SPLASHPAD, RIPRAP	108.000	TON
24	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,365.000	TON
25	205-06933 TEMP DITCH INLET PROTECTION	14.000	EACH
26	205-06936 TEMPORARY SEDIMENT TRAP	1,932.000	TON
27	205-06937 TEMPORARY SILT FENCE	24,712.000	LFT
28	205-06938 TEMPORARY SLOPE DRAIN	1,336.000	LFT
29	205-09543 NO 2 STONE	300.000	TON
30	206-51225 EXCAVATION, DRY	184.000	CYS
31	207-08262 SUBGRADE TREATMENT, TYPE I	159,090.000	SYS
32	207-08266 SUBGRADE TREATMENT, TYPE III	8,119.000	SYS
33	207-08267 SUBGRADE TREATMENT, TYPE IIIA	5,961.000	SYS
34	211-02050 B BORROW	38,616.000	CYS
35	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,039.000	CYS
36	211-09265 STRUCTURAL BACKFILL, TYPE 2	2,163.000	CYS
37	211-09266 STRUCTURAL BACKFILL, TYPE 3	21,035.000	CYS
38	215-07043 CHEMICAL MODIFICATION, SOILS	9,000.000	SYS
39	215-09385 CHEMICAL MODIFIER, SOILS, MODIFYING WET FILL SOIL,	5,000.000	TON
40	302-07455 DENSE GRADED SUBBASE	37.000	CYS
41	303-01180 COMPACTED AGGREGATE, NO. 53	48,164.000	TON
42	303-07449 COMPACTED AGGREGATE, NO. 73	1,854.000	TON
43	303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS	120.000	TON
44	304-07493 WIDENING WITH HMA, TYPE B	78.000	TON
45	306-08034 MILLING, ASPHALT, 1 1/2 IN	3,184.000	SYS
46	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
47	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	2,080.000	TON
48	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	9,741.000	TON
49	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	16,384.000	TON

CALL ORDER : 221

CONTRACT ID : IR-30851-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
50	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	5,586.000	TON
51	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	4,152.000	TON
52	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	2,060.000	TON
53	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	38,410.000	TON
54	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	16,542.000	TON
55	402-07432 HMA SURFACE, TYPE A	580.000	TON
56	402-07433 HMA SURFACE, TYPE B	1,661.000	TON
57	402-07434 HMA SURFACE, TYPE C	747.000	TON
58	402-07435 HMA INTERMEDIATE, TYPE A	612.000	TON
59	402-07438 HMA INTERMEDIATE, TYPE B	1,963.000	TON
60	402-07439 HMA INTERMEDIATE, TYPE C	722.000	TON
61	402-07441 HMA BASE, TYPE B	677.000	TON
62	402-07453 HMA FOR TEMPORARY PAVEMENT	677.000	TON
63	406-05520 ASPHALT FOR TACK COAT	142.000	TON
64	503-05240 D-1 CONTRACTION JOINT	2,585.000	LFT
65	601-01522 GUARDRAIL TRANSITION TYPE TGB	12.000	EACH
66	601-05999 CURVED TERMINAL END	4.000	EACH
67	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
68	601-06416 IMPACT ATTENUATOR SPARE PARTS PACKAGE, ED, W1, TL-3	2.000	EACH
69	601-06854 GUARDRAIL, W-BEAM, NESTED	4.000	EACH
70	601-94689 GUARDRAIL END TREATMENT, OS	12.000	EACH
71	601-94690 GUARDRAIL END TREATMENT, MS	4.000	EACH
72	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	1,700.000	LFT
73	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	912.500	LFT
74	602-06729 BARRIER DELINEATOR	128.000	EACH
75	603-06040 FENCE, FARM FIELD, 47 IN	32,194.000	LFT
76	606-07484 MILLED HMA SHOULDER CORRUGATIONS	47,687.000	LFT
77	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	2,772.000	LFT
78	608-09748 PREFABRICATED VERTICAL DRAIN	310,077.000	LFT
79	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	220.000	SYS
80	610-07486 HMA FOR APPROACHES, TYPE A	233.000	TON
81	610-07487 HMA FOR APPROACHES, TYPE B	108.000	TON
82	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
83	615-06490 RIGHT OF WAY MARKER	114.000	EACH
84	615-06505 MONUMENT, B	18.000	EACH
85	615-06510 MONUMENT, C	24.000	EACH
86	616-02320 GEOTEXTILES	1,044.000	SYS
87	616-06405 RIPRAP, REVETMENT	827.000	TON
88	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
89	621-06545 FERTILIZER	38.000	TON
90	621-06553 SEED MIXTURE, R	14,280.000	LBS
91	621-06557 SEED MIXTURE, T	3,360.000	LBS
92	621-06565 MULCHING MATERIAL	252.000	TON
93	621-06567 WATER	115.000	KGAL
94	621-06574 SODDING	31,469.000	SYS
95	621-06575 SODDING, NURSERY	444.000	SYS
96	622-05625 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT	20.000	EACH
97	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	17.000	EACH
98	622-52436 SIGN, DO NOT MOW OR SPRAY	9.000	EACH

CALL ORDER : 221

CONTRACT ID : IR-30851-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
99	622-91786 SEEDLING	784.000	EACH
100	628-09403 FIELD OFFICE, C	18.000	MOS
101	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	54.000	MOS
102	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
103	701-08253 PILE SLEEVES	14.000	EACH
104	701-09557 TEST PILE, DYNAMIC, PRODUCTION	160.000	LFT
105	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
106	701-09683 PILE SHOE, HP 12 X 74	70.000	EACH
107	701-09901 AGGREGATE PIER	LUMP	LUMP
108	701-95780 PILE, STEEL H, HP 12 IN X 74	4,130.000	LFT
109	702-51005 CONCRETE, A, SUBSTRUCTURE	252.900	CYS
110	702-51015 CONCRETE, B, FOOTINGS	70.000	CYS
111	702-92857 CONCRETE, C, SUBSTRUCTURE	217.000	CYS
112	703-06028 REINFORCING BARS	71,437.000	LBS
113	703-06029 REINFORCING BARS, EPOXY COATED	298,956.000	LBS
114	704-51002 CONCRETE, C, SUPERSTRUCTURE	539.900	CYS
115	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	8.000	EACH
116	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	5,104.000	SYS
117	706-09545 COARSE AGGREGATE, NO 8	1,278.000	CYS
118	706-51020 CONCRETE, C, RAILING	505.400	CYS
119	707-05997 STRUCTURAL MEMBERS, CONCRETE BULB-T	1,618.000	LFT
120	709-51821 SURFACE SEAL	LUMP	LUMP
121	714-01633 STRUCTURE, PRECAST, RC, BOX SECTION 9FT X 5FT	92.000	LFT
122	714-09868 STRUCTURE, PRECAST REINFORCED CONCRETE	288.000	LFT
123	714-09869 STRUCTURE, PRECAST REINFORCED CONCRETE	245.000	LFT
124	715-02399 SAFETY METAL END SECTION, 4:1, 42 IN	2.000	EACH
125	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN	396.000	LFT
126	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	57,596.000	LFT
127	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN	500.000	LFT
128	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN	500.000	LFT
129	715-05052 PIPE, TYPE 4, CIRCULAR, 12 IN	500.000	LFT
130	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	6,297.000	LFT
131	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN	86.000	LFT
132	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN	88.000	LFT
133	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN	140.000	LFT
134	715-05127 PIPE, TYPE 1, CIRCULAR, 42 IN	180.000	LFT
135	715-05133 PIPE, TYPE 1, CIRCULAR, 60 IN	233.000	LFT
136	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	1,480.000	LFT
137	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN	130.000	LFT
138	715-05213 PIPE, TYPE 4, CIRCULAR, 24 IN.	222.000	LFT
139	715-05252 PIPE, TYPE 1, DEFORMED, MIN AREA 20.5 SF	195.000	LFT
140	715-05841 CONCRETE ANCHOR, 60 IN	2.000	EACH
141	715-08303 CONCRETE ANCHOR, MIN AREA 20.5 SF	2.000	EACH
142	715-09064 VIDEO INSPECTION FOR PIPE	2,563.000	LFT
143	715-46000 PIPE END SECTION, 12 IN	8.000	EACH
144	715-46005 PIPE END SECTION, 15 IN	16.000	EACH
145	715-46010 PIPE END SECTION, 18 IN	2.000	EACH
146	715-46020 PIPE END SECTION, 24 IN	2.000	EACH
147	715-46040 PIPE END SECTION, 36 IN	4.000	EACH

CALL ORDER : 221

CONTRACT ID : IR-30851-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
148	718-06529 OUTLET PROTECTOR, 2	106.000	EACH
149	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	6,500.000	LFT
150	718-52610 AGGREGATE FOR UNDERDRAINS	5,219.000	CYS
151	718-99153 GEOTEXTILES FOR UNDERDRAIN	39,550.000	SYS
152	720-45070 INLET, P12A	14.000	EACH
153	731-07016 FACE PANELS, WIRE	2,365.000	SFT
154	731-93945 FACE PANELS, CONCRETE	24,083.000	SFT
155	731-93946 WALL ERECTION	26,448.000	SFT
156	731-93947 LEVELING PAD, CONCRETE	1,080.000	LFT
157	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	2.000	EACH
158	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
159	801-04308 ROAD CLOSURE SIGN ASSEMBLY	20.000	EACH
160	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	61,467.000	LFT
161	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,370.000	LFT
162	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	40.000	LFT
163	801-06586 TEMPORARY PAVEMENT MARKING, 8 IN	10,216.000	LFT
164	801-06625 DETOUR ROUTE MARKER ASSEMBLY	61.000	EACH
165	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
166	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
167	801-07118 BARRICADE, III-A	360.000	LFT
168	801-07119 BARRICADE, III-B	144.000	LFT
169	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	1,792.000	LFT
170	801-52817 TEMPORARY CROSSOVER, B	1.000	EACH
171	801-52818 TEMPORARY CROSSOVER, A	2.000	EACH
172	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	910.000	LFT
173	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	85.320	SFT
174	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	498.480	SFT
175	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN	274.000	LFT
176	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN	2,026.000	LFT
177	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN	2,026.000	LFT
178	808-06694 LINE, PAINT, SOLID, YELLOW, 8 IN	4,213.000	LFT
179	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	6,927.000	LFT
180	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	32,291.000	LFT
181	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	2,555.000	LFT
182	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	2,357.000	LFT
183	808-06716 LINE, REMOVE	71,903.000	LFT
184	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN	3,985.000	LFT
185	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	34,445.000	LFT
186	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	219.000	LFT
187	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	10.000	EACH
188	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	10.000	EACH
189	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	457.000	EACH

CALL ORDER : 235

CONTRACT ID : IR-31091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	104-05404 DESIGN/BUILD	LUMP	LUMP
2	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	17,162.000	SYS
14	202-02271 HEADWALL, REMOVE	2.000	EACH
15	202-02278 CURB, CONCRETE, REMOVE	20,651.000	LFT
16	202-02637 PIPE, ABANDON AND GROUT FILL	200.000	LFT
17	202-05555 REGULATED MATERIALS, TRANSPORT, C	400.000	CYS
18	202-05826 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE,	4.000	EACH
19	202-06580 CONTAMINATED SOIL, REMOVE	400.000	CYS
20	202-07603 TESTING FOR WASTE, C	8.000	EACH
21	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
22	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
23	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
24	202-52710 SIDEWALK, CONCRETE, REMOVE	3,381.000	SYS
25	202-91385 INLET, REMOVE	40.000	EACH
26	202-93047 MANHOLE, REMOVE	19.000	EACH
27	202-93741 GUARDRAIL END TREATMENT, REMOVE	4.000	EACH
28	202-94954 BARRIER WALL, CONCRETE, REMOVE	300.000	LFT
29	202-96133 PIPE, REMOVE	585.000	LFT
30	203-02000 EXCAVATION, COMMON	245,015.000	CYS
31	203-02070 BORROW	2,478.000	CYS
32	203-03089 CLAY LINER	5,040.000	CYS
33	203-51223 EXCAVATION, WATERWAY	570.000	CYS
34	205-06933 TEMP DITCH INLET PROTECTION	11.000	EACH
35	205-06937 TEMPORARY SILT FENCE	12,900.000	LFT
36	205-09543 NO 2 STONE	100.000	TON
37	206-51225 EXCAVATION, DRY	8,298.000	CYS
38	206-51817 SHEET PILING, STEEL	9,956.000	SFT
39	206-51817 SHEET PILING, STEEL	1,377.000	SFT
40	207-08262 SUBGRADE TREATMENT, TYPE I	103,096.000	SYS
41	207-08264 SUBGRADE TREATMENT, TYPE II	56,762.000	SYS
42	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,588.000	SYS
43	210-07805 WATERSTOP	216.000	LFT
44	210-09827 VEGETATED	788.000	LFT
45	210-09828 GROUNDWATER	3.000	EACH
46	210-09828 GROUNDWATER	1.000	EACH
47	210-09829 OBSERVATION	1.000	EACH
48	210-09830 SUBMERSIBLE	4.000	EACH
49	211-02050 B BORROW	2,076.000	CYS

CALL ORDER : 235

CONTRACT ID : IR-31091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	211-09264 STRUCTURAL BACKFILL, TYPE 1	27,246.000	CYS
51	211-09265 STRUCTURAL BACKFILL, TYPE 2	528.000	CYS
52	211-09266 STRUCTURAL BACKFILL, TYPE 3	13,813.000	CYS
53	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	22,185.500	TON
54	303-01180 COMPACTED AGGREGATE, NO. 53	11,300.000	TON
55	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	7,591.000	TON
56	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	12,639.000	TON
57	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	20,214.000	TON
58	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	13,718.000	TON
59	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	16,255.000	TON
60	402-07432 HMA SURFACE, TYPE A	4,726.000	TON
61	402-07435 HMA INTERMEDIATE, TYPE A	12,222.000	TON
62	406-05520 ASPHALT FOR TACK COAT	112.300	TON
63	601-02241 GUARDRAIL, REMOVE	1,123.000	LFT
64	601-02800 GUARDRAIL TRANSITION, TGT	1.000	EACH
65	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	4.000	EACH
66	601-06417 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R1, W1, TL-2	8.000	EACH
67	601-06421 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R1, W1, TL-3	1.000	EACH
68	601-06454 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R2, W1, TL-3	4.000	EACH
69	601-07009 IMPACT ATTENUATOR, LS, W1, TL-1	2.000	EACH
70	601-07589 IMPACT ATTENUATOR SPARE PARTS PACKAGE, LS, W1, TL-1	2.000	EACH
71	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
72	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
73	601-09146 IMPACT ATTENUATOR, CRL, W1, TL-2	8.000	EACH
74	601-09149 IMPACT ATTENUATOR, CRL, W1, TL-3	1.000	EACH
75	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
76	601-95344 HANDRAIL, PEDESTRIAN	50.000	LFT
77	601-95434 HANDRAIL, STEEL PIPE, 1.5"	16.000	LFT
78	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	967.500	LFT
79	602-02098 MEDIAN BARRIER RAIL TRANSITION	2.000	EACH
80	602-06729 BARRIER DELINEATOR	53.000	EACH
81	602-08605 CONCRETE BARRIER, 33 IN	653.000	LFT
82	603-01932 FENCE, CHAIN LINK, 96 IN	2,953.000	LFT
83	603-02009 FENCE GATE, CHAIN LINK, 96 IN X 20 FT	2.000	EACH
84	603-06045 FENCE, CHAIN LINK, 48 IN	9,015.000	LFT
85	603-92636 FENCE, CHAIN LINK, 72 IN	347.000	LFT
86	603-97283 FENCE GATE, CHAIN LINK, 48 IN X 24 FT	2.000	EACH
87	604-07897 CURB RAMP, CONCRETE, C	95.000	SYS
88	604-07900 CURB RAMP, CONCRETE, F	30.000	SYS
89	604-07901 CURB RAMP, CONCRETE, G	170.000	SYS
90	604-07902 CURB RAMP, CONCRETE, H	65.000	SYS
91	604-91531 SIDEWALK, CONCRETE, 4 IN	7,890.000	SYS
92	605-06090 CURB, INTEGRAL, CONCRETE	765.000	LFT
93	605-06145 CURB AND GUTTER, B, CONCRETE	10,860.000	LFT
94	605-06150 CURB AND GUTTER, C, CONCRETE	12,275.000	LFT
95	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	12,165.000	LFT
96	605-06160 CURB AND GUTTER, B, CONCRETE, MODIFIED	4,525.000	LFT
97	605-06165 CURB AND GUTTER, C, CONCRETE, MODIFIED	665.000	LFT
98	605-06245 CENTER CURB, B, CONCRETE	403.000	SYS

CALL ORDER : 235

CONTRACT ID : IR-31091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
99	605-06250 CENTER CURB, C, CONCRETE	936.000	SYS
100	605-97937 CURB AND GUTTER, CONCRETE, ROLL	46.000	LFT
101	610-08446 PCCP FOR APPROACHES, 6 IN	1,243.000	SYS
102	610-09108 PCCP FOR APPROACHES, 9 IN	2,345.000	SYS
103	611-06497 MAILBOX ASSEMBLY, SINGLE	4.000	EACH
104	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
105	615-06490 RIGHT OF WAY MARKER	160.000	EACH
106	615-06496 PARKING BARRIER	33.000	EACH
107	615-06505 MONUMENT, B	49.000	EACH
108	615-06510 MONUMENT, C	9.000	EACH
109	615-06527 MONUMENT, SECTION CORNER	6.000	EACH
110	616-02320 GEOTEXTILES	3,401.000	SYS
111	616-05688 RIPRAP, CLASS 1	1,585.000	TON
112	616-06405 RIPRAP, REVETMENT	1,288.000	TON
113	616-06451 RIPRAP, UNIFORM	133.000	TON
114	617-08121 EXPANSION JOINT	216.000	LFT
115	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.000	EACH
116	621-02770 EROSION CONTROL BLANKET	5,129.000	SYS
117	621-06545 FERTILIZER	16.200	TON
118	621-06553 SEED MIXTURE, R	524.000	LBS
119	621-06554 SEED MIXTURE, U	4,635.000	LBS
120	621-06557 SEED MIXTURE, T	1,490.000	LBS
121	621-06565 MULCHING MATERIAL	108.000	TON
122	621-06574 SODDING	17,587.000	SYS
123	621-06575 SODDING, NURSERY	8,646.000	SYS
124	621-07109 WATER PUMPING	LUMP	LUMP
125	621-08161 PERMANENT TURF REINFORCEMENT MAT	1,384.000	SYS
126	621-09398 SEED MIXTURE, SLOPE STABILIZATION	66.000	LBS
127	621-09399 SEED MIXTURE, WET MESIC	32.000	LBS
128	622-05641 PLANT, DECIDUOUS SHRUB, 36 TO 48 IN	70.000	EACH
129	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	143.000	EACH
130	622-05654 PLANT, PERENNIAL	12,000.000	EACH
131	622-52436 SIGN, DO NOT MOW OR SPRAY	11.000	EACH
132	628-09403 FIELD OFFICE, C	24.000	MOS
133	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
134	701-08122 PILE, CONCRETE, STEEL SHELL, ENCASED, 0375 IN, 14 IN	11,576.000	LFT
135	701-09557 TEST PILE, DYNAMIC, PRODUCTION	316.000	LFT
136	701-09559 TEST PILE, DYNAMIC, RESTRIKE	4.000	EACH
137	702-02925 WATERPROOFING MEMBRANE SYSTEM	11,131.000	SFT
138	702-51005 CONCRETE, A, SUBSTRUCTURE	1,002.300	CYS
139	702-51015 CONCRETE, B, FOOTINGS	809.300	CYS
140	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	1,805.000	LBS
141	702-90915 CONCRETE, CLASS A	438.000	CYS
142	703-06029 REINFORCING BARS, EPOXY COATED	254,712.000	LBS
143	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	265.000	EACH
144	704-51002 CONCRETE, C, SUPERSTRUCTURE	416.000	CYS
145	706-09545 COARSE AGGREGATE, NO 8	4.000	CYS
146	709-51821 SURFACE SEAL	LUMP	LUMP
147	711-04121 ANCHOR BOLT, AB1	252.000	EACH

CALL ORDER : 235

CONTRACT ID : IR-31091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
148	711-51035 STRUCTURAL STEEL	909,260.000	LBS
149	712-04272 LUMBER AND TIMBER, UNTREATED	0.800	MFBM
150	712-05097 METAL PARTS	175.000	LBS
151	712-06386 PLANK FLOORS, SINGLE PLY	10,476.000	SFT
152	712-95676 LUMBER AND TIMBER, TREATED	0.900	MFBM
153	714-06277 STRUCTURE, PRECAST, RC, BOX SECTION 14FT X 8	134.000	LFT
154	714-08514 WINGWALL	1,306.000	SFT
155	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN	2.000	EACH
156	715-04611 SAFETY METAL END SECTION, 4:1, 12 IN	1.000	EACH
157	715-04612 PIPE	125.000	LFT
158	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN	398.000	LFT
159	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	36,051.000	LFT
160	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	1,877.000	LFT
161	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN	420.000	LFT
162	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN	60.000	LFT
163	715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN	282.000	LFT
164	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	10,931.000	LFT
165	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	8,888.000	LFT
166	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	3,454.000	LFT
167	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN	3,806.000	LFT
168	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN	1,351.000	LFT
169	715-05159 PIPE, TYPE 2, CIRCULAR, 42 IN	847.000	LFT
170	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN	743.000	LFT
171	715-05162 PIPE, TYPE 2, CIRCULAR, 54 IN	1,341.000	LFT
172	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	169.000	LFT
173	715-05415 PIPE, SANITARY SEWER, 24 IN	59.000	LFT
174	715-05422 PIPE, SLOTTED DRAIN, 12 IN	135.000	LFT
175	715-05712 PIPE, SANITARY SEWER, 16 IN.	125.000	LFT
176	715-06004 CONCRETE ANCHOR, 48 IN	1.000	EACH
177	715-06492 CONCRETE ANCHOR, 54 IN	1.000	EACH
178	715-07073 WATER LINE	312.000	LFT
179	715-07794 WATER MAIN CONNECTIONS	2.000	EACH
180	715-08282 HMA FOR STRUCTURE INSTALLATION, TYPE A	45.000	TON
181	715-09064 VIDEO INSPECTION FOR PIPE	31,959.000	LFT
182	715-46005 PIPE END SECTION, 15 IN	13.000	EACH
183	715-46010 PIPE END SECTION, 18 IN	3.000	EACH
184	715-46020 PIPE END SECTION, 24 IN	1.000	EACH
185	715-46030 PIPE END SECTION, 30 IN	1.000	EACH
186	715-90052 LIFT STATION	LUMP	LUMP
187	715-91361 PIPE, PVC, 6 IN	1,408.000	LFT
188	715-92037 PIPE, PVC, 4 IN	711.000	LFT
189	715-98165 WATER MAIN, 12 IN	446.000	LFT
190	715-98961 FORCE MAIN	307.000	LFT
191	715-98961 FORCE MAIN	308.000	LFT
192	716-07630 PIPE INSTALLATION, TRENCHLESS, 12 IN	809.000	LFT
193	716-09334 PIPE INSTALLATION, TRENCHLESS, 16 IN	809.000	LFT
194	718-06529 OUTLET PROTECTOR, 2	4.000	EACH
195	718-06531 OUTLET PROTECTOR, 3	2.000	EACH
196	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	6,500.000	LFT



CALL ORDER : 235

CONTRACT ID : IR-31091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
197	718-52610 AGGREGATE FOR UNDERDRAINS	2,665.000	CYS
198	718-99153 GEOTEXTILES FOR UNDERDRAIN	35,495.000	SYS
199	720-07299 INLET, H	3.000	EACH
200	720-07300 INLET, TYPE H, WITH SLOTTED DRAIN	6.000	EACH
201	720-07301 INLET, TYPE HA	4.000	EACH
202	720-07302 INLET, TYPE HA, WITH SLOTTED DRAIN	15.000	EACH
203	720-08559 BEST MANAGEMENT PRACTICES	10.000	EACH
204	720-08628 SLOTTED DRAIN PIPE CLEANOUT PORT, TYPE II	1.000	EACH
205	720-09079 INLET, HA5, MODIFIED	28.000	EACH
206	720-09768 CATCH BASIN TYPE HA5	69.000	EACH
207	720-44000 CASTING, ADJUST TO GRADE	26.000	EACH
208	720-45040 INLET, G7	2.000	EACH
209	720-45045 INLET, J10	43.000	EACH
210	720-45055 INLET, M10	28.000	EACH
211	720-45135 INLET, F7, MODIFIED	11.000	EACH
212	720-45235 CATCH BASIN, E7	42.000	EACH
213	720-45240 CATCH BASIN, J10	1.000	EACH
214	720-45250 CATCH BASIN, K10	1.000	EACH
215	720-45410 MANHOLE, C4	189.000	EACH
216	720-91352 CATCH BASIN, F7	1.000	EACH
217	720-91973 MANHOLE, H4	12.000	EACH
218	720-93501 MANHOLE, L4	12.000	EACH
219	720-94612 MANHOLE, K4	15.000	EACH
220	720-94612 MANHOLE, K4	2.000	EACH
221	720-95422 MANHOLE, J4	3.000	EACH
222	720-98174 INLET, B15	36.000	EACH
223	720-98555 INLET, C15	12.000	EACH
224	720-98687 CATCH BASIN, M10	34.000	EACH
225	720-99416 CATCH BASIN, B15	27.000	EACH
226	720-99417 CATCH BASIN, C15	36.000	EACH
227	721-43020 AUTOMATIC DRAINAGE GATE, 24"	1.000	EACH
228	721-43115 AUTOMATIC DRAINAGE GATE, 30 IN X 30 IN	1.000	EACH
229	721-43155 AUTOMATIC DRAINAGE GATE, 48 IN x 48 IN	1.000	EACH
230	723-06927 STRUCTURE, PRECAST THREE-SIDED,	76.000	LFT
231	723-06927 STRUCTURE, PRECAST THREE-SIDED,	82.000	LFT
232	731-93945 FACE PANELS, CONCRETE	14,025.000	SFT
233	731-93946 WALL ERECTION	14,025.000	SFT
234	731-93947 LEVELING PAD, CONCRETE	813.000	LFT
235	732-09202 VALVE WITH BOX, RESTRAINED, GATE,	2.000	EACH
236	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	64.000	EACH
237	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
238	801-04308 ROAD CLOSURE SIGN ASSEMBLY	11.000	EACH
239	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	147,008.100	LFT
240	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	791.000	LFT
241	801-06625 DETOUR ROUTE MARKER ASSEMBLY	52.000	EACH
242	801-06640 CONSTRUCTION SIGN, A	78.000	EACH
243	801-06710 FLASHING ARROW SIGN	300.000	DAY
244	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
245	801-07118 BARRICADE, III-A	1,573.000	LFT

CALL ORDER : 235

CONTRACT ID : IR-31091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
246	801-07119 BARRICADE, III-B	216.000	LFT
247	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	5,522.000	LFT
248	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	602.500	LFT
249	802-09837 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.080 IN	14.750	SFT
250	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	463.980	SFT
251	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN	32.870	SFT
252	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	207.000	SFT
253	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN	36.000	SFT
254	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.000	EACH
255	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	8.000	EACH
256	805-01842 HANDHOLE, SIGNAL	34.000	EACH
257	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
258	805-02150 PEDESTRIAN SIGNAL HEAD, 18 IN	10.000	EACH
259	805-02373 SIGNAL INTERCONNECT CABLE, FIBER OPTIC	4,135.000	LFT
260	805-09471 SIGNAL CABLE, PREFORMED PAVE-OVER LOOP	121.000	EACH
261	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000	EACH
262	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
263	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	15.000	EACH
264	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	15.000	EACH
265	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	7.000	EACH
266	805-78370 PEDESTRIAN PUSH BUTTON	10.000	EACH
267	805-78415 SPAN, CATENARY, AND TETHER	10.000	EACH
268	805-78420 DISCONNECT HANGER	7.000	EACH
269	805-78445 SIGNAL SERVICE	2.000	EACH
270	805-78467 SIGNAL CABLE, 3C 8GA	300.000	LFT
271	805-78480 SIGNAL CABLE, 3C 14GA	1,910.000	LFT
272	805-78485 SIGNAL CABLE, 5C 14GA	4,065.000	LFT
273	805-78490 SIGNAL CABLE, 7C 14GA	3,170.000	LFT
274	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	17,960.000	LFT
275	805-78925 CONTROLLER CABINET FOUNDATION, P1	2.000	EACH
276	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT	8.000	EACH
277	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHAN	35.000	EACH
278	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	7,050.000	LFT
279	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	3,998.000	LFT
280	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	17,197.000	LFT
281	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	1,323.000	LFT
282	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN	183.000	LFT
283	808-75043 LINE THERMOPLASTIC, SOLID, WHITE, 6 IN	2,444.000	LFT
284	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	388.000	LFT
285	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	26,219.000	LFT
286	808-75260 TRANSVERSE MARKING THERMOPLASTIC, SOLID,	1,389.000	LFT
287	808-75278 TRANSVERSE MARKING, THERMOPLASTIC, SOLID, YELLOW,	88.000	LFT
288	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	801.000	LFT
289	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	48.000	EACH
290	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	33.000	EACH
291	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	62.000	EACH
292	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	303.000	EACH
293	808-92027 LINE, THERMO, SOLID, YELLOW, 8 IN	5,107.000	LFT
294	808-97664 PAVEMENT MESSAGE MARKING THERMOPLASTIC, HANDICAP SYMBOL	3.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 235

CONTRACT ID : IR-31091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
295 808-98796	LINE, THERMOPLASTIC DOTTED WHITE, 4 IN, 2FT LINE, 4FT GAP	1,133.000	LFT

CALL ORDER : 241

CONTRACT ID : IR-31909-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HOUSES AND BUILDINGS, REMOVE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
7	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
8	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
9	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
11	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
12	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
13	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
14	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
19	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
20	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
21	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
22	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
23	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
24	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
25	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
26	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
27	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
28	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
29	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	322.000	SFT
30	205-04948 TEMPORARY CONSTRUCTION ENTRANCE/EXIT	LUMP	LUMP
31	205-06933 TEMP DITCH INLET PROTECTION	2.000	EACH
32	205-06937 TEMPORARY SILT FENCE	5,240.000	LFT
33	621-06560 MULCHED SEEDING, U	24,581.000	SYS
34	628-09401 FIELD OFFICE, A	4.000	MOS
35	732-09111 SERVICE	23.000	EACH
36	732-09111 SERVICE	23.000	EACH
37	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
38	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
39	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 301

CONTRACT ID : IR-32982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENVIRONMENTAL MITIGATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	203-09334 BACKFILL, ROCK	546.000	TON
6	203-09334 BACKFILL, ROCK	106.000	TON
7	205-03371 SEDIMENT, REMOVE	100.000	CYS
8	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	48.000	TON
9	205-06935 TEMPORARY SEDIMENT BASIN	1.000	EACH
10	205-06937 TEMPORARY SILT FENCE	1,800.000	LFT
11	206-51220 EXCAVATION, WET	1,365.000	CYS
12	211-09265 STRUCTURAL BACKFILL, TYPE 2	30.000	CYS
13	212-06282 STOCKPILED SELECTED MATERIAL, SALVAGED	30.000	CYS
14	616-02320 GEOTEXTILES	81.000	SYS
15	621-02318 SEED MIXTURE, PRAIRIE GRASS	74.500	LBS
16	621-02770 EROSION CONTROL BLANKET	2,167.000	SYS
17	621-09400 SEED MIXTURE, SEDGE MEADOW	13.700	LBS
18	622-05654 PLANT, PERENNIAL	1,300.000	EACH
19	622-52436 SIGN, DO NOT MOW OR SPRAY	7.000	EACH
20	622-91786 SEEDLING	75.000	EACH
21	622-91786 SEEDLING	20.000	EACH
22	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	8.000	MOS
23	628-09409 MOBILE INTERNET SERVICE	8.000	MOS
24	712-04784 STRUCTURE	1.000	EACH
25	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN	210.000	LFT
26	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	20.000	LFT
27	715-05177 PIPE, TYPE 3, CIRCULAR, 36 IN	36.000	LFT
28	715-05442 PIPE, DRAIN TILE TERMINAL SECTION, 10 IN	20.000	LFT
29	715-46040 PIPE END SECTION, 36 IN	2.000	EACH
30	802-04314 SIGN	1.000	EACH

CALL ORDER : 311

CONTRACT ID : IR-33070-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	3.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
11	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	300.000	SFT
12	205-06937 TEMPORARY SILT FENCE	200.000	LFT
13	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
14	621-06559 MULCHED SEEDING, R	1,000.000	SYS
15	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
16	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
17	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
18	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 371

CONTRACT ID : R -30881-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-91385 INLET, REMOVE	2.000	EACH
12	203-02000 EXCAVATION, COMMON	614.000	CYS
13	203-02070 BORROW	263.000	CYS
14	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	18.000	EACH
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	27.000	TON
16	205-06937 TEMPORARY SILT FENCE	1,919.000	LFT
17	205-09543 NO 2 STONE	100.000	TON
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,287.000	SYS
19	211-09265 STRUCTURAL BACKFILL, TYPE 2	94.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	16.000	TON
21	303-01180 COMPACTED AGGREGATE, NO. 53	97.000	TON
22	303-07449 COMPACTED AGGREGATE, NO. 73	15.000	TON
23	304-07490 HMA PATCHING, TYPE B	29.000	TON
24	306-08033 MILLING, ASPHALT, 1 IN	171.000	SYS
25	506-06333 PCCP PATCHING, FULL DEPTH	29.000	SYS
26	604-07894 CURB RAMP, CONCRETE, A	20.000	SYS
27	604-07901 CURB RAMP, CONCRETE, G	46.000	SYS
28	604-07902 CURB RAMP, CONCRETE, H	4.000	SYS
29	604-07903 CURB RAMP, CONCRETE, K	12.000	SYS
30	604-07903 CURB RAMP, CONCRETE, K	24.000	SYS
31	604-90256 SIDEWALK, CONCRETE, 6 IN	48.000	SYS
32	604-91531 SIDEWALK, CONCRETE, 4 IN	2,762.000	SYS
33	605-06095 CURB, INTEGRAL, B, CONCRETE	86.000	LFT
34	605-06120 CURB, CONCRETE	15.000	LFT
35	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	379.000	LFT
36	610-07487 HMA FOR APPROACHES, TYPE B	66.000	TON
37	610-08446 PCCP FOR APPROACHES, 6 IN	1,099.000	SYS
38	610-09108 PCCP FOR APPROACHES, 9 IN	110.000	SYS
39	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	39.000	EACH
40	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
41	621-06545 FERTILIZER	0.410	TON
42	621-06554 SEED MIXTURE, U	151.000	LBS
43	621-06565 MULCHING MATERIAL	2.000	TON
44	628-09401 FIELD OFFICE, A	6.000	MOS
45	702-03607 CORED HOLE IN CONCRETE	6.000	EACH
46	714-44240 CONCRETE, A, STRUCTURES	0.200	CYS
47	715-04611 SAFETY METAL END SECTION, 4:1, 12 IN	5.000	EACH
48	715-05147 PIPE, TYPE 2, CIRCULAR, 8 IN	30.000	LFT
49	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	316.000	LFT

CALL ORDER : 371

CONTRACT ID : R -30881-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
50	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN	356.000	LFT
51	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	73.000	TON
52	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	4.000	EACH
53	720-04682 INLET	2.000	EACH
54	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
55	720-45045 INLET, J10	2.000	EACH
56	720-45260 PIPE CATCH BASIN, 12 IN	1.000	EACH
57	720-45270 PIPE CATCH BASIN, 18 IN	4.000	EACH
58	720-45615 STRUCTURE, INLET, RECONSTRUCTED	1.000	LFT
59	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
60	801-06640 CONSTRUCTION SIGN, A	25.000	EACH
61	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
62	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
63	802-07060 SIGN, SHEET, RELOCATE	10.000	EACH
64	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	12.500	SFT
65	802-76055 SIGN POST, A	24.000	LFT
66	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	2.000	EACH
67	805-78370 PEDESTRIAN PUSH BUTTON	2.000	EACH
68	805-78412 SIGNAL PEDESTAL, 9FT	1.000	EACH
69	805-78485 SIGNAL CABLE, 5C 14GA	470.000	LFT
70	805-78900 PEDESTAL FOUNDATION, A	1.000	EACH
71	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	30.000	LFT
72	808-03439 TRANSVERSE MARKING THERMOPLASTIC	140.000	LFT
73	808-09506 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC,	12.000	EACH
74	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	25.000	LFT



CALL ORDER : 461

CONTRACT ID : R -32105-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	303-07449 COMPACTED AGGREGATE, NO. 73	2,900.000	TON
13	304-07491 HMA PATCHING, TYPE C	1,000.000	TON
14	306-08042 MILLING, SCARIFICATION/PROFILE	35,325.000	SYS
15	306-08043 MILLING, TRANSITION	3,300.000	SYS
16	306-08432 MILLING, APPROACH	19,250.000	SYS
17	306-08595 MILLING ASPHALT, 3 1/2 IN	66,652.000	SYS
18	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
19	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,050.000	TON
20	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	5,500.000	TON
21	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,800.000	TON
22	401-07399 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	11,000.000	TON
23	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	11,000.000	TON
24	406-05520 ASPHALT FOR TACK COAT	70.000	TON
25	610-07488 HMA FOR APPROACHES, TYPE C	3,000.000	TON
26	615-06520 MONUMENT, RE-ESTABLISH	5.000	EACH
27	628-09402 FIELD OFFICE, B	6.000	MOS
28	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	16.000	MOS
29	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
30	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
31	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,500.000	LFT
32	801-06209 TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN	1,500.000	LFT
33	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
34	801-06710 FLASHING ARROW SIGN	50.000	DAY
35	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
36	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	4.000	EACH
37	805-02441 SIGNAL CABLE, ROADWAY LOOP, 1C 14 GA.	990.000	LFT
38	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	330.000	LFT
39	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	3.000	EACH
40	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	45,623.000	LFT
41	808-75043 LINE THERMOPLASTIC, SOLID, WHITE, 6 IN	403.000	LFT
42	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	3,291.000	LFT
43	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,517.000	LFT
44	808-75260 TRANSVERSE MARKING THERMOPLASTIC, SOLID,	236.000	LFT
45	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	92.000	LFT
46	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	4.000	EACH
47	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	4.000	EACH
48	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	677.000	EACH
49	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	677.000	EACH

CALL ORDER : 481

CONTRACT ID : R -32582-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING ENHANCEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-07846 TREE	10.000	EACH
9	205-02459 EROSION CONTROL	LUMP	LUMP
10	621-06570 TOPSOIL	4.000	CYS
11	621-06575 SODDING, NURSERY	20.000	SYS
12	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	14.000	MOS
13	628-09409 MOBILE INTERNET SERVICE	14.000	MOS
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
15	807-02191 HANDHOLE, LIGHTING	3.000	EACH
16	807-03802 LIGHT STANDARDS	71.000	EACH
17	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	890.000	LFT
18	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	9,340.000	LFT
19	807-86805 SERVICE POINT, I	1.000	EACH
20	807-86810 SERVICE POINT, II	2.000	EACH
21	807-86838 WIRE, NO. 4 COPPER IN CONDUIT, 1C	43,880.000	LFT
22	807-86910 CONNECTOR KIT, UNFUSED	71.000	EACH
23	807-86915 CONNECTOR KIT, FUSED	71.000	EACH
24	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	186.000	EACH
25	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	10.000	EACH
26	807-86930 INSULATION LINK, NON-WATERPROOFED	151.000	EACH
27	807-86935 INSULATION LINK, WATERPROOFED	16.000	EACH
28	807-86950 SIGN UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	71.000	EACH
29	807-95889 WIRE, NO. 10 COPPER, 1C	7,100.000	LFT
30	807-03950 LUMINAIRE, ORNAMENTAL	71.000	EACH
31	807-03950 LUMINAIRE, ORNAMENTAL	71.000	EACH
32	807-03950 LUMINAIRE, ORNAMENTAL	71.000	EACH
33	807-03802 LIGHT STANDARDS	71.000	EACH
34	807-03802 LIGHT STANDARDS	71.000	EACH

CALL ORDER : 531

CONTRACT ID : R -33098-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-93615 CONCRETE, REMOVE	245.900	SYS
13	202-93741 GUARDRAIL END TREATMENT, REMOVE	2.000	EACH
14	202-99080 CONCRETE, REMOVE	10.800	CYS
15	203-02000 EXCAVATION, COMMON	9,372.100	CYS
16	203-02070 BORROW	27.000	CYS
17	205-03371 SEDIMENT, REMOVE	10.000	CYS
18	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	100.000	TON
19	205-06934 TEMPORARY MULCHING	5.000	TON
20	205-06937 TEMPORARY SILT FENCE	6,000.000	LFT
21	207-08263 SUBGRADE TREATMENT, TYPE IA	13,100.000	SYS
22	211-09265 STRUCTURAL BACKFILL, TYPE 2	121.500	CYS
23	215-07043 CHEMICAL MODIFICATION, SOILS	13,100.000	SYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,832.700	TON
25	302-07455 DENSE GRADED SUBBASE	42.900	CYS
26	303-01180 COMPACTED AGGREGATE, NO. 53	1,204.100	TON
27	303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS	200.000	TON
28	304-07493 WIDENING WITH HMA, TYPE B	25.600	TON
29	306-08034 MILLING, ASPHALT, 1 1/2 IN	729.800	SYS
30	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
31	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	482.900	TON
32	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	627.300	TON
33	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	936.700	TON
34	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	1,374.600	TON
35	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	2,317.100	TON
36	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	1,018.200	TON
37	406-05520 ASPHALT FOR TACK COAT	13.600	TON
38	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
39	601-06035 GUARDRAIL, RESET	724.000	LFT
40	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
41	602-06729 BARRIER DELINEATOR	30.000	EACH
42	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	245.900	SYS
43	610-07487 HMA FOR APPROACHES, TYPE B	20.000	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
45	621-06545 FERTILIZER	1.000	TON
46	621-06553 SEED MIXTURE, R	340.000	LBS
47	621-06565 MULCHING MATERIAL	4.000	TON
48	628-09402 FIELD OFFICE, B	12.000	MOS
49	703-51032 REINFORCING STEEL, EPOXY COATED	12,181.800	LBS

CALL ORDER : 531

CONTRACT ID : R -33098-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
51	709-51821 SURFACE SEAL	LUMP	LUMP
52	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	4,968.000	LFT
53	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	780.000	LFT
54	718-06529 OUTLET PROTECTOR, 2	13.000	EACH
55	718-06531 OUTLET PROTECTOR, 3	3.000	EACH
56	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
57	718-52610 AGGREGATE FOR UNDERDRAINS	431.000	CYS
58	718-99153 GEOTEXTILES FOR UNDERDRAIN	3,794.000	SYS
59	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	88.000	LFT
60	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
61	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
62	801-06209 TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN	276.000	LFT
63	801-06625 DETOUR ROUTE MARKER ASSEMBLY	45.000	EACH
64	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
65	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
66	801-07118 BARRICADE, III-A	48.000	LFT
67	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	2.000	EACH
68	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	172.000	LFT
69	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	6,500.000	LFT
70	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	5,814.000	LFT
71	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	71.000	EACH
72	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	71.000	EACH

CALL ORDER : 581

CONTRACT ID : RS-30521-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-93741 GUARDRAIL END TREATMENT, REMOVE	4.000	EACH
13	203-02000 EXCAVATION, COMMON	35.000	CYS
14	203-08607 LINEAR GRADING	200.000	LFT
15	211-09264 STRUCTURAL BACKFILL, TYPE 1	220.000	CYS
16	303-07449 COMPACTED AGGREGATE, NO. 73	5,350.000	TON
17	304-07490 HMA PATCHING, TYPE B	100.000	TON
18	306-08036 MILLING, ASPHALT, 2 IN	105,815.000	SYS
19	306-08042 MILLING, SCARIFICATION/PROFILE	32,155.000	SYS
20	306-08043 MILLING, TRANSITION	590.000	SYS
21	306-08432 MILLING, APPROACH	9,645.000	SYS
22	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
23	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	11,385.000	TON
24	401-07371 QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm	11,640.000	TON
25	406-05520 ASPHALT FOR TACK COAT	60.000	TON
26	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
27	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
28	610-07487 HMA FOR APPROACHES, TYPE B	1,760.000	TON
29	615-06527 MONUMENT, SECTION CORNER	16.000	EACH
30	628-09402 FIELD OFFICE, B	6.000	MOS
31	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN	8.000	EACH
32	715-02629 SAFETY METAL END SECTION, 6:1, 18 IN	2.000	EACH
33	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN	170.000	LFT
34	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN	100.000	LFT
35	720-45205 CATCH BASIN, A2	2.000	EACH
36	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
37	801-04308 ROAD CLOSURE SIGN ASSEMBLY	18.000	EACH
38	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	15,435.000	LFT
39	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8,750.000	LFT
40	801-06625 DETOUR ROUTE MARKER ASSEMBLY	17.000	EACH
41	801-06640 CONSTRUCTION SIGN, A	128.000	EACH
42	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
43	801-07118 BARRICADE, III-A	400.000	LFT
44	801-07119 BARRICADE, III-B	600.000	LFT
45	804-06771 DELINEATOR POST, FLEXIBLE	10.000	EACH
46	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	84,290.000	LFT
47	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	32,103.000	LFT
48	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	34,078.000	LFT
49	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	75.000	LFT

CALL ORDER : 581

CONTRACT ID : RS-30521-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50 808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	2.000	EACH
51 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	910.000	EACH
52 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	910.000	EACH

CALL ORDER : 585

CONTRACT ID : RS-31725-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE OVERLAY ON PCCP		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	8.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	395.000	CYS
13	203-08607 LINEAR GRADING	500.000	LFT
14	207-08263 SUBGRADE TREATMENT, TYPE IA	1,290.000	SYS
15	303-01180 COMPACTED AGGREGATE, NO. 53	80.000	TON
16	303-07449 COMPACTED AGGREGATE, NO. 73	165.000	TON
17	304-07783 HMA PATCHING, TYPE D	310.000	TON
18	305-06465 PCCP CRACKING AND SEATING	2,950.000	SYS
19	306-08036 MILLING, ASPHALT, 2 IN	2,750.000	SYS
20	306-08041 MILLING, PCCP	2,950.000	SYS
21	306-08041 MILLING, PCCP	1,870.000	SYS
22	306-08043 MILLING, TRANSITION	4,395.000	SYS
23	306-08432 MILLING, APPROACH	1,000.000	SYS
24	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	840.000	TON
25	401-07399 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	3,915.000	TON
26	402-07786 HMA BASE, TYPE D	475.000	TON
27	406-05520 ASPHALT FOR TACK COAT	20.000	TON
28	610-07788 HMA FOR APPROACHES, TYPE D	275.000	TON
29	628-09402 FIELD OFFICE, B	4.000	MOS
30	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	4.000	MOS
31	720-44000 CASTING, ADJUST TO GRADE	20.000	EACH
32	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
33	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	5.000	EACH
34	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	3.000	EACH
35	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	3.000	EACH
36	801-01505 TEMPORARY PAVEMENT MESSAGE MARKING, (ONLY)	1.000	EACH
37	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
38	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,980.000	LFT
39	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	650.000	LFT
40	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
41	801-06710 FLASHING ARROW SIGN	100.000	DAY
42	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
43	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	3.000	EACH
44	802-02475 SIGN, PANEL, RELOCATE	3.000	EACH
45	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	204.000	LFT
46	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	48.000	LFT
47	802-07057 SIGN, PANEL, WITH LEGEND	360.000	SFT
48	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	18.000	SFT
49	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	106.500	SFT

CALL ORDER : 585

CONTRACT ID : RS-31725-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE OVERLAY ON PCCP		
50	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA	9,294.000	LFT
51	805-78785 SIGNAL DETECTOR HOUSING	34.000	EACH
52	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	2,255.000	LFT
53	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN	1,615.000	LFT
54	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN	8,125.000	LFT
55	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN	8,705.000	LFT
56	808-74805 TRANSVERSE MARKING EPOXY,	113.000	LFT
57	808-74807 PAVEMENT MESSAGE MARKING, EPOXY, LANE INDICATIONS ARROWS	3.000	EACH
58	808-98000 LINE, EPOXY, SOLID, YELLOW, 8 IN	835.000	LFT



CALL ORDER : 755

CONTRACT ID : B -31463-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02271 HEADWALL, REMOVE	4.000	EACH
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	202-96133 PIPE, REMOVE	131.000	LFT
12	202-99187 FENCE, FARM FIELD, REMOVE	197.000	LFT
13	203-02000 EXCAVATION, COMMON	6,184.000	CYS
14	203-02010 EXCAVATION, ROCK	200.000	CYS
15	203-02070 BORROW	4,018.000	CYS
16	203-51223 EXCAVATION, WATERWAY	107.000	CYS
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	420.000	TON
18	205-06936 TEMPORARY SEDIMENT TRAP	160.000	TON
19	205-06937 TEMPORARY SILT FENCE	2,758.000	LFT
20	206-51220 EXCAVATION, WET	282.000	CYS
21	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	10.000	CYS
22	207-08265 SUBGRADE TREATMENT, TYPE IIA	5,246.000	SYS
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	176.000	SYS
24	211-02050 B BORROW	695.000	CYS
25	211-06467 AGGREGATE FOR END BENT BACKFILL	64.000	CYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	127.000	CYS
27	211-09266 STRUCTURAL BACKFILL, TYPE 3	1,658.000	CYS
28	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	515.000	TON
29	302-07455 DENSE GRADED SUBBASE	34.000	CYS
30	306-08043 MILLING, TRANSITION	134.000	SYS
31	402-07432 HMA SURFACE, TYPE A	315.000	TON
32	402-07435 HMA INTERMEDIATE, TYPE A	505.000	TON
33	402-07440 HMA BASE, TYPE A	1,615.000	TON
34	406-05520 ASPHALT FOR TACK COAT	2.000	TON
35	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	2.000	EACH
36	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
37	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
38	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	800.000	LFT
39	605-06120 CURB, CONCRETE	110.000	LFT
40	607-06175 GUTTER, CONCRETE, TYPE	50.000	LFT
41	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	200.000	SYS
42	610-07487 HMA FOR APPROACHES, TYPE B	49.000	TON
43	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
44	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
45	615-06505 MONUMENT, B	6.000	EACH
46	616-02320 GEOTEXTILES	2,711.000	SYS
47	616-06405 RIPRAP, REVETMENT	1,638.000	TON
48	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
49	621-02356 SEEDING, WETLAND	15.000	LBS

CALL ORDER : 755

CONTRACT ID : B -31463-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	4,200.000	SYS
51	621-06545 FERTILIZER	0.200	TON
52	621-06553 SEED MIXTURE, R	295.000	LBS
53	621-06565 MULCHING MATERIAL	3.500	TON
54	621-06574 SODDING	475.000	SYS
55	622-05648 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	41.000	EACH
56	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	4.000	EACH
57	622-52436 SIGN, DO NOT MOW OR SPRAY	7.000	EACH
58	622-91786 SEEDLING	193.000	EACH
59	628-09402 FIELD OFFICE, B	9.000	MOS
60	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	9.000	MOS
61	701-04732 PILE	2,509.000	LFT
62	701-09679 CONICAL PILE TIP, 14 IN	31.000	EACH
63	702-51005 CONCRETE, A, SUBSTRUCTURE	236.500	CYS
64	702-51015 CONCRETE, B, FOOTINGS	71.200	CYS
65	703-06028 REINFORCING BARS	29,379.000	LBS
66	703-06029 REINFORCING BARS, EPOXY COATED	90,614.000	LBS
67	704-51002 CONCRETE, C, SUPERSTRUCTURE	257.600	CYS
68	706-06344 RAILING, TS-1	551.000	LFT
69	707-08158 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	810.000	LFT
70	709-51821 SURFACE SEAL	LUMP	LUMP
71	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN	2.000	EACH
72	715-02629 SAFETY METAL END SECTION, 6:1, 18 IN	6.000	EACH
73	715-03487 SAFETY METAL END SECTION, 4:1, 30 IN	1.000	EACH
74	715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN	45.000	LFT
75	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	46.000	LFT
76	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN	166.000	LFT
77	715-05407 PIPE, END BENT DRAIN, 6 IN	134.000	LFT
78	724-51925 STRUCTURAL EXPANSION JOINT, SS	82.000	LFT
79	731-93945 FACE PANELS, CONCRETE	4,884.000	SFT
80	731-93946 WALL ERECTION	4,884.000	SFT
81	731-93947 LEVELING PAD, CONCRETE	473.000	LFT
82	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
83	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
84	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
85	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
86	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
87	801-07118 BARRICADE, III-A	48.000	LFT
88	801-07119 BARRICADE, III-B	24.000	LFT
89	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	20.000	LFT
90	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	10.000	SFT
91	804-06770 DELINEATOR POST	1.000	EACH
92	805-97602 ENERGY DISSIPATOR	LUMP	LUMP
93	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN	695.000	LFT
94	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN	695.000	LFT
95	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,418.000	LFT
96	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,418.000	LFT

CALL ORDER : 781

CONTRACT ID : B -33024-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02240 PAVEMENT REMOVAL	43.000	SYS
8	203-02000 EXCAVATION, COMMON	153.000	CYS
9	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	10.000	CYS
10	303-09533 COARSE AGGREGATE	72.000	TON
11	305-08445 PCC BASE, 4 IN	34.000	SYS
12	503-05240 D-1 CONTRACTION JOINT	143.000	LFT
13	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
14	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
15	602-06729 BARRIER DELINEATOR	8.000	EACH
16	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	9.000	SYS
17	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	25,024.000	SFT
18	702-51863 FIELD DRILLED HOLE IN CONCRETE	306.000	EACH
19	703-06029 REINFORCING BARS, EPOXY COATED	16,500.000	LBS
20	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	1.000	EACH
21	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	306.000	SYS
22	706-51020 CONCRETE, C, RAILING	33.000	CYS
23	715-03321 SAFETY METAL END SECTION, 6:1, 12 IN	2.000	EACH
24	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN	40.000	LFT
25	715-05422 PIPE, SLOTTED DRAIN, 12 IN	290.000	LFT
26	715-91361 PIPE, PVC, 6 IN	100.000	LFT
27	801-06201 TEMPORARY PANEL SIGNS	200.000	SFT
28	801-06640 CONSTRUCTION SIGN, A	3.000	EACH
29	801-06710 FLASHING ARROW SIGN	20.000	DAY
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	801-08507 TEMP TRAFFIC BARRIER, TYPE 1, ANCHORED	120.000	LFT
32	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	1.000	EACH
33	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	31.250	LFT

