

CALL ORDER : 500

CONTRACT ID : B -29688-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	236.000	CYS
12	203-02070 BORROW	1,759.000	CYS
13	203-51223 EXCAVATION, WATERWAY	301.000	CYS
14	205-02770 EROSION CONTROL BLANKET	1,380.000	SYS
15	205-06937 TEMPORARY SILT FENCE	375.000	LFT
16	205-09543 NO 2 STONE	100.000	TON
17	206-51220 EXCAVATION, WET	110.000	CYS
18	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	44.000	CYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,495.000	SYS
20	211-06467 AGGREGATE FOR END BENT BACKFILL	12.000	CYS
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	31.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	615.000	TON
23	302-07455 DENSE GRADED SUBBASE	20.000	CYS
24	402-07432 HMA SURFACE, TYPE A	115.000	TON
25	402-07435 HMA INTERMEDIATE, TYPE A	190.000	TON
26	406-05521 ASPHALT FOR TACK COAT	1,385.000	SYS
27	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
28	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
29	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	387.500	LFT
30	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	112.000	SYS
31	615-06505 MONUMENT, B	2.000	EACH
32	616-02320 GEOTEXTILES	568.000	SYS
33	616-05688 RIPRAP, CLASS 1	420.000	TON
34	616-06405 RIPRAP, REVETMENT	6.000	TON
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
36	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	1,380.000	SYS
37	621-06559 MULCHED SEEDING, R	1,380.000	SYS
38	622-91786 SEEDLING	84.000	EACH
39	628-09401 FIELD OFFICE, A	8.000	MOS
40	701-09662 PILE, STEEL PIPE, 0.250 IN, 14 IN	980.000	LFT
41	701-09679 CONICAL PILE TIP, 14 IN	20.000	EACH
42	702-51005 CONCRETE, A, SUBSTRUCTURE	60.600	CYS
43	703-06028 REINFORCING BARS	4,590.000	LBS
44	703-06029 REINFORCING BARS, EPOXY COATED	29,407.000	LBS
45	704-51002 CONCRETE, C, SUPERSTRUCTURE	98.800	CYS
46	706-06344 RAILING, TS-1	237.500	LFT
47	707-05971 STRUCTURAL MEMBERS, CONCRETE BOX BEAM,	1,368.000	SFT
48	709-51821 SURFACE SEAL	LUMP	LUMP
49	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN	60.000	LFT

SCHEDULE OF PAY ITEMS

CALL ORDER : 500

CONTRACT ID : B -29688-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	715-05407 PIPE, END BENT DRAIN, 6 IN	60.000	LFT
51	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
52	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
53	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
54	801-07118 BARRICADE, III-A	48.000	LFT
55	801-07119 BARRICADE, III-B	48.000	LFT

CALL ORDER : 510

CONTRACT ID : B -31727-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SCOUR PROTECTION		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	3.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	303-01180 COMPACTED AGGREGATE, NO. 53	1.000	TON
11	607-95754 PAVED SIDE DITCH, BREAK	82.000	LFT
12	616-02320 GEOTEXTILES	924.000	SYS
13	616-03472 RIPRAP, REVEMENT 18 IN.	130.000	TON
14	616-05688 RIPRAP, CLASS 1	173.000	TON
15	616-05689 RIPRAP, CLASS 2	982.000	TON
16	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
17	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
18	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
20	801-06710 FLASHING ARROW SIGN	14.000	DAY
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

