

CALL ORDER : 311

CONTRACT ID : R -34238-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN FACILITY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	1,744.000	SYS
10	202-91385 INLET, REMOVE	4.000	EACH
11	203-02000 EXCAVATION, COMMON	3,111.000	CYS
12	203-02070 BORROW	602.000	CYS
13	203-11332 EMERGENCY SANDBAG CLOSURE	LUMP	LUMP
14	205-03371 SEDIMENT, REMOVE	25.000	CYS
15	205-04948 TEMPORARY CONSTRUCTION ENTRANCE/EXIT	LUMP	LUMP
16	205-06930 SPLASHPAD, RIPRAP	2.000	TON
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	3.000	TON
18	205-06933 TEMPORARY DITCH INLET PROTECTION	26.000	EACH
19	205-06934 TEMPORARY MULCHING	13.000	TON
20	205-06937 TEMPORARY SILT FENCE	1,578.000	LFT
21	205-09543 NO 2 STONE	100.000	TON
22	207-08266 SUBGRADE TREATMENT, TYPE III	4,798.000	SYS
23	210-05873 TESTING	LUMP	LUMP
24	211-09264 STRUCTURAL BACKFILL, TYPE 1	96.000	CYS
25	211-09266 STRUCTURAL BACKFILL, TYPE 3	140.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,570.000	TON
27	303-04489 COMPACTED CRUSHED AGGREGATE, 8	43.000	TON
28	304-07489 HMA PATCHING, TYPE A	188.000	TON
29	306-08034 MILLING, ASPHALT, 1 1/2 IN	228.000	SYS
30	306-08043 MILLING, TRANSITION	60.000	SYS
31	402-07432 HMA SURFACE, TYPE A	401.000	TON
32	402-07435 HMA INTERMEDIATE, TYPE A	309.000	TON
33	402-07440 HMA BASE, TYPE A	128.000	TON
34	402-07450 HMA WEDGE AND LEVEL, TYPE A	105.000	TON
35	406-05520 ASPHALT FOR TACK COAT	1.240	TON
36	602-08605 CONCRETE BARRIER, 33 IN	236.000	LFT
37	602-98036 BARRIER MAT, WEED	935.000	SYS
38	603-03692 FENCE, WOOD,	236.000	LFT
39	603-03692 FENCE, WOOD,	121.000	LFT
40	603-03692 FENCE, WOOD,	349.000	LFT
41	603-06045 FENCE, CHAIN LINK, 48 IN	339.000	LFT
42	603-11054 FENCE GATE, CHAIN LINK, 96 IN. X 28 FT.	2.000	EACH
43	603-11056 FENCE GATE, CHAIN LINK, 96 IN. X 24 FT.	2.000	EACH
44	603-11057 FENCE GATE, CHAIN LINK, 96 IN. X 32 FT.	2.000	EACH
45	603-11058 FENCE GATE, CHAIN LINK, 96 IN. X 13 FT. 6 IN.	2.000	EACH
46	604-07894 CURB RAMP, CONCRETE, A	35.000	SYS
47	604-91404 SIDEWALK, CONCRETE, 5 IN	474.000	SYS
48	604-91404 SIDEWALK, CONCRETE, 5 IN	63.000	SYS
49	605-06120 CURB, CONCRETE	106.000	LFT

CALL ORDER : 311

CONTRACT ID : R -34238-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN FACILITY		
50	605-06144 CURB AND GUTTER, A, CONCRETE	2,907.000	LFT
51	605-09176 CURB TURNOUT, CONCRETE	8.000	LFT
52	607-06335 PAVED SIDE DITCH, A	16.000	LFT
53	610-07713 PCCP FOR APPROACHES, 8 IN	476.000	SYS
54	610-08526 PCCP FOR APPROACHES, 11 IN	2,060.000	SYS
55	610-08526 PCCP FOR APPROACHES, 11 IN	223.000	SYS
56	616-02320 GEOTEXTILES	2.000	SYS
57	616-06405 RIPRAP, REVETMENT	2.000	TON
58	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
59	621-02770 EROSION CONTROL BLANKET	1,863.000	SYS
60	621-06545 FERTILIZER	0.700	TON
61	621-06554 SEED MIXTURE, U	410.000	LBS
62	621-06557 SEED MIXTURE, T	820.000	LBS
63	621-06565 MULCHING MATERIAL	3.000	TON
64	621-06567 WATER	32.000	KGAL
65	621-06570 TOPSOIL	500.000	CYS
66	621-06575 SODDING, NURSERY	7,962.000	SYS
67	621-07642 SOIL PREPARATION	467.000	CYS
68	621-98038 MULCH, HARDWOOD SHREDDED BARK	103.000	CYS
69	622-05639 PLANT, DECIDUOUS SHRUB, 18 TO 24 IN	209.000	EACH
70	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	14.000	EACH
71	622-05654 PLANT, PERENNIAL	359.000	EACH
72	622-08101 DECORATIVE	LUMP	LUMP
73	622-08101 DECORATIVE	LUMP	LUMP
74	628-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
75	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
76	628-09402 FIELD OFFICE, B	12.000	MOS
77	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
78	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	24.000	MOS
79	711-05101 EDGING	194.000	LFT
80	711-05101 EDGING	4,517.000	LFT
81	715-04612 PIPE	90.000	LFT
82	715-07729 PIPE, RCP, III, DO.3=75, 15 IN	2.000	LFT
83	715-08071 PIPE, RCP, III, DO.3=75, 12 IN.	1,070.000	LFT
84	715-90714 PIPE, PVC, 12 IN	145.000	LFT
85	715-91361 PIPE, PVC, 6 IN	8.000	LFT
86	720-44000 CASTING, ADJUST TO GRADE	6.000	EACH
87	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
88	720-45045 INLET, J10	12.000	EACH
89	720-96422 INLET, A, MODIFIED	12.000	EACH
90	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	105.000	SYS
91	732-08421 MODULAR BLOCK WALL ERECTION	105.000	SYS
92	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
93	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
94	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
95	801-07119 BARRICADE, III-B	72.000	LFT
96	802-03896 BOLLARD	12.000	EACH
97	802-03896 BOLLARD	4.000	EACH
98	802-03896 BOLLARD	4.000	EACH

CALL ORDER : 311

CONTRACT ID : R -34238-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN FACILITY		
99 802-03896	BOLLARD	9.000	EACH
100 802-03896	BOLLARD	6.000	EACH
101 802-04314	SIGN	1.000	EACH
102 802-04314	SIGN	1.000	EACH
103 802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	238.000	LFT
104 802-09838	SIGN, SHEET, WITH LEGEND 0.080"	58.000	SFT
105 802-09838	SIGN, SHEET, WITH LEGEND 0.080"	52.000	SFT
106 808-04767	LINE	2,538.000	LFT
107 808-05929	TRANSVERSE MARKING THERMOPLASTIC,	56.000	LFT
108 808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT,	2.000	EACH
109 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	80.000	LFT
110 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	13.000	LFT

CALL ORDER : 381

CONTRACT ID : RS-34145-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	207-09935 SUBGRADE TREATMENT, TYPE 1C	1,620.000	SYS
11	211-09264 STRUCTURAL BACKFILL, TYPE 1	8.000	CYS
12	302-07455 DENSE GRADED SUBBASE	275.000	CYS
13	303-07449 COMPACTED AGGREGATE, NO. 73	9,800.000	TON
14	304-07783 HMA PATCHING, TYPE D	80.000	TON
15	306-08033 MILLING, ASPHALT, 1 IN	66,300.000	SYS
16	306-08034 MILLING, ASPHALT, 1 1/2 IN	43,800.000	SYS
17	306-08039 MILLING, ASPHALT REMOVE	1,650.000	SYS
18	306-08043 MILLING, TRANSITION	22,100.000	SYS
19	306-08432 MILLING, APPROACH	1,410.000	SYS
20	306-08595 MILLING ASPHALT, 3 1/2 IN	124,100.000	SYS
21	306-10163 MILLING ASPHALT, 2 1/2 IN	254,500.000	SYS
22	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
23	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	17,300.000	TON
24	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2,450.000	TON
25	401-07330 QC/QA-HMA, 5, 70, SURFACE, 9.5 mm	22,050.000	TON
26	401-07355 QC/QA-HMA, 1, 64, INTERMEDIATE, 9.5 mm	9,925.000	TON
27	401-07370 QC/QA-HMA, 1, 64, INTERMEDIATE, 12.5 mm	7,750.000	TON
28	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	3,800.000	TON
29	401-07400 QC/QA-HMA, 5, 70, INTERMEDIATE, 19.0 mm	51,325.000	TON
30	401-07422 QC/QA-HMA, 1, 64, BASE, 19.0 mm	20,200.000	TON
31	406-05520 ASPHALT FOR TACK COAT	375.000	TON
32	503-03489 RETROFITTED TIE BARS	370.000	EACH
33	503-05240 D-1 CONTRACTION JOINT	816.000	LFT
34	506-06333 PCCP PATCHING, FULL DEPTH	1,650.000	SYS
35	506-06334 PCCP PATCHING, PARTIAL DEPTH	12.000	SYS
36	601-01522 GUARDRAIL, TRANSITION TYPE TGB	1.000	EACH
37	601-02241 GUARDRAIL, REMOVE	350.000	LFT
38	601-06035 GUARDRAIL, RESET	31,613.000	LFT
39	601-07050 GUARDRAIL END TREATMENT, OS, RESET	28.000	EACH
40	601-91147 GUARDRAIL END TREATMENT, RESET	8.000	EACH
41	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	3,755.000	LFT
42	606-07484 MILLED HMA SHOULDER CORRUGATIONS	218,000.000	LFT
43	610-07487 HMA FOR APPROACHES, TYPE B	275.000	TON
44	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	3.000	TON
45	612-60410 DRILLED HOLE FOR UNDERSEAL	56.000	EACH
46	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
47	621-06559 MULCHED SEEDING, R	500.000	SYS
48	628-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
49	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL

CALL ORDER : 381

CONTRACT ID : RS-34145-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	628-09402 FIELD OFFICE, B	16.000	MOS
51	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	32.000	MOS
52	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	64.000	MOS
53	715-03475 SAFETY METAL END SECTION, 4:1 15 IN	2.000	EACH
54	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	200.000	LFT
55	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	140.000	LFT
56	718-06526 HMA FOR UNDERDRAINS	7.000	TON
57	718-06529 OUTLET PROTECTOR, 2	8.000	EACH
58	718-52610 AGGREGATE FOR UNDERDRAINS	4.000	CYS
59	718-99153 GEOTEXTILES FOR UNDERDRAIN	90.000	SYS
60	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	530.000	LFT
61	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
62	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
63	801-03291 CONSTRUCTION SIGN, D	20.000	EACH
64	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
65	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	439,000.000	LFT
66	801-06208 TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN	35,000.000	LFT
67	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	400.000	LFT
68	801-06625 DETOUR ROUTE MARKER ASSEMBLY	4.000	EACH
69	801-06640 CONSTRUCTION SIGN, A	80.000	EACH
70	801-06645 CONSTRUCTION SIGN, B	20.000	EACH
71	801-06710 FLASHING ARROW SIGN	960.000	DAY
72	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
73	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	8.000	EACH
74	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	25,600.000	LFT
75	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	109,700.000	LFT
76	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	8,300.000	LFT
77	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
78	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	12,750.000	LFT
79	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	12,750.000	LFT
80	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	3,200.000	LFT
81	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	109,700.000	LFT
82	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	500.000	LFT
83	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	1,260.000	LFT
84	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	200.000	LFT
85	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	12.000	EACH
86	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,900.000	EACH
87	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,900.000	EACH

