

CALL ORDER : 350

CONTRACT ID : B -33424-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-------------|-------|
| SECTION NO. 0001 | BRIDGE REPLACEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-08520 CELLULAR TELEPHONE/RADIO | 2.000 | EACH |
| 3 | 105-08521 CELLULAR TELEPHONE/RADIO SERVICE | 14.000 | MOS |
| 4 | 105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES | 1.000 | DOL |
| 5 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 6 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 10 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 11 | 202-02279 CURB AND GUTTER, REMOVE | 270.000 | LFT |
| 12 | 202-51328 PRESENT STRUCTURE, REMOVE PORTIONS | LUMP | LUMP |
| 13 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 187.000 | SYS |
| 14 | 205-06937 TEMPORARY SILT FENCE | 404.000 | LFT |
| 15 | 211-06467 AGGREGATE FOR END BENT BACKFILL | 83.000 | CYS |
| 16 | 213-09269 FLOWABLE BACKFILL, NON-REMOVABLE | 17.000 | CYS |
| 17 | 302-07455 DENSE GRADED SUBBASE | 58.000 | CYS |
| 18 | 306-08034 MILLING, ASPHALT, 1 1/2 IN | 374.000 | SYS |
| 19 | 402-07452 HMA WEDGE AND LEVEL, TYPE C | 144.000 | TON |
| 20 | 406-05521 ASPHALT FOR TACK COAT | 996.000 | SYS |
| 21 | 502-06627 PCCP, 6 IN | 35.000 | SYS |
| 22 | 601-01522 GUARDRAIL TRANSITION TYPE TGB | 2.000 | EACH |
| 23 | 601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3 | 1.000 | EACH |
| 24 | 601-06035 GUARDRAIL, RESET | 56.000 | LFT |
| 25 | 601-95871 HANDRAIL | 115.000 | LFT |
| 26 | 601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING | 7.000 | LFT |
| 27 | 604-07902 CURB RAMP, CONCRETE, H | 23.000 | SYS |
| 28 | 604-91531 SIDEWALK, CONCRETE, 4 IN | 187.000 | SYS |
| 29 | 605-06090 CURB, INTEGRAL, CONCRETE | 35.000 | LFT |
| 30 | 605-06150 CURB AND GUTTER, C, CONCRETE | 270.000 | LFT |
| 31 | 605-06250 CENTER CURB, C, CONCRETE | 72.000 | SYS |
| 32 | 609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN | 347.000 | SYS |
| 33 | 628-09402 FIELD OFFICE, B | 7.000 | MOS |
| 34 | 628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL | 7.000 | MOS |
| 35 | 702-51005 CONCRETE, A, SUBSTRUCTURE | 43.000 | CYS |
| 36 | 702-51863 FIELD DRILLED HOLE IN CONCRETE | 36.000 | EACH |
| 37 | 703-06028 REINFORCING BARS | 2,213.000 | LBS |
| 38 | 703-06029 REINFORCING BARS, EPOXY COATED | 230,877.000 | LBS |
| 39 | 704-51002 CONCRETE, C, SUPERSTRUCTURE | 1,072.100 | CYS |
| 40 | 706-06342 RAILING, PS-1 | 567.000 | LFT |
| 41 | 706-06353 CONCRETE BRIDGE RAILING TRANSITION, TPS-1 | 4.000 | EACH |
| 42 | 706-51025 CONCRETE, C, RAILING | 34.000 | LFT |
| 43 | 707-09598 STRUCTURAL MEMBERS, CONCRETE, BULB-T | 2,735.000 | LFT |
| 44 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 45 | 711-51070 ANCHOR PLATE, AP 1 | 12.000 | EACH |
| 46 | 720-44000 CASTING, ADJUST TO GRADE | 2.000 | EACH |
| 47 | 729-51875 CONCRETE, A, PATCHING | 250.000 | SFT |
| 48 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |