

CALL ORDER : 150

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
1	203-02000 EXCAVATION, COMMON	100,834.000	CYS
2	203-02070 BORROW	548,296.000	CYS
3	207-08262 SUBGRADE TREATMENT, TYPE I	57,007.000	SYS
4	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	9,062.000	TON
5	302-06464 SUBBASE FOR PCCP	8,514.000	CYS
6	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,434.000	TON
7	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	2,644.000	TON
8	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	3,085.000	TON
9	406-05520 ASPHALT FOR TACK COAT	9.100	TON
10	501-06321 QC/QA-PCCP, 10 IN	34,055.000	SYS
11	503-05240 D-1 CONTRACTION JOINT	17,028.000	LFT
SECTION NO. 0002 NEW ROAD CONSTRUCTION			
12	203-02000 EXCAVATION, COMMON	99,931.000	CYS
13	203-02070 BORROW	552,681.000	CYS
14	207-08262 SUBGRADE TREATMENT, TYPE I	54,287.000	SYS
15	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	15,111.000	TON
16	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	998.000	TON
17	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	3,242.000	TON
18	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	5,484.000	TON
19	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	2,994.000	TON
20	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	15,348.000	TON
21	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	6,661.000	TON
22	406-05520 ASPHALT FOR TACK COAT	46.000	TON
SECTION NO. 0003 NEW ROAD CONSTRUCTION			
23	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
24	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
25	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
26	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
27	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
28	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
29	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
30	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
31	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
32	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
33	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
34	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
35	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
36	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
37	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
38	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
39	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
40	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
41	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
42	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
43	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP

CALL ORDER : 150

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW ROAD CONSTRUCTION		
44	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
45	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
46	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
47	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
48	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
49	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
50	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
51	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	432.000	SFT
52	203-02000 EXCAVATION, COMMON	21,222.000	CYS
53	203-02070 BORROW	35,968.000	CYS
54	204-02290 SETTLEMENT PLATE	12.000	EACH
55	204-08415 STAKE, SETTLEMENT	12.000	EACH
56	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	7.000	EACH
57	205-03371 SEDIMENT, REMOVE	339.000	CYS
58	205-06930 SPLASHPAD, RIPRAP	66.600	TON
59	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	464.500	TON
60	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
61	205-06933 TEMPORARY DITCH INLET PROTECTION	6.000	EACH
62	205-06934 TEMPORARY MULCHING	36.600	TON
63	205-06937 TEMPORARY SILT FENCE	5,190.000	LFT
64	205-06938 TEMPORARY SLOPE DRAIN	732.000	LFT
65	205-09543 NO 2 STONE	1,894.000	TON
66	206-51220 EXCAVATION, WET	1,447.000	CYS
67	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	247.000	CYS
68	206-51235 COFFERDAM	LUMP	LUMP
69	207-08264 SUBGRADE TREATMENT, TYPE II	5,876.000	SYS
70	207-08265 SUBGRADE TREATMENT, TYPE IIA	295.000	SYS
71	207-08266 SUBGRADE TREATMENT, TYPE III	752.000	SYS
72	211-02050 B BORROW	26,026.000	CYS
73	211-09264 STRUCTURAL BACKFILL, TYPE 1	536.600	CYS
74	211-09265 STRUCTURAL BACKFILL, TYPE 2	5,030.000	CYS
75	211-09266 STRUCTURAL BACKFILL, TYPE 3	31,315.000	CYS
76	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	37.200	CYS
77	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,854.000	TON
78	302-06464 SUBBASE FOR PCCP	650.000	CYS
79	302-07455 DENSE GRADED SUBBASE	178.200	CYS
80	302-08562 COARSE AGGREGATE, 8	214.000	TON
81	303-01180 COMPACTED AGGREGATE, NO. 53	490.700	TON
82	303-07449 COMPACTED AGGREGATE, NO. 73	26.000	TON
83	306-08034 MILLING, ASPHALT, 1 1/2 IN	377.800	SYS
84	402-07432 HMA SURFACE, TYPE A	62.000	TON
85	402-07433 HMA SURFACE, TYPE B	479.300	TON
86	402-07435 HMA INTERMEDIATE, TYPE A	103.000	TON
87	402-07438 HMA INTERMEDIATE, TYPE B	753.700	TON
88	406-05520 ASPHALT FOR TACK COAT	1.500	TON
89	502-06331 PCCP, 14 IN	2,288.000	SYS
90	502-06331 PCCP, 14 IN	312.000	SYS
91	503-05240 D-1 CONTRACTION JOINT	1,850.000	LFT
92	507-07480 PROFILING PCCP	2,600.000	SYS

CALL ORDER : 150

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW ROAD CONSTRUCTION		
93	601-01522 GUARDRAIL, TRANSITION TYPE TGB	11.000	EACH
94	601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION	3.000	EACH
95	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
96	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
97	601-94690 GUARDRAIL END TREATMENT, MS	2.000	EACH
98	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	3,007.000	LFT
99	601-99108 GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	588.000	LFT
100	602-06729 BARRIER DELINEATOR	68.000	EACH
101	603-06040 FENCE, FARM FIELD, 47 IN	12,981.000	LFT
102	606-07484 MILLED HMA SHOULDER CORRUGATIONS	25,145.000	LFT
103	606-11064 MILLED PCCP SHOULDER CORRUGATIONS	232.000	LFT
104	607-06335 PAVED SIDE DITCH, A	65.000	LFT
105	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	1,068.800	SYS
106	610-07486 HMA FOR APPROACHES, TYPE A	55.000	TON
107	610-07487 HMA FOR APPROACHES, TYPE B	52.700	TON
108	610-08446 PCCP FOR APPROACHES, 6 IN	103.000	SYS
109	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
110	611-08233 MAILBOX ASSEMBLY, DOUBLE, RESET	2.000	EACH
111	615-06490 RIGHT OF WAY MARKER	12.000	EACH
112	615-06505 MONUMENT, B	4.000	EACH
113	615-06510 MONUMENT, C	14.000	EACH
114	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
115	616-02320 GEOTEXTILES	3,298.500	SYS
116	616-06405 RIPRAP, REVETMENT	2,632.800	TON
117	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.000	EACH
118	621-03787 SEED MIXTURE, D	28.000	LBS
119	621-03909 SEED MIXTURE, NATIVE	277.000	LBS
120	621-06545 FERTILIZER	14.750	TON
121	621-06545 FERTILIZER	100.000	TON
122	621-06553 SEED MIXTURE, R	3,928.200	LBS
123	621-06557 SEED MIXTURE, T	4,856.700	LBS
124	621-06557 SEED MIXTURE, T	395.000	LBS
125	621-06565 MULCHING MATERIAL	59.600	TON
126	621-06567 WATER	16.140	KGAL
127	621-06574 SODDING	4,511.000	SYS
128	622-98200 SIGN, DO NOT DISTURB	2.000	EACH
129	624-92647 HERBICIDE TREATMENT	12.000	ACRE
130	624-92647 HERBICIDE TREATMENT	12.000	ACRE
131	628-09403 FIELD OFFICE, C	27.000	MOS
132	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	252.000	MOS
133	628-09409 MOBILE INTERNET SERVICE	120.000	MOS
134	628-09893 WORK TRUCK	81.000	MOS
135	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	252.000	MOS
136	628-11068 CELLULAR TELEPHONE/RADIO	7.000	EACH
137	701-06011 DYNAMIC PILE LOAD TEST	9.000	EACH
138	701-08253 PILE SLEEVES	24.000	EACH
139	701-09557 TEST PILE, DYNAMIC, PRODUCTION	693.000	LFT
140	701-09559 TEST PILE, DYNAMIC, RESTRIKE	9.000	EACH
141	701-09770 PILE SHOE, HP 14 X 73	161.000	EACH

CALL ORDER : 150

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW ROAD CONSTRUCTION			
142	701-09824 PREBORED HOLE, 18 IN.	2,471.000	LFT
143	701-93575 PILE, STEEL H, HP 14 IN X 73	6,644.000	LFT
144	702-51005 CONCRETE, A, SUBSTRUCTURE	373.600	CYS
145	702-51015 CONCRETE, B, FOOTINGS	71.400	CYS
146	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	768.000	LBS
147	703-06028 REINFORCING BARS	24,648.000	LBS
148	703-06029 REINFORCING BARS, EPOXY COATED	396,391.000	LBS
149	704-51002 CONCRETE, C, SUPERSTRUCTURE	824.700	CYS
150	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
151	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	8.000	EACH
152	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	919.000	SYS
153	706-51020 RAILING, CONCRETE, C	245.200	CYS
154	709-07110 SEAL COAT, GRAFFITI RESISTANT	37,101.000	SFT
155	709-51821 SURFACE SEAL	LUMP	LUMP
156	709-51821 SURFACE SEAL	LUMP	LUMP
157	709-51821 SURFACE SEAL	LUMP	LUMP
158	709-51821 SURFACE SEAL	LUMP	LUMP
159	711-51038 STRUCTURAL STEEL	LUMP	LUMP
160	711-51038 STRUCTURAL STEEL	LUMP	LUMP
161	711-51038 STRUCTURAL STEEL	LUMP	LUMP
162	714-11173 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	104.000	LFT
163	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	844.000	LFT
164	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	25,298.000	LFT
165	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	400.000	LFT
166	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	1,664.000	LFT
167	715-05118 PIPE, TYPE 1 CIRCULAR 12 IN	2,000.000	LFT
168	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	400.000	LFT
169	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	439.000	LFT
170	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	470.000	LFT
171	715-05168 PIPE, TYPE 3 CIRCULAR 12 IN	36.000	LFT
172	715-05212 PIPE, TYPE 4 CIRCULAR 24 IN	600.000	LFT
173	715-05218 PIPE, TYPE 5 CIRCULAR 15 IN	264.000	LFT
174	715-09446 PIPE, TYPE 4 CIRCULAR 36 IN	400.000	LFT
175	715-46000 PIPE END SECTION, 12 IN	3.000	EACH
176	715-46005 PIPE END SECTION, 15 IN	7.000	EACH
177	715-46040 PIPE END SECTION, 36 IN	4.000	EACH
178	718-06528 OUTLET PROTECTOR, 1	55.000	EACH
179	718-06529 OUTLET PROTECTOR, 2	4.000	EACH
180	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
181	718-52610 AGGREGATE FOR UNDERDRAINS	2,277.000	CYS
182	718-99153 GEOTEXTILES FOR UNDERDRAIN	22,769.000	SYS
183	719-05443 PIPE, DRAINTILE TERMINAL SECTION, 12 IN	30.000	LFT
184	719-09447 PIPE, DRAIN TILE TERMINAL SECTION, 24 IN	10.000	LFT
185	719-09448 PIPE, DRAIN TILE, TERMINAL SECTION, 36 IN	10.000	LFT
186	720-08617 INLET, INTAKE RISER	10.000	EACH
187	720-45066 INLET, N12, MODIFIED	6.000	EACH
188	720-45070 INLET, P12A	7.000	EACH
189	720-45270 PIPE CATCH BASIN, 18 IN	3.000	EACH
190	720-45410 MANHOLE, C4	12.000	EACH

CALL ORDER : 150

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW ROAD CONSTRUCTION			
191	721-43000	AUTOMATIC DRAINAGE GATE, 12 IN	6.000 EACH
192	722-95883	BRIDGE DECK DRAIN SYSTEM	LUMP LUMP
193	723-11318	STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	278.000 LFT
194	724-51925	STRUCTURAL EXPANSION JOINT, SS	148.000 LFT
195	731-08252	LEVELING PAD	615.000 LFT
196	731-93945	FACE PANELS, CONCRETE	44,539.000 SFT
197	731-93946	WALL ERECTION	44,539.000 SFT
198	731-93947	LEVELING PAD, CONCRETE	1,214.000 LFT
199	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.000 EACH
200	801-06625	DETOUR ROUTE MARKER ASSEMBLY	8.000 EACH
201	801-06640	CONSTRUCTION SIGN, A	22.000 EACH
202	801-06775	MAINTAINING TRAFFIC	LUMP LUMP
203	801-07118	BARRICADE, III-A	48.000 LFT
204	801-07119	BARRICADE, III-B	48.000 LFT
205	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	48.000 LFT
206	802-05705	SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	21.000 LFT
207	802-09838	SIGN, SHEET, WITH LEGEND 0.080"	18.750 SFT
208	802-09840	SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	12.020 SFT
209	805-09616	VWIM STATION, QUARTZ	LUMP LUMP
210	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,885.000 LFT
211	808-09381	RETRO-REFLECTIVITY TESTING	LUMP LUMP
212	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	894.000 LFT
213	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	894.000 LFT
214	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	3,810.000 LFT
215	808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	16.000 LFT
SECTION NO. 0004 NEW BRIDGE			
216	109-08359	LIQUIDATED DAMAGES	1.000 DOL
217	109-08360	CONTRACT LIENS	1.000 DOL
218	109-08440	QUALITY ADJUSTMENTS, HMA	1.000 DOL
219	109-08441	QUALITY ADJUSTMENTS, PCCP	1.000 DOL
220	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000 DOL
221	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000 DOL
222	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.000 DOL
223	109-09377	QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000 DOL
224	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000 DOL
225	628-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000 DOL

CALL ORDER : 164

CONTRACT ID : IR-33986-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENVIRONMENTAL MITIGATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	205-09543 NO 2 STONE	100.000	TON
7	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
8	621-02318 SEED MIXTURE, PRAIRIE GRASS	19.000	LBS
9	621-02770 EROSION CONTROL BLANKET	31,194.000	SYS
10	621-06557 SEED MIXTURE, T	212.000	LBS
11	621-09400 SEED MIXTURE, SEDGE MEADOW	5.000	LBS
12	621-09400 SEED MIXTURE, SEDGE MEADOW	21.000	LBS
13	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	582.000	EACH
14	622-05648 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN OR UNDER	1,232.000	EACH
15	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	95.000	EACH
16	622-52436 SIGN, DO NOT MOW OR SPRAY	51.000	EACH
17	622-91786 SEEDLING	360.000	EACH
18	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	6.000	EACH

CALL ORDER : 170

CONTRACT ID : IR-34068-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
6	205-09543 NO 2 STONE	712.000	TON
7	205-09952 DESIGN BUILD EROSION AND SEDIMENT CONTROL	LUMP	LUMP
8	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
9	628-09403 FIELD OFFICE, C	6.000	MOS
10	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	6.000	MOS
11	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
12	713-04858 TEMPORARY BRIDGE	LUMP	LUMP
13	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
14	801-06645 CONSTRUCTION SIGN, B	23.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 200

CONTRACT ID : R -29975-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	1,366.000	CYS
11	203-02070 BORROW	1,854.000	CYS
12	203-51223 EXCAVATION, WATERWAY	1,096.000	CYS
13	205-02770 EROSION CONTROL BLANKET	1,252.000	SYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	70.000	TON
15	205-06937 TEMPORARY SILT FENCE	935.000	LFT
16	205-09543 NO 2 STONE	100.000	TON
17	207-08265 SUBGRADE TREATMENT, TYPE IIA	2,941.000	SYS
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	10.400	CYS
19	211-09266 STRUCTURAL BACKFILL, TYPE 3	282.000	CYS
20	211-09268 STRUCTURAL BACKFILL, TYPE 5	249.000	CYS
21	214-07202 GEOGRID, TYPE I	1,100.000	SYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,050.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	249.000	SYS
24	402-07433 HMA SURFACE, TYPE B	208.000	TON
25	402-07438 HMA INTERMEDIATE, TYPE B	556.000	TON
26	406-05521 ASPHALT FOR TACK COAT	2,691.000	SYS
27	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	2.000	EACH
28	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
29	601-06856 MODIFIED POSTS, NESTED GUARDRAIL	4.000	EACH
30	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
31	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	106.250	LFT
32	610-07487 HMA FOR APPROACHES, TYPE B	57.000	TON
33	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
34	615-06490 RIGHT OF WAY MARKER	16.000	EACH
35	615-06505 MONUMENT, B	2.000	EACH
36	616-02320 GEOTEXTILES	771.000	SYS
37	616-06405 RIPRAP, REVETMENT	615.000	TON
38	616-06451 RIPRAP, UNIFORM	248.000	TON
39	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
40	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	3,260.000	SYS
41	621-06559 MULCHED SEEDING, R	3,260.000	SYS
42	622-98200 SIGN, DO NOT DISTURB	8.000	EACH
43	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
44	628-09401 FIELD OFFICE, A	9.000	MOS
45	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	18.000	MOS
46	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
47	701-51195 PILE, STEEL H, HP 12 IN X 53	608.000	LFT
48	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	88.000	LFT
49	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	36.000	LFT



CALL ORDER : 200

CONTRACT ID : R -29975-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	715-46005 PIPE END SECTION, 15 IN	6.000	EACH
51	715-46010 PIPE END SECTION, 18 IN	2.000	EACH
52	723-11346 STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS,	68.000	LFT
53	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
54	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
55	801-06625 DETOUR ROUTE MARKER ASSEMBLY	15.000	EACH
56	801-06640 CONSTRUCTION SIGN, A	9.000	EACH
57	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
58	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
59	801-07118 BARRICADE, III-A	72.000	LFT
60	801-07119 BARRICADE, III-B	48.000	LFT
61	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,700.000	LFT
62	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,700.000	LFT
63	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	10.000	EACH
64	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	10.000	EACH

CALL ORDER : 210

CONTRACT ID : R -30330-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	5,360.000	SYS
12	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
13	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	2,400.000	SFT
14	202-03729 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	50.000	LFT
15	202-91385 INLET, REMOVE	1.000	EACH
16	202-96133 PIPE, REMOVE	850.000	LFT
17	203-02000 EXCAVATION, COMMON	8,459.000	CYS
18	205-02770 EROSION CONTROL BLANKET	550.000	SYS
19	205-03371 SEDIMENT, REMOVE	99.000	CYS
20	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	35.000	TON
21	205-06936 TEMPORARY SEDIMENT TRAP	209.000	TON
22	205-06937 TEMPORARY SILT FENCE	1,605.000	LFT
23	205-09543 NO 2 STONE	100.000	TON
24	207-08263 SUBGRADE TREATMENT, TYPE IA	14,739.000	SYS
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,316.000	SYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	239.000	CYS
27	211-09265 STRUCTURAL BACKFILL, TYPE 2	245.000	CYS
28	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,785.000	TON
29	304-07494 WIDENING WITH HMA, TYPE C	744.000	TON
30	306-08034 MILLING, ASPHALT, 1 1/2 IN	11,061.000	SYS
31	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
32	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,613.000	TON
33	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,172.000	TON
34	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	2,830.000	TON
35	402-07432 HMA SURFACE, TYPE A	239.000	TON
36	402-07440 HMA BASE, TYPE A	398.000	TON
37	402-10086 HMA FOR TEMPORARY PAVEMENT, C	100.000	TON
38	406-05520 ASPHALT FOR TACK COAT	10.000	TON
39	601-01626 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 2	2.000	EACH
40	601-01700 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 1	1.000	EACH
41	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
42	601-02241 GUARDRAIL, REMOVE	548.000	LFT
43	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
44	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
45	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	56.250	LFT
46	604-91531 SIDEWALK, CONCRETE, 4 IN	37.000	SYS
47	605-06145 CURB AND GUTTER, B, CONCRETE	1,777.000	LFT
48	610-07487 HMA FOR APPROACHES, TYPE B	354.000	TON
49	610-08446 PCCP FOR APPROACHES, 6 IN	901.000	SYS

CALL ORDER : 210

CONTRACT ID : R -30330-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
50	611-06497 MAILBOX ASSEMBLY, SINGLE	13.000	EACH
51	611-06498 MAILBOX ASSEMBLY, DOUBLE	6.000	EACH
52	615-06505 MONUMENT, B	5.000	EACH
53	616-02320 GEOTEXTILES	1,436.000	SYS
54	616-06405 RIPRAP, REVETMENT	632.000	TON
55	616-06451 RIPRAP, UNIFORM	41.000	TON
56	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
57	621-06545 FERTILIZER	0.400	TON
58	621-06553 SEED MIXTURE, R	170.000	LBS
59	621-06557 SEED MIXTURE, T	300.000	LBS
60	621-06565 MULCHING MATERIAL	6.000	TON
61	621-06567 WATER	34.000	KGAL
62	621-06574 SODDING	356.000	SYS
63	621-06575 SODDING, NURSERY	9,092.000	SYS
64	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
65	628-09403 FIELD OFFICE, C	20.000	MOS
66	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	40.000	MOS
67	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	60.000	MOS
68	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
69	714-11179 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	96.000	LFT
70	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	170.000	LFT
71	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	192.000	LFT
72	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	32.000	LFT
73	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	728.000	LFT
74	715-05173 PIPE, TYPE 3 CIRCULAR 24 IN	40.000	LFT
75	715-46000 PIPE END SECTION, 12 IN	4.000	EACH
76	715-46005 PIPE END SECTION, 15 IN	31.000	EACH
77	715-46020 PIPE END SECTION, 24 IN	6.000	EACH
78	720-45005 INLET, A2	3.000	EACH
79	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
80	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
81	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	19,480.000	LFT
82	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	12,120.000	LFT
83	801-06625 DETOUR ROUTE MARKER ASSEMBLY	30.000	EACH
84	801-06640 CONSTRUCTION SIGN, A	27.000	EACH
85	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
86	801-06710 FLASHING ARROW SIGN	800.000	DAY
87	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
88	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000	EACH
89	801-07119 BARRICADE, III-B	312.000	LFT
90	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	1,270.000	LFT
91	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	237.000	LFT
92	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	42.000	LFT
93	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	17.000	EACH
94	802-07060 SIGN, SHEET, RELOCATE	8.000	EACH
95	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	104.750	SFT
96	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	1,900.000	LFT
97	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8,340.000	LFT
98	808-06716 LINE, REMOVE	1,200.000	LFT

CALL ORDER : 210

CONTRACT ID : R -30330-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
99 808-09381	RETRO-REFLECTIVITY TESTING	LUMP	LUMP
100 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	8,752.000	LFT
101 808-75290	TRANSVERSE MARKING, THERMOPLASTIC,	110.000	LFT
102 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	94.000	LFT
103 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	6.000	EACH
104 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	174.000	EACH
105 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	174.000	EACH
106 808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	1,440.000	LFT

CALL ORDER : 220

CONTRACT ID : R -31882-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-02245 TREE, 6 IN, REMOVE	2.000	EACH
11	201-02250 TREE, 10 IN, REMOVE	2.000	EACH
12	201-02255 TREE, 18 IN, REMOVE	2.000	EACH
13	201-02260 TREE, 30 IN, REMOVE	2.000	EACH
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02278 CURB, CONCRETE, REMOVE	4,675.000	LFT
16	202-03875 CONCRETE STEPS, REMOVE	11.000	EACH
17	202-52710 SIDEWALK, CONCRETE, REMOVE	3,277.000	SYS
18	202-91385 INLET, REMOVE	7.000	EACH
19	202-96133 PIPE, REMOVE	162.000	LFT
20	203-02000 EXCAVATION, COMMON	1,270.000	CYS
21	203-02070 BORROW	165.000	CYS
22	205-03371 SEDIMENT, REMOVE	739.000	CYS
23	205-06937 TEMPORARY SILT FENCE	3,404.000	LFT
24	207-08265 SUBGRADE TREATMENT, TYPE IIA	3,645.000	SYS
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	808.000	SYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	3,947.000	CYS
27	211-09265 STRUCTURAL BACKFILL, TYPE 2	812.000	CYS
28	302-06464 SUBBASE FOR PCCP	561.000	CYS
29	305-95873 PAVEMENT, BRICK, REMOVE AND SALVAGE	1,866.000	SYS
30	306-08034 MILLING, ASPHALT, 1 1/2 IN	6,320.000	SYS
31	306-10163 MILLING ASPHALT, 2 1/2 IN	8,500.000	SYS
32	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,447.000	TON
33	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	3,089.000	TON
34	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	813.000	TON
35	402-09873 STAMPED	1,464.000	SFT
36	406-05520 ASPHALT FOR TACK COAT	10.000	TON
37	502-06457 PCCP, 9 IN	2,659.000	SYS
38	502-06457 PCCP, 9 IN	120.000	SYS
39	503-05240 D-1 CONTRACTION JOINT	1,167.500	LFT
40	604-01268 HAND RAIL, ALUMINUM	5.000	LFT
41	604-07900 CURB RAMP, CONCRETE, F	37.000	SYS
42	604-07901 CURB RAMP, CONCRETE, G	4.000	SYS
43	604-07902 CURB RAMP, CONCRETE, H	169.000	SYS
44	604-44251 STEPS, CONCRETE	7.500	CYS
45	604-91404 SIDEWALK, CONCRETE, 5 IN	838.000	SYS
46	604-91531 SIDEWALK, CONCRETE, 4 IN	1,909.000	SYS
47	605-06090 CURB, INTEGRAL, CONCRETE	733.000	LFT
48	605-06120 CURB, CONCRETE	431.000	LFT
49	605-06140 CURB AND GUTTER, CONCRETE	4,389.000	LFT

CALL ORDER : 220

CONTRACT ID : R -31882-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	605-92578 CURB WALK, CONCRETE	14.000	SYS
51	610-07486 HMA FOR APPROACHES, TYPE A	299.000	TON
52	610-08446 PCCP FOR APPROACHES, 6 IN	469.000	SYS
53	610-09108 PCCP FOR APPROACHES, 9 IN	340.000	SYS
54	611-02825 MAILBOX ASSEMBLY, TRIPLE	5.000	EACH
55	611-06498 MAILBOX ASSEMBLY, DOUBLE	23.000	EACH
56	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
57	621-06567 WATER	10.000	KGAL
58	621-06575 SODDING, NURSERY	2,378.000	SYS
59	622-04648 TREE GRATE	5.000	EACH
60	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN	5.000	EACH
61	628-09401 FIELD OFFICE, A	12.000	MOS
62	702-03607 CORED HOLE IN CONCRETE	6.000	EACH
63	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	779.000	LFT
64	715-05146 PIPE, TYPE 2 CIRCULAR 6 IN	61.000	LFT
65	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	878.000	LFT
66	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	744.000	LFT
67	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	867.000	LFT
68	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	150.000	TON
69	718-52610 AGGREGATE FOR UNDERDRAINS	70.000	CYS
70	718-99153 GEOTEXTILES FOR UNDERDRAIN	683.000	SYS
71	720-01092 MANHOLE, J15, MODIFIED	4.000	EACH
72	720-02442 PIPE, PLUG EXISTING	2.000	EACH
73	720-07309 TRENCH DRAIN	55.000	LFT
74	720-44000 CASTING, ADJUST TO GRADE	7.000	EACH
75	720-45410 MANHOLE, C4	3.000	EACH
76	720-95422 MANHOLE, J4	3.000	EACH
77	720-98174 INLET, B15	1.000	EACH
78	720-98555 INLET, C15	1.000	EACH
79	720-99416 CATCH BASIN, B15	12.000	EACH
80	720-99417 CATCH BASIN, C15	3.000	EACH
81	732-08419 MODULAR BLOCK WALL	21.000	SYS
82	732-08421 MODULAR BLOCK WALL ERECTION	21.000	SYS
83	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
84	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
85	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	9,691.000	LFT
86	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	7,140.000	LFT
87	801-06625 DETOUR ROUTE MARKER ASSEMBLY	38.000	EACH
88	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
89	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
90	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
91	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	307.500	LFT
92	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	121.630	SFT
93	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	9.000	SFT
94	802-99058 SIGN SHEET, INSTALL	4.000	EACH
95	802-99058 SIGN SHEET, INSTALL	4.000	EACH
96	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
97	805-01816 SIGNAL SUPPORT FOUNDATION, 36 IN X 36 IN X 96 IN	1.000	EACH
98	805-01879 SIGNAL SERVICE, INSTALL	1.000	EACH

CALL ORDER : 220

CONTRACT ID : R -31882-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
99	805-02077 SIGNAL CANTILEVER STRUCTURE, MAST ARM 40FT	1.000	EACH
100	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
101	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN RED	8.000	EACH
102	805-78480 SIGNAL CABLE, 3C/14GA	358.000	LFT
103	807-02191 HANDHOLE, LIGHTING	2.000	EACH
104	807-04143 LIGHT STANDARD, 14 FT EMH, 12 FT, DECORATIVE	7.000	EACH
105	807-04143 LIGHT STANDARD, 14 FT EMH, 12 FT, DECORATIVE	1.000	EACH
106	807-04653 LIGHTING FOUNDATION,	7.000	EACH
107	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	988.000	LFT
108	807-86805 SERVICE POINT, I	1.000	EACH
109	807-86889 CABLE, POLE CIRCUIT THWH, NO10 COPPER, STRANDED, 1/C	420.000	LFT
110	807-86910 CONNECTOR KIT, UNFUSED	7.000	EACH
111	807-86915 CONNECTOR KIT, FUSED	7.000	EACH
112	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	9.000	EACH
113	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.000	EACH
114	807-86930 INSULATION LINK, NON-WATERPROOFED	14.000	EACH
115	807-86935 INSULATION LINK, WATERPROOFED	12.000	EACH
116	807-93647 LUMINAIRE, POST TOP, HIGH PRESSURE SODIUM, 150 WATT	7.000	EACH
117	807-93647 LUMINAIRE, POST TOP, HIGH PRESSURE SODIUM, 150 WATT	1.000	EACH
118	807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	232.000	LFT
119	808-02977 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	8.000	EACH
120	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
121	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	511.000	LFT
122	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	728.000	LFT
123	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	87.000	LFT
124	808-10056 TRANSVERSE MARKING, MULTI-COMPONENT,	92.000	LFT
125	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	7,879.000	LFT
126	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	140.000	LFT
127	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	7,853.000	LFT
128	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	128.000	LFT
129	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	204.000	LFT
130	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	8.000	EACH
131	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	3.000	EACH

CALL ORDER : 230

CONTRACT ID : R -33078-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	303-07449 COMPACTED AGGREGATE, NO. 73	1,188.000	TON
9	304-07783 HMA PATCHING, TYPE D	1,500.000	TON
10	306-08042 MILLING, SCARIFICATION/PROFILE	53,779.000	SYS
11	306-08043 MILLING, TRANSITION	1,442.000	SYS
12	306-08432 MILLING, APPROACH	705.000	SYS
13	402-07435 HMA INTERMEDIATE, TYPE A	6,211.000	TON
14	402-07784 HMA SURFACE, TYPE D	4,731.000	TON
15	402-07787 HMA WEDGE AND LEVEL, TYPE D	932.000	TON
16	406-05520 ASPHALT FOR TACK COAT	19.000	TON
17	610-07788 HMA FOR APPROACHES, TYPE D	81.000	TON
18	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	2.000	MOS
19	628-09409 MOBILE INTERNET SERVICE	2.000	MOS
20	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
21	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	46,596.000	LFT
24	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	2,762.000	LFT
25	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	24,200.000	LFT
26	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	80.000	LFT
27	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH



CALL ORDER : 240

CONTRACT ID : R -33255-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT SMALL STRUCTURE PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-02245 TREE, 6 IN, REMOVE	3.000	EACH
9	616-02320 GEOTEXTILES	135.000	SYS
10	616-06451 RIPRAP, UNIFORM	80.000	TON
11	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
12	621-01620 MULCHED SEEDING, LEGUME, 1	600.000	SYS
13	621-06567 WATER	1.500	KGAL
14	621-06626 MULCHED SEEDING, D	400.000	SYS
15	622-52436 SIGN, DO NOT MOW OR SPRAY	8.000	EACH
16	725-11019 LINER PIPE THERMOPLASTIC DEFORMED 10.3-12.6 SFT	485.000	LFT
17	725-11038 LINER PIPE THERMOPLASTIC CIRCULAR 15.9-16.0 SFT	190.000	LFT
18	725-11039 LINER PIPE THERMOPLASTIC CIRCULAR 19.6-19.7 SFT	207.000	LFT
19	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
20	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
21	801-06710 FLASHING ARROW SIGN	90.000	DAY
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 250

CONTRACT ID : R -33373-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PIPE LINING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-96531 FENCE, RIGHT-OF-WAY, REMOVE	75.000	LFT
9	202-98488 PIPE END SECTION, REMOVE	4.000	EACH
10	616-02320 GEOTEXTILES	14.500	SYS
11	616-05688 RIPRAP, CLASS 1	4.000	TON
12	616-05689 RIPRAP, CLASS 2	8.000	TON
13	616-06405 RIPRAP, REVETMENT	1.500	TON
14	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
15	628-09402 FIELD OFFICE, B	6.000	MOS
16	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
17	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
18	715-04857 SAFETY METAL END SECTION	2.000	EACH
19	715-07579 SAFETY METAL END SEC 6:1 MIN AREA 2.9SF	2.000	EACH
20	725-10225 LINER PIPE, THERMOPLASTIC, CIRCULAR, 10.7-10.8 SFT	162.000	LFT
21	725-11008 LINER PIPE THERMOPLASTIC DEFORMED 1.5-1.8 SFT	221.000	LFT
22	725-11039 LINER PIPE THERMOPLASTIC CIRCULAR 19.6-19.7 SFT	265.000	LFT
23	725-11399 PIPE LINER, CURED-IN-PLACE, 84 IN.	225.000	LFT
24	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	16.000	EACH
25	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
26	801-06640 CONSTRUCTION SIGN, A	32.000	EACH
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 260

CONTRACT ID : R -33652-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PIPE LINING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-06541 REMOVE	2.000	EACH
8	205-06932 TEMPORARY CHECK DAM, STRAW BALES	25.000	LFT
9	205-06937 TEMPORARY SILT FENCE	100.000	LFT
10	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
11	621-06559 MULCHED SEEDING, R	100.000	SYS
12	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
13	628-09402 FIELD OFFICE, B	4.000	MOS
14	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	4.000	MOS
15	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
16	715-05841 CONCRETE ANCHOR 60 IN	2.000	EACH
17	716-07782 PIPE INSTALLATION, TRENCHLESS, 60 IN	180.000	LFT
18	725-10245 PERPETUATION, EXISTING PIPE	1.000	EACH
19	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
20	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 270

CONTRACT ID : R -34075-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02272 PAVED SIDE DITCH, REMOVE	10.000	LFT
10	202-02278 CURB, CONCRETE, REMOVE	224.000	LFT
11	202-52710 SIDEWALK, CONCRETE, REMOVE	73.000	SYS
12	203-02000 EXCAVATION, COMMON	2,122.000	CYS
13	205-06933 TEMPORARY DITCH INLET PROTECTION	13.000	EACH
14	205-06934 TEMPORARY MULCHING	4.200	TON
15	205-06937 TEMPORARY SILT FENCE	1,272.000	LFT
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,133.000	SYS
17	207-09934 SUBGRADE TREATMENT, TYPE 1B	6,950.000	SYS
18	210-09475 STORMWATER QUALITY STRUCTURE	1.000	EACH
19	211-09265 STRUCTURAL BACKFILL, TYPE 2	926.000	CYS
20	211-09268 STRUCTURAL BACKFILL, TYPE 5	1.000	CYS
21	303-01180 COMPACTED AGGREGATE, NO. 53	2,232.000	TON
22	303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS	100.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	534.000	SYS
24	402-07433 HMA SURFACE, TYPE B	505.000	TON
25	402-07438 HMA INTERMEDIATE, TYPE B	1,087.000	TON
26	406-05520 ASPHALT FOR TACK COAT	3.000	TON
27	604-07894 CURB RAMP, CONCRETE, A	18.000	SYS
28	604-07897 CURB RAMP, CONCRETE, C	8.000	SYS
29	604-07901 CURB RAMP, CONCRETE, G	18.000	SYS
30	604-91531 SIDEWALK, CONCRETE, 4 IN	184.000	SYS
31	605-06140 CURB AND GUTTER, CONCRETE	3,255.000	LFT
32	610-08446 PCCP FOR APPROACHES, 6 IN	652.000	SYS
33	610-09108 PCCP FOR APPROACHES, 9 IN	248.000	SYS
34	611-06497 MAILBOX ASSEMBLY, SINGLE	15.000	EACH
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.000	EACH
36	621-06557 SEED MIXTURE, T	320.000	LBS
37	621-06567 WATER	3.400	KGAL
38	621-06574 SODDING	3,440.000	SYS
39	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
40	628-09403 FIELD OFFICE, C	12.000	MOS
41	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	12.000	MOS
42	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
43	715-05032 PIPE, TYPE 2 CIRCULAR 15 IN	39.000	LFT
44	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	50.000	LFT
45	715-05049 PIPE, TYPE 4 CIRCULAR 8 IN	58.000	LFT
46	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,009.000	LFT
47	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	279.000	LFT
48	715-05153 PIPE, TYPE 2 CIRCULAR 21 IN	577.000	LFT
49	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	356.000	LFT

CALL ORDER : 270

CONTRACT ID : R -34075-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	715-05155 PIPE, TYPE 2 CIRCULAR 27 IN	16.000	LFT
51	715-05168 PIPE, TYPE 3 CIRCULAR 12 IN	104.000	LFT
52	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	54.000	LFT
53	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	94.000	TON
54	715-09064 VIDEO INSPECTION FOR PIPE	2,542.000	LFT
55	715-46000 PIPE END SECTION, 12 IN	2.000	EACH
56	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
57	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
58	720-45070 INLET, P12A	1.000	EACH
59	720-45235 CATCH BASIN, E7	2.000	EACH
60	720-45260 PIPE CATCH BASIN, 12 IN	7.000	EACH
61	720-45410 MANHOLE, C4	14.000	EACH
62	720-92884 MANHOLE, K4, MODIFIED	1.000	EACH
63	720-95422 MANHOLE, J4	1.000	EACH
64	720-98174 INLET, B15	6.000	EACH
65	720-98555 INLET, C15	4.000	EACH
66	720-99416 CATCH BASIN, B15	3.000	EACH
67	720-99417 CATCH BASIN, C15	11.000	EACH
68	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
69	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	100.000	LFT
70	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
71	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
72	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
73	801-07118 BARRICADE, III-A	96.000	LFT
74	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	183.000	LFT
75	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	103.000	SFT
76	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	9.000	SFT
77	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	3,660.000	LFT
78	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	85.000	LFT
79	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	233.000	LFT

CALL ORDER : 300

CONTRACT ID : RS-30917-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-93741 GUARDRAIL END TREATMENT, REMOVE	8.000	EACH
11	303-07449 COMPACTED AGGREGATE, NO. 73	7,162.000	TON
12	304-07490 HMA PATCHING, TYPE B	200.000	TON
13	306-08033 MILLING, ASPHALT, 1 IN	76,991.000	SYS
14	306-08043 MILLING, TRANSITION	1,500.000	SYS
15	306-08432 MILLING, APPROACH	5,174.000	SYS
16	306-08595 MILLING ASPHALT, 3 1/2 IN	1,790.000	SYS
17	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	6,655.000	TON
18	401-07371 QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm	8,875.000	TON
19	406-05520 ASPHALT FOR TACK COAT	43.800	TON
20	601-02241 GUARDRAIL, REMOVE	500.000	LFT
21	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
22	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	8.000	EACH
23	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	8.000	EACH
24	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
25	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	500.000	LFT
26	606-09729 MILLED CENTERLINE CORRUGATIONS	29,949.000	LFT
27	610-07487 HMA FOR APPROACHES, TYPE B	854.000	TON
28	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	115.000	TON
29	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
30	612-60410 DRILLED HOLE FOR UNDERSEAL	1,920.000	EACH
31	615-06527 MONUMENT, SECTION CORNER	10.000	EACH
32	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
33	628-09402 FIELD OFFICE, B	6.000	MOS
34	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
35	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	18.000	MOS
36	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
37	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
38	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
39	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
40	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	6,000.000	LFT
41	801-06209 TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN	3,000.000	LFT
42	801-06640 CONSTRUCTION SIGN, A	17.000	EACH
43	801-06710 FLASHING ARROW SIGN	60.000	DAY
44	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
45	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	4.500	SFT
46	802-76055 SIGN POST, A	11.000	LFT
47	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	1.000	EACH
48	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	59,044.000	LFT
49	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP

CALL ORDER : 300

CONTRACT ID : RS-30917-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	7,230.000	LFT
51 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	3,726.000	LFT
52 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	48.000	LFT
53 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	405.000	EACH
54 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	405.000	EACH

CALL ORDER : 310

CONTRACT ID : RS-31987-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SURFACE TREATMENT, MICROSURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	303-01180 COMPACTED AGGREGATE, NO. 53	50.000	TON
10	304-07490 HMA PATCHING, TYPE B	919.000	TON
11	306-08043 MILLING, TRANSITION	1,000.000	SYS
12	406-05520 ASPHALT FOR TACK COAT	0.200	TON
13	411-09521 MICRO-SURFACING, WARRANTED, MULTIPLE COURSE	278,100.000	SYS
14	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	2.000	TON
15	612-60410 DRILLED HOLE FOR UNDERSEAL	34.000	EACH
16	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
17	628-09402 FIELD OFFICE, B	6.000	MOS
18	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
19	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	12.000	MOS
20	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
21	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
22	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
23	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	19,970.000	LFT
24	801-06640 CONSTRUCTION SIGN, A	64.000	EACH
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	12,564.000	LFT
27	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	164,026.000	LFT
28	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	90,554.000	LFT
29	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
30	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN	1,690.000	LFT
31	808-75035 LINE, PAINT, SOLID, WHITE, 24 IN	800.000	LFT
32	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	60.000	LFT
33	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	17.000	EACH
34	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	7.000	EACH
35	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,790.000	EACH
36	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,790.000	EACH
37	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	22.000	EACH



CALL ORDER : 320

CONTRACT ID : RS-34094-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	306-08043 MILLING, TRANSITION	20.000	SYS
10	402-05497 HMA FOR PARK ROAD	150.000	TON
11	404-05512 SEAL COAT, 3	48,265.000	SYS
12	406-05520 ASPHALT FOR TACK COAT	0.500	TON
13	615-97768 PARKING BARRIER, RESET	343.000	EACH
14	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
15	628-09402 FIELD OFFICE, B	10.000	MOS
16	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	20.000	MOS
17	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
18	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
21	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	12,420.000	LFT

CALL ORDER : 330

CONTRACT ID : RS-34109-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DNR PROPERTIES PROJECT (ROAD)		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	304-07489 HMA PATCHING, TYPE A	50.000	TON
9	402-07450 HMA WEDGE AND LEVEL, TYPE A	3,400.000	TON
10	406-05520 ASPHALT FOR TACK COAT	11.000	TON
11	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
12	628-09402 FIELD OFFICE, B	6.000	MOS
13	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
14	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
15	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
16	801-03290 CONSTRUCTION SIGN, C	1.000	EACH
17	801-06640 CONSTRUCTION SIGN, A	3.000	EACH
18	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
19	808-03442 PAVEMENT MESSAGE MARKING, PAINT, BIKE SYMBOL	15.000	EACH
20	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	7,500.000	LFT

CALL ORDER : 340

CONTRACT ID : RS-34210-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SURFACE TREATMENT, ULTRATHIN BONDED		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	303-07449 COMPACTED AGGREGATE, NO. 73	850.000	TON
9	304-07491 HMA PATCHING, TYPE C	150.000	TON
10	306-08043 MILLING, TRANSITION	280.000	SYS
11	402-09325 ULTRATHIN BONDED WEARING COURSE	72,000.000	SYS
12	406-05520 ASPHALT FOR TACK COAT	1.000	TON
13	408-07478 CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	2.000	TON
14	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
15	628-09402 FIELD OFFICE, B	10.000	MOS
16	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	20.000	MOS
17	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
18	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
19	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	2,350.000	LFT
20	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	1,000.000	LFT
23	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	46,000.000	LFT
24	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	42,000.000	LFT
25	808-06716 LINE, REMOVE	89,000.000	LFT
26	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
27	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	575.000	EACH
28	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	575.000	EACH

CALL ORDER : 380

CONTRACT ID : B -29428-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
8	203-02000 EXCAVATION, COMMON	1,825.000	CYS
9	203-02070 BORROW	2,688.000	CYS
10	203-51223 EXCAVATION, WATERWAY	978.000	CYS
11	205-03371 SEDIMENT, REMOVE	36.000	CYS
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	59.400	TON
13	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
14	205-06934 TEMPORARY MULCHING	2.200	TON
15	205-06937 TEMPORARY SILT FENCE	935.000	LFT
16	206-51215 EXCAVATION, X	520.000	CYS
17	206-51220 EXCAVATION, WET	196.000	CYS
18	207-08266 SUBGRADE TREATMENT, TYPE III	5,593.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	356.000	SYS
20	211-09264 STRUCTURAL BACKFILL, TYPE 1	263.100	CYS
21	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	300.000	CYS
22	302-07455 DENSE GRADED SUBBASE	23.000	CYS
23	303-01180 COMPACTED AGGREGATE, NO. 53	145.000	TON
24	402-07432 HMA SURFACE, TYPE A	410.000	TON
25	402-07435 HMA INTERMEDIATE, TYPE A	682.000	TON
26	402-07440 HMA BASE, TYPE A	1,690.000	TON
27	402-07450 HMA WEDGE AND LEVEL, TYPE A	40.000	TON
28	406-05520 ASPHALT FOR TACK COAT	27.700	TON
29	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
30	601-01626 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
31	601-01701 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
32	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
33	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	200.000	LFT
34	602-06729 BARRIER DELINEATOR	8.000	EACH
35	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	140.000	SYS
36	610-07486 HMA FOR APPROACHES, TYPE A	99.000	TON
37	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
38	615-06505 MONUMENT, B	10.000	EACH
39	615-06510 MONUMENT, C	2.000	EACH
40	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
41	616-02320 GEOTEXTILES	394.000	SYS
42	616-05688 RIPRAP, CLASS 1	170.000	TON
43	616-06405 RIPRAP, REVETMENT	18.000	TON
44	616-06451 RIPRAP, UNIFORM	131.000	TON
45	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
46	621-03909 SEED MIXTURE, NATIVE	30.000	LBS
47	621-06545 FERTILIZER	0.110	TON
48	621-06557 SEED MIXTURE, T	85.000	LBS
49	621-06559 MULCHED SEEDING, R	2,000.000	SYS

CALL ORDER : 380

CONTRACT ID : B -29428-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06567 WATER	12.000	KGAL
51	621-06574 SODDING	260.000	SYS
52	621-06575 SODDING, NURSERY	5,120.000	SYS
53	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	25.000	EACH
54	628-09402 FIELD OFFICE, B	6.000	MOS
55	702-51005 CONCRETE, A, SUBSTRUCTURE	170.900	CYS
56	702-51010 CONCRETE, B, ABOVE FOOTINGS	82.000	CYS
57	702-51015 CONCRETE, B, FOOTINGS	95.300	CYS
58	703-06028 REINFORCING BARS	30,462.000	LBS
59	703-06029 REINFORCING BARS, EPOXY COATED	65,830.000	LBS
60	704-51002 CONCRETE, C, SUPERSTRUCTURE	221.800	CYS
61	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
62	706-51020 RAILING, CONCRETE, C	18.400	CYS
63	709-51821 SURFACE SEAL	LUMP	LUMP
64	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	120.000	LFT
65	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	112.000	LFT
66	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	46.000	LFT
67	720-45005 INLET, A2	2.000	EACH
68	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
69	801-06625 DETOUR ROUTE MARKER ASSEMBLY	12.000	EACH
70	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
71	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
72	801-07118 BARRICADE, III-A	64.000	LFT
73	801-07119 BARRICADE, III-B	32.000	LFT
74	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	93.000	LFT
75	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	42.250	SFT
76	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,704.000	LFT
77	808-06726 TRANSVERSE MARKING, PAINT,	23.000	LFT
78	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,752.000	LFT

CALL ORDER : 390

CONTRACT ID : B -29596-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	30.000	CYS
10	205-06932 TEMPORARY CHECK DAM, STRAW BALES	85.000	LFT
11	205-06937 TEMPORARY SILT FENCE	340.000	LFT
12	302-07455 DENSE GRADED SUBBASE	12.000	CYS
13	303-01180 COMPACTED AGGREGATE, NO. 53	8.000	TON
14	304-07490 HMA PATCHING, TYPE B	1.000	TON
15	306-08034 MILLING, ASPHALT, 1 1/2 IN	39.000	SYS
16	406-05521 ASPHALT FOR TACK COAT	39.000	SYS
17	605-06105 CURB, INTEGRAL, CONCRETE, MODIFIED	82.000	LFT
18	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	67.000	SYS
19	610-07487 HMA FOR APPROACHES, TYPE B	4.000	TON
20	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
21	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
22	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
23	621-06559 MULCHED SEEDING, R	162.000	SYS
24	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
25	628-09402 FIELD OFFICE, B	12.000	MOS
26	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	12.000	MOS
27	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
28	702-51863 FIELD DRILLED HOLE IN CONCRETE	58.000	EACH
29	703-06029 REINFORCING BARS, EPOXY COATED	2,669.000	LBS
30	706-04683 RAILING,	129.000	LFT
31	710-09158 PATCHING CONCRETE STRUCTURES	3.000	SFT
32	711-51038 STRUCTURAL STEEL	LUMP	LUMP
33	711-51864 DRILLED HOLE	1,094.000	EACH
34	711-91149 STRAIGHTEN STEEL BEAM	LUMP	LUMP
35	712-94080 TIMBER DECK	3,312.000	SFT
36	712-95676 LUMBER AND TIMBER, TREATED	3.000	MFBM
37	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
38	801-06625 DETOUR ROUTE MARKER ASSEMBLY	23.000	EACH
39	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
40	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
41	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
42	801-07118 BARRICADE, III-A	48.000	LFT
43	801-07119 BARRICADE, III-B	96.000	LFT
44	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	91.500	LFT
45	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	4.000	EACH
46	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	59.500	SFT

CALL ORDER : 400

CONTRACT ID : B -29699-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	26,405.000	CYS
11	205-03371 SEDIMENT, REMOVE	427.000	CYS
12	205-06930 SPLASHPAD, RIPRAP	7.000	TON
13	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	223.000	TON
14	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
15	205-06934 TEMPORARY MULCHING	22.000	TON
16	205-06936 TEMPORARY SEDIMENT TRAP	174.000	TON
17	205-06937 TEMPORARY SILT FENCE	2,694.000	LFT
18	205-06938 TEMPORARY SLOPE DRAIN	160.000	LFT
19	205-09543 NO 2 STONE	100.000	TON
20	207-08264 SUBGRADE TREATMENT, TYPE II	9,502.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	286.000	SYS
22	211-02050 B BORROW	2,015.000	CYS
23	211-06467 AGGREGATE FOR END BENT BACKFILL	112.000	CYS
24	211-09264 STRUCTURAL BACKFILL, TYPE 1	110.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,601.000	TON
26	302-07455 DENSE GRADED SUBBASE	65.000	CYS
27	303-01180 COMPACTED AGGREGATE, NO. 53	1,703.000	TON
28	303-07449 COMPACTED AGGREGATE, NO. 73	78.000	TON
29	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	609.000	TON
30	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,445.000	TON
31	402-07432 HMA SURFACE, TYPE A	93.000	TON
32	406-05520 ASPHALT FOR TACK COAT	2.000	TON
33	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
34	601-05999 CURVED TERMINAL END	4.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
36	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	550.000	LFT
37	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	391.000	SYS
38	610-07486 HMA FOR APPROACHES, TYPE A	183.000	TON
39	610-07487 HMA FOR APPROACHES, TYPE B	80.000	TON
40	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
41	615-06505 MONUMENT, B	9.000	EACH
42	615-06510 MONUMENT, C	2.000	EACH
43	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
44	616-02320 GEOTEXTILES	2,836.000	SYS
45	616-05689 RIPRAP, CLASS 2	2,491.000	TON
46	616-06405 RIPRAP, REVETMENT	524.000	TON
47	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	14.000	EACH
48	621-06545 FERTILIZER	4.000	TON
49	621-06553 SEED MIXTURE, R	1,324.000	LBS

CALL ORDER : 400

CONTRACT ID : B -29699-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06557 SEED MIXTURE, T	696.000	LBS
51	621-06565 MULCHING MATERIAL	16.000	TON
52	621-06567 WATER	2.000	KGAL
53	621-06574 SODDING	502.000	SYS
54	628-09402 FIELD OFFICE, B	12.000	MOS
55	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
56	701-05561 DRILLED SHAFT	723.000	LFT
57	701-05785 EXPLORATION (SHAFT EXCAVATION)	723.000	LFT
58	701-09663 PILE, STEEL PIPE, 0.312 IN, 14 IN	1,398.000	LFT
59	701-09679 CONICAL PILE TIP, 14 IN	28.000	EACH
60	702-51005 CONCRETE, A, SUBSTRUCTURE	385.600	CYS
61	702-51100 DRAIN PIPE, CAST IRON, 6 IN	452.000	LBS
62	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	480.000	LBS
63	703-06028 REINFORCING BARS	148,962.000	LBS
64	703-06029 REINFORCING BARS, EPOXY COATED	225,840.000	LBS
65	704-51002 CONCRETE, C, SUPERSTRUCTURE	651.700	CYS
66	706-06352 CONCRETE BRIDGE RAILING TRANSITION, TPF-2	4.000	EACH
67	706-09963 RAILING, CONCRETE, PF-2	1,002.000	LFT
68	706-51020 RAILING, CONCRETE, C	46.200	CYS
69	707-07605 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 54 IN X 48 IN	1,950.000	LFT
70	709-51821 SURFACE SEAL	LUMP	LUMP
71	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	62.000	LFT
72	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	128.000	LFT
73	715-05407 PIPE, END BENT DRAIN, 6 IN	230.000	LFT
74	715-07536 CONCRETE ANCHOR MIN AREA 12.9 SF	2.000	EACH
75	715-08171 PIPE, TYPE 1 DEFORMED MIN AREA 12.9 SF	60.000	LFT
76	715-46000 PIPE END SECTION, 12 IN	1.000	EACH
77	715-46005 PIPE END SECTION, 15 IN	4.000	EACH
78	720-45030 INLET, E7	1.000	EACH
79	720-45035 INLET, F7	1.000	EACH
80	724-51925 STRUCTURAL EXPANSION JOINT, SS	156.000	LFT
81	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
82	801-06625 DETOUR ROUTE MARKER ASSEMBLY	14.000	EACH
83	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
84	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
85	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
86	801-07118 BARRICADE, III-A	144.000	LFT
87	801-07119 BARRICADE, III-B	96.000	LFT
88	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	38.000	LFT
89	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	19.000	SFT
90	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	6,552.000	LFT
91	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	6,552.000	LFT



CALL ORDER : 410

CONTRACT ID : B -29976-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	166.000	SYS
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	202-91385 INLET, REMOVE	1.000	EACH
12	202-96133 PIPE, REMOVE	25.000	LFT
13	203-02000 EXCAVATION, COMMON	335.000	CYS
14	205-06934 TEMPORARY MULCHING	1.000	TON
15	205-06937 TEMPORARY SILT FENCE	360.000	LFT
16	205-09543 NO 2 STONE	100.000	TON
17	206-93520 TEMPORARY SHEET PILING	2,052.000	SFT
18	207-08263 SUBGRADE TREATMENT, TYPE IA	1,142.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	152.000	SYS
20	211-09264 STRUCTURAL BACKFILL, TYPE 1	10.000	CYS
21	211-09266 STRUCTURAL BACKFILL, TYPE 3	24.000	CYS
22	211-09268 STRUCTURAL BACKFILL, TYPE 5	397.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	93.000	TON
24	303-01180 COMPACTED AGGREGATE, NO. 53	179.000	TON
25	306-08042 MILLING, SCARIFICATION/PROFILE	537.000	SYS
26	402-07432 HMA SURFACE, TYPE A	20.000	TON
27	402-07434 HMA SURFACE, TYPE C	105.000	TON
28	402-07435 HMA INTERMEDIATE, TYPE A	32.000	TON
29	402-07439 HMA INTERMEDIATE, TYPE C	164.000	TON
30	402-07442 HMA BASE, TYPE C	255.000	TON
31	406-05521 ASPHALT FOR TACK COAT	3,655.000	SYS
32	601-02241 GUARDRAIL, REMOVE	131.000	LFT
33	601-02800 GUARDRAIL TRANSITION, TGT	1.000	EACH
34	601-02800 GUARDRAIL TRANSITION, TGT	2.000	EACH
35	601-04793 GUARDRAIL	31.250	LFT
36	601-05999 CURVED TERMINAL END	3.000	EACH
37	601-06053 GUARDRAIL	3.000	EACH
38	601-08182 GUARDRAIL, THRIE BEAM	12.500	LFT
39	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	31.250	LFT
40	604-91531 SIDEWALK, CONCRETE, 4 IN	47.000	SYS
41	604-91531 SIDEWALK, CONCRETE, 4 IN	15.000	SYS
42	605-06140 CURB AND GUTTER, CONCRETE	109.000	LFT
43	605-06150 CURB AND GUTTER, C, CONCRETE	60.000	LFT
44	610-07487 HMA FOR APPROACHES, TYPE B	42.000	TON
45	615-06490 RIGHT OF WAY MARKER	5.000	EACH
46	615-06505 MONUMENT, B	3.000	EACH
47	616-02320 GEOTEXTILES	419.000	SYS
48	616-06405 RIPRAP, REVETMENT	284.000	TON
49	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH

CALL ORDER : 410

CONTRACT ID : B -29976-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06557 SEED MIXTURE, T	30.000	LBS
51	621-06560 MULCHED SEEDING, U	606.000	SYS
52	621-06567 WATER	1.000	KGAL
53	621-06575 SODDING, NURSERY	207.000	SYS
54	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
55	628-09402 FIELD OFFICE, B	12.000	MOS
56	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
57	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	24.000	MOS
58	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
59	706-06347 RAILING, STEEL CF-1	40.000	LFT
60	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	82.000	LFT
61	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	24.000	LFT
62	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	29.000	LFT
63	715-06566 PIPE EXTENSION, CIRCULAR, 6 IN.	2.000	LFT
64	715-46000 PIPE END SECTION, 12 IN	1.000	EACH
65	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
66	720-98174 INLET, B15	1.000	EACH
67	723-11341 STRUCTURE, COATED REINFORCED CONCRETE THREE-SIDED SECTIONS,	73.000	LFT
68	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	40.000	SYS
69	732-08421 MODULAR BLOCK WALL ERECTION	40.000	SYS
70	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
71	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
72	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
73	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	575.000	LFT
74	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,440.000	LFT
75	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24"	59.000	LFT
76	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
77	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
78	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
79	801-07119 BARRICADE, III-B	240.000	LFT
80	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	257.000	LFT
81	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	34.000	LFT
82	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	4.000	EACH
83	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
84	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	12.000	SFT
85	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	7.000	SFT
86	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	497.000	LFT
87	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,094.000	LFT
88	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	47.000	LFT

CALL ORDER : 420

CONTRACT ID : B -30464-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT SMALL STRUCTURE PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	356.000	SYS
10	202-02272 PAVED SIDE DITCH, REMOVE	75.000	LFT
11	202-02276 GUTTER TURNOUT, REINFORCED CONCRETE, REMOVE	4.000	EACH
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	202-96133 PIPE, REMOVE	80.000	LFT
14	203-02070 BORROW	137.000	CYS
15	205-03371 SEDIMENT, REMOVE	10.000	CYS
16	205-06936 TEMPORARY SEDIMENT TRAP	50.000	TON
17	205-09543 NO 2 STONE	100.000	TON
18	207-08263 SUBGRADE TREATMENT, TYPE IA	321.000	SYS
19	211-09265 STRUCTURAL BACKFILL, TYPE 2	119.000	CYS
20	211-09268 STRUCTURAL BACKFILL, TYPE 5	149.000	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	20.100	TON
22	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,991.000	SYS
23	402-07433 HMA SURFACE, TYPE B	29.300	TON
24	402-07438 HMA INTERMEDIATE, TYPE B	58.700	TON
25	402-07441 HMA BASE, TYPE B	136.900	TON
26	402-07451 HMA WEDGE AND LEVEL, TYPE B	333.200	TON
27	406-05520 ASPHALT FOR TACK COAT	0.800	TON
28	601-02241 GUARDRAIL, REMOVE	850.000	LFT
29	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
30	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
31	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
32	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
33	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	507.000	LFT
34	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	460.000	LFT
35	605-09131 CURB AND GUTTER TURNOUT CONCRETE	28.000	LFT
36	615-06490 RIGHT OF WAY MARKER	4.000	EACH
37	615-06505 MONUMENT, B	2.000	EACH
38	616-02320 GEOTEXTILES	239.000	SYS
39	616-06405 RIPRAP, REVETMENT	120.000	TON
40	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
41	621-06559 MULCHED SEEDING, R	712.000	SYS
42	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
43	628-09402 FIELD OFFICE, B	9.000	MOS
44	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	18.000	MOS
45	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	27.000	MOS
46	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
47	714-11411 STRUCTURE, REINFORCED CONCRETE, BOX	79.000	LFT
48	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	85.000	LFT
49	715-46005 PIPE END SECTION, 15 IN	4.000	EACH

CALL ORDER : 420

CONTRACT ID : B -30464-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT SMALL STRUCTURE PROJECT		
50	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
51	801-03291 CONSTRUCTION SIGN, D	1.000	EACH
52	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
53	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	9,980.000	LFT
54	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	1.000	EACH
55	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	1.000	EACH
56	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
57	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
58	801-06710 FLASHING ARROW SIGN	180.000	DAY
59	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
60	801-07119 BARRICADE, III-B	48.000	LFT
61	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	520.000	LFT
62	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	180.000	LFT
63	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	1,050.000	LFT
64	808-06716 LINE, REMOVE	3,885.000	LFT
65	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	650.000	LFT
66	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,620.000	LFT
67	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	24.000	EACH
68	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	24.000	EACH

CALL ORDER : 430

CONTRACT ID : B -30876-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	625.000	CYS
11	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
12	205-06937 TEMPORARY SILT FENCE	305.000	LFT
13	205-09543 NO 2 STONE	100.000	TON
14	206-51220 EXCAVATION, WET	95.000	CYS
15	206-51225 EXCAVATION, DRY	280.000	CYS
16	207-08265 SUBGRADE TREATMENT, TYPE IIA	688.000	SYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	53.000	SYS
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	215.000	CYS
19	211-09267 STRUCTURAL BACKFILL, TYPE 4	150.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	276.000	TON
21	302-07455 DENSE GRADED SUBBASE	19.000	CYS
22	303-01180 COMPACTED AGGREGATE, NO. 53	32.000	TON
23	402-07433 HMA SURFACE, TYPE B	58.000	TON
24	402-07438 HMA INTERMEDIATE, TYPE B	95.000	TON
25	406-05520 ASPHALT FOR TACK COAT	1.000	TON
26	601-01128 GUARDRAIL, TRANSITION TYPE WGB	2.000	EACH
27	601-01128 GUARDRAIL, TRANSITION TYPE WGB	2.000	EACH
28	601-01704 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, MODIFIED	1.000	EACH
29	601-02241 GUARDRAIL, REMOVE	210.000	LFT
30	601-06037 GUARDRAIL END TREATMENT, I	3.000	EACH
31	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	188.000	LFT
32	602-06729 BARRIER DELINEATOR	8.000	EACH
33	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	110.000	SYS
34	610-07487 HMA FOR APPROACHES, TYPE B	15.000	TON
35	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
36	616-02320 GEOTEXTILES	765.000	SYS
37	616-05688 RIPRAP, CLASS 1	146.000	TON
38	616-06405 RIPRAP, REVETMENT	364.000	TON
39	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
40	621-02770 EROSION CONTROL BLANKET	467.000	SYS
41	621-06559 MULCHED SEEDING, R	581.000	SYS
42	621-06575 SODDING, NURSERY	278.000	SYS
43	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
44	628-09401 FIELD OFFICE, A	9.000	MOS
45	701-09558 TEST PILE, INDICATOR, PRODUCTION	94.000	LFT
46	701-09560 TEST PILE, INDICATOR, RESTRIKE	2.000	EACH
47	701-09739 PILE SHOE, HP 12 X 53	23.000	EACH
48	701-51195 PILE, STEEL H, HP 12 IN X 53	777.000	LFT
49	702-51005 CONCRETE, A, SUBSTRUCTURE	47.200	CYS

CALL ORDER : 430

CONTRACT ID : B -30876-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	702-51015 CONCRETE, B, FOOTINGS	67.400	CYS
51	703-06028 REINFORCING BARS	11,434.000	LBS
52	703-06029 REINFORCING BARS, EPOXY COATED	14,520.000	LBS
53	704-51006 CONCRETE, C, SUPERSTRUCTURE, MODIFIED	48.100	CYS
54	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	4.000	EACH
55	706-94947 RAILING, CONCRETE, C, MODIFIED	2.200	CYS
56	709-51821 SURFACE SEAL	LUMP	LUMP
57	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	44.000	LFT
58	715-05197 PIPE, TYPE 3 CIRCULAR 84 IN	60.000	LFT
59	715-07150 CONCRETE ANCHOR 84 IN	2.000	EACH
60	720-04682 INLET	1.000	EACH
61	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
62	801-06625 DETOUR ROUTE MARKER ASSEMBLY	29.000	EACH
63	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
64	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
65	801-07118 BARRICADE, III-A	72.000	LFT
66	801-07119 BARRICADE, III-B	24.000	LFT
67	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	21.000	LFT
68	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
69	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	6.250	SFT
70	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	300.000	LFT
71	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	402.000	LFT
72	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	2,348.000	LFT
73	808-06726 TRANSVERSE MARKING, PAINT,	12.000	LFT

CALL ORDER : 440

CONTRACT ID : B -31643-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SCOUR PROTECTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	203-51223 EXCAVATION, WATERWAY	290.000	CYS
9	205-06934 TEMPORARY MULCHING	5.200	TON
10	616-02320 GEOTEXTILES	1,021.000	SYS
11	616-05688 RIPRAP, CLASS 1	1,591.000	TON
12	616-06405 RIPRAP, REVETMENT	699.000	TON
13	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
14	621-06557 SEED MIXTURE, T	312.000	LBS
15	621-06559 MULCHED SEEDING, R	10,056.000	SYS
16	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
17	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	8.000	MOS
18	628-09409 MOBILE INTERNET SERVICE	8.000	MOS
19	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	8.000	MOS
20	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
21	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
22	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
23	801-06710 FLASHING ARROW SIGN	60.000	DAY
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 470

CONTRACT ID : M -31164-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
5 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
6 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
7 623-04887	MOWING, CYCLE NO 4	1.000	CYCL
8 623-05684	MOWING, CYCLE NO 5	1.000	CYCL
9 623-06008	MOWING, CYCLE NO 7	1.000	CYCL
10 623-06704	MOWING, CYCLE NO 6	1.000	CYCL
11 623-06707	MOWING, CYCLE NO 8	1.000	CYCL
12 801-03290	CONSTRUCTION SIGN, C	4.000	EACH



CALL ORDER : 480

CONTRACT ID : M -31166-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
5 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
6 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
7 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 490

CONTRACT ID : M -31167-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08463	PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
4 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
5 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
6 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
7 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 500

CONTRACT ID : M -31168-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
5 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
6 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
7 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

