

CALL ORDER : 130

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
1	203-02000 EXCAVATION, COMMON	211,595.000	CYS
2	203-02070 BORROW	799,100.000	CYS
3	207-08262 SUBGRADE TREATMENT, TYPE I	148,201.000	SYS
4	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	24,732.000	TON
5	302-06464 SUBBASE FOR PCCP	28,119.000	CYS
6	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	3,222.000	TON
7	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	310.000	TON
8	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	6,102.000	TON
9	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	522.000	TON
10	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	7,015.000	TON
11	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	1,453.000	TON
12	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	639.000	TON
13	406-05520 ASPHALT FOR TACK COAT	22.000	TON
14	501-06321 QC/QA-PCCP, 10 IN	102,001.000	SYS
15	503-05240 D-1 CONTRACTION JOINT	51,001.000	LFT
16	503-05310 TERMINAL JOINT	148.000	LFT
17	606-07484 MILLED HMA SHOULDER CORRUGATIONS	65,411.000	LFT
18	615-06515 MONUMENT, D	21.000	EACH
19	718-99153 GEOTEXTILES FOR UNDERDRAIN	61,417.000	SYS
SECTION NO. 0002 NEW ROAD CONSTRUCTION			
20	203-02000 EXCAVATION, COMMON	197,695.000	CYS
21	203-02070 BORROW	824,225.000	CYS
22	207-08262 SUBGRADE TREATMENT, TYPE I	145,485.000	SYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	37,803.000	TON
24	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	2,068.000	TON
25	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	9,656.000	TON
26	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	16,281.000	TON
27	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	5,902.000	TON
28	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	44,264.000	TON
29	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	19,149.000	TON
30	406-05520 ASPHALT FOR TACK COAT	129.000	TON
31	606-07484 MILLED HMA SHOULDER CORRUGATIONS	65,409.000	LFT
32	615-06505 MONUMENT, B	21.000	EACH
33	718-99153 GEOTEXTILES FOR UNDERDRAIN	53,687.000	SYS
SECTION NO. 0003 NEW BRIDGE			
34	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
35	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
36	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
37	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
38	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
39	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
40	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
41	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
42	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
43	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP

CALL ORDER : 130

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW BRIDGE		
44	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
45	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
46	202-02240 PAVEMENT REMOVAL	24,886.000	SYS
47	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
48	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
49	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
50	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
51	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
52	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
53	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
54	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
55	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
56	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
57	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
58	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
59	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
60	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
61	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
62	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
63	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
64	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	432.000	SFT
65	203-02000 EXCAVATION, COMMON	31,312.000	CYS
66	203-02070 BORROW	83,708.000	CYS
67	204-02290 SETTLEMENT PLATE	24.000	EACH
68	204-08415 STAKE, SETTLEMENT	24.000	EACH
69	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	3.000	EACH
70	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	6.000	EACH
71	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	18.000	EACH
72	205-03371 SEDIMENT, REMOVE	329.000	CYS
73	205-06930 SPLASHPAD, RIPRAP	69.600	TON
74	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	940.500	TON
75	205-06932 TEMPORARY CHECK DAM, STRAW BALES	156.000	LFT
76	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
77	205-06933 TEMPORARY DITCH INLET PROTECTION	17.000	EACH
78	205-06934 TEMPORARY MULCHING	61.600	TON
79	205-06936 TEMPORARY SEDIMENT TRAP	27.000	TON
80	205-06937 TEMPORARY SILT FENCE	9,565.000	LFT
81	205-06938 TEMPORARY SLOPE DRAIN	946.000	LFT
82	205-09543 NO 2 STONE	5,578.000	TON
83	206-51220 EXCAVATION, WET	1,447.000	CYS
84	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	247.000	CYS
85	206-51235 COFFERDAM	LUMP	LUMP
86	207-08264 SUBGRADE TREATMENT, TYPE II	12,194.000	SYS
87	207-08265 SUBGRADE TREATMENT, TYPE IIA	295.000	SYS
88	207-08266 SUBGRADE TREATMENT, TYPE III	3,038.000	SYS
89	207-08267 SUBGRADE TREATMENT, TYPE IIIA	10,560.000	SYS
90	211-02050 B BORROW	46,539.000	CYS
91	211-02050 B BORROW	14,629.000	CYS
92	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,621.600	CYS

CALL ORDER : 130

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW BRIDGE		
93	211-09265 STRUCTURAL BACKFILL, TYPE 2	7,373.000	CYS
94	211-09266 STRUCTURAL BACKFILL, TYPE 3	50,779.000	CYS
95	211-09268 STRUCTURAL BACKFILL, TYPE 5	1,593.000	CYS
96	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	37.200	CYS
97	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5,153.000	TON
98	302-06464 SUBBASE FOR PCCP	650.000	CYS
99	302-07455 DENSE GRADED SUBBASE	272.000	CYS
100	302-08562 COARSE AGGREGATE, 8	750.000	TON
101	303-01180 COMPACTED AGGREGATE, NO. 53	490.700	TON
102	303-02172 TEMPORARY AGGREGATE	992.000	TON
103	303-07449 COMPACTED AGGREGATE, NO. 73	97.000	TON
104	304-07489 HMA PATCHING, TYPE A	6.000	TON
105	306-08034 MILLING, ASPHALT, 1 1/2 IN	377.800	SYS
106	306-08043 MILLING, TRANSITION	786.000	SYS
107	402-07432 HMA SURFACE, TYPE A	778.000	TON
108	402-07433 HMA SURFACE, TYPE B	1,351.300	TON
109	402-07435 HMA INTERMEDIATE, TYPE A	1,237.000	TON
110	402-07438 HMA INTERMEDIATE, TYPE B	3,077.700	TON
111	406-05520 ASPHALT FOR TACK COAT	3.500	TON
112	502-06331 PCCP, 14 IN	2,288.000	SYS
113	502-06331 PCCP, 14 IN	312.000	SYS
114	503-05240 D-1 CONTRACTION JOINT	2,448.000	LFT
115	507-07480 PROFILING PCCP	2,600.000	SYS
116	601-01522 GUARDRAIL, TRANSITION TYPE TGB	20.000	EACH
117	601-01839 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 6	1.000	EACH
118	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
119	601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION	7.000	EACH
120	601-05071 GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, 7	2.000	EACH
121	601-05586 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 9	1.000	EACH
122	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	10.000	EACH
123	601-06238 IMPACT ATTENUATOR, R1, W1, TL-3	4.000	EACH
124	601-94689 GUARDRAIL END TREATMENT, OS	15.000	EACH
125	601-94690 GUARDRAIL END TREATMENT, MS	2.000	EACH
126	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	5,730.250	LFT
127	601-99108 GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	588.000	LFT
128	602-06729 BARRIER DELINEATOR	123.000	EACH
129	603-06040 FENCE, FARM FIELD, 47 IN	41,350.000	LFT
130	603-06045 FENCE, CHAIN LINK, 48 IN	2,500.000	LFT
131	605-06140 CURB AND GUTTER, CONCRETE	865.000	LFT
132	605-06145 CURB AND GUTTER, B, CONCRETE	1,088.000	LFT
133	606-11064 MILLED PCCP SHOULDER CORRUGATIONS	232.000	LFT
134	607-06335 PAVED SIDE DITCH, A	65.000	LFT
135	607-06370 PAVED SIDE DITCH, H	934.000	LFT
136	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	1,614.800	SYS
137	610-07486 HMA FOR APPROACHES, TYPE A	124.000	TON
138	610-07487 HMA FOR APPROACHES, TYPE B	52.700	TON
139	610-08446 PCCP FOR APPROACHES, 6 IN	574.000	SYS
140	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
141	611-08233 MAILBOX ASSEMBLY, DOUBLE, RESET	2.000	EACH

CALL ORDER : 130

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW BRIDGE		
142	615-06490 RIGHT OF WAY MARKER	38.000	EACH
143	615-06505 MONUMENT, B	11.000	EACH
144	615-06510 MONUMENT, C	50.000	EACH
145	615-06527 MONUMENT, SECTION CORNER	4.000	EACH
146	616-02320 GEOTEXTILES	10,800.500	SYS
147	616-06405 RIPRAP, REVETMENT	4,067.800	TON
148	619-51860 PAINT STEEL BRIDGE, PARTIAL, BR. NO.	LUMP	LUMP
149	619-51860 PAINT STEEL BRIDGE, PARTIAL, BR. NO.	LUMP	LUMP
150	619-51860 PAINT STEEL BRIDGE, PARTIAL, BR. NO.	LUMP	LUMP
151	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	9.000	EACH
152	621-02770 EROSION CONTROL BLANKET	2,811.000	SYS
153	621-03787 SEED MIXTURE, D	292.000	LBS
154	621-03909 SEED MIXTURE, NATIVE	614.000	LBS
155	621-04258 SEED MIXTURE	85.000	LBS
156	621-04258 SEED MIXTURE	22.000	LBS
157	621-06545 FERTILIZER	42.750	TON
158	621-06545 FERTILIZER	100.000	TON
159	621-06553 SEED MIXTURE, R	8,451.200	LBS
160	621-06557 SEED MIXTURE, T	7,451.700	LBS
161	621-06557 SEED MIXTURE, T	875.000	LBS
162	621-06565 MULCHING MATERIAL	265.600	TON
163	621-06567 WATER	62.140	KGAL
164	621-06574 SODDING	16,548.000	SYS
165	622-98200 SIGN, DO NOT DISTURB	2.000	EACH
166	624-92647 HERBICIDE TREATMENT	25.000	ACRE
167	624-92647 HERBICIDE TREATMENT	25.000	ACRE
168	628-09403 FIELD OFFICE, C	27.000	MOS
169	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	252.000	MOS
170	628-09409 MOBILE INTERNET SERVICE	120.000	MOS
171	628-09893 WORK TRUCK	81.000	MOS
172	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	252.000	MOS
173	628-11068 CELLULAR TELEPHONE/RADIO	7.000	EACH
174	701-06011 DYNAMIC PILE LOAD TEST	13.000	EACH
175	701-08253 PILE SLEEVES	52.000	EACH
176	701-09557 TEST PILE, DYNAMIC, PRODUCTION	1,040.000	LFT
177	701-09559 TEST PILE, DYNAMIC, RESTRIKE	13.000	EACH
178	701-09770 PILE SHOE, HP 14 X 73	214.000	EACH
179	701-09824 PREBORED HOLE, 18 IN.	2,471.000	LFT
180	701-93575 PILE, STEEL H, HP 14 IN X 73	10,559.000	LFT
181	702-51005 CONCRETE, A, SUBSTRUCTURE	662.200	CYS
182	702-51015 CONCRETE, B, FOOTINGS	71.400	CYS
183	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	2,378.000	LBS
184	703-06028 REINFORCING BARS	52,688.000	LBS
185	703-06029 REINFORCING BARS, EPOXY COATED	724,005.000	LBS
186	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,669.600	CYS
187	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	12.000	EACH
188	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	8.000	EACH
189	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	2,096.000	SYS
190	706-51020 RAILING, CONCRETE, C	460.600	CYS

CALL ORDER : 130

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW BRIDGE			
191	707-09382	STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 54 IN X 61 IN	1,026.000 LFT
192	707-09383	STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 60 IN X 61 IN	1,093.000 LFT
193	709-07110	SEAL COAT, GRAFFITI RESISTANT	73,810.000 SFT
194	709-51821	SURFACE SEAL	LUMP LUMP
195	709-51821	SURFACE SEAL	LUMP LUMP
196	709-51821	SURFACE SEAL	LUMP LUMP
197	709-51821	SURFACE SEAL	LUMP LUMP
198	709-51821	SURFACE SEAL	LUMP LUMP
199	711-51038	STRUCTURAL STEEL	LUMP LUMP
200	711-51038	STRUCTURAL STEEL	LUMP LUMP
201	711-51038	STRUCTURAL STEEL	LUMP LUMP
202	711-51070	ANCHOR PLATE, AP 1	8.000 EACH
203	714-11073	STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	90.000 LFT
204	714-11173	STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	104.000 LFT
205	714-11179	STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	402.000 LFT
206	714-11191	STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	140.000 LFT
207	714-11322	STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	64.000 LFT
208	715-04548	GRATED BOX END SECTION, II 6:1 30 IN	1.000 EACH
209	715-05019	PIPE, TYPE 1 CIRCULAR 36 IN	844.000 LFT
210	715-05024	PIPE, TYPE 2 CIRCULAR 36 IN	238.000 LFT
211	715-05048	PIPE, TYPE 4 CIRCULAR 6 IN	68,240.000 LFT
212	715-05052	PIPE, TYPE 4 CIRCULAR 12 IN	400.000 LFT
213	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN	5,306.000 LFT
214	715-05118	PIPE, TYPE 1 CIRCULAR 12 IN	3,000.000 LFT
215	715-05123	PIPE, TYPE 1 CIRCULAR 24 IN	400.000 LFT
216	715-05149	PIPE, TYPE 2 CIRCULAR 12 IN	779.000 LFT
217	715-05151	PIPE, TYPE 2 CIRCULAR 15 IN	1,174.000 LFT
218	715-05152	PIPE, TYPE 2 CIRCULAR 18 IN	34.000 LFT
219	715-05154	PIPE, TYPE 2 CIRCULAR 24 IN	283.000 LFT
220	715-05156	PIPE, TYPE 2 CIRCULAR 30 IN	38.000 LFT
221	715-05168	PIPE, TYPE 3 CIRCULAR 12 IN	36.000 LFT
222	715-05212	PIPE, TYPE 4 CIRCULAR 24 IN	600.000 LFT
223	715-05217	PIPE, TYPE 5 CIRCULAR 12 IN	95.000 LFT
224	715-05218	PIPE, TYPE 5 CIRCULAR 15 IN	264.000 LFT
225	715-09446	PIPE, TYPE 4 CIRCULAR 36 IN	400.000 LFT
226	715-26772	GRATED BOX END SECTION, I, 6:1, 24 IN.	2.000 EACH
227	715-46000	PIPE END SECTION, 12 IN	7.000 EACH
228	715-46005	PIPE END SECTION, 15 IN	13.000 EACH
229	715-46020	PIPE END SECTION, 24 IN	1.000 EACH
230	715-46040	PIPE END SECTION, 36 IN	7.000 EACH
231	715-98974	GRATED BOX END SECTION,, II, 6:1, 36 IN	1.000 EACH
232	715-99044	GRATED BOX END SECTION,, II, 6:1, 18 IN	1.000 EACH
233	718-06528	OUTLET PROTECTOR, 1	115.000 EACH
234	718-06529	OUTLET PROTECTOR, 2	50.000 EACH
235	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	6,500.000 LFT
236	718-52610	AGGREGATE FOR UNDERDRAINS	6,142.000 CYS
237	719-05443	PIPE, DRAINTILE TERMINAL SECTION, 12 IN	30.000 LFT
238	719-09447	PIPE, DRAIN TILE TERMINAL SECTION, 24 IN	10.000 LFT
239	719-09448	PIPE, DRAIN TILE, TERMINAL SECTION, 36 IN	10.000 LFT

CALL ORDER : 130

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW BRIDGE			
240	720-08617 INLET, INTAKE RISER	10.000	EACH
241	720-45042 INLET, HA5	5.000	EACH
242	720-45066 INLET, N12, MODIFIED	12.000	EACH
243	720-45070 INLET, P12A	12.000	EACH
244	720-45270 PIPE CATCH BASIN, 18 IN	3.000	EACH
245	720-45275 PIPE CATCH BASIN, 24 IN	1.000	EACH
246	720-45410 MANHOLE, C4	12.000	EACH
247	720-95310 INLET, P12A, MODIFIED	2.000	EACH
248	720-98013 INLET, M	1.000	EACH
249	720-99416 CATCH BASIN, B15	2.000	EACH
250	720-99417 CATCH BASIN, C15	2.000	EACH
251	721-43000 AUTOMATIC DRAINAGE GATE, 12 IN	12.000	EACH
252	721-43010 AUTOMATIC DRAINAGE GATE, 18 IN	1.000	EACH
253	721-43030 AUTOMATIC DRAINAGE GATE, 30 IN	1.000	EACH
254	722-95883 BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
255	722-95883 BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
256	723-11318 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	278.000	LFT
257	724-51925 STRUCTURAL EXPANSION JOINT, SS	148.000	LFT
258	731-08252 LEVELING PAD	615.000	LFT
259	731-93945 FACE PANELS, CONCRETE	77,358.000	SFT
260	731-93946 WALL ERECTION	77,358.000	SFT
261	731-93947 LEVELING PAD, CONCRETE	3,494.000	LFT
262	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
263	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
264	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	50,100.000	LFT
265	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	15,620.000	LFT
266	801-06625 DETOUR ROUTE MARKER ASSEMBLY	26.000	EACH
267	801-06640 CONSTRUCTION SIGN, A	72.000	EACH
268	801-06645 CONSTRUCTION SIGN, B	17.000	EACH
269	801-06710 FLASHING ARROW SIGN	300.000	DAY
270	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
271	801-07118 BARRICADE, III-A	156.000	LFT
272	801-07119 BARRICADE, III-B	156.000	LFT
273	801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1	2,371.000	LFT
274	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	3,510.000	LFT
275	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
276	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	56.000	LFT
277	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	48.000	LFT
278	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	21.000	LFT
279	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	55.750	SFT
280	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	18.020	SFT
281	805-09616 VWIM STATION, QUARTZ	LUMP	LUMP
282	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,093.000	LFT
283	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	4,234.000	LFT
284	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	1,272.000	LFT
285	808-06716 LINE, REMOVE	3,345.000	LFT
286	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
287	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	894.000	LFT
288	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	894.000	LFT

CALL ORDER : 130

CONTRACT ID : IR-30107-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW BRIDGE			
289	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	7,421.000	LFT
290	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	34.000	LFT
291	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH
292	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH
SECTION NO. 0004 NEW BRIDGE			
293	109-08359 LIQUIDATED DAMAGES	1.000	DOL
294	109-08360 CONTRACT LIENS	1.000	DOL
295	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
296	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
297	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
298	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
299	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
300	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
301	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
302	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL

CALL ORDER : 380

CONTRACT ID : B -32017-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51133 RAILING, REMOVE	387.000	LFT
10	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	550.000	CYS
12	203-02070 BORROW	544.000	CYS
13	205-06937 TEMPORARY SILT FENCE	761.000	LFT
14	206-51220 EXCAVATION, WET	18.000	CYS
15	206-51817 SHEET PILING, STEEL	2,160.000	SFT
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	471.000	SYS
17	211-06467 AGGREGATE FOR END BENT BACKFILL	42.000	CYS
18	211-09265 STRUCTURAL BACKFILL, TYPE 2	136.000	CYS
19	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	18.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	145.000	TON
21	302-07455 DENSE GRADED SUBBASE	26.000	CYS
22	304-07489 HMA PATCHING, TYPE A	19.000	TON
23	402-07432 HMA SURFACE, TYPE A	54.000	TON
24	402-07435 HMA INTERMEDIATE, TYPE A	18.000	TON
25	406-05521 ASPHALT FOR TACK COAT	263.000	SYS
26	601-02241 GUARDRAIL, REMOVE	536.000	LFT
27	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
28	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
29	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
30	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	331.250	LFT
31	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	154.000	SYS
32	616-02320 GEOTEXTILES	592.000	SYS
33	616-06405 RIPRAP, REVETMENT	445.000	TON
34	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	110.000	EACH
35	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
36	628-09402 FIELD OFFICE, B	12.000	MOS
37	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	24.000	MOS
38	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
39	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
40	701-09557 TEST PILE, DYNAMIC, PRODUCTION	84.000	LFT
41	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
42	701-09739 PILE SHOE, HP 12 X 53	8.000	EACH
43	701-51195 PILE, STEEL H, HP 12 IN X 53	252.000	LFT
44	702-51005 CONCRETE, A, SUBSTRUCTURE	20.500	CYS
45	703-06028 REINFORCING BARS	2,904.000	LBS
46	703-06029 REINFORCING BARS, EPOXY COATED	53,638.000	LBS
47	704-51002 CONCRETE, C, SUPERSTRUCTURE	214.300	CYS
48	706-06344 RAILING, STEEL TS-1	404.000	LFT
49	707-05984 STRUCTURAL MEMBER, CONCRETE I-BEAM , 45 IN X 16 IN	814.000	LFT



CALL ORDER : 380

CONTRACT ID : B -32017-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
50	709-51821 SURFACE SEAL	LUMP	LUMP
51	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	270.000	LFT
52	715-05407 PIPE, END BENT DRAIN, 6 IN	95.000	LFT
53	715-26730 GRATED BOX END SECTION,, II, 4:1, 24 IN	1.000	EACH
54	715-46020 PIPE END SECTION, 24 IN	1.000	EACH
55	720-45410 MANHOLE, C4	1.000	EACH
56	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
57	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
58	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
59	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
60	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
61	801-07118 BARRICADE, III-A	48.000	LFT
62	801-07119 BARRICADE, III-B	24.000	LFT
63	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	69.000	LFT
64	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
65	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	41.500	SFT
66	804-06770 DELINEATOR POST	2.000	EACH
67	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	497.000	LFT
68	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	115.000	LFT
69	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	508.000	LFT
70	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	508.000	LFT

CALL ORDER : 390

CONTRACT ID : B -32688-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEBRIS REMOVAL FROM CHANNEL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
8	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
9	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
10	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
11	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
12	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
13	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
14	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
15	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
16	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
17	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
18	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
19	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
20	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
21	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	8.000	MOS
22	628-09409 MOBILE INTERNET SERVICE	8.000	MOS
23	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	8.000	MOS
24	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
25	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
26	801-03290 CONSTRUCTION SIGN, C	30.000	EACH
27	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
28	801-06710 FLASHING ARROW SIGN	100.000	DAY
29	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
30	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH

CALL ORDER : 400

CONTRACT ID : B -33263-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE, SPECIAL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	277.000	SYS
11	202-91385 INLET, REMOVE	1.000	EACH
12	202-93995 SIGNAL POLE FOUNDATION, REMOVE	3.000	EACH
13	202-93999 SIGNAL POLE, REMOVE	4.000	EACH
14	202-96133 PIPE, REMOVE	78.000	LFT
15	202-98370 POLE, REMOVE	1.000	EACH
16	203-02000 EXCAVATION, COMMON	2,421.000	CYS
17	205-03371 SEDIMENT, REMOVE	14.000	CYS
18	205-06932 TEMPORARY CHECK DAM, STRAW BALES	126.000	LFT
19	205-06933 TEMPORARY DITCH INLET PROTECTION	5.000	EACH
20	205-06937 TEMPORARY SILT FENCE	2,360.000	LFT
21	205-09543 NO 2 STONE	100.000	TON
22	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	502.000	CYS
23	211-02050 B BORROW	373.000	CYS
24	211-09264 STRUCTURAL BACKFILL, TYPE 1	183.000	CYS
25	211-09266 STRUCTURAL BACKFILL, TYPE 3	3,517.000	CYS
26	303-01180 COMPACTED AGGREGATE, NO. 53	1,025.000	TON
27	303-07449 COMPACTED AGGREGATE, NO. 73	56.000	TON
28	402-07432 HMA SURFACE, TYPE A	152.000	TON
29	402-07435 HMA INTERMEDIATE, TYPE A	255.000	TON
30	406-05521 ASPHALT FOR TACK COAT	1,844.200	SYS
31	502-06627 PCCP, 6 IN	138.000	SYS
32	603-02736 FENCE, WOOD, RESET	464.000	LFT
33	604-06367 JOINT MATERIAL	354.000	LFT
34	604-07901 CURB RAMP, CONCRETE, G	12.000	SYS
35	604-95344 HANDRAIL, PEDESTRIAN	2,080.000	LFT
36	605-52807 CURB AND GUTTER, COMBINED	70.000	LFT
37	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	24.000	SYS
38	621-02770 EROSION CONTROL BLANKET	58.000	SYS
39	621-06560 MULCHED SEEDING, U	1,656.000	SYS
40	621-06575 SODDING, NURSERY	401.000	SYS
41	628-09402 FIELD OFFICE, B	16.000	MOS
42	701-51190 PILE, STEEL H, HP 10 IN X 42	350.000	LFT
43	701-51195 PILE, STEEL H, HP 12 IN X 53	480.000	LFT
44	702-51005 CONCRETE, A, SUBSTRUCTURE	231.000	CYS
45	702-51015 CONCRETE, B, FOOTINGS	94.600	CYS
46	703-06029 REINFORCING BARS, EPOXY COATED	18,656.000	LBS
47	704-51106 DECK DRAIN	12.000	EACH
48	709-51821 SURFACE SEAL	LUMP	LUMP
49	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP

CALL ORDER : 400

CONTRACT ID : B -33263-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE, SPECIAL		
50	715-05146 PIPE, TYPE 2 CIRCULAR 6 IN	493.000	LFT
51	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	233.000	LFT
52	715-46000 PIPE END SECTION, 12 IN	1.000	EACH
53	720-45030 INLET, E7	1.000	EACH
54	720-45035 INLET, F7	1.000	EACH
55	720-45270 PIPE CATCH BASIN, 18 IN	1.000	EACH
56	724-51885 STRUCTURAL EXPANSION JOINT, BS6	89.400	LFT
57	732-08419 MODULAR BLOCK WALL	1,336.000	SYS
58	732-08421 MODULAR BLOCK WALL ERECTION	1,336.000	SYS
59	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
60	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
61	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
62	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
63	801-07119 BARRICADE, III-B	144.000	LFT
64	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	40.000	LFT
65	801-94295 SIGNAL HEAD, RELOCATE	7.000	EACH
66	802-04314 SIGN	4.000	EACH
67	802-07060 SIGN, SHEET, RELOCATE	4.000	EACH
68	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	185.000	SFT
69	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
70	805-01579 MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	LUMP	LUMP
71	805-09366 SIGNAL SUPPORT FOUNDATION, 36 IN DIAMETER X 120 IN	4.000	EACH
72	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
73	805-78420 DISCONNECT HANGER	3.000	EACH
74	805-78485 SIGNAL CABLE, 5C 14GA	197.000	LFT
75	805-78490 SIGNAL CABLE, 7C 14GA	338.000	LFT
76	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
77	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	705.000	LFT
78	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	473.000	LFT
79	808-06716 LINE, REMOVE	120.000	LFT
80	808-75015 LINE, PAINT, SOLID, WHITE, 12 IN	30.000	LFT

