

CALL ORDER : 161

CONTRACT ID : IR-34282-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, HOUSES AND BUILDINGS REMOVE		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
7 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
8 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
9 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
10 205-06932	TEMPORARY CHECK DAM, STRAW BALES	48.000	LFT
11 205-06933	TEMPORARY DITCH INLET PROTECTION	4.000	EACH
12 205-06937	TEMPORARY SILT FENCE	1,586.000	LFT
13 205-09543	NO 2 STONE	217.000	TON
14 621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
15 621-06560	MULCHED SEEDING, U	9,016.000	SYS
16 621-06570	TOPSOIL	250.000	CYS
17 801-03290	CONSTRUCTION SIGN, C	3.000	EACH
18 801-06640	CONSTRUCTION SIGN, A	6.000	EACH
19 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 365

CONTRACT ID : R -34492-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-02250 TREE, 10 IN, REMOVE	3.000	EACH
9	201-02255 TREE, 18 IN, REMOVE	2.000	EACH
10	201-02260 TREE, 30 IN, REMOVE	5.000	EACH
11	201-02265 TREE, 48 IN, REMOVE	1.000	EACH
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	31.000	SYS
14	202-02278 CURB, CONCRETE, REMOVE	2,725.000	LFT
15	202-52710 SIDEWALK, CONCRETE, REMOVE	1,848.000	SYS
16	202-91385 INLET, REMOVE	5.000	EACH
17	202-96035 CONCRETE WALL, REMOVE	418.000	LFT
18	202-96133 PIPE, REMOVE	142.000	LFT
19	203-02000 EXCAVATION, COMMON	2,165.000	CYS
20	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	1.000	EACH
21	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	13.000	EACH
22	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
23	205-06937 TEMPORARY SILT FENCE	922.000	LFT
24	207-08265 SUBGRADE TREATMENT, TYPE IIA	3,836.000	SYS
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	202.000	SYS
26	210-06750 INSTALL	LUMP	LUMP
27	210-06752 INSTALL	3.000	EACH
28	210-09472 LIMESTONE	154.000	LFT
29	211-09264 STRUCTURAL BACKFILL, TYPE 1	729.000	CYS
30	213-09270 FLOWABLE BACKFILL, REMOVABLE	32.000	CYS
31	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	788.000	TON
32	302-06464 SUBBASE FOR PCCP	280.000	CYS
33	303-01180 COMPACTED AGGREGATE, NO. 53	499.000	TON
34	303-93506 AGGREGATE, 2	539.000	CYS
35	304-07489 HMA PATCHING, TYPE A	7.000	TON
36	402-07432 HMA SURFACE, TYPE A	199.000	TON
37	402-07435 HMA INTERMEDIATE, TYPE A	463.000	TON
38	406-05520 ASPHALT FOR TACK COAT	2.000	TON
39	502-06327 PCCP, 10 IN	570.000	SYS
40	502-06999 PCCP, 8 IN	550.000	SYS
41	503-05240 D-1 CONTRACTION JOINT	1,053.000	LFT
42	604-02007 SIDEWALK, CONCRETE, RECONSTRUCT	34.000	SYS
43	604-04452 LIMESTONE	924.000	CFT
44	604-04452 LIMESTONE	91.000	CFT
45	604-06070 SIDEWALK, CONCRETE	11.000	SYS
46	604-06070 SIDEWALK, CONCRETE	1,168.000	SYS
47	604-06070 SIDEWALK, CONCRETE	21.000	SYS
48	604-07894 CURB RAMP, CONCRETE, A	13.000	SYS
49	604-07900 CURB RAMP, CONCRETE, F	118.000	SYS

CALL ORDER : 365

CONTRACT ID : R -34492-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	604-44251 STEPS, CONCRETE	4.000	CYS
51	604-91531 SIDEWALK, CONCRETE, 4 IN	242.000	SYS
52	604-95344 HANDRAIL, PEDESTRIAN	62.000	LFT
53	605-06125 CURB, CONCRETE, MODIFIED	1,884.000	LFT
54	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	596.000	LFT
55	607-11470 GUTTER, PERVIOUS CONCRETE	2,073.000	LFT
56	610-07486 HMA FOR APPROACHES, TYPE A	6.000	TON
57	610-08446 PCCP FOR APPROACHES, 6 IN	114.000	SYS
58	610-09108 PCCP FOR APPROACHES, 9 IN	69.000	SYS
59	616-02320 GEOTEXTILES	125.000	SYS
60	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
61	621-04978 SEED MIXTURE	3,540.000	SYS
62	621-06567 WATER	10.000	KGAL
63	621-06575 SODDING, NURSERY	1,535.000	SYS
64	621-09907 STAGING PLAN AND PREPARATION	LUMP	LUMP
65	622-01937 PLANT	52.000	EACH
66	622-05627 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, OVER 96	14.000	EACH
67	622-05639 PLANT, DECIDUOUS SHRUB, 18 TO 24 IN	32.000	EACH
68	622-05647 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 120 IN	8.000	EACH
69	622-05653 PLANT, GROUND COVER	605.000	EACH
70	622-05655 PLANT, ROOT, TUBER, CORM, BULB	350.000	EACH
71	628-09401 FIELD OFFICE, A	9.000	MOS
72	706-09545 COARSE AGGREGATE, NO 8	74.000	CYS
73	711-10103 ARCHITECTURAL	LUMP	LUMP
74	711-51864 DRILLED HOLE	1.000	EACH
75	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	2,057.000	LFT
76	715-05146 PIPE, TYPE 2 CIRCULAR 6 IN	39.000	LFT
77	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	622.000	LFT
78	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	34.000	LFT
79	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	69.000	LFT
80	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	2,057.000	LFT
81	718-99153 GEOTEXTILES FOR UNDERDRAIN	3,245.000	SYS
82	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	2.000	EACH
83	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
84	720-45030 INLET, E7	1.000	EACH
85	720-45410 MANHOLE, C4	5.000	EACH
86	720-93411 INLET, C15, MODIFIED	4.000	EACH
87	720-98174 INLET, B15	4.000	EACH
88	720-98555 INLET, C15	5.000	EACH
89	801-06625 DETOUR ROUTE MARKER ASSEMBLY	48.000	EACH
90	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
91	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
92	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
93	801-07118 BARRICADE, III-A	96.000	LFT
94	801-07119 BARRICADE, III-B	64.000	LFT
95	802-04314 SIGN	13.000	EACH
96	805-04197 CONDUIT, PVC, 6 IN.	357.000	LFT
97	805-04973 CONDUIT	166.000	LFT
98	805-95568 CONDUIT, PVC, 4 IN.	9,476.000	LFT

CALL ORDER : 365

CONTRACT ID : R -34492-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
99 807-03972	CONDUIT, PVC, 1 IN, SCHEDULE 40, FOR ELECTRIC	4,850.000	LFT
100 807-06595	CONDUIT, PVC, 2 IN	1,649.000	LFT
101 807-11471	AERIAL	3.000	EACH
102 807-11505	LIGHT, INSTALL	54.000	EACH
103 807-78590	HANDHOLE	5.000	EACH
104 807-78590	HANDHOLE	4.000	EACH
105 807-78590	HANDHOLE	1.000	EACH
106 807-78590	HANDHOLE	1.000	EACH
107 808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	204.000	LFT
108 808-10043	LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN	30.000	LFT
109 808-10047	TRANSVERSE MARKINGS MULTI-COMPONENT,	485.000	LFT