

CALL ORDER : 130

CONTRACT ID : IR-33741-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	108-09283 CPM SCHEDULE	LUMP	LUMP
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	203-02020 EXCAVATION, UNCLASSIFIED	3,648,063.400	CYS
8	203-09567 SPILL CONTAINMENT DAM	4.000	EACH
9	203-11546 NATURAL STONE MATERIAL 12-18"	242.000	CYS
10	203-11546 NATURAL STONE MATERIAL 12-18"	242.000	CYS
11	203-11547 STREAM SUBSTRATE MATERIAL, LESS THAN 12"	817.000	CYS
12	204-02290 SETTLEMENT PLATE	11.000	EACH
13	204-08414 STAKE, LATERAL	22.000	EACH
14	205-06935 TEMPORARY SEDIMENT BASIN	7.000	EACH
15	205-09543 NO 2 STONE	442,031.000	TON
16	205-09952 DESIGN BUILD EROSION AND SEDIMENT CONTROL	LUMP	LUMP
17	205-11545 FILTER BERM	4,705.000	LFT
18	207-08265 SUBGRADE TREATMENT, TYPE IIA	14,321.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	423.000	SYS
20	211-02050 B BORROW	35,884.400	CYS
21	211-06467 AGGREGATE FOR END BENT BACKFILL	288.000	CYS
22	211-09264 STRUCTURAL BACKFILL, TYPE 1	7,397.000	CYS
23	211-09265 STRUCTURAL BACKFILL, TYPE 2	9,191.000	CYS
24	211-09266 STRUCTURAL BACKFILL, TYPE 3	62,097.000	CYS
25	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	922.000	CYS
26	215-07043 CHEMICAL MODIFICATION, SOILS	330,169.000	SYS
27	215-11477 CHEMICAL STABILIZATION	48,288.000	TON
28	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,705.000	TON
29	302-07455 DENSE GRADED SUBBASE	483.600	CYS
30	302-08562 COARSE AGGREGATE, NO 8	974.000	TON
31	303-01180 COMPACTED AGGREGATE, NO. 53	2,516.000	TON
32	303-07449 COMPACTED AGGREGATE, NO. 73	345.000	TON
33	303-07662 STONE	222.000	TON
34	306-08043 MILLING, TRANSITION	223.000	SYS
35	402-07432 HMA SURFACE, TYPE A	916.000	TON
36	402-07435 HMA INTERMEDIATE, TYPE A	1,541.000	TON
37	402-07440 HMA BASE, TYPE A	223.000	TON
38	406-05520 ASPHALT FOR TACK COAT	11.000	TON
39	503-05240 D-1 CONTRACTION JOINT	19.000	LFT
40	601-01522 GUARDRAIL, TRANSITION TYPE TGB	28.000	EACH
41	601-01700 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 1	1.000	EACH
42	601-06777 GRAVEL BARREL ARRAY	2.000	EACH
43	601-94689 GUARDRAIL END TREATMENT, OS	14.000	EACH
44	601-94690 GUARDRAIL END TREATMENT, MS	9.000	EACH
45	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	18,325.000	LFT
46	601-99108 GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	2,781.250	LFT
47	602-06729 BARRIER DELINEATOR	81.000	EACH
48	602-08344 REINFORCED CONCRETE MOMENT SLAB	35.000	SYS
49	603-06040 FENCE, FARM FIELD, 47 IN	45,285.000	LFT

CALL ORDER : 130

CONTRACT ID : IR-33741-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
50	605-06121 CURB, CONCRETE, B	138.000	LFT
51	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	210.000	SYS
52	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	2,688.400	SYS
53	610-07486 HMA FOR APPROACHES, TYPE A	55.000	TON
54	610-07487 HMA FOR APPROACHES, TYPE B	117.000	TON
55	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
56	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
57	615-06490 RIGHT OF WAY MARKER	39.000	EACH
58	615-06505 MONUMENT, B	30.000	EACH
59	615-06510 MONUMENT, C	29.000	EACH
60	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
61	616-02320 GEOTEXTILES	81,972.000	SYS
62	616-05688 RIPRAP, CLASS 1	13,274.000	TON
63	616-05689 RIPRAP, CLASS 2	7,357.000	TON
64	616-06405 RIPRAP, REVETMENT	43,113.000	TON
65	616-09395 GEOMEMBRANE	6,984.000	SYS
66	616-51367 SLOPEWALL, CONCRETE, 4 IN	80.000	SYS
67	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
68	621-02770 EROSION CONTROL BLANKET	89,994.000	SYS
69	621-02770 EROSION CONTROL BLANKET	2,231.000	SYS
70	621-04258 SEED MIXTURE	32.800	LBS
71	621-04258 SEED MIXTURE	175.600	LBS
72	621-06545 FERTILIZER	42.770	TON
73	621-06553 SEED MIXTURE, R	17,170.000	LBS
74	621-06565 MULCHING MATERIAL	215.320	TON
75	621-06567 WATER	128.000	KGAL
76	621-06574 SODDING	40,753.000	SYS
77	622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT	480.000	EACH
78	622-10003 LIVE PLANT STAKING	1,140.000	EACH
79	622-52436 SIGN, DO NOT MOW OR SPRAY	157.000	EACH
80	622-91786 SEEDLING	651.000	EACH
81	622-91786 SEEDLING	1,199.000	EACH
82	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
83	628-09403 FIELD OFFICE, C	36.000	MOS
84	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	180.000	MOS
85	628-11068 CELLULAR TELEPHONE/RADIO	6.000	EACH
86	628-11069 CELLULAR TELEPHONE/RADIO SERVICE, ANYTIME MINUTES	216.000	MOS
87	701-02936 PILE, STEEL H, HP 14 IN X 89	1,092.000	LFT
88	701-02938 CORED HOLE IN ROCK, 24 IN	570.000	LFT
89	701-05561 DRILLED SHAFT	420.000	LFT
90	701-05785 EXPLORATION (SHAFT EXCAVATION)	270.000	LFT
91	701-06011 DYNAMIC PILE LOAD TEST	5.000	EACH
92	701-09557 TEST PILE, DYNAMIC, PRODUCTION	284.000	LFT
93	701-09559 TEST PILE, DYNAMIC, RESTRIKE	3.000	EACH
94	701-09683 PILE SHOE, HP 12 X 74	82.000	EACH
95	701-09684 PILE SHOE, HP 14 X 89	28.000	EACH
96	701-09739 PILE SHOE, HP 12 X 53	20.000	EACH
97	701-51195 PILE, STEEL H, HP 12 IN X 53	650.000	LFT
98	701-95780 PILE, STEEL H, HP 12 IN X 74	3,374.000	LFT

CALL ORDER : 130

CONTRACT ID : IR-33741-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
99	702-51005 CONCRETE, A, SUBSTRUCTURE	714.900	CYS
100	702-51005 CONCRETE, A, SUBSTRUCTURE	653.100	CYS
101	702-51015 CONCRETE, B, FOOTINGS	219.600	CYS
102	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	3,864.000	LBS
103	702-51863 FIELD DRILLED HOLE IN CONCRETE	12.000	EACH
104	702-76240 CONCRETE	461.000	CYS
105	702-92857 CONCRETE, C, SUBSTRUCTURE	473.000	CYS
106	703-06028 REINFORCING BARS	274,662.000	LBS
107	703-06029 REINFORCING BARS, EPOXY COATED	1,017,273.000	LBS
108	704-09031 ARTICULATING CONCRETE MATTRESS	1,906.000	SYS
109	704-51002 CONCRETE, C, SUPERSTRUCTURE	2,613.300	CYS
110	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	32.000	EACH
111	706-06352 CONCRETE BRIDGE RAILING TRANSITION, TPF-2	4.000	EACH
112	706-09545 COARSE AGGREGATE, NO 8	7.000	CYS
113	706-09545 COARSE AGGREGATE, NO 8	16.000	CYS
114	706-09963 RAILING, CONCRETE, PF-2	1,080.000	LFT
115	706-11405 RAILING, STEEL, PF-2	1,097.000	LFT
116	706-51020 RAILING, CONCRETE, C	253.300	CYS
117	707-05983 STRUCTURAL MEMBER, CONCRETE I-BEAM, 36 IN X 12 IN	555.000	LFT
118	707-08643 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 60 IN X 48 IN	3,004.000	LFT
119	707-09865 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 36 IN X 49 IN	568.000	LFT
120	707-10176 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 72 IN X 49 IN	2,152.000	LFT
121	709-51821 SURFACE SEAL	LUMP	LUMP
122	709-51821 SURFACE SEAL	LUMP	LUMP
123	709-51821 SURFACE SEAL	LUMP	LUMP
124	709-51821 SURFACE SEAL	LUMP	LUMP
125	709-51821 SURFACE SEAL	LUMP	LUMP
126	709-51821 SURFACE SEAL	LUMP	LUMP
127	709-51821 SURFACE SEAL	LUMP	LUMP
128	709-51821 SURFACE SEAL	LUMP	LUMP
129	709-51821 SURFACE SEAL	LUMP	LUMP
130	711-96800 STUD SHEAR CONNECTORS	546.000	EACH
131	713-11199 TEMPORARY PIPE	112.000	LFT
132	714-11177 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	86.000	LFT
133	714-11304 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	39.000	LFT
134	715-01471 PIPE END SECTION, PRECAST CONCRETE, 15 IN	39.000	EACH
135	715-01472 PIPE END SECTION, PRECAST CONCRETE, 18 IN	2.000	EACH
136	715-01765 PIPE END SECTION, PRECAST CONCRETE, 12 IN	5.000	EACH
137	715-04632 PIPE END SECTION, PRECAST CONCRETE, 36"	6.000	EACH
138	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	790.000	LFT
139	715-05032 PIPE, TYPE 2 CIRCULAR 15 IN	3,105.000	LFT
140	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	103,419.000	LFT
141	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	10,673.000	LFT
142	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	66.000	LFT
143	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	92.000	LFT
144	715-05128 PIPE, TYPE 1 CIRCULAR 48 IN	741.000	LFT
145	715-05129 PIPE, TYPE 1 CIRCULAR 54 IN	628.000	LFT
146	715-05133 PIPE, TYPE 1 CIRCULAR 60 IN	317.000	LFT
147	715-05145 PIPE, TYPE 1, CIRCULAR, 96 IN	354.000	LFT

CALL ORDER : 130

CONTRACT ID : IR-33741-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
148	715-05146 PIPE, TYPE 2 CIRCULAR 6 IN	705.000	LFT
149	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	257.000	LFT
150	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	25.000	LFT
151	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	70.000	LFT
152	715-05168 PIPE, TYPE 3 CIRCULAR 12 IN	87.000	LFT
153	715-05173 PIPE, TYPE 3 CIRCULAR 24 IN	46.000	LFT
154	715-05217 PIPE, TYPE 5 CIRCULAR 12 IN	163.000	LFT
155	715-05218 PIPE, TYPE 5 CIRCULAR 15 IN	511.000	LFT
156	715-05407 PIPE, END BENT DRAIN, 6 IN	464.000	LFT
157	715-05841 CONCRETE ANCHOR 60 IN	2.000	EACH
158	715-06004 CONCRETE ANCHOR, 48 IN	6.000	EACH
159	715-06492 CONCRETE ANCHOR, 54 IN	4.000	EACH
160	715-06691 CONCRETE ANCHOR, 96 IN	2.000	EACH
161	715-07625 PIPE, TYPE 1 CIRCULAR MIN AREA 66 IN	274.000	LFT
162	715-07626 CONCRETE ANCHOR 66 IN	2.000	EACH
163	715-09064 VIDEO INSPECTION FOR PIPE	3,341.000	LFT
164	715-96389 PIPE END SECTION, PRECAST CONCRETE, 24"	5.000	EACH
165	718-03277 PIPE, UNDERDRAIN, CORRUGATED PLASTIC, PERFORATED, 6 IN.	705.000	LFT
166	718-06528 OUTLET PROTECTOR, 1	32.000	EACH
167	718-06529 OUTLET PROTECTOR, 2	134.000	EACH
168	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	10,000.000	LFT
169	718-52610 AGGREGATE FOR UNDERDRAINS	6,593.000	CYS
170	718-99153 GEOTEXTILES FOR UNDERDRAIN	68,236.000	SYS
171	720-03905 CATCH BASIN, A	6.000	EACH
172	720-45065 INLET, N12	37.000	EACH
173	720-45070 INLET, P12A	4.000	EACH
174	720-45075 INLET, R13	2.000	EACH
175	720-45090 INLET, UA	1.000	EACH
176	720-45095 INLET, WA	1.000	EACH
177	722-95883 BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
178	722-95883 BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
179	722-95883 BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
180	722-95883 BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
181	723-11558 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS	475.000	LFT
182	723-11559 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	272.000	LFT
183	723-11560 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	506.000	LFT
184	731-93945 FACE PANELS, CONCRETE	48,482.000	SFT
185	731-93946 WALL ERECTION	48,482.000	SFT
186	731-93947 LEVELING PAD, CONCRETE	1,892.000	LFT
187	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
188	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	5,682.000	LFT
189	801-06640 CONSTRUCTION SIGN, A	19.000	EACH
190	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
191	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
192	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	4.000	EACH
193	801-07119 BARRICADE, III-B	192.000	LFT
194	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	2,460.000	LFT
195	802-04893 REFERENCE POST	16.000	EACH
196	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	313.000	LFT

CALL ORDER : 130

CONTRACT ID : IR-33741-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
197	802-07057 SIGN, PANEL, WITH LEGEND	614.000	SFT
198	802-07153 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	6.000	EACH
199	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	64.250	SFT
200	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	136.000	SFT
201	802-76095 STRUCTURAL STEEL, BREAKAWAY	3,088.000	LBS
202	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	6,267.000	LFT
203	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	6,267.000	LFT
204	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
205	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	600.000	EACH
SECTION NO. 0002 NEW ROAD CONSTRUCTION			
206	207-08263 SUBGRADE TREATMENT, TYPE IA	186,456.000	SYS
207	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	15,207.000	TON
208	303-01180 COMPACTED AGGREGATE, NO. 53	11,875.000	TON
209	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
210	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	3,246.000	TON
211	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	11,064.000	TON
212	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	18,942.000	TON
213	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	9,737.000	TON
214	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	20,332.000	TON
215	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	60,545.000	TON
216	406-05520 ASPHALT FOR TACK COAT	176.000	TON
217	606-07484 MILLED HMA SHOULDER CORRUGATIONS	79,810.000	LFT
218	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	9,976.000	LFT
219	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	1,595.000	LFT
220	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	1,595.000	LFT
221	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	399.000	LFT
222	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	39,905.000	LFT
223	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	39,905.000	LFT
SECTION NO. 0003 NEW ROAD CONSTRUCTION			
224	207-08263 SUBGRADE TREATMENT, TYPE IA	198,290.000	SYS
225	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	10,021.000	TON
226	302-06464 SUBBASE FOR PCCP	28,820.000	CYS
227	303-01180 COMPACTED AGGREGATE, NO. 53	16,489.000	TON
228	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	4,801.000	TON
229	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	10,537.000	TON
230	402-07786 HMA BASE, TYPE D	20,997.000	TON
231	406-05520 ASPHALT FOR TACK COAT	57.000	TON
232	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
233	501-08193 QC/QA-PCCP, 10.5 IN	115,280.000	SYS
234	503-05240 D-1 CONTRACTION JOINT	69,168.000	LFT
235	503-05310 TERMINAL JOINT	430.000	LFT
236	606-07484 MILLED HMA SHOULDER CORRUGATIONS	39,905.000	LFT
237	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	39,905.000	LFT
238	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	41,500.000	LFT
239	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	41,500.000	LFT

CALL ORDER : 130

CONTRACT ID : IR-33741-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW ROAD CONSTRUCTION		
240 808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	10,375.000	LFT