

CALL ORDER : 191

CONTRACT ID : IR-33030-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD CONSTRUCTION - HMA			
1	203-02000 EXCAVATION, COMMON	247,865.000	CYS
2	203-02070 BORROW	12,941.000	CYS
3	211-09264 STRUCTURAL BACKFILL, TYPE 1	922.000	CYS
4	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	16,627.000	TON
5	303-01180 COMPACTED AGGREGATE, NO. 53	8,284.000	TON
6	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,564.000	TON
7	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	3,582.000	TON
8	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	6,025.000	TON
9	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	4,689.000	TON
10	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	14,829.000	TON
11	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	5,638.000	TON
12	406-05520 ASPHALT FOR TACK COAT	59.700	TON
13	606-07484 MILLED HMA SHOULDER CORRUGATIONS	14,630.000	LFT
14	615-06505 MONUMENT, B	26.000	EACH
15	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	40,395.000	LFT
16	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	546.000	LFT
17	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	546.000	LFT
18	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	590.000	LFT
19	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	34,604.000	LFT
20	808-75290 TRANSVERSE MARKING, THERMOPLASTIC,	1,700.000	LFT
21	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	125.000	LFT
22	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	15.000	EACH
23	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	18.000	EACH
SECTION NO. 0002 ROAD CONSTRUCTION - PCCP			
24	203-02000 EXCAVATION, COMMON	250,192.000	CYS
25	203-02070 BORROW	7,092.000	CYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	911.000	CYS
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	15,726.000	TON
28	302-06464 SUBBASE FOR PCCP	12,033.000	CYS
29	303-01180 COMPACTED AGGREGATE, NO. 53	6,806.000	TON
30	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,582.000	TON
31	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	3,227.000	TON
32	406-05520 ASPHALT FOR TACK COAT	18.600	TON
33	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
34	501-09749 QC/QA PCCP, 9.5"	43,250.000	SYS
35	503-05240 D-1 CONTRACTION JOINT	24,754.000	LFT
36	503-05310 TERMINAL JOINT	56.000	LFT
37	606-11064 MILLED PCCP SHOULDER CORRUGATIONS	14,630.000	LFT
38	615-06505 MONUMENT, B	20.000	EACH
39	615-06515 MONUMENT, D	6.000	EACH
40	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	41,106.000	LFT
41	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	35,150.000	LFT
42	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	590.000	LFT
43	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	125.000	LFT
44	808-10052 PAVEMENT MESSAGE MKG, MULTI-COMP, (ONLY)	18.000	EACH
45	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	15.000	EACH
46	808-10119 TRANSVERSE MARKING, MULTI-COMPONENT, SOLID,	1,700.000	LFT

CALL ORDER : 191

CONTRACT ID : IR-33030-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	ROAD AND BRIDGE CONSTRUCTION--COMMON ITEMS		
47	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
48	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
49	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
50	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
51	202-01261 TESTING FOR ASBESTOS	7.000	EACH
52	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
53	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
54	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
55	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
56	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
57	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
58	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
59	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
60	203-02010 EXCAVATION, ROCK	16,500.000	CYS
61	204-08415 STAKE, SETTLEMENT	11.000	EACH
62	205-03371 SEDIMENT, REMOVE	1,134.000	CYS
63	205-06930 SPLASHPAD, RIPRAP	163.800	TON
64	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	436.000	TON
65	205-06932 TEMPORARY CHECK DAM, STRAW BALES	483.000	LFT
66	205-06936 TEMPORARY SEDIMENT TRAP	1,198.000	TON
67	205-06937 TEMPORARY SILT FENCE	11,571.000	LFT
68	205-06938 TEMPORARY SLOPE DRAIN	502.000	LFT
69	205-09543 NO 2 STONE	200.000	TON
70	206-51220 EXCAVATION, WET	4,237.000	CYS
71	207-08263 SUBGRADE TREATMENT, TYPE IA	85,874.000	SYS
72	207-08265 SUBGRADE TREATMENT, TYPE IIA	14,312.000	SYS
73	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,813.000	SYS
74	211-02050 B BORROW	12,509.000	CYS
75	211-09266 STRUCTURAL BACKFILL, TYPE 3	18,029.000	CYS
76	302-07455 DENSE GRADED SUBBASE	104.000	CYS
77	306-08043 MILLING, TRANSITION	1,395.000	SYS
78	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
79	402-07432 HMA SURFACE, TYPE A	1,402.000	TON
80	402-07433 HMA SURFACE, TYPE B	461.000	TON
81	402-07435 HMA INTERMEDIATE, TYPE A	2,418.000	TON
82	402-07438 HMA INTERMEDIATE, TYPE B	776.000	TON
83	402-10087 HMA FOR TEMPORARY PAVEMENT, D	3,110.000	TON
84	601-01522 GUARDRAIL, TRANSITION TYPE TGB	8.000	EACH
85	601-94689 GUARDRAIL END TREATMENT, OS	12.000	EACH
86	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,156.250	LFT
87	602-06729 BARRIER DELINEATOR	24.000	EACH
88	603-06040 FENCE, FARM FIELD, 47 IN	23,764.000	LFT
89	603-93373 FENCE, PEDESTRIAN	404.000	LFT
90	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	616.000	SYS
91	610-07486 HMA FOR APPROACHES, TYPE A	683.000	TON
92	610-07487 HMA FOR APPROACHES, TYPE B	1,056.000	TON
93	611-06497 MAILBOX ASSEMBLY, SINGLE	4.000	EACH
94	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
95	615-06490 RIGHT OF WAY MARKER	75.000	EACH
96	615-06510 MONUMENT, C	13.000	EACH

CALL ORDER : 191

CONTRACT ID : IR-33030-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	ROAD AND BRIDGE CONSTRUCTION--COMMON ITEMS		
97	616-02320 GEOTEXTILES	2,350.000	SYS
98	616-05688 RIPRAP, CLASS 1	35.400	TON
99	616-06405 RIPRAP, REVETMENT	1,374.000	TON
100	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
101	621-02770 EROSION CONTROL BLANKET	36,671.000	SYS
102	621-06545 FERTILIZER	18.900	TON
103	621-06553 SEED MIXTURE, R	8,027.000	LBS
104	621-06557 SEED MIXTURE, T	7,083.000	LBS
105	621-06565 MULCHING MATERIAL	95.000	TON
106	621-06567 WATER	77.000	KGAL
107	621-06574 SODDING	21,271.000	SYS
108	622-52436 SIGN, DO NOT MOW OR SPRAY	19.000	EACH
109	628-09403 FIELD OFFICE, C	24.000	MOS
110	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	24.000	MOS
111	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	96.000	MOS
112	628-11068 CELLULAR TELEPHONE/RADIO	4.000	EACH
113	701-02938 CORED HOLE IN ROCK, 24 IN	45.000	LFT
114	701-06011 DYNAMIC PILE LOAD TEST	3.000	EACH
115	701-09557 TEST PILE, DYNAMIC, PRODUCTION	159.000	LFT
116	701-09559 TEST PILE, DYNAMIC, RESTRIKE	3.000	EACH
117	701-09739 PILE SHOE, HP 12 X 53	32.000	EACH
118	701-51195 PILE, STEEL H, HP 12 IN X 53	1,230.000	LFT
119	703-06029 REINFORCING BARS, EPOXY COATED	140,795.000	LBS
120	704-51002 CONCRETE, C, SUPERSTRUCTURE	519.600	CYS
121	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	8.000	EACH
122	706-51020 RAILING, CONCRETE, C	39.200	CYS
123	707-05984 STRUCTURAL MEMBER, CONCRETE I-BEAM, 45 IN X 16 IN	332.000	LFT
124	707-09634 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 48 IN X 49 IN	583.000	LFT
125	709-51821 SURFACE SEAL	LUMP	LUMP
126	709-51821 SURFACE SEAL	LUMP	LUMP
127	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	972.000	LFT
128	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	21,738.000	LFT
129	715-05049 PIPE, TYPE 4 CIRCULAR 8 IN	400.000	LFT
130	715-05051 PIPE, TYPE 4 CIRCULAR 10 IN	400.000	LFT
131	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	2,046.000	LFT
132	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	64.000	LFT
133	715-05125 PIPE, TYPE 1 CIRCULAR 30 IN	67.000	LFT
134	715-05128 PIPE, TYPE 1 CIRCULAR 48 IN	192.000	LFT
135	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	588.000	LFT
136	715-06004 CONCRETE ANCHOR, 48 IN	2.000	EACH
137	715-08177 PIPE, TYPE 1 DEFORMED MIN AREA 10.2 SF	110.000	LFT
138	715-08179 CONCRETE ANCHOR MIN AREA 10.2 SF	2.000	EACH
139	715-09064 VIDEO INSPECTION FOR PIPE	2,042.000	LFT
140	715-46005 PIPE END SECTION, 15 IN	28.000	EACH
141	715-46010 PIPE END SECTION, 18 IN	2.000	EACH
142	715-46030 PIPE END SECTION, 30 IN	2.000	EACH
143	715-46040 PIPE END SECTION, 36 IN	12.000	EACH
144	718-06528 OUTLET PROTECTOR, 1	14.000	EACH
145	718-06531 OUTLET PROTECTOR, 3	53.000	EACH

CALL ORDER : 191

CONTRACT ID : IR-33030-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	ROAD AND BRIDGE CONSTRUCTION--COMMON ITEMS		
146	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
147	718-52610 AGGREGATE FOR UNDERDRAINS	1,921.000	CYS
148	718-99153 GEOTEXTILES FOR UNDERDRAIN	21,734.000	SYS
149	719-05439 PIPE, DRAIN TILE TERMINAL SECTION, 6 IN	40.000	LFT
150	719-05440 PIPE, DRAIN TILE TERMINAL SECTION, 8 IN	40.000	LFT
151	719-05442 PIPE, DRAINTILE TERMINAL SECTION, 10 IN	40.000	LFT
152	731-93945 FACE PANELS, CONCRETE	13,244.000	SFT
153	731-93945 FACE PANELS, CONCRETE	5,889.000	SFT
154	731-93946 WALL ERECTION	19,133.000	SFT
155	731-93947 LEVELING PAD, CONCRETE	780.000	LFT
156	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	19,594.000	LFT
157	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	469.000	LFT
158	801-06640 CONSTRUCTION SIGN, A	67.000	EACH
159	801-06645 CONSTRUCTION SIGN, B	17.000	EACH
160	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
161	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	4.000	EACH
162	801-07118 BARRICADE, III-A	250.000	LFT
163	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	1,649.000	LFT
164	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	447.000	LFT
165	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	586.500	LFT
166	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	26.000	LFT
167	802-07057 SIGN, PANEL, WITH LEGEND	18.800	SFT
168	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	5.000	EACH
169	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	2.000	EACH
170	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	149.000	SFT
171	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	348.000	SFT
172	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	1,126.000	LFT
173	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
174	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	877.000	EACH

CALL ORDER : 221

CONTRACT ID : IR-34264-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENVIRONMENTAL MITIGATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-07083 REMOVAL	LUMP	LUMP
9	203-02020 EXCAVATION, UNCLASSIFIED	47.900	CYS
10	205-09543 NO 2 STONE	150.000	TON
11	603-06040 FENCE, FARM FIELD, 47 IN	813.000	LFT
12	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
13	621-04258 SEED MIXTURE	337.500	LBS
14	621-06545 FERTILIZER	16.340	TON
15	621-06565 MULCHING MATERIAL	5.000	TON
16	622-52436 SIGN, DO NOT MOW OR SPRAY	49.000	EACH
17	622-91786 SEEDLING	6,404.000	EACH
18	622-91786 SEEDLING	25,628.000	EACH
19	628-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
20	628-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
21	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
22	628-09403 FIELD OFFICE, C	6.000	MOS
23	804-06770 DELINEATOR POST	80.000	EACH

CALL ORDER : 281

CONTRACT ID : R -29395-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02271 HEADWALL, REMOVE	1.000	EACH
12	202-02272 PAVED SIDE DITCH, REMOVE	60.000	LFT
13	202-02273 CENTER CURB, CONCRETE, REMOVE	9.000	SYS
14	202-02278 CURB, CONCRETE, REMOVE	177.000	LFT
15	202-02772 CASTING, REMOVE	2.000	EACH
16	202-52710 SIDEWALK, CONCRETE, REMOVE	3.100	SYS
17	202-90277 DETECTOR HOUSING, REMOVE	4.000	EACH
18	202-91385 INLET, REMOVE	1.000	EACH
19	202-94749 CURB, ASPHALT, REMOVE	71.000	LFT
20	202-96133 PIPE, REMOVE	166.000	LFT
21	203-02000 EXCAVATION, COMMON	11,561.000	CYS
22	203-02010 EXCAVATION, ROCK	760.000	CYS
23	203-02070 BORROW	3,397.000	CYS
24	205-06930 SPLASHPAD, RIPRAP	1.400	TON
25	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	56.300	TON
26	205-06932 TEMPORARY CHECK DAM, STRAW BALES	132.000	LFT
27	205-06933 TEMPORARY DITCH INLET PROTECTION	4.000	EACH
28	205-06934 TEMPORARY MULCHING	3.100	TON
29	205-06937 TEMPORARY SILT FENCE	2,261.000	LFT
30	205-06938 TEMPORARY SLOPE DRAIN	55.000	LFT
31	205-09543 NO 2 STONE	45.000	TON
32	205-09543 NO 2 STONE	100.000	TON
33	207-06014 LIME STABILIZED SOIL	388.000	SYS
34	207-08263 SUBGRADE TREATMENT, TYPE IA	3,546.000	SYS
35	207-08265 SUBGRADE TREATMENT, TYPE IIA	4,453.000	SYS
36	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,017.000	SYS
37	207-09935 SUBGRADE TREATMENT, TYPE 1C	2,894.000	SYS
38	211-02050 B BORROW	6.000	CYS
39	211-02050 B BORROW	970.000	CYS
40	211-09194 B BORROW	2,600.000	TON
41	211-09264 STRUCTURAL BACKFILL, TYPE 1	377.000	CYS
42	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,467.000	TON
43	302-08562 COARSE AGGREGATE, NO 8	1,560.000	TON
44	303-01180 COMPACTED AGGREGATE, NO. 53	1,374.000	TON
45	303-07449 COMPACTED AGGREGATE, NO. 73	374.000	TON
46	303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS	30.000	TON
47	304-07491 HMA PATCHING, TYPE C	8.000	TON
48	306-08034 MILLING, ASPHALT, 1 1/2 IN	3,649.000	SYS
49	306-08042 MILLING, SCARIFICATION/PROFILE	3,016.000	SYS

CALL ORDER : 281

CONTRACT ID : R -29395-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	401-06264		LUMP
51	401-07334		LUMP
52	402-07432	747.000	TON
53	402-07433	212.000	TON
54	402-07434	20.000	TON
55	402-07435	223.000	TON
56	402-07438	108.000	TON
57	402-07439	45.000	TON
58	402-07442	1,151.000	TON
59	402-07784	1,128.000	TON
60	402-07785	336.000	TON
61	402-07786	145.000	TON
62	402-07787	348.000	TON
63	402-10083	26.000	TON
64	406-05520	96.000	TON
65	601-01522	7.000	TON
66	601-01740	1.000	EACH
67	601-02241	3.000	EACH
68	601-06242	328.000	LFT
69	601-94689	1.000	EACH
70	601-99105	3.000	EACH
71	602-06729	452.000	LFT
72	602-08605	15.000	EACH
73	605-06120	140.000	LFT
74	605-06145	25.000	LFT
75	605-06215	325.000	LFT
76	605-97305	5.000	LFT
77	607-06335	1.000	EACH
78	610-07487	119.000	LFT
79	610-09108	440.000	TON
80	615-06490	57.000	SYS
81	615-06505	40.000	EACH
82	616-02320	14.000	EACH
83	616-06405	906.000	SYS
84	616-06451	172.000	TON
85	621-01004	112.000	TON
86	621-06545	4.000	EACH
87	621-06553	1.000	TON
88	621-06557	258.000	LBS
89	621-06560	486.000	LBS
90	621-06565	2,517.000	SYS
91	621-06567	7.000	TON
92	621-06574	26.500	kgAL
93	621-06575	1,308.000	SYS
94	628-08524	5,800.000	SYS
95	628-09402	1.000	DOL
96	628-09407	9.000	MOS
97	628-10246	18.000	MOS
98	628-11068	27.000	MOS
		3.000	EACH

CALL ORDER : 281

CONTRACT ID : R -29395-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
99	702-90915 CONCRETE, CLASS A	74.000	CYS
100	703-06028 REINFORCING BARS	276.000	LBS
101	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	104.000	LFT
102	715-05128 PIPE, TYPE 1 CIRCULAR 48 IN	78.000	LFT
103	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	104.000	LFT
104	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	305.000	LFT
105	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	33.000	LFT
106	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	116.000	LFT
107	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	138.000	LFT
108	715-06004 CONCRETE ANCHOR, 48 IN	2.000	EACH
109	715-46005 PIPE END SECTION, 15 IN	14.000	EACH
110	715-46010 PIPE END SECTION, 18 IN	2.000	EACH
111	715-46040 PIPE END SECTION, 36 IN	4.000	EACH
112	715-97122 PIPE, PVC, 2 IN	90.000	LFT
113	716-07635 PIPE INSTALLATION, TRENCHLESS, 36 IN	124.000	LFT
114	718-09978 UNDERDRAIN OUTLET INSPECTION	1.000	EACH
115	718-09979 UNDERDRAIN OUTLET CLEANING	1.000	EACH
116	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	2.000	EACH
117	720-02442 PIPE, PLUG EXISTING	1.000	EACH
118	720-07301 INLET, TYPE HA	1.000	EACH
119	720-07301 INLET, TYPE HA	1.000	EACH
120	720-45035 INLET, F7	1.000	EACH
121	801-03290 CONSTRUCTION SIGN, C	14.000	EACH
122	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
123	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	6,768.000	LFT
124	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	16,387.000	LFT
125	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	63.000	LFT
126	801-06625 DETOUR ROUTE MARKER ASSEMBLY	29.000	EACH
127	801-06640 CONSTRUCTION SIGN, A	61.000	EACH
128	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
129	801-06710 FLASHING ARROW SIGN	5.000	DAY
130	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
131	801-07118 BARRICADE, III-A	96.000	LFT
132	801-07119 BARRICADE, III-B	92.000	LFT
133	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	1,120.000	LFT
134	802-04089 SIGN, SHEET, REMOVE	1.000	EACH
135	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	161.000	LFT
136	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	9.000	EACH
137	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	84.000	SFT
138	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	29.100	SFT
139	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	6.500	SFT
140	802-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	3.000	EACH
141	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	3.000	EACH
142	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	142.000	LFT
143	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	3.000	EACH
144	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	1.000	EACH
145	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	1.000	EACH
146	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	2,500.000	LFT
147	805-78485 SIGNAL CABLE, 5C/14GA	125.000	LFT



CALL ORDER : 281

CONTRACT ID : R -29395-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
148	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	250.000	LFT
149	805-78785 SIGNAL DETECTOR HOUSING	5.000	EACH
150	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	680.000	LFT
151	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	1.000	EACH
152	808-02157 PAVEMENT MESSAGE MARKING, REMOVE	3.000	EACH
153	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	826.000	LFT
154	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,684.000	LFT
155	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	2,229.000	LFT
156	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	1,207.000	LFT
157	808-06716 LINE, REMOVE	9,774.000	LFT
158	808-06723 PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	8.000	EACH
159	808-06726 TRANSVERSE MARKING, PAINT,	33.000	LFT
160	808-11350 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN., 24 IN. LINE,	125.000	LFT
161	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	4,054.000	LFT
162	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	7,089.000	LFT
163	808-75290 TRANSVERSE MARKING, THERMOPLASTIC,	254.000	LFT
164	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	239.000	LFT
165	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	8.000	EACH
166	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	7.000	EACH
167	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	41.000	EACH
168	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	115.000	EACH