

CALL ORDER : 140

CONTRACT ID : IB-33804-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	1,745.000	CYS
13	203-02055 EMBANKMENT	185,478.000	CYS
14	203-04523 DEWATERING	LUMP	LUMP
15	205-03371 SEDIMENT, REMOVE	500.000	CYS
16	205-06930 SPLASHPAD, RIPRAP	16.000	TON
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	244.000	TON
18	205-06934 TEMPORARY MULCHING	24.000	TON
19	205-06935 TEMPORARY SEDIMENT BASIN	1.000	EACH
20	205-06936 TEMPORARY SEDIMENT TRAP	154.000	TON
21	205-06938 TEMPORARY SLOPE DRAIN	518.000	LFT
22	205-09543 NO 2 STONE	200.000	TON
23	206-51225 EXCAVATION, DRY	185.000	CYS
24	207-08265 SUBGRADE TREATMENT, TYPE IIA	16,071.000	SYS
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	94.000	SYS
26	211-02050 B BORROW	14,180.000	CYS
27	211-09264 STRUCTURAL BACKFILL, TYPE 1	28.000	CYS
28	211-09266 STRUCTURAL BACKFILL, TYPE 3	9,382.000	CYS
29	215-07043 CHEMICAL MODIFICATION, SOILS	50,000.000	SYS
30	215-09385 CHEMICAL MODIFIER, SOILS, MODIFYING WET FILL SOIL,	1,000.000	TON
31	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,705.000	TON
32	302-07455 DENSE GRADED SUBBASE	27.000	CYS
33	303-01180 COMPACTED AGGREGATE, NO. 53	1,814.000	TON
34	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
35	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	951.000	TON
36	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	2,894.000	TON
37	402-07432 HMA SURFACE, TYPE A	494.000	TON
38	406-05521 ASPHALT FOR TACK COAT	25,917.000	SYS
39	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
40	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
41	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
42	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	187.500	LFT
43	602-06729 BARRIER DELINEATOR	24.000	EACH
44	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	166.000	SYS
45	610-07487 HMA FOR APPROACHES, TYPE B	28.000	TON
46	615-06490 RIGHT OF WAY MARKER	22.000	EACH
47	615-06505 MONUMENT, B	5.000	EACH
48	615-06510 MONUMENT, C	1.000	EACH
49	615-06515 MONUMENT, D	1.000	EACH

CALL ORDER : 140

CONTRACT ID : IB-33804-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
50	616-02320 GEOTEXTILES	769.000	SYS
51	616-06405 RIPRAP, REVETMENT	416.000	TON
52	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
53	621-06545 FERTILIZER	5.000	TON
54	621-06553 SEED MIXTURE, R	2,040.000	LBS
55	621-06557 SEED MIXTURE, T	1,800.000	LBS
56	621-06565 MULCHING MATERIAL	24.000	TON
57	621-06567 WATER	1.000	KGAL
58	621-06574 SODDING	365.000	SYS
59	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
60	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	36.000	MOS
61	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
62	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
63	701-09557 TEST PILE, DYNAMIC, PRODUCTION	150.000	LFT
64	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
65	701-09683 PILE SHOE, HP 12 X 74	46.000	EACH
66	701-95780 PILE, STEEL H, HP 12 IN X 74	2,495.000	LFT
67	702-51005 CONCRETE, A, SUBSTRUCTURE	158.300	CYS
68	702-51015 CONCRETE, B, FOOTINGS	95.600	CYS
69	703-06028 REINFORCING BARS	43,677.000	LBS
70	703-06029 REINFORCING BARS, EPOXY COATED	154,933.000	LBS
71	704-51002 CONCRETE, C, SUPERSTRUCTURE	625.300	CYS
72	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
73	706-09960 RAILING, CONCRETE, FC	824.000	LFT
74	707-10176 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 72 IN X 49 IN	2,050.000	LFT
75	709-51821 SURFACE SEAL	LUMP	LUMP
76	711-02707 ANCHOR PLATE	20.000	EACH
77	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	500.000	LFT
78	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	500.000	LFT
79	715-05118 PIPE, TYPE 1 CIRCULAR 12 IN	500.000	LFT
80	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	145.000	LFT
81	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	500.000	LFT
82	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	204.000	LFT
83	715-05212 PIPE, TYPE 4 CIRCULAR 24 IN	500.000	LFT
84	715-09064 VIDEO INSPECTION FOR PIPE	145.000	LFT
85	715-09446 PIPE, TYPE 4 CIRCULAR 36 IN	500.000	LFT
86	715-46010 PIPE END SECTION, 18 IN	10.000	EACH
87	719-05443 PIPE, DRAINTILE TERMINAL SECTION, 12 IN	100.000	LFT
88	719-09447 PIPE, DRAIN TILE TERMINAL SECTION, 24 IN	100.000	LFT
89	719-09448 PIPE, DRAIN TILE, TERMINAL SECTION, 36 IN	100.000	LFT
90	720-45410 MANHOLE, C4	4.000	EACH
91	731-93945 FACE PANELS, CONCRETE	11,184.000	SFT
92	731-93946 WALL ERECTION	11,184.000	SFT
93	731-93947 LEVELING PAD, CONCRETE	431.000	LFT
94	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
95	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
96	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
97	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
98	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 140

CONTRACT ID : IB-33804-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
99	801-07118 BARRICADE, III-A	118.000	LFT
100	801-07119 BARRICADE, III-B	72.000	LFT
101	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	101.500	LFT
102	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	47.500	SFT
103	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	6.250	SFT
104	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,541.000	LFT
105	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
106	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	906.000	LFT
107	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	906.000	LFT
108	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	7,442.000	LFT
109	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	15.000	LFT

CALL ORDER : 150

CONTRACT ID : IR-30293-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	28,674.000	SYS
14	202-02271 HEADWALL, REMOVE	16.000	EACH
15	202-02272 PAVED SIDE DITCH, REMOVE	344.000	LFT
16	202-02279 CURB AND GUTTER, REMOVE	961.000	LFT
17	202-06580 CONTAMINATED SOIL, REMOVE	20.000	CYS
18	202-74045 SIGN AND SUPPORTS, CHAN POSTS, REMOVE	74.000	EACH
19	202-74080 OVERHEAD SIGN STRUCTURE,	2.000	EACH
20	202-82066 SIGN CIRCUITRY, CANTILEVERS, REMOVE	2.000	EACH
21	202-86946 HANDHOLE, REMOVE	3.000	EACH
22	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	8.000	EACH
23	202-96035 CONCRETE WALL, REMOVE	20.000	LFT
24	202-96133 PIPE, REMOVE	1,108.000	LFT
25	202-99187 FENCE, FARM FIELD, REMOVE	2,579.000	LFT
26	203-02000 EXCAVATION, COMMON	41,965.000	CYS
27	203-02070 BORROW	9,115.000	CYS
28	205-03371 SEDIMENT, REMOVE	2,051.000	CYS
29	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	253.000	TON
30	205-06932 TEMPORARY CHECK DAM, STRAW BALES	402.000	LFT
31	205-06933 TEMPORARY DITCH INLET PROTECTION	7.000	EACH
32	205-06934 TEMPORARY MULCHING	73.000	TON
33	205-06936 TEMPORARY SEDIMENT TRAP	20.000	TON
34	205-06937 TEMPORARY SILT FENCE	18,458.000	LFT
35	205-09543 NO 2 STONE	46.000	TON
36	207-08263 SUBGRADE TREATMENT, TYPE IA	102,662.000	SYS
37	207-08263 SUBGRADE TREATMENT, TYPE IA	9,100.000	SYS
38	207-08267 SUBGRADE TREATMENT, TYPE IIIA	5,305.000	SYS
39	211-09264 STRUCTURAL BACKFILL, TYPE 1	900.000	CYS
40	211-09265 STRUCTURAL BACKFILL, TYPE 2	1,251.000	CYS
41	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	613.000	CYS
42	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	7,516.000	TON
43	302-06464 SUBBASE FOR PCCP	24,464.000	CYS
44	303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS	30.000	TON
45	306-08034 MILLING, ASPHALT, 1 1/2 IN	3,039.000	SYS
46	402-07784 HMA SURFACE, TYPE D	268.000	TON
47	402-07785 HMA INTERMEDIATE, TYPE D	67.000	TON
48	402-10083 HMA FOR TEMPORARY PAVEMENT, A	2,241.000	TON
49	406-05521 ASPHALT FOR TACK COAT	15,143.000	SYS

CALL ORDER : 150

CONTRACT ID : IR-30293-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
50	501-06321 QC/QA-PCCP, 10 IN	93,599.000	SYS
51	503-05240 D-1 CONTRACTION JOINT	53,189.000	LFT
52	601-01522 GUARDRAIL, TRANSITION TYPE TGB	2.000	EACH
53	601-01701 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 2	2.000	EACH
54	601-01848 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 5	1.000	EACH
55	601-02241 GUARDRAIL, REMOVE	1,325.000	LFT
56	601-05071 GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, 7	1.000	EACH
57	601-06411 IMPACT ATTENUATOR SPARE PARTS PACKAGE, CR, W1, TL-3	1.000	EACH
58	601-06854 GUARDRAIL, W-BEAM, NESTED	5.000	EACH
59	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
60	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
61	601-09149 IMPACT ATTENUATOR, CR1, W1, TL-3	2.000	EACH
62	601-94689 GUARDRAIL END TREATMENT, OS	15.000	EACH
63	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	3,583.000	LFT
64	601-99123 GUARDRAIL, TRANSITION, GP	4.000	EACH
65	603-06040 FENCE, FARM FIELD, 47 IN	2,579.000	LFT
66	605-06090 CURB, INTEGRAL, CONCRETE	217.000	LFT
67	605-06121 CURB, CONCRETE, B	1,442.000	LFT
68	605-06140 CURB AND GUTTER, CONCRETE	42.000	LFT
69	605-06145 CURB AND GUTTER, B, CONCRETE	177.000	LFT
70	605-06245 CENTER CURB, B, CONCRETE	4,255.000	SYS
71	610-07487 HMA FOR APPROACHES, TYPE B	1,776.000	TON
72	610-09108 PCCP FOR APPROACHES, 9 IN	2,088.000	SYS
73	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
74	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
75	615-06490 RIGHT OF WAY MARKER	61.000	EACH
76	615-06500 MONUMENT, A	2.000	EACH
77	615-06505 MONUMENT, B	6.000	EACH
78	615-06510 MONUMENT, C	2.000	EACH
79	615-06515 MONUMENT, D	48.000	EACH
80	615-06520 MONUMENT, RE-ESTABLISH	1.000	EACH
81	615-06535 BENCH MARK POST, RESET	1.000	EACH
82	616-02320 GEOTEXTILES	1,282.000	SYS
83	616-05688 RIPRAP, CLASS 1	77.000	TON
84	616-06405 RIPRAP, REVETMENT	445.000	TON
85	616-06451 RIPRAP, UNIFORM	62.000	TON
86	619-04414 DRAIN EXTENSION	8.000	EACH
87	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
88	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
89	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
90	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
91	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
92	621-02770 EROSION CONTROL BLANKET	66,315.000	SYS
93	621-06545 FERTILIZER	6.000	TON
94	621-06557 SEED MIXTURE, T	1,088.000	LBS
95	621-06565 MULCHING MATERIAL	29.000	TON
96	621-06567 WATER	253.000	KGAL
97	621-06574 SODDING	3,864.000	SYS
98	621-06575 SODDING, NURSERY	66,315.000	SYS

CALL ORDER : 150

CONTRACT ID : IR-30293-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
99	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
100	628-09403 FIELD OFFICE, C	15.000	MOS
101	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	30.000	MOS
102	628-11007 CELLULAR TELEPHONE/RADIO SERVICE, 750 MINUTES	60.000	MOS
103	628-11068 CELLULAR TELEPHONE/RADIO	4.000	EACH
104	702-51863 FIELD DRILLED HOLE IN CONCRETE	158.000	EACH
105	702-90915 CONCRETE, CLASS A	47.400	CYS
106	703-06029 REINFORCING BARS, EPOXY COATED	3,869.000	LBS
107	706-09545 COARSE AGGREGATE, NO 8	400.000	CYS
108	709-51821 SURFACE SEAL	LUMP	LUMP
109	714-11175 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	225.000	LFT
110	714-11311 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	137.000	LFT
111	715-04555 PIPE END SECTION, MIN AREA 5.1 SF	8.000	EACH
112	715-05032 PIPE, TYPE 2 CIRCULAR 15 IN	961.000	LFT
113	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	16,505.000	LFT
114	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	775.000	LFT
115	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	114.000	LFT
116	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	210.000	LFT
117	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	409.000	LFT
118	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	1,037.000	LFT
119	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	130.000	LFT
120	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	319.000	LFT
121	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	88.000	LFT
122	715-05236 PIPE, TYPE 1 DEFORMED MIN AREA 5 SF	308.000	LFT
123	715-06471 PIPE END SECTION, MIN AREA 3.3 SF	2.000	EACH
124	715-08243 PIPE, TYPE 3 DEFORMED MIN AREA 3.3 SF	48.000	LFT
125	715-09064 VIDEO INSPECTION FOR PIPE	2,792.000	LFT
126	715-09769 PIPE, TYPE 3 DEFORMED, MIN AREA 5.1 SFT	240.000	LFT
127	715-46005 PIPE END SECTION, 15 IN	14.000	EACH
128	715-46010 PIPE END SECTION, 18 IN	5.000	EACH
129	715-46020 PIPE END SECTION, 24 IN	4.000	EACH
130	715-46030 PIPE END SECTION, 30 IN	1.000	EACH
131	718-06529 OUTLET PROTECTOR, 2	6.000	EACH
132	718-06531 OUTLET PROTECTOR, 3	30.000	EACH
133	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
134	718-52610 AGGREGATE FOR UNDERDRAINS	1,496.000	CYS
135	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
136	720-45025 INLET, D6	1.000	EACH
137	720-45030 INLET, E7	1.000	EACH
138	720-45035 INLET, F7	3.000	EACH
139	720-45040 INLET, G7	2.000	EACH
140	720-45510 MANHOLE, C4, MODIFIED	2.000	EACH
141	720-95409 MANHOLE, J4, MODIFIED	2.000	EACH
142	720-97865 MANHOLE, C2, MODIFIED	4.000	EACH
143	720-98555 INLET, C15	1.000	EACH
144	723-08608 WINGWALL	608.000	SFT
145	727-90308 EPOXY INJECTION, CRACK PREPARATION	119.000	LFT
146	727-90309 EPOXY INJECTION, EPOXY MATERIAL	15.000	GAL
147	727-93560 EPOXY INJECTION, FURNISHING EQUIPMENT	LUMP	LUMP

CALL ORDER : 150

CONTRACT ID : IR-30293-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
148	801-02595 CONTROLLER, RESET TIMING	3.000	EACH
149	801-03290 CONSTRUCTION SIGN, C	12.000	EACH
150	801-04308 ROAD CLOSURE SIGN ASSEMBLY	20.000	EACH
151	801-06201 TEMPORARY PANEL SIGNS	22.500	SFT
152	801-06202 TEMPORARY PANEL SIGN SUPPORTS	56.000	LFT
153	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	35,000.000	LFT
154	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	64,300.000	LFT
155	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	13.000	EACH
156	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	377.000	LFT
157	801-06640 CONSTRUCTION SIGN, A	37.000	EACH
158	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
159	801-06710 FLASHING ARROW SIGN	30.000	DAY
160	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
161	801-07118 BARRICADE, III-A	468.000	LFT
162	801-07119 BARRICADE, III-B	48.000	LFT
163	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	9,260.000	LFT
164	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	252.000	LFT
165	801-94295 SIGNAL HEAD, RELOCATE	32.000	EACH
166	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	765.500	LFT
167	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	211.250	LFT
168	802-07057 SIGN, PANEL, WITH LEGEND	899.000	SFT
169	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	10.000	EACH
170	802-08456 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	12.000	EACH
171	802-09578 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	2.000	EACH
172	802-09581 OVERHEAD BALANCED CANTILEVER SIGN STRUCTURE FOUNDATION,	2.000	EACH
173	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	504.780	SFT
174	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	104.100	SFT
175	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	78.000	SFT
176	802-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	6.000	EACH
177	802-76095 STRUCTURAL STEEL, BREAKAWAY	4,874.000	LBS
178	804-06771 DELINEATOR POST, FLEXIBLE	50.000	EACH
179	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.000	EACH
180	805-01842 HANDHOLE, SIGNAL	21.000	EACH
181	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	4.000	EACH
182	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	4,042.000	LFT
183	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
184	805-02373 SIGNAL INTERCONNECT CABLE, FIBER OPTIC	2,057.000	LFT
185	805-09366 SIGNAL SUPPORT FOUNDATION, 36 IN DIAMETER X 120 IN	10.000	EACH
186	805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL	2.000	EACH
187	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
188	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	20.000	EACH
189	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	4.000	EACH
190	805-78415 SPAN, CATENARY, AND TETHER	10.000	EACH
191	805-78420 DISCONNECT HANGER	10.000	EACH
192	805-78467 SIGNAL CABLE, 3C/8GA	55.000	LFT
193	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	6,552.000	LFT
194	805-78485 SIGNAL CABLE, 5C/14GA	538.000	LFT
195	805-78490 SIGNAL CABLE, 7C/14GA	2,486.000	LFT
196	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	7,814.000	LFT

CALL ORDER : 150

CONTRACT ID : IR-30293-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
197	805-78785 SIGNAL DETECTOR HOUSING	17.000	EACH
198	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	2,336.000	LFT
199	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
200	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT	10.000	EACH
201	805-86890 CABLE POLE CIRCUIT THWH, NO 10 COPPER STRANDED	840.000	LFT
202	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	10.000	EACH
203	807-02191 HANDHOLE, LIGHTING	3.000	EACH
204	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	8.000	EACH
205	807-02426 WIRE, THW, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	535.000	LFT
206	807-03051 LIGHT CABLE, 1/C 10GA.	960.000	LFT
207	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	2,990.000	LFT
208	807-82052 CIRCUIT INSTALLATION, UNDERPASS, 2 LUMINAIRE,S	2.000	EACH
209	807-85752 LIGHT POLE, 40 FT E.M.H., 10.0 FT MAST ARM, BREAKAWAY BASE	8.000	EACH
210	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	8.000	EACH
211	807-86750 LUMINAIRE, UNDERPASS, WALL MOUNTED, HIGH PRESSURE, 150	4.000	EACH
212	807-86910 CONNECTOR KIT, UNFUSED	8.000	EACH
213	807-86915 CONNECTOR KIT, FUSED	8.000	EACH
214	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	18.000	EACH
215	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.000	EACH
216	807-86930 INSULATION LINK, NON-WATERPROOFED	16.000	EACH
217	807-86935 INSULATION LINK, WATERPROOFED	12.000	EACH
218	807-86955 CABLE-DUCT MARKER	11.000	EACH
219	808-01328 PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, WRONG WAY RAMP	5.000	EACH
220	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROW	51.000	EACH
221	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	20.000	EACH
222	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,771.000	LFT
223	808-06716 LINE, REMOVE	3,615.000	LFT
224	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
225	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	2,630.000	LFT
226	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	29,503.000	LFT
227	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	13,980.000	LFT
228	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	300.000	LFT
229	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	1,838.000	LFT
230	808-10038 TRANSVERSE MARKINGS MULTI-COMPONENT,	999.000	LFT
231	808-10042 TRANSVERSE MARKING MULTI-COMPONENT,	210.000	LFT
232	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	354.000	LFT
233	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	4,078.000	LFT
234	808-10078 LINE, MULTI-COMPONENT, DOTTED, WHITE,	130.000	LFT
235	808-10119 TRANSVERSE MARKING, MULTI-COMPONENT, SOLID,	477.000	LFT
236	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	3,086.000	LFT
237	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	432.000	EACH

CALL ORDER : 160

CONTRACT ID : IR-34397-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	201-06587 CLEARING AND GRUBBING	14.260	ACRE
6	202-01261 TESTING FOR ASBESTOS, TYPE	13.000	EACH
7	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
8	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
9	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
11	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
12	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
13	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
14	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
19	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
20	202-99187 FENCE, FARM FIELD, REMOVE	2,962.000	LFT
21	205-06937 TEMPORARY SILT FENCE	7,832.000	LFT
22	205-09543 NO 2 STONE	222.000	TON
23	211-02050 B BORROW	5,065.000	CYS
24	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
25	621-06545 FERTILIZER	0.600	TON
26	621-06553 SEED MIXTURE, R	267.000	LBS
27	621-06565 MULCHING MATERIAL	3.000	TON

CALL ORDER : 166

CONTRACT ID : IR-34469-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS AND		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
7	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
8	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
9	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
11	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
12	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
13	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
14	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
19	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	10,031.000	SFT
20	205-06937 TEMPORARY SILT FENCE	2,600.000	LFT
21	621-06560 MULCHED SEEDING, U	6,500.000	SYS
22	621-06570 TOPSOIL	546.000	CYS
23	628-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
24	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
25	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	5.000	MOS
26	628-09409 MOBILE INTERNET SERVICE	5.000	MOS
27	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	5.000	MOS

CALL ORDER : 170

CONTRACT ID : IR-34488-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION, REMOVE BUILDINGS AND FOUNDATIONS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
6	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
7	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
8	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
9	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
11	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
12	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
13	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
14	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
17	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
19	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
20	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
21	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
22	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
23	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
24	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
25	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
26	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
27	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
28	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
29	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
30	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
31	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
32	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
33	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
34	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	4,996.000	SFT
35	202-03729 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	199.000	LFT
36	628-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
37	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
38	628-09402 FIELD OFFICE, B	4.000	MOS
39	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	4.000	MOS

CALL ORDER : 200

CONTRACT ID : R -24201-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW FLASHER INSTALLATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	11,767.000	CYS
12	203-02070 BORROW	40.000	CYS
13	203-08607 LINEAR GRADING	1,000.000	LFT
14	205-03371 SEDIMENT, REMOVE	16.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	8.000	TON
16	205-06932 TEMPORARY CHECK DAM, STRAW BALES	210.000	LFT
17	205-06933 TEMPORARY DITCH INLET PROTECTION	8.000	EACH
18	205-06934 TEMPORARY MULCHING	7.100	TON
19	205-06936 TEMPORARY SEDIMENT TRAP	18.000	TON
20	205-06937 TEMPORARY SILT FENCE	3,375.000	LFT
21	207-08263 SUBGRADE TREATMENT, TYPE IA	13,530.000	SYS
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	8,420.000	SYS
23	211-09264 STRUCTURAL BACKFILL, TYPE 1	93.000	CYS
24	211-09265 STRUCTURAL BACKFILL, TYPE 2	117.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,080.000	TON
26	303-01180 COMPACTED AGGREGATE, NO. 53	3,655.000	TON
27	303-01180 COMPACTED AGGREGATE, NO. 53	1,123.000	TON
28	303-07449 COMPACTED AGGREGATE, NO. 73	200.000	TON
29	303-07662 STONE	360.000	TON
30	306-08034 MILLING, ASPHALT, 1 1/2 IN	4,340.000	SYS
31	306-08042 MILLING, SCARIFICATION/PROFILE	4,852.000	SYS
32	306-08043 MILLING, TRANSITION	1,056.000	SYS
33	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
34	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,410.000	TON
35	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1,280.000	TON
36	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	2,180.000	TON
37	402-07432 HMA SURFACE, TYPE A	600.000	TON
38	402-07435 HMA INTERMEDIATE, TYPE A	925.000	TON
39	402-07439 HMA INTERMEDIATE, TYPE C	30.000	TON
40	402-07442 HMA BASE, TYPE C	80.000	TON
41	402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE	1,505.000	TON
42	406-05520 ASPHALT FOR TACK COAT	18.000	TON
43	601-06038 GUARDRAIL END TREATMENT, II	1.000	EACH
44	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
45	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	175.000	LFT
46	606-07484 MILLED HMA SHOULDER CORRUGATIONS	5,542.000	LFT
47	610-07487 HMA FOR APPROACHES, TYPE B	525.000	TON
48	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
49	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH

CALL ORDER : 200

CONTRACT ID : R -24201-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW FLASHER INSTALLATION		
50	615-06490 RIGHT OF WAY MARKER	37.000	EACH
51	615-06505 MONUMENT, B	6.000	EACH
52	615-06510 MONUMENT, C	1.000	EACH
53	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
54	616-02320 GEOTEXTILES	330.000	SYS
55	616-05688 RIPRAP, CLASS 1	62.000	TON
56	616-06405 RIPRAP, REVETMENT	118.000	TON
57	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
58	621-06545 FERTILIZER	1.400	TON
59	621-06553 SEED MIXTURE, R	620.000	LBS
60	621-06557 SEED MIXTURE, T	425.000	LBS
61	621-06565 MULCHING MATERIAL	7.200	TON
62	621-06567 WATER	540.000	KGAL
63	621-06570 TOPSOIL	49.000	CYS
64	621-06574 SODDING	10,531.000	SYS
65	628-09402 FIELD OFFICE, B	9.000	MOS
66	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	9.000	MOS
67	702-93722 CONCRETE, C	149.000	CYS
68	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	129.000	LFT
69	715-05239 PIPE, TYPE 1 DEFORMED MIN AREA 7.4 SF	136.000	LFT
70	715-05363 PIPE, TYPE 3 DEFORMED MIN AREA 1.8 SF	36.000	LFT
71	715-06471 PIPE END SECTION, MIN AREA 3.3 SF	2.000	EACH
72	715-06629 PIPE END SECTION, MIN. AREA 10.2 SFT.	2.000	EACH
73	715-07587 PIPE, TYPE 1 DEFORMED MIN AREA 1.8 SF	55.000	LFT
74	715-08177 PIPE, TYPE 1 DEFORMED MIN AREA 10.2 SF	89.000	LFT
75	715-08243 PIPE, TYPE 3 DEFORMED MIN AREA 3.3 SF	41.000	LFT
76	715-08455 SAFETY METAL END SEC 4:1, MIN AREA 7.4SF	2.000	EACH
77	715-46005 PIPE END SECTION, 15 IN	4.000	EACH
78	715-46055 PIPE END SECTION, MIN AREA 1.8 SF	4.000	EACH
79	715-97804 PIPE END SECTION,, MIN AREA 7.4 SF	2.000	EACH
80	719-05439 PIPE, DRAIN TILE TERMINAL SECTION, 6 IN	20.000	LFT
81	719-05440 PIPE, DRAIN TILE TERMINAL SECTION, 8 IN	20.000	LFT
82	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
83	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
84	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	16,100.000	LFT
85	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	16,000.000	LFT
86	801-06625 DETOUR ROUTE MARKER ASSEMBLY	41.000	EACH
87	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
88	801-06710 FLASHING ARROW SIGN	120.000	DAY
89	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
90	801-07118 BARRICADE, III-A	72.000	LFT
91	801-07119 BARRICADE, III-B	48.000	LFT
92	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	3,725.000	LFT
93	802-03896 BOLLARD	9.000	EACH
94	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	86.000	LFT
95	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	74.800	SFT
96	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	21.300	SFT
97	805-02262 FLASHER INSTALLATION, LOCATION NO	LUMP	LUMP
98	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	10,550.000	LFT

CALL ORDER : 200

CONTRACT ID : R -24201-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW FLASHER INSTALLATION		
99 808-06716	LINE, REMOVE	12,100.000	LFT
100 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	5,100.000	LFT
101 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	45.000	LFT
102 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	13.000	EACH
103 808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	10.000	EACH
104 808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	3,290.000	LFT
105 808-99176	LINE, THERMOPLASTIC, SOLID, YELLOW, 24 IN	320.000	LFT

CALL ORDER : 220

CONTRACT ID : R -29612-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-02245 TREE, 6 IN, REMOVE	1.000	EACH
10	201-02250 TREE, 10 IN, REMOVE	5.000	EACH
11	201-02255 TREE, 18 IN, REMOVE	3.000	EACH
12	201-02260 TREE, 30 IN, REMOVE	5.000	EACH
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-02240 PAVEMENT REMOVAL	520.000	SYS
15	202-02278 CURB, CONCRETE, REMOVE	5,903.000	LFT
16	202-03875 CONCRETE STEPS, REMOVE	15.000	EACH
17	202-06542 RELOCATE	5.000	EACH
18	202-52710 SIDEWALK, CONCRETE, REMOVE	3,714.000	SYS
19	202-91385 INLET, REMOVE	4.000	EACH
20	202-93047 MANHOLE, REMOVE	6.000	EACH
21	202-96133 PIPE, REMOVE	935.000	LFT
22	203-02000 EXCAVATION, COMMON	4,330.000	CYS
23	203-02070 BORROW	105.000	CYS
24	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	44.000	EACH
25	205-03371 SEDIMENT, REMOVE	177.000	CYS
26	205-06937 TEMPORARY SILT FENCE	496.000	LFT
27	207-08263 SUBGRADE TREATMENT, TYPE IA	13,783.000	SYS
28	207-08267 SUBGRADE TREATMENT, TYPE IIA	520.000	SYS
29	211-09264 STRUCTURAL BACKFILL, TYPE 1	5,954.000	CYS
30	211-09265 STRUCTURAL BACKFILL, TYPE 2	5.000	CYS
31	211-09268 STRUCTURAL BACKFILL, TYPE 5	19.000	CYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,243.000	TON
33	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,033.000	SYS
34	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	1,013.000	TON
35	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	1,405.000	TON
36	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	2,244.000	TON
37	406-05520 ASPHALT FOR TACK COAT	12.000	TON
38	601-02241 GUARDRAIL, REMOVE	15.000	LFT
39	604-07900 CURB RAMP, CONCRETE, F	40.000	SYS
40	604-07901 CURB RAMP, CONCRETE, G	137.000	SYS
41	604-07901 CURB RAMP, CONCRETE, G	3.000	SYS
42	604-44251 STEPS, CONCRETE	33.000	CYS
43	604-91531 SIDEWALK, CONCRETE, 4 IN	2,915.000	SYS
44	605-06120 CURB, CONCRETE	51.000	LFT
45	605-06140 CURB AND GUTTER, CONCRETE	6,172.000	LFT
46	610-07487 HMA FOR APPROACHES, TYPE B	284.000	TON
47	610-08446 PCCP FOR APPROACHES, 6 IN	186.000	SYS
48	610-09108 PCCP FOR APPROACHES, 9 IN	334.000	SYS
49	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH

CALL ORDER : 220

CONTRACT ID : R -29612-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	616-02320 GEOTEXTILES	25.000	SYS
51	616-06405 RIPRAP, REVETMENT	34.000	TON
52	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
53	621-06557 SEED MIXTURE, T	126.000	LBS
54	621-06560 MULCHED SEEDING, U	1,266.000	SYS
55	621-06567 WATER	12.000	KGAL
56	621-06575 SODDING, NURSERY	2,785.000	SYS
57	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	39.000	EACH
58	628-09402 FIELD OFFICE, B	12.000	MOS
59	702-03607 CORED HOLE IN CONCRETE	1.000	EACH
60	715-02907 WATER LINE, 6 IN	200.000	LFT
61	715-03025 SANITARY MANHOLE	6.000	EACH
62	715-03025 SANITARY MANHOLE	2.000	EACH
63	715-03053 METER PIT	63.000	EACH
64	715-04926 VALVE	10.000	EACH
65	715-04965 WATER SERVICE LINE	1,545.000	LFT
66	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	40.000	LFT
67	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	525.000	LFT
68	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	554.000	LFT
69	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	58.000	LFT
70	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	2,588.000	LFT
71	715-05411 PIPE SANITARY SEWER 12 IN	2,054.000	LFT
72	715-05711 PIPE SANITARY SEWER 6 IN	1,100.000	LFT
73	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	105.000	TON
74	715-09064 VIDEO INSPECTION FOR PIPE	3,142.000	LFT
75	715-46040 PIPE END SECTION, 36 IN	1.000	EACH
76	720-02367 MANHOLE, J10	5.000	EACH
77	720-02442 PIPE, PLUG EXISTING	1.000	EACH
78	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
79	720-44000 CASTING, ADJUST TO GRADE	6.000	EACH
80	720-45250 CATCH BASIN, K10	29.000	EACH
81	720-45410 MANHOLE, C4	5.000	EACH
82	720-95422 MANHOLE, J4	10.000	EACH
83	720-96999 FIRE HYDRANT ASSEMBLY	8.000	EACH
84	720-98174 INLET, B15	1.000	EACH
85	720-98687 CATCH BASIN, M10	1.000	EACH
86	732-06839 TAP	24.000	EACH
87	801-03290 CONSTRUCTION SIGN, C	15.000	EACH
88	801-04308 ROAD CLOSURE SIGN ASSEMBLY	14.000	EACH
89	801-06625 DETOUR ROUTE MARKER ASSEMBLY	28.000	EACH
90	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
91	801-07118 BARRICADE, III-A	286.000	LFT
92	801-07119 BARRICADE, III-B	64.000	LFT
93	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	202.000	LFT
94	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	41.000	EACH
95	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	97.000	SFT
96	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	58.850	SFT
97	802-91122 SIGN, GROUND MOUNTED, RESET	2.000	EACH
98	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	2,022.000	LFT

CALL ORDER : 220

CONTRACT ID : R -29612-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
99 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	5,260.000	LFT
100 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	135.000	LFT
101 808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	588.000	LFT
102 808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH
103 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	8.000	EACH

CALL ORDER : 230

CONTRACT ID : R -30901-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-02245 TREE, 6 IN, REMOVE	13.000	EACH
10	201-02250 TREE, 10 IN, REMOVE	4.000	EACH
11	201-02255 TREE, 18 IN, REMOVE	4.000	EACH
12	201-02260 TREE, 30 IN, REMOVE	7.000	EACH
13	201-02265 TREE, 48 IN, REMOVE	1.000	EACH
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02278 CURB, CONCRETE, REMOVE	543.000	LFT
16	202-52710 SIDEWALK, CONCRETE, REMOVE	3,163.000	SYS
17	202-91385 INLET, REMOVE	30.000	EACH
18	202-96133 PIPE, REMOVE	3,251.000	LFT
19	203-02000 EXCAVATION, COMMON	19,000.000	CYS
20	205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE	1.000	EACH
21	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	4.000	EACH
22	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	68.000	EACH
23	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	45.000	TON
24	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
25	205-06936 TEMPORARY SEDIMENT TRAP	96.000	TON
26	205-06937 TEMPORARY SILT FENCE	5,257.000	LFT
27	205-09543 NO 2 STONE	121.400	TON
28	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,169.000	SYS
29	207-09934 SUBGRADE TREATMENT, TYPE 1B	25,766.000	SYS
30	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,606.000	CYS
31	214-07202 GEOGRID, TYPE I	192.900	SYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	64.100	TON
33	303-05738 AGGREGATE, NO. 5	41.500	TON
34	303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS	120.000	TON
35	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,489.300	TON
36	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2,482.200	TON
37	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	3,971.500	TON
38	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	2,978.500	TON
39	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	2,256.500	TON
40	402-07432 HMA SURFACE, TYPE A	272.000	TON
41	402-07433 HMA SURFACE, TYPE B	22.500	TON
42	402-07435 HMA INTERMEDIATE, TYPE A	815.200	TON
43	402-07438 HMA INTERMEDIATE, TYPE B	52.600	TON
44	402-07440 HMA BASE, TYPE A	814.200	TON
45	402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE	179.000	TON
46	402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE	134.000	TON
47	402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE	45.000	TON
48	406-05520 ASPHALT FOR TACK COAT	20.140	TON
49	601-95434 HANDRAIL, STEEL PIPE, 1.5"	254.000	LFT

CALL ORDER : 230

CONTRACT ID : R -30901-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT		
50	604-07900 CURB RAMP, CONCRETE, F	34.200	SYS
51	604-07900 CURB RAMP, CONCRETE, F	13.000	SYS
52	604-07901 CURB RAMP, CONCRETE, G	4.900	SYS
53	604-07901 CURB RAMP, CONCRETE, G	9.800	SYS
54	604-07902 CURB RAMP, CONCRETE, H	154.700	SYS
55	604-07902 CURB RAMP, CONCRETE, H	44.800	SYS
56	604-07903 CURB RAMP, CONCRETE, K	26.700	SYS
57	604-44251 STEPS, CONCRETE	27.230	CYS
58	604-91531 SIDEWALK, CONCRETE, 4 IN	6,190.000	SYS
59	605-06140 CURB AND GUTTER, CONCRETE	8,212.000	LFT
60	610-08446 PCCP FOR APPROACHES, 6 IN	1,601.000	SYS
61	610-09108 PCCP FOR APPROACHES, 9 IN	568.000	SYS
62	611-06497 MAILBOX ASSEMBLY, SINGLE	25.000	EACH
63	611-06498 MAILBOX ASSEMBLY, DOUBLE	9.000	EACH
64	616-02320 GEOTEXTILES	274.000	SYS
65	616-05689 RIPRAP, CLASS 2	278.000	TON
66	616-06405 RIPRAP, REVETMENT	45.660	TON
67	616-06451 RIPRAP, UNIFORM	480.000	TON
68	621-06559 MULCHED SEEDING, R	4,809.000	SYS
69	621-06567 WATER	26.000	KGAL
70	621-06575 SODDING, NURSERY	6,820.000	SYS
71	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
72	628-09402 FIELD OFFICE, B	18.000	MOS
73	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	36.000	MOS
74	628-09409 MOBILE INTERNET SERVICE	36.000	MOS
75	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	54.000	MOS
76	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
77	714-11186 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	82.000	LFT
78	714-11331 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	56.000	LFT
79	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	10,825.000	LFT
80	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,415.000	LFT
81	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	3,449.000	LFT
82	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	884.000	LFT
83	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	336.000	LFT
84	715-46005 PIPE END SECTION, 15 IN	5.000	EACH
85	715-46020 PIPE END SECTION, 24 IN	1.000	EACH
86	715-91361 PIPE, PVC, 6 IN	80.000	LFT
87	718-06529 OUTLET PROTECTOR, 2	4.000	EACH
88	718-52610 AGGREGATE FOR UNDERDRAINS	975.000	CYS
89	718-99153 GEOTEXTILES FOR UNDERDRAIN	7,253.000	SYS
90	720-01092 MANHOLE, J15, MODIFIED	4.000	EACH
91	720-02810 INLET, B5	2.000	EACH
92	720-03757 MANHOLE, C15	1.000	EACH
93	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
94	720-45030 INLET, E7	1.000	EACH
95	720-45035 INLET, F7	2.000	EACH
96	720-45075 INLET, R13	2.000	EACH
97	720-45410 MANHOLE, C4	12.000	EACH
98	720-95422 MANHOLE, J4	16.000	EACH

CALL ORDER : 230

CONTRACT ID : R -30901-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT		
99 720-98174	INLET, B15	56.000	EACH
100 720-98555	INLET, C15	4.000	EACH
101 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
102 802-05705	SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	406.500	LFT
103 802-09838	SIGN, SHEET, WITH LEGEND 0.080"	229.640	SFT
104 802-09840	SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	71.730	SFT
105 804-06770	DELINEATOR POST	4.000	EACH
106 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	388.000	LFT
107 808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN	71.000	LFT
108 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN	1,160.000	LFT
109 808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN	417.000	LFT
110 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,843.000	LFT
111 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	8,296.000	LFT
112 808-96016	LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN	60.000	LFT
113 808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH

CALL ORDER : 250

CONTRACT ID : R -32004-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	625.000	CYS
11	203-02070 BORROW	25.000	CYS
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	9.000	TON
13	205-06937 TEMPORARY SILT FENCE	679.000	LFT
14	205-09543 NO 2 STONE	100.000	TON
15	206-51220 EXCAVATION, WET	100.000	CYS
16	207-08265 SUBGRADE TREATMENT, TYPE IIA	1,404.000	SYS
17	211-02050 B BORROW	100.000	CYS
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	168.000	CYS
19	211-09268 STRUCTURAL BACKFILL, TYPE 5	75.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	488.000	TON
21	303-07449 COMPACTED AGGREGATE, NO. 73	350.000	TON
22	306-08042 MILLING, SCARIFICATION/PROFILE	796.000	SYS
23	306-08043 MILLING, TRANSITION	282.000	SYS
24	402-07433 HMA SURFACE, TYPE B	158.000	TON
25	402-07438 HMA INTERMEDIATE, TYPE B	114.000	TON
26	402-07451 HMA WEDGE AND LEVEL, TYPE B	83.000	TON
27	406-05520 ASPHALT FOR TACK COAT	1.000	TON
28	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
29	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
30	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
31	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	382.000	LFT
32	610-07487 HMA FOR APPROACHES, TYPE B	29.000	TON
33	615-06505 MONUMENT, B	3.000	EACH
34	616-02320 GEOTEXTILES	600.000	SYS
35	616-06405 RIPRAP, REVETMENT	196.000	TON
36	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
37	621-06559 MULCHED SEEDING, R	1,334.000	SYS
38	621-06567 WATER	3.100	KGAL
39	621-06575 SODDING, NURSERY	860.000	SYS
40	628-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
41	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
42	628-09401 FIELD OFFICE, A	9.000	MOS
43	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
44	714-11327 STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS,	50.000	LFT
45	715-04618 SAFETY METAL END SECTION, 6:1 30 IN	1.000	EACH
46	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	20.000	LFT
47	715-05125 PIPE, TYPE 1 CIRCULAR 30 IN	72.000	LFT
48	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	56.000	LFT
49	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	77.000	TON

CALL ORDER : 250

CONTRACT ID : R -32004-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	715-46010 PIPE END SECTION, 18 IN	2.000	EACH
51	715-46030 PIPE END SECTION, 30 IN	1.000	EACH
52	719-05439 PIPE, DRAIN TILE TERMINAL SECTION, 6 IN	20.000	LFT
53	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
54	801-06625 DETOUR ROUTE MARKER ASSEMBLY	27.000	EACH
55	801-06640 CONSTRUCTION SIGN, A	27.000	EACH
56	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
57	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
58	801-07118 BARRICADE, III-A	72.000	LFT
59	801-07119 BARRICADE, III-B	48.000	LFT
60	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	45.000	LFT
61	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
62	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	12.000	SFT
63	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	1,081.000	LFT
64	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	518.000	LFT
65	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	4,601.000	LFT
66	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	14.000	EACH
67	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	14.000	EACH

CALL ORDER : 260

CONTRACT ID : R -32206-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-02245 TREE, 6 IN, REMOVE	5.000	EACH
8	201-02255 TREE, 18 IN, REMOVE	2.000	EACH
9	201-02260 TREE, 30 IN, REMOVE	1.000	EACH
10	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
11	202-90747 RETAINING WALL, REMOVE	180.000	LFT
12	202-91922 STUMP, REMOVE	2.000	EACH
13	203-02000 EXCAVATION, COMMON	1,200.000	CYS
14	205-06932 TEMPORARY CHECK DAM, STRAW BALES	180.000	LFT
15	205-06937 TEMPORARY SILT FENCE	250.000	LFT
16	303-01180 COMPACTED AGGREGATE, NO. 53	45.000	TON
17	616-02320 GEOTEXTILES	10.000	SYS
18	616-06451 RIPRAP, UNIFORM	8.000	TON
19	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
20	621-02770 EROSION CONTROL BLANKET	360.000	SYS
21	621-06559 MULCHED SEEDING, R	1,700.000	SYS
22	621-06570 TOPSOIL	285.000	CYS
23	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
24	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	5.000	MOS
25	628-09409 MOBILE INTERNET SERVICE	5.000	MOS
26	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	5.000	MOS
27	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
28	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.000	EACH
29	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
30	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH

CALL ORDER : 270

CONTRACT ID : R -33037-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	200.000	SYS
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	163.000	CYS
11	205-06937 TEMPORARY SILT FENCE	150.000	LFT
12	207-09935 SUBGRADE TREATMENT, TYPE 1C	612.000	SYS
13	211-09194 B BORROW	96.000	TON
14	211-09265 STRUCTURAL BACKFILL, TYPE 2	110.000	CYS
15	211-09268 STRUCTURAL BACKFILL, TYPE 5	140.000	CYS
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	197.000	TON
17	303-07449 COMPACTED AGGREGATE, NO. 73	14.000	TON
18	406-05520 ASPHALT FOR TACK COAT	0.200	TON
19	601-06035 GUARDRAIL, RESET	250.000	LFT
20	615-06505 MONUMENT, B	2.000	EACH
21	616-02320 GEOTEXTILES	316.000	SYS
22	616-06405 RIPRAP, REVETMENT	126.000	TON
23	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
24	621-06559 MULCHED SEEDING, R	213.000	SYS
25	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
26	628-09401 FIELD OFFICE, A	9.000	MOS
27	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	9.000	MOS
28	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
29	714-11338 STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS,	80.000	LFT
30	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	137.000	TON
31	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
32	801-06625 DETOUR ROUTE MARKER ASSEMBLY	28.000	EACH
33	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	801-07118 BARRICADE, III-A	96.000	LFT
36	801-07119 BARRICADE, III-B	48.000	LFT
37	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	200.000	LFT
38	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	25.000	LFT
39	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.000	EACH
40	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2.000	EACH

CALL ORDER : 280

CONTRACT ID : R -33179-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN FACILITY,		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-02250 TREE, 10 IN, REMOVE	1.000	EACH
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-52710 SIDEWALK, CONCRETE, REMOVE	665.000	SYS
11	202-74035 SIGN, REMOVE	2.000	EACH
12	203-02000 EXCAVATION, COMMON	70.000	CYS
13	203-02070 BORROW	660.000	CYS
14	204-08396 STANDPIPE PIEZOMETER	2.000	EACH
15	205-06933 TEMPORARY DITCH INLET PROTECTION	5.000	EACH
16	205-06937 TEMPORARY SILT FENCE	1,500.000	LFT
17	205-09543 NO 2 STONE	100.000	TON
18	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	1,820.000	CYS
19	206-51817 SHEET PILING, STEEL	9,600.000	SFT
20	210-07893 IRRIGATION	LUMP	LUMP
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	80.000	CYS
22	211-09266 STRUCTURAL BACKFILL, TYPE 3	1,495.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	680.000	TON
24	306-08036 MILLING, ASPHALT, 2 IN	1,005.000	SYS
25	402-07432 HMA SURFACE, TYPE A	110.000	TON
26	406-05520 ASPHALT FOR TACK COAT	1.000	TON
27	603-97461 TEMP FENCE	2,000.000	LFT
28	604-10082 INCLINE	2.000	EACH
29	604-44251 STEPS, CONCRETE	41.000	CYS
30	604-90256 SIDEWALK, CONCRETE, 6 IN	860.000	SYS
31	604-91531 SIDEWALK, CONCRETE, 4 IN	58.000	SYS
32	604-95344 HANDRAIL, PEDESTRIAN	226.000	LFT
33	604-95344 HANDRAIL, PEDESTRIAN	144.000	LFT
34	604-95344 HANDRAIL, PEDESTRIAN	72.000	LFT
35	616-02320 GEOTEXTILES	390.000	SYS
36	621-06545 FERTILIZER	1.000	TON
37	621-06565 MULCHING MATERIAL	1.000	TON
38	621-06570 TOPSOIL	400.000	CYS
39	621-06575 SODDING, NURSERY	2,350.000	SYS
40	621-09499 SEED MIXTURE, SEDGE MEADOW	5.000	LBS
41	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	5.000	EACH
42	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	8.000	MOS
43	628-09409 MOBILE INTERNET SERVICE	8.000	MOS
44	702-01724 CONCRETE, C, FOOTINGS	100.000	CYS
45	702-51015 CONCRETE, B, FOOTINGS	137.000	CYS
46	702-93722 CONCRETE, C	151.000	CYS
47	703-06028 REINFORCING BARS	65,382.000	LBS
48	709-51821 SURFACE SEAL	LUMP	LUMP
49	714-11188 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	54.000	LFT

CALL ORDER : 280

CONTRACT ID : R -33179-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN FACILITY,		
50	715-04612 PIPE	500.000	LFT
51	715-04612 PIPE	500.000	LFT
52	715-04612 PIPE	500.000	LFT
53	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	150.000	LFT
54	715-05407 PIPE, END BENT DRAIN, 6 IN	250.000	LFT
55	715-05408 PIPE SANITARY SEWER 8 IN	136.000	LFT
56	715-90052 LIFT STATION	LUMP	LUMP
57	715-98961 FORCE MAIN	364.000	LFT
58	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	2.000	EACH
59	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
60	720-45410 MANHOLE, C4	2.000	EACH
61	720-45510 MANHOLE, C4, MODIFIED	1.000	EACH
62	720-94157 MANHOLE, C	2.000	EACH
63	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	1.000	EACH
64	728-98377 MASONRY COATING	LUMP	LUMP
65	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	20.000	LFT
66	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	4.500	SFT
67	805-01439 MICROWAVE DETECTOR	4.000	EACH
68	805-02658 CABLE, COAXIAL	250.000	LFT
69	805-02658 CABLE, COAXIAL	500.000	LFT
70	805-90739 CABLE, COMMUNICATION, 6 PAIR, IMSA SPEC, 40 2 (UNDERGROUND)	250.000	LFT
71	805-94069 CONDUIT, STEEL, GALVANIZED, 1 IN	100.000	LFT
72	805-94971 FIBER OPTICS CABLE	1,000.000	LFT
73	805-94971 FIBER OPTICS CABLE	1,000.000	LFT
74	805-95568 CONDUIT, PVC, 4 IN.	1,000.000	LFT
75	807-02822 LIGHT POLE, STEEL, RELOCATE	3.000	EACH
76	807-02857 CIRCUIT BREAKER PANEL	1.000	EACH
77	807-03758 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING	3.000	EACH
78	807-78590 HANDHOLE	5.000	EACH
79	807-86898 CONDUIT, STEEL, GALVANIZED, 0.75 IN	1,100.000	LFT
80	807-92155 WIRE, XHHW, NO 6 COPPER, 1/C	400.000	LFT
81	807-94480 LIGHT STANDARD, INSTALL	10.000	EACH
82	807-94480 LIGHT STANDARD, INSTALL	2.000	EACH
83	807-95709 PHOTOCELLS	1.000	EACH
84	807-95889 WIRE, NO 10 COPPER, 1/C	1,000.000	LFT
85	807-95890 WIRE, NO 12 COPPER, 1/C	1,650.000	LFT
86	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	1,000.000	LFT
87	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN	150.000	LFT
88	808-97222 PAVEMENT MESSAGE MARKING, PAINT, HANDICAP SYMBOL	1.000	EACH

CALL ORDER : 284

CONTRACT ID : R -33240-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT BIKE/PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02278 CURB, CONCRETE, REMOVE	2,780.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	1,370.000	SYS
11	203-02000 EXCAVATION, COMMON	3,511.000	CYS
12	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	88.000	EACH
13	205-06937 TEMPORARY SILT FENCE	4,254.000	LFT
14	207-08267 SUBGRADE TREATMENT, TYPE IIIA	7,710.000	SYS
15	211-09264 STRUCTURAL BACKFILL, TYPE 1	3,802.000	CYS
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,311.000	TON
17	402-07433 HMA SURFACE, TYPE B	614.000	TON
18	402-07438 HMA INTERMEDIATE, TYPE B	688.000	TON
19	402-07441 HMA BASE, TYPE B	2,202.000	TON
20	406-05520 ASPHALT FOR TACK COAT	5.400	TON
21	603-09065 FENCE GATE, CHAIN LINK, PVC COATED, 72 IN	2.000	EACH
22	603-09066 FENCE, CHAIN LINK, PVC COATED, 72 IN	80.000	LFT
23	604-07894 CURB RAMP, CONCRETE, A	27.000	SYS
24	604-07897 CURB RAMP, CONCRETE, C	109.000	SYS
25	604-07899 CURB RAMP, CONCRETE, E	81.000	SYS
26	604-07901 CURB RAMP, CONCRETE, G	32.000	SYS
27	604-07902 CURB RAMP, CONCRETE, H	23.000	SYS
28	604-91404 SIDEWALK, CONCRETE, 5 IN	452.000	SYS
29	604-91531 SIDEWALK, CONCRETE, 4 IN	4,662.000	SYS
30	605-04742 WALL	LUMP	LUMP
31	605-04742 WALL	LUMP	LUMP
32	605-06120 CURB, CONCRETE	5,251.000	LFT
33	610-08446 PCCP FOR APPROACHES, 6 IN	1,928.000	SYS
34	610-09108 PCCP FOR APPROACHES, 9 IN	624.000	SYS
35	616-02320 GEOTEXTILES	12.000	SYS
36	616-06405 RIPRAP, REVETMENT	12.000	TON
37	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
38	621-06567 WATER	500.000	KGAL
39	621-06570 TOPSOIL	700.000	CYS
40	621-06575 SODDING, NURSERY	9,900.000	SYS
41	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN OR UNDER	5.000	EACH
42	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	5.000	EACH
43	628-09402 FIELD OFFICE, B	8.000	MOS
44	702-90915 CONCRETE, CLASS A	24.000	CYS
45	703-06028 REINFORCING BARS	41.000	LBS
46	712-03017 PARK BENCH	2.000	EACH
47	715-03795 PIPE DUCTILE IRON 6"	52.000	LFT
48	715-04987 CONNECTION	1.000	EACH
49	715-04995 LINE STOP	4.000	EACH

CALL ORDER : 284

CONTRACT ID : R -33240-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT BIKE/PEDESTRIAN FACILITIES		
50	715-05147 PIPE, TYPE 2 CIRCULAR 8 IN	10.000	LFT
51	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	666.000	LFT
52	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,019.000	LFT
53	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	196.000	LFT
54	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	300.000	LFT
55	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	683.000	LFT
56	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	788.000	LFT
57	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	30.000	LFT
58	720-01092 MANHOLE, J15, MODIFIED	1.000	EACH
59	720-02810 INLET, B5	3.000	EACH
60	720-04467 INLET, C5	1.000	EACH
61	720-04467 INLET, C5	2.000	EACH
62	720-44000 CASTING, ADJUST TO GRADE	42.000	EACH
63	720-44296 INLET, CAP	4.000	EACH
64	720-45145 INLET, J10, MODIFIED	8.000	EACH
65	720-45410 MANHOLE, C4	18.000	EACH
66	720-93409 INLET, B15, MODIFIED	14.000	EACH
67	720-93411 INLET, C15, MODIFIED	4.000	EACH
68	720-95409 MANHOLE, J4, MODIFIED	1.000	EACH
69	720-98174 INLET, B15	3.000	EACH
70	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
71	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
72	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	3,200.000	LFT
73	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	100.000	LFT
74	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
75	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
76	801-06645 CONSTRUCTION SIGN, B	16.000	EACH
77	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
78	801-07118 BARRICADE, III-A	216.000	LFT
79	801-07119 BARRICADE, III-B	324.000	LFT
80	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	505.000	LFT
81	802-07060 SIGN, SHEET, RELOCATE	14.000	EACH
82	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	194.000	SFT
83	805-06742 SOLAR POWERED FLASHING BEACON ASSEMBLY	2.000	EACH
84	805-78370 PEDESTRIAN PUSH BUTTON	2.000	EACH
85	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	1,480.000	LFT
86	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
87	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,631.000	LFT
88	805-78900 PEDESTAL FOUNDATION, A	2.000	EACH
89	807-01603 SERVICE POINT, TYPE II	2.000	EACH
90	807-02191 HANDHOLE, LIGHTING	7.000	EACH
91	807-02426 WIRE, THW, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	1,008.000	LFT
92	807-03951 LIGHT POLE, ORNAMENTAL	33.000	EACH
93	807-04653 LIGHTING FOUNDATION,	33.000	EACH
94	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	1,008.000	LFT
95	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	3,178.000	LFT
96	807-86889 CABLE, POLE CIRCUIT THWH, NO10 COPPER, STRANDED, 1/C	1,815.000	LFT
97	807-86910 CONNECTOR KIT, UNFUSED	33.000	EACH
98	807-86915 CONNECTOR KIT, FUSED	33.000	EACH

CALL ORDER : 284

CONTRACT ID : R -33240-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT BIKE/PEDESTRIAN FACILITIES		
99	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	94.000	EACH
100	807-86935 INSULATION LINK, WATERPROOFED	94.000	EACH
101	807-86955 CABLE-DUCT MARKER	2.000	EACH
102	808-03114 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (XING) 8 FT	2.000	EACH
103	808-03115 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC (XING), 4 FT	1.000	EACH
104	808-03775 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (BIKE)	2.000	EACH
105	808-04096 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (LANE)	10.000	EACH
106	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	1,030.000	LFT
107	808-06716 LINE, REMOVE	360.000	LFT
108	808-75067 TRANSVERSE MARKING, PREFORMED PLASTIC,	210.000	LFT
109	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,400.000	LFT
110	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	400.000	LFT

CALL ORDER : 290

CONTRACT ID : R -34148-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SAFE ROUTE TO SCHOOL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02278 CURB, CONCRETE, REMOVE	247.000	LFT
9	202-52710 SIDEWALK, CONCRETE, REMOVE	1,154.000	SYS
10	203-02000 EXCAVATION, COMMON	47.000	CYS
11	203-02070 BORROW	15.000	CYS
12	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	7.000	EACH
13	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
14	205-06937 TEMPORARY SILT FENCE	325.000	LFT
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	417.000	SYS
16	304-07490 HMA PATCHING, TYPE B	7.000	TON
17	604-07897 CURB RAMP, CONCRETE, C	9.000	SYS
18	604-07897 CURB RAMP, CONCRETE, C	11.000	SYS
19	604-07900 CURB RAMP, CONCRETE, F	15.000	SYS
20	604-07901 CURB RAMP, CONCRETE, G	45.000	SYS
21	604-07901 CURB RAMP, CONCRETE, G	33.000	SYS
22	604-90256 SIDEWALK, CONCRETE, 6 IN	7.000	SYS
23	604-91531 SIDEWALK, CONCRETE, 4 IN	1,675.000	SYS
24	605-06120 CURB, CONCRETE	169.000	LFT
25	610-08446 PCCP FOR APPROACHES, 6 IN	417.000	SYS
26	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
27	621-06560 MULCHED SEEDING, U	2,143.000	SYS
28	621-06570 TOPSOIL	2.000	CYS
29	621-06575 SODDING, NURSERY	100.000	SYS
30	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
31	628-09401 FIELD OFFICE, A	6.000	MOS
32	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	12.000	MOS
33	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
34	715-94530 ADJUST WATER VALVE TO GRADE	9.000	EACH
35	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	3.000	EACH
36	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
37	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
38	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
39	801-06640 CONSTRUCTION SIGN, A	41.000	EACH
40	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
41	801-07119 BARRICADE, III-B	40.000	LFT
42	802-07060 SIGN, SHEET, RELOCATE	9.000	EACH
43	808-75100 TRANSVERSE MARKING, PAINT,	688.000	LFT

CALL ORDER : 350

CONTRACT ID : RS-31724-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	304-07489 HMA PATCHING, TYPE A	150.000	TON
9	503-05240 D-1 CONTRACTION JOINT	1,000.000	LFT
10	506-06333 PCCP PATCHING, FULL DEPTH	2,000.000	SYS
11	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	2.200	TON
12	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
13	612-60410 DRILLED HOLE FOR UNDERSEAL	50.000	EACH
14	619-91969 CLEAN UNDERDRAIN OUTLET	50.000	EACH
15	628-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
16	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
17	628-09401 FIELD OFFICE, A	4.000	MOS
18	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	4.000	MOS
19	628-11007 CELLULAR TELEPHONE/RADIO SERVICE, 750 MINUTES	8.000	MOS
20	715-01354 CLEAN EXISTING PIPE	5,150.000	LFT
21	718-06269 UNDERDRAIN INSPECTION	5,150.000	LFT
22	801-03290 CONSTRUCTION SIGN, C	20.000	EACH
23	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
24	801-06625 DETOUR ROUTE MARKER ASSEMBLY	26.000	EACH
25	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	801-07118 BARRICADE, III-A	300.000	LFT
28	801-07119 BARRICADE, III-B	600.000	LFT
29	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
30	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	600.000	LFT
31	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	5,450.000	LFT
32	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	5,450.000	LFT
33	808-75215 LINE, THERMOPLASTIC, SOLID, WHITE 12 IN	500.000	LFT
34	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	200.000	EACH
35	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	200.000	EACH

CALL ORDER : 360

CONTRACT ID : RS-33254-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SURFACE TREATMENT, MICROSURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	304-07491 HMA PATCHING, TYPE C	79.700	TON
6	306-08043 MILLING, TRANSITION	186.600	SYS
7	408-07478 CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	3.240	TON
8	411-09521 MICRO-SURFACING, WARRANTED, MULTIPLE COURSE	50,526.000	SYS
9	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
10	628-09401 FIELD OFFICE, A	6.000	MOS
11	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
12	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
13	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
14	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	14,516.000	LFT
15	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	808-06716 LINE, REMOVE	36,111.000	LFT
18	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	28,652.000	LFT
19	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	3,962.000	LFT
20	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	3,497.000	LFT
21	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	203.000	EACH
22	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	203.000	EACH

CALL ORDER : 370

CONTRACT ID : RS-33604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-75997 PRISMATIC REFLECTOR, REMOVE	329.000	EACH
11	202-93741 GUARDRAIL END TREATMENT, REMOVE	2.000	EACH
12	203-08607 LINEAR GRADING	131,796.000	LFT
13	205-06937 TEMPORARY SILT FENCE	1,000.000	LFT
14	207-09935 SUBGRADE TREATMENT, TYPE 1C	1,201.000	SYS
15	211-09264 STRUCTURAL BACKFILL, TYPE 1	7.000	CYS
16	302-07455 DENSE GRADED SUBBASE	200.000	CYS
17	304-07783 HMA PATCHING, TYPE D	755.000	TON
18	305-11423 PCC BASE PATCHING, 16 IN.	1,134.000	SYS
19	306-08033 MILLING, ASPHALT, 1 IN	49,922.000	SYS
20	306-08034 MILLING, ASPHALT, 1 1/2 IN	37,358.000	SYS
21	306-08039 MILLING, ASPHALT REMOVAL	1,981.000	SYS
22	306-08041 MILLING, PCCP	129.300	SYS
23	306-08043 MILLING, TRANSITION	24,700.000	SYS
24	306-08432 MILLING, APPROACH	927.000	SYS
25	306-08595 MILLING ASPHALT, 3 1/2 IN	57,897.000	SYS
26	306-10163 MILLING ASPHALT, 2 1/2 IN	164,528.000	SYS
27	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
28	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	10,339.000	TON
29	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,733.000	TON
30	401-07330 QC/QA-HMA, 5, 70, SURFACE, 9.5 mm	13,574.000	TON
31	401-07355 QC/QA-HMA, 1, 64, INTERMEDIATE, 9.5 mm	4,777.000	TON
32	401-07370 QC/QA-HMA, 1, 64, INTERMEDIATE, 12.5 mm	5,492.000	TON
33	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2,890.000	TON
34	401-07400 QC/QA-HMA, 5, 70, INTERMEDIATE, 19.0 mm	31,672.000	TON
35	401-07422 QC/QA-HMA, 1, 64, BASE, 19.0 mm	9,553.000	TON
36	402-07784 HMA SURFACE, TYPE D	10.800	TON
37	406-05520 ASPHALT FOR TACK COAT	162.000	TON
38	503-03489 RETROFITTED TIE BARS	120.000	EACH
39	503-05240 D-1 CONTRACTION JOINT	442.000	LFT
40	506-06333 PCCP PATCHING, FULL DEPTH	68.000	SYS
41	506-06334 PCCP PATCHING, PARTIAL DEPTH	26.600	SYS
42	601-06035 GUARDRAIL, RESET	2,737.000	LFT
43	601-07050 GUARDRAIL END TREATMENT, OS, RESET	8.000	EACH
44	601-91147 GUARDRAIL END TREATMENT, RESET	2.000	EACH
45	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
46	601-94690 GUARDRAIL END TREATMENT, MS	1.000	EACH
47	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	181.250	LFT
48	604-06367 JOINT MATERIAL	124.450	LFT
49	606-07484 MILLED HMA SHOULDER CORRUGATIONS	78,578.000	LFT

CALL ORDER : 370

CONTRACT ID : RS-33604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	610-07487 HMA FOR APPROACHES, TYPE B	180.000	TON
51	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	1.860	TON
52	612-60410 DRILLED HOLE FOR UNDERSEAL	31.000	EACH
53	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
54	621-06559 MULCHED SEEDING, R	18.000	SYS
55	628-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
56	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
57	628-09402 FIELD OFFICE, B	15.000	MOS
58	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	30.000	MOS
59	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	60.000	MOS
60	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	138.000	LFT
61	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	144.000	LFT
62	718-06526 HMA FOR UNDERDRAINS	6.500	TON
63	718-06529 OUTLET PROTECTOR, 2	7.000	EACH
64	718-52610 AGGREGATE FOR UNDERDRAINS	4.200	CYS
65	718-99153 GEOTEXTILES FOR UNDERDRAIN	94.000	SYS
66	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
67	801-03290 CONSTRUCTION SIGN, C	19.000	EACH
68	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	2,569,151.000	LFT
69	801-06640 CONSTRUCTION SIGN, A	93.000	EACH
70	801-06710 FLASHING ARROW SIGN	240.000	DAY
71	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
72	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
73	808-06368 TRANSVERSE MARKING, REMOVE	102.000	LFT
74	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	17,147.000	LFT
75	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	76,673.000	LFT
76	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	7,506.000	LFT
77	808-06716 LINE, REMOVE	134,173.000	LFT
78	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
79	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	13,127.000	LFT
80	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	13,127.000	LFT
81	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	3,282.000	LFT
82	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	66,258.000	LFT
83	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	1,032.000	LFT
84	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	102.000	LFT
85	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH
86	808-75994 PRISMATIC REFLECTOR	329.000	EACH
87	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,413.000	EACH
88	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,413.000	EACH

CALL ORDER : 380

CONTRACT ID : RS-33793-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INSTITUTIONAL ROAD PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-06542 RELOCATE	15.000	EACH
9	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	350.000	TON
10	304-07489 HMA PATCHING, TYPE A	600.000	TON
11	306-08043 MILLING, TRANSITION	350.000	SYS
12	402-07432 HMA SURFACE, TYPE A	1,550.000	TON
13	402-07435 HMA INTERMEDIATE, TYPE A	250.000	TON
14	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 390

CONTRACT ID : RS-33794-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	90.000	TON
9	304-07489 HMA PATCHING, TYPE A	205.000	TON
10	306-08043 MILLING, TRANSITION	350.000	SYS
11	402-07432 HMA SURFACE, TYPE A	486.000	TON
12	402-07435 HMA INTERMEDIATE, TYPE A	130.000	TON
13	404-05511 SEAL COAT, 2	18,386.000	SYS
14	406-05520 ASPHALT FOR TACK COAT	2.000	TON
15	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 400

CONTRACT ID : RS-34021-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	303-07449 COMPACTED AGGREGATE, NO. 73	10.000	TON
9	304-07489 HMA PATCHING, TYPE A	50.000	TON
10	306-08042 MILLING, SCARIFICATION/PROFILE	8,500.000	SYS
11	402-07432 HMA SURFACE, TYPE A	1,134.000	TON
12	406-05520 ASPHALT FOR TACK COAT	5.000	TON
13	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
15	802-07057 SIGN, PANEL, WITH LEGEND	15.000	SFT
16	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN	1,200.000	LFT
17	808-06726 TRANSVERSE MARKING, PAINT,	100.000	LFT
18	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN	200.000	LFT

CALL ORDER : 410

CONTRACT ID : RS-34194-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-05545 REGULATED MATERIALS, DISPOSE, C	20.000	CYS
11	202-05550 REGULATED MATERIALS, REMOVE, C	20.000	CYS
12	202-05555 REGULATED MATERIALS, TRANSPORT, C	20.000	CYS
13	202-07603 TESTING FOR WASTES, C	2.000	EACH
14	202-90277 DETECTOR HOUSING, REMOVE	6.000	EACH
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	500.000	SYS
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	80.000	TON
17	303-01180 COMPACTED AGGREGATE, NO. 53	250.000	TON
18	304-07491 HMA PATCHING, TYPE C	100.000	TON
19	304-07491 HMA PATCHING, TYPE C	200.000	TON
20	304-07491 HMA PATCHING, TYPE C	1,100.000	TON
21	306-08034 MILLING, ASPHALT, 1 1/2 IN	66,000.000	SYS
22	306-08432 MILLING, APPROACH	3,900.000	SYS
23	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	2,350.000	TON
24	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	3,110.000	TON
25	406-05520 ASPHALT FOR TACK COAT	21.000	TON
26	604-07894 CURB RAMP, CONCRETE, A	10.000	SYS
27	604-07900 CURB RAMP, CONCRETE, F	50.000	SYS
28	604-07901 CURB RAMP, CONCRETE, G	40.000	SYS
29	604-07901 CURB RAMP, CONCRETE, G	10.000	SYS
30	604-07902 CURB RAMP, CONCRETE, H	30.000	SYS
31	610-07488 HMA FOR APPROACHES, TYPE C	500.000	TON
32	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
33	615-06520 MONUMENT, RE-ESTABLISH	4.000	EACH
34	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
35	628-09402 FIELD OFFICE, B	6.000	MOS
36	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
37	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	12.000	MOS
38	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
39	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
40	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
41	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	2.000	LFT
42	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	3.000	EACH
43	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	10.000	EACH
44	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
45	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	5,800.000	LFT
46	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	5,800.000	LFT
47	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	10.000	EACH
48	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	160.000	LFT
49	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	160.000	LFT

CALL ORDER : 410

CONTRACT ID : RS-34194-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
51	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
52	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
53	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	1,400.000	LFT
54	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	300.000	LFT
55	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
56	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	450.000	LFT
57	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
58	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	30,700.000	LFT
59	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	16,800.000	LFT
60	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	1,900.000	LFT
61	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	2,300.000	LFT
62	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	550.000	LFT
63	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	160.000	LFT
64	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	430.000	LFT
65	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	10.000	EACH
66	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	490.000	EACH
67	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	490.000	EACH

CALL ORDER : 420

CONTRACT ID : RS-34214-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT PAVEMENT PROJECT (NON-I)		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	303-07449 COMPACTED AGGREGATE, NO. 73	2,900.000	TON
10	304-07490 HMA PATCHING, TYPE B	150.000	TON
11	306-08042 MILLING, SCARIFICATION/PROFILE	12,100.000	SYS
12	306-08043 MILLING, TRANSITION	1,570.000	SYS
13	306-08432 MILLING, APPROACH	279.000	SYS
14	402-07451 HMA WEDGE AND LEVEL, TYPE B	50.000	TON
15	402-09325 ULTRATHIN BONDED WEARING COURSE	91,210.000	SYS
16	406-05521 ASPHALT FOR TACK COAT	850.000	SYS
17	408-07478 CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	5.000	TON
18	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
19	628-09402 FIELD OFFICE, B	8.000	MOS
20	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	16.000	MOS
21	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
22	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
23	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	2,924.000	LFT
24	801-06640 CONSTRUCTION SIGN, A	70.000	EACH
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	808-02157 PAVEMENT MESSAGE MARKING, REMOVE	6.000	EACH
27	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	6.000	EACH
28	808-06368 TRANSVERSE MARKING, REMOVE	155.000	LFT
29	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	6,160.000	LFT
30	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	58,740.000	LFT
31	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	26,922.000	LFT
32	808-06716 LINE, REMOVE	91,822.000	LFT
33	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
34	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	60.000	LFT
35	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	30.000	LFT
36	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	85.000	LFT
37	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	600.000	EACH
38	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	616.000	EACH

CALL ORDER : 460

CONTRACT ID : B -29063-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT BRIDGE PROJECT (REHABILITATION)		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	545.000	SYS
9	202-02272 PAVED SIDE DITCH, REMOVE	115.000	LFT
10	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
11	202-51368 SLOPEWALL, REMOVE	840.000	SYS
12	203-02070 BORROW	20.000	CYS
13	203-08607 LINEAR GRADING	280.000	LFT
14	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	24.000	CYS
15	206-51817 SHEET PILING, STEEL	726.000	SFT
16	211-06467 AGGREGATE FOR END BENT BACKFILL	16.000	CYS
17	302-07455 DENSE GRADED SUBBASE	83.000	CYS
18	306-08034 MILLING, ASPHALT, 1 1/2 IN	748.000	SYS
19	406-05521 ASPHALT FOR TACK COAT	1,369.000	SYS
20	502-06329 PCCP, 12 IN	202.000	SYS
21	503-03489 RETROFITTED TIE BARS	92.000	EACH
22	503-05310 TERMINAL JOINT	92.000	LFT
23	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
24	601-02241 GUARDRAIL, REMOVE	690.000	LFT
25	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
26	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	550.000	LFT
27	601-99132 GUARDRAIL, TRANSITION, VH, 6 FT-3 IN SPACING	1.000	EACH
28	602-06729 BARRIER DELINEATOR	8.000	EACH
29	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	352.000	SYS
30	610-07487 HMA FOR APPROACHES, TYPE B	383.000	TON
31	616-02320 GEOTEXTILES	1,375.000	SYS
32	616-06405 RIPRAP, REVETMENT	1,005.000	TON
33	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
34	628-09401 FIELD OFFICE, A	12.000	MOS
35	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	12.000	MOS
36	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
37	702-51005 CONCRETE, A, SUBSTRUCTURE	92.400	CYS
38	702-51863 FIELD DRILLED HOLE IN CONCRETE	228.000	EACH
39	703-06028 REINFORCING BARS	7,342.000	LBS
40	703-06029 REINFORCING BARS, EPOXY COATED	58,116.000	LBS
41	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	477.000	EACH
42	704-51002 CONCRETE, C, SUPERSTRUCTURE	170.600	CYS
43	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
44	706-51020 RAILING, CONCRETE, C	21.000	CYS
45	707-11443 STRUCTURAL MEMBER, CONCRETE BOX BEAM,	754.000	LFT
46	709-51821 SURFACE SEAL	LUMP	LUMP
47	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
48	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	640.000	LFT
49	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	4,644.000	LFT

CALL ORDER : 460

CONTRACT ID : B -29063-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT BRIDGE PROJECT (REHABILITATION)		
50	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
51	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
52	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
53	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	1.000	EACH
54	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	100.000	LFT
55	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	600.000	LFT
56	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
57	808-06716 LINE, REMOVE	1,777.000	LFT
58	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	1,570.000	LFT
59	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	430.000	LFT
60	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	227.000	LFT
61	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	17.000	EACH
62	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	17.000	EACH

CALL ORDER : 470

CONTRACT ID : B -29991-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	3,462.000	CYS
13	203-02070 BORROW	852.000	CYS
14	205-06934 TEMPORARY MULCHING	2.200	TON
15	205-06937 TEMPORARY SILT FENCE	260.000	LFT
16	205-08511 EROSION CONTROL	782.000	LFT
17	205-09543 NO 2 STONE	100.000	TON
18	206-51220 EXCAVATION, WET	336.800	CYS
19	206-51225 EXCAVATION, DRY	1,183.300	CYS
20	206-51235 COFFERDAM	LUMP	LUMP
21	206-51235 COFFERDAM	LUMP	LUMP
22	207-08263 SUBGRADE TREATMENT, TYPE IA	1,902.000	SYS
23	208-09232 REINFORCED STEEPENED SLOPE	9,731.000	SFT
24	211-09267 STRUCTURAL BACKFILL, TYPE 4	20.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	692.000	TON
26	302-07455 DENSE GRADED SUBBASE	68.000	CYS
27	303-01180 COMPACTED AGGREGATE, NO. 53	312.000	TON
28	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,957.000	SYS
29	402-07432 HMA SURFACE, TYPE A	130.000	TON
30	402-07433 HMA SURFACE, TYPE B	215.000	TON
31	402-07435 HMA INTERMEDIATE, TYPE A	258.000	TON
32	402-07438 HMA INTERMEDIATE, TYPE B	138.000	TON
33	406-05520 ASPHALT FOR TACK COAT	1.030	TON
34	601-01522 GUARDRAIL, TRANSITION TYPE TGB	8.000	EACH
35	601-01701 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
36	601-02241 GUARDRAIL, REMOVE	1,241.000	LFT
37	601-94689 GUARDRAIL END TREATMENT, OS	7.000	EACH
38	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,075.000	LFT
39	602-06729 BARRIER DELINEATOR	20.000	EACH
40	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	406.000	SYS
41	615-06490 RIGHT OF WAY MARKER	13.000	EACH
42	616-02320 GEOTEXTILES	1,931.000	SYS
43	616-06405 RIPRAP, REVETMENT	1,375.000	TON
44	616-07266 COIR ROLL	1,790.000	LFT
45	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
46	621-02770 EROSION CONTROL BLANKET	3,691.000	SYS
47	621-06557 SEED MIXTURE, T	133.000	LBS
48	621-06559 MULCHED SEEDING, R	4,275.000	SYS
49	621-06574 SODDING	96.000	SYS

CALL ORDER : 470

CONTRACT ID : B -29991-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	622-52436 SIGN, DO NOT MOW OR SPRAY	8.000	EACH
51	628-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
52	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
53	628-09402 FIELD OFFICE, B	24.000	MOS
54	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	24.000	MOS
55	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	48.000	MOS
56	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
57	701-09557 TEST PILE, DYNAMIC, PRODUCTION	164.000	LFT
58	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
59	701-09683 PILE SHOE, HP 12 X 74	28.000	EACH
60	701-09739 PILE SHOE, HP 12 X 53	24.000	EACH
61	701-09779 PREBORED HOLE, 15"	656.000	LFT
62	701-51195 PILE, STEEL H, HP 12 IN X 53	1,135.000	LFT
63	701-95780 PILE, STEEL H, HP 12 IN X 74	2,162.000	LFT
64	702-51005 CONCRETE, A, SUBSTRUCTURE	201.400	CYS
65	703-01540 THREADED TIE BAR ASSEMBLY	168.000	EACH
66	703-06028 REINFORCING BARS	74,112.000	LBS
67	703-06029 REINFORCING BARS, EPOXY COATED	95,996.000	LBS
68	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	608.000	EACH
69	704-51002 CONCRETE, C, SUPERSTRUCTURE	773.600	CYS
70	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	8.000	EACH
71	706-51025 RAILING, CONCRETE, C	488.000	LFT
72	709-51821 SURFACE SEAL	LUMP	LUMP
73	709-51821 SURFACE SEAL	LUMP	LUMP
74	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
75	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
76	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	2,530.000	LFT
77	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	10,321.000	LFT
78	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	24.000	LFT
79	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
80	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
81	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
82	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	6.000	EACH
83	801-07119 BARRICADE, III-B	72.000	LFT
84	801-08507 TEMPORARY TRAFFIC BARRIER, TYPE 1, ANCHORED	1,620.000	LFT
85	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
86	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
87	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	526.000	LFT
88	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	4,200.000	LFT
89	808-06716 LINE, REMOVE	3,785.000	LFT
90	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	24.000	EACH
91	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	24.000	EACH

CALL ORDER : 480

CONTRACT ID : B -30780-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	428.000	SYS
9	203-02000 EXCAVATION, COMMON	26.000	CYS
10	306-08043 MILLING, TRANSITION	1,768.000	SYS
11	402-07452 HMA WEDGE AND LEVEL, TYPE C	200.000	TON
12	406-05520 ASPHALT FOR TACK COAT	0.700	TON
13	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
14	601-02241 GUARDRAIL, REMOVE	100.000	LFT
15	601-06035 GUARDRAIL, RESET	100.000	LFT
16	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	183.000	SYS
17	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	232.000	SYS
18	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
19	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
20	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
21	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
22	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
23	702-51864 FIELD DRILLED HOLE	177.000	EACH
24	703-06029 REINFORCING BARS, EPOXY COATED	19,474.000	LBS
25	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
26	708-51813 PNEUMATICALLY PLACED MORTAR	350.000	SFT
27	709-04647 FIBER WRAP CONCRETE CASING SYSTEM	LUMP	LUMP
28	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	7,565.000	SFT
29	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	177.000	LFT
30	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	1,056.000	LFT
31	724-51925 STRUCTURAL EXPANSION JOINT, SS	34.000	LFT
32	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
33	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
34	801-06625 DETOUR ROUTE MARKER ASSEMBLY	63.000	EACH
35	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
36	801-06710 FLASHING ARROW SIGN	28.000	DAY
37	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
38	801-07118 BARRICADE, III-A	240.000	LFT
39	801-07119 BARRICADE, III-B	40.000	LFT
40	801-92448 CONSTRUCTION SIGNS, MOBILE	372.000	DAY
41	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	28.000	LFT
42	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	462.000	LFT
43	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	562.000	LFT

CALL ORDER : 490

CONTRACT ID : B -30915-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02240 PAVEMENT REMOVAL	258.000	SYS
8	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	400.000	CYS
10	203-02070 BORROW	260.000	CYS
11	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	259.000	CYS
12	206-93520 TEMPORARY SHEET PILING	1,200.000	SFT
13	211-06467 AGGREGATE FOR END BENT BACKFILL	38.000	CYS
14	302-07455 DENSE GRADED SUBBASE	52.000	CYS
15	306-08043 MILLING, TRANSITION	480.000	SYS
16	406-05521 ASPHALT FOR TACK COAT	1,366.000	SYS
17	502-06329 PCCP, 12 IN	161.000	SYS
18	503-03489 RETROFITTED TIE BARS	72.000	EACH
19	503-05310 TERMINAL JOINT	74.000	LFT
20	601-01522 GUARDRAIL, TRANSITION TYPE TGB	2.000	EACH
21	601-02241 GUARDRAIL, REMOVE	80.000	LFT
22	601-99132 GUARDRAIL, TRANSITION, VH, 6 FT-3 IN SPACING	2.000	EACH
23	602-06729 BARRIER DELINEATOR	12.000	EACH
24	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	226.000	SYS
25	610-07788 HMA FOR APPROACHES, TYPE D	833.000	TON
26	616-02320 GEOTEXTILES	94.000	SYS
27	619-04414 DRAIN EXTENSION	2.000	EACH
28	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
29	628-09401 FIELD OFFICE, A	12.000	MOS
30	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	24.000	MOS
31	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
32	701-09739 PILE SHOE, HP 12 X 53	8.000	EACH
33	701-51195 PILE, STEEL H, HP 12 IN X 53	508.000	LFT
34	702-51005 CONCRETE, A, SUBSTRUCTURE	168.500	CYS
35	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	644.000	LBS
36	702-51863 FIELD DRILLED HOLE IN CONCRETE	208.000	EACH
37	703-06028 REINFORCING BARS	24,563.000	LBS
38	703-06029 REINFORCING BARS, EPOXY COATED	82,670.000	LBS
39	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	417.000	EACH
40	704-51002 CONCRETE, C, SUPERSTRUCTURE	216.900	CYS
41	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	2.000	EACH
42	706-51020 RAILING, CONCRETE, C	36.800	CYS
43	707-11443 STRUCTURAL MEMBER, CONCRETE BOX BEAM,	729.000	LFT
44	709-51821 SURFACE SEAL	LUMP	LUMP
45	710-09158 PATCHING CONCRETE STRUCTURES	200.000	SFT
46	711-02707 ANCHOR PLATE	12.000	EACH
47	711-51038 STRUCTURAL STEEL	LUMP	LUMP
48	711-96800 STUD SHEAR CONNECTORS	1,428.000	EACH
49	711-96899 BEAMS, RESET	LUMP	LUMP

CALL ORDER : 490

CONTRACT ID : B -30915-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT		
50	713-51820 TEMPORARY SUPPORT	LUMP	LUMP
51	715-05407 PIPE, END BENT DRAIN, 6 IN	106.000	LFT
52	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	86.000	LFT
53	726-92406 BEARING ASSEMBLY, ELASTOMERIC	8.000	EACH
54	726-96576 BEARING ASSEMBLY, FIXED	8.000	EACH
55	801-03290 CONSTRUCTION SIGN, C	1.000	EACH
56	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	360.000	LFT
57	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	3,471.000	LFT
58	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
59	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
60	801-06710 FLASHING ARROW SIGN	180.000	DAY
61	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
62	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	1.000	EACH
63	801-07118 BARRICADE, III-A	72.000	LFT
64	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	250.000	LFT
65	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	520.000	LFT
66	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
67	808-06716 LINE, REMOVE	970.000	LFT
68	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	269.000	LFT
69	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	974.000	LFT
70	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	811.000	LFT

CALL ORDER : 500

CONTRACT ID : B -31380-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	1,738.000	SYS
10	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
11	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	500.000	CYS
13	203-02070 BORROW	560.000	CYS
14	205-06930 SPLASHPAD, RIPRAP	16.800	TON
15	205-06932 TEMPORARY CHECK DAM, STRAW BALES	120.000	LFT
16	205-06937 TEMPORARY SILT FENCE	3,920.000	LFT
17	205-09543 NO 2 STONE	100.000	TON
18	207-08263 SUBGRADE TREATMENT, TYPE IA	6,300.000	SYS
19	211-09267 STRUCTURAL BACKFILL, TYPE 4	51.200	CYS
20	302-06464 SUBBASE FOR PCCP	34.000	CYS
21	302-07455 DENSE GRADED SUBBASE	96.200	CYS
22	303-01180 COMPACTED AGGREGATE, NO. 53	12.000	TON
23	306-08036 MILLING, ASPHALT, 2 IN	89.000	SYS
24	306-08037 MILLING, ASPHALT, 3 IN	89.000	SYS
25	306-08043 MILLING, TRANSITION	70.000	SYS
26	402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE	4,626.000	TON
27	402-07784 HMA SURFACE, TYPE D	123.000	TON
28	402-07785 HMA INTERMEDIATE, TYPE D	211.000	TON
29	402-07786 HMA BASE, TYPE D	721.000	TON
30	402-07787 HMA WEDGE AND LEVEL, TYPE D	59.500	TON
31	406-05520 ASPHALT FOR TACK COAT	1.440	TON
32	502-06329 PCCP, 12 IN	1,160.000	SYS
33	503-03489 RETROFITTED TIE BARS	104.000	EACH
34	503-05240 D-1 CONTRACTION JOINT	520.000	LFT
35	503-05310 TERMINAL JOINT	104.000	LFT
36	601-01522 GUARDRAIL, TRANSITION TYPE TGB	6.000	EACH
37	601-02241 GUARDRAIL, REMOVE	1,125.000	LFT
38	601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION	2.000	EACH
39	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
40	601-94690 GUARDRAIL END TREATMENT, MS	2.000	EACH
41	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	425.000	LFT
42	601-99108 GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	450.000	LFT
43	601-99132 GUARDRAIL, TRANSITION, VH, 6 FT-3 IN SPACING	1.000	EACH
44	602-06729 BARRIER DELINEATOR	20.000	EACH
45	606-07484 MILLED HMA SHOULDER CORRUGATIONS	5,307.000	LFT
46	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	577.400	SYS
47	616-02320 GEOTEXTILES	633.300	SYS
48	616-05688 RIPRAP, CLASS 1	430.000	TON
49	616-06405 RIPRAP, REVETMENT	40.000	TON

CALL ORDER : 500

CONTRACT ID : B -31380-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE RECONSTRUCTION		
50	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
51	621-02770 EROSION CONTROL BLANKET	2,941.000	SYS
52	621-06545 FERTILIZER	1.600	TON
53	621-06553 SEED MIXTURE, R	646.000	LBS
54	621-06557 SEED MIXTURE, T	324.000	LBS
55	621-06565 MULCHING MATERIAL	12.000	TON
56	621-06574 SODDING	53.400	SYS
57	628-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
58	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
59	628-09402 FIELD OFFICE, B	12.000	MOS
60	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	12.000	MOS
61	702-51005 CONCRETE, A, SUBSTRUCTURE	29.600	CYS
62	702-51863 FIELD DRILLED HOLE IN CONCRETE	84.000	EACH
63	703-06029 REINFORCING BARS, EPOXY COATED	185,038.000	LBS
64	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	204.000	EACH
65	704-51002 CONCRETE, C, SUPERSTRUCTURE	596.400	CYS
66	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	8.000	EACH
67	706-09959 RAILING, CONCRETE, FT	436.000	LFT
68	709-51821 SURFACE SEAL	LUMP	LUMP
69	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	80.000	LFT
70	718-06528 OUTLET PROTECTOR, 1	8.000	EACH
71	718-08308 UNDERDRAIN, PATCHING	1,240.000	LFT
72	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
73	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	12,680.000	LFT
74	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN	8,296.000	LFT
75	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
76	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
77	801-06710 FLASHING ARROW SIGN	500.000	DAY
78	801-07118 BARRICADE, III-A	36.000	LFT
79	801-07119 BARRICADE, III-B	72.000	LFT
80	801-07606 TEMPORARY CROSSOVER DRAINAGE PIPE	1,130.000	LFT
81	801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1	1,805.000	LFT
82	801-08507 TEMPORARY TRAFFIC BARRIER, TYPE 1, ANCHORED	780.000	LFT
83	801-52817 TEMPORARY CROSSOVER, B	2.000	EACH
84	804-06770 DELINEATOR POST	8.000	EACH
85	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN	2,318.000	LFT
86	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	9,274.000	LFT
87	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	9,274.000	LFT
88	808-06716 LINE, REMOVE	4,847.000	LFT
89	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN	746.000	LFT
90	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN	746.000	LFT
91	808-75059 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN	186.000	LFT
92	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	40.000	EACH
93	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	40.000	EACH

CALL ORDER : 510

CONTRACT ID : B -31382-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
7	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
8	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
9	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
10	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
11	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
12	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
13	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
14	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
15	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
16	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
17	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
18	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
19	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
20	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
21	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
22	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
23	709-51821 SURFACE SEAL	LUMP	LUMP
24	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
25	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
26	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
27	801-06710 FLASHING ARROW SIGN	150.000	DAY
28	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 514

CONTRACT ID : B -31643-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SCOUR PROTECTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	203-51223 EXCAVATION, WATERWAY	290.000	CYS
9	205-06934 TEMPORARY MULCHING	5.200	TON
10	616-02320 GEOTEXTILES	1,021.000	SYS
11	616-05688 RIPRAP, CLASS 1	1,591.000	TON
12	616-06405 RIPRAP, REVETMENT	699.000	TON
13	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
14	621-06557 SEED MIXTURE, T	312.000	LBS
15	621-06559 MULCHED SEEDING, R	10,056.000	SYS
16	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
17	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	8.000	MOS
18	628-09409 MOBILE INTERNET SERVICE	8.000	MOS
19	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	8.000	MOS
20	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
21	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
22	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
23	801-06710 FLASHING ARROW SIGN	60.000	DAY
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 520

CONTRACT ID : B -32457-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION OR REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	606.000	SYS
10	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
11	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	12.000	CYS
13	205-06932 TEMPORARY CHECK DAM, STRAW BALES	192.000	LFT
14	205-06937 TEMPORARY SILT FENCE	400.000	LFT
15	302-07455 DENSE GRADED SUBBASE	102.000	CYS
16	402-07433 HMA SURFACE, TYPE B	4.000	TON
17	402-07438 HMA INTERMEDIATE, TYPE B	20.000	TON
18	601-06035 GUARDRAIL, RESET	50.000	LFT
19	602-06729 BARRIER DELINEATOR	218.000	EACH
20	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	606.000	SYS
21	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
22	621-06559 MULCHED SEEDING, R	222.000	SYS
23	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
24	628-09402 FIELD OFFICE, B	6.000	MOS
25	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
26	628-11007 CELLULAR TELEPHONE/RADIO SERVICE, 750 MINUTES	6.000	MOS
27	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
28	702-51100 DRAIN PIPE, CAST IRON, 6 IN	130.000	LBS
29	702-51863 FIELD DRILLED HOLE IN CONCRETE	188.000	EACH
30	703-06029 REINFORCING BARS, EPOXY COATED	27,556.000	LBS
31	706-03872 RAILING, ALUMINUM	30.000	LFT
32	706-03872 RAILING, ALUMINUM	19.000	LFT
33	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
34	706-09410 RAILING	4.000	EACH
35	706-92586 RAILING POST	12.000	EACH
36	709-51821 SURFACE SEAL	LUMP	LUMP
37	709-51821 SURFACE SEAL	LUMP	LUMP
38	710-09158 PATCHING CONCRETE STRUCTURES	20.000	SFT
39	722-09456 POLYMERIC OVERLAY SYSTEM	19,380.000	SYS
40	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	280.000	SFT
41	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	1,150.000	SFT
42	724-09627 STRUCTURAL EXPANSION JOINT SEAL, M, REPLACE	104.000	LFT
43	727-90308 EPOXY INJECTION, CRACK PREPARATION	50.000	LFT
44	727-90309 EPOXY INJECTION, EPOXY MATERIAL	2.000	GAL
45	727-93560 EPOXY INJECTION, FURNISHING EQUIPMENT	LUMP	LUMP
46	727-93560 EPOXY INJECTION, FURNISHING EQUIPMENT	LUMP	LUMP
47	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
48	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	25,429.000	LFT
49	801-06640 CONSTRUCTION SIGN, A	24.000	EACH

CALL ORDER : 520

CONTRACT ID : B -32457-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION OR REPAIR		
50	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
51	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
52	801-07118 BARRICADE, III-A	24.000	LFT
53	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	4,240.000	LFT
54	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	460.000	LFT
55	808-06716 LINE, REMOVE	10,725.000	LFT
56	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	1,744.000	LFT
57	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	5,600.000	LFT
58	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	5,140.000	LFT

CALL ORDER : 530

CONTRACT ID : B -33378-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-07025 MOBILIZATION AND DEMOBILIZATION	1.000	EACH
7	202-51368 SLOPEWALL, REMOVE	5,650.000	SYS
8	202-96128 GUTTER, CONCRETE, REMOVE	885.000	LFT
9	203-02000 EXCAVATION, COMMON	450.000	CYS
10	203-02070 BORROW	380.000	CYS
11	213-52830 FLOWABLE MORTAR	55.000	CYS
12	506-06334 PCCP PATCHING, PARTIAL DEPTH	1,650.000	SYS
13	605-06120 CURB, CONCRETE	1,135.000	LFT
14	616-51367 SLOPEWALL, CONCRETE, 4 IN	4,950.000	SYS
15	616-93772 INSPECTION HOLE	24.000	EACH
16	619-91919 JOINT AND CRACK CLEANING AND SEALING	1,098.000	LFT
17	628-09402 FIELD OFFICE, B	6.000	MOS
18	715-01662 PIPE CLEANING, 12 IN. TO 48 IN. DIA.	130.000	LFT
19	718-52610 AGGREGATE FOR UNDERDRAINS	10.000	CYS
20	718-99153 GEOTEXTILES FOR UNDERDRAIN	220.000	SYS
21	720-04499 INLET, RECONSTRUCT	6.000	EACH
22	720-96995 CLEAN INLET	6.000	EACH
23	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
24	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 570

CONTRACT ID : M -31203-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MECHANICAL SWEEPING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 210-93708	SWEEPING, CYCLE NO. 1	LUMP	LUMP
5 210-93709	SWEEPING, CYCLE NO. 2	LUMP	LUMP
6 210-93710	SWEEPING, CYCLE NO. 3	LUMP	LUMP
7 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 580

CONTRACT ID : M -31215-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
7 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
8 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
9 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
10 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
11 623-04887	MOWING, CYCLE NO 4	1.000	CYCL
12 623-04887	MOWING, CYCLE NO 4	1.000	CYCL

CALL ORDER : 590

CONTRACT ID : M -31216-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
5 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
8 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
9 623-04887	MOWING, CYCLE NO 4	1.000	CYCL
10 623-04887	MOWING, CYCLE NO 4	1.000	CYCL
11 628-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
12 628-11006	CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	14.000	MOS
13 628-11068	CELLULAR TELEPHONE/RADIO	2.000	EACH
14 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 600

CONTRACT ID : M -31217-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
5 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
6 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
7 623-04887	MOWING, CYCLE NO 4	1.000	CYCL
8 623-05684	MOWING, CYCLE NO 5	1.000	CYCL
9 623-06008	MOWING, CYCLE NO 7	1.000	CYCL
10 623-06010	MOWING, CYCLE NO 9	1.000	CYCL
11 623-06704	MOWING, CYCLE NO 6	1.000	CYCL
12 623-06707	MOWING, CYCLE NO 8	1.000	CYCL
13 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 610

CONTRACT ID : M -33700-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE OR REPAIR		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	601-01522 GUARDRAIL, TRANSITION TYPE TGB	2.000	EACH
5	601-02103 GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	120.000	LFT
6	601-02212 GUARDRAIL POST, BRACKET, 8.5 LBS PER FT, GALVANIZED,	200.000	EACH
7	601-03443 CAT UNIT FOUNDATION TUBE, MK ST WITH SOIL PLATES, MK SP	5.000	EACH
8	601-03460 GUARDRAIL, CHAN 6.7 LBS PER LFT., LABOR ONLY	2.000	LFT
9	601-03462 GUARDRAIL, POST STEEL, 8.5 LBS PER LFT, 7 FT. 0 IN.	300.000	EACH
10	601-03599 GUARDRAIL, THRIE BEAM, RAIL SECTION, 12 FT. 6 IN	100.000	EACH
11	601-03683 COMBINATION ATTENUATING TERMINAL, REPAIR, LABOR ONLY	20.000	HRS
12	601-06247 IMPACT ATTENUATOR, R2, W2, TL-3	1.000	EACH
13	601-06773 ENERGY ABSORBING TERMINAL, B, SPARE PARTS PACKAGE	2.000	EACH
14	601-61340 GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN.	100.000	EACH
15	601-61350 GUARDRAIL POST BRACKET, 15.5 LBS PER LFT., GALVANIZED,	50.000	EACH
16	601-61390 GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE,	7.000	EACH
17	601-62530 GUARDRAIL PIER CONNECTION, ES	1.000	EACH
18	601-62540 GUARDRAIL POST, PLUMB	500.000	EACH
19	601-91428 GUARDRAIL ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	12.000	EACH
20	601-91432 GUARDRAIL ATTENUATING TERMINAL, SIDE PLATE, MKSD	25.000	EACH
21	601-91504 GUARDRAIL POST, W1, 10 IN X 10 IN	7.000	EACH
22	601-91505 GUARDRAIL POST, W2, 8 IN. X 8 IN.	15.000	EACH
23	601-91542 GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	200.000	EACH
24	601-91649 GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	5.000	EACH
25	601-91653 GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	5.000	EACH
26	601-94689 GUARDRAIL END TREATMENT, OS	15.000	EACH
27	601-94690 GUARDRAIL END TREATMENT, MS	5.000	EACH
28	601-95972 GUARDRAIL POST (CRT), 8 IN X 6 IN TREATED LUMBER,	5.000	EACH
29	601-96591 GUARDRAIL PANEL, STEEL BEAM	7,500.000	LFT
30	601-97950 GUARDRAIL POST BRACKET, TREATED TIMBER, 6 IN. X 6 IN.	50.000	EACH
31	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	300.000	LFT
32	627-09331 SAFETY TERMINAL, TYPE TL-4	18.000	EACH
33	628-09402 FIELD OFFICE, B	14.000	MOS
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 620

CONTRACT ID : M -33701-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
5 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
6 623-04887	MOWING, CYCLE NO 4	1.000	CYCL
7 623-05684	MOWING, CYCLE NO 5	1.000	CYCL
8 623-06704	MOWING, CYCLE NO 6	1.000	CYCL
9 628-08520	CELLULAR TELEPHONE/RADIO	1.000	EACH
10 628-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
11 628-11006	CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	24.000	MOS

CALL ORDER : 630

CONTRACT ID : M -33702-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
5 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
6 623-04887	MOWING, CYCLE NO 4	1.000	CYCL
7 623-05684	MOWING, CYCLE NO 5	1.000	CYCL
8 623-06704	MOWING, CYCLE NO 6	1.000	CYCL

CALL ORDER : 670

CONTRACT ID : T -31672-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02279 CURB AND GUTTER, REMOVE	30.000	LFT
9	202-05545 REGULATED MATERIALS, DISPOSE, C	30.000	CYS
10	202-05555 REGULATED MATERIALS, TRANSPORT, C	30.000	CYS
11	202-06580 CONTAMINATED SOIL, REMOVE	30.000	CYS
12	202-07603 TESTING FOR WASTES, C	8.000	EACH
13	202-52710 SIDEWALK, CONCRETE, REMOVE	230.000	SYS
14	304-07491 HMA PATCHING, TYPE C	15.000	TON
15	406-05520 ASPHALT FOR TACK COAT	0.010	TON
16	604-07894 CURB RAMP, CONCRETE, A	10.000	SYS
17	604-07896 CURB RAMP, CONCRETE, B	40.000	SYS
18	604-07900 CURB RAMP, CONCRETE, F	50.000	SYS
19	604-07902 CURB RAMP, CONCRETE, H	25.000	SYS
20	604-91531 SIDEWALK, CONCRETE, 4 IN	340.000	SYS
21	605-02278 CURB, REMOVE	30.000	LFT
22	605-06120 CURB, CONCRETE	30.000	LFT
23	605-06140 CURB AND GUTTER, CONCRETE	30.000	LFT
24	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
25	621-06559 MULCHED SEEDING, R	50.000	SYS
26	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
27	628-09401 FIELD OFFICE, A	8.000	MOS
28	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	16.000	MOS
29	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
30	801-03290 CONSTRUCTION SIGN, C	19.000	EACH
31	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
32	801-06710 FLASHING ARROW SIGN	60.000	DAY
33	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
34	801-07119 BARRICADE, III-B	20.000	LFT
35	802-04089 SIGN, SHEET, REMOVE	6.000	EACH
36	802-04089 SIGN, SHEET, REMOVE	3.000	EACH
37	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	230.000	SFT
38	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	6.000	EACH
39	805-01842 HANDHOLE, SIGNAL	31.000	EACH
40	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	2,900.000	LFT
41	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	34.000	EACH
42	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	8.000	EACH
43	805-02645 SIGNAL PEDESTAL FOUNDATION, A	2.000	EACH
44	805-02658 CABLE, COAXIAL	300.000	LFT
45	805-05405 SIGNAL PEDESTAL, 4FT	2.000	EACH
46	805-08493 RADIO SYSTEM TESTING INTERCONNECT	LUMP	LUMP
47	805-08494 RADIO SPREAD SPECTRUM	1.000	EACH
48	805-09089 RADIO, YAGI ANTENNA	4.000	EACH
49	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	5.000	EACH

CALL ORDER : 670

CONTRACT ID : T -31672-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
50	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000	EACH
51	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	32.000	EACH
52	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	6.000	EACH
53	805-78370 PEDESTRIAN PUSH BUTTON	42.000	EACH
54	805-78415 SPAN, CATENARY, AND TETHER	2.000	EACH
55	805-78420 DISCONNECT HANGER	2.000	EACH
56	805-78445 SIGNAL SERVICE	4.000	EACH
57	805-78467 SIGNAL CABLE, 3C/8GA	750.000	LFT
58	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	9,800.000	LFT
59	805-78480 SIGNAL CABLE, 3C/14GA	2,750.000	LFT
60	805-78485 SIGNAL CABLE, 5C/14GA	4,000.000	LFT
61	805-78485 SIGNAL CABLE, 5C/14GA	6,300.000	LFT
62	805-78490 SIGNAL CABLE, 7C/14GA	2,500.000	LFT
63	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	6,600.000	LFT
64	805-78785 SIGNAL DETECTOR HOUSING	34.000	EACH
65	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	3,500.000	LFT
66	805-78906 SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 12 FT	1.000	EACH
67	805-78925 CONTROLLER CABINET FOUNDATION, P1	2.000	EACH
68	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	1.000	EACH
69	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	7.000	EACH
70	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	21.000	EACH
71	805-97509 CONTROL CABINET FOUNDATION, M, MODIFY TO P1	4.000	EACH
72	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	165.000	LFT
73	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	470.000	LFT
74	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	10.000	EACH
75	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH

CALL ORDER : 680

CONTRACT ID : T -33757-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL SAFETY PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	628-09402 FIELD OFFICE, B	5.000	MOS
9	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
10	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
11	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
12	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	40.000	SFT
13	805-06742 SOLAR POWERED FLASHING BEACON ASSEMBLY	5.000	EACH
14	805-78900 PEDESTAL FOUNDATION, A	5.000	EACH

CALL ORDER : 690

CONTRACT ID : T -33787-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL CONTROLLERS UPGRADE		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
4 628-09408	MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
5 628-09409	MOBILE INTERNET SERVICE	4.000	MOS
6 805-06483	CONTROLLER	274.000	EACH

CALL ORDER : 700

CONTRACT ID : T -33811-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	628-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
7	628-08521 CELLULAR TELEPHONE/RADIO SERVICE	4.000	MOS
8	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
9	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
10	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
11	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
12	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
13	802-07060 SIGN, SHEET, RELOCATE	7.000	EACH
14	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	1,228.300	SFT
15	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	395.490	SFT
16	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	135.800	SFT
17	802-76055 SIGN POST, A	1,600.000	LFT

CALL ORDER : 710

CONTRACT ID : T -33883-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW SIGNAL INSTALLATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02278 CURB, CONCRETE, REMOVE	205.000	LFT
10	202-05545 REGULATED MATERIALS, DISPOSE, C	40.000	CYS
11	202-05550 REGULATED MATERIALS, REMOVE, C	40.000	CYS
12	202-52710 SIDEWALK, CONCRETE, REMOVE	92.400	SYS
13	202-96022 CONCRETE FOUNDATION, REMOVE	3.000	EACH
14	202-98370 POLE, REMOVE	1.000	EACH
15	203-02020 EXCAVATION, UNCLASSIFIED	12.200	CYS
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	16.700	TON
17	304-07490 HMA PATCHING, TYPE B	22.000	TON
18	406-05520 ASPHALT FOR TACK COAT	1.000	TON
19	604-07901 CURB RAMP, CONCRETE, G	85.500	SYS
20	604-91531 SIDEWALK, CONCRETE, 4 IN	9.700	SYS
21	605-90726 CURB, CONCRETE, DEPRESSED	191.500	LFT
22	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
23	621-06570 TOPSOIL	7.500	CYS
24	621-06575 SODDING, NURSERY	67.200	SYS
25	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
26	628-09402 FIELD OFFICE, B	7.000	MOS
27	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	7.000	MOS
28	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
29	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
30	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	5.000	EACH
33	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	56.000	SFT
34	802-09841 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.125 IN THICKNESS	42.000	SFT
35	805-01579 MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	LUMP	LUMP
36	805-01842 HANDHOLE, SIGNAL	5.000	EACH
37	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	650.000	LFT
38	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	8.000	EACH
39	805-02596 CONDUIT RISER WITH WEATHERHEAD, STEEL	1.000	EACH
40	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
41	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	4.000	EACH
42	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	4.000	EACH
43	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
44	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
45	805-78420 DISCONNECT HANGER	4.000	EACH
46	805-78445 SIGNAL SERVICE	1.000	EACH
47	805-78467 SIGNAL CABLE, 3C/8GA	20.000	LFT
48	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	3,000.000	LFT
49	805-78480 SIGNAL CABLE, 3C/14GA	620.000	LFT

CALL ORDER : 710

CONTRACT ID : T -33883-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW SIGNAL INSTALLATION		
50	805-78485 SIGNAL CABLE, 5C/14GA	680.000	LFT
51	805-78490 SIGNAL CABLE, 7C/14GA	690.000	LFT
52	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	595.000	LFT
53	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
54	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	990.000	LFT
55	805-78906 SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 12 FT	4.000	EACH
56	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
57	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
58	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	3.000	EACH
59	805-94554 PULL BOX, POLYETHYLENE	4.000	EACH
60	807-02782 LUMINAIRE, MAST ARM, 12 FT	1.000	EACH
61	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	400.000	LFT
62	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,450.000	LFT
63	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	100.000	LFT
64	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	320.000	LFT
65	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH
66	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH

CALL ORDER : 720

CONTRACT ID : T -34100-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS, NEW OR MODERNIZED		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
8	628-09401 FIELD OFFICE, A	5.000	MOS
9	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	5.000	MOS
10	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	10.000	MOS
11	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
12	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
14	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	5.000	SFT
15	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	8.000	SFT
16	805-01816 SIGNAL SUPPORT FOUNDATION, 36 IN X 36 IN X 96 IN	4.000	EACH
17	805-01842 HANDHOLE, SIGNAL	10.000	EACH
18	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	500.000	LFT
19	805-02373 SIGNAL INTERCONNECT CABLE, FIBER OPTIC	1,000.000	LFT
20	805-09540 LOOP DETECTOR RACK	1.000	EACH
21	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
22	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	4.000	EACH
23	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	1.000	EACH
24	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
25	805-78420 DISCONNECT HANGER	3.000	EACH
26	805-78445 SIGNAL SERVICE	1.000	EACH
27	805-78467 SIGNAL CABLE, 3C/8GA	50.000	LFT
28	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	1,200.000	LFT
29	805-78485 SIGNAL CABLE, 5C/14GA	1,500.000	LFT
30	805-78490 SIGNAL CABLE, 7C/14GA	1,500.000	LFT
31	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	3,000.000	LFT
32	805-78785 SIGNAL DETECTOR HOUSING	5.000	EACH
33	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	2,000.000	LFT
34	805-78900 PEDESTAL FOUNDATION, A	1.000	EACH
35	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
36	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT	4.000	EACH
37	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	4.000	EACH
38	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	120.000	LFT
39	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	3.000	EACH
40	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH

CALL ORDER : 730

CONTRACT ID : TM-32905-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	RAISED PAVEMENT MARKINGS, REFURBISHED		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6 628-08520	CELLULAR TELEPHONE/RADIO	1.000	EACH
7 628-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
8 628-09408	MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
9 628-09409	MOBILE INTERNET SERVICE	6.000	MOS
10 628-10246	CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	6.000	MOS
11 801-06710	FLASHING ARROW SIGN	300.000	DAY
12 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
13 801-09133	TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
14 808-75994	PRISMATIC REFLECTOR	33,825.000	EACH
15 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	800.000	EACH
16 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1,600.000	EACH

