

CALL ORDER : 156

CONTRACT ID : IR-33291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HMA PAVEMENT/ CROSSOVER OPTION		
1	203-02000 EXCAVATION, COMMON	114,485.000	CYS
2	203-02070 BORROW	76,913.000	CYS
3	207-08263 SUBGRADE TREATMENT, TYPE IA	53,514.000	SYS
4	211-02050 B BORROW	4,914.000	CYS
5	211-09266 STRUCTURAL BACKFILL, TYPE 3	10,874.000	CYS
6	215-07043 CHEMICAL MODIFICATION, SOILS	11,013.000	SYS
7	302-06464 SUBBASE FOR PCCP	160.000	CYS
8	303-01180 COMPACTED AGGREGATE, NO. 53	5,776.000	TON
9	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,912.000	TON
10	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	1,073.000	TON
11	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	3,187.000	TON
12	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 mm	1,789.000	TON
13	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	1,885.000	TON
14	401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm	5,725.000	TON
15	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	6,232.000	TON
16	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	5,174.000	TON
17	402-10087 HMA FOR TEMPORARY PAVEMENT, D	6,486.000	TON
18	406-05520 ASPHALT FOR TACK COAT	58.000	TON
19	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
20	605-06100 CURB, INTEGRAL, C, CONCRETE	345.000	LFT
21	605-06120 CURB, CONCRETE	885.000	LFT
22	605-06145 CURB AND GUTTER, B, CONCRETE	483.000	LFT
23	605-06150 CURB AND GUTTER, C, CONCRETE	3,159.000	LFT
24	615-06505 MONUMENT, B	30.000	EACH
25	621-06545 FERTILIZER	27.000	TON
26	621-06554 SEED MIXTURE, U	525.000	LBS
27	621-06557 SEED MIXTURE, T	4,965.000	LBS
28	621-06565 MULCHING MATERIAL	134.000	TON
29	713-04509 TEMPORARY PIPE	LUMP	LUMP
30	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	2,162.000	LFT
31	718-06528 OUTLET PROTECTOR, 1	31.000	EACH
32	720-95310 INLET, P12A, MODIFIED	2.000	EACH
33	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	31,741.000	LFT
34	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	39,858.000	LFT
35	801-06640 CONSTRUCTION SIGN, A	83.000	EACH
36	801-06645 CONSTRUCTION SIGN, B	18.000	EACH
37	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
38	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	3.000	EACH
39	801-07118 BARRICADE, III-A	36.000	LFT
40	801-07119 BARRICADE, III-B	456.000	LFT
41	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	8,932.000	LFT
SECTION NO. 0002	HMA PAVEMENT / MOT NIGHTTIME CLOSURE OPTION		
42	203-02000 EXCAVATION, COMMON	109,273.000	CYS
43	203-02070 BORROW	75,187.000	CYS
44	207-08263 SUBGRADE TREATMENT, TYPE IA	44,465.000	SYS
45	211-02050 B BORROW	4,914.000	CYS
46	211-09266 STRUCTURAL BACKFILL, TYPE 3	10,874.000	CYS

CALL ORDER : 156

CONTRACT ID : IR-33291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	HMA PAVEMENT / MOT NIGHTTIME CLOSURE OPTION		
47	302-06464 SUBBASE FOR PCCP	160.000	CYS
48	303-01180 COMPACTED AGGREGATE, NO. 53	4,919.000	TON
49	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,912.000	TON
50	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	1,073.000	TON
51	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	3,187.000	TON
52	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 mm	1,789.000	TON
53	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	1,885.000	TON
54	401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm	5,725.000	TON
55	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	6,232.000	TON
56	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	5,174.000	TON
57	402-10087 HMA FOR TEMPORARY PAVEMENT, D	1,509.000	TON
58	406-05520 ASPHALT FOR TACK COAT	53.000	TON
59	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	1.000	EACH
60	605-06100 CURB, INTEGRAL, C, CONCRETE	345.000	LFT
61	605-06120 CURB, CONCRETE	885.000	LFT
62	605-06145 CURB AND GUTTER, B, CONCRETE	483.000	LFT
63	605-06150 CURB AND GUTTER, C, CONCRETE	3,519.000	LFT
64	615-06505 MONUMENT, B	30.000	EACH
65	621-06545 FERTILIZER	26.000	TON
66	621-06554 SEED MIXTURE, U	273.000	LBS
67	621-06557 SEED MIXTURE, T	4,896.000	LBS
68	621-06565 MULCHING MATERIAL	130.000	TON
69	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	2,125.000	LFT
70	718-06528 OUTLET PROTECTOR, 1	25.000	EACH
71	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	17,780.000	LFT
72	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	18,351.000	LFT
73	801-06640 CONSTRUCTION SIGN, A	84.000	EACH
74	801-06645 CONSTRUCTION SIGN, B	16.000	EACH
75	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
76	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH
77	801-07119 BARRICADE, III-B	384.000	LFT
78	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	7,358.000	LFT
79	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
SECTION NO. 0003	PCC PAVEMENT / MOT CROSSOVER OPTION		
80	203-02000 EXCAVATION, COMMON	117,312.000	CYS
81	203-02070 BORROW	66,744.000	CYS
82	207-08263 SUBGRADE TREATMENT, TYPE IA	53,514.000	SYS
83	211-02050 B BORROW	4,643.000	CYS
84	211-09266 STRUCTURAL BACKFILL, TYPE 3	10,834.000	CYS
85	215-07043 CHEMICAL MODIFICATION, SOILS	11,013.000	SYS
86	302-06464 SUBBASE FOR PCCP	9,337.000	CYS
87	303-01180 COMPACTED AGGREGATE, NO. 53	4,957.000	TON
88	402-10087 HMA FOR TEMPORARY PAVEMENT, D	6,486.000	TON
89	406-05520 ASPHALT FOR TACK COAT	13.000	TON
90	501-06321 QC/QA-PCCP, 10 IN	9,024.000	SYS
91	501-06323 QC/QA-PCCP, 12 IN	27,685.000	SYS
92	503-03489 RETROFITTED TIE BARS	4,607.000	EACH

CALL ORDER : 156

CONTRACT ID : IR-33291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 PCC PAVEMENT / MOT CROSSOVER OPTION			
93	503-05240 D-1 CONTRACTION JOINT	20,744.000	LFT
94	503-05310 TERMINAL JOINT	215.000	LFT
95	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
96	605-06095 CURB, INTEGRAL, B, CONCRETE	483.000	LFT
97	605-06100 CURB, INTEGRAL, C, CONCRETE	3,553.000	LFT
98	605-06150 CURB AND GUTTER, C, CONCRETE	836.000	LFT
99	615-06505 MONUMENT, B	2.000	EACH
100	615-06515 MONUMENT, D	28.000	EACH
101	621-06545 FERTILIZER	27.000	TON
102	621-06554 SEED MIXTURE, U	525.000	LBS
103	621-06557 SEED MIXTURE, T	4,965.000	LBS
104	621-06565 MULCHING MATERIAL	134.000	TON
105	713-04509 TEMPORARY PIPE	LUMP	LUMP
106	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	2,162.000	LFT
107	718-06528 OUTLET PROTECTOR, 1	31.000	EACH
108	720-95310 INLET, P12A, MODIFIED	2.000	EACH
109	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	31,741.000	LFT
110	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	39,858.000	LFT
111	801-06640 CONSTRUCTION SIGN, A	83.000	EACH
112	801-06645 CONSTRUCTION SIGN, B	18.000	EACH
113	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
114	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	3.000	EACH
115	801-07118 BARRICADE, III-A	36.000	LFT
116	801-07119 BARRICADE, III-B	456.000	LFT
117	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	8,932.000	LFT
SECTION NO. 0004 PCC PAVEMENT / MOT NIGHTTIME CLOSURE OPTION			
118	203-02000 EXCAVATION, COMMON	112,100.000	CYS
119	203-02070 BORROW	65,019.000	CYS
120	207-08263 SUBGRADE TREATMENT, TYPE IA	44,465.000	SYS
121	211-02050 B BORROW	4,643.000	CYS
122	211-09266 STRUCTURAL BACKFILL, TYPE 3	10,834.000	CYS
123	302-06464 SUBBASE FOR PCCP	9,337.000	CYS
124	303-01180 COMPACTED AGGREGATE, NO. 53	4,100.000	TON
125	402-10087 HMA FOR TEMPORARY PAVEMENT, D	1,509.000	TON
126	406-05520 ASPHALT FOR TACK COAT	8.000	TON
127	501-06321 QC/QA-PCCP, 10 IN	9,024.000	SYS
128	501-06323 QC/QA-PCCP, 12 IN	27,685.000	SYS
129	503-03489 RETROFITTED TIE BARS	4,607.000	EACH
130	503-05240 D-1 CONTRACTION JOINT	20,744.000	LFT
131	503-05310 TERMINAL JOINT	215.000	LFT
132	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	1.000	EACH
133	605-06095 CURB, INTEGRAL, B, CONCRETE	483.000	LFT
134	605-06100 CURB, INTEGRAL, C, CONCRETE	3,553.000	LFT
135	605-06150 CURB AND GUTTER, C, CONCRETE	836.000	LFT
136	615-06505 MONUMENT, B	2.000	EACH
137	615-06515 MONUMENT, D	28.000	EACH
138	621-06545 FERTILIZER	26.000	TON

CALL ORDER : 156

CONTRACT ID : IR-33291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004 PCC PAVEMENT / MOT NIGHTTIME CLOSURE OPTION			
139	621-06554 SEED MIXTURE, U	273.000	LBS
140	621-06557 SEED MIXTURE, T	4,896.000	LBS
141	621-06565 MULCHING MATERIAL	130.000	TON
142	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	2,125.000	LFT
143	718-06528 OUTLET PROTECTOR, 1	25.000	EACH
144	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	17,780.000	LFT
145	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	18,351.000	LFT
146	801-06640 CONSTRUCTION SIGN, A	84.000	EACH
147	801-06645 CONSTRUCTION SIGN, B	16.000	EACH
148	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
149	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH
150	801-07119 BARRICADE, III-B	384.000	LFT
151	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	7,358.000	LFT
152	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
SECTION NO. 0005 COMMON ITEMS			
153	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
154	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
155	107-09358 INSPECTION HOLE, GREATER THAN 3'	10.000	EACH
156	107-09367 INSPECTION HOLE, 3 FT DEPTH OR LESS	10.000	EACH
157	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
158	113-01614 PARTNERING OVERHEAD	LUMP	LUMP
159	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
160	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
161	202-01261 TESTING FOR ASBESTOS, TYPE	1.000	EACH
162	202-02240 PAVEMENT REMOVAL	27.000	SYS
163	202-02637 PIPE, ABANDON AND GROUT FILL	264.000	LFT
164	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
165	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
166	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
167	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
168	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
169	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
170	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	1,797.000	SFT
171	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
172	202-91385 INLET, REMOVE	13.000	EACH
173	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	70.000	LFT
174	202-96133 PIPE, REMOVE	120.000	LFT
175	203-51223 EXCAVATION, WATERWAY	691.000	CYS
176	205-02770 EROSION CONTROL BLANKET	2,535.000	SYS
177	205-03371 SEDIMENT, REMOVE	3,213.000	CYS
178	205-06930 SPLASHPAD, RIPRAP	26.000	TON
179	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	392.000	TON
180	205-06933 TEMPORARY DITCH INLET PROTECTION	10.000	EACH
181	205-06935 TEMPORARY SEDIMENT BASIN	1.000	EACH
182	205-06936 TEMPORARY SEDIMENT TRAP	218.000	TON
183	205-06937 TEMPORARY SILT FENCE	4,384.000	LFT
184	205-06938 TEMPORARY SLOPE DRAIN	507.000	LFT

CALL ORDER : 156

CONTRACT ID : IR-33291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	COMMON ITEMS		
185	205-09543 NO 2 STONE	128.000	TON
186	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	128.000	CYS
187	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,158.000	SYS
188	211-02050 B BORROW	7,324.000	CYS
189	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,736.000	CYS
190	211-09265 STRUCTURAL BACKFILL, TYPE 2	306.000	CYS
191	211-09266 STRUCTURAL BACKFILL, TYPE 3	10,366.000	CYS
192	211-09267 STRUCTURAL BACKFILL, TYPE 4	92.000	CYS
193	211-09268 STRUCTURAL BACKFILL, TYPE 5	164.000	CYS
194	214-07202 GEOGRID, TYPE I	16,688.000	SYS
195	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	23,253.000	TON
196	302-07455 DENSE GRADED SUBBASE	82.000	CYS
197	302-08562 COARSE AGGREGATE, 8	52.000	TON
198	303-07449 COMPACTED AGGREGATE, NO. 73	153.000	TON
199	303-07662 STONE	42.000	TON
200	303-07662 STONE	46.000	TON
201	303-07662 STONE	557.000	TON
202	306-08042 MILLING, SCARIFICATION/PROFILE	4,510.000	SYS
203	401-06264 PROFIOLOGRAPH, HMA	LUMP	LUMP
204	402-07432 HMA SURFACE, TYPE A	216.000	TON
205	402-07434 HMA SURFACE, TYPE C	607.000	TON
206	402-07435 HMA INTERMEDIATE, TYPE A	350.000	TON
207	402-07439 HMA INTERMEDIATE, TYPE C	1,721.000	TON
208	402-07442 HMA BASE, TYPE C	941.000	TON
209	501-06266 PROFIOLOGRAPH, PCCP	LUMP	LUMP
210	502-06327 PCCP, 10 IN	639.000	SYS
211	502-09531 PCCP	191.000	SYS
212	601-01522 GUARDRAIL, TRANSITION TYPE TGB	1.000	EACH
213	601-02241 GUARDRAIL, REMOVE	1,693.000	LFT
214	601-06238 IMPACT ATTENUATOR, R1, W1, TL-3	1.000	EACH
215	601-06239 IMPACT ATTENUATOR, R1, W2, TL-3	1.000	EACH
216	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	2.000	EACH
217	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
218	601-06855 GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	3.000	EACH
219	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
220	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	600.000	LFT
221	601-99123 GUARDRAIL, TRANSITION, GP	1.000	EACH
222	602-02098 MEDIAN BARRIER RAIL TRANSITION	2.000	EACH
223	602-08605 CONCRETE BARRIER, 33 IN	325.000	LFT
224	603-03829 FENCE,	180.000	LFT
225	603-04160 FENCE GATE, CHAIN LINK, 48 IN X 32 FT	1.000	EACH
226	603-06045 FENCE, CHAIN LINK, 48 IN	10,389.000	LFT
227	603-09066 FENCE, CHAIN LINK, PVC COATED, 72 IN	355.900	LFT
228	604-01268 HAND RAIL, ALUMINUM	106.000	LFT
229	604-07901 CURB RAMP, CONCRETE, G	109.000	SYS
230	604-07904 CURB RAMP, CONCRETE, L	29.000	SYS
231	604-08086 CURB RAMP, CONCRETE	12.000	SYS
232	605-06250 CENTER CURB, C, CONCRETE	733.000	SYS
233	605-06250 CENTER CURB, C, CONCRETE	166.000	SYS

CALL ORDER : 156

CONTRACT ID : IR-33291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	COMMON ITEMS		
234	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	509.900	SYS
235	610-07487 HMA FOR APPROACHES, TYPE B	409.000	TON
236	610-09108 PCCP FOR APPROACHES, 9 IN	101.000	SYS
237	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
238	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
239	615-06490 RIGHT OF WAY MARKER	21.000	EACH
240	615-06510 MONUMENT, C	5.000	EACH
241	615-06530 BENCH MARK POST	2.000	EACH
242	616-02320 GEOTEXTILES	5,726.000	SYS
243	616-05688 RIPRAP, CLASS 1	880.000	TON
244	616-05689 RIPRAP, CLASS 2	15.000	TON
245	616-06405 RIPRAP, REVETMENT	869.000	TON
246	616-06451 RIPRAP, UNIFORM	281.000	TON
247	616-07210 FIBER ROLL	3,842.000	LFT
248	616-11349 ROOTWAD REVETMENT	707.000	LFT
249	620-01753 SOUND BARRIER PANELS, WALL MOUNTED, TYPE	29,870.000	SFT
250	620-01754 SOUND BARRIER PANELS, GROUND MOUNTED, TYPE	2,870.000	SFT
251	620-01755 SOUND BARRIER ERECTION, WALL MOUNTED, TYPE	29,870.000	SFT
252	620-01756 SOUND BARRIER ERECTION, GROUND MOUNTED, TYPE	2,870.000	SFT
253	620-08426 SOUND BARRIER DESIGN AND LAYOUT	LUMP	LUMP
254	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
255	621-04258 SEED MIXTURE	11.400	LBS
256	621-04258 SEED MIXTURE	6.900	LBS
257	621-04258 SEED MIXTURE	4.000	LBS
258	621-04258 SEED MIXTURE	105.000	LBS
259	621-04258 SEED MIXTURE	9.800	LBS
260	621-06553 SEED MIXTURE, R	4,545.000	LBS
261	621-06560 MULCHED SEEDING, U	306.000	SYS
262	621-06567 WATER	201.000	KGAL
263	621-06570 TOPSOIL	2,267.000	CYS
264	621-06574 SODDING	11,010.000	SYS
265	621-06575 SODDING, NURSERY	3,295.000	SYS
266	621-09908 SOIL	413.000	CYS
267	621-09909 SOIL	7,211.000	SYS
268	621-90853 TAPPING SLEEVE WITH VALVE	3.000	EACH
269	621-98038 MULCH, HARDWOOD SHREDDED BARK	104.000	CYS
270	622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT	23.000	EACH
271	622-05634 PLANT, CONIFEROUS EVERGREEN, PROSTRATE, BROAD SPREADING,	328.000	EACH
272	622-05639 PLANT, DECIDUOUS SHRUB, 18 TO 24 IN	380.000	EACH
273	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	41.000	EACH
274	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	7.000	EACH
275	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	7.000	EACH
276	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	2.000	EACH
277	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	2.000	EACH
278	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	2.000	EACH
279	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	7.000	EACH
280	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	7.000	EACH
281	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	7.000	EACH
282	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	2.000	EACH

CALL ORDER : 156

CONTRACT ID : IR-33291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	COMMON ITEMS		
283	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	2.000	EACH
284	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN	5.000	EACH
285	622-05654 PLANT, PERENNIAL	300.000	EACH
286	622-10003 LIVE PLANT STAKING	6,966.000	EACH
287	622-52436 SIGN, DO NOT MOW OR SPRAY	47.000	EACH
288	622-91786 SEEDLING	1,164.000	EACH
289	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
290	628-09403 FIELD OFFICE, C	26.000	MOS
291	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	26.000	MOS
292	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	78.000	MOS
293	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	130.000	MOS
294	628-11068 CELLULAR TELEPHONE/RADIO	5.000	EACH
295	701-06011 DYNAMIC PILE LOAD TEST	3.000	EACH
296	701-09557 TEST PILE, DYNAMIC, PRODUCTION	231.000	LFT
297	701-09557 TEST PILE, DYNAMIC, PRODUCTION	108.000	LFT
298	701-09559 TEST PILE, DYNAMIC, RESTRIKE	3.000	EACH
299	701-09683 PILE SHOE, HP 12 X 74	28.000	EACH
300	701-09891 PILE SHOE, 12 X 84, HP	22.000	EACH
301	701-09892 PILE, STEEL H, HP 12 X 84	2,058.000	LFT
302	701-95780 PILE, STEEL H, HP 12 IN X 74	2,738.000	LFT
303	702-04325 TEMPORARY SHORING	LUMP	LUMP
304	702-51005 CONCRETE, A, SUBSTRUCTURE	246.200	CYS
305	702-51015 CONCRETE, B, FOOTINGS	15.500	CYS
306	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	2,378.000	LBS
307	702-92857 CONCRETE, C, SUBSTRUCTURE	85.000	CYS
308	703-06028 REINFORCING BARS	28,430.000	LBS
309	703-06029 REINFORCING BARS, EPOXY COATED	365,488.000	LBS
310	704-51002 CONCRETE, C, SUPERSTRUCTURE	979.800	CYS
311	706-06342 RAILING, PS-1	403.200	LFT
312	706-06351 CONCRETE BRIDGE RAILING TRANSITION, TPF-1	1.000	EACH
313	706-06353 CONCRETE BRIDGE RAILING TRANSITION, TPS-1	3.000	EACH
314	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	3,274.000	SYS
315	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	26.000	SYS
316	706-51020 RAILING, CONCRETE, C	210.600	CYS
317	707-08158 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 42 IN X 49 IN	1,966.000	LFT
318	709-51821 SURFACE SEAL	LUMP	LUMP
319	714-08514 WINGWALL	1,821.000	SFT
320	715-02246 PIPE END SECTION, 48 IN	2.000	EACH
321	715-02534 VALVE WITH BOX, RESTRAINED, GATE,	5.000	EACH
322	715-02961 WATER MAIN 16 IN	2,997.000	LFT
323	715-03475 SAFETY METAL END SECTION, 4:1 15 IN	5.000	EACH
324	715-04522 PIPE END SECTION, 42 IN	2.000	EACH
325	715-04965 WATER SERVICE LINE	238.000	LFT
326	715-04995 LINE STOP	2.000	EACH
327	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	19,622.000	LFT
328	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	698.000	LFT
329	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	2,583.000	LFT
330	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	169.000	LFT
331	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	1,055.000	LFT

CALL ORDER : 156

CONTRACT ID : IR-33291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	COMMON ITEMS		
332	715-05161 PIPE, TYPE 2 CIRCULAR 48 IN	1.000	LFT
333	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	210.000	LFT
334	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	93.000	LFT
335	715-05234 PIPE, TYPE 1 DEFORMED MIN AREA 4.1 SF	72.000	LFT
336	715-08181 PIPE END SECTION, MIN AREA 4.1 SF	1.000	EACH
337	715-08452 SAFETY METAL END SEC, 4:1, 34 IN X 22 IN	1.000	EACH
338	715-09064 VIDEO INSPECTION FOR PIPE	5,647.000	LFT
339	715-46000 PIPE END SECTION, 12 IN	2.000	EACH
340	715-46005 PIPE END SECTION, 15 IN	16.000	EACH
341	715-46010 PIPE END SECTION, 18 IN	6.000	EACH
342	715-46020 PIPE END SECTION, 24 IN	1.000	EACH
343	715-91742 WATER METER, RELOCATE	2.000	EACH
344	716-01382 AIR RELEASE VALVE	3.000	EACH
345	716-04832 PIPE CASING	1,049.000	LFT
346	716-04832 PIPE CASING	511.000	LFT
347	716-07632 PIPE INSTALLATION, TRENCHLESS, 18 IN	96.000	LFT
348	716-07633 PIPE INSTALLATION, TRENCHLESS, 24 IN	400.000	LFT
349	716-07634 PIPE INSTALLATION, TRENCHLESS, 30 IN	200.000	LFT
350	716-07636 PIPE INSTALLATION, TRENCHLESS, 42 IN	460.000	LFT
351	716-07637 PIPE INSTALLATION, TRENCHLESS, 48 IN	210.000	LFT
352	718-06531 OUTLET PROTECTOR, 3	9.000	EACH
353	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
354	718-52610 AGGREGATE FOR UNDERDRAINS	1,747.000	CYS
355	718-99153 GEOTEXTILES FOR UNDERDRAIN	18,937.000	SYS
356	720-01092 MANHOLE, J15, MODIFIED	1.000	EACH
357	720-02442 PIPE, PLUG EXISTING	13.000	EACH
358	720-02442 PIPE, PLUG EXISTING	2.000	EACH
359	720-03194 MANHOLE	4.000	EACH
360	720-03194 MANHOLE	1.000	EACH
361	720-07301 INLET, TYPE HA	7.000	EACH
362	720-45070 INLET, P12A	5.000	EACH
363	720-45270 PIPE CATCH BASIN, 18 IN	1.000	EACH
364	720-45410 MANHOLE, C4	12.000	EACH
365	720-94612 MANHOLE, K4	1.000	EACH
366	720-96999 FIRE HYDRANT ASSEMBLY	2.000	EACH
367	720-97009 FIRE HYDRANT ASSEMBLY, REMOVE	3.000	EACH
368	720-98174 INLET, B15	19.000	EACH
369	720-98555 INLET, C15	2.000	EACH
370	722-95883 BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
371	723-11215 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	107.000	LFT
372	731-93945 FACE PANELS, CONCRETE	36,784.000	SFT
373	731-93946 WALL ERECTION	36,784.000	SFT
374	731-93947 LEVELING PAD, CONCRETE	2,625.500	LFT
375	732-05538 TESTING AND DISINFECTION	LUMP	LUMP
376	735-10241 TEMPORARY WIRE FACING	816.000	SFT
377	735-10242 TEMPORARY WALL ERECTION	816.000	SFT
378	801-03290 CONSTRUCTION SIGN, C	19.000	EACH
379	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
380	801-06201 TEMPORARY PANEL SIGNS	168.000	SFT

CALL ORDER : 156

CONTRACT ID : IR-33291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	COMMON ITEMS		
381	801-06202	TEMPORARY PANEL SIGN SUPPORTS	83.000 LFT
382	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	39.000 LFT
383	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.000 EACH
384	801-06710	FLASHING ARROW SIGN	8.000 DAY
385	801-53072	TEMPORARY TRAFFIC SIGNAL	LUMP LUMP
386	802-04314	SIGN	11.000 EACH
387	802-04893	REFERENCE POST	12.000 EACH
388	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	612.000 LFT
389	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	240.750 LFT
390	802-05706	SIGN POST, SQUARE, TYPE 3, UNREINFORCED ANCHOR BASE	155.000 LFT
391	802-07057	SIGN, PANEL, WITH LEGEND	2,565.500 SFT
392	802-07138	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, IX	2.000 EACH
393	802-07151	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	12.000 EACH
394	802-07152	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, X	4.000 EACH
395	802-07154	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XII	2.000 EACH
396	802-09536	BOX TRUSS SIGN STRUCTURE FOUNDATION, 45 IN.	1.000 EACH
397	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN.	7.000 EACH
398	802-09578	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	1.000 EACH
399	802-09581	OVERHEAD BALANCED CANTILEVER SIGN STRUCTURE FOUNDATION,	1.000 EACH
400	802-09712	OVERHEAD SIGN STRUCTURE, A	4.000 EACH
401	802-09838	SIGN, SHEET, WITH LEGEND 0.080"	197.660 SFT
402	802-09840	SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	468.600 SFT
403	802-09842	SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	185.000 SFT
404	802-74040	SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	10.000 EACH
405	802-74045	SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	19.000 EACH
406	802-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	1.000 EACH
407	802-76055	SIGN POST, A	126.000 LFT
408	802-76095	STRUCTURAL STEEL, BREAKAWAY	5,372.000 LBS
409	802-76160	BRIDGE BRACKET ASSEMBLY	2.000 EACH
410	807-01603	SERVICE POINT, TYPE II	2.000 EACH
411	807-02191	HANDHOLE, LIGHTING	9.000 EACH
412	807-02193	LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	35.000 EACH
413	807-02426	WIRE, THW, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	1,695.000 LFT
414	807-07580	WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	10,110.000 LFT
415	807-11406	LIGHT POLE, ROADWAY, 36 FT. E.M.H., 5 FT. MAST ARM,	2.000 EACH
416	807-83752	LIGHT POLE, 40FT E.M.H., 10FT MAST ARM, ANCHOR BASE	1.000 EACH
417	807-85752	LIGHT POLE, 40 FT E.M.H., 10.0 FT MAST ARM, BREAKAWAY BASE	35.000 EACH
418	807-86620	LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	38.000 EACH
419	807-86889	CABLE, POLE CIRCUIT THWH, NO10 COPPER, STRANDED, 1/C	4,180.000 LFT
420	807-86910	CONNECTOR KIT, UNFUSED	38.000 EACH
421	807-86915	CONNECTOR KIT, FUSED	38.000 EACH
422	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	72.000 EACH
423	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	36.000 EACH
424	807-86930	INSULATION LINK, NON-WATERPROOFED	76.000 EACH
425	807-86935	INSULATION LINK, WATERPROOFED	36.000 EACH
426	807-86955	CABLE-DUCT MARKER	7.000 EACH
427	808-09381	RETRO-REFLECTIVITY TESTING	LUMP LUMP
428	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	760.000 LFT
429	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	22,871.000 LFT

CALL ORDER : 156

CONTRACT ID : IR-33291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	COMMON ITEMS		
430	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	20,508.000	LFT
431	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	3,260.000	LFT
432	808-10039 LINE, MULTI-COMPONENT, SOLID, WHITE, 12 IN	37.000	LFT
433	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	28.000	LFT
434	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	134.000	LFT
435	808-10059 LINE, MULTI-COMPONENT, SOLID, YELLOW, 12 IN	8.000	LFT
436	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	4.000	EACH
437	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	20.000	EACH
438	808-10078 LINE, MULTI-COMPONENT, DOTTED, WHITE,	180.000	LFT
439	808-11401 TRANSVERSE MARKING, PREFORMED PLASTIC,	53.000	LFT
440	808-11402 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN., 3 FT.	780.000	LFT
441	808-75061 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN	2,560.000	LFT
442	808-75510 TRANSVERSE MARKINGS, PREFORMED PLASTIC,	385.000	LFT
443	808-75510 TRANSVERSE MARKINGS, PREFORMED PLASTIC,	585.000	LFT
444	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	124.000	EACH
445	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	421.000	EACH