

CALL ORDER : 221

CONTRACT ID : IR-30853-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	113-01614 PARTNERING OVERHEAD	LUMP	LUMP
5	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
6	202-02271 HEADWALL, REMOVE	3.000	EACH
7	202-02272 PAVED SIDE DITCH, REMOVE	84.000	LFT
8	202-02273 CENTER CURB, CONCRETE, REMOVE	400.000	SYS
9	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE,	1.000	EACH
10	202-05824 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, 3000 THROUGH	1.000	EACH
11	202-06580 CONTAMINATED SOIL, REMOVE	100.000	CYS
12	202-07603 TESTING FOR WASTES, C	14.000	EACH
13	202-08192 UNDERGROUND STORAGE TANK, LIQUID WASTE DISPOSAL C	1,000.000	GAL
14	202-91385 INLET, REMOVE	3.000	EACH
15	202-93741 GUARDRAIL END TREATMENT, REMOVE	5.000	EACH
16	202-96133 PIPE, REMOVE	631.000	LFT
17	202-99187 FENCE, FARM FIELD, REMOVE	6,741.000	LFT
18	203-02000 EXCAVATION, COMMON	1,915.000	CYS
19	203-02010 EXCAVATION, ROCK	100.000	CYS
20	203-02055 EMBANKMENT	1,105,315.000	CYS
21	203-08607 LINEAR GRADING	300.000	LFT
22	205-03371 SEDIMENT, REMOVE	3,000.000	CYS
23	205-06930 SPLASHPAD	802.000	TON
24	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,820.000	TON
25	205-06933 TEMPORARY INLET PROTECTION	40.000	EACH
26	205-06936 TEMPORARY SEDIMENT TRAP	502.000	TON
27	205-06937 TEMPORARY SILT FENCE	19,126.000	LFT
28	205-06938 TEMPORARY SLOPE DRAIN	4,500.000	LFT
29	205-09543 NO 2 STONE	540.000	TON
30	206-51220 EXCAVATION, WET	105.000	CYS
31	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	562.000	CYS
32	207-08267 SUBGRADE TREATMENT, TYPE IIIA	625.000	SYS
33	207-09934 SUBGRADE TREATMENT, TYPE 1B	208,079.000	SYS
34	211-02050 B BORROW	4,692.000	CYS
35	211-06467 AGGREGATE FOR END BENT BACKFILL	118.000	CYS
36	211-09264 STRUCTURAL BACKFILL, TYPE 1	4,090.000	CYS
37	211-09265 STRUCTURAL BACKFILL, TYPE 2	10.000	CYS
38	211-09266 STRUCTURAL BACKFILL, TYPE 3	5,124.000	CYS
39	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,192.000	TON
40	302-07455 DENSE GRADED SUBBASE	168.000	CYS
41	303-01180 COMPACTED AGGREGATE, NO. 53	2,774.000	TON
42	306-08034 MILLING, ASPHALT, 1 1/2 IN	3,385.000	SYS
43	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	2,892.000	TON
44	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,087.000	TON
45	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1,829.000	TON
46	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	8,903.000	TON
47	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	1,275.000	TON
48	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	3,086.000	TON
49	401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 25.0 mm	1,319.000	TON

CALL ORDER : 221

CONTRACT ID : IR-30853-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
50	402-07432 HMA SURFACE, TYPE A	632.000	TON
51	402-07435 HMA INTERMEDIATE, TYPE A	689.000	TON
52	402-10087 HMA FOR TEMPORARY PAVEMENT, D	3,671.000	TON
53	406-05520 ASPHALT FOR TACK COAT	17.000	TON
54	601-01522 GUARDRAIL, TRANSITION TYPE TGB	19.000	EACH
55	601-02241 GUARDRAIL, REMOVE	1,817.000	LFT
56	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
57	601-94690 GUARDRAIL END TREATMENT, MS	7.000	EACH
58	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	4,353.750	LFT
59	601-99108 GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	1,743.750	LFT
60	602-06729 BARRIER DELINEATOR	56.000	EACH
61	603-06040 FENCE, FARM FIELD, 47 IN	13,600.000	LFT
62	603-92636 FENCE, CHAIN LINK, 72 IN	550.000	LFT
63	605-02278 CURB, REMOVE	1,689.000	LFT
64	605-06120 CURB, CONCRETE	588.000	LFT
65	605-06215 CENTER CURB, D, CONCRETE	3,561.000	LFT
66	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	976.000	SYS
67	610-07487 HMA FOR APPROACHES, TYPE B	310.000	TON
68	615-06490 RIGHT OF WAY MARKER	71.000	EACH
69	615-06505 MONUMENT, B	9.000	EACH
70	615-06510 MONUMENT, C	21.000	EACH
71	616-02320 GEOTEXTILES	9,459.100	SYS
72	616-05689 RIPRAP, CLASS 2	310.000	TON
73	616-06405 RIPRAP, REVETMENT	4,855.800	TON
74	616-06451 RIPRAP, UNIFORM	61.000	TON
75	616-51367 SLOPEWALL, CONCRETE, 4 IN	1,440.000	SYS
76	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.000	EACH
77	621-02770 EROSION CONTROL BLANKET	2,170.000	SYS
78	621-06545 FERTILIZER	59.000	TON
79	621-06553 SEED MIXTURE, R	22,270.000	LBS
80	621-06557 SEED MIXTURE, T	5,240.000	LBS
81	621-06565 MULCHING MATERIAL	393.000	TON
82	621-06567 WATER	95.000	KGAL
83	621-06574 SODDING	23,631.800	SYS
84	701-06011 DYNAMIC PILE LOAD TEST	10.000	EACH
85	701-09557 TEST PILE, DYNAMIC, PRODUCTION	413.000	LFT
86	701-09559 TEST PILE, DYNAMIC, RESTRIKE	10.000	EACH
87	701-09739 PILE SHOE, HP 12 X 53	64.000	EACH
88	701-09891 PILE SHOE, 12 X 84, HP	56.000	EACH
89	701-51195 PILE, STEEL H, HP 12 IN X 53	1,874.000	LFT
90	701-95782 PILE, STEEL H, HP 12 X 84	1,188.000	LFT
91	702-51005 CONCRETE, A, SUBSTRUCTURE	533.100	CYS
92	702-51015 CONCRETE, B, FOOTINGS	328.400	CYS
93	702-92857 CONCRETE, C, SUBSTRUCTURE	139.700	CYS
94	703-06028 REINFORCING BARS	125,920.000	LBS
95	703-06029 REINFORCING BARS, EPOXY COATED	482,719.000	LBS
96	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,200.400	CYS
97	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	16.000	EACH
98	706-51020 RAILING, CONCRETE, C	153.000	CYS

CALL ORDER : 221

CONTRACT ID : IR-30853-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
99	707-09634 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 48 IN X 49 IN	2,380.000	LFT
100	707-09865 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 36 IN X 49 IN	1,580.000	LFT
101	709-51821 SURFACE SEAL	LUMP	LUMP
102	714-11177 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	558.000	LFT
103	714-11183 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	320.000	LFT
104	714-11188 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	588.000	LFT
105	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	1,000.000	LFT
106	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	66,165.000	LFT
107	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	1,000.000	LFT
108	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	9,320.000	LFT
109	715-05118 PIPE, TYPE 1 CIRCULAR 12 IN	1,000.000	LFT
110	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	1,000.000	LFT
111	715-05128 PIPE, TYPE 1 CIRCULAR 48 IN	260.000	LFT
112	715-05136 PIPE, TYPE 1 CIRCULAR 72 IN	486.000	LFT
113	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,507.000	LFT
114	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	2,059.000	LFT
115	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	139.000	LFT
116	715-05212 PIPE, TYPE 4 CIRCULAR 24 IN	1,000.000	LFT
117	715-05233 PIPE, TYPE 1 DEFORMED MIN AREA 3.3 SF	71.000	LFT
118	715-05252 PIPE, TYPE 1 DEFORMED MIN AREA 20.5 SF	182.000	LFT
119	715-05407 PIPE, END BENT DRAIN, 6 IN	240.000	LFT
120	715-08171 PIPE, TYPE 1 DEFORMED MIN AREA 12.9 SF	292.000	LFT
121	715-09064 VIDEO INSPECTION FOR PIPE	4,992.000	LFT
122	715-09446 PIPE, TYPE 4 CIRCULAR 36 IN	1,000.000	LFT
123	715-46000 PIPE END SECTION, DIA 12"	17.000	EACH
124	715-46005 PIPE END SECTION, DIA 15"	29.000	EACH
125	718-06528 OUTLET PROTECTOR, 1	223.000	EACH
126	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	6,500.000	LFT
127	718-52610 AGGREGATE FOR UNDERDRAINS	5,955.000	CYS
128	718-99153 GEOTEXTILES FOR UNDERDRAIN	56,042.000	SYS
129	719-05443 PIPE, DRAIN TILE TERMINAL SECTION, 12 IN	100.000	LFT
130	719-09447 PIPE, DRAIN TILE TERMINAL SECTION, 24 IN	100.000	LFT
131	719-09448 PIPE, DRAIN TILE, TERMINAL SECTION, 36 IN	100.000	LFT
132	720-45065 INLET, N12	40.000	EACH
133	731-93945 FACE PANELS, CONCRETE	10,284.000	SFT
134	731-93946 WALL ERECTION	10,284.000	SFT
135	731-93947 LEVELING PAD, CONCRETE	735.000	LFT
136	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	17,550.000	LFT
137	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	25,017.000	LFT
138	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	133.000	LFT
139	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
140	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
141	801-07118 BARRICADE, III-A	72.000	LFT
142	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	3,843.000	LFT
143	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	450.000	LFT
144	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
145	802-03811 OVERHEAD SIGN STRUCTURE, BOX TRUSS	2.000	EACH
146	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	755.000	LFT
147	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	147.000	LFT

CALL ORDER : 221

CONTRACT ID : IR-30853-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
148	802-05703 SIGN POST, SQUARE, TYPE 3, REINFORCED ANCHOR BASE	27.000	LFT
149	802-07057 SIGN, PANEL, WITH LEGEND	3,036.500	SFT
150	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	42.000	EACH
151	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	10.000	EACH
152	802-07154 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XII	8.000	EACH
153	802-08456 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	4.000	EACH
154	802-09710 BOX TRUSS SIGN STRUCTURE FOUNDATION 36 IN HEIGHT	8.000	EACH
155	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	472.000	SFT
156	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	366.250	SFT
157	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	48.000	SFT
158	802-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	2.000	EACH
159	802-74050 SIGN, OVERHEAD, REMOVE	7.000	EACH
160	802-74055 OVERHEAD SIGN STRUCTURE BOX TRUSS, REMOVE	3.000	EACH
161	802-76095 STRUCTURAL STEEL, BREAKAWAY	7,436.000	LBS
162	802-76160 BRIDGE BRACKET ASSEMBLY	4.000	EACH
163	804-06770 DELINEATOR POST	140.000	EACH
164	805-06595 CONDUIT, PVC, 2 IN	850.000	LFT
165	805-09281 WIM STATION, QUARTZ	LUMP	LUMP
166	807-04651 WIRE,	475.000	LFT
167	807-04651 WIRE,	475.000	LFT
168	807-04652 SERVICE POINT	1.000	EACH
169	807-78590 HANDHOLE	5.000	EACH
170	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5,298.000	LFT
171	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	251.000	LFT
172	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	998.000	LFT
173	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	998.000	LFT
174	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	5,190.000	LFT
175	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	91.000	EACH
176	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
177	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	571.000	EACH
SECTION NO. 0002 NEW ROAD CONSTRUCTION			
178	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	12,272.000	TON
179	303-01180 COMPACTED AGGREGATE, NO. 53	23,293.000	TON
180	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
181	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	615.000	TON
182	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	10,651.000	TON
183	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1,035.000	TON
184	401-07399 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	17,909.000	TON
185	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	2,454.000	TON
186	401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 25.0 mm	19,193.000	TON
187	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	42,535.000	TON
188	406-05520 ASPHALT FOR TACK COAT	129.000	TON
189	615-06505 MONUMENT, B	25.000	EACH
190	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	8,844.000	LFT
191	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	44,149.000	LFT
192	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	1,747.000	LFT
193	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	37,181.000	LFT

CALL ORDER : 221

CONTRACT ID : IR-30853-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 NEW ROAD CONSTRUCTION			
194	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	1,210.000	LFT
195	808-75290 TRANSVERSE MARKING, THERMOPLASTIC,	279.000	LFT
196	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	42.000	LFT
197	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	29.000	EACH
198	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	14.000	EACH
199	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	2,014.000	LFT
SECTION NO. 0003 NEW ROAD CONSTRUCTION			
200	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	8,145.000	TON
201	302-06464 SUBBASE FOR PCCP	33,993.000	CYS
202	303-01180 COMPACTED AGGREGATE, NO. 53	17,993.000	TON
203	501-03489 TIE BAR, RETROFIT	80.000	EACH
204	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
205	501-06321 QC/QA-PCCP, 10 IN	26,905.000	SYS
206	501-08193 QC/QA-PCCP, 10.5 IN	96,167.000	SYS
207	501-09749 QC/QA PCCP, 9.5"	12,560.000	SYS
208	503-05240 D-1 CONTRACTION JOINT	76,272.000	LFT
209	503-05310 TERMINAL JOINT	127.000	LFT
210	615-06515 MONUMENT, D	25.000	EACH
211	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	44,149.000	LFT
212	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	37,181.000	LFT
213	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	1,747.000	LFT
214	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	9,440.000	LFT
215	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	2,014.000	LFT
216	808-74812 TRANSVERSE MARKING, PREFORMED PLASTIC, SOLID, YELLOW	1,210.000	LFT
217	808-75067 TRANSVERSE MARKING, PREFORMED PLASTIC,	42.000	LFT
218	808-75071 PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC,	29.000	EACH
219	808-75073 PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC,	14.000	EACH
220	808-75510 TRANSVERSE MARKINGS, PREFORMED PLASTIC,	279.000	LFT

CALL ORDER : 251

CONTRACT ID : IR-34266-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENVIRONMENTAL MITIGATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
8	202-99187 FENCE, FARM FIELD, REMOVE	1,450.000	LFT
9	203-02000 EXCAVATION, COMMON	7,590.000	CYS
10	203-04523 DEWATERING	LUMP	LUMP
11	204-08553 DATA LOGGING SYSTEM	2.000	EACH
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	2.500	TON
13	205-06934 TEMPORARY MULCH	12.500	TON
14	205-06937 TEMPORARY SILT FENCE	4,600.000	LFT
15	205-08517 ROCK FILTER BERM	13.400	TON
16	205-09543 NO 2 STONE	350.000	TON
17	303-07662 STONE	16.100	TON
18	616-02320 GEOTEXTILES	1,830.000	SYS
19	616-06405 RIPRAP, REVETMENT	1,139.000	TON
20	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.000	EACH
21	621-02770 EROSION CONTROL BLANKET	14,500.000	SYS
22	621-04258 SEED MIXTURE	252.300	LBS
23	621-04258 SEED MIXTURE	372.300	LBS
24	621-04258 SEED MIXTURE	3,749.600	LBS
25	621-06545 FERTILIZER	40.940	TON
26	621-06557 SEED MIXTURE, T	750.000	LBS
27	621-06565 MULCHING MATERIAL	47.800	TON
28	621-06737 SEED MIXTURE, EMERGENT WETLAND	408.300	LBS
29	622-01937 PLANT	7,641.000	EACH
30	622-52436 SIGN, DO NOT MOW OR SPRAY	44.000	EACH
31	622-91786 SEEDLING	18,448.000	EACH
32	622-91786 SEEDLING	73,952.000	EACH
33	622-98200 SIGN, DO NOT DISTURB	43.000	EACH
34	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
35	628-09403 FIELD OFFICE, C	12.000	MOS
36	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
37	628-11069 CELLULAR TELEPHONE/RADIO SERVICE, ANYTIME MINUTES	12.000	MOS
38	712-04784 STRUCTURE	2.000	EACH
39	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	76.000	LFT
40	804-06770 DELINEATOR POST	215.000	EACH

CALL ORDER : 281

CONTRACT ID : R -30261-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	336.000	SYS
11	202-02272 PAVED SIDE DITCH, REMOVE	240.000	LFT
12	202-02279 CURB AND GUTTER, REMOVE	260.000	LFT
13	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
14	203-02000 EXCAVATION, COMMON	9,693.000	CYS
15	203-02070 BORROW	16,778.000	CYS
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	70.000	TON
17	205-06933 TEMPORARY INLET PROTECTION	26.000	EACH
18	205-06937 TEMPORARY SILT FENCE	980.000	LFT
19	207-08262 SUBGRADE TREATMENT, TYPE I	17,731.000	SYS
20	207-08267 SUBGRADE TREATMENT, TYPE IIIA	754.000	SYS
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,399.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,728.000	TON
23	303-07449 COMPACTED AGGREGATE, NO. 73	213.000	TON
24	306-08034 MILLING, ASPHALT, 1 1/2 IN	400.000	SYS
25	306-08043 MILLING, TRANSITION	435.000	SYS
26	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
27	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,469.000	TON
28	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2,444.000	TON
29	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	4,721.000	TON
30	402-07433 HMA SURFACE, TYPE B	433.000	TON
31	402-07441 HMA BASE, TYPE B	1,370.000	TON
32	402-07451 HMA WEDGE AND LEVEL, TYPE B	572.000	TON
33	406-05520 ASPHALT FOR TACK COAT	13.000	TON
34	603-06045 FENCE, CHAIN LINK, 48 IN	590.000	LFT
35	604-06070 SIDEWALK, CONCRETE	2,128.000	SYS
36	604-07901 CURB RAMP, CONCRETE, G	57.000	SYS
37	605-06120 CURB, CONCRETE	220.000	LFT
38	605-52807 CURB AND GUTTER, COMBINED	3,220.000	LFT
39	610-07487 HMA FOR APPROACHES, TYPE B	330.000	TON
40	610-09108 PCCP FOR APPROACHES, 9 IN	280.000	SYS
41	615-06505 MONUMENT, B	4.000	EACH
42	615-06510 MONUMENT, C	2.000	EACH
43	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
44	616-02320 GEOTEXTILES	665.000	SYS
45	616-06405 RIPRAP, REVETMENT	391.000	TON
46	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
47	621-02770 EROSION CONTROL BLANKET	15,570.000	SYS
48	621-06545 FERTILIZER	2.700	TON
49	621-06553 SEED MIXTURE, R	1,109.000	LBS

CALL ORDER : 281

CONTRACT ID : R -30261-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
50	621-06557 SEED MIXTURE, T	490.000	LBS
51	621-06565 MULCHING MATERIAL	13.100	TON
52	621-06567 WATER	8.150	KGAL
53	621-06574 SODDING	2,082.000	SYS
54	621-06575 SODDING, NURSERY	180.000	SYS
55	622-52436 SIGN, DO NOT MOW OR SPRAY	6.000	EACH
56	622-91786 SEEDLING	310.000	EACH
57	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
58	628-09402 FIELD OFFICE, B	18.000	MOS
59	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	36.000	MOS
60	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	36.000	MOS
61	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
62	715-03584 SAFETY METAL END SECTION 4:1 DIA 18"	2.000	EACH
63	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	265.000	LFT
64	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	63.000	LFT
65	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	805.000	LFT
66	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	753.000	LFT
67	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	190.000	LFT
68	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	790.000	LFT
69	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	555.000	LFT
70	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	106.000	LFT
71	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	1,430.000	LFT
72	715-05212 PIPE, TYPE 4 CIRCULAR 24 IN	110.000	LFT
73	715-06802 CONCRETE ANCHOR, 18.1 SFT	2.000	EACH
74	715-07270 PIPE, TYPE 1 DEFORMED MIN AREA 18.1 SF	94.000	LFT
75	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	181.000	TON
76	715-10166 PIPE, TYPE 1, DEFORMED, MIN AREA 37 SFT	186.000	LFT
77	715-10167 CONCRETE ANCHOR, MIN AREA 37 SFT	2.000	EACH
78	715-46000 PIPE END SECTION, DIA 12"	3.000	EACH
79	715-46005 PIPE END SECTION, DIA 15"	6.000	EACH
80	715-46020 PIPE END SECTION, DIA 24"	1.000	EACH
81	715-46030 PIPE END SECTION, DIA 30"	1.000	EACH
82	718-52610 AGGREGATE FOR UNDERDRAINS	239.000	CYS
83	720-01092 MANHOLE, J15, MODIFIED	8.000	EACH
84	720-45030 INLET, E7	5.000	EACH
85	720-45035 INLET, F7	2.000	EACH
86	720-45055 INLET, M10	1.000	EACH
87	720-45270 PIPE CATCH BASIN, 18 IN	1.000	EACH
88	720-45410 MANHOLE, C4	4.000	EACH
89	720-95422 MANHOLE, J4	4.000	EACH
90	720-98174 INLET, B15	6.000	EACH
91	720-98555 INLET, C15	3.000	EACH
92	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
93	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
94	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	32,380.000	LFT
95	801-06625 DETOUR ROUTE MARKER ASSEMBLY	46.000	EACH
96	801-06640 CONSTRUCTION SIGN, A	27.000	EACH
97	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
98	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 281

CONTRACT ID : R -30261-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
99	801-07119 BARRICADE, III-B	180.000	LFT
100	802-02475 SIGN, PANEL, RELOCATE	1.000	EACH
101	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	21.300	LFT
102	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	2.000	EACH
103	802-09837 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.080 IN THICKNESS	4.000	SFT
104	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	104.130	SFT
105	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	38.000	SFT
106	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	84.000	SFT
107	802-76055 SIGN POST, A	334.000	LFT
108	802-76095 STRUCTURAL STEEL, BREAKAWAY	409.000	LBS
109	807-02191 HANDHOLE, LIGHTING	2.000	EACH
110	807-02428 LIGHTING FOUNDATION, CONCRETE, WITH GROUND	11.000	EACH
111	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	450.000	LFT
112	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	3,376.000	LFT
113	807-83644 LIGHT POLE, 36 FT E.M.H., 8.0 FT MAST ARM, ANCHOR BASE	10.000	EACH
114	807-84660 LIGHT POLE, ROADWAY, 36 FT E.M.H., 16.0 FT MAST ARM,	1.000	EACH
115	807-86615 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	11.000	EACH
116	807-86805 SERVICE POINT, I	2.000	EACH
117	807-86889 CABLE, POLE CIRCUIT THWH, NO10 COPPER, STRANDED, 1/C	1,650.000	LFT
118	807-86910 CONNECTOR KIT, UNFUSED	11.000	EACH
119	807-86915 CONNECTOR KIT, FUSED	11.000	EACH
120	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	27.000	EACH
121	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	18.000	EACH
122	807-86930 INSULATION LINK, NON-WATERPROOFED	22.000	EACH
123	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8,492.000	LFT
124	808-06716 LINE, REMOVE	15,930.000	LFT
125	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	5,721.000	LFT
126	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	959.000	LFT
127	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	58.000	LFT
128	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	6.000	EACH
129	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	6.000	EACH
130	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	2,982.000	LFT

CALL ORDER : 291

CONTRACT ID : R -30422-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02278 CURB, CONCRETE, REMOVE	100.000	LFT
11	202-52710 SIDEWALK, CONCRETE, REMOVE	812.000	SYS
12	202-90277 DETECTOR HOUSING, REMOVE	37.000	EACH
13	303-07449 COMPACTED AGGREGATE, NO. 73	2,000.000	TON
14	304-07491 HMA PATCHING, TYPE C	190.000	TON
15	306-08034 MILLING, ASPHALT, 1 1/2 IN	230,646.000	SYS
16	306-08043 MILLING, TRANSITION	3,200.000	SYS
17	306-08432 MILLING, APPROACH	4,750.000	SYS
18	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
19	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	19,100.000	TON
20	406-05520 ASPHALT FOR TACK COAT	60.000	TON
21	604-07894 CURB RAMP, CONCRETE, A	285.000	SYS
22	604-07896 CURB RAMP, CONCRETE, B	90.000	SYS
23	604-07897 CURB RAMP, CONCRETE, C	74.000	SYS
24	604-07899 CURB RAMP, CONCRETE, E	47.000	SYS
25	604-07900 CURB RAMP, CONCRETE, F	63.000	SYS
26	604-07901 CURB RAMP, CONCRETE, G	216.000	SYS
27	604-07902 CURB RAMP, CONCRETE, H	28.000	SYS
28	604-07903 CURB RAMP, CONCRETE, K	10.000	SYS
29	605-06120 CURB, CONCRETE	100.000	LFT
30	610-07488 HMA FOR APPROACHES, TYPE C	280.000	TON
31	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	21.000	TON
32	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	2.000	EACH
33	612-60410 DRILLED HOLE FOR UNDERSEAL	388.000	EACH
34	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	27.000	EACH
35	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
36	628-09402 FIELD OFFICE, B	6.000	MOS
37	628-11007 CELLULAR TELEPHONE/RADIO SERVICE, 750 MINUTES	1.000	MOS
38	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
39	720-44000 CASTING, ADJUST TO GRADE	17.000	EACH
40	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	48.000	EACH
41	801-01505 TEMPORARY PAVEMENT MESSAGE MARKING, (ONLY)	46.000	EACH
42	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
43	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	7,000.000	LFT
44	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	7,000.000	LFT
45	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	48.000	EACH
46	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	46.000	EACH
47	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	1,400.000	LFT
48	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	1,400.000	LFT
49	801-06640 CONSTRUCTION SIGN, A	85.000	EACH

CALL ORDER : 291

CONTRACT ID : R -30422-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	801-06710 FLASHING ARROW SIGN	60.000	DAY
51	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
52	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	18,500.000	LFT
53	805-78785 SIGNAL DETECTOR HOUSING	37.000	EACH
54	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	5,920.000	LFT
55	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	2.000	EACH
56	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	1,200.000	LFT
57	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	117,000.000	LFT
58	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	950.000	LFT
59	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
60	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	13,700.000	LFT
61	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	28,700.000	LFT
62	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	1,300.000	LFT
63	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	1,400.000	LFT
64	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	3,300.000	LFT
65	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	48.000	EACH
66	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	46.000	EACH
67	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	750.000	EACH
68	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	740.000	EACH
69	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	10.000	EACH
70	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	2,000.000	LFT

CALL ORDER : 301

CONTRACT ID : R -31877-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	3,665.000	CYS
12	203-02070 BORROW	2,461.000	CYS
13	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	110.000	TON
14	205-06933 TEMPORARY INLET PROTECTION	2.000	EACH
15	205-06937 TEMPORARY SILT FENCE	2,160.000	LFT
16	205-09543 NO 2 STONE	100.000	TON
17	207-08263 SUBGRADE TREATMENT, TYPE IA	12,846.000	SYS
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,377.000	SYS
19	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,224.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,907.000	TON
21	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,595.000	SYS
22	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	942.000	TON
23	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,451.000	TON
24	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	1,982.000	TON
25	402-07432 HMA SURFACE, TYPE A	58.000	TON
26	402-07435 HMA INTERMEDIATE, TYPE A	97.000	TON
27	406-05520 ASPHALT FOR TACK COAT	7.400	TON
28	502-11564 PCCP, 7 IN	491.800	SYS
29	503-05240 D-1 CONTRACTION JOINT	279.300	LFT
30	604-07092 BED COURSE MATERIAL	235.000	TON
31	604-07897 CURB RAMP, CONCRETE, C	13.000	SYS
32	604-07904 CURB RAMP, CONCRETE, L	43.000	SYS
33	604-91531 SIDEWALK, CONCRETE, 4 IN	53.000	SYS
34	605-06120 CURB, CONCRETE	2,190.000	LFT
35	605-06121 CURB, CONCRETE, B	378.000	LFT
36	605-06245 CENTER CURB, B, CONCRETE	39.000	SYS
37	605-06255 CENTER CURB, D, CONCRETE	15.000	SYS
38	605-52807 CURB AND GUTTER, COMBINED	2,237.000	LFT
39	610-07487 HMA FOR APPROACHES, TYPE B	67.400	TON
40	610-08446 PCCP FOR APPROACHES, 6 IN	312.800	SYS
41	610-09108 PCCP FOR APPROACHES, 9 IN	277.700	SYS
42	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
43	615-06490 RIGHT OF WAY MARKER	16.000	EACH
44	615-06505 MONUMENT, B	1.000	EACH
45	615-06510 MONUMENT, C	1.000	EACH
46	616-02320 GEOTEXTILES	137.000	SYS
47	616-06405 RIPRAP, REVETMENT	4.000	TON
48	616-06451 RIPRAP, UNIFORM	99.000	TON
49	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH

CALL ORDER : 301

CONTRACT ID : R -31877-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
50	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	5,000.000	SYS
51	621-06545 FERTILIZER	1.000	TON
52	621-06554 SEED MIXTURE, U	383.000	LBS
53	621-06565 MULCHING MATERIAL	5.100	TON
54	621-06567 WATER	11.700	KGAL
55	621-06570 TOPSOIL	111.000	CYS
56	621-06574 SODDING	174.000	SYS
57	621-06575 SODDING, NURSERY	3,077.000	SYS
58	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN OR UNDER	22.000	EACH
59	622-05654 PLANT, PERENNIAL	535.000	EACH
60	622-07764 IRRIGATION SYSTEM	LUMP	LUMP
61	628-09402 FIELD OFFICE, B	8.000	MOS
62	715-04855 PIPE END SECTION DIA 42"	1.000	EACH
63	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	289.000	LFT
64	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	358.000	LFT
65	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	505.000	LFT
66	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	774.000	LFT
67	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	635.000	LFT
68	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	735.000	LFT
69	715-05159 PIPE, TYPE 2 CIRCULAR 42 IN	236.000	LFT
70	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	68.000	LFT
71	715-05173 PIPE, TYPE 3 CIRCULAR 24 IN	94.000	LFT
72	715-05174 PIPE TYPE 3 CIRCULAR 27 IN	40.000	LFT
73	715-05175 PIPE, TYPE 3 CIRCULAR 30 IN	50.000	LFT
74	715-09064 VIDEO INSPECTION FOR PIPE	3,150.000	LFT
75	715-46005 PIPE END SECTION, DIA 15"	10.000	EACH
76	715-46020 PIPE END SECTION, DIA 24"	3.000	EACH
77	715-46030 PIPE END SECTION, DIA 30"	2.000	EACH
78	720-45030 INLET, E7	1.000	EACH
79	720-45035 INLET, F7	2.000	EACH
80	720-45410 MANHOLE, C4	4.000	EACH
81	720-45415 MANHOLE, D4	7.000	EACH
82	720-98174 INLET, B15	6.000	EACH
83	720-98555 INLET, C15	12.000	EACH
84	801-03290 CONSTRUCTION SIGN, C	25.000	EACH
85	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
86	801-06625 DETOUR ROUTE MARKER ASSEMBLY	35.000	EACH
87	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
88	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
89	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
90	801-07119 BARRICADE, III-B	96.000	LFT
91	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	327.500	LFT
92	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	72.000	LFT
93	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	6.000	EACH
94	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
95	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	94.000	SFT
96	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	94.000	SFT
97	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	19.500	SFT
98	807-03965 CONDUIT, PVC, 2.50 IN, SCHEDULE 80, FOR ELECTRIC	250.000	LFT

CALL ORDER : 301

CONTRACT ID : R -31877-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
99	808-03439 TRANSVERSE MARKING THERMOPLASTIC	200.000	LFT
100	808-05878 YIELD LINE TRIANGLE, THERMOPLASTIC	53.000	EACH
101	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,878.000	LFT
102	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	222.000	LFT
103	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
104	808-11478 LINE, THERMOPLASTIC, DOTTED, WHITE 8 IN	68.000	LFT
105	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	4,392.000	LFT
106	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	477.000	LFT
107	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	9.000	EACH

CALL ORDER : 311

CONTRACT ID : R -31930-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SLIDE CORRECTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	205-06937 TEMPORARY SILT FENCE	300.000	LFT
9	216-06397 WIRE MESH	295.000	SYS
10	615-06490 RIGHT OF WAY MARKER	3.000	EACH
11	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
12	621-06559 MULCHED SEEDING, R	300.000	SYS
13	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
14	628-09402 FIELD OFFICE, B	9.000	MOS
15	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	18.000	MOS
16	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
17	731-06223 SOIL NAILED WALL	200.000	SYS
18	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
20	801-08646 MAINTAINING TRAFFIC	1.000	EACH

CALL ORDER : 315

CONTRACT ID : R -31931-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BIKE/PEDESTRIAN FACILITIES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02279 CURB AND GUTTER, REMOVE	50.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	64.000	SYS
11	202-94747 POST, REMOVE	1.000	EACH
12	203-02000 EXCAVATION, COMMON	89.000	CYS
13	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	7.000	TON
14	604-02007 SIDEWALK, CONCRETE, RECONSTRUCT	64.000	SYS
15	604-06070 SIDEWALK, CONCRETE	600.000	SYS
16	604-07897 CURB RAMP, CONCRETE, C	95.000	SYS
17	604-07899 CURB RAMP, CONCRETE, E	102.000	SYS
18	604-07902 CURB RAMP, CONCRETE, H	28.000	SYS
19	604-07903 CURB RAMP, CONCRETE, K	9.000	SYS
20	605-06120 CURB, CONCRETE	803.000	LFT
21	621-06574 SODDING	311.000	SYS
22	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
23	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
24	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
25	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	12.000	MOS
26	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	802-02475 SIGN, PANEL, RELOCATE	1.000	EACH
29	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	195.000	LFT
30	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	95.000	SFT
31	808-75060 TRANSVERSE MARKING, PAINT,	1,885.000	LFT

CALL ORDER : 321

CONTRACT ID : R -32726-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02278 CURB, CONCRETE, REMOVE	560.000	LFT
11	202-02772 CASTING, REMOVE	1.000	EACH
12	202-52710 SIDEWALK, CONCRETE, REMOVE	374.000	SYS
13	202-93741 GUARDRAIL END TREATMENT, REMOVE	2.000	EACH
14	203-08607 LINEAR GRADING	100.000	LFT
15	303-01180 COMPACTED AGGREGATE, NO. 53	45.000	TON
16	303-07449 COMPACTED AGGREGATE, NO. 73	95.000	TON
17	304-07491 HMA PATCHING, TYPE C	257.000	TON
18	306-08034 MILLING, ASPHALT, 1 1/2 IN	32,306.000	SYS
19	306-08043 MILLING, TRANSITION	439.000	SYS
20	306-08432 MILLING, APPROACH	5,962.000	SYS
21	401-07347 QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	3,555.000	TON
22	406-05520 ASPHALT FOR TACK COAT	8.200	TON
23	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
24	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
25	604-06070 SIDEWALK, CONCRETE	188.000	SYS
26	604-07897 CURB RAMP, CONCRETE, C	164.500	SYS
27	604-07899 CURB RAMP, CONCRETE, E	42.800	SYS
28	604-07900 CURB RAMP, CONCRETE, F	28.600	SYS
29	604-07901 CURB RAMP, CONCRETE, G	9.800	SYS
30	604-07902 CURB RAMP, CONCRETE, H	6.300	SYS
31	605-06120 CURB, CONCRETE	280.000	LFT
32	610-07488 HMA FOR APPROACHES, TYPE C	657.000	TON
33	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	4.500	TON
34	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
35	612-60410 DRILLED HOLE FOR UNDERSEAL	80.000	EACH
36	615-06520 MONUMENT, RE-ESTABLISH	1.000	EACH
37	621-06574 SODDING	623.000	SYS
38	628-09403 FIELD OFFICE, C	5.000	MOS
39	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
40	720-44000 CASTING, ADJUST TO GRADE	93.000	EACH
41	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
42	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	1,729.000	LFT
43	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,729.000	LFT
44	801-06640 CONSTRUCTION SIGN, A	44.000	EACH
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	808-05929 TRANSVERSE MARKING THERMOPLASTIC,	3,322.000	LFT
47	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,993.000	LFT
48	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	2,010.000	LFT
49	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	3,877.000	LFT

CALL ORDER : 321

CONTRACT ID : R -32726-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	38.000	LFT
51 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	159.000	EACH

CALL ORDER : 331

CONTRACT ID : R -32767-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION - COMMON ITEMS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	113-01614 PARTNERING OVERHEAD	LUMP	LUMP
3	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
4	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
5	202-93615 CONCRETE, REMOVE	41.000	SYS
6	205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE	2.000	EACH
7	205-03371 SEDIMENT, REMOVE	144.000	CYS
8	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	190.000	TON
9	205-06933 TEMPORARY INLET PROTECTION	24.000	EACH
10	205-06936 TEMPORARY SEDIMENT TRAP	30.000	TON
11	205-06937 TEMPORARY SILT FENCE	4,111.000	LFT
12	207-08263 SUBGRADE TREATMENT, TYPE IA	46,153.000	SYS
13	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,473.000	SYS
14	211-09264 STRUCTURAL BACKFILL, TYPE 1	6,132.000	CYS
15	211-09264 STRUCTURAL BACKFILL, TYPE 1	236.000	CYS
16	303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS	100.000	TON
17	402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE	699.000	TON
18	610-07487 HMA FOR APPROACHES, TYPE B	667.000	TON
19	610-08446 PCCP FOR APPROACHES, 6 IN	41.000	SYS
20	610-09108 PCCP FOR APPROACHES, 9 IN	941.000	SYS
21	611-06497 MAILBOX ASSEMBLY, SINGLE	9.000	EACH
22	614-06480 HEADER, CEMENT CONCRETE, C	28.000	LFT
23	614-06482 HEADER, CEMENT CONCRETE, D	56.000	LFT
24	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
25	616-02320 GEOTEXTILES	79.000	SYS
26	616-06405 RIPRAP, REVETMENT	43.000	TON
27	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
28	621-06545 FERTILIZER	8.000	TON
29	621-06553 SEED MIXTURE, R	3,263.000	LBS
30	621-06557 SEED MIXTURE, T	3,017.000	LBS
31	621-06565 MULCHING MATERIAL	80.000	TON
32	621-06567 WATER	2.000	KGAL
33	621-06575 SODDING, NURSERY	4,456.000	SYS
34	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
35	621-90853 TAPPING SLEEVE WITH VALVE	2.000	EACH
36	628-09402 FIELD OFFICE, B	15.000	MOS
37	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	15.000	MOS
38	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	15.000	MOS
39	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
40	715-01336 GATE VALVE, 12 IN	1.000	EACH
41	715-01898 WATER MAIN, DUCTILE IRON, 10 IN	218.000	LFT
42	715-04836 GATE VALVE	1.000	EACH
43	715-04995 LINE STOP	2.000	EACH
44	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	492.000	LFT
45	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	20,916.000	LFT
46	715-05049 PIPE, TYPE 4 CIRCULAR 8 IN	100.000	LFT
47	715-05051 PIPE, TYPE 4 CIRCULAR 10 IN	100.000	LFT
48	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	100.000	LFT
49	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	1,033.000	LFT

CALL ORDER : 331

CONTRACT ID : R -32767-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION - COMMON ITEMS		
50	715-05129 PIPE, TYPE 1 CIRCULAR 54 IN	84.000	LFT
51	715-05148 PIPE, TYPE 2 CIRCULAR 10 IN	26.000	LFT
52	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	331.000	LFT
53	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	683.000	LFT
54	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	221.000	LFT
55	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	1,248.000	LFT
56	715-05155 PIPE, TYPE 2 CIRCULAR 27 IN	454.000	LFT
57	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	466.000	LFT
58	715-05159 PIPE, TYPE 2 CIRCULAR 42 IN	750.000	LFT
59	715-05161 PIPE, TYPE 2 CIRCULAR 48 IN	1,446.000	LFT
60	715-05162 PIPE, TYPE 2 CIRCULAR 54 IN	2,986.000	LFT
61	715-05168 PIPE, TYPE 3 CIRCULAR 12 IN	343.000	LFT
62	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	513.000	LFT
63	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	100.000	LFT
64	715-05212 PIPE, TYPE 4 CIRCULAR 24 IN	54.000	LFT
65	715-05228 PIPE, TYPE 1 DEFORMED MIN AREA 1.6 SF	130.000	LFT
66	715-05244 PIPE, TYPE 1 DEFORMED MIN AREA 11.6 SF	49.000	LFT
67	715-06492 CONCRETE ANCHOR, 54 IN	3.000	EACH
68	715-07107 PIPE END SECTION, MIN AREA 11.6 SFT	2.000	EACH
69	715-07794 WATER MAIN CONNECTIONS	1.000	EACH
70	715-07794 WATER MAIN CONNECTIONS	2.000	EACH
71	715-07806 PIPE STEEL CASING	20.000	LFT
72	715-46000 PIPE END SECTION, DIA 12"	13.000	EACH
73	715-46005 PIPE END SECTION, DIA 15"	16.000	EACH
74	715-46010 PIPE END SECTION, DIA 18"	3.000	EACH
75	715-46020 PIPE END SECTION, DIA 24"	3.000	EACH
76	715-46025 PIPE END SECTION, DIA 27"	1.000	EACH
77	715-46030 PIPE END SECTION, DIA 30"	1.000	EACH
78	715-46050 PIPE END SECTION, MIN AREA 1.6 SFT	1.000	EACH
79	715-90836 PIPE END SECTION, DIA 8"	2.000	EACH
80	715-92543 WATER MAIN, 8 IN, RELOCATE	65.000	LFT
81	715-92544 WATER MAIN, DUCTILE IRON, 12 IN	105.000	LFT
82	715-93912 WATER MAIN, 6 IN	25.000	LFT
83	718-06528 OUTLET PROTECTOR, 1	17.000	EACH
84	718-06529 OUTLET PROTECTOR, 2	17.000	EACH
85	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
86	718-52610 AGGREGATE FOR UNDERDRAINS	1,872.000	CYS
87	718-99153 GEOTEXTILES FOR UNDERDRAIN	18,711.000	SYS
88	719-05438 PIPE, DRAIN TILE TERMINAL SECTION, 4 IN	10.000	LFT
89	719-05439 PIPE, DRAIN TILE TERMINAL SECTION, 6 IN	10.000	LFT
90	719-05440 PIPE, DRAIN TILE TERMINAL SECTION, 8 IN	10.000	LFT
91	719-05442 PIPE, DRAIN TILE TERMINAL SECTION, 10 IN	10.000	LFT
92	719-05443 PIPE, DRAIN TILE TERMINAL SECTION, 12 IN	10.000	LFT
93	720-45030 INLET, E7	17.000	EACH
94	720-45035 INLET, F7	2.000	EACH
95	720-45040 INLET, G7	5.000	EACH
96	720-45410 MANHOLE, C4	4.000	EACH
97	720-90579 HYDRANT SETTING, RELOCATE	2.000	EACH
98	720-90579 HYDRANT SETTING, RELOCATE	1.000	EACH

CALL ORDER : 331

CONTRACT ID : R -32767-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION - COMMON ITEMS			
99	720-90579 HYDRANT SETTING, RELOCATE	1.000	EACH
100	720-90984 MANHOLE, C2	1.000	EACH
101	720-92883 MANHOLE, M4, MODIFIED	1.000	EACH
102	720-92884 MANHOLE, K4, MODIFIED	3.000	EACH
103	720-93501 MANHOLE, L4	7.000	EACH
104	720-94612 MANHOLE, K4	2.000	EACH
105	720-95335 MANHOLE, M4	6.000	EACH
106	720-95422 MANHOLE, J4	5.000	EACH
107	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
108	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
109	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	9,697.000	LFT
110	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	9,544.000	LFT
111	801-06625 DETOUR ROUTE MARKER ASSEMBLY	19.000	EACH
112	801-06640 CONSTRUCTION SIGN, A	37.000	EACH
113	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
114	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
115	801-07119 BARRICADE, III-B	105.000	LFT
116	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	235.000	LFT
117	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	120.000	SFT
118	805-01842 HANDHOLE, SIGNAL	1.000	EACH
119	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	12.000	LFT
120	805-04952 CONTROLLER AND CABINET	1.000	EACH
121	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN RED	8.000	EACH
122	805-78415 SPAN, CATENARY, AND TETHER	1.000	EACH
123	805-78420 DISCONNECT HANGER	1.000	EACH
124	805-78445 SIGNAL SERVICE	1.000	EACH
125	805-78480 SIGNAL CABLE, 3C/14GA	63.000	LFT
126	805-78485 SIGNAL CABLE, 5C/14GA	73.000	LFT
127	805-78906 SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 12 FT	2.000	EACH
128	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	2.000	EACH
SECTION NO. 0002 ROAD RECONSTRUCTION -HMA			
129	203-02000 EXCAVATION, COMMON	22,730.000	CYS
130	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	7,990.000	TON
131	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	3,777.000	TON
132	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	5,125.000	TON
133	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	14,399.000	TON
134	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	5,205.000	TON
135	401-10258 JOINT ADHESIVE, SURFACE	31,720.000	LFT
136	401-10259 JOINT ADHESIVE, INTERMEDIATE	31,720.000	LFT
137	406-05520 ASPHALT FOR TACK COAT	41.000	TON
138	615-06505 MONUMENT, B	10.000	EACH
139	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	22,363.000	LFT
140	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	80.000	LFT
141	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,725.000	LFT
142	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	8,826.000	LFT
143	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	227.000	LFT
144	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH

CALL ORDER : 331

CONTRACT ID : R -32767-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	ROAD RECONSTRUCTION - PCCP		
145	203-02000 EXCAVATION, COMMON	25,590.000	CYS
146	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5,501.000	TON
147	302-06464 SUBBASE FOR PCCP	9,182.000	CYS
148	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	745.000	TON
149	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	2,336.000	TON
150	406-05520 ASPHALT FOR TACK COAT	5.000	TON
151	501-09749 QC/QA PCCP, 9.5"	36,725.000	SYS
152	503-05240 D-1 CONTRACTION JOINT	21,944.000	LFT
153	615-06515 MONUMENT, D	10.000	EACH
154	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	22,363.000	LFT
155	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	8,906.000	LFT
156	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	1,725.000	LFT
157	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	227.000	LFT
158	808-10053 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT,	2.000	EACH

CALL ORDER : 341

CONTRACT ID : R -32827-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02278 CURB, CONCRETE, REMOVE	1,915.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	705.000	SYS
11	303-07449 COMPACTED AGGREGATE, NO. 73	390.000	TON
12	304-07491 HMA PATCHING, TYPE C	100.000	TON
13	306-08036 MILLING, ASPHALT, 2 IN	3,600.000	SYS
14	306-08037 MILLING, ASPHALT, 3 IN	39,220.000	SYS
15	306-08043 MILLING, TRANSITION	835.000	SYS
16	306-08432 MILLING, APPROACH	9,280.000	SYS
17	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	3,535.000	TON
18	401-07379 QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	4,715.000	TON
19	406-05520 ASPHALT FOR TACK COAT	26.000	TON
20	604-06070 SIDEWALK, CONCRETE	330.000	SYS
21	604-07894 CURB RAMP, CONCRETE, A	40.000	SYS
22	604-07896 CURB RAMP, CONCRETE, B	140.000	SYS
23	604-07897 CURB RAMP, CONCRETE, C	85.000	SYS
24	604-07901 CURB RAMP, CONCRETE, G	110.000	SYS
25	605-06120 CURB, CONCRETE	1,915.000	LFT
26	610-07488 HMA FOR APPROACHES, TYPE C	1,790.000	TON
27	615-06520 MONUMENT, RE-ESTABLISH	1.000	EACH
28	621-06574 SODDING	130.000	SYS
29	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
30	628-09403 FIELD OFFICE, C	4.000	MOS
31	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	8.000	MOS
32	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
33	720-44000 CASTING, ADJUST TO GRADE	44.000	EACH
34	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
35	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	2,390.000	LFT
36	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,195.000	LFT
37	801-06640 CONSTRUCTION SIGN, A	58.000	EACH
38	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
39	805-02328 SIGNAL CABLE, 1c/14 GA	400.000	LFT
40	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
41	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	160.000	LFT
42	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	2.000	EACH
43	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
44	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	13,270.000	LFT
45	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,530.000	LFT
46	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	12,170.000	LFT
47	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	130.000	LFT
48	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	260.000	LFT
49	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH

CALL ORDER : 341

CONTRACT ID : R -32827-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	236.000	EACH
51 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	236.000	EACH

CALL ORDER : 351

CONTRACT ID : R -34105-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SAFE ROUTE TO SCHOOL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-02245 TREE, 6 IN, REMOVE	4.000	EACH
8	201-02255 TREE, 18 IN, REMOVE	2.000	EACH
9	201-02260 TREE, 30 IN, REMOVE	9.000	EACH
10	201-02265 TREE, 48 IN, REMOVE	2.000	EACH
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-52710 SIDEWALK, CONCRETE, REMOVE	1,038.000	SYS
13	202-74035 SIGN, REMOVE	9.000	EACH
14	203-02000 EXCAVATION, COMMON	183.000	CYS
15	203-02070 BORROW	50.000	CYS
16	205-03371 SEDIMENT, REMOVE	1.500	CYS
17	205-06933 TEMPORARY INLET PROTECTION	10.000	EACH
18	205-06934 TEMPORARY MULCH	0.300	TON
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	86.000	SYS
20	304-07490 HMA PATCHING, TYPE B	36.000	TON
21	604-07901 CURB RAMP, CONCRETE, G	95.000	SYS
22	604-07902 CURB RAMP, CONCRETE, H	7.000	SYS
23	604-91531 SIDEWALK, CONCRETE, 4 IN	1,078.000	SYS
24	610-08446 PCCP FOR APPROACHES, 6 IN	86.000	SYS
25	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
26	621-06545 FERTILIZER	0.060	TON
27	621-06557 SEED MIXTURE, T	22.500	LBS
28	621-06567 WATER	12.000	KGAL
29	621-06570 TOPSOIL	82.000	CYS
30	621-06575 SODDING, NURSERY	733.000	SYS
31	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
32	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
33	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
34	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
35	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	88.000	LFT
38	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	72.000	SFT
39	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	81.000	LFT
40	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	455.000	LFT

CALL ORDER : 361

CONTRACT ID : R -34330-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	400.000	SYS
10	202-02278 CURB, CONCRETE, REMOVE	1,539.000	LFT
11	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	7.000	EACH
12	202-93994 SIGNAL MAST ARM AND POLE, REMOVE	2.000	EACH
13	202-93994 SIGNAL MAST ARM AND POLE, REMOVE	2.000	EACH
14	203-02000 EXCAVATION, COMMON	1,846.000	CYS
15	205-02459 EROSION CONTROL	LUMP	LUMP
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	122.000	SYS
17	207-09935 SUBGRADE TREATMENT, TYPE 1C	225.000	SYS
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	113.000	CYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	75.000	TON
20	402-07433 HMA SURFACE, TYPE B	19.000	TON
21	402-07438 HMA INTERMEDIATE, TYPE B	31.000	TON
22	406-05521 ASPHALT FOR TACK COAT	225.000	SYS
23	502-06329 PCCP, 12 IN	21.000	SYS
24	502-06999 PCCP, 8 IN	325.000	SYS
25	604-04740 PAVERS	1,524.000	SFT
26	604-04740 PAVERS	2,926.000	SFT
27	604-04740 PAVERS	17,337.000	SFT
28	604-04740 PAVERS	1,502.000	SFT
29	604-04740 PAVERS	194.000	SFT
30	604-04740 PAVERS	2,926.000	SFT
31	604-04740 PAVERS	795.000	SFT
32	604-04740 PAVERS	797.000	SFT
33	604-06070 SIDEWALK, CONCRETE	1,400.000	SYS
34	604-07894 CURB RAMP, CONCRETE, A	32.000	SYS
35	604-07894 CURB RAMP, CONCRETE, A	36.000	SYS
36	604-07898 CURB RAMP, CONCRETE, D	20.000	SYS
37	604-07898 CURB RAMP, CONCRETE, D	28.000	SYS
38	604-91531 SIDEWALK, CONCRETE, 4 IN	255.000	SYS
39	605-01870 CURB, CONCRETE, A	1,115.000	LFT
40	605-06121 CURB, CONCRETE, B	20.000	LFT
41	610-09108 PCCP FOR APPROACHES, 9 IN	107.000	SYS
42	615-97672 TRASH RECEPTACLE	4.000	EACH
43	621-06570 TOPSOIL	36.000	CYS
44	621-10164 STRUCTURAL SOIL MIXES	65.000	CYS
45	621-98038 MULCH, HARDWOOD SHREDDED BARK	6.000	CYS
46	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN	13.000	EACH
47	622-05653 PLANT, GROUND COVER	580.000	EACH
48	622-05654 PLANT, PERENNIAL	208.000	EACH
49	622-05655 PLANT, ROOT, TUBER, CORM, BULB	160.000	EACH

CALL ORDER : 361

CONTRACT ID : R -34330-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
50	628-09401 FIELD OFFICE, A	6.000	MOS
51	712-03812 BENCH	18.000	EACH
52	715-01902 WATER SERVICE LINE 2 IN	90.000	LFT
53	715-02889 SERVICE LINE 1"	215.000	LFT
54	715-04995 LINE STOP	4.000	EACH
55	715-05147 PIPE, TYPE 2 CIRCULAR 8 IN	85.000	LFT
56	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	103.000	LFT
57	715-09883 VALVE WITH BOX	8.000	EACH
58	715-92543 WATER MAIN, 8 IN, RELOCATE	768.000	LFT
59	715-94780 WATER MAIN, DUCTILE IRON, 6 IN	67.000	LFT
60	715-95866 GATE VALVE, 6 IN.	3.000	EACH
61	715-96948 GATE VALVE, 8 IN	4.000	EACH
62	720-04499 INLET, RECONSTRUCT	6.000	EACH
63	720-07309 TRENCH DRAIN	592.000	LFT
64	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
65	720-44296 INLET, CAP	6.000	EACH
66	720-45015 INLET, A8	3.000	EACH
67	720-45045 INLET, J10	5.000	EACH
68	720-45400 MANHOLE, A4	4.000	EACH
69	720-96999 FIRE HYDRANT ASSEMBLY	1.000	EACH
70	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
71	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
72	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
73	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
74	801-07119 BARRICADE, III-B	216.000	LFT
75	802-03126 SIGN, OVERHEAD, RELOCATE	6.000	EACH
76	802-03896 BOLLARD	8.000	EACH
77	802-03896 BOLLARD	8.000	EACH
78	802-04089 SIGN, SHEET, REMOVE	8.000	EACH
79	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	182.500	LFT
80	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	157.500	SFT
81	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
82	805-01816 SIGNAL SUPPORT FOUNDATION, 36 IN X 36 IN X 96 IN	4.000	EACH
83	805-01842 HANDHOLE, SIGNAL	5.000	EACH
84	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	300.000	LFT
85	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	8.000	EACH
86	805-03972 CONDUIT, PVC, 1 IN, SCHEDULE 40	308.000	LFT
87	805-08214 CONDUIT, PVC, 2 IN, SCHEDULE 40, FOR ELECTRIC	1,018.000	LFT
88	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
89	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	6.000	EACH
90	805-78445 SIGNAL SERVICE	1.000	EACH
91	805-78467 SIGNAL CABLE, 3C/8GA	195.000	LFT
92	805-78485 SIGNAL CABLE, 5C/14GA	810.000	LFT
93	805-78490 SIGNAL CABLE, 7C/14GA	1,395.000	LFT
94	805-78930 CONTROLLER CABINET FOUNDATION, M	1.000	EACH
95	805-94069 CONDUIT, STEEL, GALVANIZED, 1 IN	20.000	LFT
96	805-95568 CONDUIT, PVC, 4 IN.	355.000	LFT
97	805-99327 CONDUIT, SPLICE	2.000	EACH
98	807-02191 HANDHOLE, LIGHTING	10.000	EACH

CALL ORDER : 361

CONTRACT ID : R -34330-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, STREETScape		
99 807-02191	HANDHOLE, LIGHTING	1.000	EACH
100 807-02426	WIRE, THW, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	200.000	LFT
101 807-03051	LIGHT CABLE, 1/C 10GA.	1,880.000	LFT
102 807-07580	WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	6,510.000	LFT
103 807-11567	LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 18" X 60"	16.000	EACH
104 807-11568	WIRE, XHHW, NO 2/0 COPPER, 1C	6,400.000	LFT
105 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	47.000	LFT
106 808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	72.000	LFT

CALL ORDER : 371

CONTRACT ID : R -34459-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	1,488.000	CYS
10	203-02070 BORROW	1,185.000	CYS
11	205-06932 TEMPORARY CHECK DAM, STRAW BALES	24.000	LFT
12	205-06937 TEMPORARY SILT FENCE	1,521.000	LFT
13	205-09543 NO 2 STONE	166.000	TON
14	207-08263 SUBGRADE TREATMENT, TYPE IA	4,611.000	SYS
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	53.000	SYS
16	210-09475 STORMWATER QUALITY STRUCTURE	1.000	EACH
17	211-02050 B BORROW	436.000	CYS
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	410.000	CYS
19	214-07202 GEOGRID, TYPE I	872.000	SYS
20	303-01180 COMPACTED AGGREGATE, NO. 53	196.000	TON
21	402-07434 HMA SURFACE, TYPE C	285.000	TON
22	402-07439 HMA INTERMEDIATE, TYPE C	475.000	TON
23	402-07442 HMA BASE, TYPE C	1,174.000	TON
24	406-05520 ASPHALT FOR TACK COAT	2.600	TON
25	502-09531 PCCP	748.000	SYS
26	604-06070 SIDEWALK, CONCRETE	235.000	SYS
27	604-07903 CURB RAMP, CONCRETE, K	25.000	SYS
28	604-07904 CURB RAMP, CONCRETE, L	19.000	SYS
29	604-92237 HAND RAIL, STEEL	68.000	LFT
30	605-06120 CURB, CONCRETE	201.000	LFT
31	605-06160 CURB AND GUTTER, B, CONCRETE, MODIFIED	812.000	LFT
32	605-52807 CURB AND GUTTER, COMBINED	624.000	LFT
33	610-08446 PCCP FOR APPROACHES, 6 IN	53.000	SYS
34	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
36	621-06560 MULCHED SEEDING, U	3,207.000	SYS
37	621-08161 PERMANENT TURF REINFORCEMENT MAT	371.000	SYS
38	621-09399 SEED MIXTURE, WET MESIC	3.000	LBS
39	628-09401 FIELD OFFICE, A	8.000	MOS
40	714-11097 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	114.000	LFT
41	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	38.000	LFT
42	715-05147 PIPE, TYPE 2 CIRCULAR 8 IN	11.000	LFT
43	715-05148 PIPE, TYPE 2 CIRCULAR 10 IN	7.000	LFT
44	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	126.000	LFT
45	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	243.000	LFT
46	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	60.000	LFT
47	715-46010 PIPE END SECTION, DIA 18"	2.000	EACH
48	720-45410 MANHOLE, C4	6.000	EACH
49	720-91973 MANHOLE, H4	1.000	EACH

CALL ORDER : 371

CONTRACT ID : R -34459-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
50	720-98174 INLET, B15	3.000	EACH
51	720-98555 INLET, C15	4.000	EACH
52	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
53	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
54	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	7,343.000	LFT
55	801-06625 DETOUR ROUTE MARKER ASSEMBLY	49.000	EACH
56	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
57	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
58	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
59	801-07118 BARRICADE, III-A	24.000	LFT
60	801-07119 BARRICADE, III-B	120.000	LFT
61	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	436.000	LFT
62	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	121.000	SFT
63	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	58.000	SFT
64	805-78930 CONTROLLER CABINET FOUNDATION, M	1.000	EACH
65	805-93555 CONTROLLER CABINET, M	1.000	EACH
66	807-02191 HANDHOLE, LIGHTING	6.000	EACH
67	807-02194 SERVICE POINT, II, MODIFIED	1.000	EACH
68	807-02428 LIGHTING FOUNDATION, CONCRETE, WITH GROUND	8.000	EACH
69	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	190.000	LFT
70	807-11365 LUMINAIRE, ROADWAY, LED, 250 WATT	8.000	EACH
71	807-11425 LIGHT POLE, ROADWAY, 25 FT. EMH, 8 FT. MAST ARM,	8.000	EACH
72	807-86910 CONNECTOR KIT, UNFUSED	8.000	EACH
73	807-86915 CONNECTOR KIT, FUSED	8.000	EACH
74	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	24.000	EACH
75	807-86935 INSULATION LINK, WATERPROOFED	8.000	EACH
76	807-86955 CABLE-DUCT MARKER	3.000	EACH
77	807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	190.000	LFT
78	807-98335 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C	422.000	LFT
79	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,024.000	LFT
80	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN	200.000	LFT
81	808-09083 LINE THERMOPLASTIC BROKEN WHITE 8 IN	111.000	LFT
82	808-10118 TRANSVERSE MARKING, THERMOPLASTIC, YIELD, WHITE,	64.000	LFT
83	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,114.000	LFT

CALL ORDER : 381

CONTRACT ID : R -34543-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 CONCRETE PAVEMENT RESTORATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	205-06933 TEMPORARY INLET PROTECTION	5.000	EACH
8	207-09935 SUBGRADE TREATMENT, TYPE 1C	7,085.000	SYS
9	211-09265 STRUCTURAL BACKFILL, TYPE 2	106.000	CYS
10	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,350.000	TON
11	302-06464 SUBBASE FOR PCCP	828.000	CYS
12	503-03489 RETROFITTED TIE BARS	4,489.000	EACH
13	503-05240 D-1 CONTRACTION JOINT	6,135.000	LFT
14	506-06333 PCCP PATCHING, FULL DEPTH	9,464.000	SYS
15	507-07505 RETROFIT LOAD TRANSFER	336.000	EACH
16	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	41.000	TON
17	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	2.000	EACH
18	612-60410 DRILLED HOLE FOR UNDERSEAL	680.000	EACH
19	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
20	621-06559 MULCHED SEEDING, R	5,700.000	SYS
21	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
22	628-09402 FIELD OFFICE, B	14.000	MOS
23	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	28.000	MOS
24	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
25	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	5,476.000	LFT
26	718-06529 OUTLET PROTECTOR, 2	310.000	EACH
27	718-06531 OUTLET PROTECTOR, 3	15.000	EACH
28	718-52610 AGGREGATE FOR UNDERDRAINS	38.000	CYS
29	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	16.000	EACH
30	801-03290 CONSTRUCTION SIGN, C	13.000	EACH
31	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	52,060.000	LFT
32	801-06640 CONSTRUCTION SIGN, A	96.000	EACH
33	801-06710 FLASHING ARROW SIGN	500.000	DAY
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	3,551.000	LFT
36	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	480.000	LFT
37	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
38	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	6,010.000	LFT
39	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	20,860.000	LFT
40	808-06716 LINE, REMOVE	23,380.000	LFT
41	808-75001 LINE, PAINT, BROKEN, WHITE, 5 IN	4,150.000	LFT
42	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	100.000	EACH

CALL ORDER : 391

CONTRACT ID : R -34604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PIPE LINING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	205-09235 TEMPORARY FILTER BAG	15.000	DAY
8	616-02320 GEOTEXTILES	15.000	SYS
9	616-05688 RIPRAP, CLASS 1	16.000	TON
10	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
11	621-06559 MULCHED SEEDING, R	10.000	SYS
12	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
13	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
14	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
15	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	9.000	MOS
16	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
17	725-11399 PIPE LINER, CURED-IN-PLACE, 84 IN	41.000	LFT
18	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 401

CONTRACT ID : R -34699-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SAFE ROUTE TO SCHOOL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02278 CURB, CONCRETE, REMOVE	3,243.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	2,936.000	SYS
11	203-02000 EXCAVATION, COMMON	120.000	CYS
12	203-02070 BORROW	560.000	CYS
13	207-08267 SUBGRADE TREATMENT, TYPE IIIA	170.000	SYS
14	304-07491 HMA PATCHING, TYPE C	231.000	TON
15	604-07894 CURB RAMP, CONCRETE, A	10.000	SYS
16	604-07894 CURB RAMP, CONCRETE, A	10.000	SYS
17	604-07900 CURB RAMP, CONCRETE, F	97.000	SYS
18	604-07901 CURB RAMP, CONCRETE, G	5.000	SYS
19	604-07901 CURB RAMP, CONCRETE, G	30.000	SYS
20	604-07902 CURB RAMP, CONCRETE, H	57.000	SYS
21	604-07903 CURB RAMP, CONCRETE, K	9.000	SYS
22	604-91531 SIDEWALK, CONCRETE, 4 IN	2,718.000	SYS
23	605-06120 CURB, CONCRETE	2,682.000	LFT
24	605-06125 CURB, CONCRETE, MODIFIED	561.000	LFT
25	610-08446 PCCP FOR APPROACHES, 6 IN	170.000	SYS
26	621-06570 TOPSOIL	220.000	CYS
27	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
28	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
29	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN	20.000	LFT
30	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	370.000	LFT
31	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	1,780.000	LFT

CALL ORDER : 411

CONTRACT ID : R -34761-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 AUXILARY LANES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-91385 INLET, REMOVE	3.000	EACH
9	203-02000 EXCAVATION, COMMON	358.000	CYS
10	203-02070 BORROW	149.000	CYS
11	205-03371 SEDIMENT, REMOVE	30.000	CYS
12	205-06933 TEMPORARY INLET PROTECTION	3.000	EACH
13	205-06937 TEMPORARY SILT FENCE	553.000	LFT
14	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,577.000	SYS
15	303-07449 COMPACTED AGGREGATE, NO. 73	234.000	TON
16	402-07433 HMA SURFACE, TYPE B	102.000	TON
17	402-07438 HMA INTERMEDIATE, TYPE B	174.000	TON
18	402-07441 HMA BASE, TYPE B	436.000	TON
19	406-05520 ASPHALT FOR TACK COAT	1.000	TON
20	610-07487 HMA FOR APPROACHES, TYPE B	10.000	TON
21	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
22	616-06941 GROUT	4.000	CYS
23	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
24	621-06559 MULCHED SEEDING, R	633.000	SYS
25	621-06575 SODDING, NURSERY	120.000	SYS
26	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
27	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
28	720-45035 INLET, F7	3.000	EACH
29	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
30	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	5,790.000	LFT
31	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
32	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
33	802-04893 REFERENCE POST	1.000	EACH
34	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	320.000	LFT
35	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	1,125.000	LFT
36	808-06716 LINE, REMOVE	320.000	LFT

CALL ORDER : 421

CONTRACT ID : R -34801-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT RAILROAD WORK		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	205-09543 NO 2 STONE	4,200.000	TON
8	614-92148 RAILROAD TRACK	45,000.000	LFT
9	711-05395 REPLACE	4,800.000	EACH
10	711-05395 REPLACE	2,000.000	EACH

CALL ORDER : 431

CONTRACT ID : R -34865-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	WEDGE AND LEVEL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	303-01180 COMPACTED AGGREGATE, NO. 53	32.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,183.000	SYS
10	306-10163 MILLING ASPHALT, 2 1/2 IN	507.000	SYS
11	402-07784 HMA SURFACE, TYPE D	98.000	TON
12	402-07785 HMA INTERMEDIATE, TYPE D	70.000	TON
13	406-05520 ASPHALT FOR TACK COAT	0.460	TON
14	601-06035 GUARDRAIL, RESET	1,075.000	LFT
15	606-07484 MILLED HMA SHOULDER CORRUGATIONS	645.000	LFT
16	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
17	801-03290 CONSTRUCTION SIGN, C	1.000	EACH
18	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	2,836.000	LFT
19	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
20	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
21	801-06710 FLASHING ARROW SIGN	30.000	DAY
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	1.000	EACH
24	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	851.000	LFT
25	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	645.000	LFT
26	808-06716 LINE, REMOVE	1,296.000	LFT
27	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	130.000	LFT
28	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	45.000	LFT
29	808-75001 LINE, PAINT, BROKEN, WHITE, 5 IN	432.000	LFT
30	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	24.000	EACH
31	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	24.000	EACH

CALL ORDER : 481

CONTRACT ID : RS-31923-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02273 CENTER CURB, CONCRETE, REMOVE	20.000	SYS
10	202-02278 CURB, CONCRETE, REMOVE	470.000	LFT
11	202-52710 SIDEWALK, CONCRETE, REMOVE	625.000	SYS
12	203-02000 EXCAVATION, COMMON	40.000	CYS
13	203-02070 BORROW	25.000	CYS
14	304-07491 HMA PATCHING, TYPE C	64.000	TON
15	306-08034 MILLING, ASPHALT, 1 1/2 IN	90,800.000	SYS
16	306-08432 MILLING, APPROACH	12,400.000	SYS
17	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	7,800.000	TON
18	406-05520 ASPHALT FOR TACK COAT	26.000	TON
19	604-06070 SIDEWALK, CONCRETE	70.000	SYS
20	604-07894 CURB RAMP, CONCRETE, A	45.000	SYS
21	604-07896 CURB RAMP, CONCRETE, B	400.000	SYS
22	604-07897 CURB RAMP, CONCRETE, C	15.000	SYS
23	604-07901 CURB RAMP, CONCRETE, G	70.000	SYS
24	604-07902 CURB RAMP, CONCRETE, H	15.000	SYS
25	605-06120 CURB, CONCRETE	532.000	LFT
26	610-07488 HMA FOR APPROACHES, TYPE C	1,025.000	TON
27	621-06574 SODDING	78.000	SYS
28	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
29	628-09402 FIELD OFFICE, B	5.000	MOS
30	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	15.000	MOS
31	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
32	720-44000 CASTING, ADJUST TO GRADE	55.000	EACH
33	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
34	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	14,400.000	LFT
35	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	14,400.000	LFT
36	801-06640 CONSTRUCTION SIGN, A	44.000	EACH
37	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
38	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	1.000	EACH
39	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	9,260.000	LFT
40	805-78785 SIGNAL DETECTOR HOUSING	38.000	EACH
41	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	4,160.000	LFT
42	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	4.000	EACH
43	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	6,700.000	LFT
44	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	9,900.000	LFT
45	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	100.000	LFT
46	808-75100 TRANSVERSE MARKING, PAINT,	2,600.000	LFT
47	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	22,200.000	LFT
48	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	45.000	LFT
49	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	730.000	LFT

CALL ORDER : 481

CONTRACT ID : RS-31923-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	1,400.000	LFT
51 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	34.000	EACH
52 808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	8.000	EACH
53 808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	2,100.000	LFT

CALL ORDER : 491

CONTRACT ID : RS-32689-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-06541 REMOVE	1.000	EACH
11	202-06541 REMOVE	4.000	EACH
12	203-02020 EXCAVATION, UNCLASSIFIED	605.000	CYS
13	207-09935 SUBGRADE TREATMENT, TYPE 1C	5,000.000	SYS
14	211-09264 STRUCTURAL BACKFILL, TYPE 1	105.000	CYS
15	302-07455 DENSE GRADED SUBBASE	780.000	CYS
16	303-01180 COMPACTED AGGREGATE, NO. 53	190.000	TON
17	303-07449 COMPACTED AGGREGATE, NO. 73	10,250.000	TON
18	304-07783 HMA PATCHING, TYPE D	425.000	TON
19	306-08033 MILLING, ASPHALT, 1 IN	47,365.000	SYS
20	306-08034 MILLING, ASPHALT, 1 1/2 IN	12,565.000	SYS
21	306-08043 MILLING, TRANSITION	25,365.000	SYS
22	306-08432 MILLING, APPROACH	870.000	SYS
23	306-08595 MILLING ASPHALT, 3 1/2 IN	113,900.000	SYS
24	306-10163 MILLING ASPHALT, 2 1/2 IN	263,550.000	SYS
25	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
26	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	10,420.000	TON
27	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	500.000	TON
28	401-07330 QC/QA-HMA, 5, 70, SURFACE, 9.5 mm	27,050.000	TON
29	401-07355 QC/QA-HMA, 1, 64, INTERMEDIATE, 9.5 mm	9,500.000	TON
30	401-07370 QC/QA-HMA, 1, 64, INTERMEDIATE, 12.5 mm	425.000	TON
31	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	850.000	TON
32	401-07400 QC/QA-HMA, 5, 70, INTERMEDIATE, 19.0 mm	58,700.000	TON
33	401-07422 QC/QA-HMA, 1, 64, BASE, 19.0 mm	19,300.000	TON
34	406-05520 ASPHALT FOR TACK COAT	350.000	TON
35	503-03489 RETROFITTED TIE BARS	1,050.000	EACH
36	503-05240 D-1 CONTRACTION JOINT	1,630.000	LFT
37	506-06333 PCCP PATCHING, FULL DEPTH	4,700.000	SYS
38	506-06334 PCCP PATCHING, PARTIAL DEPTH	4.000	SYS
39	507-08272 JOINTS IN PCCP, SAW AND SEAL	10,500.000	LFT
40	601-06035 GUARDRAIL, RESET	7,183.000	LFT
41	601-06777 GRAVEL BARREL ARRAY	1.000	EACH
42	601-07050 GUARDRAIL END TREATMENT, OS, RESET	16.000	EACH
43	601-91147 GUARDRAIL END TREATMENT, RESET	9.000	EACH
44	606-07484 MILLED HMA SHOULDER CORRUGATIONS	222,060.000	LFT
45	610-07487 HMA FOR APPROACHES, TYPE B	265.000	TON
46	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	25.000	TON
47	612-60410 DRILLED HOLE FOR UNDERSEAL	485.000	EACH
48	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
49	621-02770 EROSION CONTROL BLANKET	1,000.000	SYS

CALL ORDER : 491

CONTRACT ID : RS-32689-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	621-06559 MULCHED SEEDING, R	5,000.000	SYS
51	621-06626 MULCHED SEEDING, D	1,000.000	SYS
52	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
53	628-09402 FIELD OFFICE, B	15.000	MOS
54	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	15.000	MOS
55	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	45.000	MOS
56	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
57	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	2,064.000	LFT
58	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	230.000	LFT
59	718-06526 HMA FOR UNDERDRAINS	11.000	TON
60	718-06529 OUTLET PROTECTOR, 2	140.000	EACH
61	718-52610 AGGREGATE FOR UNDERDRAINS	7.000	CYS
62	718-99153 GEOTEXTILES FOR UNDERDRAIN	150.000	SYS
63	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	41.000	LFT
64	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
65	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
66	801-03291 CONSTRUCTION SIGN, D	12.000	EACH
67	801-04308 ROAD CLOSURE SIGN ASSEMBLY	1.000	EACH
68	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	110,510.000	LFT
69	801-06204 TEMPORARY PAVEMENT MARKING, 5 IN	15,000.000	LFT
70	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	985,000.000	LFT
71	801-06208 TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN	30,000.000	LFT
72	801-06625 DETOUR ROUTE MARKER ASSEMBLY	4.000	EACH
73	801-06640 CONSTRUCTION SIGN, A	93.000	EACH
74	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
75	801-06710 FLASHING ARROW SIGN	360.000	DAY
76	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
77	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	8.000	EACH
78	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	53.000	LFT
79	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	32.000	SFT
80	804-06740 DELINEATOR WITH POST, D2	2.000	EACH
81	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	26,250.000	LFT
82	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	108,650.000	LFT
83	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	1,780.000	LFT
84	808-06716 LINE, REMOVE	118,000.000	LFT
85	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
86	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	5,825.000	LFT
87	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	5,825.000	LFT
88	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	60.000	LFT
89	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	1,460.000	LFT
90	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	3.000	EACH
91	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	108,650.000	LFT
92	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	215.000	LFT
93	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,550.000	EACH
94	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,550.000	EACH

CALL ORDER : 501

CONTRACT ID : RS-32950-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02676 TRANSPORTATION OF SALVAGEABLE MILLED MATERIAL	1,000.000	TON
11	202-90277 DETECTOR HOUSING, REMOVE	15.000	EACH
12	202-93741 GUARDRAIL END TREATMENT, REMOVE	1.000	EACH
13	203-02000 EXCAVATION, COMMON	75.000	CYS
14	205-06937 TEMPORARY SILT FENCE	430.000	LFT
15	207-09935 SUBGRADE TREATMENT, TYPE 1C	378.000	SYS
16	303-01180 COMPACTED AGGREGATE, NO. 53	115.000	TON
17	304-07491 HMA PATCHING, TYPE C	290.000	TON
18	306-08034 MILLING, ASPHALT, 1 1/2 IN	50,300.000	SYS
19	306-08432 MILLING, APPROACH	915.000	SYS
20	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	4,176.000	TON
21	402-07439 HMA INTERMEDIATE, TYPE C	42.000	TON
22	402-07442 HMA BASE, TYPE C	145.000	TON
23	402-07452 HMA WEDGE AND LEVEL, TYPE C	20.000	TON
24	406-05520 ASPHALT FOR TACK COAT	14.000	TON
25	601-02241 GUARDRAIL, REMOVE	175.000	LFT
26	601-09238 HAND DIG GUARDRAIL POST HOLES	35.000	EACH
27	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
28	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	344.000	LFT
29	601-99106 GUARDRAIL, W-BEAM, 3 FT 1.5 IN SPACING	29.000	LFT
30	610-07488 HMA FOR APPROACHES, TYPE C	76.000	TON
31	616-02320 GEOTEXTILES	7.000	SYS
32	616-06405 RIPRAP, REVETMENT	6.000	TON
33	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
34	621-06559 MULCHED SEEDING, R	60.000	SYS
35	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
36	628-09402 FIELD OFFICE, B	9.000	MOS
37	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	18.000	MOS
38	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
39	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	5.000	LFT
40	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	1.000	LFT
41	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	28.000	EACH
42	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
43	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	6,625.000	LFT
44	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	6,870.000	LFT
45	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	28.000	EACH
46	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24"	410.000	LFT
47	801-06640 CONSTRUCTION SIGN, A	25.000	EACH
48	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
49	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN	410.000	LFT

CALL ORDER : 501

CONTRACT ID : RS-32950-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
50	801-92448 CONSTRUCTION SIGNS, MOBILE	500.000	DAY
51	802-02475 SIGN, PANEL, RELOCATE	1.000	EACH
52	802-03706 SIGN, PANEL, INSTALL	1.000	EACH
53	802-04089 SIGN, SHEET, REMOVE	4.000	EACH
54	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	2.000	EACH
55	802-76095 STRUCTURAL STEEL, BREAKAWAY	183.000	LBS
56	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	1.000	EACH
57	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	5,420.000	LFT
58	805-78485 SIGNAL CABLE, 5C/14GA	20.000	LFT
59	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	300.000	LFT
60	805-78785 SIGNAL DETECTOR HOUSING	15.000	EACH
61	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,880.000	LFT
62	807-02191 HANDHOLE, LIGHTING	2.000	EACH
63	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	465.000	LFT
64	807-98690 HANDHOLE ADJUSTED TO GRADE	1.000	EACH
65	808-01329 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WRONG WAY RAMP	3.000	EACH
66	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
67	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	3,860.000	LFT
68	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	16,050.000	LFT
69	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	10,150.000	LFT
70	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	1,000.000	LFT
71	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	1,115.000	LFT
72	808-11481 LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	255.000	LFT
73	808-11548 LINE MULTI-COMPONENT DOTTED YELLOW 4"	80.000	LFT
74	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	220.000	LFT
75	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	115.000	LFT
76	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	410.000	LFT
77	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	28.000	EACH
78	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	426.000	EACH
79	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	426.000	EACH

CALL ORDER : 511

CONTRACT ID : RS-34058-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INSTITUTIONAL ROAD PROJECT		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-01180 COMPACTED AGGREGATE, NO. 53	300.000	TON
8	304-07490 HMA PATCHING, TYPE B	100.000	TON
9	306-08034 MILLING, ASPHALT, 1 1/2 IN	2,000.000	SYS
10	402-07433 HMA SURFACE, TYPE B	165.000	TON
11	406-05520 ASPHALT FOR TACK COAT	1.000	TON
12	628-09402 FIELD OFFICE, B	2.000	MOS
13	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 521

CONTRACT ID : RS-34059-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02278 CURB, CONCRETE, REMOVE	200.000	LFT
8	306-08034 MILLING, ASPHALT, 1 1/2 IN	2,700.000	SYS
9	402-07433 HMA SURFACE, TYPE B	223.000	TON
10	406-05520 ASPHALT FOR TACK COAT	1.000	TON
11	605-06120 CURB, CONCRETE	200.000	LFT
12	628-09402 FIELD OFFICE, B	2.000	MOS
13	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	1,700.000	LFT
17	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN	150.000	LFT
18	808-97222 PAVEMENT MESSAGE MARKING, PAINT, HANDICAP SYMBOL	2.000	EACH

CALL ORDER : 531

CONTRACT ID : RS-34168-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SURFACE TREATMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	303-01180 COMPACTED AGGREGATE, NO. 53	16.110	TON
10	304-07490 HMA PATCHING, TYPE B	65.950	TON
11	306-08043 MILLING, TRANSITION	226.670	SYS
12	408-07478 CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	13.500	TON
13	414-11468 ULTRATHIN BONDED WEARING COURSE, 9.5 mm	74,904.440	SYS
14	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	11.000	EACH
15	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
16	628-09402 FIELD OFFICE, B	8.000	MOS
17	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
18	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	16.000	MOS
19	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
20	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
21	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	808-06716 LINE, REMOVE	76,991.000	LFT
24	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
25	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	48,597.000	LFT
26	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	8,983.000	LFT
27	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	19,213.000	LFT
28	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	11.000	LFT
29	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	406.000	EACH
30	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	406.000	EACH
31	808-97323 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN	198.000	LFT

CALL ORDER : 541

CONTRACT ID : RS-34542-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SURFACE TREATMENT, THIN HMA OVERLAY			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-90277 DETECTOR HOUSING, REMOVE	17.000	EACH
10	303-07449 COMPACTED AGGREGATE, NO. 73	33.000	TON
11	304-07490 HMA PATCHING, TYPE B	467.000	TON
12	306-08432 MILLING, APPROACH	2,196.000	SYS
13	306-11553 MILLING, ASPHALT, 3/4 IN	43,186.000	SYS
14	402-07433 HMA SURFACE, TYPE B	1,837.000	TON
15	406-05520 ASPHALT FOR TACK COAT	13.000	TON
16	610-07487 HMA FOR APPROACHES, TYPE B	94.000	TON
17	615-06500 MONUMENT, A	2.000	EACH
18	615-06520 MONUMENT, RE-ESTABLISH	1.000	EACH
19	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
20	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	4.000	MOS
21	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
22	720-44045 CASTING, 8, FURNISH AND ADJUST TO GRADE	7.000	EACH
23	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	9.000	EACH
24	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
25	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	3,328.000	LFT
26	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	3,328.000	LFT
27	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	371.000	LFT
28	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	371.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	27.000	EACH
30	801-06710 FLASHING ARROW SIGN	90.000	DAY
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	801-92448 CONSTRUCTION SIGNS, MOBILE	540.000	DAY
33	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	3,165.000	LFT
34	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	300.000	LFT
35	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
36	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,078.000	LFT
37	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
38	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	1,816.000	LFT
39	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	7,205.000	LFT
40	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	10,062.000	LFT
41	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	1,280.000	LFT
42	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	2,740.000	LFT
43	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	622.000	LFT
44	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	371.000	LFT
45	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	27.000	EACH
46	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	128.000	EACH
47	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	128.000	EACH

CALL ORDER : 551

CONTRACT ID : RS-34544-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SURFACE TREATMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	304-07783 HMA PATCHING, TYPE D	320.000	TON
11	304-07783 HMA PATCHING, TYPE D	540.000	TON
12	306-08043 MILLING, TRANSITION	1,390.000	SYS
13	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
14	406-05520 ASPHALT FOR TACK COAT	2.000	TON
15	408-07504 CRACKS AND JOINTS IN ASPHALT PAVEMENT, SEAL	15.000	TON
16	414-11468 ULTRATHIN BONDED WEARING COURSE, 9.5 mm	141,820.000	SYS
17	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
18	628-09402 FIELD OFFICE, B	4.000	MOS
19	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	8.000	MOS
20	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
21	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
22	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
23	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	4,909.000	LFT
24	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
25	801-06710 FLASHING ARROW SIGN	240.000	DAY
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
28	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	49,089.000	LFT
29	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	49,089.000	LFT
30	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	12,273.000	LFT
31	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	616.000	EACH
32	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	616.000	EACH

CALL ORDER : 581

CONTRACT ID : B -29052-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	202-96133 PIPE, REMOVE	112.000	LFT
11	203-02000 EXCAVATION, COMMON	1,463.000	CYS
12	205-03371 SEDIMENT, REMOVE	3.000	CYS
13	205-06933 TEMPORARY INLET PROTECTION	3.000	EACH
14	205-06937 TEMPORARY SILT FENCE	3,400.000	LFT
15	205-09543 NO 2 STONE	100.000	TON
16	207-08263 SUBGRADE TREATMENT, TYPE IA	3,600.000	SYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	563.000	SYS
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	15.000	CYS
19	211-09265 STRUCTURAL BACKFILL, TYPE 2	525.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,515.000	TON
21	303-01180 COMPACTED AGGREGATE, NO. 53	595.000	TON
22	303-07449 COMPACTED AGGREGATE, NO. 73	55.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,870.000	SYS
24	306-08042 MILLING, SCARIFICATION/PROFILE	2,780.000	SYS
25	402-07433 HMA SURFACE, TYPE B	765.000	TON
26	402-07438 HMA INTERMEDIATE, TYPE B	760.000	TON
27	402-07441 HMA BASE, TYPE B	5.000	TON
28	406-05520 ASPHALT FOR TACK COAT	3.000	TON
29	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	2.000	EACH
30	601-02103 GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	50.000	LFT
31	601-05999 CURVED TERMINAL END	6.000	EACH
32	601-06053 GUARDRAIL	75.000	EACH
33	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
34	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,875.000	LFT
35	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	185.000	LFT
36	605-06160 CURB AND GUTTER, B, CONCRETE, MODIFIED	420.000	LFT
37	605-08636 CURB AND GUTTER, TURNOUT, COMBINED	3.500	LFT
38	605-08636 CURB AND GUTTER, TURNOUT, COMBINED	7.000	LFT
39	610-07486 HMA FOR APPROACHES, TYPE A	237.000	TON
40	610-07487 HMA FOR APPROACHES, TYPE B	338.000	TON
41	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
42	615-06490 RIGHT OF WAY MARKER	2.000	EACH
43	615-06505 MONUMENT, B	4.000	EACH
44	615-06510 MONUMENT, C	1.000	EACH
45	616-02320 GEOTEXTILES	3,765.000	SYS
46	616-05688 RIPRAP, CLASS 1	535.000	TON
47	616-06405 RIPRAP, REVETMENT	1,020.000	TON
48	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
49	621-02770 EROSION CONTROL BLANKET	1,150.000	SYS

CALL ORDER : 581

CONTRACT ID : B -29052-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
50	621-06545 FERTILIZER	0.300	TON
51	621-06554 SEED MIXTURE, U	115.000	LBS
52	621-06565 MULCHING MATERIAL	1.500	TON
53	621-06567 WATER	10.000	KGAL
54	621-06574 SODDING	135.000	SYS
55	621-06575 SODDING, NURSERY	32.000	SYS
56	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
57	628-09402 FIELD OFFICE, B	9.000	MOS
58	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	18.000	MOS
59	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
60	715-04964 WATER MAIN	165.000	LFT
61	715-04964 WATER MAIN	200.000	LFT
62	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	24.000	LFT
63	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	100.000	LFT
64	715-46005 PIPE END SECTION, DIA 15"	6.000	EACH
65	715-98961 FORCE MAIN	150.000	LFT
66	723-11211 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	88.000	LFT
67	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
68	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
69	801-06625 DETOUR ROUTE MARKER ASSEMBLY	52.000	EACH
70	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
71	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
72	801-07118 BARRICADE, III-A	48.000	LFT
73	801-07119 BARRICADE, III-B	204.000	LFT
74	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	154.000	LFT
75	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	69.000	LFT
76	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
77	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	97.000	SFT
78	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	34.000	SFT
79	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,700.000	LFT
80	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	4,100.000	LFT
81	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	30.000	LFT

CALL ORDER : 585

CONTRACT ID : B -30069-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHAB OR REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02278 CURB, CONCRETE, REMOVE	350.000	LFT
10	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	180.600	SFT
11	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
12	202-52710 SIDEWALK, CONCRETE, REMOVE	230.000	SYS
13	203-02000 EXCAVATION, COMMON	89.900	CYS
14	203-51223 EXCAVATION, WATERWAY	182.000	CYS
15	205-06937 TEMPORARY SILT FENCE	844.000	LFT
16	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	91.600	CYS
17	211-06467 AGGREGATE FOR END BENT BACKFILL	27.100	CYS
18	302-07455 DENSE GRADED SUBBASE	44.900	CYS
19	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,210.000	SYS
20	402-07432 HMA SURFACE, TYPE A	100.200	TON
21	402-07450 HMA WEDGE AND LEVEL, TYPE A	133.000	TON
22	402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE	18.100	TON
23	406-05521 ASPHALT FOR TACK COAT	2,420.000	SYS
24	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
25	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
26	604-91531 SIDEWALK, CONCRETE, 4 IN	220.600	SYS
27	605-06145 CURB AND GUTTER, B, CONCRETE	337.300	LFT
28	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	269.600	SYS
29	616-02320 GEOTEXTILES	588.600	SYS
30	616-06405 RIPRAP, REVETMENT	339.300	TON
31	621-06575 SODDING, NURSERY	471.600	SYS
32	628-09402 FIELD OFFICE, B	10.000	MOS
33	701-09665 PILE, STEEL PIPE, 0.375 IN, 14 IN	152.000	LFT
34	702-51005 CONCRETE, A, SUBSTRUCTURE	39.200	CYS
35	702-51863 FIELD DRILLED HOLE IN CONCRETE	330.000	EACH
36	702-92857 CONCRETE, C, SUBSTRUCTURE	26.400	CYS
37	703-06028 REINFORCING BARS	6,317.000	LBS
38	703-06029 REINFORCING BARS, EPOXY COATED	65,701.000	LBS
39	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	568.000	EACH
40	704-51002 CONCRETE, C, SUPERSTRUCTURE	173.800	CYS
41	706-06349 RAILING, TX	215.800	LFT
42	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	4.000	EACH
43	709-51821 SURFACE SEAL	LUMP	LUMP
44	711-51038 STRUCTURAL STEEL	LUMP	LUMP
45	715-05407 PIPE, END BENT DRAIN, 6 IN	184.000	LFT
46	715-11360 INSERTION VALVE, 12 IN.	2.000	EACH
47	715-98165 WATER MAIN, 12 IN	160.000	LFT
48	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
49	801-03290 CONSTRUCTION SIGN, C	3.000	EACH

CALL ORDER : 585

CONTRACT ID : B -30069-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHAB OR REPAIR		
50	801-03291 CONSTRUCTION SIGN, D	4.000	EACH
51	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	3,180.000	LFT
52	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	24.000	LFT
53	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
54	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
55	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
56	801-07119 BARRICADE, III-B	40.000	LFT
57	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	620.000	LFT

CALL ORDER : 591

CONTRACT ID : B -30918-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02271 HEADWALL, REMOVE	1.000	EACH
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	202-96133 PIPE, REMOVE	65.000	LFT
12	202-99187 FENCE, FARM FIELD, REMOVE	15.000	LFT
13	203-02000 EXCAVATION, COMMON	698.000	CYS
14	203-02020 EXCAVATION, UNCLASSIFIED	1,179.000	CYS
15	203-02070 BORROW	388.000	CYS
16	203-51223 EXCAVATION, WATERWAY	254.000	CYS
17	205-03371 SEDIMENT, REMOVE	1.000	CYS
18	205-06933 TEMPORARY INLET PROTECTION	1.000	EACH
19	205-06937 TEMPORARY SILT FENCE	1,850.000	LFT
20	205-09543 NO 2 STONE	100.000	TON
21	206-51220 EXCAVATION, WET	34.000	CYS
22	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	46.000	CYS
23	207-08265 SUBGRADE TREATMENT, TYPE IIA	2,480.000	SYS
24	207-08267 SUBGRADE TREATMENT, TYPE IIIA	40.000	SYS
25	211-02050 B BORROW	1,474.000	CYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	160.000	CYS
27	211-09267 STRUCTURAL BACKFILL, TYPE 4	10.800	CYS
28	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	660.000	TON
29	302-07455 DENSE GRADED SUBBASE	46.000	CYS
30	306-08034 MILLING, ASPHALT, 1 1/2 IN	955.000	SYS
31	402-07433 HMA SURFACE, TYPE B	305.000	TON
32	402-07438 HMA INTERMEDIATE, TYPE B	520.000	TON
33	406-05520 ASPHALT FOR TACK COAT	1.300	TON
34	601-01522 GUARDRAIL, TRANSITION TYPE TGB	3.000	EACH
35	601-06234 IMPACT ATTENUATOR, R1, W1, TL-2	1.000	EACH
36	601-06417 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R1, W1, TL-2	1.000	EACH
37	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
38	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
39	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	300.000	LFT
40	602-06729 BARRIER DELINEATOR	8.000	EACH
41	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	268.000	SYS
42	610-07487 HMA FOR APPROACHES, TYPE B	52.500	TON
43	615-06490 RIGHT OF WAY MARKER	4.000	EACH
44	615-06505 MONUMENT, B	2.000	EACH
45	616-02320 GEOTEXTILES	576.000	SYS
46	616-05688 RIPRAP, CLASS 1	351.000	TON
47	616-06405 RIPRAP, REVETMENT	27.000	TON
48	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
49	621-06559 MULCHED SEEDING, R	1,800.000	SYS

CALL ORDER : 591

CONTRACT ID : B -30918-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06567 WATER	5.000	KGAL
51	621-06574 SODDING	75.000	SYS
52	628-09402 FIELD OFFICE, B	6.000	MOS
53	701-09558 TEST PILE, INDICATOR, PRODUCTION	428.000	LFT
54	701-09560 TEST PILE, INDICATOR, RESTRIKE	4.000	EACH
55	701-09739 PILE SHOE, HP 12 X 53	24.000	EACH
56	701-51195 PILE, STEEL H, HP 12 IN X 53	1,932.000	LFT
57	701-97874 PILE, STEEL H, REINFORCED CONCRETE ENCASED, HP 12 IN X 53	132.000	LFT
58	703-06028 REINFORCING BARS	16,353.000	LBS
59	703-06029 REINFORCING BARS, EPOXY COATED	40,264.000	LBS
60	704-51002 CONCRETE, C, SUPERSTRUCTURE	200.000	CYS
61	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	3.000	EACH
62	706-51020 RAILING, CONCRETE, C	16.100	CYS
63	709-51821 SURFACE SEAL	LUMP	LUMP
64	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	220.000	LFT
65	720-45035 INLET, F7	1.000	EACH
66	720-45065 INLET, N12	1.000	EACH
67	721-43010 AUTOMATIC DRAINAGE GATE, 18 IN	1.000	EACH
68	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
69	801-06625 DETOUR ROUTE MARKER ASSEMBLY	29.000	EACH
70	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
71	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
72	801-07118 BARRICADE, III-A	96.000	LFT
73	801-07119 BARRICADE, III-B	144.000	LFT
74	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	20.000	LFT
75	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	16.000	SFT
76	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,580.000	LFT
77	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	315.000	LFT
78	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	40.000	LFT
79	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	200.000	LFT
80	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	240.000	LFT
81	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	15.000	EACH

CALL ORDER : 601

CONTRACT ID : B -31508-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	213.000	SYS
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	1,238.000	CYS
12	203-51223 EXCAVATION, WATERWAY	148.000	CYS
13	205-03371 SEDIMENT, REMOVE	85.000	CYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	15.000	TON
15	205-06934 TEMPORARY MULCH	0.300	TON
16	205-06936 TEMPORARY SEDIMENT TRAP	6.500	TON
17	205-08594 FILTER SOCK	1,400.000	LFT
18	205-09235 TEMPORARY FILTER BAG	60.000	DAY
19	205-09543 NO 2 STONE	45.000	TON
20	206-51215 EXCAVATION, X	20.000	CYS
21	206-51220 EXCAVATION, WET	524.000	CYS
22	206-51225 EXCAVATION, DRY	304.000	CYS
23	207-08263 SUBGRADE TREATMENT, TYPE IA	2,035.000	SYS
24	211-09268 STRUCTURAL BACKFILL, TYPE 5	386.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	538.000	TON
26	303-01180 COMPACTED AGGREGATE, NO. 53	259.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,401.000	SYS
28	402-07432 HMA SURFACE, TYPE A	141.000	TON
29	402-07434 HMA SURFACE, TYPE C	134.000	TON
30	402-07435 HMA INTERMEDIATE, TYPE A	240.000	TON
31	402-07439 HMA INTERMEDIATE, TYPE C	30.000	TON
32	402-07442 HMA BASE, TYPE C	71.000	TON
33	406-05521 ASPHALT FOR TACK COAT	3,374.000	SYS
34	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
35	601-06856 MODIFIED POSTS, NESTED GUARDRAIL	4.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
37	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	500.000	LFT
38	615-06490 RIGHT OF WAY MARKER	8.000	EACH
39	615-06495 RIGHT OF WAY MARKER, RESET	4.000	EACH
40	615-06500 MONUMENT, A	5.000	EACH
41	615-06530 BENCH MARK POST	1.000	EACH
42	616-02320 GEOTEXTILES	2,421.000	SYS
43	616-05688 RIPRAP, CLASS 1	568.000	TON
44	616-05689 RIPRAP, CLASS 2	34.000	TON
45	616-06405 RIPRAP, REVETMENT	535.000	TON
46	616-06451 RIPRAP, UNIFORM	98.000	TON
47	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
48	621-02770 EROSION CONTROL BLANKET	788.000	SYS
49	621-03909 SEED MIXTURE, NATIVE	3.000	LBS

CALL ORDER : 601

CONTRACT ID : B -31508-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
50	621-06545 FERTILIZER	0.250	TON
51	621-06553 SEED MIXTURE, R	91.000	LBS
52	621-06557 SEED MIXTURE, T	32.000	LBS
53	621-06565 MULCHING MATERIAL	1.000	TON
54	621-06567 WATER	7.000	KGAL
55	621-06574 SODDING	213.000	SYS
56	621-09399 SEED MIXTURE, WET MESIC	2.100	LBS
57	622-05639 PLANT, DECIDUOUS SHRUB, 18 TO 24 IN	170.000	EACH
58	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	24.000	EACH
59	622-05648 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN OR UNDER	4.000	EACH
60	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	6.000	EACH
61	622-98200 SIGN, DO NOT DISTURB	16.000	EACH
62	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
63	628-09402 FIELD OFFICE, B	12.000	MOS
64	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
65	628-11007 CELLULAR TELEPHONE/RADIO SERVICE, 750 MINUTES	12.000	MOS
66	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
67	723-11424 STRUCTURE, COATED REINFORCED CONCRETE,	70.000	LFT
68	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
69	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
70	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	5,621.000	LFT
71	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	48.000	LFT
72	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
73	801-06645 CONSTRUCTION SIGN, B	15.000	EACH
74	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
75	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	718.000	LFT
76	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	26.200	LFT
77	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
78	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	5.600	SFT
79	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,249.000	LFT
80	808-06716 LINE, REMOVE	2,206.000	LFT
81	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	90.000	LFT
82	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,396.000	LFT
83	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	14.000	EACH
84	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	14.000	EACH

CALL ORDER : 611

CONTRACT ID : B -33054-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	397.000	CYS
11	205-06937 TEMPORARY SILT FENCE	500.000	LFT
12	205-09543 NO 2 STONE	200.000	TON
13	206-51220 EXCAVATION, WET	75.000	CYS
14	207-08267 SUBGRADE TREATMENT, TYPE IIIA	612.000	SYS
15	211-02050 B BORROW	168.000	CYS
16	211-09266 STRUCTURAL BACKFILL, TYPE 3	475.000	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	270.000	TON
18	302-07455 DENSE GRADED SUBBASE	28.000	CYS
19	302-08562 COARSE AGGREGATE, NO 8	454.000	TON
20	306-08043 MILLING, TRANSITION	570.000	SYS
21	402-07432 HMA SURFACE, TYPE A	47.000	TON
22	402-07435 HMA INTERMEDIATE, TYPE A	79.000	TON
23	406-05521 ASPHALT FOR TACK COAT	570.000	SYS
24	601-02800 GUARDRAIL TRANSITION, TGT	4.000	EACH
25	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
26	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	162.200	SYS
27	610-07486 HMA FOR APPROACHES, TYPE A	35.000	TON
28	615-06505 MONUMENT, B	2.000	EACH
29	616-02320 GEOTEXTILES	195.000	SYS
30	616-06405 RIPRAP, REVETMENT	150.000	TON
31	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
32	621-06560 MULCHED SEEDING, U	485.000	SYS
33	621-06574 SODDING	11.000	SYS
34	628-09401 FIELD OFFICE, A	9.000	MOS
35	701-09558 TEST PILE, INDICATOR, PRODUCTION	152.000	LFT
36	701-09560 TEST PILE, INDICATOR, RESTRIKE	2.000	EACH
37	701-09739 PILE SHOE, HP 12 X 53	8.000	EACH
38	701-51195 PILE, STEEL H, HP 12 IN X 53	396.000	LFT
39	703-06029 REINFORCING BARS, EPOXY COATED	25,319.000	LBS
40	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	330.000	EACH
41	704-51002 CONCRETE, C, SUPERSTRUCTURE	80.000	CYS
42	706-06347 RAILING, STEEL CF-1	220.000	LFT
43	706-51020 RAILING, CONCRETE, C	11.800	CYS
44	707-11494 STRUCTURAL MEMBER, CONCRETE BOX BEAM, 21 IN. X 48 IN.	252.000	LFT
45	709-51821 SURFACE SEAL	LUMP	LUMP
46	731-93945 FACE PANELS, CONCRETE	2,306.000	SFT
47	731-93946 WALL ERECTION	2,306.000	SFT
48	731-93947 LEVELING PAD, CONCRETE	178.300	LFT
49	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP

CALL ORDER : 611

CONTRACT ID : B -33054-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
51	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	202.000	LFT
52	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,485.000	LFT
53	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
54	801-06645 CONSTRUCTION SIGN, B	27.000	EACH
55	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
56	801-07119 BARRICADE, III-B	12.000	LFT
57	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	310.000	LFT
58	807-06595 CONDUIT, PVC, 2 IN	224.000	LFT

CALL ORDER : 621

CONTRACT ID : B -33713-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	933.800	SYS
9	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
10	202-52710 SIDEWALK, CONCRETE, REMOVE	174.700	SYS
11	202-91385 INLET, REMOVE	4.000	EACH
12	203-02070 BORROW	26.400	CYS
13	203-51223 EXCAVATION, WATERWAY	227.000	CYS
14	205-03371 SEDIMENT, REMOVE	3.000	CYS
15	205-06933 TEMPORARY INLET PROTECTION	4.000	EACH
16	205-06937 TEMPORARY SILT FENCE	327.000	LFT
17	205-09543 NO 2 STONE	100.000	TON
18	206-09387 TURBIDITY CURTAIN	338.000	LFT
19	207-08263 SUBGRADE TREATMENT, TYPE IA	490.900	SYS
20	211-06467 AGGREGATE FOR END BENT BACKFILL	95.700	CYS
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	293.100	CYS
22	302-07455 DENSE GRADED SUBBASE	161.700	CYS
23	502-06329 PCCP, 12 IN	452.900	SYS
24	503-03489 RETROFITTED TIE BARS	107.000	EACH
25	503-05240 D-1 CONTRACTION JOINT	202.000	LFT
26	503-05310 TERMINAL JOINT	98.000	LFT
27	506-06333 PCCP PATCHING, FULL DEPTH	0.600	SYS
28	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
29	601-02241 GUARDRAIL, REMOVE	396.000	LFT
30	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
31	604-02007 SIDEWALK, CONCRETE, RECONSTRUCT	1.400	SYS
32	604-06070 SIDEWALK, CONCRETE	223.400	SYS
33	605-06090 CURB, INTEGRAL, CONCRETE	335.000	LFT
34	605-06215 CENTER CURB, D, CONCRETE	10.000	LFT
35	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	479.100	SYS
36	615-06490 RIGHT OF WAY MARKER	10.000	EACH
37	615-06505 MONUMENT, B	2.000	EACH
38	616-02320 GEOTEXTILES	714.900	SYS
39	616-06405 RIPRAP, REVETMENT	386.000	TON
40	619-93790 CLEAN AND EPOXY COAT EXISTING PILES	LUMP	LUMP
41	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
42	621-02770 EROSION CONTROL BLANKET	412.500	SYS
43	621-06545 FERTILIZER	0.100	TON
44	621-06557 SEED MIXTURE, T	412.500	LBS
45	621-06560 MULCHED SEEDING, U	412.500	SYS
46	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	5.000	EACH
47	628-09402 FIELD OFFICE, B	6.000	MOS
48	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
49	628-09409 MOBILE INTERNET SERVICE	6.000	MOS

CALL ORDER : 621

CONTRACT ID : B -33713-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT		
50	701-11463 PILE, STEEL H, HP 10 IN. X 57	448.000	LFT
51	702-51005 CONCRETE, A, SUBSTRUCTURE	88.200	CYS
52	702-92857 CONCRETE, C, SUBSTRUCTURE	120.400	CYS
53	703-06028 REINFORCING BARS	9,986.000	LBS
54	703-06029 REINFORCING BARS, EPOXY COATED	271,048.000	LBS
55	704-51002 CONCRETE, C, SUPERSTRUCTURE	761.700	CYS
56	704-51106 DECK DRAIN	2.000	EACH
57	706-06349 RAILING, TX	451.000	LFT
58	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	4.000	EACH
59	707-09865 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 36 IN X 49 IN	1,574.000	LFT
60	709-51821 SURFACE SEAL	LUMP	LUMP
61	710-09158 PATCHING CONCRETE STRUCTURES	50.000	SFT
62	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	108.000	LFT
63	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	58.000	LFT
64	715-05407 PIPE, END BENT DRAIN, 6 IN	200.000	LFT
65	715-46000 PIPE END SECTION, DIA 12"	1.000	EACH
66	715-46005 PIPE END SECTION, DIA 15"	1.000	EACH
67	715-46020 PIPE END SECTION, DIA 24"	1.000	EACH
68	715-92537 PIPE, PVC, 8 IN	7.000	LFT
69	720-44296 INLET, CAP	1.000	EACH
70	720-45045 INLET, J10	3.000	EACH
71	720-45055 INLET, M10	1.000	EACH
72	720-45410 MANHOLE, C4	1.000	EACH
73	724-51925 STRUCTURAL EXPANSION JOINT, SS	39.000	LFT
74	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
75	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
76	801-06625 DETOUR ROUTE MARKER ASSEMBLY	27.000	EACH
77	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
78	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
79	801-07118 BARRICADE, III-A	180.000	LFT
80	801-07119 BARRICADE, III-B	24.000	LFT
81	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	180.000	LFT
82	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	15.000	LFT
83	802-91122 SIGN, GROUND MOUNTED, RESET	1.000	EACH
84	807-04744 LIGHTING	LUMP	LUMP
85	808-02157 PAVEMENT MESSAGE MARKING, REMOVE	2.000	EACH
86	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	220.000	LFT
87	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	878.000	LFT
88	808-10053 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT,	2.000	EACH

CALL ORDER : 631

CONTRACT ID : B -33779-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	202-99187 FENCE, FARM FIELD, REMOVE	679.000	LFT
11	203-02000 EXCAVATION, COMMON	900.000	CYS
12	203-02070 BORROW	330.000	CYS
13	203-51223 EXCAVATION, WATERWAY	675.000	CYS
14	205-06932 TEMPORARY CHECK DAM, STRAW BALES	12.000	LFT
15	205-06936 TEMPORARY SEDIMENT TRAP	18.000	TON
16	205-06937 TEMPORARY SILT FENCE	1,084.000	LFT
17	205-08517 ROCK FILTER BERM	94.000	TON
18	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	45.000	CYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,722.000	SYS
20	211-09267 STRUCTURAL BACKFILL, TYPE 4	10.000	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	659.000	TON
22	302-07455 DENSE GRADED SUBBASE	31.000	CYS
23	304-07493 WIDENING WITH HMA, TYPE B	22.000	TON
24	306-08034 MILLING, ASPHALT, 1 1/2 IN	244.000	SYS
25	402-07433 HMA SURFACE, TYPE B	138.000	TON
26	402-07438 HMA INTERMEDIATE, TYPE B	197.000	TON
27	402-07451 HMA WEDGE AND LEVEL, TYPE B	20.000	TON
28	406-05520 ASPHALT FOR TACK COAT	1.000	TON
29	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
30	601-02241 GUARDRAIL, REMOVE	160.500	LFT
31	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
32	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
33	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	156.250	LFT
34	603-06042 FENCE, FARM FIELD, BARBED WIRE	680.000	LFT
35	603-95217 FENCE GATE, FARM FIELD, 47 IN X 30FT	1.000	EACH
36	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	182.000	SYS
37	615-06500 MONUMENT, A	2.000	EACH
38	616-02320 GEOTEXTILES	638.000	SYS
39	616-06405 RIPRAP, REVETMENT	426.000	TON
40	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
41	621-06545 FERTILIZER	1.000	TON
42	621-06553 SEED MIXTURE, R	86.000	LBS
43	621-06557 SEED MIXTURE, T	76.000	LBS
44	621-06565 MULCHING MATERIAL	3.000	TON
45	621-06567 WATER	1.000	KGAL
46	621-06575 SODDING, NURSERY	126.000	SYS
47	628-09401 FIELD OFFICE, A	6.000	MOS
48	701-09665 PILE, STEEL PIPE, 0.375 IN, 14 IN	1,112.000	LFT
49	701-09677 PILE STEEL PIPE EPOXY COATED 0.375 IN, 14 IN	123.000	LFT

CALL ORDER : 631

CONTRACT ID : B -33779-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	703-06029 REINFORCING BARS, EPOXY COATED	35,777.000	LBS
51	704-51002 CONCRETE, C, SUPERSTRUCTURE	138.100	CYS
52	706-06344 RAILING, STEEL TS-1	150.000	LFT
53	709-51821 SURFACE SEAL	LUMP	LUMP
54	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	166.000	LFT
55	715-46005 PIPE END SECTION, DIA 15"	4.000	EACH
56	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
57	801-06625 DETOUR ROUTE MARKER ASSEMBLY	14.000	EACH
58	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
59	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
60	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
61	801-07118 BARRICADE, III-A	48.000	LFT
62	801-07119 BARRICADE, III-B	60.000	LFT
63	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	18.000	LFT
64	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	12.000	SFT
65	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	1,400.000	LFT
66	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	1,400.000	LFT

CALL ORDER : 671

CONTRACT ID : M -31234-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	601-01522 GUARDRAIL, TRANSITION TYPE TGB	1.000	EACH
7	601-03452 EXCAVATION OF DAMAGED STEEL BEAM GUARDRAIL BURIED END	1.000	EACH
8	601-03456 GUARDRAIL POST, WOOD TYPE W5	10.000	EACH
9	601-03457 GUARDRAIL W THRIE BEAM RAIL SECTION, 12FT-6 IN	10.000	EACH
10	601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION	3.000	EACH
11	601-03469 W BEAM BACK UP PLATE, STEEL	6.000	EACH
12	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	3.000	EACH
13	601-03492 GUARDRAIL, MISCELLANEOUS MATERIAL, AND LABOR FOR REPAIR	LUMP	LUMP
14	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
15	601-06798 TIMBER BLOCK	120.000	EACH
16	601-07179 ET_2000 OS UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL	30.000	EACH
17	601-07564 SOIL TUBE AND PLATE FOR END TREATMENT, OS OR MS	1.000	EACH
18	601-08132 GUARDRAIL, THRIE BEAM, BLOCKOUT, STEEL	5.000	EACH
19	601-52501 GUARDRAIL POST	120.000	EACH
20	601-52501 GUARDRAIL POST	6.000	EACH
21	601-52501 GUARDRAIL POST	5.000	EACH
22	601-52501 GUARDRAIL POST	50.000	EACH
23	601-52501 GUARDRAIL POST	1.000	EACH
24	601-52501 GUARDRAIL POST	120.000	EACH
25	601-62070 GUARDRAIL, STEEL BEAM, GALVANIZED	3,500.000	LFT
26	601-62080 GUARDRAIL, STEEL BEAM, CURVED SECTION, GALVANIZED	100.000	LFT
27	601-62540 GUARDRAIL POST, PLUMB	200.000	EACH
28	601-91511 GUARDRAIL POST, W4, 8 IN. X 8 IN.	1.000	EACH
29	601-91542 GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	1.000	EACH
30	601-91575 GUARDRAIL BLOCK, 6 IN. X 8 IN., B2	1.000	EACH
31	601-91576 GUARDRAIL BLOCK, 6 IN. X 8 IN., B3	1.000	EACH
32	601-91649 GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	1.000	EACH
33	601-97054 GUARDRAIL BRACKET, STEEL, OFFSET	1.000	EACH
34	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
35	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 681

CONTRACT ID : M -31235-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	601-01522 GUARDRAIL, TRANSITION TYPE TGB	1.000	EACH
7	601-03452 EXCAVATION OF DAMAGED STEEL BEAM GUARDRAIL BURIED END	2.000	EACH
8	601-03456 GUARDRAIL POST, WOOD TYPE W5	3.000	EACH
9	601-03457 GUARDRAIL W THRIE BEAM RAIL SECTION, 12FT-6 IN	2.000	EACH
10	601-03460 GUARDRAIL, CHAN 6.7 LBS PER LFT., LABOR ONLY	50.000	LFT
11	601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION	2.000	EACH
12	601-03469 W BEAM BACK UP PLATE, STEEL	20.000	EACH
13	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	4.000	EACH
14	601-03492 GUARDRAIL, MISCELLANEOUS MATERIAL, AND LABOR FOR REPAIR	LUMP	LUMP
15	601-03492 GUARDRAIL, MISCELLANEOUS MATERIAL, AND LABOR FOR REPAIR	LUMP	LUMP
16	601-03492 GUARDRAIL, MISCELLANEOUS MATERIAL, AND LABOR FOR REPAIR	LUMP	LUMP
17	601-03492 GUARDRAIL, MISCELLANEOUS MATERIAL, AND LABOR FOR REPAIR	LUMP	LUMP
18	601-03492 GUARDRAIL, MISCELLANEOUS MATERIAL, AND LABOR FOR REPAIR	LUMP	LUMP
19	601-03492 GUARDRAIL, MISCELLANEOUS MATERIAL, AND LABOR FOR REPAIR	LUMP	LUMP
20	601-03492 GUARDRAIL, MISCELLANEOUS MATERIAL, AND LABOR FOR REPAIR	LUMP	LUMP
21	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
22	601-06798 TIMBER BLOCK	100.000	EACH
23	601-07179 ET_2000 OS UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL	15.000	EACH
24	601-07564 SOIL TUBE AND PLATE FOR END TREATMENT, OS OR MS	9.000	EACH
25	601-08131 GUARDRAIL, THRIE BEAM, BACKUP PLATE, STEEL	1.000	EACH
26	601-08132 GUARDRAIL, THRIE BEAM, BLOCKOUT, STEEL	1.000	EACH
27	601-52501 GUARDRAIL POST	50.000	EACH
28	601-52501 GUARDRAIL POST	6.000	EACH
29	601-52501 GUARDRAIL POST	75.000	EACH
30	601-52501 GUARDRAIL POST	1.000	EACH
31	601-52501 GUARDRAIL POST	150.000	EACH
32	601-52501 GUARDRAIL POST	25.000	EACH
33	601-62070 GUARDRAIL, STEEL BEAM, GALVANIZED	4,800.000	LFT
34	601-62080 GUARDRAIL, STEEL BEAM, CURVED SECTION, GALVANIZED	300.000	LFT
35	601-62100 GUARDRAIL POST, STEEL, INSTALL	5.000	EACH
36	601-62510 GUARDRAIL BREAKAWAY CABLE TERMINAL, MICHIGAN END SHOE	1.000	EACH
37	601-62540 GUARDRAIL POST, PLUMB	350.000	EACH
38	601-90678 CONCRETE, A, BURIED END SECTION	1.000	CYS
39	601-91649 GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	1.000	EACH
40	601-91653 GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	1.000	EACH
41	601-92271 GUARDRAIL POST BRACKET, GALVANIZED, LABOR ONLY	10.000	EACH
42	601-95342 GUARDRAIL SPLICE PLATE, C, GALVANIZED	2.000	EACH
43	601-97054 GUARDRAIL BRACKET, STEEL, OFFSET	10.000	EACH
44	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
45	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 691

CONTRACT ID : M -35014-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 202-04486	LITTER, REMOVE	25.000	MILE
4 202-04486	LITTER, REMOVE	25.000	MILE
5 202-04486	LITTER, REMOVE	25.000	MILE
6 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
7 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
8 623-04886	MOWING, CYCLE NO 3	1.000	CYCL

CALL ORDER : 721

CONTRACT ID : T -33218-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 DISTRICT SIGNAL PROJECT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02279 CURB AND GUTTER, REMOVE	52.000	LFT
9	202-52710 SIDEWALK, CONCRETE, REMOVE	35.000	SYS
10	604-06070 SIDEWALK, CONCRETE	35.000	SYS
11	604-07894 CURB RAMP, CONCRETE, A	173.800	SYS
12	604-07896 CURB RAMP, CONCRETE, B	13.300	SYS
13	604-07897 CURB RAMP, CONCRETE, C	32.200	SYS
14	604-07900 CURB RAMP, CONCRETE, F	15.780	SYS
15	605-06120 CURB, CONCRETE	125.000	LFT
16	605-06140 CURB AND GUTTER, CONCRETE	79.000	LFT
17	621-06574 SODDING	5.000	SYS
18	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
19	628-09402 FIELD OFFICE, B	9.000	MOS
20	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	18.000	MOS
21	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
22	801-03290 CONSTRUCTION SIGN, C	16.000	EACH
23	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
25	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	167.900	SFT
26	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	46.000	SFT
27	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	300.000	SFT
28	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	3.000	EACH
29	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	4.000	EACH
30	805-01842 HANDHOLE, SIGNAL	13.000	EACH
31	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	2,465.000	LFT
32	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
33	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	8.000	EACH
34	805-02658 CABLE, COAXIAL	179.000	LFT
35	805-03174 SYSTEM MASTER AND RELATED EQUIPMENT	LUMP	LUMP
36	805-08464 RADIO, INTERCONNECT	3.000	EACH
37	805-09088 RADIO, OMNI ANTENNA	1.000	EACH
38	805-09089 RADIO, YAGI ANTENNA	2.000	EACH
39	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	2.000	EACH
40	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000	EACH
41	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	24.000	EACH
42	805-78370 PEDESTRIAN PUSH BUTTON	24.000	EACH
43	805-78415 SPAN, CATENARY, AND TETHER	12.000	EACH
44	805-78420 DISCONNECT HANGER	12.000	EACH
45	805-78445 SIGNAL SERVICE	3.000	EACH
46	805-78467 SIGNAL CABLE, 3C/8GA	88.000	LFT
47	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	7,140.000	LFT
48	805-78480 SIGNAL CABLE, 3C/14GA	3,672.000	LFT
49	805-78485 SIGNAL CABLE, 5C/14GA	3,189.000	LFT

CALL ORDER : 721

CONTRACT ID : T -33218-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT SIGNAL PROJECT		
50	805-78490 SIGNAL CABLE, 7C/14GA	1,433.000	LFT
51	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	2,664.000	LFT
52	805-78785 SIGNAL DETECTOR HOUSING	16.000	EACH
53	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,360.000	LFT
54	805-78925 CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
55	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
56	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	9.000	EACH
57	808-06368 TRANSVERSE MARKING, REMOVE	1,420.000	LFT
58	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	570.000	LFT
59	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	570.000	LFT
60	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	280.000	LFT
61	808-10056 TRANSVERSE MARKING, MULTI-COMPONENT,	1,140.000	LFT
62	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	16.000	EACH
63	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH

CALL ORDER : 731

CONTRACT ID : T -33244-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-04890 WELL	1.000	EACH
10	202-05545 REGULATED MATERIALS, DISPOSE, C	1,094.000	CYS
11	202-05550 REGULATED MATERIALS, REMOVE, C	1,094.000	CYS
12	202-05555 REGULATED MATERIALS, TRANSPORT, C	1,094.000	CYS
13	202-07603 TESTING FOR WASTES, C	4.000	EACH
14	203-02000 EXCAVATION, COMMON	194.000	CYS
15	203-02100 EXCAVATION, PEAT	1,220.000	CYS
16	205-03371 SEDIMENT, REMOVE	10.000	CYS
17	205-06937 TEMPORARY SILT FENCE	655.000	LFT
18	205-09543 NO 2 STONE	100.000	TON
19	206-51817 SHEET PILING, STEEL	870.000	SFT
20	207-08264 SUBGRADE TREATMENT, TYPE II	2,025.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	55.000	SYS
22	211-02050 B BORROW	1,470.000	CYS
23	211-09264 STRUCTURAL BACKFILL, TYPE 1	81.000	CYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	598.000	TON
25	303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS	100.000	TON
26	402-07432 HMA SURFACE, TYPE A	65.000	TON
27	402-07433 HMA SURFACE, TYPE B	77.000	TON
28	402-07435 HMA INTERMEDIATE, TYPE A	107.000	TON
29	402-07438 HMA INTERMEDIATE, TYPE B	129.000	TON
30	402-07441 HMA BASE, TYPE B	206.000	TON
31	406-05520 ASPHALT FOR TACK COAT	0.690	TON
32	506-06333 PCCP PATCHING, FULL DEPTH	120.000	SYS
33	604-07894 CURB RAMP, CONCRETE, A	41.000	SYS
34	604-07896 CURB RAMP, CONCRETE, B	60.000	SYS
35	604-07902 CURB RAMP, CONCRETE, H	13.000	SYS
36	604-07903 CURB RAMP, CONCRETE, K	125.000	SYS
37	604-07904 CURB RAMP, CONCRETE, L	5.000	SYS
38	604-91531 SIDEWALK, CONCRETE, 4 IN	598.000	SYS
39	605-06090 CURB, INTEGRAL, CONCRETE	450.000	LFT
40	605-06105 CURB, INTEGRAL, CONCRETE, MODIFIED	24.000	LFT
41	605-06120 CURB, CONCRETE	36.000	LFT
42	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	828.000	LFT
43	610-09108 PCCP FOR APPROACHES, 9 IN	55.000	SYS
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
45	621-06545 FERTILIZER	0.200	TON
46	621-06554 SEED MIXTURE, U	75.000	LBS
47	621-06557 SEED MIXTURE, T	105.000	LBS
48	621-06565 MULCHING MATERIAL	1.000	TON
49	621-06567 WATER	39.000	KGAL

CALL ORDER : 731

CONTRACT ID : T -33244-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
50	621-06570 TOPSOIL	52.000	CYS
51	621-06575 SODDING, NURSERY	465.000	SYS
52	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	8.000	EACH
53	628-09402 FIELD OFFICE, B	10.000	MOS
54	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	250.000	LFT
55	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	5.000	LFT
56	715-09064 VIDEO INSPECTION FOR PIPE	257.000	LFT
57	720-44296 INLET, CAP	1.000	EACH
58	720-45045 INLET, J10	4.000	EACH
59	720-45055 INLET, M10	6.000	EACH
60	720-45410 MANHOLE, C4	2.000	EACH
61	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	6.000	EACH
62	801-01505 TEMPORARY PAVEMENT MESSAGE MARKING, (ONLY)	5.000	EACH
63	801-03290 CONSTRUCTION SIGN, C	1.000	EACH
64	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	4,705.000	LFT
65	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	900.000	LFT
66	801-06640 CONSTRUCTION SIGN, A	92.000	EACH
67	801-06645 CONSTRUCTION SIGN, B	66.000	EACH
68	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
69	801-07119 BARRICADE, III-B	90.000	LFT
70	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN	130.000	LFT
71	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	150.000	LFT
72	801-94295 SIGNAL HEAD, RELOCATE	24.000	EACH
73	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	67.000	LFT
74	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	105.376	SFT
75	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	267.900	SFT
76	802-99045 SIGN REMOUNTING	26.000	EACH
77	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	7.000	EACH
78	805-01842 HANDHOLE, SIGNAL	29.000	EACH
79	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	2.000	EACH
80	805-01893 MAINTAINING TRAFFIC SIGNAL	LUMP	LUMP
81	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
82	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	48.000	EACH
83	805-02262 FLASHER INSTALLATION	LUMP	LUMP
84	805-02373 SIGNAL INTERCONNECT CABLE, FIBER OPTIC	9,200.000	LFT
85	805-02658 CABLE, COAXIAL	5,670.000	LFT
86	805-03978 EMERGENCY VEHICLE PREEMPTION DETECTOR,	1.000	EACH
87	805-03979 EMERGENCY VEHICLE PREEMPTION DETECTOR,	6.000	EACH
88	805-04133 SIGNAL PEDESTAL, 12FT	4.000	EACH
89	805-04782 VIDEO VEHICLE DETECTOR SYSTEM	7.000	EACH
90	805-05870 SIGNAL SUPPORT FOUNDATION	2.000	EACH
91	805-06997 CAMERA	2.000	EACH
92	805-09343 ITS	1.000	EACH
93	805-09773 SIGNAL POLE	2.000	EACH
94	805-11375 SIGNAL CANTILEVER STRUCTURE, SIGNAL	5.000	EACH
95	805-11376 SIGNAL CANTILEVER STRUCTURE, SIGNAL	8.000	EACH
96	805-11377 SIGNAL CANTILEVER STRUCTURE, SIGNAL	7.000	EACH
97	805-11378 SIGNAL CANTILEVER STRUCTURE, SIGNAL	2.000	EACH
98	805-11383 SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT	20.000	EACH

CALL ORDER : 731

CONTRACT ID : T -33244-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
99	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT	2.000 EACH
100	805-11430	SIGNAL CANTILEVER STRUCTURE, POLE SECTION 2,	20.000 EACH
101	805-11431	SIGNAL CANTILEVER STRUCTURE, POLE SECTION 2,	2.000 EACH
102	805-11434	SIGNAL CANTILEVER STRUCTURE, COMBINATION	8.000 EACH
103	805-11435	SIGNAL CANTILEVER STRUCTURE, COMBINATION	7.000 EACH
104	805-11436	SIGNAL CANTILEVER STRUCTURE, COMBINATION	5.000 EACH
105	805-78010	CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000 EACH
106	805-78106	CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000 EACH
107	805-78109	CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	6.000 EACH
108	805-78205	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	52.000 EACH
109	805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	5.000 EACH
110	805-78370	PEDESTRIAN PUSH BUTTON	48.000 EACH
111	805-78415	SPAN, CATENARY, AND TETHER	2.000 EACH
112	805-78420	DISCONNECT HANGER	2.000 EACH
113	805-78445	SIGNAL SERVICE	6.000 EACH
114	805-78467	SIGNAL CABLE, 3C/8GA	700.000 LFT
115	805-78480	SIGNAL CABLE, 3C/14GA	4,840.000 LFT
116	805-78485	SIGNAL CABLE, 5C/14GA	7,260.000 LFT
117	805-78490	SIGNAL CABLE, 7C/14GA	4,000.000 LFT
118	805-78510	SIGNAL CABLE, 2C/16GA., SHIELDED	745.000 LFT
119	805-78520	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	LUMP LUMP
120	805-78906	SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 12 FT	1.000 EACH
121	805-78925	CONTROLLER CABINET FOUNDATION, P1	6.000 EACH
122	805-81060	SIGNAL STRAIN POLE, STEEL, 36 FT	1.000 EACH
123	805-91615	EMERGENCY PRE-EMPTOR	1.000 EACH
124	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000 EACH
125	807-02191	HANDHOLE, LIGHTING	1.000 EACH
126	807-02426	WIRE, THW, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	20.000 LFT
127	807-02579	MAST ARM, 15FT	2.000 EACH
128	807-02784	LUMINAIRE, MAST ARM, 20 FT	1.000 EACH
129	807-04940	MAST ARM	1.000 EACH
130	807-04940	MAST ARM	3.000 EACH
131	807-04940	MAST ARM	1.000 EACH
132	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN	2,975.000 LFT
133	807-86615	LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	1.000 EACH
134	807-86889	CABLE, POLE CIRCUIT THWH, NO10 COPPER, STRANDED, 1/C	160.000 LFT
135	807-86910	CONNECTOR KIT, UNFUSED	1.000 EACH
136	807-86915	CONNECTOR KIT, FUSED	1.000 EACH
137	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	1.000 EACH
138	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	1.000 EACH
139	807-86930	INSULATION LINK, NON-WATERPROOFED	3.000 EACH
140	807-86935	INSULATION LINK, WATERPROOFED	4.000 EACH
141	807-86950	SIGN UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	1.000 EACH
142	808-02066	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE,	205.000 LFT
143	808-06368	TRANSVERSE MARKING, REMOVE	3,100.000 LFT
144	808-06716	LINE, REMOVE	6,000.000 LFT
145	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN	50.000 LFT
146	808-75205	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	624.000 LFT
147	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,890.000 LFT

CALL ORDER : 731

CONTRACT ID : T -33244-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
148 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	810.000	LFT
149 808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	2,896.000	LFT
150 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	9.000	EACH
151 808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	6.000	EACH
152 808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN	120.000	LFT

CALL ORDER : 741

CONTRACT ID : T -33882-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	205-02459 EROSION CONTROL	LUMP	LUMP
9	628-09402 FIELD OFFICE, B	3.000	MOS
10	801-02595 CONTROLLER, RESET TIMING	1.000	EACH
11	801-03290 CONSTRUCTION SIGN, C	11.000	EACH
12	801-06640 CONSTRUCTION SIGN, A	34.000	EACH
13	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
15	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
16	805-01579 MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	LUMP	LUMP
17	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
18	805-03793 DETECTOR CARD RACK AND DETECTOR MODULES	22.000	EACH
19	805-03978 EMERGENCY VEHICLE PREEMPTION DETECTOR,	42.000	EACH
20	805-03979 EMERGENCY VEHICLE PREEMPTION DETECTOR,	22.000	EACH
21	805-03980 EMERGENCY VEHICLE CONFIRMATION LIGHT KIT	86.000	EACH
22	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	2.000	EACH
23	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	528.000	LFT
24	805-78480 SIGNAL CABLE, 3C/14GA	11,646.000	LFT
25	805-78490 SIGNAL CABLE, 7C/14GA	215.000	LFT
26	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	80.000	LFT
27	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	176.000	LFT
28	805-91615 EMERGENCY PRE-EMPTOR	20.000	EACH
29	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	1.000	EACH
30	809-03983 PHASE SELECTORS	22.000	EACH
31	809-04982 CABLE	11,646.000	LFT

CALL ORDER : 751

CONTRACT ID : T -34232-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT MARKINGS		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
7	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	6.000	MOS
8	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
9	801-06710 FLASHING ARROW SIGN	90.000	DAY
10	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
11	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
12	801-92448 CONSTRUCTION SIGNS, MOBILE	120.000	DAY
13	808-75994 PRISMATIC REFLECTOR	29,626.000	EACH
14	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,200.000	EACH
15	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2,690.000	EACH

CALL ORDER : 761

CONTRACT ID : T -34473-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
7	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	2.000	MOS
8	628-09409 MOBILE INTERNET SERVICE	2.000	MOS
9	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	2.000	MOS
10	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
11	801-06710 FLASHING ARROW SIGN	50.000	DAY
12	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
13	801-92448 CONSTRUCTION SIGNS, MOBILE	200.000	DAY
14	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	7,515.500	LFT
15	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	1,001.000	EACH
16	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	3,655.200	SFT
17	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	402.500	SFT

CALL ORDER : 771

CONTRACT ID : T -34678-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-92607 SIGN POST, CHANNEL, REMOVE	191.000	EACH
9	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
10	802-04089 SIGN, SHEET, REMOVE	1,456.000	EACH
11	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	2,710.000	LFT
12	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	22.000	LFT
13	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	2,443.000	SFT
14	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	2,438.000	SFT
15	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	1,795.000	SFT
16	802-99045 SIGN REMOUNTING	64.000	EACH

