

CALL ORDER : 120

CONTRACT ID : IR-30700-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	113-01614 PARTNERING OVERHEAD	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02272 PAVED SIDE DITCH, REMOVE	721.000	LFT
13	202-96133 PIPE, REMOVE	149.000	LFT
14	202-96531 FENCE, RIGHT-OF-WAY, REMOVE	8,980.000	LFT
15	203-02000 EXCAVATION, COMMON	41,849.000	CYS
16	203-02000 EXCAVATION, COMMON	2,754.000	CYS
17	203-02070 BORROW	121,876.000	CYS
18	205-03371 SEDIMENT, REMOVE	1,000.000	CYS
19	205-06930 SPLASHPAD, RIPRAP	6.000	TON
20	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	205.000	TON
21	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
22	205-06936 TEMPORARY SEDIMENT TRAP	1,655.000	TON
23	205-06937 TEMPORARY SILT FENCE	4,082.000	LFT
24	205-06938 TEMPORARY SLOPE DRAIN	210.000	LFT
25	205-09543 NO 2 STONE	200.000	TON
26	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	188.400	CYS
27	207-08263 SUBGRADE TREATMENT, TYPE IA	48,503.640	SYS
28	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,300.000	SYS
29	211-02050 B BORROW	3,450.200	CYS
30	211-02050 B BORROW	2,754.000	CYS
31	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,142.400	CYS
32	211-09265 STRUCTURAL BACKFILL, TYPE 2	149.400	CYS
33	211-09266 STRUCTURAL BACKFILL, TYPE 3	4,504.000	CYS
34	211-09268 STRUCTURAL BACKFILL, TYPE 5	105.300	CYS
35	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	36.400	CYS
36	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	765.740	TON
37	302-07455 DENSE GRADED SUBBASE	229.700	CYS
38	303-01180 COMPACTED AGGREGATE, NO. 53	4,633.800	TON
39	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
40	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	3,207.630	TON
41	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	5,656.480	TON
42	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	3,548.520	TON
43	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	5,509.990	TON
44	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	3,949.370	TON
45	402-07432 HMA SURFACE, TYPE A	152.720	TON
46	402-07435 HMA INTERMEDIATE, TYPE A	248.010	TON
47	406-05520 ASPHALT FOR TACK COAT	30.020	TON
48	502-06457 PCCP, 9 IN	1,100.000	SYS
49	503-05240 D-1 CONTRACTION JOINT	795.000	LFT

CALL ORDER : 120

CONTRACT ID : IR-30700-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
50	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
51	601-05999 CURVED TERMINAL END	2.000	EACH
52	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
53	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	3.000	EACH
54	601-94689 GUARDRAIL END TREATMENT, OS	6.000	EACH
55	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	575.000	LFT
56	602-06729 BARRIER DELINEATOR	12.000	EACH
57	603-06040 FENCE, FARM FIELD, 47 IN	11,471.900	LFT
58	603-97461 TEMPORARY FENCE	1,800.000	LFT
59	605-06120 CURB, CONCRETE	788.000	LFT
60	605-06140 CURB AND GUTTER, CONCRETE	5,178.000	LFT
61	605-06145 CURB AND GUTTER, B, CONCRETE	97.000	LFT
62	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	57.000	LFT
63	605-06160 CURB AND GUTTER, B, CONCRETE, MODIFIED	1,472.000	LFT
64	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	278.000	SYS
65	615-06490 RIGHT OF WAY MARKER	8.000	EACH
66	615-06505 MONUMENT, B	4.000	EACH
67	615-06530 BENCH MARK POST	1.000	EACH
68	616-02320 GEOTEXTILES	4,587.000	SYS
69	616-05688 RIPRAP, CLASS 1	143.000	TON
70	616-06405 RIPRAP, REVETMENT	2,533.000	TON
71	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
72	621-06545 FERTILIZER	16.600	TON
73	621-06553 SEED MIXTURE, R	6,210.000	LBS
74	621-06557 SEED MIXTURE, T	1,343.000	LBS
75	621-06565 MULCHING MATERIAL	118.600	TON
76	621-06574 SODDING	11,014.000	SYS
77	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
78	628-09403 FIELD OFFICE, C	14.000	MOS
79	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	56.000	MOS
80	628-11068 CELLULAR TELEPHONE/RADIO	4.000	EACH
81	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
82	701-08122 PILE, STEEL PIPE, 0.375", 14	2,002.000	LFT
83	701-09557 TEST PILE, DYNAMIC, PRODUCTION	139.000	LFT
84	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
85	701-09679 CONICAL PILE TIP, 14 IN	36.000	EACH
86	702-51005 CONCRETE, A, SUBSTRUCTURE	92.200	CYS
87	702-51015 CONCRETE, B, FOOTINGS	66.700	CYS
88	703-06028 REINFORCING BARS	19,280.000	LBS
89	703-06029 REINFORCING BARS, EPOXY COATED	122,817.000	LBS
90	704-51002 CONCRETE, C, SUPERSTRUCTURE	341.500	CYS
91	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	4.000	EACH
92	706-09960 RAILING, CONCRETE, FC	373.000	LFT
93	706-92612 RAILING, CONCRETE, C, MODIFIED	221.500	LFT
94	707-07605 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 54 IN X 48 IN	1,083.000	LFT
95	709-51821 SURFACE SEAL	LUMP	LUMP
96	711-51070 ANCHOR PLATE, AP 1	24.000	EACH
97	714-11174 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	97.000	LFT
98	714-11498 STRUCTURE EXTENSION, REINFORCED CONCRETE BOX	40.000	LFT

CALL ORDER : 120

CONTRACT ID : IR-30700-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
99	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	84.000	LFT
100	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	14,286.000	LFT
101	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	1,850.000	LFT
102	715-05124 PIPE, TYPE 1, CIRCULAR, 27 IN	92.000	LFT
103	715-05127 PIPE, TYPE 1 CIRCULAR 42 IN	126.000	LFT
104	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,876.000	LFT
105	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	164.000	LFT
106	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	16.000	LFT
107	715-05422 PIPE, SLOTTED DRAIN, 12 IN	20.000	LFT
108	715-05842 CONCRETE ANCHOR 42 IN	2.000	EACH
109	715-06004 CONCRETE ANCHOR, 48 IN	2.000	EACH
110	715-06939 CONCRETE ANCHOR MIN AREA 29.5 SF	2.000	EACH
111	715-08162 PIPE, TYPE 1 DEFORMED MIN AREA 8.8 SF	82.000	LFT
112	715-08177 PIPE, TYPE 1 DEFORMED MIN AREA 10.2 SF	108.000	LFT
113	715-08179 CONCRETE ANCHOR MIN AREA 10.2 SF	2.000	EACH
114	715-09064 VIDEO INSPECTION FOR PIPE	2,106.000	LFT
115	715-09992 PIPE, TYPE 1 DEFORMED MIN AREA 29.5 SF	109.000	LFT
116	715-11500 CONCRETE ANCHOR, MIN. AREA 82.0 SFT.	2.000	EACH
117	715-11508 PIPE, TYPE 1, DEFORMED, MIN. AREA 82.0 SFT.	234.000	LFT
118	715-11509 CONCRETE ANCHOR, MIN. AREA 8.8 SFT.	2.000	EACH
119	715-46000 PIPE END SECTION, 12 IN	7.000	EACH
120	715-46010 PIPE END SECTION, 18 IN	1.000	EACH
121	715-46020 PIPE END SECTION, 24 IN	1.000	EACH
122	715-46025 PIPE END SECTION, 27 IN	2.000	EACH
123	715-46040 PIPE END SECTION, 36 IN	2.000	EACH
124	716-07637 PIPE INSTALLATION, TRENCHLESS, 48 IN	255.000	LFT
125	718-06528 OUTLET PROTECTOR, 1	24.000	EACH
126	718-06529 OUTLET PROTECTOR, 2	6.000	EACH
127	718-06531 OUTLET PROTECTOR, 3	8.000	EACH
128	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
129	718-52610 AGGREGATE FOR UNDERDRAINS	1,139.000	CYS
130	718-99153 GEOTEXTILES FOR UNDERDRAIN	2,938.000	SYS
131	720-45005 INLET, A2	1.000	EACH
132	720-45070 INLET, P12A	1.000	EACH
133	720-45410 MANHOLE, C4	18.000	EACH
134	720-98174 INLET, B15	23.000	EACH
135	720-98555 INLET, C15	7.000	EACH
136	731-93945 FACE PANELS, CONCRETE	7,235.000	SFT
137	731-93946 WALL ERECTION	7,235.000	SFT
138	731-93947 LEVELING PAD, CONCRETE	360.000	LFT
139	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
140	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
141	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
142	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	5,321.000	LFT
143	801-06625 DETOUR ROUTE MARKER ASSEMBLY	26.000	EACH
144	801-06640 CONSTRUCTION SIGN, A	22.000	EACH
145	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
146	801-06710 FLASHING ARROW SIGN	40.000	DAY
147	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 120

CONTRACT ID : IR-30700-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW BRIDGE			
148	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	4.000	EACH
149	801-07118 BARRICADE, III-A	48.000	LFT
150	801-07119 BARRICADE, III-B	72.000	LFT
151	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	1,880.000	LFT
152	802-04089 SIGN, SHEET, REMOVE	3.000	EACH
153	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	561.900	LFT
154	802-07057 SIGN, PANEL, WITH LEGEND	1,001.000	SFT
155	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	1.000	EACH
156	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	20.000	EACH
157	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
158	802-07138 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, IX	2.000	EACH
159	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	24.000	EACH
160	802-08456 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	8.000	EACH
161	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	253.300	SFT
162	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	164.100	SFT
163	802-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	2.000	EACH
164	802-76095 STRUCTURAL STEEL, BREAKAWAY	3,754.000	LBS
165	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
166	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
167	807-01416 GROUND ROD WITH CONNECTORS, FURNISH	8.000	EACH
168	807-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	169.000	LFT
169	807-02191 HANDHOLE, LIGHTING	5.000	EACH
170	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	8.000	EACH
171	807-03950 LUMINAIRE, ORNAMENTAL	8.000	EACH
172	807-03951 LIGHT POLE, ORNAMENTAL	8.000	EACH
173	807-05073 JUNCTION BOX	24.000	EACH
174	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	122.000	LFT
175	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	1,787.000	LFT
176	807-86838 WIRE, NO 4 COPPER IN CONDUIT, 1/C	1,146.000	LFT
177	807-86910 CONNECTOR KIT, UNFUSED	8.000	EACH
178	807-86915 CONNECTOR KIT, FUSED	8.000	EACH
179	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	21.000	EACH
180	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	6.000	EACH
181	807-86930 INSULATION LINK, NON-WATERPROOFED	17.000	EACH
182	807-86935 INSULATION LINK, WATERPROOFED	20.000	EACH
183	807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	93.000	LFT
184	808-01329 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WRONG WAY RAMP	2.000	EACH
185	808-02157 PAVEMENT MESSAGE MARKING, REMOVE	6.000	EACH
186	808-05878 YIELD LINE TRIANGLE, THERMOPLASTIC	4.000	EACH
187	808-06368 TRANSVERSE MARKING, REMOVE	95.000	LFT
188	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	1,145.000	LFT
189	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	15,924.000	LFT
190	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	2,340.000	LFT
191	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN	263.000	LFT
192	808-06716 LINE, REMOVE	1,005.000	LFT
193	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
194	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	463.000	LFT
195	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	463.000	LFT
196	808-11478 LINE, THERMOPLASTIC, DOTTED, WHITE 8 IN	188.000	LFT

CALL ORDER : 120

CONTRACT ID : IR-30700-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
197 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	10,930.000	LFT
198 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
199 808-75994	PRISMATIC REFLECTOR	204.000	EACH
200 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	56.000	EACH
201 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	204.000	EACH

CALL ORDER : 200

CONTRACT ID : R -29622-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN FACILITY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	429.000	SYS
10	202-02271 HEADWALL, REMOVE	1.000	EACH
11	202-02278 CURB, CONCRETE, REMOVE	377.000	LFT
12	202-52710 SIDEWALK, CONCRETE, REMOVE	75.000	SYS
13	202-74035 SIGN, REMOVE	4.000	EACH
14	202-90413 SLOPEWALL, CONCRETE, 4 IN, REMOVE	134.000	SYS
15	202-91385 INLET, REMOVE	1.000	EACH
16	202-96133 PIPE, REMOVE	7.000	LFT
17	202-96430 FENCE AND POSTS, REMOVE	LUMP	LUMP
18	203-02000 EXCAVATION, COMMON	6,722.000	CYS
19	203-02070 BORROW	4,498.000	CYS
20	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	4.000	EACH
21	205-06937 TEMPORARY SILT FENCE	12,912.000	LFT
22	207-08266 SUBGRADE TREATMENT, TYPE III	14,099.000	SYS
23	210-06382 CANOPY	LUMP	LUMP
24	210-06990 LIMESTONE	14.000	EACH
25	211-09264 STRUCTURAL BACKFILL, TYPE 1	529.000	CYS
26	214-07202 GEOGRID, TYPE I	2,694.000	SYS
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,586.000	TON
28	402-07432 HMA SURFACE, TYPE A	1,089.000	TON
29	402-07433 HMA SURFACE, TYPE B	44.000	TON
30	402-07435 HMA INTERMEDIATE, TYPE A	1,812.000	TON
31	402-07438 HMA INTERMEDIATE, TYPE B	87.000	TON
32	402-07441 HMA BASE, TYPE B	174.000	TON
33	406-05520 ASPHALT FOR TACK COAT	6.000	TON
34	502-06627 PCCP, 6 IN	112.000	SYS
35	601-02241 GUARDRAIL, REMOVE	255.000	LFT
36	601-04793 GUARDRAIL	97.000	LFT
37	601-04793 GUARDRAIL	246.500	LFT
38	601-95871 HANDRAIL	322.000	LFT
39	603-02969 FENCE GATE, RELOCATE	LUMP	LUMP
40	603-06065 FENCE, CHAIN LINK, RESET	255.000	LFT
41	604-06367 JOINT MATERIAL	393.000	LFT
42	604-07894 CURB RAMP, CONCRETE, A	26.000	SYS
43	604-91531 SIDEWALK, CONCRETE, 4 IN	707.000	SYS
44	605-06090 CURB, INTEGRAL, CONCRETE	142.000	LFT
45	605-06120 CURB, CONCRETE	339.000	LFT
46	605-06125 CURB, CONCRETE, MODIFIED	3,181.000	LFT
47	605-06125 CURB, CONCRETE, MODIFIED	491.000	LFT
48	615-97672 TRASH RECEPTACLE	5.000	EACH
49	616-02320 GEOTEXTILES	765.000	SYS

CALL ORDER : 200

CONTRACT ID : R -29622-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN FACILITY		
50	616-05688 RIPRAP, CLASS 1	549.000	TON
51	616-06405 RIPRAP, REVETMENT	116.000	TON
52	616-51367 SLOPEWALL, CONCRETE, 4 IN	134.000	SYS
53	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
54	621-02318 SEED MIXTURE, PRAIRIE GRASS	57.000	LBS
55	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	31,204.000	SYS
56	621-02770 EROSION CONTROL BLANKET	312.000	SYS
57	621-06560 MULCHED SEEDING, U	22,841.000	SYS
58	621-06565 MULCHING MATERIAL	20.000	TON
59	621-06570 TOPSOIL	3,431.000	CYS
60	621-07189 COMPOST SOIL MULCH	5.000	CYS
61	621-07762 COMPOST AMENDED SOIL	156.000	CYS
62	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	9.000	EACH
63	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	30.000	EACH
64	622-05654 PLANT, PERENNIAL	947.000	EACH
65	625-09373 GABIONS, METALLIC COATED	158.000	CYS
66	628-09402 FIELD OFFICE, B	24.000	MOS
67	701-05561 DRILLED SHAFT	147.000	LFT
68	701-05780 DRILLED SHAFT CONCRETE	32.000	CYS
69	702-51001 CONCRETE, A, SUPERSTRUCTURE	91.000	CYS
70	702-51005 CONCRETE, A, SUBSTRUCTURE	51.000	CYS
71	702-76240 CONCRETE	188.000	CYS
72	711-91981 TIE ROD	6.000	EACH
73	712-95676 LUMBER AND TIMBER, TREATED	13.000	MFBM
74	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	305.000	LFT
75	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	78.000	LFT
76	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	96.000	LFT
77	715-46000 PIPE END SECTION, 12 IN	5.000	EACH
78	715-46020 PIPE END SECTION, 24 IN	7.000	EACH
79	718-52610 AGGREGATE FOR UNDERDRAINS	26.000	CYS
80	718-99153 GEOTEXTILES FOR UNDERDRAIN	206.000	SYS
81	720-45005 INLET, A2	1.000	EACH
82	720-45030 INLET, E7	3.000	EACH
83	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
84	801-06710 FLASHING ARROW SIGN	50.000	DAY
85	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
86	802-03866 MILE MARKER	9.000	EACH
87	802-03896 BOLLARD	2.000	EACH
88	802-04314 SIGN	3.000	EACH
89	802-04314 SIGN	3.000	EACH
90	802-04314 SIGN	6.000	EACH
91	802-04314 SIGN	2.000	EACH
92	802-04314 SIGN	9.000	EACH
93	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	152.000	LFT
94	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	128.000	SFT
95	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	793.000	LFT
96	808-75060 TRANSVERSE MARKING, PAINT,	162.000	LFT
97	808-97222 PAVEMENT MESSAGE MARKING, PAINT, HANDICAP SYMBOL	5.000	EACH

CALL ORDER : 220

CONTRACT ID : R -30178-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT SMALL STRUCTURE PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-96133 PIPE, REMOVE	120.000	LFT
10	203-02000 EXCAVATION, COMMON	331.000	CYS
11	203-02070 BORROW	100.000	CYS
12	205-06932 TEMPORARY CHECK DAM, STRAW BALES	20.000	LFT
13	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
14	205-06937 TEMPORARY SILT FENCE	1,200.000	LFT
15	205-09543 NO 2 STONE	100.000	TON
16	207-09935 SUBGRADE TREATMENT, TYPE 1C	268.000	SYS
17	211-09268 STRUCTURAL BACKFILL, TYPE 5	125.000	CYS
18	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	645.000	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN	375.000	SYS
20	402-07433 HMA SURFACE, TYPE B	59.000	TON
21	402-07438 HMA INTERMEDIATE, TYPE B	29.000	TON
22	406-05521 ASPHALT FOR TACK COAT	700.000	SYS
23	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
24	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
25	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	493.750	LFT
26	616-02320 GEOTEXTILES	70.000	SYS
27	616-05689 RIPRAP, CLASS 2	140.000	TON
28	621-06557 SEED MIXTURE, T	78.000	LBS
29	621-06565 MULCHING MATERIAL	1.000	TON
30	621-06626 MULCHED SEEDING, D	1,100.000	SYS
31	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
32	628-09402 FIELD OFFICE, B	5.000	MOS
33	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	20.000	MOS
34	628-11068 CELLULAR TELEPHONE/RADIO	4.000	EACH
35	714-11091 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	43.000	LFT
36	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	124.000	LFT
37	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	24.500	LFT
38	720-45235 CATCH BASIN, E7	1.000	EACH
39	720-45410 MANHOLE, C4	2.000	EACH
40	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
41	801-06625 DETOUR ROUTE MARKER ASSEMBLY	29.000	EACH
42	801-06640 CONSTRUCTION SIGN, A	22.000	EACH
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	801-07118 BARRICADE, III-A	60.000	LFT
45	801-07119 BARRICADE, III-B	20.000	LFT
46	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	402.000	LFT
47	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	51.000	LFT

CALL ORDER : 240

CONTRACT ID : R -30474-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-01261 TESTING FOR ASBESTOS	1.000	EACH
11	202-02240 PAVEMENT REMOVAL	732.000	SYS
12	202-02278 CURB, CONCRETE, REMOVE	2,535.000	LFT
13	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
14	202-52710 SIDEWALK, CONCRETE, REMOVE	100.000	SYS
15	203-02000 EXCAVATION, COMMON	9,196.000	CYS
16	203-02070 BORROW	9,303.000	CYS
17	205-03371 SEDIMENT, REMOVE	2,150.000	CYS
18	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	116.000	TON
19	205-06933 TEMPORARY DITCH INLET PROTECTION	19.000	EACH
20	205-06934 TEMPORARY MULCHING	34.000	TON
21	205-06937 TEMPORARY SILT FENCE	2,275.000	LFT
22	205-09543 NO 2 STONE	100.000	TON
23	207-08263 SUBGRADE TREATMENT, TYPE IA	28,809.000	SYS
24	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,128.000	SYS
25	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,584.000	CYS
26	211-09265 STRUCTURAL BACKFILL, TYPE 2	183.000	CYS
27	211-09266 STRUCTURAL BACKFILL, TYPE 3	170.000	CYS
28	211-09268 STRUCTURAL BACKFILL, TYPE 5	111.000	CYS
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	8,714.000	TON
30	306-08042 MILLING, SCARIFICATION/PROFILE	9,679.000	SYS
31	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
32	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,507.000	TON
33	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	6,037.000	TON
34	406-05520 ASPHALT FOR TACK COAT	11.000	TON
35	601-05999 CURVED TERMINAL END	1.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
37	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	193.750	LFT
38	604-07894 CURB RAMP, CONCRETE, A	35.000	SYS
39	604-07902 CURB RAMP, CONCRETE, H	17.000	SYS
40	604-91531 SIDEWALK, CONCRETE, 4 IN	833.000	SYS
41	604-91531 SIDEWALK, CONCRETE, 4 IN	21.000	SYS
42	605-06140 CURB AND GUTTER, CONCRETE	13,859.000	LFT
43	605-06140 CURB AND GUTTER, CONCRETE	131.000	LFT
44	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	248.000	LFT
45	607-06175 GUTTER, CONCRETE, A	4.000	LFT
46	607-06335 PAVED SIDE DITCH, A	32.000	LFT
47	610-07487 HMA FOR APPROACHES, TYPE B	315.000	TON
48	610-08446 PCCP FOR APPROACHES, 6 IN	2,959.000	SYS
49	611-06497 MAILBOX ASSEMBLY, SINGLE	21.000	EACH

CALL ORDER : 240

CONTRACT ID : R -30474-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	611-06498 MAILBOX ASSEMBLY, DOUBLE	3.000	EACH
51	615-06505 MONUMENT, B	6.000	EACH
52	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
53	616-02320 GEOTEXTILES	223.000	SYS
54	616-05688 RIPRAP, CLASS 1	84.000	TON
55	616-05689 RIPRAP, CLASS 2	31.000	TON
56	616-06405 RIPRAP, REVETMENT	20.000	TON
57	616-07210 FIBER ROLL	1,100.000	LFT
58	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
59	621-02770 EROSION CONTROL BLANKET	790.000	SYS
60	621-06545 FERTILIZER	0.900	TON
61	621-06554 SEED MIXTURE, U	180.000	LBS
62	621-06557 SEED MIXTURE, T	2,025.000	LBS
63	621-06565 MULCHING MATERIAL	2.400	TON
64	621-06567 WATER	66.000	KGAL
65	621-06575 SODDING, NURSERY	16,411.000	SYS
66	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
67	628-09402 FIELD OFFICE, B	20.000	MOS
68	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	40.000	MOS
69	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
70	714-11096 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	72.000	LFT
71	715-04555 PIPE END SECTION, MIN AREA 5.1 SF	1.000	EACH
72	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	220.000	LFT
73	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	8.000	LFT
74	715-05128 PIPE, TYPE 1 CIRCULAR 48 IN	68.000	LFT
75	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	4,666.000	LFT
76	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	1,555.000	LFT
77	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	880.000	LFT
78	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	177.000	LFT
79	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	57.000	LFT
80	715-05335 PIPE, TYPE 2 DEFORMED MIN AREA 5.1 SF	495.000	LFT
81	715-05756 PIPE EXTENSION, CIRCULAR 12 IN	12.000	LFT
82	715-05889 PIPE EXTENSION, CIRCULAR 30 IN	97.000	LFT
83	715-06004 CONCRETE ANCHOR, 48 IN	2.000	EACH
84	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	24.000	TON
85	715-09064 VIDEO INSPECTION FOR PIPE	7,632.000	LFT
86	715-46000 PIPE END SECTION, 12 IN	1.000	EACH
87	715-46005 PIPE END SECTION, 15 IN	9.000	EACH
88	715-46010 PIPE END SECTION, 18 IN	1.000	EACH
89	715-46020 PIPE END SECTION, 24 IN	2.000	EACH
90	720-04682 INLET	10.000	EACH
91	720-04682 INLET	4.000	EACH
92	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
93	720-45030 INLET, E7	1.000	EACH
94	720-45035 INLET, F7	1.000	EACH
95	720-45415 MANHOLE, D4	1.000	EACH
96	720-90352 MANHOLE, D8	1.000	EACH
97	720-93409 INLET, B15, MODIFIED	9.000	EACH
98	720-93411 INLET, C15, MODIFIED	39.000	EACH

CALL ORDER : 240

CONTRACT ID : R -30474-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
99	720-98174 INLET, B15	12.000	EACH
100	720-98555 INLET, C15	1.000	EACH
101	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	166.000	SYS
102	732-08421 MODULAR BLOCK WALL ERECTION	166.000	SYS
103	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
104	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
105	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	1,000.000	LFT
106	801-06625 DETOUR ROUTE MARKER ASSEMBLY	26.000	EACH
107	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
108	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
109	801-07119 BARRICADE, III-B	64.000	LFT
110	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	342.000	LFT
111	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	35.000	EACH
112	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	155.000	SFT
113	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	33.000	SFT
114	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,094.000	LFT
115	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	184.000	LFT
116	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	70.000	LFT
117	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	80.000	LFT
118	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	9,588.000	LFT
119	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	1,285.000	LFT
120	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	337.000	LFT
121	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	13.000	EACH
122	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	7.000	EACH
123	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	5,665.000	LFT

CALL ORDER : 244

CONTRACT ID : R -30556-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL ROAD PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02271 HEADWALL, REMOVE	9.000	EACH
12	202-91385 INLET, REMOVE	6.000	EACH
13	202-96133 PIPE, REMOVE	198.000	LFT
14	202-98488 PIPE END SECTION, REMOVE	2.000	EACH
15	203-02020 EXCAVATION, UNCLASSIFIED	10,771.000	CYS
16	205-06933 TEMPORARY DITCH INLET PROTECTION	27.000	EACH
17	205-06937 TEMPORARY SILT FENCE	4,554.000	LFT
18	207-08263 SUBGRADE TREATMENT, TYPE IA	25,205.600	SYS
19	207-08265 SUBGRADE TREATMENT, TYPE IIA	3,621.300	SYS
20	207-08267 SUBGRADE TREATMENT, TYPE IIIA	725.100	SYS
21	211-02050 B BORROW	771.000	CYS
22	303-01180 COMPACTED AGGREGATE, NO. 53	1,049.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	4,208.600	SYS
24	306-08038 MILLING, ASPHALT, 4 IN	176.000	SYS
25	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	2,435.300	TON
26	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	3,799.500	TON
27	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	7,420.200	TON
28	402-07433 HMA SURFACE, TYPE B	57.800	TON
29	402-07438 HMA INTERMEDIATE, TYPE B	96.600	TON
30	402-07441 HMA BASE, TYPE B	310.300	TON
31	406-05520 ASPHALT FOR TACK COAT	18.800	TON
32	605-92800 CURB AND GUTTER, COMBINED, B, MODIFIED	2,432.000	LFT
33	615-06490 RIGHT OF WAY MARKER	4.000	EACH
34	615-06505 MONUMENT, B	3.000	EACH
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
36	621-01852 MULCHED SEEDING, GRASS, 2	21,731.000	SYS
37	621-06567 WATER	9.000	KGAL
38	621-06574 SODDING	2,324.000	SYS
39	628-09401 FIELD OFFICE, A	14.000	MOS
40	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,445.000	LFT
41	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	1,483.000	LFT
42	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	255.000	LFT
43	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	251.000	LFT
44	715-46000 PIPE END SECTION, 12 IN	1.000	EACH
45	715-90714 PIPE, PVC, 12 IN	254.000	LFT
46	718-34000 PIPE, UNDERDRAIN, PERFORATED, 0.052 IN., 6 IN.	2,828.000	LFT
47	718-52610 AGGREGATE FOR UNDERDRAINS	125.400	CYS
48	718-99153 GEOTEXTILES FOR UNDERDRAIN	1,254.600	SYS
49	720-08660 MANHOLE, J5, MODIFIED	2.000	EACH

CALL ORDER : 244

CONTRACT ID : R -30556-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL ROAD PROJECT		
50	720-44296 INLET, CAP	1.000	EACH
51	720-45045 INLET, J10	2.000	EACH
52	720-45075 INLET, R13	24.000	EACH
53	720-45410 MANHOLE, C4	5.000	EACH
54	720-95422 MANHOLE, J4	2.000	EACH
55	720-95902 CATCH BASIN, E2	1.000	EACH
56	720-98068 MANHOLE, E2	2.000	EACH
57	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
58	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
59	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
60	801-06645 CONSTRUCTION SIGN, B	71.000	EACH
61	801-06710 FLASHING ARROW SIGN	98.000	DAY
62	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
63	801-07118 BARRICADE, III-A	52.000	LFT
64	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	1,323.000	LFT
65	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	31.000	SFT
66	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	430.300	SFT
67	805-01842 HANDHOLE, SIGNAL	14.000	EACH
68	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	2,255.000	LFT
69	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000	EACH
70	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	8.000	EACH
71	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	2.000	EACH
72	805-78245 TRAFFIC SIGNAL HEAD, OPTICALLY PROGRAMMED, 3 FACE, 12 IN	2.000	EACH
73	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
74	805-78420 DISCONNECT HANGER	4.000	EACH
75	805-78467 SIGNAL CABLE, 3C/8GA	8.000	LFT
76	805-78480 SIGNAL CABLE, 3C/14GA	1,080.000	LFT
77	805-78485 SIGNAL CABLE, 5C/14GA	350.000	LFT
78	805-78490 SIGNAL CABLE, 7C/14GA	950.000	LFT
79	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	5,530.000	LFT
80	805-78785 SIGNAL DETECTOR HOUSING	18.000	EACH
81	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	850.000	LFT
82	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
83	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
84	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	1.000	EACH
85	805-98540 FOUNDATION AND ANCHOR BOLTS FOR	4.000	EACH
86	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	15,241.000	LFT
87	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	224.000	LFT
88	808-75215 LINE, THERMOPLASTIC, SOLID, WHITE 12 IN	428.000	LFT
89	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	2,065.300	LFT
90	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	9,628.000	LFT
91	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	340.400	LFT
92	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	42.000	EACH
93	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	10.000	EACH
94	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	93.000	EACH
95	808-94435 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	14.000	EACH

CALL ORDER : 250

CONTRACT ID : R -30742-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	934.000	SYS
12	202-02278 CURB, CONCRETE, REMOVE	1,192.000	LFT
13	202-52710 SIDEWALK, CONCRETE, REMOVE	49.000	SYS
14	202-91385 INLET, REMOVE	9.000	EACH
15	202-96133 PIPE, REMOVE	1,269.000	LFT
16	203-02000 EXCAVATION, COMMON	9,477.000	CYS
17	203-02070 BORROW	19,785.000	CYS
18	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	36.000	TON
19	205-06933 TEMPORARY DITCH INLET PROTECTION	49.000	EACH
20	205-06936 TEMPORARY SEDIMENT TRAP	59.000	TON
21	205-06937 TEMPORARY SILT FENCE	11,883.000	LFT
22	205-09543 NO 2 STONE	100.000	TON
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,030.000	SYS
24	207-09935 SUBGRADE TREATMENT, TYPE 1C	13,730.000	SYS
25	211-02050 B BORROW	220.000	CYS
26	211-09265 STRUCTURAL BACKFILL, TYPE 2	7,997.000	CYS
27	211-09266 STRUCTURAL BACKFILL, TYPE 3	820.000	CYS
28	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,091.000	TON
29	304-07493 WIDENING WITH HMA, TYPE B	236.000	TON
30	306-08034 MILLING, ASPHALT, 1 1/2 IN	21,762.000	SYS
31	306-08037 MILLING, ASPHALT, 3 IN	2,186.000	SYS
32	306-10113 MILLING ASPHALT, 4 1/2 IN	1,495.000	SYS
33	306-10163 MILLING ASPHALT, 2 1/2 IN	915.000	SYS
34	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,905.000	TON
35	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	989.000	TON
36	402-07451 HMA WEDGE AND LEVEL, TYPE B	2,934.000	TON
37	406-05520 ASPHALT FOR TACK COAT	10.000	TON
38	601-02241 GUARDRAIL, REMOVE	188.000	LFT
39	604-06070 SIDEWALK, CONCRETE	3,385.000	SYS
40	604-07897 CURB RAMP, CONCRETE, C	48.000	SYS
41	604-07899 CURB RAMP, CONCRETE, E	80.000	SYS
42	604-07901 CURB RAMP, CONCRETE, G	41.000	SYS
43	604-07904 CURB RAMP, CONCRETE, L	14.000	SYS
44	605-06125 CURB, CONCRETE, MODIFIED	161.000	LFT
45	605-06140 CURB AND GUTTER, CONCRETE	13,071.000	LFT
46	605-97937 CURB AND GUTTER, CONCRETE, ROLL	39.000	LFT
47	610-07487 HMA FOR APPROACHES, TYPE B	850.000	TON
48	610-08446 PCCP FOR APPROACHES, 6 IN	2,633.000	SYS
49	610-09108 PCCP FOR APPROACHES, 9 IN	221.000	SYS

CALL ORDER : 250

CONTRACT ID : R -30742-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	611-06497 MAILBOX ASSEMBLY, SINGLE	20.000	EACH
51	611-06498 MAILBOX ASSEMBLY, DOUBLE	8.000	EACH
52	615-06505 MONUMENT, B	8.000	EACH
53	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
54	616-02320 GEOTEXTILES	495.000	SYS
55	616-05688 RIPRAP, CLASS 1	100.000	TON
56	616-06405 RIPRAP, REVETMENT	241.000	TON
57	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
58	621-06545 FERTILIZER	2.000	TON
59	621-06554 SEED MIXTURE, U	648.000	LBS
60	621-06557 SEED MIXTURE, T	900.000	LBS
61	621-06565 MULCHING MATERIAL	22.000	TON
62	621-06567 WATER	20.000	KGAL
63	621-06570 TOPSOIL	470.000	CYS
64	621-06574 SODDING	223.000	SYS
65	621-06575 SODDING, NURSERY	4,225.000	SYS
66	622-05625 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT	15.000	EACH
67	628-09402 FIELD OFFICE, B	15.000	MOS
68	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	15.000	MOS
69	702-90915 CONCRETE, CLASS A	7.000	CYS
70	715-01898 WATER MAIN, DUCTILE IRON, 10 IN	3,004.000	LFT
71	715-01898 WATER MAIN, DUCTILE IRON, 10 IN	216.000	LFT
72	715-04836 GATE VALVE	11.000	EACH
73	715-04964 WATER MAIN	2,747.000	LFT
74	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	324.000	LFT
75	715-05049 PIPE, TYPE 4 CIRCULAR 8 IN	1,114.000	LFT
76	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	4,286.000	LFT
77	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	128.000	LFT
78	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	976.000	LFT
79	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	89.000	LFT
80	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	903.000	LFT
81	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	3,256.000	LFT
82	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	25.000	LFT
83	715-06825 CONCRETE ANCHOR	4.000	EACH
84	715-07590 CULVERT	84.000	LFT
85	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	1,281.000	TON
86	715-09064 VIDEO INSPECTION FOR PIPE	10,027.000	LFT
87	715-41045 PIPE, REINFORCED CONCRETE, 12 IN	26.000	LFT
88	715-46000 PIPE END SECTION, 12 IN	4.000	EACH
89	715-46005 PIPE END SECTION, 15 IN	3.000	EACH
90	715-46020 PIPE END SECTION, 24 IN	1.000	EACH
91	715-46040 PIPE END SECTION, 36 IN	1.000	EACH
92	715-92253 SEWER, SANITARY LATERAL, RECONNECT	12.000	EACH
93	715-94780 WATER MAIN, DUCTILE IRON, 6 IN	40.000	LFT
94	715-97873 WATER SERVICE LINE, 1 IN	50.000	EACH
95	720-02367 MANHOLE, J10	2.000	EACH
96	720-04682 INLET	41.000	EACH
97	720-04721 MANHOLE, K	1.000	EACH
98	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH

CALL ORDER : 250

CONTRACT ID : R -30742-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
99	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
100	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
101	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
102	720-45045 INLET, J10	73.000	EACH
103	720-45055 INLET, M10	65.000	EACH
104	720-45145 INLET, J10, MODIFIED	1.000	EACH
105	720-45235 CATCH BASIN, E7	2.000	EACH
106	720-45410 MANHOLE, C4	51.000	EACH
107	720-45431 MANHOLE, J	1.000	EACH
108	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	15.000	LFT
109	720-94157 MANHOLE, C	2.000	EACH
110	720-94208 MANHOLE, C10	5.000	EACH
111	720-94612 MANHOLE, K4	2.000	EACH
112	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	35.000	EACH
113	720-95422 MANHOLE, J4	1.000	EACH
114	720-96999 FIRE HYDRANT ASSEMBLY	5.000	EACH
115	720-97008 FIRE HYDRANT ASSEMBLY, RELOCATE	8.000	EACH
116	720-97009 FIRE HYDRANT ASSEMBLY, REMOVE	2.000	EACH
117	720-97958 MANHOLE, K2	1.000	EACH
118	732-91739 WATER MAIN, DUCTILE IRON, 8 IN	37.000	LFT
119	732-93403 WATER SERVICE CONNECTION, 0.75 IN.	10.000	EACH
120	732-93403 WATER SERVICE CONNECTION, 0.75 IN.	10.000	EACH
121	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
122	801-03291 CONSTRUCTION SIGN, D	8.000	EACH
123	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
124	801-06625 DETOUR ROUTE MARKER ASSEMBLY	30.000	EACH
125	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
126	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
127	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
128	801-07119 BARRICADE, III-B	216.000	LFT
129	802-04089 SIGN, SHEET, REMOVE	58.000	EACH
130	802-04314 SIGN	4.000	EACH
131	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	593.000	LFT
132	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	297.000	LFT
133	802-07060 SIGN, SHEET, RELOCATE	5.000	EACH
134	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	147.000	SFT
135	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	383.000	SFT
136	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	6.000	SFT
137	802-76235 INSTALL OVERHEAD SIGN	2.000	EACH
138	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
139	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	2.000	EACH
140	805-02056 SPAN AND CATENARY FOR FLASHER	1.000	EACH
141	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
142	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN RED	8.000	EACH
143	805-78420 DISCONNECT HANGER	1.000	EACH
144	805-78445 SIGNAL SERVICE	1.000	EACH
145	805-78467 SIGNAL CABLE, 3C/8GA	38.000	LFT
146	805-78480 SIGNAL CABLE, 3C/14GA	147.000	LFT
147	805-78485 SIGNAL CABLE, 5C/14GA	63.000	LFT

CALL ORDER : 250

CONTRACT ID : R -30742-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
148 805-81032	SIGNAL STRAIN POLE, STEEL, 30 FT	2.000	EACH
149 808-09381	RETRO-REFLECTIVITY TESTING	LUMP	LUMP
150 808-75205	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	467.000	LFT
151 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,845.000	LFT
152 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	10,740.000	LFT
153 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	478.000	LFT
154 808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	1,447.000	LFT
155 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	26.000	EACH

CALL ORDER : 260

CONTRACT ID : R -30956-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	36,735.000	CYS
12	203-02010 EXCAVATION, ROCK	4,795.000	CYS
13	205-03371 SEDIMENT, REMOVE	100.000	CYS
14	205-06930 SPLASHPAD, RIPRAP	24.000	TON
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	96.000	TON
16	205-06934 TEMPORARY MULCHING	13.200	TON
17	205-06937 TEMPORARY SILT FENCE	966.000	LFT
18	205-09543 NO 2 STONE	200.000	TON
19	207-08263 SUBGRADE TREATMENT, TYPE IA	18,635.000	SYS
20	207-08265 SUBGRADE TREATMENT, TYPE IIA	1,833.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	258.000	SYS
22	211-09264 STRUCTURAL BACKFILL, TYPE 1	365.000	CYS
23	303-01180 COMPACTED AGGREGATE, NO. 53	6,945.000	TON
24	303-07449 COMPACTED AGGREGATE, NO. 73	25.000	TON
25	306-08043 MILLING, TRANSITION	584.000	SYS
26	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	1,234.000	TON
27	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	1,976.000	TON
28	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	1,889.000	TON
29	402-07432 HMA SURFACE, TYPE A	74.000	TON
30	402-07435 HMA INTERMEDIATE, TYPE A	123.000	TON
31	402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE	105.000	TON
32	406-05520 ASPHALT FOR TACK COAT	4.300	TON
33	601-01626 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
34	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	5.000	EACH
36	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	987.000	LFT
37	605-06121 CURB, CONCRETE, B	2,180.000	LFT
38	607-06340 PAVED SIDE DITCH, B	3,129.000	LFT
39	610-07486 HMA FOR APPROACHES, TYPE A	269.000	TON
40	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
41	615-06490 RIGHT OF WAY MARKER	51.000	EACH
42	615-06505 MONUMENT, B	13.000	EACH
43	616-02320 GEOTEXTILES	2,939.000	SYS
44	616-05688 RIPRAP, CLASS 1	23.000	TON
45	616-06405 RIPRAP, REVETMENT	1,261.000	TON
46	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
47	621-06545 FERTILIZER	2.100	TON
48	621-06553 SEED MIXTURE, R	893.000	LBS
49	621-06557 SEED MIXTURE, T	788.000	LBS

CALL ORDER : 260

CONTRACT ID : R -30956-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	621-06565 MULCHING MATERIAL	10.500	TON
51	621-06567 WATER	21.100	KGAL
52	621-06574 SODDING	6,660.000	SYS
53	621-09815 ARTICULATED CONCRETE BLOCK	1,068.000	SYS
54	622-98200 SIGN, DO NOT DISTURB	26.000	EACH
55	628-09402 FIELD OFFICE, B	12.000	MOS
56	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	24.000	MOS
57	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
58	702-51863 FIELD DRILLED HOLE IN CONCRETE	60.000	EACH
59	709-51821 SURFACE SEAL	LUMP	LUMP
60	714-11186 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	62.000	LFT
61	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	216.000	LFT
62	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	95.000	LFT
63	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	84.000	LFT
64	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	215.000	LFT
65	715-46005 PIPE END SECTION, 15 IN	14.000	EACH
66	715-46040 PIPE END SECTION, 36 IN	6.000	EACH
67	720-45045 INLET, J10	1.000	EACH
68	720-98174 INLET, B15	1.000	EACH
69	723-11203 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	120.000	LFT
70	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	1,550.000	LFT
71	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,586.000	LFT
72	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	20.000	LFT
73	801-06625 DETOUR ROUTE MARKER ASSEMBLY	24.000	EACH
74	801-06640 CONSTRUCTION SIGN, A	22.000	EACH
75	801-06645 CONSTRUCTION SIGN, B	11.000	EACH
76	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
77	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000	EACH
78	801-07118 BARRICADE, III-A	156.000	LFT
79	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	900.000	LFT
80	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	114.800	LFT
81	802-09837 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.080 IN THICKNESS	1.330	SFT
82	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	44.250	SFT
83	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	2.330	SFT
84	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,750.000	LFT
85	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	7,530.000	LFT
86	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	15.000	LFT

CALL ORDER : 270

CONTRACT ID : R -30970-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	203-02020 EXCAVATION, UNCLASSIFIED	125,550.000	CYS
13	205-03371 SEDIMENT, REMOVE	138.000	CYS
14	205-06930 SPLASHPAD, RIPRAP	6.000	TON
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	96.600	TON
16	205-06937 TEMPORARY SILT FENCE	4,118.000	LFT
17	205-06938 TEMPORARY SLOPE DRAIN	116.000	LFT
18	207-08264 SUBGRADE TREATMENT, TYPE II	11,196.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	531.000	SYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,792.000	TON
21	303-01180 COMPACTED AGGREGATE, NO. 53	1,676.000	TON
22	303-07449 COMPACTED AGGREGATE, NO. 73	283.000	TON
23	303-93506 AGGREGATE, 2	100.000	CYS
24	304-07492 WIDENING WITH HMA, TYPE A	12.000	TON
25	306-08043 MILLING, TRANSITION	175.000	SYS
26	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	679.000	TON
27	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,128.000	TON
28	406-05520 ASPHALT FOR TACK COAT	3.000	TON
29	601-01839 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 6	1.000	EACH
30	601-01848 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 5	2.000	EACH
31	601-06037 GUARDRAIL END TREATMENT, I	5.000	EACH
32	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,975.000	LFT
33	607-06340 PAVED SIDE DITCH, B	477.000	LFT
34	610-07486 HMA FOR APPROACHES, TYPE A	146.000	TON
35	615-06490 RIGHT OF WAY MARKER	41.000	EACH
36	615-06505 MONUMENT, B	17.000	EACH
37	615-06510 MONUMENT, C	3.000	EACH
38	616-02320 GEOTEXTILES	233.000	SYS
39	616-06405 RIPRAP, REVETMENT	112.000	TON
40	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
41	621-06545 FERTILIZER	4.000	TON
42	621-06553 SEED MIXTURE, R	1,700.000	LBS
43	621-06557 SEED MIXTURE, T	1,500.000	LBS
44	621-06565 MULCHING MATERIAL	40.000	TON
45	628-09402 FIELD OFFICE, B	12.000	MOS
46	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	305.000	LFT
47	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	400.000	LFT
48	718-06528 OUTLET PROTECTOR, 1	7.000	EACH
49	718-52610 AGGREGATE FOR UNDERDRAINS	52.000	CYS

CALL ORDER : 270

CONTRACT ID : R -30970-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	718-99153 GEOTEXTILES FOR UNDERDRAIN	205.000	SYS
51	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
52	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
53	801-06625 DETOUR ROUTE MARKER ASSEMBLY	47.000	EACH
54	801-06640 CONSTRUCTION SIGN, A	7.000	EACH
55	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
56	801-07118 BARRICADE, III-A	72.000	LFT
57	801-07119 BARRICADE, III-B	36.000	LFT
58	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	46.000	LFT
59	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	32.100	SFT
60	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
61	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	5,992.000	LFT
62	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	6,074.000	LFT

CALL ORDER : 280

CONTRACT ID : R -31397-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	51.000	SYS
9	202-02279 CURB AND GUTTER, REMOVE	1,074.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	361.000	SYS
11	203-02000 EXCAVATION, COMMON	629.000	CYS
12	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	13.000	EACH
13	207-08267 SUBGRADE TREATMENT, TYPE IIIA	243.000	SYS
14	207-09935 SUBGRADE TREATMENT, TYPE 1C	1,853.000	SYS
15	211-09264 STRUCTURAL BACKFILL, TYPE 1	47.000	CYS
16	306-08034 MILLING, ASPHALT, 1 1/2 IN	4,444.000	SYS
17	402-07433 HMA SURFACE, TYPE B	468.000	TON
18	402-07438 HMA INTERMEDIATE, TYPE B	169.000	TON
19	402-07441 HMA BASE, TYPE B	203.000	TON
20	406-05520 ASPHALT FOR TACK COAT	2.100	TON
21	604-06070 SIDEWALK, CONCRETE	403.000	SYS
22	604-07897 CURB RAMP, CONCRETE, C	18.000	SYS
23	604-07903 CURB RAMP, CONCRETE, K	20.000	SYS
24	605-06140 CURB AND GUTTER, CONCRETE	1,204.000	LFT
25	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	36.000	LFT
26	610-09108 PCCP FOR APPROACHES, 9 IN	243.000	SYS
27	615-06490 RIGHT OF WAY MARKER	20.000	EACH
28	615-06505 MONUMENT, B	1.000	EACH
29	621-06574 SODDING	295.000	SYS
30	628-09402 FIELD OFFICE, B	12.000	MOS
31	715-05146 PIPE, TYPE 2 CIRCULAR 6 IN	8.000	LFT
32	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	88.000	LFT
33	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	72.000	LFT
34	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
35	720-45305 CATCH BASIN, A2, MODIFIED	1.000	EACH
36	720-94713 CATCH BASIN, C15, MODIFIED	1.000	EACH
37	720-95157 CATCH BASIN, R13, MODIFIED	2.000	EACH
38	720-99416 CATCH BASIN, B15	4.000	EACH
39	720-99417 CATCH BASIN, C15	2.000	EACH
40	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
41	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	3,541.000	LFT
42	801-06625 DETOUR ROUTE MARKER ASSEMBLY	34.000	EACH
43	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
44	801-06645 CONSTRUCTION SIGN, B	7.000	EACH
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	801-07118 BARRICADE, III-A	343.000	LFT
47	801-07119 BARRICADE, III-B	12.000	LFT
48	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	43.000	LFT
49	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	10.000	EACH

CALL ORDER : 280

CONTRACT ID : R -31397-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	63.500	SFT
51	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	8.000	SFT
52	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	9.000	SFT
53	802-09841 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.125 IN THICKNESS	48.000	SFT
54	805-01421 SERVICE POINT RISER AND WEATHERHEAD	1.000	EACH
55	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	4.000	EACH
56	805-01842 HANDHOLE, SIGNAL	4.000	EACH
57	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	8.000	EACH
58	805-02658 CABLE, COAXIAL	1,090.000	LFT
59	805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL	8.000	EACH
60	805-09540 LOOP DETECTOR RACK	1.000	EACH
61	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
62	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	4.000	EACH
63	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	4.000	EACH
64	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
65	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
66	805-78420 DISCONNECT HANGER	4.000	EACH
67	805-78445 SIGNAL SERVICE	1.000	EACH
68	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	3,659.000	LFT
69	805-78480 SIGNAL CABLE, 3C/14GA	1,514.000	LFT
70	805-78485 SIGNAL CABLE, 5C/14GA	272.000	LFT
71	805-78490 SIGNAL CABLE, 7C/14GA	921.000	LFT
72	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	3,068.000	LFT
73	805-78785 SIGNAL DETECTOR HOUSING	8.000	EACH
74	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,140.000	LFT
75	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
76	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
77	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	4.000	EACH
78	807-06595 CONDUIT, PVC, 2 IN	649.000	LFT
79	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	1.000	EACH
80	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	447.000	LFT
81	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	191.000	LFT
82	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,981.000	LFT
83	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	26.000	LFT
84	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	105.000	LFT
85	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	426.000	LFT
86	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	5.000	EACH

CALL ORDER : 300

CONTRACT ID : R -33079-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT PROJECT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	100.000	SYS
11	203-02000 EXCAVATION, COMMON	595.000	CYS
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	4.000	TON
13	205-06937 TEMPORARY SILT FENCE	231.000	LFT
14	207-08263 SUBGRADE TREATMENT, TYPE IA	665.000	SYS
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	507.000	SYS
16	211-09264 STRUCTURAL BACKFILL, TYPE 1	224.000	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	280.000	TON
18	304-07783 HMA PATCHING, TYPE D	27.000	TON
19	304-07789 WIDENING WITH HMA, TYPE D	93.000	TON
20	306-08034 MILLING, ASPHALT, 1 1/2 IN	2,042.000	SYS
21	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	311.000	TON
22	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	13.000	TON
23	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	40.000	TON
24	402-07435 HMA INTERMEDIATE, TYPE A	21.000	TON
25	402-07785 HMA INTERMEDIATE, TYPE D	294.000	TON
26	406-05520 ASPHALT FOR TACK COAT	2.700	TON
27	506-06333 PCCP PATCHING, FULL DEPTH	50.000	SYS
28	605-06090 CURB, INTEGRAL, CONCRETE	100.000	LFT
29	605-06120 CURB, CONCRETE	184.000	LFT
30	605-06140 CURB AND GUTTER, CONCRETE	713.000	LFT
31	605-06255 CENTER CURB, D, CONCRETE	45.000	SYS
32	605-06255 CENTER CURB, D, CONCRETE	20.000	SYS
33	605-09131 CURB AND GUTTER TURNOUT CONCRETE	18.000	LFT
34	610-07487 HMA FOR APPROACHES, TYPE B	8.000	TON
35	610-09108 PCCP FOR APPROACHES, 9 IN	507.000	SYS
36	615-06505 MONUMENT, B	2.000	EACH
37	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
38	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	2,768.000	SYS
39	621-06575 SODDING, NURSERY	2,768.000	SYS
40	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
41	628-09401 FIELD OFFICE, A	4.500	MOS
42	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	4.500	MOS
43	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
44	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	501.000	LFT
45	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	160.000	LFT
46	715-05153 PIPE, TYPE 2 CIRCULAR 21 IN	168.000	LFT
47	715-05946 SAFETY METAL END SECTION, 6:1 21 IN	1.000	EACH
48	715-08307 HMA FOR STRUCTURE INSTALLATION, TYPE D	129.000	TON
49	715-46000 PIPE END SECTION, 12 IN	1.000	EACH

CALL ORDER : 300

CONTRACT ID : R -33079-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT PROJECT		
50	720-45010 INLET, A3	2.000	EACH
51	720-45030 INLET, E7	3.000	EACH
52	720-45410 MANHOLE, C4	2.000	EACH
53	720-98174 INLET, B15	1.000	EACH
54	720-98555 INLET, C15	6.000	EACH
55	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
56	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
57	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,672.000	LFT
58	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	4.000	EACH
59	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	40.000	LFT
60	801-06625 DETOUR ROUTE MARKER ASSEMBLY	18.000	EACH
61	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
62	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
63	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
64	801-07119 BARRICADE, III-B	248.000	LFT
65	802-03126 SIGN, OVERHEAD, RELOCATE	1.000	EACH
66	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	122.500	LFT
67	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
68	802-09837 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.080 IN THICKNESS	2.500	SFT
69	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	34.750	SFT
70	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	3.500	SFT
71	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	13.900	SFT
72	805-01842 HANDHOLE, SIGNAL	2.000	EACH
73	805-02437 CONTROLLER, RELOCATE AND REWIRE	1.000	EACH
74	805-09540 LOOP DETECTOR RACK	1.000	EACH
75	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	1.000	EACH
76	805-78420 DISCONNECT HANGER	1.000	EACH
77	805-78467 SIGNAL CABLE, 3C/8GA	61.000	LFT
78	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	1,137.000	LFT
79	805-78485 SIGNAL CABLE, 5C/14GA	121.000	LFT
80	805-78490 SIGNAL CABLE, 7C/14GA	312.000	LFT
81	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	904.000	LFT
82	805-78785 SIGNAL DETECTOR HOUSING	3.000	EACH
83	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	453.000	LFT
84	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
85	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	3.000	EACH
86	805-94295 SIGNAL HEAD, RELOCATE	2.000	EACH
87	805-95933 CURB PAINTING, YELLOW	400.000	LFT
88	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	210.000	LFT
89	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,194.000	LFT
90	808-06716 LINE, REMOVE	100.000	LFT
91	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,286.000	LFT
92	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	63.000	LFT
93	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	11.000	EACH

CALL ORDER : 310

CONTRACT ID : R -33158-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, RAILROAD DEPOT RESTORATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	2,190.000	SFT
8	202-05668 DEMOLITION	LUMP	LUMP
9	202-11501 SHORING	LUMP	LUMP
10	211-09264 STRUCTURAL BACKFILL, TYPE 1	47.000	CYS
11	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	14.000	TON
12	304-07489 HMA PATCHING, TYPE A	7.000	TON
13	604-92237 HAND RAIL, STEEL	52.000	LFT
14	621-06560 MULCHED SEEDING, U	20.000	SYS
15	711-03973 BUILDING ARCHITECTURAL	LUMP	LUMP
16	711-98282 BUILDING ELECTRICAL	LUMP	LUMP
17	711-98751 BUILDING, MECHANICAL	LUMP	LUMP
18	712-06852 BOARDWALK	425.000	SFT
19	719-03975 BUILDING PLUMBING	LUMP	LUMP
20	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
21	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
22	801-07118 BARRICADE, III-A	48.000	LFT

CALL ORDER : 320

CONTRACT ID : R -33309-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BIKE AND PEDESTRIAN FACILITIES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-02245 TREE, 6 IN, REMOVE	3.000	EACH
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	1,275.000	SYS
11	202-02271 HEADWALL, REMOVE	2.000	EACH
12	202-02272 PAVED SIDE DITCH, REMOVE	13.000	LFT
13	202-02273 CENTER CURB, CONCRETE, REMOVE	30.000	SYS
14	202-02278 CURB, CONCRETE, REMOVE	154.000	LFT
15	202-02279 CURB AND GUTTER, REMOVE	1,010.000	LFT
16	202-04791 PARKING BARRIER, REMOVE	6.000	EACH
17	202-52710 SIDEWALK, CONCRETE, REMOVE	525.000	SYS
18	202-91385 INLET, REMOVE	3.000	EACH
19	202-91840 FENCE, CHAIN LINK, REMOVE	398.000	LFT
20	202-93615 CONCRETE, REMOVE	11.000	SYS
21	202-94747 POST, REMOVE	2.000	EACH
22	202-96133 PIPE, REMOVE	53.000	LFT
23	203-02000 EXCAVATION, COMMON	927.000	CYS
24	205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE	2.000	EACH
25	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	11.000	EACH
26	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	10.000	TON
27	205-06937 TEMPORARY SILT FENCE	3,263.000	LFT
28	205-09543 NO 2 STONE	100.000	TON
29	207-08266 SUBGRADE TREATMENT, TYPE III	799.000	SYS
30	211-09264 STRUCTURAL BACKFILL, TYPE 1	68.480	CYS
31	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,584.000	TON
32	304-07489 HMA PATCHING, TYPE A	80.000	TON
33	306-08034 MILLING, ASPHALT, 1 1/2 IN	972.000	SYS
34	402-07432 HMA SURFACE, TYPE A	225.000	TON
35	402-07435 HMA INTERMEDIATE, TYPE A	388.000	TON
36	406-05520 ASPHALT FOR TACK COAT	0.880	TON
37	502-06627 PCCP, 6 IN	750.000	SYS
38	601-02241 GUARDRAIL, REMOVE	6.250	LFT
39	603-01932 FENCE, CHAIN LINK, 96 IN	55.000	LFT
40	603-03692 FENCE, WOOD,	223.000	LFT
41	603-06045 FENCE, CHAIN LINK, 48 IN	182.000	LFT
42	603-93513 FENCE GATE, PEDESTRIAN, 4FT	1.000	EACH
43	604-04740 PAVERS	48.000	SFT
44	604-07900 CURB RAMP, CONCRETE, F	38.000	SYS
45	604-07901 CURB RAMP, CONCRETE, G	44.000	SYS
46	604-07901 CURB RAMP, CONCRETE, G	676.000	SYS
47	604-91531 SIDEWALK, CONCRETE, 4 IN	22.000	SYS
48	605-06120 CURB, CONCRETE	474.000	LFT
49	605-06140 CURB AND GUTTER, CONCRETE	1,469.000	LFT

CALL ORDER : 320

CONTRACT ID : R -33309-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE AND PEDESTRIAN FACILITIES		
50	616-06405 RIPRAP, REVETMENT	43.450	TON
51	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
52	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	3,450.000	SYS
53	621-02770 EROSION CONTROL BLANKET	525.000	SYS
54	621-04316 SPADE EDGE	427.000	LFT
55	621-06560 MULCHED SEEDING, U	3,450.000	SYS
56	621-06570 TOPSOIL	51.000	CYS
57	621-94798 SUBGRADE STABILIZATION TREATMENT	907.000	SYS
58	621-98038 MULCH, HARDWOOD SHREDDED BARK	17.000	CYS
59	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	62.000	EACH
60	622-05653 PLANT, GROUND COVER	34.000	EACH
61	622-05654 PLANT, PERENNIAL	109.000	EACH
62	622-05654 PLANT, PERENNIAL	342.000	EACH
63	715-03475 SAFETY METAL END SECTION, 4:1 15 IN	1.000	EACH
64	715-03487 SAFETY METAL END SECTION, 4:1 30 IN	1.000	EACH
65	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	27.000	LFT
66	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	216.000	LFT
67	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	27.000	LFT
68	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	5.000	LFT
69	715-46000 PIPE END SECTION, 12 IN	2.000	EACH
70	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
71	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
72	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
73	720-45030 INLET, E7	1.000	EACH
74	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	2.000	EACH
75	720-95422 MANHOLE, J4	1.000	EACH
76	720-98174 INLET, B15	2.000	EACH
77	720-98555 INLET, C15	3.000	EACH
78	801-06640 CONSTRUCTION SIGN, A	7.000	EACH
79	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
80	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
81	801-07119 BARRICADE, III-B	72.000	LFT
82	802-04250 SIGN, TRAIL INFORMATION	2.000	EACH
83	802-04250 SIGN, TRAIL INFORMATION	4.000	EACH
84	802-04314 SIGN	7.000	EACH
85	802-04314 SIGN	6.000	EACH
86	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	19.000	LFT
87	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	1.000	EACH
88	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	12.500	SFT
89	802-91122 SIGN, GROUND MOUNTED, RESET	1.000	EACH
90	805-01842 HANDHOLE, SIGNAL	5.000	EACH
91	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	6.000	EACH
92	805-02328 SIGNAL CABLE, 1C/14 GA	40.000	LFT
93	805-02645 SIGNAL PEDESTAL FOUNDATION, A	3.000	EACH
94	805-78370 PEDESTRIAN PUSH BUTTON	6.000	EACH
95	805-78485 SIGNAL CABLE, 5C/14GA	1,271.000	LFT
96	805-90005 SIGNAL PEDESTAL, 10 FT	3.000	EACH
97	805-96014 SAW CUT, FULL DEPTH	1,637.000	LFT
98	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	350.000	LFT

CALL ORDER : 320

CONTRACT ID : R -33309-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	BIKE AND PEDESTRIAN FACILITIES		
99 808-03439	TRANSVERSE MARKING THERMOPLASTIC	2,029.000	LFT
100 808-06726	TRANSVERSE MARKING, PAINT,	66.000	LFT

CALL ORDER : 340

CONTRACT ID : R -33656-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PIPE LINING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	205-06932 TEMPORARY CHECK DAM, STRAW BALES	50.000	LFT
8	205-06937 TEMPORARY SILT FENCE	200.000	LFT
9	616-02320 GEOTEXTILES	30.000	SYS
10	616-05688 RIPRAP, CLASS 1	15.000	TON
11	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
12	621-06559 MULCHED SEEDING, R	200.000	SYS
13	725-10224 LINER PIPE, THERMOPLASTIC, CIRCULAR, 8.4-8.8 SFT	82.000	LFT
14	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 350

CONTRACT ID : R -33716-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGHT DISTANCE IMPROVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	2,595.000	CYS
10	203-02070 BORROW	4,040.000	CYS
11	205-03371 SEDIMENT, REMOVE	10.000	CYS
12	205-06932 TEMPORARY CHECK DAM, STRAW BALES	104.000	LFT
13	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
14	205-06937 TEMPORARY SILT FENCE	2,393.000	LFT
15	205-09543 NO 2 STONE	148.000	TON
16	207-08263 SUBGRADE TREATMENT, TYPE IA	4,701.000	SYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,482.000	SYS
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	142.000	CYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,566.000	TON
20	303-01180 COMPACTED AGGREGATE, NO. 53	183.000	TON
21	304-07494 WIDENING WITH HMA, TYPE C	130.000	TON
22	306-08033 MILLING, ASPHALT, 1 IN	318.000	SYS
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,784.000	SYS
24	306-08036 MILLING, ASPHALT, 2 IN	196.000	SYS
25	306-08042 MILLING, SCARIFICATION/PROFILE	1,662.000	SYS
26	402-07432 HMA SURFACE, TYPE A	365.000	TON
27	402-07434 HMA SURFACE, TYPE C	470.000	TON
28	402-07439 HMA INTERMEDIATE, TYPE C	543.000	TON
29	402-07452 HMA WEDGE AND LEVEL, TYPE C	162.000	TON
30	406-05520 ASPHALT FOR TACK COAT	2.000	TON
31	502-06627 PCCP, 6 IN	84.000	SYS
32	601-02241 GUARDRAIL, REMOVE	959.000	LFT
33	601-91147 GUARDRAIL END TREATMENT, RESET	2.000	EACH
34	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
35	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	350.000	LFT
36	610-07487 HMA FOR APPROACHES, TYPE B	788.000	TON
37	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
38	615-06490 RIGHT OF WAY MARKER	29.000	EACH
39	615-06500 MONUMENT, A	6.000	EACH
40	616-02320 GEOTEXTILES	477.000	SYS
41	616-05688 RIPRAP, CLASS 1	25.000	TON
42	616-06405 RIPRAP, REVETMENT	30.000	TON
43	616-06451 RIPRAP, UNIFORM	126.000	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
45	621-01956 SEED MIXTURE, LEGUME, 1	280.000	LBS
46	621-02770 EROSION CONTROL BLANKET	989.000	SYS
47	621-06545 FERTILIZER	0.600	TON
48	621-06557 SEED MIXTURE, T	390.000	LBS
49	621-06565 MULCHING MATERIAL	8.200	TON

CALL ORDER : 350

CONTRACT ID : R -33716-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
50	621-06567 WATER	20.000	KGAL
51	621-06574 SODDING	715.000	SYS
52	621-06575 SODDING, NURSERY	4,249.000	SYS
53	628-09401 FIELD OFFICE, A	8.000	MOS
54	702-51863 FIELD DRILLED HOLE IN CONCRETE	4.000	EACH
55	702-90915 CONCRETE, CLASS A	3.000	CYS
56	713-04509 TEMPORARY PIPE	LUMP	LUMP
57	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	73.000	LFT
58	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	107.000	LFT
59	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	40.000	LFT
60	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	64.000	LFT
61	715-05173 PIPE, TYPE 3 CIRCULAR 24 IN	159.000	LFT
62	715-09064 VIDEO INSPECTION FOR PIPE	220.000	LFT
63	715-46005 PIPE END SECTION, 15 IN	2.000	EACH
64	715-46010 PIPE END SECTION, 18 IN	2.000	EACH
65	715-46020 PIPE END SECTION, 24 IN	4.000	EACH
66	720-45030 INLET, E7	1.000	EACH
67	720-45130 INLET, E7, MODIFIED	1.000	EACH
68	721-43005 AUTOMATIC DRAINAGE GATE, 15 IN	1.000	EACH
69	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
70	801-03291 CONSTRUCTION SIGN, D	11.000	EACH
71	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
72	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	8,390.000	LFT
73	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	6,240.000	LFT
74	801-06625 DETOUR ROUTE MARKER ASSEMBLY	25.000	EACH
75	801-06640 CONSTRUCTION SIGN, A	29.000	EACH
76	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
77	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
78	801-07118 BARRICADE, III-A	48.000	LFT
79	801-07119 BARRICADE, III-B	36.000	LFT
80	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN	16.000	LFT
81	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	5.100	SFT
82	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	60.000	SFT
83	802-76055 SIGN POST, A	262.000	LFT
84	802-76065 SIGN POST, B	108.000	LFT
85	807-04967 CABLE	320.000	LFT
86	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	112.000	LFT
87	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	4,322.000	LFT
88	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	4,404.000	LFT
89	808-06716 LINE, REMOVE	1,618.000	LFT
90	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	18.000	LFT

CALL ORDER : 360

CONTRACT ID : R -33718-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE AND PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	205-06937 TEMPORARY SILT FENCE	180.000	LFT
9	211-09264 STRUCTURAL BACKFILL, TYPE 1	10.000	CYS
10	604-01268 HAND RAIL, ALUMINUM	94.000	LFT
11	604-06070 SIDEWALK, CONCRETE	600.000	SYS
12	604-07897 CURB RAMP, CONCRETE, C	3.000	SYS
13	604-07899 CURB RAMP, CONCRETE, E	17.000	SYS
14	604-07901 CURB RAMP, CONCRETE, G	25.000	SYS
15	605-06120 CURB, CONCRETE	46.000	LFT
16	610-08446 PCCP FOR APPROACHES, 6 IN	96.000	SYS
17	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
18	621-06560 MULCHED SEEDING, U	3,600.000	SYS
19	621-06567 WATER	12.000	KGAL
20	621-06575 SODDING, NURSERY	18.000	SYS
21	621-08161 PERMANENT TURF REINFORCEMENT MAT	62.000	SYS
22	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
23	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
24	715-05168 PIPE, TYPE 3 CIRCULAR 12 IN	48.000	LFT
25	715-46000 PIPE END SECTION, 12 IN	3.000	EACH
26	720-07309 TRENCH DRAIN	45.000	LFT
27	720-45260 PIPE CATCH BASIN, 12 IN	1.000	EACH
28	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
29	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
30	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	802-04314 SIGN	1.000	EACH
33	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	91.000	SFT
34	802-76055 SIGN POST, A	145.000	LFT
35	807-03950 LUMINAIRE, ORNAMENTAL	11.000	EACH
36	807-03951 LIGHT POLE, ORNAMENTAL	11.000	EACH
37	807-03972 CONDUIT, PVC, 1 IN, SCHEDULE 40, FOR ELECTRIC	1,400.000	LFT
38	807-04922 LIGHT STANDARD FOUNDATION	11.000	EACH
39	807-86810 SERVICE POINT, II	1.000	EACH
40	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	118.000	LFT
41	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	280.000	LFT

CALL ORDER : 400

CONTRACT ID : R -34128-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-52710 SIDEWALK, CONCRETE, REMOVE	1,897.000	SYS
9	207-08267 SUBGRADE TREATMENT, TYPE IIIA	375.000	SYS
10	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	453.000	TON
11	502-03289 QUALITY ASSURANCE ADJUSTMENT	1.000	DOL
12	604-07896 CURB RAMP, CONCRETE, B	10.000	SYS
13	604-07897 CURB RAMP, CONCRETE, C	55.000	SYS
14	604-07901 CURB RAMP, CONCRETE, G	43.000	SYS
15	604-07902 CURB RAMP, CONCRETE, H	24.000	SYS
16	604-07903 CURB RAMP, CONCRETE, K	64.000	SYS
17	604-08086 CURB RAMP, CONCRETE	113.000	SYS
18	604-91531 SIDEWALK, CONCRETE, 4 IN	2,037.000	SYS
19	605-02278 CURB, REMOVE	451.000	LFT
20	605-06140 CURB AND GUTTER, CONCRETE	451.000	LFT
21	610-08446 PCCP FOR APPROACHES, 6 IN	310.000	SYS
22	610-09108 PCCP FOR APPROACHES, 9 IN	65.000	SYS
23	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
24	621-06560 MULCHED SEEDING, U	235.000	SYS
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	16.000	SFT
27	805-02645 SIGNAL PEDESTAL FOUNDATION, A	2.000	EACH
28	805-06742 SOLAR POWERED FLASHING BEACON ASSEMBLY	2.000	EACH
29	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	970.000	LFT

CALL ORDER : 410

CONTRACT ID : R -34593-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	203-02000 EXCAVATION, COMMON	94.000	CYS
9	205-03371 SEDIMENT, REMOVE	20.000	CYS
10	205-06937 TEMPORARY SILT FENCE	1,435.000	LFT
11	207-09935 SUBGRADE TREATMENT, TYPE 1C	1,010.000	SYS
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	40.000	TON
13	303-01180 COMPACTED AGGREGATE, NO. 53	27.000	TON
14	304-07491 HMA PATCHING, TYPE C	105.500	TON
15	304-07494 WIDENING WITH HMA, TYPE C	141.000	TON
16	306-08034 MILLING, ASPHALT, 1 1/2 IN	6,965.000	SYS
17	306-08432 MILLING, APPROACH	450.000	SYS
18	402-07434 HMA SURFACE, TYPE C	635.000	TON
19	406-05520 ASPHALT FOR TACK COAT	2.200	TON
20	610-07488 HMA FOR APPROACHES, TYPE C	223.000	TON
21	621-06575 SODDING, NURSERY	100.000	SYS
22	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
23	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	12.000	MOS
24	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
25	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
26	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
27	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	828.000	LFT
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	828.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	17.000	EACH
30	801-06735 TUBULAR MARKER, PERMANENT	45.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,469.000	LFT
33	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
34	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	360.000	LFT
35	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,032.000	LFT
36	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	60.000	LFT
37	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
38	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	65.000	EACH

CALL ORDER : 414

CONTRACT ID : R -34763-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PATCH AND REHAB PAVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	678.000	TON
8	303-07449 COMPACTED AGGREGATE, NO. 73	833.000	TON
9	304-07490 HMA PATCHING, TYPE B	1,431.000	TON
10	306-08034 MILLING, ASPHALT, 1 1/2 IN	79,832.000	SYS
11	306-08042 MILLING, SCARIFICATION/PROFILE	10,110.000	SYS
12	306-08043 MILLING, TRANSITION	4,800.000	SYS
13	306-08432 MILLING, APPROACH	1,819.000	SYS
14	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	6,587.000	TON
15	402-07451 HMA WEDGE AND LEVEL, TYPE B	1,230.000	TON
16	406-05520 ASPHALT FOR TACK COAT	23.200	TON
17	610-07487 HMA FOR APPROACHES, TYPE B	150.000	TON
18	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
19	628-09401 FIELD OFFICE, A	7.000	MOS
20	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	7.000	MOS
21	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
22	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
23	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	3,525.000	LFT
24	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	3,525.000	LFT
25	801-06640 CONSTRUCTION SIGN, A	57.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	68,800.000	LFT
28	808-06716 LINE, REMOVE	1,314.000	LFT
29	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
30	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	760.000	LFT
31	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	524.000	LFT
32	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	30.000	LFT
33	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	5,830.000	LFT
34	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	41,400.000	LFT
35	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	15.000	LFT
36	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	747.000	EACH
37	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	747.000	EACH

CALL ORDER : 450

CONTRACT ID : RS-34213-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	CLEANING AND SEALING JOINTS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	408-07478 CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	3.000	TON
8	507-08272 JOINTS IN PCCP, SAW AND SEAL	35,769.000	LFT
9	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
10	628-09402 FIELD OFFICE, B	6.000	MOS
11	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	6.000	MOS
12	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
13	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	19.000	EACH
15	801-06710 FLASHING ARROW SIGN	40.000	DAY
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 470

CONTRACT ID : RS-34498-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	WEDGE AND LEVEL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	178.000	TON
10	303-07449 COMPACTED AGGREGATE, NO. 73	605.000	TON
11	304-07489 HMA PATCHING, TYPE A	1,054.000	TON
12	306-08043 MILLING, TRANSITION	940.000	SYS
13	306-08432 MILLING, APPROACH	1,506.000	SYS
14	402-07432 HMA SURFACE, TYPE A	3,994.000	TON
15	406-05520 ASPHALT FOR TACK COAT	13.700	TON
16	610-07486 HMA FOR APPROACHES, TYPE A	125.000	TON
17	615-06520 MONUMENT, RE-ESTABLISH	4.000	EACH
18	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
19	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
20	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	8.000	MOS
21	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
22	720-44000 CASTING, ADJUST TO GRADE	16.000	EACH
23	720-45615 STRUCTURE, INLET, RECONSTRUCTED	5.000	LFT
24	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
25	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,902.000	LFT
26	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	801-92448 CONSTRUCTION SIGNS, MOBILE	500.000	DAY
29	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	4,080.000	LFT
30	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	38,030.000	LFT
31	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	7,484.000	LFT
32	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
33	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	299.000	EACH

CALL ORDER : 480

CONTRACT ID : RS-34642-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INSTITUTIONAL ROAD PROJECT		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	304-07489 HMA PATCHING, TYPE A	7.700	TON
8	306-08034 MILLING, ASPHALT, 1 1/2 IN	9,600.000	SYS
9	402-07432 HMA SURFACE, TYPE A	832.000	TON
10	406-05520 ASPHALT FOR TACK COAT	5.000	TON
11	408-07504 CRACKS AND JOINTS IN ASPHALT PAVEMENT, SEAL	2.000	TON
12	603-06065 FENCE, CHAIN LINK, RESET	130.000	LFT
13	603-96521 FENCE GATE, CHAIN LINK, RESET	1.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	3.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	594.000	LFT
17	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN	36.000	LFT
18	808-97222 PAVEMENT MESSAGE MARKING, PAINT, HANDICAP SYMBOL	1.000	EACH

CALL ORDER : 510

CONTRACT ID : B -30069-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL BRIDGE PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	180.600	SFT
10	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	89.900	CYS
12	203-51223 EXCAVATION, WATERWAY	182.000	CYS
13	205-06937 TEMPORARY SILT FENCE	844.000	LFT
14	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	91.600	CYS
15	211-06467 AGGREGATE FOR END BENT BACKFILL	27.100	CYS
16	302-07455 DENSE GRADED SUBBASE	44.900	CYS
17	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,210.000	SYS
18	402-07432 HMA SURFACE, TYPE A	100.200	TON
19	402-07450 HMA WEDGE AND LEVEL, TYPE A	133.000	TON
20	402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE	18.100	TON
21	406-05521 ASPHALT FOR TACK COAT	2,420.000	SYS
22	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
23	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
24	604-91531 SIDEWALK, CONCRETE, 4 IN	220.600	SYS
25	605-06145 CURB AND GUTTER, B, CONCRETE	337.300	LFT
26	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	269.600	SYS
27	616-02320 GEOTEXTILES	588.600	SYS
28	616-06405 RIPRAP, REVETMENT	339.300	TON
29	621-06575 SODDING, NURSERY	471.600	SYS
30	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
31	628-09402 FIELD OFFICE, B	6.000	MOS
32	628-11007 CELLULAR TELEPHONE/RADIO SERVICE, 750 MINUTES	6.000	MOS
33	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
34	701-09665 PILE, STEEL PIPE, 0.375 IN, 14 IN	152.000	LFT
35	702-51005 CONCRETE, A, SUBSTRUCTURE	39.200	CYS
36	702-51863 FIELD DRILLED HOLE IN CONCRETE	330.000	EACH
37	702-92857 CONCRETE, C, SUBSTRUCTURE	26.400	CYS
38	703-06028 REINFORCING BARS	6,317.000	LBS
39	703-06029 REINFORCING BARS, EPOXY COATED	65,701.000	LBS
40	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	568.000	EACH
41	704-51002 CONCRETE, C, SUPERSTRUCTURE	173.800	CYS
42	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	4.000	EACH
43	706-09965 RAILING, CONCRETE, TX	215.800	LFT
44	709-51821 SURFACE SEAL	LUMP	LUMP
45	711-51038 STRUCTURAL STEEL	LUMP	LUMP
46	715-05407 PIPE, END BENT DRAIN, 6 IN	184.000	LFT
47	715-11360 INSERTION VALVE, 12 IN.	2.000	EACH
48	715-98165 WATER MAIN, 12 IN	160.000	LFT
49	801-03290 CONSTRUCTION SIGN, C	3.000	EACH

CALL ORDER : 510

CONTRACT ID : B -30069-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL BRIDGE PROJECT		
50 801-03291	CONSTRUCTION SIGN, D	4.000	EACH
51 801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	24.000	LFT
52 801-06640	CONSTRUCTION SIGN, A	12.000	EACH
53 801-06645	CONSTRUCTION SIGN, B	5.000	EACH
54 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
55 801-07119	BARRICADE, III-B	40.000	LFT
56 801-08508	TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	620.000	LFT
57 801-53072	TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP

CALL ORDER : 520

CONTRACT ID : B -30507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	883.000	SYS
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	202-96133 PIPE, REMOVE	113.000	LFT
12	203-02000 EXCAVATION, COMMON	72.000	CYS
13	203-02070 BORROW	315.000	CYS
14	203-51223 EXCAVATION, WATERWAY	210.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	5.000	TON
16	205-06937 TEMPORARY SILT FENCE	993.000	LFT
17	205-09543 NO 2 STONE	20.000	TON
18	207-08265 SUBGRADE TREATMENT, TYPE IIA	1,453.000	SYS
19	211-09265 STRUCTURAL BACKFILL, TYPE 2	18.000	CYS
20	211-09268 STRUCTURAL BACKFILL, TYPE 5	250.000	CYS
21	303-01180 COMPACTED AGGREGATE, NO. 53	603.000	TON
22	304-07493 WIDENING WITH HMA, TYPE B	17.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	462.000	SYS
24	402-07433 HMA SURFACE, TYPE B	111.000	TON
25	402-07438 HMA INTERMEDIATE, TYPE B	170.000	TON
26	402-07451 HMA WEDGE AND LEVEL, TYPE B	39.000	TON
27	406-05520 ASPHALT FOR TACK COAT	1.000	TON
28	601-02241 GUARDRAIL, REMOVE	708.000	LFT
29	601-02800 GUARDRAIL TRANSITION, TGT	4.000	EACH
30	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
31	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	468.750	LFT
32	616-02320 GEOTEXTILES	125.000	SYS
33	616-05689 RIPRAP, CLASS 2	230.000	TON
34	621-06545 FERTILIZER	0.300	TON
35	621-06553 SEED MIXTURE, R	112.000	LBS
36	621-06557 SEED MIXTURE, T	49.000	LBS
37	621-06565 MULCHING MATERIAL	2.000	TON
38	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
39	628-09402 FIELD OFFICE, B	9.000	MOS
40	628-11007 CELLULAR TELEPHONE/RADIO SERVICE, 750 MINUTES	18.000	MOS
41	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
42	702-51863 FIELD DRILLED HOLE IN CONCRETE	48.000	EACH
43	702-93722 CONCRETE, C	1.900	CYS
44	703-06029 REINFORCING BARS, EPOXY COATED	261.000	LBS
45	706-06347 RAILING, STEEL CF-1	36.000	LFT
46	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	97.000	LFT
47	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	23.000	LFT
48	715-11446 CONCRETE ANCHOR, 24 IN.	4.000	EACH
49	720-95409 MANHOLE, J4, MODIFIED	2.000	EACH

CALL ORDER : 520

CONTRACT ID : B -30507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50 723-11403	STRUCTURE, COATED REINFORCED CONCRETE,	33.083	LFT
51 801-03290	CONSTRUCTION SIGN, C	2.000	EACH
52 801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
53 801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.000	EACH
54 801-06640	CONSTRUCTION SIGN, A	16.000	EACH
55 801-06645	CONSTRUCTION SIGN, B	2.000	EACH
56 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
57 801-07118	BARRICADE, III-A	48.000	LFT
58 801-07119	BARRICADE, III-B	84.000	LFT
59 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,100.000	LFT
60 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,100.000	LFT

CALL ORDER : 530

CONTRACT ID : B -30959-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-01261 TESTING FOR ASBESTOS	6.000	EACH
10	202-02279 CURB AND GUTTER, REMOVE	124.000	LFT
11	202-03729 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	100.000	LFT
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	202-91840 FENCE, CHAIN LINK, REMOVE	100.000	LFT
14	203-02000 EXCAVATION, COMMON	92.000	CYS
15	203-51223 EXCAVATION, WATERWAY	900.000	CYS
16	205-06937 TEMPORARY SILT FENCE	102.000	LFT
17	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	201.000	CYS
18	206-51235 COFFERDAM	LUMP	LUMP
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	230.000	SYS
20	211-09267 STRUCTURAL BACKFILL, TYPE 4	7.000	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	116.000	TON
22	306-08043 MILLING, TRANSITION	184.000	SYS
23	402-07432 HMA SURFACE, TYPE A	30.000	TON
24	402-07435 HMA INTERMEDIATE, TYPE A	24.000	TON
25	406-05520 ASPHALT FOR TACK COAT	1.000	TON
26	601-01522 GUARDRAIL, TRANSITION TYPE TGB	1.000	EACH
27	601-02103 GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	13.000	LFT
28	601-05999 CURVED TERMINAL END	1.000	EACH
29	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	12.500	LFT
30	603-01932 FENCE, CHAIN LINK, 96 IN	74.000	LFT
31	603-02009 FENCE GATE, CHAIN LINK, 96 IN X 20 FT	2.000	EACH
32	605-06095 CURB, INTEGRAL, B, CONCRETE	30.000	LFT
33	605-52807 CURB AND GUTTER, COMBINED	56.000	LFT
34	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	108.000	SYS
35	610-08446 PCCP FOR APPROACHES, 6 IN	30.000	SYS
36	616-02320 GEOTEXTILES	909.000	SYS
37	616-06405 RIPRAP, REVETMENT	618.000	TON
38	621-06574 SODDING	158.000	SYS
39	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	15.000	EACH
40	628-09401 FIELD OFFICE, A	6.000	MOS
41	701-09662 PILE, STEEL PIPE, 0.250 IN, 14 IN	1,661.000	LFT
42	702-51005 CONCRETE, A, SUBSTRUCTURE	93.000	CYS
43	702-51015 CONCRETE, B, FOOTINGS	8.000	CYS
44	702-51046 CONCRETE, FOUNDATION SEAL	25.000	CYS
45	703-06028 REINFORCING BARS	9,552.000	LBS
46	703-06029 REINFORCING BARS, EPOXY COATED	55,837.000	LBS
47	704-51002 CONCRETE, C, SUPERSTRUCTURE	246.000	CYS
48	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
49	706-51020 RAILING, CONCRETE, C	16.000	CYS

CALL ORDER : 530

CONTRACT ID : B -30959-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	709-51821 SURFACE SEAL	LUMP	LUMP
51	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
52	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
53	801-04308 ROAD CLOSURE SIGN ASSEMBLY	1.000	EACH
54	801-06625 DETOUR ROUTE MARKER ASSEMBLY	22.000	EACH
55	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
56	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
57	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
58	801-07118 BARRICADE, III-A	72.000	LFT
59	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	21.000	LFT
60	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH

CALL ORDER : 540

CONTRACT ID : B -31376-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL BRIDGE PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	202-52710 SIDEWALK, CONCRETE, REMOVE	36.000	SYS
11	202-90747 RETAINING WALL, REMOVE	36.000	LFT
12	202-96133 PIPE, REMOVE	35.000	LFT
13	203-02000 EXCAVATION, COMMON	100.000	CYS
14	203-02070 BORROW	275.000	CYS
15	205-03371 SEDIMENT, REMOVE	25.000	CYS
16	205-06933 TEMPORARY DITCH INLET PROTECTION	4.000	EACH
17	205-06934 TEMPORARY MULCHING	4.000	TON
18	205-06937 TEMPORARY SILT FENCE	288.000	LFT
19	205-09543 NO 2 STONE	100.000	TON
20	207-08263 SUBGRADE TREATMENT, TYPE IA	596.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	349.000	SYS
22	211-06467 AGGREGATE FOR END BENT BACKFILL	32.800	CYS
23	211-09264 STRUCTURAL BACKFILL, TYPE 1	55.000	CYS
24	211-09266 STRUCTURAL BACKFILL, TYPE 3	2.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	148.000	TON
26	302-07455 DENSE GRADED SUBBASE	29.200	CYS
27	306-08034 MILLING, ASPHALT, 1 1/2 IN	143.000	SYS
28	402-07433 HMA SURFACE, TYPE B	37.000	TON
29	402-07438 HMA INTERMEDIATE, TYPE B	61.000	TON
30	604-06070 SIDEWALK, CONCRETE	28.200	SYS
31	604-07902 CURB RAMP, CONCRETE, H	5.600	SYS
32	604-91531 SIDEWALK, CONCRETE, 4 IN	126.000	SYS
33	605-06095 CURB, INTEGRAL, B, CONCRETE	40.000	LFT
34	605-06140 CURB AND GUTTER, CONCRETE	233.000	LFT
35	605-06145 CURB AND GUTTER, B, CONCRETE	71.500	LFT
36	607-06335 PAVED SIDE DITCH, A	16.000	LFT
37	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	175.000	SYS
38	610-07487 HMA FOR APPROACHES, TYPE B	35.000	TON
39	610-08446 PCCP FOR APPROACHES, 6 IN	221.000	SYS
40	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
41	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
42	616-02320 GEOTEXTILES	325.000	SYS
43	616-06405 RIPRAP, REVETMENT	185.000	TON
44	621-02770 EROSION CONTROL BLANKET	69.000	SYS
45	621-06557 SEED MIXTURE, T	225.000	LBS
46	621-06567 WATER	1.800	KGAL
47	621-06575 SODDING, NURSERY	491.000	SYS
48	628-09401 FIELD OFFICE, A	4.000	MOS
49	701-51195 PILE, STEEL H, HP 12 IN X 53	450.000	LFT

CALL ORDER : 540

CONTRACT ID : B -31376-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL BRIDGE PROJECT		
50	703-06029 REINFORCING BARS, EPOXY COATED	31,326.000	LBS
51	704-51002 CONCRETE, C, SUPERSTRUCTURE	108.200	CYS
52	706-06354 CONCRETE BRIDGE RAILING TRANSITION, TPS-2	4.000	EACH
53	706-09964 RAILING, CONCRETE, PS-2	112.000	LFT
54	706-51020 RAILING, CONCRETE, C	4.400	CYS
55	707-11494 STRUCTURAL MEMBER, CONCRETE BOX BEAM, 21 IN. X 48 IN.	920.000	LFT
56	709-51821 SURFACE SEAL	LUMP	LUMP
57	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	42.000	LFT
58	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	46.000	LFT
59	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	80.000	LFT
60	715-05407 PIPE, END BENT DRAIN, 6 IN	110.000	LFT
61	720-45270 PIPE CATCH BASIN, 18 IN	2.000	EACH
62	720-45410 MANHOLE, C4	1.000	EACH
63	720-93411 INLET, C15, MODIFIED	2.000	EACH
64	720-98174 INLET, B15	1.000	EACH
65	732-08419 MODULAR BLOCK WALL	68.000	SYS
66	732-08421 MODULAR BLOCK WALL ERECTION	68.000	SYS
67	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
68	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
69	801-06625 DETOUR ROUTE MARKER ASSEMBLY	23.000	EACH
70	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
71	801-07118 BARRICADE, III-A	48.000	LFT
72	801-07119 BARRICADE, III-B	16.000	LFT
73	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	21.000	LFT
74	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	2.000	EACH
75	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	12.500	SFT
76	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	700.000	LFT
77	808-06726 TRANSVERSE MARKING, PAINT,	19.000	LFT

CALL ORDER : 550

CONTRACT ID : B -31617-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	475.400	CYS
11	203-51223 EXCAVATION, WATERWAY	564.500	CYS
12	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
13	205-06937 TEMPORARY SILT FENCE	600.000	LFT
14	205-09543 NO 2 STONE	100.000	TON
15	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	113.700	CYS
16	206-51235 COFFERDAM	LUMP	LUMP
17	207-08263 SUBGRADE TREATMENT, TYPE IA	1,537.500	SYS
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	164.200	SYS
19	211-06467 AGGREGATE FOR END BENT BACKFILL	31.700	CYS
20	211-09264 STRUCTURAL BACKFILL, TYPE 1	124.900	CYS
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	52.000	CYS
22	211-09268 STRUCTURAL BACKFILL, TYPE 5	311.900	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	54.700	TON
24	302-07455 DENSE GRADED SUBBASE	37.800	CYS
25	402-07433 HMA SURFACE, TYPE B	81.000	TON
26	402-07438 HMA INTERMEDIATE, TYPE B	134.600	TON
27	402-07441 HMA BASE, TYPE B	472.300	TON
28	406-05521 ASPHALT FOR TACK COAT	2,926.000	SYS
29	601-01522 GUARDRAIL, TRANSITION TYPE TGB	2.000	EACH
30	604-07901 CURB RAMP, CONCRETE, G	11.000	SYS
31	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
32	604-06070 SIDEWALK, CONCRETE	278.100	SYS
33	604-07902 CURB RAMP, CONCRETE, H	3.800	SYS
34	605-06140 CURB AND GUTTER, CONCRETE	462.500	LFT
35	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	226.600	SYS
36	610-07487 HMA FOR APPROACHES, TYPE B	7.500	TON
37	610-08446 PCCP FOR APPROACHES, 6 IN	119.300	SYS
38	610-09108 PCCP FOR APPROACHES, 9 IN	44.900	SYS
39	615-06490 RIGHT OF WAY MARKER	10.000	EACH
40	615-06505 MONUMENT, B	2.000	EACH
41	616-02320 GEOTEXTILES	321.400	SYS
42	616-05688 RIPRAP, CLASS 1	172.500	TON
43	621-06575 SODDING, NURSERY	687.100	SYS
44	628-09401 FIELD OFFICE, A	8.000	MOS
45	701-09739 PILE SHOE, HP 12 X 53	37.000	EACH
46	701-09779 PREBORED HOLE, 15"	90.000	LFT
47	701-51195 PILE, STEEL H, HP 12 IN X 53	1,759.000	LFT
48	702-90915 CONCRETE, CLASS A	121.500	CYS
49	702-92857 CONCRETE, C, SUBSTRUCTURE	32.300	CYS

CALL ORDER : 550

CONTRACT ID : B -31617-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	702-93722 CONCRETE, C	4.100	CYS
51	703-06028 REINFORCING BARS	14,700.000	LBS
52	703-06029 REINFORCING BARS, EPOXY COATED	31,468.000	LBS
53	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	2.000	EACH
54	704-51002 CONCRETE, C, SUPERSTRUCTURE	73.200	CYS
55	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	2.000	EACH
56	706-09965 RAILING, CONCRETE, TX	65.000	LFT
57	707-11443 STRUCTURAL MEMBER, CONCRETE BOX BEAM,	157.500	LFT
58	709-51821 SURFACE SEAL	LUMP	LUMP
59	711-51070 ANCHOR PLATE, AP 1	20.000	EACH
60	715-03025 SANITARY MANHOLE	1.000	EACH
61	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	216.100	LFT
62	715-05161 PIPE, TYPE 2 CIRCULAR 48 IN	36.900	LFT
63	715-05408 PIPE SANITARY SEWER 8 IN	106.000	LFT
64	720-45005 INLET, A2	1.000	EACH
65	720-97958 MANHOLE, K2	1.000	EACH
66	720-98174 INLET, B15	3.000	EACH
67	720-98555 INLET, C15	5.000	EACH
68	731-93947 LEVELING PAD, CONCRETE	175.700	LFT
69	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
70	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
71	801-06625 DETOUR ROUTE MARKER ASSEMBLY	17.000	EACH
72	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
73	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
74	801-07118 BARRICADE, III-A	87.000	LFT
75	801-07119 BARRICADE, III-B	75.000	LFT
76	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	5.000	SFT
77	802-76055 SIGN POST, A	10.000	LFT
78	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	746.000	LFT

CALL ORDER : 560

CONTRACT ID : B -31717-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
10	202-96133 PIPE, REMOVE	199.000	LFT
11	203-02000 EXCAVATION, COMMON	675.000	CYS
12	203-51223 EXCAVATION, WATERWAY	85.000	CYS
13	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	28.000	TON
14	205-06937 TEMPORARY SILT FENCE	1,236.000	LFT
15	205-09543 NO 2 STONE	89.000	TON
16	207-08265 SUBGRADE TREATMENT, TYPE IIA	1,826.000	SYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	103.000	SYS
18	211-09265 STRUCTURAL BACKFILL, TYPE 2	44.000	CYS
19	211-09267 STRUCTURAL BACKFILL, TYPE 4	10.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	788.000	TON
21	302-07455 DENSE GRADED SUBBASE	24.000	CYS
22	304-07493 WIDENING WITH HMA, TYPE B	6.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	230.000	SYS
24	402-07433 HMA SURFACE, TYPE B	153.000	TON
25	402-07438 HMA INTERMEDIATE, TYPE B	306.000	TON
26	406-05521 ASPHALT FOR TACK COAT	1,850.000	SYS
27	601-01128 GUARDRAIL, TRANSITION TYPE WGB	4.000	EACH
28	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	2.000	EACH
29	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
30	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	219.000	LFT
31	602-06729 BARRIER DELINEATOR	4.000	EACH
32	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	146.000	SYS
33	610-07487 HMA FOR APPROACHES, TYPE B	28.000	TON
34	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
35	615-06505 MONUMENT, B	2.000	EACH
36	616-02320 GEOTEXTILES	290.000	SYS
37	616-05688 RIPRAP, CLASS 1	213.000	TON
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
39	621-06559 MULCHED SEEDING, R	1,633.000	SYS
40	621-06567 WATER	1.100	KGAL
41	621-06574 SODDING	308.000	SYS
42	701-09558 TEST PILE, INDICATOR, PRODUCTION	106.000	LFT
43	701-09560 TEST PILE, INDICATOR, RESTRIKE	2.000	EACH
44	701-09679 CONICAL PILE TIP, 14 IN	8.000	EACH
45	701-09826 PILE, STEEL PIPE, 0.5 IN., 14 IN.	318.000	LFT
46	703-06029 REINFORCING BARS, EPOXY COATED	38,106.000	LBS
47	704-51002 CONCRETE, C, SUPERSTRUCTURE	157.500	CYS
48	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	4.000	EACH
49	706-51020 RAILING, CONCRETE, C	2.600	CYS

CALL ORDER : 560

CONTRACT ID : B -31717-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	709-51821 SURFACE SEAL	LUMP	LUMP
51	715-05116 PIPE, TYPE 1 CIRCULAR 8 IN	14.000	LFT
52	715-05168 PIPE, TYPE 3 CIRCULAR 12 IN	16.000	LFT
53	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	108.000	LFT
54	715-46000 PIPE END SECTION, 12 IN	1.000	EACH
55	715-46005 PIPE END SECTION, 15 IN	6.000	EACH
56	720-45410 MANHOLE, C4	1.000	EACH
57	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
58	801-06625 DETOUR ROUTE MARKER ASSEMBLY	28.000	EACH
59	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
60	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
61	801-07118 BARRICADE, III-A	72.000	LFT
62	801-07119 BARRICADE, III-B	72.000	LFT
63	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	179.000	LFT
64	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	90.000	LFT
65	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	1,071.000	LFT
66	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	536.000	LFT

CALL ORDER : 570

CONTRACT ID : B -33181-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	74,745.000	CYS
12	205-03371 SEDIMENT, REMOVE	40.000	CYS
13	205-06932 TEMPORARY CHECK DAM, STRAW BALES	710.000	LFT
14	205-06936 TEMPORARY SEDIMENT TRAP	27.000	TON
15	205-06937 TEMPORARY SILT FENCE	170.000	LFT
16	205-06938 TEMPORARY SLOPE DRAIN	44.000	LFT
17	205-09543 NO 2 STONE	100.000	TON
18	206-51220 EXCAVATION, WET	192.000	CYS
19	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	12.000	CYS
20	207-08262 SUBGRADE TREATMENT, TYPE I	9,305.000	SYS
21	207-08265 SUBGRADE TREATMENT, TYPE IIA	2,590.000	SYS
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	486.000	SYS
23	211-09264 STRUCTURAL BACKFILL, TYPE 1	60.000	CYS
24	211-09267 STRUCTURAL BACKFILL, TYPE 4	10.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,840.000	TON
26	302-07455 DENSE GRADED SUBBASE	38.000	CYS
27	402-07432 HMA SURFACE, TYPE A	1,130.000	TON
28	402-07435 HMA INTERMEDIATE, TYPE A	1,010.000	TON
29	402-07440 HMA BASE, TYPE A	875.000	TON
30	406-05521 ASPHALT FOR TACK COAT	14,575.000	SYS
31	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
32	601-01625 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 1	1.000	EACH
33	601-01626 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
34	601-06037 GUARDRAIL END TREATMENT, I	2.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
36	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	200.000	LFT
37	602-06729 BARRIER DELINEATOR	10.000	EACH
38	603-06040 FENCE, FARM FIELD, 47 IN	851.000	LFT
39	603-06052 FENCE GATE, FARM FIELD, 47" X 12'	2.000	EACH
40	608-04395 AGGREGATE FOR SHOULDER DRAINS	10.000	TON
41	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	218.000	SYS
42	610-07486 HMA FOR APPROACHES, TYPE A	136.000	TON
43	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
44	615-06505 MONUMENT, B	5.000	EACH
45	615-06510 MONUMENT, C	2.000	EACH
46	616-02320 GEOTEXTILES	2,289.000	SYS
47	616-05688 RIPRAP, CLASS 1	690.000	TON
48	616-06451 RIPRAP, UNIFORM	882.000	TON
49	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH

CALL ORDER : 570

CONTRACT ID : B -33181-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-02770 EROSION CONTROL BLANKET	13,805.000	SYS
51	621-03787 SEED MIXTURE, D	15.000	LBS
52	621-06545 FERTILIZER	2.400	TON
53	621-06553 SEED MIXTURE, R	800.000	LBS
54	621-06557 SEED MIXTURE, T	870.000	LBS
55	621-06557 SEED MIXTURE, T	56.000	LBS
56	621-06565 MULCHING MATERIAL	19.000	TON
57	621-06567 WATER	4.000	KGAL
58	621-06574 SODDING	793.000	SYS
59	621-06575 SODDING, NURSERY	295.000	SYS
60	622-52436 SIGN, DO NOT MOW OR SPRAY	3.000	EACH
61	622-91786 SEEDLING	165.000	EACH
62	628-09401 FIELD OFFICE, A	15.000	MOS
63	701-09739 PILE SHOE, HP 12 X 53	36.000	EACH
64	701-51195 PILE, STEEL H, HP 12 IN X 53	1,602.000	LFT
65	702-51005 CONCRETE, A, SUBSTRUCTURE	133.200	CYS
66	703-06028 REINFORCING BARS	11,852.000	LBS
67	703-06029 REINFORCING BARS, EPOXY COATED	80,724.000	LBS
68	704-51002 CONCRETE, C, SUPERSTRUCTURE	318.000	CYS
69	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
70	706-51020 RAILING, CONCRETE, C	19.500	CYS
71	709-51821 SURFACE SEAL	LUMP	LUMP
72	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	50.000	LFT
73	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	80.000	LFT
74	715-46005 PIPE END SECTION, 15 IN	4.000	EACH
75	715-46020 PIPE END SECTION, 24 IN	2.000	EACH
76	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
77	801-06625 DETOUR ROUTE MARKER ASSEMBLY	1.000	EACH
78	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
79	801-07118 BARRICADE, III-A	108.000	LFT
80	801-07119 BARRICADE, III-B	72.000	LFT
81	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	37.500	SFT
82	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	8.000	SFT
83	802-76055 SIGN POST, A	119.500	LFT

CALL ORDER : 580

CONTRACT ID : B -33263-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL BRIDGE PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	259.200	SYS
11	202-02279 CURB AND GUTTER, REMOVE	79.800	LFT
12	202-91385 INLET, REMOVE	1.000	EACH
13	202-93995 SIGNAL POLE FOUNDATION, REMOVE	3.000	EACH
14	202-93999 SIGNAL POLE, REMOVE	4.000	EACH
15	202-96133 PIPE, REMOVE	78.000	LFT
16	202-98370 POLE, REMOVE	1.000	EACH
17	203-02000 EXCAVATION, COMMON	2,421.000	CYS
18	205-03371 SEDIMENT, REMOVE	15.000	CYS
19	205-06932 TEMPORARY CHECK DAM, STRAW BALES	126.000	LFT
20	205-06933 TEMPORARY DITCH INLET PROTECTION	5.000	EACH
21	205-06937 TEMPORARY SILT FENCE	2,360.000	LFT
22	205-09543 NO 2 STONE	100.000	TON
23	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	502.000	CYS
24	210-08351 PLAQUE	2.000	EACH
25	211-02050 B BORROW	373.000	CYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	211.000	CYS
27	211-09266 STRUCTURAL BACKFILL, TYPE 3	3,517.000	CYS
28	303-01180 COMPACTED AGGREGATE, NO. 53	1,044.300	TON
29	303-07449 COMPACTED AGGREGATE, NO. 73	67.400	TON
30	402-07432 HMA SURFACE, TYPE A	152.000	TON
31	402-07435 HMA INTERMEDIATE, TYPE A	255.000	TON
32	406-05521 ASPHALT FOR TACK COAT	1,844.200	SYS
33	502-06627 PCCP, 6 IN	224.900	SYS
34	502-10134 SNOW MELT SYSTEM	5,244.000	SFT
35	603-02736 FENCE, WOOD, RESET	464.000	LFT
36	604-07901 CURB RAMP, CONCRETE, G	12.000	SYS
37	604-95344 HANDRAIL, PEDESTRIAN	2,080.000	LFT
38	605-52807 CURB AND GUTTER, COMBINED	70.000	LFT
39	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	24.000	SYS
40	621-02770 EROSION CONTROL BLANKET	58.000	SYS
41	621-06560 MULCHED SEEDING, U	1,656.000	SYS
42	621-06575 SODDING, NURSERY	401.000	SYS
43	621-98038 MULCH, HARDWOOD SHREDDED BARK	6.400	CYS
44	622-05625 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT	7.000	EACH
45	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	42.000	EACH
46	622-05643 PLANT, DECIDUOUS TREE, MULTI-STEM, 48 IN OR UNDER	8.000	EACH
47	628-09402 FIELD OFFICE, B	12.000	MOS
48	701-51190 PILE, STEEL H, HP 10 IN X 42	350.000	LFT
49	701-51195 PILE, STEEL H, HP 12 IN X 53	480.000	LFT

CALL ORDER : 580

CONTRACT ID : B -33263-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL BRIDGE PROJECT		
50	702-51005 CONCRETE, A, SUBSTRUCTURE	231.000	CYS
51	702-51015 CONCRETE, B, FOOTINGS	94.600	CYS
52	703-06029 REINFORCING BARS, EPOXY COATED	18,656.000	LBS
53	704-51106 DECK DRAIN	12.000	EACH
54	709-51821 SURFACE SEAL	LUMP	LUMP
55	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP
56	715-05146 PIPE, TYPE 2 CIRCULAR 6 IN	443.000	LFT
57	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	408.000	LFT
58	715-46000 PIPE END SECTION, 12 IN	1.000	EACH
59	720-45030 INLET, E7	2.000	EACH
60	720-45035 INLET, F7	3.000	EACH
61	720-45270 PIPE CATCH BASIN, 18 IN	1.000	EACH
62	720-98625 MANHOLE, C4, DROP	1.000	EACH
63	724-51885 STRUCTURAL EXPANSION JOINT, BS6	89.000	LFT
64	732-08419 MODULAR BLOCK WALL	1,336.000	SYS
65	732-08421 MODULAR BLOCK WALL ERECTION	1,336.000	SYS
66	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
67	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
68	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
69	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
70	801-07119 BARRICADE, III-B	144.000	LFT
71	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	40.000	LFT
72	801-94295 SIGNAL HEAD, RELOCATE	9.000	EACH
73	802-04314 SIGN	4.000	EACH
74	802-07060 SIGN, SHEET, RELOCATE	3.000	EACH
75	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	185.000	SFT
76	802-74050 SIGN, OVERHEAD, REMOVE	1.000	EACH
77	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
78	805-01579 MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	LUMP	LUMP
79	805-09366 SIGNAL SUPPORT FOUNDATION, 36 IN DIAMETER X 120 IN	4.000	EACH
80	805-78370 PEDESTRIAN PUSH BUTTON	2.000	EACH
81	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
82	805-78420 DISCONNECT HANGER	3.000	EACH
83	805-78480 SIGNAL CABLE, 3C/14GA	414.000	LFT
84	805-78485 SIGNAL CABLE, 5C/14GA	611.000	LFT
85	805-78490 SIGNAL CABLE, 7C/14GA	338.000	LFT
86	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
87	807-86810 SERVICE POINT, II	1.000	EACH
88	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	705.000	LFT
89	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	473.000	LFT
90	808-06716 LINE, REMOVE	120.000	LFT
91	808-75015 LINE, PAINT, SOLID, WHITE, 12 IN	30.000	LFT

CALL ORDER : 620

CONTRACT ID : M -34511-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 GUARDRAIL MAINTENANCE OR REPAIR			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	601-03447 CAT BRACKET MK BK, FOR TRANSITION CABLE, MK CA	2.000	EACH
5	601-03448 CAT TRANSITION STEEL POST BRACKET, MK D	4.000	EACH
6	601-03462 GUARDRAIL, POST STEEL, 8.5 LBS PER LFT, 7 FT. 0 IN.	330.000	EACH
7	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	15.000	EACH
8	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	3.000	EACH
9	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	3.000	EACH
10	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	3.000	EACH
11	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	3.000	EACH
12	601-03683 COMBINATION ATTENUATING TERMINAL, REPAIR, LABOR ONLY	50.000	HRS
13	601-05399 GUARDRAIL	LUMP	LUMP
14	601-05856 CAT	2.000	EACH
15	601-05856 CAT	2.000	EACH
16	601-05856 CAT	2.000	EACH
17	601-05856 CAT	2.000	EACH
18	601-05856 CAT	4.000	EACH
19	601-05856 CAT	4.000	EACH
20	601-05856 CAT	7.000	EACH
21	601-05856 CAT	2.000	EACH
22	601-05857 GUARDRAIL, BLOCKOUT, WOOD, 4 IN. X 6 IN.	30.000	EACH
23	601-06273 GUARDRAIL END TREATMENT, SKT-350	2.000	EACH
24	601-06273 GUARDRAIL END TREATMENT, SKT-350	2.000	EACH
25	601-06273 GUARDRAIL END TREATMENT, SKT-350	2.000	EACH
26	601-06273 GUARDRAIL END TREATMENT, SKT-350	2.000	EACH
27	601-06273 GUARDRAIL END TREATMENT, SKT-350	2.000	EACH
28	601-61340 GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN.	4.000	EACH
29	601-61350 GUARDRAIL POST BRACKET, 15.5 LBS PER LFT., GALVANIZED,	6.000	EACH
30	601-61390 GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE,	15.000	EACH
31	601-62530 GUARDRAIL PIER CONNECTION, ES	2.000	EACH
32	601-62540 GUARDRAIL POST, PLUMB	1,200.000	EACH
33	601-91428 GUARDRAIL ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	20.000	EACH
34	601-91432 GUARDRAIL ATTENUATING TERMINAL, SIDE PLATE, MKSD	31.000	EACH
35	601-91504 GUARDRAIL POST, W1, 10 IN X 10 IN	9.000	EACH
36	601-91505 GUARDRAIL POST, W2, 8 IN. X 8 IN.	4.000	EACH
37	601-91542 GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	32.000	EACH
38	601-91649 GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	3.000	EACH
39	601-91653 GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	3.000	EACH
40	601-92973 GUARDRAIL END TREATMENT, LABOR ONLY	40.000	EACH
41	601-93346 GUARDRAIL CONNECTOR, AS	4.000	EACH
42	601-94689 GUARDRAIL END TREATMENT, OS	45.000	EACH
43	601-94690 GUARDRAIL END TREATMENT, MS	18.000	EACH
44	601-95972 GUARDRAIL POST (CRT), 8 IN X 6 IN TREATED LUMBER,	90.000	EACH
45	601-97950 GUARDRAIL POST BRACKET, TREATED TIMBER, 6 IN. X 6 IN.	190.000	EACH
46	601-99123 GUARDRAIL, TRANSITION, GP	2.000	EACH
47	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
48	628-09402 FIELD OFFICE, B	12.000	MOS
49	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	24.000	MOS

CALL ORDER : 620

CONTRACT ID : M -34511-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE OR REPAIR		
50 628-11068	CELLULAR TELEPHONE/RADIO	2.000	EACH
51 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 680

CONTRACT ID : T -33890-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
9	628-09401 FIELD OFFICE, A	6.000	MOS
10	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
11	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
12	801-06710 FLASHING ARROW SIGN	150.000	DAY
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
14	801-92448 CONSTRUCTION SIGNS, MOBILE	150.000	DAY
15	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	13,540.000	SFT
16	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	1,162.000	SFT
17	802-76065 SIGN POST, B	33,332.000	LFT
18	804-06771 DELINEATOR POST, FLEXIBLE	665.000	EACH

CALL ORDER : 690

CONTRACT ID : T -34354-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-94747 POST, REMOVE	1,411.000	EACH
8	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	12.000	MOS
9	628-09409 MOBILE INTERNET SERVICE	12.000	MOS
10	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
11	802-04089 SIGN, SHEET, REMOVE	1,411.000	EACH
12	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	14,710.000	LFT
13	802-07060 SIGN, SHEET, RELOCATE	480.000	EACH
14	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	6,500.000	SFT
15	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	1,930.000	SFT

CALL ORDER : 700

CONTRACT ID : T -34504-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
9	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
10	628-11007 CELLULAR TELEPHONE/RADIO SERVICE, 750 MINUTES	6.000	MOS
11	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
12	801-06710 FLASHING ARROW SIGN	200.000	DAY
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
14	801-92448 CONSTRUCTION SIGNS, MOBILE	200.000	DAY
15	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	9,215.000	SFT
16	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	443.000	SFT
17	802-76055 SIGN POST, A	8,368.000	LFT
18	802-76065 SIGN POST, B	13,536.000	LFT
19	802-97812 STREET NAME IDENTIFICATION SIGN	515.000	EACH
20	804-06771 DELINEATOR POST, FLEXIBLE	720.000	EACH

CALL ORDER : 710

CONTRACT ID : T -34516-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
8	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	11.000	MOS
9	628-09409 MOBILE INTERNET SERVICE	11.000	MOS
10	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	9.000	MOS
11	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
12	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
13	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	7,386.000	LFT
14	802-07060 SIGN, SHEET, RELOCATE	21.000	EACH
15	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	11,415.360	SFT
16	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	2,250.480	SFT
17	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	905.600	SFT

CALL ORDER : 720

CONTRACT ID : T -34698-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-94747 POST, REMOVE	2,627.000	EACH
8	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	12.000	MOS
9	628-09409 MOBILE INTERNET SERVICE	12.000	MOS
10	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
11	802-04089 SIGN, SHEET, REMOVE	2,627.000	EACH
12	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	25,500.000	LFT
13	802-07060 SIGN, SHEET, RELOCATE	900.000	EACH
14	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	10,430.000	SFT
15	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	3,230.000	SFT

