

CALL ORDER : 130

CONTRACT ID : IR-34284-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|--|--|-----------|-------|
| SECTION NO. 0001 DEMOLITION HOUSES AND BUILDINGS | | | |
| 1 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 2 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 3 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.000 | DOL |
| 4 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 5 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 6 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 7 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 8 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 9 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 10 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 11 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 12 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 13 | 202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE | 4,172.000 | SFT |
| 14 | 205-06937 TEMPORARY SILT FENCE | 2,463.000 | LFT |
| 15 | 205-09543 NO 2 STONE | 250.000 | TON |
| 16 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 1.000 | EACH |
| 17 | 621-06560 MULCHED SEEDING, U | 7,932.000 | SYS |
| 18 | 621-06570 TOPSOIL | 250.000 | CYS |
| 19 | 801-03290 CONSTRUCTION SIGN, C | 4.000 | EACH |
| 20 | 801-06640 CONSTRUCTION SIGN, A | 8.000 | EACH |
| 21 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |

CALL ORDER : 140

CONTRACT ID : IR-34452-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-------------|-------|
| SECTION NO. 0001 | NEW ROAD CONSTRUCTION PROJECT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 3 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 4 | 113-01614 PARTNERING OVERHEAD | LUMP | LUMP |
| 5 | 201-02250 TREE, 10 IN, REMOVE | 3.000 | EACH |
| 6 | 201-02260 TREE, 30 IN, REMOVE | 12.000 | EACH |
| 7 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 8 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 9 | 202-01261 TESTING FOR ASBESTOS | 7.000 | EACH |
| 10 | 202-02271 HEADWALL, REMOVE | 10.000 | EACH |
| 11 | 202-02272 PAVED SIDE DITCH, REMOVE | 365.000 | LFT |
| 12 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 13 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 14 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 15 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 16 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 17 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 18 | 202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO | LUMP | LUMP |
| 19 | 202-74035 SIGN, REMOVE | 5.000 | EACH |
| 20 | 202-74035 SIGN, REMOVE | 1.000 | EACH |
| 21 | 202-91385 INLET, REMOVE | 1.000 | EACH |
| 22 | 202-91840 FENCE, CHAIN LINK, REMOVE | 72.000 | LFT |
| 23 | 202-93615 CONCRETE, REMOVE | 3.000 | SYS |
| 24 | 202-96133 PIPE, REMOVE | 799.000 | LFT |
| 25 | 203-02000 EXCAVATION, COMMON | 12,497.000 | CYS |
| 26 | 203-02010 EXCAVATION, ROCK | 17,500.000 | CYS |
| 27 | 204-08415 STAKE, SETTLEMENT | 6.000 | EACH |
| 28 | 205-03371 SEDIMENT, REMOVE | 1,687.000 | CYS |
| 29 | 205-06930 SPLASHPAD, RIPRAP | 203.000 | TON |
| 30 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 1,135.200 | TON |
| 31 | 205-06932 TEMPORARY CHECK DAM, STRAW BALES | 1,092.000 | LFT |
| 32 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 9.000 | EACH |
| 33 | 205-06936 TEMPORARY SEDIMENT TRAP | 1,252.000 | TON |
| 34 | 205-06937 TEMPORARY SILT FENCE | 22,096.000 | LFT |
| 35 | 205-06938 TEMPORARY SLOPE DRAIN | 811.000 | LFT |
| 36 | 205-09543 NO 2 STONE | 1,000.000 | TON |
| 37 | 206-51220 EXCAVATION, WET | 274.000 | CYS |
| 38 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 121,542.000 | SYS |
| 39 | 207-08265 SUBGRADE TREATMENT, TYPE IIA | 11,550.000 | SYS |
| 40 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 6,281.000 | SYS |
| 41 | 207-09935 SUBGRADE TREATMENT, TYPE 1C | 3,110.000 | SYS |
| 42 | 211-02050 B BORROW | 1,841.000 | CYS |
| 43 | 211-06467 AGGREGATE FOR END BENT BACKFILL | 93.000 | CYS |
| 44 | 211-09265 STRUCTURAL BACKFILL, TYPE 2 | 2,657.000 | CYS |
| 45 | 211-09266 STRUCTURAL BACKFILL, TYPE 3 | 1,240.000 | CYS |
| 46 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 1,877.000 | TON |
| 47 | 302-07455 DENSE GRADED SUBBASE | 148.000 | CYS |
| 48 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 1,683.000 | TON |
| 49 | 303-07449 COMPACTED AGGREGATE, NO. 73 | 818.000 | TON |

CALL ORDER : 140

CONTRACT ID : IR-34452-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | NEW ROAD CONSTRUCTION PROJECT | | |
| 50 | 306-08034 MILLING, ASPHALT, 1 1/2 IN | 10,125.000 | SYS |
| 51 | 306-08043 MILLING, TRANSITION | 913.000 | SYS |
| 52 | 401-06264 PROFILOGRAPH, HMA | LUMP | LUMP |
| 53 | 402-07432 HMA SURFACE, TYPE A | 1,305.000 | TON |
| 54 | 402-07433 HMA SURFACE, TYPE B | 397.000 | TON |
| 55 | 402-07435 HMA INTERMEDIATE, TYPE A | 2,069.000 | TON |
| 56 | 402-07438 HMA INTERMEDIATE, TYPE B | 752.000 | TON |
| 57 | 402-07439 HMA INTERMEDIATE, TYPE C | 226.000 | TON |
| 58 | 402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE | 163.000 | TON |
| 59 | 402-07784 HMA SURFACE, TYPE D | 365.000 | TON |
| 60 | 402-07785 HMA INTERMEDIATE, TYPE D | 614.000 | TON |
| 61 | 402-07786 HMA BASE, TYPE D | 1,501.000 | TON |
| 62 | 402-07787 HMA WEDGE AND LEVEL, TYPE D | 754.000 | TON |
| 63 | 406-05520 ASPHALT FOR TACK COAT | 3.800 | TON |
| 64 | 601-01522 GUARDRAIL, TRANSITION TYPE TGB | 14.000 | EACH |
| 65 | 601-02206 TEMPORARY GUARDRAIL, W BEAM, 6FT-3 IN SPACING | 1,018.750 | LFT |
| 66 | 601-02241 GUARDRAIL, REMOVE | 1,156.000 | LFT |
| 67 | 601-05057 SPARE PARTS PACKAGE | 1.000 | EACH |
| 68 | 601-05071 GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, 7 | 1.000 | EACH |
| 69 | 601-06035 GUARDRAIL, RESET | 242.000 | LFT |
| 70 | 601-06854 GUARDRAIL, W-BEAM, NESTED | 2.000 | EACH |
| 71 | 601-06856 MODIFIED POSTS, NESTED GUARDRAIL | 4.000 | EACH |
| 72 | 601-94689 GUARDRAIL END TREATMENT, OS | 20.000 | EACH |
| 73 | 601-97080 TEMPORARY GUARDRAIL END TREATMENT, OS | 2.000 | EACH |
| 74 | 601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING | 4,125.000 | LFT |
| 75 | 602-06729 BARRIER DELINEATOR | 54.000 | EACH |
| 76 | 603-06040 FENCE, FARM FIELD, 47 IN | 26,226.000 | LFT |
| 77 | 603-06065 FENCE, CHAIN LINK, RESET | 360.000 | LFT |
| 78 | 609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN | 869.000 | SYS |
| 79 | 610-07486 HMA FOR APPROACHES, TYPE A | 1,278.000 | TON |
| 80 | 610-07487 HMA FOR APPROACHES, TYPE B | 1,037.000 | TON |
| 81 | 611-06497 MAILBOX ASSEMBLY, SINGLE | 19.000 | EACH |
| 82 | 611-06498 MAILBOX ASSEMBLY, DOUBLE | 1.000 | EACH |
| 83 | 615-06490 RIGHT OF WAY MARKER | 103.000 | EACH |
| 84 | 615-06505 MONUMENT, B | 13.000 | EACH |
| 85 | 615-06510 MONUMENT, C | 15.000 | EACH |
| 86 | 616-02320 GEOTEXTILES | 18,238.000 | SYS |
| 87 | 616-05688 RIPRAP, CLASS 1 | 2,759.000 | TON |
| 88 | 616-06405 RIPRAP, REVETMENT | 9,552.000 | TON |
| 89 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 20.000 | EACH |
| 90 | 621-01743 SEED MIXTURE, GRASS, 2 | 20.000 | LBS |
| 91 | 621-02468 SEED MIXTURE, GRASS, 1 | 4.000 | LBS |
| 92 | 621-02770 EROSION CONTROL BLANKET | 36,104.000 | SYS |
| 93 | 621-06545 FERTILIZER | 20.600 | TON |
| 94 | 621-06553 SEED MIXTURE, R | 8,360.000 | LBS |
| 95 | 621-06557 SEED MIXTURE, T | 7,516.000 | LBS |
| 96 | 621-06565 MULCHING MATERIAL | 110.900 | TON |
| 97 | 621-06567 WATER | 82.000 | KGAL |
| 98 | 621-06574 SODDING | 22,038.000 | SYS |

CALL ORDER : 140

CONTRACT ID : IR-34452-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-------------|-------|
| SECTION NO. 0001 | NEW ROAD CONSTRUCTION PROJECT | | |
| 99 | 622-52436 SIGN, DO NOT MOW OR SPRAY | 69.000 | EACH |
| 100 | 622-91786 SEEDLING | 118.000 | EACH |
| 101 | 628-09403 FIELD OFFICE, C | 24.000 | MOS |
| 102 | 628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL | 48.000 | MOS |
| 103 | 628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN | 96.000 | MOS |
| 104 | 628-11068 CELLULAR TELEPHONE/RADIO | 3.000 | EACH |
| 105 | 628-11068 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 106 | 701-02938 CORED HOLE IN ROCK, 24 IN | 135.000 | LFT |
| 107 | 701-05671 PERMANENT CASING | 240.000 | LFT |
| 108 | 701-05672 MOBILIZATION AND DEMOBILIZATION FOR DRILLED SHAFT | LUMP | LUMP |
| 109 | 701-05780 DRILLED SHAFT CONCRETE | 21.400 | CYS |
| 110 | 701-05780 DRILLED SHAFT CONCRETE | 114.600 | CYS |
| 111 | 701-05781 UNCLASSIFIED SHAFT EXCAVATION | 21.400 | CYS |
| 112 | 701-05781 UNCLASSIFIED SHAFT EXCAVATION | 114.600 | CYS |
| 113 | 701-05783 OBSTRUCTIONS | 18.000 | HRS |
| 114 | 701-05785 EXPLORATION (SHAFT EXCAVATION) | 324.000 | LFT |
| 115 | 701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION | LUMP | LUMP |
| 116 | 701-06011 DYNAMIC PILE LOAD TEST | 3.000 | EACH |
| 117 | 701-08122 PILE, STEEL PIPE, 0.375", 14 | 1,743.000 | LFT |
| 118 | 701-09557 TEST PILE, DYNAMIC, PRODUCTION | 209.000 | LFT |
| 119 | 701-09558 TEST PILE, INDICATOR, PRODUCTION | 63.000 | LFT |
| 120 | 701-09559 TEST PILE, DYNAMIC, RESTRIKE | 3.000 | EACH |
| 121 | 701-09560 TEST PILE, INDICATOR, RESTRIKE | 2.000 | EACH |
| 122 | 701-09679 CONICAL PILE TIP, 14 IN | 28.000 | EACH |
| 123 | 701-09683 PILE SHOE, HP 12 X 74 | 18.000 | EACH |
| 124 | 701-09739 PILE SHOE, HP 12 X 53 | 18.000 | EACH |
| 125 | 701-51195 PILE, STEEL H, HP 12 IN X 53 | 790.000 | LFT |
| 126 | 701-95780 PILE, STEEL H, HP 12 IN X 74 | 344.000 | LFT |
| 127 | 702-51005 CONCRETE, A, SUBSTRUCTURE | 190.100 | CYS |
| 128 | 702-51015 CONCRETE, B, FOOTINGS | 10.000 | CYS |
| 129 | 703-01540 THREADED TIE BAR ASSEMBLY | 176.000 | EACH |
| 130 | 703-06028 REINFORCING BARS | 27,540.000 | LBS |
| 131 | 703-06029 REINFORCING BARS, EPOXY COATED | 381,363.000 | LBS |
| 132 | 703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED | 1,877.000 | EACH |
| 133 | 704-51002 CONCRETE, C, SUPERSTRUCTURE | 1,105.200 | CYS |
| 134 | 706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC | 14.000 | EACH |
| 135 | 706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN | 220.000 | SYS |
| 136 | 706-09545 COARSE AGGREGATE, NO 8 | 874.000 | CYS |
| 137 | 706-51020 RAILING, CONCRETE, C | 124.900 | CYS |
| 138 | 707-05983 STRUCTURAL MEMBER, CONCRETE I-BEAM, 36 IN X 12 IN | 900.000 | LFT |
| 139 | 707-05984 STRUCTURAL MEMBER, CONCRETE I-BEAM, 45 IN X 16 IN | 1,120.000 | LFT |
| 140 | 707-10176 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 72 IN X 49 IN | 733.000 | LFT |
| 141 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 142 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 143 | 709-51821 SURFACE SEAL | LUMP | LUMP |
| 144 | 714-11177 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS, | 217.000 | LFT |
| 145 | 715-05019 PIPE, TYPE 1 CIRCULAR 36 IN | 1,340.000 | LFT |
| 146 | 715-05048 PIPE, TYPE 4 CIRCULAR 6 IN | 25,114.000 | LFT |
| 147 | 715-05049 PIPE, TYPE 4 CIRCULAR 8 IN | 400.000 | LFT |

CALL ORDER : 140

CONTRACT ID : IR-34452-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | NEW ROAD CONSTRUCTION PROJECT | | |
| 148 | 715-05051 PIPE, TYPE 4 CIRCULAR 10 IN | 400.000 | LFT |
| 149 | 715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN | 2,050.000 | LFT |
| 150 | 715-05121 PIPE, TYPE 1 CIRCULAR 18 IN | 75.000 | LFT |
| 151 | 715-05123 PIPE, TYPE 1 CIRCULAR 24 IN | 66.000 | LFT |
| 152 | 715-05128 PIPE, TYPE 1 CIRCULAR 48 IN | 221.000 | LFT |
| 153 | 715-05149 PIPE, TYPE 2 CIRCULAR 12 IN | 512.000 | LFT |
| 154 | 715-05151 PIPE, TYPE 2 CIRCULAR 15 IN | 240.000 | LFT |
| 155 | 715-05152 PIPE, TYPE 2 CIRCULAR 18 IN | 100.000 | LFT |
| 156 | 715-05169 PIPE, TYPE 3 CIRCULAR 15 IN | 715.000 | LFT |
| 157 | 715-05171 PIPE, TYPE 3 CIRCULAR 18 IN | 127.000 | LFT |
| 158 | 715-05173 PIPE, TYPE 3 CIRCULAR 24 IN | 129.000 | LFT |
| 159 | 715-05175 PIPE, TYPE 3 CIRCULAR 30 IN | 73.000 | LFT |
| 160 | 715-05177 PIPE, TYPE 3 CIRCULAR 36 IN | 89.000 | LFT |
| 161 | 715-05188 PIPE, TYPE 3 CIRCULAR 60 IN | 153.000 | LFT |
| 162 | 715-05407 PIPE, END BENT DRAIN, 6 IN | 247.000 | LFT |
| 163 | 715-05841 CONCRETE ANCHOR 60 IN | 4.000 | EACH |
| 164 | 715-06004 CONCRETE ANCHOR, 48 IN | 1.000 | EACH |
| 165 | 715-09064 VIDEO INSPECTION FOR PIPE | 2,310.000 | LFT |
| 166 | 715-46000 PIPE END SECTION, 12 IN | 2.000 | EACH |
| 167 | 715-46005 PIPE END SECTION, 15 IN | 27.000 | EACH |
| 168 | 715-46010 PIPE END SECTION, 18 IN | 7.000 | EACH |
| 169 | 715-46020 PIPE END SECTION, 24 IN | 6.000 | EACH |
| 170 | 715-46030 PIPE END SECTION, 30 IN | 2.000 | EACH |
| 171 | 715-46040 PIPE END SECTION, 36 IN | 17.000 | EACH |
| 172 | 715-97691 GRATED BOX END SECTION,, I, 3:1, 36 IN | 1.000 | EACH |
| 173 | 715-97695 GRATED BOX END SECTION,, I, 3:1, 48 IN | 1.000 | EACH |
| 174 | 718-06528 OUTLET PROTECTOR, 1 | 23.000 | EACH |
| 175 | 718-06529 OUTLET PROTECTOR, 2 | 4.000 | EACH |
| 176 | 718-06531 OUTLET PROTECTOR, 3 | 41.000 | EACH |
| 177 | 718-06532 VIDEO INSPECTION FOR UNDERDRAINS | 3,000.000 | LFT |
| 178 | 718-52610 AGGREGATE FOR UNDERDRAINS | 2,225.000 | CYS |
| 179 | 718-99153 GEOTEXTILES FOR UNDERDRAIN | 25,172.000 | SYS |
| 180 | 719-05439 PIPE, DRAIN TILE TERMINAL SECTION, 6 IN | 1,040.000 | LFT |
| 181 | 719-05440 PIPE, DRAIN TILE TERMINAL SECTION, 8 IN | 40.000 | LFT |
| 182 | 719-05442 PIPE, DRAIN TILE TERMINAL SECTION, 10 IN | 40.000 | LFT |
| 183 | 720-45030 INLET, E7 | 3.000 | EACH |
| 184 | 720-93411 INLET, C15, MODIFIED | 3.000 | EACH |
| 185 | 720-98174 INLET, B15 | 3.000 | EACH |
| 186 | 723-11201 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS, | 64.000 | LFT |
| 187 | 723-11315 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS, | 160.000 | LFT |
| 188 | 731-93945 FACE PANELS, CONCRETE | 4,472.000 | SFT |
| 189 | 731-93946 WALL ERECTION | 4,472.000 | SFT |
| 190 | 731-93947 LEVELING PAD, CONCRETE | 430.000 | LFT |
| 191 | 801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY | 12.000 | EACH |
| 192 | 801-03290 CONSTRUCTION SIGN, C | 20.000 | EACH |
| 193 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 4.000 | EACH |
| 194 | 801-06199 ROAD CLOSURE SIGN ASSEMBLY, PERMANENT | 1.000 | EACH |
| 195 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN | 97,426.000 | LFT |
| 196 | 801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN | 72.000 | LFT |

CALL ORDER : 140

CONTRACT ID : IR-34452-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | NEW ROAD CONSTRUCTION PROJECT | | |
| 197 | 801-06640 CONSTRUCTION SIGN, A | 156.000 | EACH |
| 198 | 801-06645 CONSTRUCTION SIGN, B | 6.000 | EACH |
| 199 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 200 | 801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2 | 34.000 | EACH |
| 201 | 801-07118 BARRICADE, III-A | 174.000 | LFT |
| 202 | 801-07119 BARRICADE, III-B | 96.000 | LFT |
| 203 | 801-07120 BARRICADE, III, PERMANENT | 60.000 | LFT |
| 204 | 801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2 | 4,958.000 | LFT |
| 205 | 801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED | 1,991.000 | LFT |
| 206 | 801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN | 4.000 | EACH |
| 207 | 801-53072 TEMPORARY TRAFFIC SIGNAL | LUMP | LUMP |
| 208 | 801-53072 TEMPORARY TRAFFIC SIGNAL | LUMP | LUMP |
| 209 | 801-53072 TEMPORARY TRAFFIC SIGNAL | LUMP | LUMP |
| 210 | 802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE | 623.000 | LFT |
| 211 | 802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE | 156.000 | LFT |
| 212 | 802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE | 248.000 | LFT |
| 213 | 802-07057 SIGN, PANEL, WITH LEGEND | 57.000 | SFT |
| 214 | 802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII | 6.000 | EACH |
| 215 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080" | 296.000 | SFT |
| 216 | 802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS | 542.000 | SFT |
| 217 | 802-76095 STRUCTURAL STEEL, BREAKAWAY | 729.000 | LBS |
| 218 | 802-91122 SIGN, GROUND MOUNTED, RESET | 11.000 | EACH |
| 219 | 805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN | 4.000 | EACH |
| 220 | 805-01842 HANDHOLE, SIGNAL | 26.000 | EACH |
| 221 | 805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE | 1.000 | EACH |
| 222 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN | 4.000 | EACH |
| 223 | 805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN | 8.000 | EACH |
| 224 | 805-78415 SPAN, CATENARY, AND TETHER | 4.000 | EACH |
| 225 | 805-78420 DISCONNECT HANGER | 4.000 | EACH |
| 226 | 805-78445 SIGNAL SERVICE | 1.000 | EACH |
| 227 | 805-78467 SIGNAL CABLE, 3C/8GA | 10.000 | LFT |
| 228 | 805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA | 2,112.000 | LFT |
| 229 | 805-78485 SIGNAL CABLE, 5C/14GA | 323.000 | LFT |
| 230 | 805-78490 SIGNAL CABLE, 7C/14GA | 1,226.000 | LFT |
| 231 | 805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED | 11,193.000 | LFT |
| 232 | 805-78785 SIGNAL DETECTOR HOUSING | 25.000 | EACH |
| 233 | 805-78790 LOOP DETECTOR DELAY AMPLIFIER, 4 CHANNEL | 14.000 | EACH |
| 234 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT | 694.000 | LFT |
| 235 | 805-78925 CONTROLLER CABINET FOUNDATION, P1 | 1.000 | EACH |
| 236 | 805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT | 4.000 | EACH |
| 237 | 807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN | 5,043.000 | LFT |
| 238 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 4,565.000 | LFT |
| 239 | 808-06716 LINE, REMOVE | 1,285.000 | LFT |
| 240 | 808-09381 RETRO-REFLECTIVITY TESTING | LUMP | LUMP |
| 241 | 808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN | 1,026.000 | LFT |
| 242 | 808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN | 281.000 | LFT |
| 243 | 808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN | 129.000 | LFT |
| 244 | 808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN | 691.000 | LFT |
| 245 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN | 3,672.000 | LFT |

CALL ORDER : 140

CONTRACT ID : IR-34452-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|--|---|-------------|-------|
| SECTION NO. 0001 NEW ROAD CONSTRUCTION PROJECT | | | |
| 246 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 473.000 | EACH |
| SECTION NO. 0002 ROAD CONSTRUCTION | | | |
| 247 | 203-02000 EXCAVATION, COMMON | 294,693.000 | CYS |
| 248 | 211-09264 STRUCTURAL BACKFILL, TYPE 1 | 1,762.000 | CYS |
| 249 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 16,027.000 | TON |
| 250 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 11,947.000 | TON |
| 251 | 401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm | 1,722.000 | TON |
| 252 | 401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 6,807.000 | TON |
| 253 | 401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm | 10,016.000 | TON |
| 254 | 401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm | 5,082.000 | TON |
| 255 | 401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm | 24,445.000 | TON |
| 256 | 401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm | 7,309.000 | TON |
| 257 | 406-05520 ASPHALT FOR TACK COAT | 82.600 | TON |
| 258 | 606-07484 MILLED HMA SHOULDER CORRUGATIONS | 14,594.000 | LFT |
| 259 | 615-06505 MONUMENT, B | 26.000 | EACH |
| 260 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 52,069.000 | LFT |
| 261 | 808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN | 446.000 | LFT |
| 262 | 808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN | 446.000 | LFT |
| 263 | 808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN | 114.000 | LFT |
| 264 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN | 25,663.000 | LFT |
| 265 | 808-75272 TRANSVERSE MARKING, THERMOPLASTIC, | 435.000 | LFT |
| 266 | 808-75290 TRANSVERSE MARKING, THERMOPLASTIC, | 1,727.000 | LFT |
| 267 | 808-75297 TRANSVERSE MARKING, THERMOPLASTIC, | 281.000 | LFT |
| 268 | 808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 58.000 | EACH |
| 269 | 808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 51.000 | EACH |
| 270 | 808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8" | 10,866.000 | LFT |
| SECTION NO. 0003 ROAD CONSTRUCTION | | | |
| 271 | 203-02000 EXCAVATION, COMMON | 297,973.000 | CYS |
| 272 | 211-09264 STRUCTURAL BACKFILL, TYPE 1 | 1,742.000 | CYS |
| 273 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 14,710.000 | TON |
| 274 | 302-06464 SUBBASE FOR PCCP | 14,841.000 | CYS |
| 275 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 9,433.000 | TON |
| 276 | 401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm | 1,736.000 | TON |
| 277 | 401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 2,123.000 | TON |
| 278 | 401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm | 2,146.000 | TON |
| 279 | 401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm | 3,548.000 | TON |
| 280 | 401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm | 5,150.000 | TON |
| 281 | 406-05520 ASPHALT FOR TACK COAT | 25.900 | TON |
| 282 | 501-06266 PROFILOGRAPH, PCCP | LUMP | LUMP |
| 283 | 501-09749 QC/QA PCCP, 9.5" | 56,594.000 | SYS |
| 284 | 503-05240 D-1 CONTRACTION JOINT | 32,332.000 | LFT |
| 285 | 503-05310 TERMINAL JOINT | 56.000 | LFT |
| 286 | 606-11064 MILLED PCCP SHOULDER CORRUGATIONS | 14,594.000 | LFT |
| 287 | 615-06505 MONUMENT, B | 23.000 | EACH |
| 288 | 615-06515 MONUMENT, D | 3.000 | EACH |

CALL ORDER : 140

CONTRACT ID : IR-34452-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------------------------|---|------------|-------|
| SECTION NO. 0003 ROAD CONSTRUCTION | | | |
| 289 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 16,922.000 | LFT |
| 290 | 808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN | 35,593.000 | LFT |
| 291 | 808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN | 18,646.000 | LFT |
| 292 | 808-10038 TRANSVERSE MARKINGS MULTI-COMPONENT, | 435.000 | LFT |
| 293 | 808-10051 TRANSVERSE MARKING MULTI-COMPONENT, | 36.000 | LFT |
| 294 | 808-10052 PAVEMENT MESSAGE MKG, MULTI-COMP, (ONLY) | 24.000 | EACH |
| 295 | 808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN | 6,000.000 | LFT |
| 296 | 808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT, | 38.000 | EACH |
| 297 | 808-10119 TRANSVERSE MARKING, MULTI-COMPONENT, SOLID, | 1,185.000 | LFT |
| 298 | 808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN | 114.000 | LFT |
| 299 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN | 13,904.000 | LFT |
| 300 | 808-75290 TRANSVERSE MARKING, THERMOPLASTIC, | 542.000 | LFT |
| 301 | 808-75297 TRANSVERSE MARKING, THERMOPLASTIC, | 245.000 | LFT |
| 302 | 808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 20.000 | EACH |
| 303 | 808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 16.000 | EACH |

SCHEDULE OF PAY ITEMS

CALL ORDER : 190

CONTRACT ID : R -24950-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNALS MODERNIZATION | | |
| 1 | 105-09645 CONSTRUCTION ENGINEERING AND INSPECTION, | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 5 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.000 | DOL |
| 6 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 7 | 109-08463 PROJECT ESTIMATE ADJUSTMENT | 1.000 | DOL |
| 8 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 9 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 10 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 11 | 202-02278 CURB, CONCRETE, REMOVE | 74.000 | LFT |
| 12 | 202-02279 CURB AND GUTTER, REMOVE | 6,895.000 | LFT |
| 13 | 202-03875 CONCRETE STEPS, REMOVE | 2.000 | EACH |
| 14 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 2,282.000 | SYS |
| 15 | 202-95579 SERVICE POINT, REMOVE | 1.000 | EACH |
| 16 | 202-96133 PIPE, REMOVE | 826.000 | LFT |
| 17 | 203-02020 EXCAVATION, UNCLASSIFIED | 6,527.000 | CYS |
| 18 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 39.000 | EACH |
| 19 | 205-06937 TEMPORARY SILT FENCE | 535.000 | LFT |
| 20 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 8,077.000 | SYS |
| 21 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 1,624.000 | SYS |
| 22 | 213-09269 FLOWABLE BACKFILL, NON-REMOVABLE | 881.000 | CYS |
| 23 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 170.000 | TON |
| 24 | 306-08036 MILLING, ASPHALT, 2 IN | 9,379.000 | SYS |
| 25 | 306-08043 MILLING, TRANSITION | 1,327.000 | SYS |
| 26 | 401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm | 1,211.000 | TON |
| 27 | 401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 mm | 1,759.000 | TON |
| 28 | 401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm | 5,388.000 | TON |
| 29 | 406-05520 ASPHALT FOR TACK COAT | 12.000 | TON |
| 30 | 502-06457 PCCP, 9 IN | 1,181.000 | SYS |
| 31 | 502-06627 PCCP, 6 IN | 148.000 | SYS |
| 32 | 604-06070 SIDEWALK, CONCRETE | 2,343.000 | SYS |
| 33 | 604-08086 CURB RAMP, CONCRETE | 138.000 | SYS |
| 34 | 604-44251 STEPS, CONCRETE | 5.000 | CYS |
| 35 | 605-06240 CENTER CURB, A, CONCRETE | 176.000 | SYS |
| 36 | 610-07486 HMA FOR APPROACHES, TYPE A | 573.000 | TON |
| 37 | 615-06490 RIGHT OF WAY MARKER | 57.000 | EACH |
| 38 | 615-06505 MONUMENT, B | 5.000 | EACH |
| 39 | 621-06545 FERTILIZER | 0.200 | TON |
| 40 | 621-06567 WATER | 8.000 | KGAL |
| 41 | 621-06575 SODDING, NURSERY | 1,914.000 | SYS |
| 42 | 628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES | 1.000 | DOL |
| 43 | 628-09403 FIELD OFFICE, C | 22.000 | MOS |
| 44 | 628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN | 22.000 | MOS |
| 45 | 628-11068 CELLULAR TELEPHONE/RADIO | 2.000 | EACH |
| 46 | 702-90915 CONCRETE, CLASS A | 32.000 | CYS |
| 47 | 703-06028 REINFORCING BARS | 4,543.000 | LBS |
| 48 | 706-11404 RAILING, STEEL, PF-1 | 20.000 | LFT |
| 49 | 715-05024 PIPE, TYPE 2 CIRCULAR 36 IN | 170.000 | LFT |

CALL ORDER : 190

CONTRACT ID : R -24950-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNALS MODERNIZATION | | |
| 50 | 715-05149 PIPE, TYPE 2 CIRCULAR 12 IN | 42.000 | LFT |
| 51 | 715-05151 PIPE, TYPE 2 CIRCULAR 15 IN | 1,186.000 | LFT |
| 52 | 715-05152 PIPE, TYPE 2 CIRCULAR 18 IN | 795.000 | LFT |
| 53 | 715-05154 PIPE, TYPE 2 CIRCULAR 24 IN | 406.000 | LFT |
| 54 | 715-05156 PIPE, TYPE 2 CIRCULAR 30 IN | 32.000 | LFT |
| 55 | 720-02442 PIPE, PLUG EXISTING | 1.000 | EACH |
| 56 | 720-44000 CASTING, ADJUST TO GRADE | 2.000 | EACH |
| 57 | 720-45075 INLET, R13 | 1.000 | EACH |
| 58 | 720-45410 MANHOLE, C4 | 10.000 | EACH |
| 59 | 720-45415 MANHOLE, D4 | 5.000 | EACH |
| 60 | 720-45416 MANHOLE, E4 | 2.000 | EACH |
| 61 | 720-98174 INLET, B15 | 21.000 | EACH |
| 62 | 720-98555 INLET, C15 | 17.000 | EACH |
| 63 | 801-03290 CONSTRUCTION SIGN, C | 4.000 | EACH |
| 64 | 801-03291 CONSTRUCTION SIGN, D | 4.000 | EACH |
| 65 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 14.000 | EACH |
| 66 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN | 18,360.000 | LFT |
| 67 | 801-06625 DETOUR ROUTE MARKER ASSEMBLY | 4.000 | EACH |
| 68 | 801-06640 CONSTRUCTION SIGN, A | 15.000 | EACH |
| 69 | 801-06645 CONSTRUCTION SIGN, B | 37.000 | EACH |
| 70 | 801-06710 FLASHING ARROW SIGN | 300.000 | DAY |
| 71 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 72 | 801-07118 BARRICADE, III-A | 80.000 | LFT |
| 73 | 801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1 | 4,360.000 | LFT |
| 74 | 802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE | 256.000 | LFT |
| 75 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080" | 40.000 | SFT |
| 76 | 802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS | 300.000 | SFT |
| 77 | 802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS | 36.000 | SFT |
| 78 | 802-76135 OVERHEAD SIGN STRUCTURE, CANTILEVER SINGLE ARM | 4.000 | EACH |
| 79 | 805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE | 1.000 | EACH |
| 80 | 805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN | 8.000 | EACH |
| 81 | 805-02373 SIGNAL INTERCONNECT CABLE, FIBER OPTIC | 3,870.000 | LFT |
| 82 | 805-11379 SIGNAL CANTILEVER STRUCTURE, SIGNAL | 1.000 | EACH |
| 83 | 805-11380 SIGNAL CANTILEVER STRUCTURE, SIGNAL | 1.000 | EACH |
| 84 | 805-11381 SIGNAL CANTILEVER STRUCTURE, SIGNAL | 1.000 | EACH |
| 85 | 805-11382 SIGNAL CANTILEVER STRUCTURE, SIGNAL | 1.000 | EACH |
| 86 | 805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE | 1.000 | EACH |
| 87 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN | 8.000 | EACH |
| 88 | 805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN | 7.000 | EACH |
| 89 | 805-78370 PEDESTRIAN PUSH BUTTON | 8.000 | EACH |
| 90 | 805-78415 SPAN, CATENARY, AND TETHER | 4.000 | EACH |
| 91 | 805-78420 DISCONNECT HANGER | 4.000 | EACH |
| 92 | 805-78480 SIGNAL CABLE, 3C/14GA | 1,710.000 | LFT |
| 93 | 805-78485 SIGNAL CABLE, 5C/14GA | 1,290.000 | LFT |
| 94 | 805-78490 SIGNAL CABLE, 7C/14GA | 1,200.000 | LFT |
| 95 | 805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED | 1,610.000 | LFT |
| 96 | 805-78785 SIGNAL DETECTOR HOUSING | 14.000 | EACH |
| 97 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT | 14.000 | LFT |
| 98 | 805-78906 SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 12 FT | 4.000 | EACH |

SCHEDULE OF PAY ITEMS

CALL ORDER : 190

CONTRACT ID : R -24950-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNALS MODERNIZATION | | |
| 99 | 805-78925 CONTROLLER CABINET FOUNDATION, P1 | 1.000 | EACH |
| 100 | 805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT | 4.000 | EACH |
| 101 | 805-93067 CONTROLLER CABINET, P | 1.000 | EACH |
| 102 | 807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN | 4,000.000 | LFT |
| 103 | 807-86810 SERVICE POINT, II | 1.000 | EACH |
| 104 | 808-02977 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL | 6.000 | EACH |
| 105 | 808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN | 890.000 | LFT |
| 106 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 194.000 | LFT |
| 107 | 808-11482 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN. | 48.000 | LFT |
| 108 | 808-11493 LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN. | 26.000 | LFT |
| 109 | 808-75215 LINE, THERMOPLASTIC, SOLID, WHITE 12 IN | 194.000 | LFT |
| 110 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN | 1,560.000 | LFT |
| 111 | 808-75274 TRANSVERSE MARKING, THERMOPLASTIC, | 1,931.000 | LFT |
| 112 | 808-75297 TRANSVERSE MARKING, THERMOPLASTIC, | 322.000 | LFT |
| 113 | 808-75300 TRANSVERSE MARKING, THERMOPLASTIC, | 996.000 | LFT |
| 114 | 808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 16.000 | EACH |
| 115 | 808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 7.000 | EACH |
| 116 | 808-94435 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 5.000 | EACH |

CALL ORDER : 230

CONTRACT ID : R -30316-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNALS MODERNIZATION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 107-09358 INSPECTION HOLE, GREATER THAN 900 mm | 30.000 | EACH |
| 3 | 107-09367 INSPECTION HOLE, 900 mm DEPTH OR LESS | 30.000 | EACH |
| 4 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 5 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 6 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 7 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.000 | DOL |
| 8 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 9 | 109-08463 PROJECT ESTIMATE ADJUSTMENT | 1.000 | DOL |
| 10 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 11 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 12 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 13 | 202-02271 HEADWALL, REMOVE | 4.000 | EACH |
| 14 | 202-02272 PAVED SIDE DITCH, REMOVE | 40.000 | m |
| 15 | 202-51330 PRESENT STRUCTURE, REMOVE | LUMP | LUMP |
| 16 | 202-90277 DETECTOR HOUSING, REMOVE | 1.000 | EACH |
| 17 | 202-96133 PIPE, REMOVE | 100.500 | m |
| 18 | 203-02000 EXCAVATION, COMMON | 4,370.000 | m3 |
| 19 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 325.000 | Mg |
| 20 | 205-06933 TEMP DITCH INLET PROTECTION | 7.000 | EACH |
| 21 | 205-06934 TEMPORARY MULCHING | 6.000 | Mg |
| 22 | 205-06937 TEMPORARY SILT FENCE | 1,215.000 | m |
| 23 | 205-09543 NO 2 STONE | 100.000 | Mg |
| 24 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 8,895.000 | m2 |
| 25 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 1,775.000 | m2 |
| 26 | 211-09264 STRUCTURAL BACKFILL, TYPE 1 | 498.000 | m3 |
| 27 | 211-09267 STRUCTURAL BACKFILL, TYPE 4 | 202.000 | m3 |
| 28 | 211-09268 STRUCTURAL BACKFILL, TYPE 5 | 28.000 | m3 |
| 29 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 903.000 | Mg |
| 30 | 303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS | 329.000 | Mg |
| 31 | 306-08034 MILLING, ASPHALT, 38 mm | 1,479.000 | m2 |
| 32 | 306-08036 MILLING, ASPHALT, 50 mm | 165.000 | m2 |
| 33 | 306-08042 MILLING, SCARIFICATION/PROFILE | 11,780.000 | m2 |
| 34 | 401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm | 2,118.000 | Mg |
| 35 | 401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm | 914.000 | Mg |
| 36 | 401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm | 3,141.000 | Mg |
| 37 | 406-05521 ASPHALT FOR TACK COAT | 42,175.000 | m2 |
| 38 | 601-02241 GUARDRAIL, REMOVE | 25.000 | m |
| 39 | 610-07487 HMA FOR APPROACHES, TYPE B | 1,017.000 | Mg |
| 40 | 611-06497 MAILBOX ASSEMBLY, SINGLE | 11.000 | EACH |
| 41 | 611-06498 MAILBOX ASSEMBLY, DOUBLE | 2.000 | EACH |
| 42 | 615-01469 MONUMENT, SECTION CORNER, INSTALL | 1.000 | EACH |
| 43 | 615-06490 RIGHT OF WAY MARKER | 33.000 | EACH |
| 44 | 615-06505 MONUMENT, B | 4.000 | EACH |
| 45 | 615-06530 BENCH MARK POST | 2.000 | EACH |
| 46 | 616-02320 GEOTEXTILES | 719.000 | m2 |
| 47 | 616-05688 RIPRAP, CLASS 1 | 2.000 | Mg |
| 48 | 616-06405 RIPRAP, REVETMENT | 493.000 | Mg |
| 49 | 616-06451 RIPRAP, UNIFORM | 1.000 | Mg |

CALL ORDER : 230

CONTRACT ID : R -30316-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNALS MODERNIZATION | | |
| 50 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 4.000 | EACH |
| 51 | 621-06545 FERTILIZER | 1.000 | Mg |
| 52 | 621-06554 SEED MIXTURE, U | 198.000 | kg |
| 53 | 621-06565 MULCHING MATERIAL | 6.000 | Mg |
| 54 | 621-06567 WATER | 8.000 | kL |
| 55 | 621-06574 SODDING | 427.000 | m2 |
| 56 | 628-09401 FIELD OFFICE, A | 6.000 | MOS |
| 57 | 714-11483 STRUCTURE EXTENSION, COATED REINFORCED CONCRETE, | 13.000 | m |
| 58 | 715-02628 SAFETY METAL END SECTION, 6:1 375 mm | 12.000 | EACH |
| 59 | 715-03321 SAFETY METAL END SECTION, 6:1 300mm | 3.000 | EACH |
| 60 | 715-05121 PIPE, TYPE 1 CIRCULAR 450 mm | 11.000 | m |
| 61 | 715-05149 PIPE, TYPE 2 CIRCULAR 300 mm | 975.000 | m |
| 62 | 715-05152 PIPE, TYPE 2 CIRCULAR 450 mm | 87.500 | m |
| 63 | 715-05169 PIPE, TYPE 3 CIRCULAR 375 mm | 149.000 | m |
| 64 | 715-09064 VIDEO INSPECTION FOR PIPE | 1,073.500 | m |
| 65 | 715-09113 PIPE, TYPE 3, DEFORMED, MIN AREA 0.14 m2 | 13.000 | m |
| 66 | 715-46005 PIPE END SECTION, 375 mm | 12.000 | EACH |
| 67 | 715-46050 PIPE END SECTION, MIN AREA 0.15 m2 | 2.000 | EACH |
| 68 | 715-97691 GRATED BOX END SECTION,, I, 3:1, 900 mm | 2.000 | EACH |
| 69 | 715-97692 GRATED BOX END SECTION,, I, 4:1, 900 mm | 2.000 | EACH |
| 70 | 720-44000 CASTING, ADJUST TO GRADE | 1.000 | EACH |
| 71 | 720-45405 MANHOLE, B4 | 13.000 | EACH |
| 72 | 720-90455 MANHOLE, B2 | 3.000 | EACH |
| 73 | 720-96275 MANHOLE, A2 | 1.000 | EACH |
| 74 | 801-03290 CONSTRUCTION SIGN, C | 4.000 | EACH |
| 75 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 4.000 | EACH |
| 76 | 801-06203 TEMPORARY PAVEMENT MARKING, 100 mm | 1,440.000 | m |
| 77 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm | 5,280.000 | m |
| 78 | 801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 600 mm | 10.800 | m |
| 79 | 801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 600mm | 31.500 | m |
| 80 | 801-06640 CONSTRUCTION SIGN, A | 28.000 | EACH |
| 81 | 801-06710 FLASHING ARROW SIGN | 200.000 | DAY |
| 82 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 83 | 801-07119 BARRICADE, III-B | 36.000 | m |
| 84 | 801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN | 2.000 | EACH |
| 85 | 802-04089 SIGN, SHEET, REMOVE | 4.000 | EACH |
| 86 | 802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE | 25.000 | m |
| 87 | 802-07060 SIGN, SHEET, RELOCATE | 6.000 | EACH |
| 88 | 802-09838 SIGN, SHEET, WITH LEGEND 2.03mm THICKNESS | 2.000 | m2 |
| 89 | 802-09840 SIGN, SHEET, WITH LEGEND 2.54mm THICKNESS | 3.400 | m2 |
| 90 | 802-09842 SIGN, SHEET, WITH LEGEND 3.18mm THICKNESS | 3.700 | m2 |
| 91 | 804-04435 DELINEATOR POST, REMOVE | 16.000 | EACH |
| 92 | 804-06771 DELINEATOR POST, FLEXIBLE | 16.000 | EACH |
| 93 | 805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE | 1.000 | EACH |
| 94 | 805-01842 HANDHOLE, SIGNAL | 9.000 | EACH |
| 95 | 805-01844 CONDUIT STEEL GALVANIZED 50 mm, UNDERGROUND | 479.000 | m |
| 96 | 805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT | LUMP | LUMP |
| 97 | 805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL | 5.000 | EACH |
| 98 | 805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE | 1.000 | EACH |

CALL ORDER : 230

CONTRACT ID : R -30316-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNALS MODERNIZATION | | |
| 99 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN | 5.000 | EACH |
| 100 | 805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm | 1.000 | EACH |
| 101 | 805-78415 SPAN, CATENARY, AND TETHER | 3.000 | EACH |
| 102 | 805-78420 DISCONNECT HANGER | 3.000 | EACH |
| 103 | 805-78445 SIGNAL SERVICE | 1.000 | EACH |
| 104 | 805-78467 SIGNAL CABLE, 3C 8GA | 18.000 | m |
| 105 | 805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA | 650.000 | m |
| 106 | 805-78485 SIGNAL CABLE, 5C 14GA | 88.000 | m |
| 107 | 805-78490 SIGNAL CABLE, 7C 14GA | 205.000 | m |
| 108 | 805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED | 1,175.000 | m |
| 109 | 805-78785 SIGNAL DETECTOR HOUSING | 7.000 | EACH |
| 110 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT | 211.000 | m |
| 111 | 805-78906 SIGNAL SUPPORT FOUNDATION, 915 mm X 915 mm X 3.7 m | 4.000 | EACH |
| 112 | 805-78925 CONTROLLER CABINET FOUNDATION, P1 | 1.000 | EACH |
| 113 | 805-81060 SIGNAL STRAIN POLE, STEEL, 11.0 m | 4.000 | EACH |
| 114 | 808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100 mm | 420.000 | m |
| 115 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100 mm | 2,341.000 | m |
| 116 | 808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW 100 mm | 115.000 | m |
| 117 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100 mm | 2,552.000 | m |
| 118 | 808-75290 TRANSVERSE MARKING, THERMOPLASTIC, | 75.000 | m |
| 119 | 808-75297 TRANSVERSE MARKING, THERMOPLASTIC, | 31.000 | m |
| 120 | 808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 10.000 | EACH |
| 121 | 808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 10.000 | EACH |
| 122 | 808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 151.000 | EACH |
| 123 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 219.000 | EACH |

SCHEDULE OF PAY ITEMS

CALL ORDER : 370

CONTRACT ID : R -33790-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|---------------------------------------|--|-----------|-------|
| SECTION NO. 0001 SAFE ROUTE TO SCHOOL | | | |
| 1 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 2 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 3 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.000 | DOL |
| 4 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 5 | 201-02255 TREE, 18 IN, REMOVE | 3.000 | EACH |
| 6 | 201-02260 TREE, 30 IN, REMOVE | 3.000 | EACH |
| 7 | 202-02240 PAVEMENT REMOVAL | 320.000 | SYS |
| 8 | 202-02278 CURB, CONCRETE, REMOVE | 85.000 | LFT |
| 9 | 202-02928 CATCH BASIN, REMOVE | 2.000 | EACH |
| 10 | 202-03875 CONCRETE STEPS, REMOVE | 7.000 | EACH |
| 11 | 202-06542 RELOCATE | 1.000 | EACH |
| 12 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 350.000 | SYS |
| 13 | 202-91922 STUMP, REMOVE | 1.000 | EACH |
| 14 | 202-96133 PIPE, REMOVE | 33.000 | LFT |
| 15 | 203-08607 LINEAR GRADING | 35.000 | LFT |
| 16 | 203-09937 SLOPE | LUMP | LUMP |
| 17 | 210-07852 SOIL STABILIZATION | LUMP | LUMP |
| 18 | 211-09264 STRUCTURAL BACKFILL, TYPE 1 | 75.000 | CYS |
| 19 | 303-01180 COMPACTED AGGREGATE, NO. 53 | 50.000 | TON |
| 20 | 303-07449 COMPACTED AGGREGATE, NO. 73 | 25.000 | TON |
| 21 | 304-07490 HMA PATCHING, TYPE B | 88.000 | TON |
| 22 | 603-03398 FENCE, RELOCATE | 24.000 | LFT |
| 23 | 604-07896 CURB RAMP, CONCRETE, B | 8.000 | SYS |
| 24 | 604-07897 CURB RAMP, CONCRETE, C | 8.000 | SYS |
| 25 | 604-07899 CURB RAMP, CONCRETE, E | 4.000 | SYS |
| 26 | 604-07901 CURB RAMP, CONCRETE, G | 21.000 | SYS |
| 27 | 604-07902 CURB RAMP, CONCRETE, H | 39.000 | SYS |
| 28 | 604-07903 CURB RAMP, CONCRETE, K | 5.000 | SYS |
| 29 | 604-90256 SIDEWALK, CONCRETE, 6 IN | 162.000 | SYS |
| 30 | 604-91531 SIDEWALK, CONCRETE, 4 IN | 1,454.000 | SYS |
| 31 | 605-06120 CURB, CONCRETE | 2,549.000 | LFT |
| 32 | 611-08232 MAILBOX ASSEMBLY, SINGLE, RESET | 5.000 | EACH |
| 33 | 628-09408 MOBILE LAPTOP COMPUTER SYSTEM | 5.000 | MOS |
| 34 | 628-09409 MOBILE INTERNET SERVICE | 5.000 | MOS |
| 35 | 715-05149 PIPE, TYPE 2 CIRCULAR 12 IN | 36.000 | LFT |
| 36 | 720-44000 CASTING, ADJUST TO GRADE | 2.000 | EACH |
| 37 | 720-44000 CASTING, ADJUST TO GRADE | 2.000 | EACH |
| 38 | 720-44000 CASTING, ADJUST TO GRADE | 1.000 | EACH |
| 39 | 720-44000 CASTING, ADJUST TO GRADE | 3.000 | EACH |
| 40 | 720-92240 CATCH BASIN, W4 | 2.000 | EACH |
| 41 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 42 | 802-07060 SIGN, SHEET, RELOCATE | 8.000 | EACH |
| 43 | 802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS | 77.000 | SFT |
| 44 | 802-76055 SIGN POST, A | 988.000 | LFT |
| 45 | 805-06742 SOLAR POWERED FLASHING BEACON ASSEMBLY | 4.000 | EACH |
| 46 | 808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROW | 3.000 | EACH |
| 47 | 808-03439 TRANSVERSE MARKING THERMOPLASTIC | 816.000 | LFT |

CALL ORDER : 390

CONTRACT ID : R -34079-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | LOCAL ROAD PROJECT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 5 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.000 | DOL |
| 6 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 7 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 8 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 9 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 10 | 202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE | LUMP | LUMP |
| 11 | 202-02240 PAVEMENT REMOVAL | 4,487.000 | SYS |
| 12 | 202-02279 CURB AND GUTTER, REMOVE | 2,554.000 | LFT |
| 13 | 202-52710 SIDEWALK, CONCRETE, REMOVE | 1,519.000 | SYS |
| 14 | 202-91840 FENCE, CHAIN LINK, REMOVE | 1,352.000 | LFT |
| 15 | 202-96035 CONCRETE WALL, REMOVE | 56.000 | LFT |
| 16 | 203-02000 EXCAVATION, COMMON | 12,220.000 | CYS |
| 17 | 203-04523 DEWATERING | LUMP | LUMP |
| 18 | 205-06930 SPLASHPAD, RIPRAP | 2.000 | TON |
| 19 | 205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP | 12.000 | TON |
| 20 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 4.000 | EACH |
| 21 | 205-06937 TEMPORARY SILT FENCE | 3,589.000 | LFT |
| 22 | 205-06938 TEMPORARY SLOPE DRAIN | 21.000 | LFT |
| 23 | 205-09543 NO 2 STONE | 100.000 | TON |
| 24 | 206-51225 EXCAVATION, DRY | 734.000 | CYS |
| 25 | 207-08263 SUBGRADE TREATMENT, TYPE IA | 23,193.000 | SYS |
| 26 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 2,023.000 | SYS |
| 27 | 211-09264 STRUCTURAL BACKFILL, TYPE 1 | 1,152.000 | CYS |
| 28 | 211-09265 STRUCTURAL BACKFILL, TYPE 2 | 241.000 | CYS |
| 29 | 211-09266 STRUCTURAL BACKFILL, TYPE 3 | 661.000 | CYS |
| 30 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 431.000 | TON |
| 31 | 302-08562 COARSE AGGREGATE, NO 8 | 220.000 | TON |
| 32 | 303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS | 134.000 | TON |
| 33 | 306-08034 MILLING, ASPHALT, 1 1/2 IN | 242.000 | SYS |
| 34 | 401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm | 1,659.000 | TON |
| 35 | 401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm | 2,744.000 | TON |
| 36 | 401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm | 4,390.000 | TON |
| 37 | 401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm | 2,989.000 | TON |
| 38 | 401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM | 3,449.000 | TON |
| 39 | 402-07432 HMA SURFACE, TYPE A | 52.000 | TON |
| 40 | 402-07433 HMA SURFACE, TYPE B | 9.000 | TON |
| 41 | 402-07435 HMA INTERMEDIATE, TYPE A | 84.000 | TON |
| 42 | 406-05520 ASPHALT FOR TACK COAT | 24.000 | TON |
| 43 | 601-01522 GUARDRAIL, TRANSITION TYPE TGB | 2.000 | EACH |
| 44 | 601-02241 GUARDRAIL, REMOVE | 221.000 | LFT |
| 45 | 601-06854 GUARDRAIL, W-BEAM, NESTED | 1.000 | EACH |
| 46 | 601-94689 GUARDRAIL END TREATMENT, OS | 4.000 | EACH |
| 47 | 601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING | 12.500 | LFT |
| 48 | 603-06045 FENCE, CHAIN LINK, 48 IN | 470.000 | LFT |
| 49 | 604-07897 CURB RAMP, CONCRETE, C | 11.000 | SYS |

CALL ORDER : 390

CONTRACT ID : R -34079-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|------------|-------|
| SECTION NO. 0001 | LOCAL ROAD PROJECT | | |
| 50 | 604-07901 CURB RAMP, CONCRETE, G | 43.000 | SYS |
| 51 | 604-07902 CURB RAMP, CONCRETE, H | 20.000 | SYS |
| 52 | 604-07903 CURB RAMP, CONCRETE, K | 19.000 | SYS |
| 53 | 604-91531 SIDEWALK, CONCRETE, 4 IN | 3,387.000 | SYS |
| 54 | 605-06140 CURB AND GUTTER, CONCRETE | 6,603.000 | LFT |
| 55 | 610-07487 HMA FOR APPROACHES, TYPE B | 691.000 | TON |
| 56 | 610-09108 PCCP FOR APPROACHES, 9 IN | 464.000 | SYS |
| 57 | 615-06490 RIGHT OF WAY MARKER | 39.000 | EACH |
| 58 | 615-06505 MONUMENT, B | 10.000 | EACH |
| 59 | 615-06527 MONUMENT, SECTION CORNER | 2.000 | EACH |
| 60 | 616-02320 GEOTEXTILES | 365.000 | SYS |
| 61 | 616-06405 RIPRAP, REVETMENT | 239.000 | TON |
| 62 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 2.000 | EACH |
| 63 | 621-06554 SEED MIXTURE, U | 136.000 | LBS |
| 64 | 621-06557 SEED MIXTURE, T | 135.000 | LBS |
| 65 | 621-06565 MULCHING MATERIAL | 4.000 | TON |
| 66 | 621-06567 WATER | 18.000 | KGAL |
| 67 | 621-06574 SODDING | 2,088.000 | SYS |
| 68 | 628-09402 FIELD OFFICE, B | 14.000 | MOS |
| 69 | 702-51005 CONCRETE, A, SUBSTRUCTURE | 40.000 | CYS |
| 70 | 702-51015 CONCRETE, B, FOOTINGS | 124.000 | CYS |
| 71 | 703-06028 REINFORCING BARS | 14,115.000 | LBS |
| 72 | 704-51002 CONCRETE, C, SUPERSTRUCTURE | 5.000 | CYS |
| 73 | 714-11053 STRUCTURE EXTENSION, REINFORCED CONCRETE BOX | 42.000 | LFT |
| 74 | 715-01383 INSERTION VALVE, 8 IN. | 3.000 | EACH |
| 75 | 715-02529 VALVE WITH BOX, RESTRAINED, BUTTERFLY, DUCTILE | 1.000 | EACH |
| 76 | 715-02531 VALVE WITH BOX, RESTRAINED GATE, DUCTILE IRON 6 IN | 2.000 | EACH |
| 77 | 715-02532 VALVE WITH BOX, RESTRAINED GATE, DUCTILE IRON, 8 IN | 1.000 | EACH |
| 78 | 715-03025 SANITARY MANHOLE | 1.000 | EACH |
| 79 | 715-03025 SANITARY MANHOLE | 1.000 | EACH |
| 80 | 715-03025 SANITARY MANHOLE | 2.000 | EACH |
| 81 | 715-04964 WATER MAIN | 46.000 | LFT |
| 82 | 715-04964 WATER MAIN | 138.000 | LFT |
| 83 | 715-05048 PIPE, TYPE 4 CIRCULAR 6 IN | 5,666.000 | LFT |
| 84 | 715-05149 PIPE, TYPE 2 CIRCULAR 12 IN | 1,942.000 | LFT |
| 85 | 715-05151 PIPE, TYPE 2 CIRCULAR 15 IN | 459.000 | LFT |
| 86 | 715-05152 PIPE, TYPE 2 CIRCULAR 18 IN | 254.000 | LFT |
| 87 | 715-05411 PIPE SANITARY SEWER 12 IN | 194.000 | LFT |
| 88 | 715-05417 PIPE SANITARY SEWER 30 IN | 318.000 | LFT |
| 89 | 715-07794 WATER MAIN CONNECTIONS | 5.000 | EACH |
| 90 | 715-07794 WATER MAIN CONNECTIONS | 3.000 | EACH |
| 91 | 715-07794 WATER MAIN CONNECTIONS | 2.000 | EACH |
| 92 | 715-07794 WATER MAIN CONNECTIONS | 2.000 | EACH |
| 93 | 715-09064 VIDEO INSPECTION FOR PIPE | 2,655.000 | LFT |
| 94 | 715-09843 BYPASS PUMPING | LUMP | LUMP |
| 95 | 715-11360 INSERTION VALVE, 12 IN. | 3.000 | EACH |
| 96 | 715-46000 PIPE END SECTION, 12 IN | 4.000 | EACH |
| 97 | 715-46005 PIPE END SECTION, 15 IN | 1.000 | EACH |
| 98 | 715-46010 PIPE END SECTION, 18 IN | 1.000 | EACH |

CALL ORDER : 390

CONTRACT ID : R -34079-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | LOCAL ROAD PROJECT | | |
| 99 | 715-92544 WATER MAIN, DUCTILE IRON, 12 IN | 225.000 | LFT |
| 100 | 715-96669 WATER MAIN, DUCTILE IRON, 16 IN | 2,787.000 | LFT |
| 101 | 718-06532 VIDEO INSPECTION FOR UNDERDRAINS | 3,000.000 | LFT |
| 102 | 718-52610 AGGREGATE FOR UNDERDRAINS | 511.000 | CYS |
| 103 | 718-99153 GEOTEXTILES FOR UNDERDRAIN | 6,010.000 | SYS |
| 104 | 720-44000 CASTING, ADJUST TO GRADE | 19.000 | EACH |
| 105 | 720-45030 INLET, E7 | 1.000 | EACH |
| 106 | 720-45410 MANHOLE, C4 | 7.000 | EACH |
| 107 | 720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED | 4.000 | LFT |
| 108 | 720-96999 FIRE HYDRANT ASSEMBLY | 4.000 | EACH |
| 109 | 720-97009 FIRE HYDRANT ASSEMBLY, REMOVE | 2.000 | EACH |
| 110 | 720-98174 INLET, B15 | 11.000 | EACH |
| 111 | 720-98555 INLET, C15 | 2.000 | EACH |
| 112 | 720-99416 CATCH BASIN, B15 | 21.000 | EACH |
| 113 | 720-99417 CATCH BASIN, C15 | 10.000 | EACH |
| 114 | 732-02533 VALVE WITH BOX RESTRAINED, GATE, DUCTILE IRON, 12 IN. | 3.000 | EACH |
| 115 | 801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY | 4.000 | EACH |
| 116 | 801-03290 CONSTRUCTION SIGN, C | 7.000 | EACH |
| 117 | 801-04308 ROAD CLOSURE SIGN ASSEMBLY | 14.000 | EACH |
| 118 | 801-06625 DETOUR ROUTE MARKER ASSEMBLY | 26.000 | EACH |
| 119 | 801-06640 CONSTRUCTION SIGN, A | 6.000 | EACH |
| 120 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 121 | 801-07118 BARRICADE, III-A | 624.000 | LFT |
| 122 | 801-07119 BARRICADE, III-B | 96.000 | LFT |
| 123 | 802-04089 SIGN, SHEET, REMOVE | 5.000 | EACH |
| 124 | 802-07060 SIGN, SHEET, RELOCATE | 9.000 | EACH |
| 125 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080" | 104.000 | SFT |
| 126 | 802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS | 73.000 | SFT |
| 127 | 802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS | 48.000 | SFT |
| 128 | 802-11364 POST | 218.000 | LFT |
| 129 | 805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE | 3.000 | EACH |
| 130 | 805-01579 MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS | LUMP | LUMP |
| 131 | 805-01842 HANDHOLE, SIGNAL | 37.000 | EACH |
| 132 | 805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND | 1,810.000 | LFT |
| 133 | 805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT | LUMP | LUMP |
| 134 | 805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN | 24.000 | EACH |
| 135 | 805-02373 SIGNAL INTERCONNECT CABLE, FIBER OPTIC | 5,972.000 | LFT |
| 136 | 805-02596 CONDUIT RISER WITH WEATHERHEAD, STEEL | 1.000 | EACH |
| 137 | 805-02645 SIGNAL PEDESTAL FOUNDATION, A | 5.000 | EACH |
| 138 | 805-11376 SIGNAL CANTILEVER STRUCTURE, SIGNAL | 2.000 | EACH |
| 139 | 805-11377 SIGNAL CANTILEVER STRUCTURE, SIGNAL | 1.000 | EACH |
| 140 | 805-11378 SIGNAL CANTILEVER STRUCTURE, SIGNAL | 1.000 | EACH |
| 141 | 805-11379 SIGNAL CANTILEVER STRUCTURE, SIGNAL | 1.000 | EACH |
| 142 | 805-11382 SIGNAL CANTILEVER STRUCTURE, SIGNAL | 2.000 | EACH |
| 143 | 805-11383 SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT | 3.000 | EACH |
| 144 | 805-11384 SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT | 9.000 | EACH |
| 145 | 805-11438 SIGNAL CANTILEVER STRUCTURE, COMBINATION | 1.000 | EACH |
| 146 | 805-11439 SIGNAL CANTILEVER STRUCTURE, COMBINATION | 1.000 | EACH |
| 147 | 805-11441 SIGNAL CANTILEVER STRUCTURE, COMBINATION | 1.000 | EACH |

CALL ORDER : 390

CONTRACT ID : R -34079-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | LOCAL ROAD PROJECT | | |
| 148 | 805-11442 SIGNAL CANTILEVER STRUCTURE, COMBINATION | 2.000 | EACH |
| 149 | 805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE | 2.000 | EACH |
| 150 | 805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE | 1.000 | EACH |
| 151 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN | 21.000 | EACH |
| 152 | 805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN | 4.000 | EACH |
| 153 | 805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN | 3.000 | EACH |
| 154 | 805-78370 PEDESTRIAN PUSH BUTTON | 24.000 | EACH |
| 155 | 805-78445 SIGNAL SERVICE | 3.000 | EACH |
| 156 | 805-78465 SIGNAL CABLE, 2C 8GA | 39.000 | LFT |
| 157 | 805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA | 3,822.000 | LFT |
| 158 | 805-78480 SIGNAL CABLE, 3C/14GA | 3,213.000 | LFT |
| 159 | 805-78485 SIGNAL CABLE, 5C/14GA | 3,958.000 | LFT |
| 160 | 805-78490 SIGNAL CABLE, 7C/14GA | 829.000 | LFT |
| 161 | 805-78495 SIGNAL CABLE, 9C/14GA | 1,501.000 | LFT |
| 162 | 805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED | 3,787.000 | LFT |
| 163 | 805-78785 SIGNAL DETECTOR HOUSING | 8.000 | EACH |
| 164 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT | 1,499.000 | LFT |
| 165 | 805-78925 CONTROLLER CABINET FOUNDATION, P1 | 3.000 | EACH |
| 166 | 805-90005 SIGNAL PEDESTAL, 10 FT | 5.000 | EACH |
| 167 | 807-02191 HANDHOLE, LIGHTING | 3.000 | EACH |
| 168 | 807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT | 13.000 | EACH |
| 169 | 807-02194 SERVICE POINT, II, MODIFIED | 1.000 | EACH |
| 170 | 807-03951 LIGHT POLE, ORNAMENTAL | 13.000 | EACH |
| 171 | 807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN | 567.000 | LFT |
| 172 | 807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C | 3,359.000 | LFT |
| 173 | 807-11354 LUMINAIRE, ROADWAY, METAL HALIDE, 250 WATT | 18.000 | EACH |
| 174 | 807-86905 TRANSITION FITTINGS, GALVANIZED STEEL CONDUIT TO PLASTIC | 12.000 | EACH |
| 175 | 807-86910 CONNECTOR KIT, UNFUSED | 18.000 | EACH |
| 176 | 807-86915 CONNECTOR KIT, FUSED | 18.000 | EACH |
| 177 | 807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED | 39.000 | EACH |
| 178 | 807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED | 8.000 | EACH |
| 179 | 807-86930 INSULATION LINK, NON-WATERPROOFED | 36.000 | EACH |
| 180 | 807-86935 INSULATION LINK, WATERPROOFED | 12.000 | EACH |
| 181 | 807-86955 CABLE-DUCT MARKER | 4.000 | EACH |
| 182 | 807-87556 WIRE, THW OR TW, NO 10 COPPER STRANDED | 1,230.000 | LFT |
| 183 | 807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C | 563.000 | LFT |
| 184 | 808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN | 1,300.000 | LFT |
| 185 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 1,192.000 | LFT |
| 186 | 808-06716 LINE, REMOVE | 478.000 | LFT |
| 187 | 808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN | 409.000 | LFT |
| 188 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN | 6,102.000 | LFT |
| 189 | 808-75278 TRANSVERSE MARKING, THERMOPLASTIC, | 250.000 | LFT |
| 190 | 808-75297 TRANSVERSE MARKING, THERMOPLASTIC, | 432.000 | LFT |
| 191 | 808-75300 TRANSVERSE MARKING, THERMOPLASTIC, | 1,016.000 | LFT |
| 192 | 808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 17.000 | EACH |
| 193 | 808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 8.000 | EACH |
| 194 | 808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8" | 698.000 | LFT |

CALL ORDER : 460

CONTRACT ID : RS-34466-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | PATCH AND REHAB BITUMINOUS PAVEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 | DOL |
| 5 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.000 | DOL |
| 6 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 7 | 109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS | 1.000 | DOL |
| 8 | 109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER | 1.000 | DOL |
| 9 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 10 | 306-08034 MILLING, ASPHALT, 1 1/2 IN | 46,950.000 | SYS |
| 11 | 401-06264 PROFILOGRAPH, HMA | LUMP | LUMP |
| 12 | 401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm | 4,200.000 | TON |
| 13 | 401-10258 JOINT ADHESIVE, SURFACE | 35,218.000 | LFT |
| 14 | 406-05520 ASPHALT FOR TACK COAT | 11.800 | TON |
| 15 | 628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES | 1.000 | DOL |
| 16 | 628-09402 FIELD OFFICE, B | 10.000 | MOS |
| 17 | 628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN | 20.000 | MOS |
| 18 | 628-11068 CELLULAR TELEPHONE/RADIO | 2.000 | EACH |
| 19 | 801-03290 CONSTRUCTION SIGN, C | 6.000 | EACH |
| 20 | 801-06208 TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN | 3,524.000 | LFT |
| 21 | 801-06640 CONSTRUCTION SIGN, A | 18.000 | EACH |
| 22 | 801-06710 FLASHING ARROW SIGN | 80.000 | DAY |
| 23 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 24 | 808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN | 3,524.000 | LFT |
| 25 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 35,218.000 | LFT |
| 26 | 808-09381 RETRO-REFLECTIVITY TESTING | LUMP | LUMP |
| 27 | 808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 441.000 | EACH |
| 28 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 441.000 | EACH |

CALL ORDER : 660

CONTRACT ID : T -33749-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | TRAFFIC SIGNAL MODERNIZATION | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.000 | DOL |
| 5 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 6 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 7 | 202-06542 RELOCATE | 1.000 | EACH |
| 8 | 628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES | 1.000 | DOL |
| 9 | 628-09402 FIELD OFFICE, B | 10.000 | MOS |
| 10 | 628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN | 10.000 | MOS |
| 11 | 628-11068 CELLULAR TELEPHONE/RADIO | 1.000 | EACH |
| 12 | 801-03290 CONSTRUCTION SIGN, C | 4.000 | EACH |
| 13 | 801-06640 CONSTRUCTION SIGN, A | 12.000 | EACH |
| 14 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 15 | 802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE | 14.000 | LFT |
| 16 | 802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE | 2.000 | EACH |
| 17 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080" | 51.000 | SFT |
| 18 | 802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS | 145.000 | SFT |
| 19 | 805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE | 1.000 | EACH |
| 20 | 805-01842 HANDHOLE, SIGNAL | 13.000 | EACH |
| 21 | 805-02328 SIGNAL CABLE, 1C/14 GA | 2,608.000 | LFT |
| 22 | 805-02660 TRAFFIC SIGNAL HEAD, OPTICALLY PROGRAMMED, 5 FACE, 12 IN | 1.000 | EACH |
| 23 | 805-04973 CONDUIT | 1,690.000 | LFT |
| 24 | 805-09366 SIGNAL SUPPORT FOUNDATION, 36 IN DIAMETER X 120 IN | 2.000 | EACH |
| 25 | 805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL | 5.000 | EACH |
| 26 | 805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE | 1.000 | EACH |
| 27 | 805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN | 5.000 | EACH |
| 28 | 805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN | 2.000 | EACH |
| 29 | 805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN | 3.000 | EACH |
| 30 | 805-78245 TRAFFIC SIGNAL HEAD, OPTICALLY PROGRAMMED, 3 FACE, 12 IN | 1.000 | EACH |
| 31 | 805-78415 SPAN, CATENARY, AND TETHER | 4.000 | EACH |
| 32 | 805-78420 DISCONNECT HANGER | 4.000 | EACH |
| 33 | 805-78467 SIGNAL CABLE, 3C/8GA | 160.000 | LFT |
| 34 | 805-78485 SIGNAL CABLE, 5C/14GA | 530.000 | LFT |
| 35 | 805-78490 SIGNAL CABLE, 7C/14GA | 1,291.000 | LFT |
| 36 | 805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED | 4,206.000 | LFT |
| 37 | 805-78785 SIGNAL DETECTOR HOUSING | 10.000 | EACH |
| 38 | 805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT | 812.000 | LFT |
| 39 | 805-78925 CONTROLLER CABINET FOUNDATION, P1 | 1.000 | EACH |
| 40 | 805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT | 2.000 | EACH |
| 41 | 805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL | 2.000 | EACH |
| 42 | 808-01238 TRANSVERSE MARKING, PAINT, | 12.000 | EACH |
| 43 | 808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN | 124.000 | LFT |
| 44 | 808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN | 45.000 | LFT |
| 45 | 808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN | 550.000 | LFT |
| 46 | 808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 4.000 | EACH |