

CALL ORDER : 254

CONTRACT ID : R -30867-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	12,300.000	SYS
11	202-02273 CENTER CURB, CONCRETE, REMOVE	700.000	SYS
12	202-02278 CURB, CONCRETE, REMOVE	54,250.000	LFT
13	202-52710 SIDEWALK, CONCRETE, REMOVE	26,589.000	SYS
14	202-74045 SIGN AND SUPPORTS, CHAN POSTS, REMOVE	707.000	EACH
15	202-93741 GUARDRAIL END TREATMENT, REMOVE	2.000	EACH
16	203-02000 EXCAVATION, COMMON	2,800.000	CYS
17	203-02070 BORROW	1,200.000	CYS
18	203-08607 LINEAR GRADING	100.000	LFT
19	205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE	6.000	EACH
20	205-06937 TEMPORARY SILT FENCE	2,700.000	LFT
21	207-08268 SUBGRADE TREATMENT, TYPE IV	12,300.000	SYS
22	211-09264 STRUCTURAL BACKFILL, TYPE 1	3,000.000	CYS
23	211-09267 STRUCTURAL BACKFILL, TYPE 4	40.000	CYS
24	302-07455 DENSE GRADED SUBBASE	2,050.000	CYS
25	303-07449 COMPACTED AGGREGATE, NO. 73	1,000.000	TON
26	304-07783 HMA PATCHING, TYPE D	9,240.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN	6,160.000	SYS
28	306-08038 MILLING, ASPHALT, 4 IN	98,660.000	SYS
29	306-08039 MILLING, ASPHALT REMOVAL	147,600.000	SYS
30	306-08043 MILLING, TRANSITION	11,000.000	SYS
31	306-08432 MILLING, APPROACH	28,800.000	SYS
32	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	38,000.000	TON
33	402-07786 HMA BASE, TYPE D	1,000.000	TON
34	410-09530 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	18,820.000	TON
35	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
36	501-06322 QC/QA-PCCP, 11 IN	12,300.000	SYS
37	503-05240 D-1 CONTRACTION JOINT	12,320.000	LFT
38	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
39	601-02241 GUARDRAIL, REMOVE	1,027.000	LFT
40	601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION	2.000	EACH
41	601-06035 GUARDRAIL, RESET	859.000	LFT
42	601-07050 GUARDRAIL END TREATMENT, OS, RESET	2.000	EACH
43	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
44	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
45	601-09146 IMPACT ATTENUATOR, CRL, W1, TL-2	4.000	EACH
46	601-09238 HAND DIG GUARDRAIL POST HOLES	10.000	EACH
47	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
48	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,112.500	LFT
49	601-99123 GUARDRAIL, TRANSITION, GP	2.000	EACH

CALL ORDER : 254

CONTRACT ID : R -30867-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	602-08605 CONCRETE BARRIER, 33 IN	789.000	LFT
51	604-07894 CURB RAMP, CONCRETE, A	868.000	SYS
52	604-07896 CURB RAMP, CONCRETE, B	114.800	SYS
53	604-07897 CURB RAMP, CONCRETE, C	7.000	SYS
54	604-07900 CURB RAMP, CONCRETE, F	131.100	SYS
55	604-07901 CURB RAMP, CONCRETE, G	490.000	SYS
56	604-07902 CURB RAMP, CONCRETE, H	485.400	SYS
57	604-91531 SIDEWALK, CONCRETE, 4 IN	17,287.000	SYS
58	605-06090 CURB, INTEGRAL, CONCRETE	290.000	LFT
59	605-06120 CURB, CONCRETE	54,250.000	LFT
60	605-06255 CENTER CURB, D, CONCRETE	600.000	SYS
61	610-07788 HMA FOR APPROACHES, TYPE D	2,800.000	TON
62	616-93772 INSPECTION HOLE	200.000	EACH
63	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
64	621-06559 MULCHED SEEDING, R	10,000.000	SYS
65	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
66	628-09403 FIELD OFFICE, C	12.000	MOS
67	628-11007 CELLULAR TELEPHONE/RADIO SERVICE, 750 MINUTES	24.000	MOS
68	628-11068 CELLULAR TELEPHONE/RADIO	4.000	EACH
69	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	2,120.000	LFT
70	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	900.000	LFT
71	715-08307 HMA FOR STRUCTURE INSTALLATION, TYPE D	1,150.000	TON
72	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
73	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
74	720-45215 CATCH BASIN, A8	32.000	EACH
75	720-45425 MANHOLE, F4	2.000	EACH
76	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	15.000	LFT
77	720-45615 STRUCTURE, INLET, RECONSTRUCTED	15.000	LFT
78	720-90984 MANHOLE, C2	6.000	EACH
79	720-98068 MANHOLE, E2	4.000	EACH
80	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
81	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
82	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	20,200.000	LFT
83	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	16,700.000	LFT
84	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	3,509.000	LFT
85	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24"	3,509.000	LFT
86	801-06640 CONSTRUCTION SIGN, A	60.000	EACH
87	801-06710 FLASHING ARROW SIGN	200.000	DAY
88	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
89	801-99182 TEMPORARY CHANGEABLE MESSAGE SIGN, INSTALL AND MAINTAIN	2.000	EACH
90	802-03783 SIGN, PANEL, REMOVE	5.000	EACH
91	802-04089 SIGN, SHEET, REMOVE	50.000	EACH
92	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	4,226.000	LFT
93	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	4,825.000	SFT
94	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	798.000	SFT
95	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	757.000	SFT
96	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	23.000	EACH
97	805-01842 HANDHOLE, SIGNAL	139.000	EACH
98	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	160.000	EACH

CALL ORDER : 254

CONTRACT ID : R -30867-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
99	805-02373 SIGNAL INTERCONNECT CABLE, FIBER OPTIC	26,000.000	LFT
100	805-02645 SIGNAL PEDESTAL FOUNDATION, A	27.000	EACH
101	805-07245 ETHERNET	22.000	EACH
102	805-08244 CELLULAR MODEM KIT	1.000	EACH
103	805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL	126.000	EACH
104	805-09540 LOOP DETECTOR RACK	7.000	EACH
105	805-11374 SIGNAL CANTILEVER STRUCTURE, SIGNAL	1.000	EACH
106	805-11375 SIGNAL CANTILEVER STRUCTURE, SIGNAL	13.000	EACH
107	805-11376 SIGNAL CANTILEVER STRUCTURE, SIGNAL	15.000	EACH
108	805-11377 SIGNAL CANTILEVER STRUCTURE, SIGNAL	10.000	EACH
109	805-11378 SIGNAL CANTILEVER STRUCTURE, SIGNAL	3.000	EACH
110	805-11379 SIGNAL CANTILEVER STRUCTURE, SIGNAL	1.000	EACH
111	805-11382 SIGNAL CANTILEVER STRUCTURE, SIGNAL	1.000	EACH
112	805-11383 SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT	38.000	EACH
113	805-11384 SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT	5.000	EACH
114	805-11385 SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT	11.000	EACH
115	805-11386 SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT	5.000	EACH
116	805-11392 SIGNAL CANTILEVER STRUCTURE, DUAL ARM 30 FT.	3.000	EACH
117	805-11393 SIGNAL CANTILEVER STRUCTURE, DUAL ARM 35 FT.	6.000	EACH
118	805-11393 SIGNAL CANTILEVER STRUCTURE, DUAL ARM 35 FT.	2.000	EACH
119	805-11394 SIGNAL CANTILEVER STRUCTURE, DUAL ARM 40 FT.	1.000	EACH
120	805-11394 SIGNAL CANTILEVER STRUCTURE, DUAL ARM 40 FT.	1.000	EACH
121	805-11394 SIGNAL CANTILEVER STRUCTURE, DUAL ARM 40 FT.	1.000	EACH
122	805-11396 SIGNAL CANTILEVER STRUCTURE, DUAL ARM 45 FT.	1.000	EACH
123	805-11396 SIGNAL CANTILEVER STRUCTURE, DUAL ARM 45 FT.	1.000	EACH
124	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	20.000	EACH
125	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000	EACH
126	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	171.000	EACH
127	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	11.000	EACH
128	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	5.000	EACH
129	805-78370 PEDESTRIAN PUSH BUTTON	160.000	EACH
130	805-78420 DISCONNECT HANGER	10.000	EACH
131	805-78445 SIGNAL SERVICE	21.000	EACH
132	805-78467 SIGNAL CABLE, 3C/8GA	3,250.000	LFT
133	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	39,000.000	LFT
134	805-78480 SIGNAL CABLE, 3C/14GA	8,700.000	LFT
135	805-78485 SIGNAL CABLE, 5C/14GA	15,000.000	LFT
136	805-78490 SIGNAL CABLE, 7C/14GA	12,500.000	LFT
137	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	42,500.000	LFT
138	805-78785 SIGNAL DETECTOR HOUSING	117.000	EACH
139	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	29,500.000	LFT
140	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
141	805-78930 CONTROLLER CABINET FOUNDATION, M	20.000	EACH
142	805-90005 SIGNAL PEDESTAL, 10 FT	27.000	EACH
143	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	15.000	EACH
144	805-95933 CURB PAINTING, YELLOW	19,868.000	LFT
145	807-06595 CONDUIT, PVC, 2 IN	31,000.000	LFT
146	807-98469 PULL BOX	109.000	EACH
147	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	6.000	EACH

CALL ORDER : 254

CONTRACT ID : R -30867-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
148	808-05929 TRANSVERSE MARKING THERMOPLASTIC,	14,239.000	LFT
149	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	31,018.000	LFT
150	808-11482 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	540.000	LFT
151	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	5,400.000	LFT
152	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	6,420.000	LFT
153	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	400.000	LFT
154	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	3,509.000	LFT
155	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	27.000	EACH
156	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	16.000	EACH
157	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	6.000	EACH

CALL ORDER : 526

CONTRACT ID : B -30583-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	25.000	SYS
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	202-52710 SIDEWALK, CONCRETE, REMOVE	35.000	SYS
14	203-02000 EXCAVATION, COMMON	350.000	CYS
15	203-02070 BORROW	72.000	CYS
16	203-51223 EXCAVATION, WATERWAY	226.000	CYS
17	205-03371 SEDIMENT, REMOVE	3.000	CYS
18	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
19	205-06937 TEMPORARY SILT FENCE	1,240.000	LFT
20	205-09543 NO 2 STONE	200.000	TON
21	206-93520 TEMPORARY SHEET PILING	450.000	SFT
22	207-08263 SUBGRADE TREATMENT, TYPE IA	2,100.000	SYS
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	198.000	SYS
24	211-02050 B BORROW	280.000	CYS
25	211-09264 STRUCTURAL BACKFILL, TYPE 1	20.000	CYS
26	211-09268 STRUCTURAL BACKFILL, TYPE 5	1,601.000	CYS
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	315.000	TON
28	304-07494 WIDENING WITH HMA, TYPE C	569.000	TON
29	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,665.000	SYS
30	402-07432 HMA SURFACE, TYPE A	66.000	TON
31	402-07434 HMA SURFACE, TYPE C	327.000	TON
32	402-07435 HMA INTERMEDIATE, TYPE A	129.000	TON
33	402-07439 HMA INTERMEDIATE, TYPE C	243.000	TON
34	402-07442 HMA BASE, TYPE C	386.000	TON
35	406-05521 ASPHALT FOR TACK COAT	6,750.000	SYS
36	503-05240 D-1 CONTRACTION JOINT	18.750	LFT
37	601-01128 GUARDRAIL, TRANSITION TYPE WGB	1.000	EACH
38	601-01522 GUARDRAIL, TRANSITION TYPE TGB	5.000	EACH
39	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
40	601-02924 HANDRAIL, STEEL PIPE, GALVANIZED	3.500	LFT
41	601-05999 CURVED TERMINAL END	1.000	EACH
42	601-06234 IMPACT ATTENUATOR, R1, W1, TL-2	2.000	EACH
43	601-06417 IMPACT ATTENUATOR SPARE PARTS PACKAGE, R1, W1, TL-2	2.000	EACH
44	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
45	601-94689 GUARDRAIL END TREATMENT, OS	5.000	EACH
46	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	100.000	LFT
47	602-06729 BARRIER DELINEATOR	8.000	EACH
48	604-06070 SIDEWALK, CONCRETE	90.000	SYS
49	604-44251 STEPS, CONCRETE	2.000	CYS

CALL ORDER : 526

CONTRACT ID : B -30583-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	604-92237 HAND RAIL, STEEL	28.330	LFT
51	605-06120 CURB, CONCRETE	55.000	LFT
52	610-07486 HMA FOR APPROACHES, TYPE A	118.000	TON
53	610-08446 PCCP FOR APPROACHES, 6 IN	20.000	SYS
54	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
55	615-06490 RIGHT OF WAY MARKER	6.000	EACH
56	615-06505 MONUMENT, B	4.000	EACH
57	616-02320 GEOTEXTILES	783.000	SYS
58	616-05688 RIPRAP, CLASS 1	665.000	TON
59	616-06405 RIPRAP, REVETMENT	34.000	TON
60	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
61	621-06559 MULCHED SEEDING, R	525.000	SYS
62	621-06567 WATER	7.000	KGAL
63	621-06574 SODDING	130.000	SYS
64	628-09402 FIELD OFFICE, B	8.000	MOS
65	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
66	702-51863 FIELD DRILLED HOLE IN CONCRETE	20.000	EACH
67	703-06029 REINFORCING BARS, EPOXY COATED	4,147.000	LBS
68	704-51002 CONCRETE, C, SUPERSTRUCTURE	5.600	CYS
69	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	7.000	EACH
70	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	1.000	EACH
71	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	96.000	SYS
72	706-08502 REINFORCED CONCRETE MOMENT SLAB, 15 IN	26.000	SYS
73	709-51821 SURFACE SEAL	LUMP	LUMP
74	714-11166 STRUCTURE, COATED REINFORCED CONCRETE BOX SECTIONS,	47.000	LFT
75	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	30.000	LFT
76	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	6.000	LFT
77	715-08627 PIPE, TYPE 2, CIRCULAR, 4 IN	5.000	LFT
78	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
79	720-45275 PIPE CATCH BASIN, 24 IN	1.000	EACH
80	723-10147 TEMPORARY EARTH RETAINING SYSTEM FOR	LUMP	LUMP
81	723-11422 STRUCTURE, COATED REINFORCED CONCRETE,	45.170	LFT
82	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
83	801-03290 CONSTRUCTION SIGN, C	9.000	EACH
84	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	9,890.000	LFT
85	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24"	60.000	LFT
86	801-06625 DETOUR ROUTE MARKER ASSEMBLY	46.000	EACH
87	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
88	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
89	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
90	801-07119 BARRICADE, III-B	120.000	LFT
91	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	819.000	LFT
92	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
93	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	30.500	LFT
94	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	11.200	SFT
95	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	1.000	EACH
96	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	945.000	LFT
97	808-06716 LINE, REMOVE	1,655.000	LFT
98	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	715.000	LFT

SCHEDULE OF PAY ITEMS

CALL ORDER : 526

CONTRACT ID : B -30583-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
99 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	230.000	LFT
100 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	360.000	LFT
101 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	26.000	LFT
102 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.000	EACH
103 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	15.000	EACH