

CALL ORDER : 430

CONTRACT ID : RS-30730-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT PAVEMENT PROJECT (NON-I)		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02278 CURB, CONCRETE, REMOVE	354.000	LFT
11	202-52710 SIDEWALK, CONCRETE, REMOVE	115.000	SYS
12	202-93741 GUARDRAIL END TREATMENT, REMOVE	2.000	EACH
13	207-09935 SUBGRADE TREATMENT, TYPE 1C	112.000	SYS
14	214-11609 GEOCELL CONFINEMENT SYSTEM	1,120.000	SYS
15	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	123.000	TON
16	303-01180 COMPACTED AGGREGATE, NO. 53	680.000	TON
17	303-05738 AGGREGATE, NO. 5	493.000	TON
18	304-07491 HMA PATCHING, TYPE C	2,330.000	TON
19	306-08033 MILLING, ASPHALT, 1 IN	54,865.000	SYS
20	306-08034 MILLING, ASPHALT, 1 1/2 IN	32,906.000	SYS
21	306-08036 MILLING, ASPHALT, 2 IN	4,465.000	SYS
22	306-08042 MILLING, SCARIFICATION/PROFILE	37,063.000	SYS
23	306-08043 MILLING, TRANSITION	1,730.000	SYS
24	306-08159 MILLING ASPHALT	1,054.000	SYS
25	306-08432 MILLING, APPROACH	5,384.000	SYS
26	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
27	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	3,200.000	TON
28	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	4,175.000	TON
29	401-07347 QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	4,694.000	TON
30	401-10258 JOINT ADHESIVE, SURFACE	74,420.000	LFT
31	402-07452 HMA WEDGE AND LEVEL, TYPE C	300.000	TON
32	406-05520 ASPHALT FOR TACK COAT	42.400	TON
33	503-03489 RETROFITTED TIE BARS	14.000	EACH
34	503-05240 D-1 CONTRACTION JOINT	48.000	LFT
35	506-06333 PCCP PATCHING, FULL DEPTH	112.000	SYS
36	601-01625 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 1	1.000	EACH
37	601-01626 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
38	601-02241 GUARDRAIL, REMOVE	87.500	LFT
39	601-07050 GUARDRAIL END TREATMENT, OS, RESET	14.000	EACH
40	601-91147 GUARDRAIL END TREATMENT, RESET	22.000	EACH
41	601-91147 GUARDRAIL END TREATMENT, RESET	2.000	EACH
42	601-92948 GUARDRAIL, ADJUST HEIGHT	17,340.000	LFT
43	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
44	604-07897 CURB RAMP, CONCRETE, C	8.000	SYS
45	604-07902 CURB RAMP, CONCRETE, H	13.200	SYS
46	604-08086 CURB RAMP, CONCRETE	68.900	SYS
47	605-06120 CURB, CONCRETE	358.000	LFT
48	610-07487 HMA FOR APPROACHES, TYPE B	560.000	TON
49	616-02320 GEOTEXTILES	1,404.000	SYS

CALL ORDER : 430

CONTRACT ID : RS-30730-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 DISTRICT PAVEMENT PROJECT (NON-I)			
50	621-06575 SODDING, NURSERY	30.200	SYS
51	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
52	628-09402 FIELD OFFICE, B	18.000	MOS
53	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	18.000	MOS
54	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	36.000	MOS
55	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
56	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
57	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
58	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	7,253.000	LFT
59	801-06625 DETOUR ROUTE MARKER ASSEMBLY	30.000	EACH
60	801-06640 CONSTRUCTION SIGN, A	126.000	EACH
61	801-06710 FLASHING ARROW SIGN	100.000	DAY
62	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
63	801-07119 BARRICADE, III-B	96.000	LFT
64	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	6,286.000	LFT
65	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,883.000	LFT
66	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
67	808-05929 TRANSVERSE MARKING THERMOPLASTIC,	160.000	LFT
68	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	3,941.000	LFT
69	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	38,196.000	LFT
70	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	12,600.000	LFT
71	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
72	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	442.000	LFT
73	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,270.000	LFT
74	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	13,230.000	LFT
75	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	282.000	LFT
76	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	40.000	LFT
77	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	30.000	EACH
78	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	21.000	EACH
79	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	333.000	EACH
80	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	381.000	EACH
81	808-98875 TRANSVERSE MARKING, THERMOPLASTIC,	40.000	LFT