

CALL ORDER : 135

CONTRACT ID : IR-34269-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENVIRONMENTAL MITIGATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	500.000	CYS
10	205-06934 TEMPORARY MULCH	1.300	TON
11	205-09543 NO 2 STONE	150.000	TON
12	206-09387 TURBIDITY CURTAIN	580.000	LFT
13	616-07210 FIBER ROLL	600.000	LFT
14	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
15	621-02770 EROSION CONTROL BLANKET	665.000	SYS
16	621-04258 SEED MIXTURE	135.900	LBS
17	621-04258 SEED MIXTURE	7.300	LBS
18	621-04258 SEED MIXTURE	846.000	LBS
19	621-06545 FERTILIZER	10.360	TON
20	621-06557 SEED MIXTURE, T	75.000	LBS
21	621-06565 MULCHING MATERIAL	1.600	TON
22	622-10003 LIVE PLANT STAKING	774.000	EACH
23	622-52436 SIGN, DO NOT MOW OR SPRAY	22.000	EACH
24	622-91786 SEEDLING	4,272.000	EACH
25	622-91786 SEEDLING	15,616.000	EACH
26	622-98200 SIGN, DO NOT DISTURB	16.000	EACH
27	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
28	628-09403 FIELD OFFICE, C	18.000	MOS
29	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
30	628-11069 CELLULAR TELEPHONE/RADIO SERVICE, ANYTIME MINUTES	18.000	MOS
31	804-06770 DELINEATOR POST	116.000	EACH

CALL ORDER : 181

CONTRACT ID : R -29312-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	800.000	CYS
11	203-02070 BORROW	872.000	CYS
12	203-51223 EXCAVATION, WATERWAY	8.000	CYS
13	205-06937 TEMPORARY SILT FENCE	289.000	LFT
14	207-08267 SUBGRADE TREATMENT, TYPE IIIA	67.000	SYS
15	207-09935 SUBGRADE TREATMENT, TYPE 1C	1,446.000	SYS
16	211-09264 STRUCTURAL BACKFILL, TYPE 1	245.000	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	385.500	TON
18	303-01180 COMPACTED AGGREGATE, NO. 53	40.200	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN	94.000	SYS
20	306-08043 MILLING, TRANSITION	96.000	SYS
21	402-07433 HMA SURFACE, TYPE B	119.200	TON
22	402-07438 HMA INTERMEDIATE, TYPE B	174.800	TON
23	406-05520 ASPHALT FOR TACK COAT	0.700	TON
24	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
25	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	187.500	LFT
26	610-07487 HMA FOR APPROACHES, TYPE B	19.000	TON
27	615-06490 RIGHT OF WAY MARKER	7.000	EACH
28	615-06505 MONUMENT, B	2.000	EACH
29	616-02320 GEOTEXTILES	451.000	SYS
30	616-05688 RIPRAP, CLASS 1	59.000	TON
31	616-06405 RIPRAP, REVETMENT	170.000	TON
32	616-06451 RIPRAP, UNIFORM	54.000	TON
33	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
34	621-02770 EROSION CONTROL BLANKET	659.000	SYS
35	621-06559 MULCHED SEEDING, R	1,750.000	SYS
36	628-09402 FIELD OFFICE, B	6.000	MOS
37	702-44240 CONCRETE, A, STRUCTURES	37.900	CYS
38	702-51015 CONCRETE, B, FOOTINGS	33.200	CYS
39	703-06029 REINFORCING BARS, EPOXY COATED	10,459.000	LBS
40	715-08142 PIPE, TYPE 1 DEFORMED MIN AREA 54 SFT	52.000	LFT
41	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
42	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
43	801-06625 DETOUR ROUTE MARKER ASSEMBLY	30.000	EACH
44	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
45	801-07118 BARRICADE, III-A	72.000	LFT
46	801-07119 BARRICADE, III-B	24.000	LFT
47	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	900.000	LFT
48	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	900.000	LFT

CALL ORDER : 191

CONTRACT ID : R -29664-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE AND PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-07846 TREE	4.000	EACH
10	202-99187 FENCE, FARM FIELD, REMOVE	810.000	LFT
11	203-02000 EXCAVATION, COMMON	9,303.000	CYS
12	205-06937 TEMPORARY SILT FENCE	3,467.000	LFT
13	205-09543 NO 2 STONE	212.600	TON
14	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	30.000	CYS
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	13,769.000	SYS
16	210-04181 BICYCLE RACK	2.000	EACH
17	211-09267 STRUCTURAL BACKFILL, TYPE 4	3.000	CYS
18	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,666.000	TON
19	302-06464 SUBBASE FOR PCCP	110.000	CYS
20	402-07432 HMA SURFACE, TYPE A	850.000	TON
21	402-07435 HMA INTERMEDIATE, TYPE A	1,462.000	TON
22	406-05520 ASPHALT FOR TACK COAT	3.010	TON
23	502-06627 PCCP, 6 IN	417.000	SYS
24	502-06999 PCCP, 8 IN	83.000	SYS
25	601-03871 RAILING, WOOD, END TREATMENT	8.000	EACH
26	603-06040 FENCE, FARM FIELD, 47 IN	702.000	LFT
27	603-06060 FENCE, FARM FIELD, RESET	83.000	LFT
28	603-92230 FENCE, CHAIN LINK, SECURITY, 72 IN	140.000	LFT
29	604-06070 SIDEWALK, CONCRETE	90.000	SYS
30	604-07894 CURB RAMP, CONCRETE, A	96.000	SYS
31	605-06120 CURB, CONCRETE	377.000	LFT
32	615-97672 TRASH RECEPTACLE	1.000	EACH
33	616-02320 GEOTEXTILES	390.000	SYS
34	616-06405 RIPRAP, REVETMENT	180.000	TON
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
36	621-01935 SEED MIXTURE, A	1,320.000	LBS
37	621-02770 EROSION CONTROL BLANKET	4,849.000	SYS
38	621-06545 FERTILIZER	1.500	TON
39	621-06565 MULCHING MATERIAL	6.500	TON
40	628-09401 FIELD OFFICE, A	12.000	MOS
41	701-09663 PILE, STEEL PIPE, 0.312 IN, 14 IN	986.000	LFT
42	701-09679 CONICAL PILE TIP, 14 IN	14.000	EACH
43	702-92857 CONCRETE, C, SUBSTRUCTURE	19.500	CYS
44	703-06028 REINFORCING BARS	30,841.000	LBS
45	704-51002 CONCRETE, C, SUPERSTRUCTURE	125.300	CYS
46	706-04683 RAILING,	638.000	LFT
47	706-04683 RAILING,	130.000	LFT
48	706-04683 RAILING,	356.000	LFT
49	709-51821 SURFACE SEAL	LUMP	LUMP

CALL ORDER : 191

CONTRACT ID : R -29664-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE AND PEDESTRIAN FACILITIES		
50	711-51038 STRUCTURAL STEEL	LUMP	LUMP
51	711-92500 ANCHOR ROD	24.000	EACH
52	711-92500 ANCHOR ROD	324.000	EACH
53	712-03812 BENCH	2.000	EACH
54	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	97.000	LFT
55	715-46000 PIPE END SECTION, DIA 12"	8.000	EACH
56	732-06623 SLEEVE	10.000	EACH
57	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
58	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
59	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
60	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	90.000	LFT
61	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	59.750	SFT
62	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	43.250	SFT
63	802-97428 SIGN POST, TUBULAR	96.250	LFT
64	808-06609 PAVEMENT MESSAGE MARKING,	4.000	EACH
65	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN	108.000	LFT
66	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	290.000	LFT
67	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN	280.000	LFT
68	808-97222 PAVEMENT MESSAGE MARKING, PAINT, HANDICAP SYMBOL	2.000	EACH

CALL ORDER : 211

CONTRACT ID : R -31768-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
11	201-02245 TREE, 6 IN, REMOVE	5.000	EACH
12	201-02250 TREE, 10 IN, REMOVE	12.000	EACH
13	201-02255 TREE, 18 IN, REMOVE	4.000	EACH
14	201-02260 TREE, 30 IN, REMOVE	8.000	EACH
15	201-02270 TREE, 60 IN, REMOVE	1.000	EACH
16	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
17	202-04791 PARKING BARRIER, REMOVE	2.000	EACH
18	202-91840 FENCE, CHAIN LINK, REMOVE	200.000	LFT
19	203-02000 EXCAVATION, COMMON	8,592.000	CYS
20	203-02070 BORROW	1,457.000	CYS
21	203-08607 LINEAR GRADING	253.000	LFT
22	205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE	7.000	EACH
23	205-06933 TEMPORARY INLET PROTECTION	16.000	EACH
24	205-06937 TEMPORARY SILT FENCE	9,973.000	LFT
25	207-08265 SUBGRADE TREATMENT, TYPE IIA	18,629.000	SYS
26	207-08266 SUBGRADE TREATMENT, TYPE III	5,196.000	SYS
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	5,320.000	SYS
28	210-04181 BICYCLE RACK	3.000	EACH
29	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,920.000	CYS
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,751.000	TON
31	303-07449 COMPACTED AGGREGATE, NO. 73	3.000	TON
32	304-07489 HMA PATCHING, TYPE A	37.000	TON
33	306-08043 MILLING, TRANSITION	595.000	SYS
34	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	702.000	TON
35	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,167.000	TON
36	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	3,886.000	TON
37	402-07432 HMA SURFACE, TYPE A	314.000	TON
38	402-07435 HMA INTERMEDIATE, TYPE A	628.000	TON
39	402-10084 HMA FOR TEMPORARY PAVEMENT, B	20.000	TON
40	406-05520 ASPHALT FOR TACK COAT	7.440	TON
41	502-05402 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS	130.000	SYS
42	502-09531 PCCP	3,241.000	SYS
43	601-04793 GUARDRAIL	453.000	LFT
44	601-06035 GUARDRAIL, RESET	15.000	LFT
45	601-91147 GUARDRAIL END TREATMENT, RESET	1.000	EACH
46	604-06070 SIDEWALK, CONCRETE	1,493.000	SYS
47	604-06070 SIDEWALK, CONCRETE	7.000	SYS
48	604-07894 CURB RAMP, CONCRETE, A	16.000	SYS
49	604-07897 CURB RAMP, CONCRETE, C	8.000	SYS

CALL ORDER : 211

CONTRACT ID : R -31768-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	604-07899 CURB RAMP, CONCRETE, E	10.000	SYS
51	604-07900 CURB RAMP, CONCRETE, F	49.000	SYS
52	604-07902 CURB RAMP, CONCRETE, H	34.000	SYS
53	604-07903 CURB RAMP, CONCRETE, K	23.000	SYS
54	604-95344 HAND RAIL, PEDESTRIAN	286.000	LFT
55	605-06120 CURB, CONCRETE	778.000	LFT
56	605-06140 CURB AND GUTTER, CONCRETE	5,075.000	LFT
57	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	143.000	LFT
58	605-96305 CURB AND GUTTER, CONCRETE, DEPRESSED	957.000	LFT
59	610-07487 HMA FOR APPROACHES, TYPE B	397.000	TON
60	610-08446 PCCP FOR APPROACHES, 6 IN	562.000	SYS
61	610-09108 PCCP FOR APPROACHES, 9 IN	1,196.000	SYS
62	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
63	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
64	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
65	615-11537 PARKING BARRIER, CONCRETE	25.000	EACH
66	615-97768 PARKING BARRIER, RESET	2.000	EACH
67	616-02320 GEOTEXTILES	407.000	SYS
68	616-05688 RIPRAP, CLASS 1	88.000	TON
69	616-06405 RIPRAP, REVETMENT	215.000	TON
70	616-06451 RIPRAP, UNIFORM	56.000	TON
71	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
72	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	1,983.000	SYS
73	621-02770 EROSION CONTROL BLANKET	220.000	SYS
74	621-06545 FERTILIZER	1.100	TON
75	621-06554 SEED MIXTURE, U	406.000	LBS
76	621-06565 MULCHING MATERIAL	5.000	TON
77	621-06567 WATER	55.000	KGAL
78	621-06574 SODDING	610.000	SYS
79	621-06575 SODDING, NURSERY	14,525.000	SYS
80	621-98038 MULCH, HARDWOOD SHREDDED BARK	13.000	CYS
81	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	24.000	EACH
82	628-09402 FIELD OFFICE, B	14.000	MOS
83	702-51015 CONCRETE, B, FOOTINGS	6.400	CYS
84	703-06029 REINFORCING BARS, EPOXY COATED	1,208.000	LBS
85	706-04683 RAILING,	24.000	LFT
86	712-03812 BENCH	2.000	EACH
87	712-06852 BOARDWALK	168.000	SFT
88	715-01902 WATER SERVICE LINE 2 IN	88.000	LFT
89	715-04596 WATER SERVICE	1.000	EACH
90	715-04855 PIPE END SECTION DIA 42"	2.000	EACH
91	715-04964 WATER MAIN	425.000	LFT
92	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	476.000	LFT
93	715-05127 PIPE, TYPE 1 CIRCULAR 42 IN	80.000	LFT
94	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,422.000	LFT
95	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	359.000	LFT
96	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	113.000	LFT
97	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	143.000	LFT
98	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	37.000	LFT

CALL ORDER : 211

CONTRACT ID : R -31768-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
99	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	54.000	LFT
100	715-05175 PIPE, TYPE 3 CIRCULAR 30 IN	25.000	LFT
101	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	73.000	LFT
102	715-05342 PIPE, TYPE 2 DEFORMED MIN AREA 10.22 SFT	8.000	LFT
103	715-05595 PIPE EXTENSION, CIRCULAR 15 IN	44.000	LFT
104	715-05597 PIPE EXTENSION, CIRCULAR 24 IN	29.000	LFT
105	715-05757 PIPE EXTENSION, CIRCULAR 36 IN	55.000	LFT
106	715-07107 PIPE END SECTION, MIN AREA 11.6 SFT	1.000	EACH
107	715-07730 PIPE, RCP, III, DO.3=75, 18 IN	86.000	LFT
108	715-07731 PIPE, RCP, III, DO.3=75, 24 IN	5.000	LFT
109	715-08071 PIPE, RCP, III, DO.3=75, 12 IN.	54.000	LFT
110	715-09064 VIDEO INSPECTION FOR PIPE	2,513.000	LFT
111	715-09883 VALVE WITH BOX	1.000	EACH
112	715-09883 VALVE WITH BOX	1.000	EACH
113	715-46000 PIPE END SECTION, DIA 12"	5.000	EACH
114	715-46005 PIPE END SECTION, DIA 15"	4.000	EACH
115	715-46010 PIPE END SECTION, DIA 18"	8.000	EACH
116	715-46020 PIPE END SECTION, DIA 24"	1.000	EACH
117	715-46030 PIPE END SECTION, DIA 30"	4.000	EACH
118	715-46040 PIPE END SECTION, DIA 36"	1.000	EACH
119	715-94780 WATER MAIN, DUCTILE IRON, 6 IN	425.000	LFT
120	720-44000 CASTING, ADJUST TO GRADE	7.000	EACH
121	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
122	720-44000 CASTING, ADJUST TO GRADE	6.000	EACH
123	720-45030 INLET, E7	2.000	EACH
124	720-45035 INLET, F7	2.000	EACH
125	720-45040 INLET, G7	2.000	EACH
126	720-45042 INLET, HA5	2.000	EACH
127	720-45045 INLET, J10	1.000	EACH
128	720-45370 PIPE CATCH BASIN, 18 IN, MODIFIED	1.000	EACH
129	720-90129 MANHOLE, J2	1.000	EACH
130	720-90349 MANHOLE, C8	4.000	EACH
131	720-94612 MANHOLE, K4	1.000	EACH
132	720-95335 MANHOLE, M4	1.000	EACH
133	720-95422 MANHOLE, J4	1.000	EACH
134	720-96999 FIRE HYDRANT ASSEMBLY	1.000	EACH
135	720-98174 INLET, B15	14.000	EACH
136	720-98555 INLET, C15	17.000	EACH
137	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
138	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
139	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
140	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
141	801-06645 CONSTRUCTION SIGN, B	7.000	EACH
142	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
143	801-07118 BARRICADE, III-A	48.000	LFT
144	801-07119 BARRICADE, III-B	120.000	LFT
145	801-92448 CONSTRUCTION SIGNS, MOBILE	720.000	DAY
146	802-03866 MILE MARKER	5.000	EACH
147	802-03896 BOLLARD	14.000	EACH

CALL ORDER : 211

CONTRACT ID : R -31768-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
148	802-03896 BOLLARD	7.000	EACH
149	802-04314 SIGN	1.000	EACH
150	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	493.000	LFT
151	802-07060 SIGN, SHEET, RELOCATE	12.000	EACH
152	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	233.300	SFT
153	808-03439 TRANSVERSE MARKING THERMOPLASTIC	430.000	LFT
154	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	188.000	LFT
155	808-75215 LINE, THERMOPLASTIC, SOLID, WHITE 12 IN	2,364.000	LFT
156	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	10,077.000	LFT
157	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	240.000	LFT
158	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	168.000	LFT

CALL ORDER : 215

CONTRACT ID : R -31906-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PATCH AND REHAB PAVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02859 GRATED BOX END SECTION, REMOVE	3.000	EACH
9	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,920.000	SYS
10	211-09265 STRUCTURAL BACKFILL, TYPE 2	12.000	CYS
11	303-07449 COMPACTED AGGREGATE, NO. 73	191.200	TON
12	306-08034 MILLING, ASPHALT, 1 1/2 IN	10,420.000	SYS
13	402-07784 HMA SURFACE, TYPE D	1,183.000	TON
14	402-07785 HMA INTERMEDIATE, TYPE D	650.000	TON
15	402-07786 HMA BASE, TYPE D	970.000	TON
16	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
17	503-03489 RETROFITTED TIE BARS	125.000	EACH
18	503-05240 D-1 CONTRACTION JOINT	5,210.000	LFT
19	506-06333 PCCP PATCHING, FULL DEPTH	10,430.000	SYS
20	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	1,000.000	SYS
21	621-06559 MULCHED SEEDING, R	1,000.000	SYS
22	627-09327 CABLE BARRIER SYSTEM, TYPE TL-4	1,670.000	LFT
23	628-09402 FIELD OFFICE, B	6.000	MOS
24	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	340.000	LFT
25	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	564.000	LFT
26	715-05595 PIPE EXTENSION, CIRCULAR 15 IN	444.000	LFT
27	715-97686 GRATED BOX END SECTION II, 10:1 DIA 15"	3.000	EACH
28	718-03277 PIPE, UNDERDRAIN, CORRUGATED PLASTIC, PERFORATED, 6 IN.	7,815.000	LFT
29	718-06526 HMA FOR UNDERDRAINS	458.000	TON
30	718-06531 OUTLET PROTECTOR, 3	21.000	EACH
31	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	7,815.000	LFT
32	718-52610 AGGREGATE FOR UNDERDRAINS	267.000	CYS
33	718-99153 GEOTEXTILES FOR UNDERDRAIN	5,037.000	SYS
34	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	10.000	EACH
35	801-03290 CONSTRUCTION SIGN, C	29.000	EACH
36	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	42,010.000	LFT
37	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN	5,380.000	LFT
38	801-06710 FLASHING ARROW SIGN	75.000	DAY
39	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
40	801-07119 BARRICADE, III-B	72.000	LFT
41	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	8,820.000	LFT
42	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	650.000	LFT
43	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
44	801-52817 TEMPORARY CROSSOVER, B	2.000	EACH
45	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN	2,210.000	LFT
46	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	8,820.000	LFT
47	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	8,820.000	LFT
48	808-06716 LINE, REMOVE	10,990.000	LFT
49	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	195.000	EACH

CALL ORDER : 215

CONTRACT ID : R -31906-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PATCH AND REHAB PAVEMENT		
50 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	195.000	EACH

CALL ORDER : 221

CONTRACT ID : R -33356-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, BIKE AND PEDESTRIAN FACILITIES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02272 PAVED SIDE DITCH, REMOVE	45.000	LFT
10	202-02278 CURB, CONCRETE, REMOVE	221.000	LFT
11	203-02000 EXCAVATION, COMMON	4,737.000	CYS
12	203-02100 EXCAVATION, PEAT	36.000	CYS
13	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	6.900	TON
14	205-06933 TEMPORARY INLET PROTECTION	6.000	EACH
15	205-06934 TEMPORARY MULCH	3.390	TON
16	205-06937 TEMPORARY SILT FENCE	8,454.000	LFT
17	205-09543 NO 2 STONE	100.000	TON
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	8,308.000	SYS
19	210-97671 PICNIC TABLE	2.000	EACH
20	211-02050 B BORROW	96.000	CYS
21	211-09266 STRUCTURAL BACKFILL, TYPE 3	485.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,730.000	TON
23	304-07490 HMA PATCHING, TYPE B	21.000	TON
24	402-07432 HMA SURFACE, TYPE A	472.000	TON
25	402-07435 HMA INTERMEDIATE, TYPE A	816.000	TON
26	406-05520 ASPHALT FOR TACK COAT	2.000	TON
27	502-06627 PCCP, 6 IN	154.000	SYS
28	603-03692 FENCE, WOOD,	768.000	LFT
29	604-06070 SIDEWALK, CONCRETE	82.000	SYS
30	604-07903 CURB RAMP, CONCRETE, K	22.000	SYS
31	605-06120 CURB, CONCRETE	126.000	LFT
32	605-06140 CURB AND GUTTER, CONCRETE	95.000	LFT
33	607-06365 PAVED SIDE DITCH, G	10.000	LFT
34	610-08446 PCCP FOR APPROACHES, 6 IN	64.000	SYS
35	616-02320 GEOTEXTILES	8.000	SYS
36	616-06405 RIPRAP, REVETMENT	6.000	TON
37	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
38	621-01935 SEED MIXTURE, A	647.000	LBS
39	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	8,175.000	SYS
40	621-02770 EROSION CONTROL BLANKET	949.000	SYS
41	621-06545 FERTILIZER	0.700	TON
42	621-06565 MULCHING MATERIAL	3.400	TON
43	621-06574 SODDING	5.000	SYS
44	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	40.000	EACH
45	622-05645 PLANT, DECIDUOUS TREE, MULTI-STEM, 72 TO 96 IN	30.000	EACH
46	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	20.000	EACH
47	628-09401 FIELD OFFICE, A	10.000	MOS
48	715-05177 PIPE, TYPE 3 CIRCULAR 36 IN	36.000	LFT
49	720-45035 INLET, F7	1.000	EACH

CALL ORDER : 221

CONTRACT ID : R -33356-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE AND PEDESTRIAN FACILITIES		
50	732-08419 MODULAR BLOCK WALL	162.000	SYS
51	732-08421 MODULAR BLOCK WALL ERECTION	162.000	SYS
52	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
53	801-07119 BARRICADE, III-B	80.000	LFT
54	802-03896 BOLLARD	7.000	EACH
55	802-04314 SIGN	7.000	EACH
56	802-04314 SIGN	7.000	EACH
57	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	104.500	LFT
58	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	80.750	SFT
59	808-03439 TRANSVERSE MARKING THERMOPLASTIC	240.000	LFT
60	808-06609 PAVEMENT MESSAGE MARKING,	1.000	EACH
61	808-75072 TRANSVERSE MARKING, PAINT,	40.000	LFT
62	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	12.000	LFT
63	808-75330 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	8.000	EACH

CALL ORDER : 231

CONTRACT ID : R -34151-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENVIRONMENTAL MITIGATION PROJECT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
8	203-02000 EXCAVATION, COMMON	700.000	CYS
9	205-06937 TEMPORARY SILT FENCE	1,000.000	LFT
10	205-09543 NO 2 STONE	300.000	TON
11	206-09387 TURBIDITY CURTAIN	560.000	LFT
12	303-07662 STONE	124.000	TON
13	616-02320 GEOTEXTILES	200.000	SYS
14	616-05688 RIPRAP, CLASS 1	420.000	TON
15	616-05689 RIPRAP, CLASS 2	20.000	TON
16	616-06451 RIPRAP, UNIFORM	20.000	TON
17	621-02770 EROSION CONTROL BLANKET	1,495.000	SYS
18	621-02770 EROSION CONTROL BLANKET	2,080.000	SYS
19	621-06545 FERTILIZER	1.300	TON
20	621-06565 MULCHING MATERIAL	6.600	TON
21	621-09398 SEED MIXTURE, SLOPE STABILIZATION	241.000	LBS
22	622-10003 LIVE PLANT STAKING	2,175.000	EACH
23	622-10003 LIVE PLANT STAKING	4,263.000	EACH
24	622-52436 SIGN, DO NOT MOW OR SPRAY	9.000	EACH
25	622-91786 SEEDLING	18.000	EACH
26	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
27	628-09402 FIELD OFFICE, B	6.000	MOS
28	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	6.000	MOS
29	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH

CALL ORDER : 241

CONTRACT ID : R -34800-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BIKE/PEDESTRIAN FACILITIES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-02250 TREE, 10 IN, REMOVE	2.000	EACH
8	201-02255 TREE, 18 IN, REMOVE	4.000	EACH
9	201-02260 TREE, 30 IN, REMOVE	1.000	EACH
10	201-02265 TREE, 48 IN, REMOVE	2.000	EACH
11	202-02278 CURB, CONCRETE, REMOVE	884.000	LFT
12	202-52710 SIDEWALK, CONCRETE, REMOVE	975.000	SYS
13	203-02000 EXCAVATION, COMMON	21.000	CYS
14	203-02070 BORROW	55.000	CYS
15	205-06933 TEMPORARY INLET PROTECTION	2.000	EACH
16	304-07489 HMA PATCHING, TYPE A	20.000	TON
17	604-06070 SIDEWALK, CONCRETE	1,220.000	SYS
18	604-07900 CURB RAMP, CONCRETE, F	76.000	SYS
19	604-07901 CURB RAMP, CONCRETE, G	8.000	SYS
20	604-07902 CURB RAMP, CONCRETE, H	142.000	SYS
21	604-07903 CURB RAMP, CONCRETE, K	29.000	SYS
22	605-06120 CURB, CONCRETE	884.000	LFT
23	621-06560 MULCHED SEEDING, U	600.000	SYS
24	702-90915 CONCRETE, CLASS A	23.000	CYS
25	703-06028 REINFORCING BARS	668.000	LBS
26	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	8.000	LFT
27	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	8.000	LFT
28	720-44296 INLET, CAP	2.000	EACH
29	720-98174 INLET, B15	2.000	EACH
30	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
31	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
32	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
33	802-07060 SIGN, SHEET, RELOCATE	10.000	EACH
34	808-74815 TRANSVERSE MARKING, THERMOPLASTIC,	106.000	LFT
35	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	255.000	LFT
36	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	1,020.000	LFT

CALL ORDER : 251

CONTRACT ID : R -34818-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	6,128.000	SYS
12	202-02278 CURB, CONCRETE, REMOVE	6,755.000	LFT
13	202-02279 CURB AND GUTTER, REMOVE	5,235.000	LFT
14	202-52710 SIDEWALK, CONCRETE, REMOVE	9,653.000	SYS
15	203-02000 EXCAVATION, COMMON	18,659.000	CYS
16	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	143.000	EACH
17	205-03662 IRRIGATION, LANDSCAPE	LUMP	LUMP
18	205-06934 TEMPORARY MULCH	2.000	TON
19	205-06937 TEMPORARY SILT FENCE	80.000	LFT
20	205-09543 NO 2 STONE	200.000	TON
21	207-08263 SUBGRADE TREATMENT, TYPE IA	22,680.000	SYS
22	207-08265 SUBGRADE TREATMENT, TYPE IIA	16,978.000	SYS
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,906.000	SYS
24	211-09264 STRUCTURAL BACKFILL, TYPE 1	9,172.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,673.000	TON
26	302-07455 DENSE GRADED SUBBASE	11.000	CYS
27	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,919.000	SYS
28	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,043.000	TON
29	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3,142.000	TON
30	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	3,770.000	TON
31	402-07433 HMA SURFACE, TYPE B	147.000	TON
32	402-07438 HMA INTERMEDIATE, TYPE B	244.000	TON
33	406-05520 ASPHALT FOR TACK COAT	13.000	TON
34	601-07607 IMPACT ATTENUATOR	1.000	EACH
35	603-93373 FENCE, PEDESTRIAN	64.000	LFT
36	604-06070 SIDEWALK, CONCRETE	2,976.000	SYS
37	604-06070 SIDEWALK, CONCRETE	4,719.000	SYS
38	604-06367 JOINT MATERIAL	8,823.000	LFT
39	604-07897 CURB RAMP, CONCRETE, C	21.700	SYS
40	604-07897 CURB RAMP, CONCRETE, C	462.900	SYS
41	604-07898 CURB RAMP, CONCRETE, D	62.100	SYS
42	604-07901 CURB RAMP, CONCRETE, G	159.900	SYS
43	604-07901 CURB RAMP, CONCRETE, G	9.100	SYS
44	604-07902 CURB RAMP, CONCRETE, H	59.600	SYS
45	604-07902 CURB RAMP, CONCRETE, H	6.700	SYS
46	604-07903 CURB RAMP, CONCRETE, K	21.100	SYS
47	605-06120 CURB, CONCRETE	2,221.000	LFT
48	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	9,965.000	LFT
49	605-96305 CURB AND GUTTER, CONCRETE, DEPRESSED	1,041.000	LFT

CALL ORDER : 251

CONTRACT ID : R -34818-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	65.500	SYS
51	610-08446 PCCP FOR APPROACHES, 6 IN	436.000	SYS
52	610-09108 PCCP FOR APPROACHES, 9 IN	1,471.000	SYS
53	615-06505 MONUMENT, B	7.000	EACH
54	615-97672 TRASH RECEPTACLE	17.000	EACH
55	616-02320 GEOTEXTILES	70.000	SYS
56	616-06405 RIPRAP, REVETMENT	38.000	TON
57	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
58	621-04316 SPADE EDGE	807.000	LFT
59	621-06557 SEED MIXTURE, T	87.000	LBS
60	621-06567 WATER	20.000	KGAL
61	621-06570 TOPSOIL	933.000	CYS
62	621-06575 SODDING, NURSERY	5,596.000	SYS
63	621-08538 MULCH	123.000	CYS
64	622-05630 PLANT, CONIFEROUS EVERGREEN, GLOBE, DWARF, OVER 18 TO 24 IN	576.000	EACH
65	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN	218.000	EACH
66	622-05654 PLANT, PERENNIAL	4,189.000	EACH
67	628-09403 FIELD OFFICE, C	18.000	MOS
68	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	18.000	MOS
69	702-51863 FIELD DRILLED HOLE IN CONCRETE	71.000	EACH
70	702-90915 CONCRETE, CLASS A	2.000	CYS
71	703-06029 REINFORCING BARS, EPOXY COATED	2,711.000	LBS
72	712-03812 BENCH	26.000	EACH
73	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	162.000	LFT
74	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	2,635.000	LFT
75	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	861.000	LFT
76	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	512.000	LFT
77	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	817.000	LFT
78	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	735.000	LFT
79	715-05159 PIPE, TYPE 2 CIRCULAR 42 IN	323.000	LFT
80	715-05161 PIPE, TYPE 2 CIRCULAR 48 IN	935.000	LFT
81	715-05162 PIPE, TYPE 2 CIRCULAR 54 IN	1,223.000	LFT
82	715-05756 PIPE EXTENSION, CIRCULAR 12 IN	4.000	LFT
83	715-06492 CONCRETE ANCHOR, 54 IN	1.000	EACH
84	715-91361 PIPE, PVC, 6 IN	32.000	LFT
85	715-92037 PIPE, PVC, 4 IN	99.000	LFT
86	720-45410 MANHOLE, C4	36.000	EACH
87	720-45415 MANHOLE, D4	16.000	EACH
88	720-45416 MANHOLE, E4	24.000	EACH
89	720-45515 MANHOLE, D4, MODIFIED	1.000	EACH
90	720-45520 MANHOLE, E4, MODIFIED	1.000	EACH
91	720-98174 INLET, B15	135.000	EACH
92	720-98555 INLET, C15	8.000	EACH
93	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
94	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
95	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	880.000	LFT
96	801-06625 DETOUR ROUTE MARKER ASSEMBLY	18.000	EACH
97	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
98	801-06645 CONSTRUCTION SIGN, B	6.000	EACH

CALL ORDER : 251

CONTRACT ID : R -34818-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
99	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
100	801-07119 BARRICADE, III-B	480.000	LFT
101	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	654.000	LFT
102	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	56.000	EACH
103	802-07060 SIGN, SHEET, RELOCATE	19.000	EACH
104	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	432.750	SFT
105	802-91122 SIGN, GROUND MOUNTED, RESET	9.000	EACH
106	805-06595 CONDUIT, PVC, 2 IN	6,160.000	LFT
107	805-78900 PEDESTAL FOUNDATION, A	2.000	EACH
108	807-02191 HANDHOLE, LIGHTING	4.000	EACH
109	807-03950 LUMINAIRE, ORNAMENTAL	41.000	EACH
110	807-03951 LIGHT POLE, ORNAMENTAL	41.000	EACH
111	807-04651 WIRE,	645.000	LFT
112	807-04651 WIRE,	799.000	LFT
113	807-04651 WIRE,	2,411.000	LFT
114	807-04653 LIGHTING FOUNDATION,	41.000	EACH
115	807-04671 OUTLET BOX, ELECTRICAL, WEATHERPROOF	2.000	EACH
116	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	1,757.000	LFT
117	807-86805 SERVICE POINT, I	2.000	EACH
118	807-86838 WIRE, NO 4 COPPER IN CONDUIT, 1/C	2,672.000	LFT
119	807-86910 CONNECTOR KIT, UNFUSED	41.000	EACH
120	807-86915 CONNECTOR KIT, FUSED	41.000	EACH
121	807-86935 INSULATION LINK, WATERPROOFED	96.000	EACH
122	807-95888 WIRE, NO 8 COPPER, 1/C	3,921.000	LFT
123	807-95889 WIRE, NO 10 COPPER, 1/C	6,516.000	LFT
124	807-95890 WIRE, NO 12 COPPER, 1/C	351.000	LFT
125	808-02977 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	24.000	EACH
126	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	12,840.000	LFT
127	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN	483.000	LFT
128	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
129	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	646.000	LFT
130	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	356.000	LFT
131	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	6,630.000	LFT
132	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	271.000	LFT
133	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	2,179.000	LFT
134	808-97664 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	14.000	EACH

CALL ORDER : 261

CONTRACT ID : R -35071-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PCCP PATCHING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02240 PAVEMENT REMOVAL	80.000	SYS
8	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	105.000	CYS
9	503-03489 RETROFITTED TIE BARS	12.000	EACH
10	503-05240 D-1 CONTRACTION JOINT	24.000	LFT
11	506-06333 PCCP PATCHING, FULL DEPTH	80.000	SYS
12	801-03290 CONSTRUCTION SIGN, C	1.000	EACH
13	801-06640 CONSTRUCTION SIGN, A	1.000	EACH
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
15	801-07118 BARRICADE, III-A	24.000	LFT
16	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	1.000	EACH

CALL ORDER : 271

CONTRACT ID : R -35164-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT BIKE PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	669.000	CYS
10	203-02070 BORROW	3,445.000	CYS
11	205-06937 TEMPORARY SILT FENCE	1,892.000	LFT
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,778.000	TON
13	303-07662 STONE	362.000	TON
14	303-08640 CRUSHED STONE	36.000	SYS
15	303-93714 BOULDER	3.000	EACH
16	402-07432 HMA SURFACE, TYPE A	269.000	TON
17	402-07435 HMA INTERMEDIATE, TYPE A	359.000	TON
18	604-06070 SIDEWALK, CONCRETE	45.000	SYS
19	604-07901 CURB RAMP, CONCRETE, G	133.000	SYS
20	605-96305 CURB AND GUTTER, CONCRETE, DEPRESSED	5,778.000	LFT
21	605-97937 CURB AND GUTTER, ROLL CURB	50.000	LFT
22	615-97672 TRASH RECEPTACLE	4.000	EACH
23	621-06570 TOPSOIL	1,337.000	CYS
24	621-09906 SEED MIXTURE, PRAIRIE SEED	3.310	ACRE
25	622-04990 LANDSCAPE EDGING	1,749.000	LFT
26	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	26.000	EACH
27	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	4.000	EACH
28	622-05654 PLANT, PERENNIAL	755.000	EACH
29	622-91786 SEEDLING	186.000	EACH
30	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	12.000	MOS
31	628-09409 MOBILE INTERNET SERVICE	12.000	MOS
32	711-90932 EDGING, STEEL	3,216.000	LFT
33	712-03812 BENCH	8.000	EACH
34	712-06852 BOARDWALK	4,416.000	SFT
35	715-05032 PIPE, TYPE 2 CIRCULAR 15 IN	161.000	LFT
36	720-45410 MANHOLE, C4	1.000	EACH
37	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
38	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	89.000	SFT
39	802-76055 SIGN POST, A	160.000	LFT
40	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	2.000	EACH
41	805-04952 CONTROLLER AND CABINET	1.000	EACH
42	805-78370 PEDESTRIAN PUSH BUTTON	2.000	EACH
43	805-78480 SIGNAL CABLE, 3C/14GA	462.000	LFT
44	805-78485 SIGNAL CABLE, 5C/14GA	462.000	LFT
45	808-03114 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (XING) 8 FT	2.000	EACH
46	808-03439 TRANSVERSE MARKING THERMOPLASTIC	380.000	LFT
47	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	51.000	LFT
48	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	480.000	LFT
49	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	5.000	EACH

CALL ORDER : 301

CONTRACT ID : RS-30730-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT PAVEMENT PROJECT (NON-I)		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02278 CURB, CONCRETE, REMOVE	354.000	LFT
11	202-52710 SIDEWALK, CONCRETE, REMOVE	115.000	SYS
12	202-93741 GUARDRAIL END TREATMENT, REMOVE	2.000	EACH
13	207-09935 SUBGRADE TREATMENT, TYPE 1C	112.000	SYS
14	214-11609 GEOCELL CONFINEMENT SYSTEM	1,120.000	SYS
15	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	123.000	TON
16	303-01180 COMPACTED AGGREGATE, NO. 53	680.000	TON
17	303-05738 AGGREGATE, NO. 5	493.000	TON
18	304-07491 HMA PATCHING, TYPE C	2,330.000	TON
19	306-08033 MILLING, ASPHALT, 1 IN	54,865.000	SYS
20	306-08034 MILLING, ASPHALT, 1 1/2 IN	32,906.000	SYS
21	306-08036 MILLING, ASPHALT, 2 IN	4,465.000	SYS
22	306-08042 MILLING, SCARIFICATION/PROFILE	37,063.000	SYS
23	306-08043 MILLING, TRANSITION	1,730.000	SYS
24	306-08159 MILLING ASPHALT	1,054.000	SYS
25	306-08432 MILLING, APPROACH	5,384.000	SYS
26	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
27	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	3,200.000	TON
28	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	4,175.000	TON
29	401-07347 QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	4,694.000	TON
30	401-10258 JOINT ADHESIVE, SURFACE	74,420.000	LFT
31	402-07452 HMA WEDGE AND LEVEL, TYPE C	300.000	TON
32	406-05520 ASPHALT FOR TACK COAT	42.400	TON
33	503-03489 RETROFITTED TIE BARS	14.000	EACH
34	503-05240 D-1 CONTRACTION JOINT	48.000	LFT
35	506-06333 PCCP PATCHING, FULL DEPTH	112.000	SYS
36	601-01625 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 1	1.000	EACH
37	601-01626 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
38	601-02241 GUARDRAIL, REMOVE	87.500	LFT
39	601-07050 GUARDRAIL END TREATMENT, OS, RESET	14.000	EACH
40	601-91147 GUARDRAIL END TREATMENT, RESET	22.000	EACH
41	601-91147 GUARDRAIL END TREATMENT, RESET	2.000	EACH
42	601-92948 GUARDRAIL, ADJUST HEIGHT	17,340.000	LFT
43	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
44	604-07897 CURB RAMP, CONCRETE, C	8.000	SYS
45	604-07902 CURB RAMP, CONCRETE, H	13.200	SYS
46	604-08086 CURB RAMP, CONCRETE	68.900	SYS
47	605-06120 CURB, CONCRETE	358.000	LFT
48	610-07487 HMA FOR APPROACHES, TYPE B	560.000	TON
49	616-02320 GEOTEXTILES	1,404.000	SYS

CALL ORDER : 301

CONTRACT ID : RS-30730-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT PAVEMENT PROJECT (NON-I)		
50	621-06575 SODDING, NURSERY	30.200	SYS
51	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
52	628-09402 FIELD OFFICE, B	18.000	MOS
53	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	18.000	MOS
54	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	36.000	MOS
55	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
56	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
57	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
58	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	7,253.000	LFT
59	801-06625 DETOUR ROUTE MARKER ASSEMBLY	30.000	EACH
60	801-06640 CONSTRUCTION SIGN, A	126.000	EACH
61	801-06710 FLASHING ARROW SIGN	100.000	DAY
62	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
63	801-07119 BARRICADE, III-B	96.000	LFT
64	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	6,286.000	LFT
65	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,883.000	LFT
66	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
67	808-05929 TRANSVERSE MARKING THERMOPLASTIC,	160.000	LFT
68	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	3,941.000	LFT
69	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	38,196.000	LFT
70	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	12,600.000	LFT
71	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
72	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	442.000	LFT
73	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,270.000	LFT
74	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	13,230.000	LFT
75	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	282.000	LFT
76	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	40.000	LFT
77	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	30.000	EACH
78	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	21.000	EACH
79	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	333.000	EACH
80	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	381.000	EACH
81	808-98875 TRANSVERSE MARKING, THERMOPLASTIC,	40.000	LFT

CALL ORDER : 321

CONTRACT ID : RS-33613-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	149.000	SYS
11	202-02273 CENTER CURB, CONCRETE, REMOVE	360.000	SYS
12	202-02274 CURB, CONCRETE, INTEGRAL, REMOVE	1,777.000	LFT
13	202-02279 CURB AND GUTTER, REMOVE	755.000	LFT
14	202-52710 SIDEWALK, CONCRETE, REMOVE	1,374.000	SYS
15	202-90277 DETECTOR HOUSING, REMOVE	8.000	EACH
16	202-93741 GUARDRAIL END TREATMENT, REMOVE	2.000	EACH
17	202-94749 CURB, ASPHALT, REMOVE	448.000	LFT
18	203-02000 EXCAVATION, COMMON	913.000	CYS
19	203-02070 BORROW	40.000	CYS
20	203-08607 LINEAR GRADING	200.000	LFT
21	205-03371 SEDIMENT, REMOVE	20.000	CYS
22	205-06937 TEMPORARY SILT FENCE	2,000.000	LFT
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,901.000	TON
24	302-06464 SUBBASE FOR PCCP	255.000	CYS
25	303-07449 COMPACTED AGGREGATE, NO. 73	450.000	TON
26	304-07490 HMA PATCHING, TYPE B	4,107.000	TON
27	306-08033 MILLING, ASPHALT, 1 IN	3,820.000	SYS
28	306-08034 MILLING, ASPHALT, 1 1/2 IN	81,207.000	SYS
29	306-08041 MILLING, PCCP	5,330.000	SYS
30	306-08043 MILLING, TRANSITION	3,514.000	SYS
31	306-08432 MILLING, APPROACH	6,545.000	SYS
32	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
33	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	7,545.000	TON
34	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	997.000	TON
35	401-10258 JOINT ADHESIVE, SURFACE	57,500.000	LFT
36	402-07433 HMA SURFACE, TYPE B	345.000	TON
37	402-07438 HMA INTERMEDIATE, TYPE B	434.000	TON
38	402-07441 HMA BASE, TYPE B	651.000	TON
39	406-05520 ASPHALT FOR TACK COAT	28.000	TON
40	503-03489 RETROFITTED TIE BARS	763.000	EACH
41	503-05240 D-1 CONTRACTION JOINT	439.000	LFT
42	503-09261 PCCP STITCHING	76.000	EACH
43	506-06333 PCCP PATCHING, FULL DEPTH	3,654.000	SYS
44	507-07479 HMA PARTIAL DEPTH PATCH	91.000	TON
45	507-07482 CRACKS IN PCCP, ROUT AND SEAL	150.000	LFT
46	507-08272 JOINTS IN PCCP, SAW AND SEAL	104,300.000	LFT
47	601-02241 GUARDRAIL, REMOVE	322.000	LFT
48	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
49	601-94690 GUARDRAIL END TREATMENT, MS	1.000	EACH

CALL ORDER : 321

CONTRACT ID : RS-33613-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	322.000	LFT
51	604-07894 CURB RAMP, CONCRETE, A	116.000	SYS
52	604-07896 CURB RAMP, CONCRETE, B	33.000	SYS
53	604-07897 CURB RAMP, CONCRETE, C	50.000	SYS
54	604-07900 CURB RAMP, CONCRETE, F	477.000	SYS
55	604-07901 CURB RAMP, CONCRETE, G	162.000	SYS
56	604-07902 CURB RAMP, CONCRETE, H	421.000	SYS
57	604-07903 CURB RAMP, CONCRETE, K	114.000	SYS
58	604-91531 SIDEWALK, CONCRETE, 4 IN	28.000	SYS
59	605-05523 CURB, HMA	448.000	LFT
60	605-06090 CURB, INTEGRAL, CONCRETE	1,767.000	LFT
61	605-06100 CURB, INTEGRAL, C, CONCRETE	717.000	LFT
62	605-06140 CURB AND GUTTER, CONCRETE	14.000	LFT
63	605-06150 CURB AND GUTTER, C, CONCRETE	741.000	LFT
64	605-06210 CENTER CURB, C, CONCRETE	360.000	LFT
65	610-07487 HMA FOR APPROACHES, TYPE B	644.000	TON
66	615-06505 MONUMENT, B	11.000	EACH
67	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	1.000	EACH
68	621-06575 SODDING, NURSERY	648.000	SYS
69	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
70	628-09402 FIELD OFFICE, B	8.000	MOS
71	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
72	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	32.000	MOS
73	628-11068 CELLULAR TELEPHONE/RADIO	4.000	EACH
74	720-44000 CASTING, ADJUST TO GRADE	25.000	EACH
75	720-44045 CASTING, 8, FURNISH AND ADJUST TO GRADE	1.000	EACH
76	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	27.000	EACH
77	720-44080 CASTING, 15, FURNISH AND ADJUST TO GRADE	5.000	EACH
78	720-90105 INLET, REPAIR	3.000	EACH
79	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	75.000	EACH
80	801-01505 TEMPORARY PAVEMENT MESSAGE MARKING, (ONLY)	15.000	EACH
81	801-03290 CONSTRUCTION SIGN, C	10.000	EACH
82	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	10,833.000	LFT
83	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	10,833.000	LFT
84	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	75.000	EACH
85	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	15.000	EACH
86	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	1,175.000	LFT
87	801-06217 TEMPORARY TRANSVERSE PAVEMENT MARKING REMOVABLE 6 IN	800.000	LFT
88	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	1,175.000	LFT
89	801-06640 CONSTRUCTION SIGN, A	57.000	EACH
90	801-06645 CONSTRUCTION SIGN, B	60.000	EACH
91	801-06710 FLASHING ARROW SIGN	240.000	DAY
92	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
93	801-07118 BARRICADE, III-A	400.000	LFT
94	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	0.750	SFT
95	805-02645 SIGNAL PEDESTAL FOUNDATION, A	1.000	EACH
96	805-04133 SIGNAL PEDESTAL, 12FT	1.000	EACH
97	805-06483 CONTROLLER	6.000	EACH
98	805-07245 ETHERNET	5.000	EACH

CALL ORDER : 321

CONTRACT ID : RS-33613-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
99	805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL	4.000	EACH
100	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	3.000	EACH
101	805-78370 PEDESTRIAN PUSH BUTTON	1.000	EACH
102	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	11,420.000	LFT
103	805-78480 SIGNAL CABLE, 3C/14GA	200.000	LFT
104	805-78485 SIGNAL CABLE, 5C/14GA	200.000	LFT
105	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	400.000	LFT
106	805-78785 SIGNAL DETECTOR HOUSING	8.000	EACH
107	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	3,995.000	LFT
108	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	8.000	EACH
109	805-95933 CURB PAINTING, YELLOW	360.000	LFT
110	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	240.000	LFT
111	808-03439 TRANSVERSE MARKING THERMOPLASTIC	360.000	LFT
112	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	5,840.000	LFT
113	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,855.000	LFT
114	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	2,350.000	LFT
115	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
116	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	500.000	LFT
117	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	17,775.000	LFT
118	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	750.000	LFT
119	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	1,050.000	LFT
120	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	1,175.000	LFT
121	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	3,377.000	LFT
122	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	75.000	EACH
123	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	15.000	EACH
124	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	100.000	EACH
125	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	100.000	EACH

CALL ORDER : 331

CONTRACT ID : RS-34482-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	304-07490 HMA PATCHING, TYPE B	100.000	TON
9	306-08042 MILLING, SCARIFICATION/PROFILE	26,867.000	SYS
10	402-07433 HMA SURFACE, TYPE B	2,217.000	TON
11	406-05520 ASPHALT FOR TACK COAT	8.000	TON
12	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 361

CONTRACT ID : B -31891-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SUBSTRUCTURE REPAIR AND REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	166.000	SYS
10	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	144.000	CYS
12	203-02070 BORROW	607.000	CYS
13	205-03371 SEDIMENT, REMOVE	23.000	CYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	45.000	TON
15	205-06937 TEMPORARY SILT FENCE	1,627.000	LFT
16	206-51215 EXCAVATION, X	25.000	CYS
17	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	604.000	CYS
18	207-08265 SUBGRADE TREATMENT, TYPE IIA	559.000	SYS
19	211-06467 AGGREGATE FOR END BENT BACKFILL	20.000	CYS
20	211-09265 STRUCTURAL BACKFILL, TYPE 2	2.000	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	163.000	TON
22	302-07455 DENSE GRADED SUBBASE	27.000	CYS
23	303-01180 COMPACTED AGGREGATE, NO. 53	364.000	TON
24	306-08042 MILLING, SCARIFICATION/PROFILE	1,219.000	SYS
25	306-08043 MILLING, TRANSITION	489.000	SYS
26	402-07433 HMA SURFACE, TYPE B	177.000	TON
27	402-07438 HMA INTERMEDIATE, TYPE B	87.000	TON
28	406-05520 ASPHALT FOR TACK COAT	1.000	TON
29	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
30	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
31	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	325.000	LFT
32	602-06729 BARRIER DELINEATOR	27.000	EACH
33	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	164.000	SYS
34	615-06490 RIGHT OF WAY MARKER	12.000	EACH
35	615-06505 MONUMENT, B	2.000	EACH
36	616-02320 GEOTEXTILES	1,865.000	SYS
37	616-05688 RIPRAP, CLASS 1	1,227.000	TON
38	616-05689 RIPRAP, CLASS 2	546.000	TON
39	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
40	621-02770 EROSION CONTROL BLANKET	1,750.000	SYS
41	621-06559 MULCHED SEEDING, R	1,834.000	SYS
42	621-06567 WATER	2.000	KGAL
43	621-06575 SODDING, NURSERY	434.000	SYS
44	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
45	628-09403 FIELD OFFICE, C	20.000	MOS
46	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	60.000	MOS
47	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
48	701-09662 PILE, STEEL PIPE, 0.250 IN, 14 IN	244.000	LFT
49	701-09679 CONICAL PILE TIP, 14 IN	4.000	EACH

CALL ORDER : 361

CONTRACT ID : B -31891-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SUBSTRUCTURE REPAIR AND REHABILITATION		
50	701-09739 PILE SHOE, HP 12 X 53	68.000	EACH
51	701-51195 PILE, STEEL H, HP 12 IN X 53	3,300.000	LFT
52	702-51005 CONCRETE, A, SUBSTRUCTURE	236.600	CYS
53	702-51015 CONCRETE, B, FOOTINGS	157.000	CYS
54	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	1,920.000	LBS
55	702-51863 FIELD DRILLED HOLE IN CONCRETE	444.000	EACH
56	703-06028 REINFORCING BARS	74,289.000	LBS
57	703-06029 REINFORCING BARS, EPOXY COATED	170,694.000	LBS
58	704-51002 CONCRETE, C, SUPERSTRUCTURE	500.600	CYS
59	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
60	706-09960 RAILING, CONCRETE, FC	1,080.000	LFT
61	709-51821 SURFACE SEAL	LUMP	LUMP
62	710-09158 PATCHING CONCRETE STRUCTURES	720.000	SFT
63	711-51038 STRUCTURAL STEEL	LUMP	LUMP
64	715-05168 PIPE, TYPE 3 CIRCULAR 12 IN	16.000	LFT
65	715-05407 PIPE, END BENT DRAIN, 6 IN	114.000	LFT
66	715-10238 PIPE ROADWAY DRAIN CASTING EXTENSION	10.000	EACH
67	715-46000 PIPE END SECTION, DIA 12"	2.000	EACH
68	724-51925 STRUCTURAL EXPANSION JOINT, SS	73.000	LFT
69	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
70	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
71	801-06625 DETOUR ROUTE MARKER ASSEMBLY	21.000	EACH
72	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
73	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
74	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
75	801-07118 BARRICADE, III-A	96.000	LFT
76	801-07119 BARRICADE, III-B	36.000	LFT
77	802-04893 REFERENCE POST	1.000	EACH
78	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	12.000	LFT
79	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	6.000	SFT
80	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	2,500.000	LFT
81	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	998.000	LFT
82	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	1,250.000	LFT
83	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	32.000	EACH
84	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	32.000	EACH

CALL ORDER : 363

CONTRACT ID : B -32084-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	MAJOR BRIDGE PROJECT (REPLACEMENT/REHABILITATION)		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	304-07783 HMA PATCHING, TYPE D	14.000	TON
10	306-08038 MILLING, ASPHALT, 4 IN	60.000	SYS
11	722-09456 POLYMERIC OVERLAY SYSTEM	13,134.000	SYS
12	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	200.000	SFT
13	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
14	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	8,500.000	LFT
15	801-06640 CONSTRUCTION SIGN, A	80.000	EACH
16	801-06710 FLASHING ARROW SIGN	32.000	DAY
17	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
18	808-06716 LINE, REMOVE	19,550.000	LFT
19	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	2,840.000	LFT
20	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	4,700.000	LFT
21	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	4,200.000	LFT
22	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	216.000	EACH
23	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	216.000	EACH

CALL ORDER : 371

CONTRACT ID : B -32626-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	127.600	SYS
9	202-02272 PAVED SIDE DITCH, REMOVE	360.000	LFT
10	202-02276 GUTTER TURNOUT, REINFORCED CONCRETE, REMOVE	2.000	EACH
11	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	240.000	CYS
13	203-08607 LINEAR GRADING	660.000	LFT
14	207-08266 SUBGRADE TREATMENT, TYPE III	853.000	SYS
15	211-06467 AGGREGATE FOR END BENT BACKFILL	27.200	CYS
16	302-07455 DENSE GRADED SUBBASE	28.600	CYS
17	306-08043 MILLING, TRANSITION	600.000	SYS
18	402-07432 HMA SURFACE, TYPE A	70.300	TON
19	402-07435 HMA INTERMEDIATE, TYPE A	117.200	TON
20	402-07440 HMA BASE, TYPE A	281.400	TON
21	402-07451 HMA WEDGE AND LEVEL, TYPE B	148.600	TON
22	406-05521 ASPHALT FOR TACK COAT	1,400.000	SYS
23	503-05310 TERMINAL JOINT	72.000	LFT
24	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
25	601-02241 GUARDRAIL, REMOVE	960.000	LFT
26	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	700.000	LFT
27	601-99132 GUARDRAIL, TRANSITION, VH, 6 FT-3 IN SPACING	4.000	EACH
28	602-06729 BARRIER DELINEATOR	30.000	EACH
29	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	171.300	SYS
30	616-02320 GEOTEXTILES	126.300	SYS
31	616-06405 RIPRAP, REVETMENT	26.700	TON
32	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
33	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
34	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
35	621-06553 SEED MIXTURE, R	115.000	LBS
36	621-06574 SODDING	35.600	SYS
37	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
38	628-09402 FIELD OFFICE, B	21.000	MOS
39	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	42.000	MOS
40	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
41	701-09558 TEST PILE, INDICATOR, PRODUCTION	81.000	LFT
42	701-09560 TEST PILE, INDICATOR, RESTRIKE	2.000	EACH
43	701-09662 PILE, STEEL PIPE, 0.250 IN, 14 IN	486.000	LFT
44	702-51005 CONCRETE, A, SUBSTRUCTURE	56.500	CYS
45	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	3,220.000	LBS
46	703-06029 REINFORCING BARS, EPOXY COATED	173,172.000	LBS
47	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	74.000	EACH
48	704-51002 CONCRETE, C, SUPERSTRUCTURE	585.000	CYS
49	706-06351 CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.000	EACH

CALL ORDER : 371

CONTRACT ID : B -32626-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT		
50	706-09962 RAILING, CONCRETE, PF-1	1,112.000	LFT
51	706-11404 RAILING, STEEL, PF-1	1,129.000	LFT
52	709-51821 SURFACE SEAL	LUMP	LUMP
53	711-04297 STRUCTURAL STEEL, FIELD CUT	1,389.000	SQIN
54	711-51038 STRUCTURAL STEEL	LUMP	LUMP
55	711-51864 DRILLED HOLE	728.000	EACH
56	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
57	711-51878 JACKING AND SUPPORTING GIRDERS	LUMP	LUMP
58	711-96800 STUD SHEAR CONNECTORS	4,046.000	EACH
59	715-05407 PIPE, END BENT DRAIN, 6 IN	82.300	LFT
60	715-10238 PIPE ROADWAY DRAIN CASTING EXTENSION	10.000	EACH
61	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
62	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
63	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	1,112.000	LFT
64	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	7,428.000	LFT
65	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	24.000	LFT
66	801-06640 CONSTRUCTION SIGN, A	36.000	EACH
67	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
68	801-07118 BARRICADE, III-A	40.000	LFT
69	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	1,218.000	LFT
70	808-06716 LINE, REMOVE	2,754.000	LFT
71	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	1,194.000	LFT
72	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	149.000	LFT
73	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN	1,238.000	LFT
74	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	184.800	LFT
75	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	14.000	EACH

CALL ORDER : 381

CONTRACT ID : B -34507-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEBRIS REMOVAL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	203-02020 EXCAVATION, UNCLASSIFIED	500.000	CYS
8	205-06937 TEMPORARY SILT FENCE	400.000	LFT
9	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
10	621-06626 MULCHED SEEDING, D	1,000.000	SYS
11	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
12	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	5.000	MOS
13	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
14	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 411

CONTRACT ID : M -35059-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 DEBRIS REMOVAL			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
6	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
7	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
8	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
9	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
10	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
11	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
12	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
13	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
14	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
15	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	3.000	MOS
16	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
17	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
18	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
20	801-06710 FLASHING ARROW SIGN	5.000	DAY
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 431

CONTRACT ID : T -33244-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-04890 WELL	1.000	EACH
10	202-05545 REGULATED MATERIALS, DISPOSE, C	1,094.000	CYS
11	202-05550 REGULATED MATERIALS, REMOVE, C	1,094.000	CYS
12	202-05555 REGULATED MATERIALS, TRANSPORT, C	1,094.000	CYS
13	202-07603 TESTING FOR WASTES, C	4.000	EACH
14	203-02000 EXCAVATION, COMMON	194.000	CYS
15	203-02100 EXCAVATION, PEAT	1,220.000	CYS
16	205-03371 SEDIMENT, REMOVE	10.000	CYS
17	205-06937 TEMPORARY SILT FENCE	655.000	LFT
18	205-09543 NO 2 STONE	100.000	TON
19	206-51817 SHEET PILING, STEEL	870.000	SFT
20	207-08264 SUBGRADE TREATMENT, TYPE II	2,025.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	55.000	SYS
22	211-02050 B BORROW	1,470.000	CYS
23	211-09264 STRUCTURAL BACKFILL, TYPE 1	81.000	CYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	598.000	TON
25	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	100.000	TON
26	402-07432 HMA SURFACE, TYPE A	65.000	TON
27	402-07433 HMA SURFACE, TYPE B	77.000	TON
28	402-07435 HMA INTERMEDIATE, TYPE A	107.000	TON
29	402-07438 HMA INTERMEDIATE, TYPE B	129.000	TON
30	402-07441 HMA BASE, TYPE B	206.000	TON
31	406-05520 ASPHALT FOR TACK COAT	0.690	TON
32	506-06333 PCCP PATCHING, FULL DEPTH	120.000	SYS
33	604-06070 SIDEWALK, CONCRETE	598.000	SYS
34	604-07894 CURB RAMP, CONCRETE, A	41.000	SYS
35	604-07896 CURB RAMP, CONCRETE, B	60.000	SYS
36	604-07902 CURB RAMP, CONCRETE, H	13.000	SYS
37	604-07903 CURB RAMP, CONCRETE, K	125.000	SYS
38	604-07904 CURB RAMP, CONCRETE, L	5.000	SYS
39	605-06090 CURB, INTEGRAL, CONCRETE	450.000	LFT
40	605-06105 CURB, INTEGRAL, CONCRETE, MODIFIED	24.000	LFT
41	605-06120 CURB, CONCRETE	36.000	LFT
42	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	828.000	LFT
43	610-09108 PCCP FOR APPROACHES, 9 IN	55.000	SYS
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
45	621-06545 FERTILIZER	0.200	TON
46	621-06554 SEED MIXTURE, U	75.000	LBS
47	621-06557 SEED MIXTURE, T	105.000	LBS
48	621-06565 MULCHING MATERIAL	1.000	TON
49	621-06567 WATER	39.000	KGAL

CALL ORDER : 431

CONTRACT ID : T -33244-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
50	621-06570 TOPSOIL	52.000	CYS
51	621-06575 SODDING, NURSERY	465.000	SYS
52	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	8.000	EACH
53	628-09402 FIELD OFFICE, B	10.000	MOS
54	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	250.000	LFT
55	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	5.000	LFT
56	715-09064 VIDEO INSPECTION FOR PIPE	257.000	LFT
57	720-44296 INLET, CAP	1.000	EACH
58	720-45045 INLET, J10	4.000	EACH
59	720-45055 INLET, M10	6.000	EACH
60	720-45410 MANHOLE, C4	2.000	EACH
61	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	6.000	EACH
62	801-01505 TEMPORARY PAVEMENT MESSAGE MARKING, (ONLY)	5.000	EACH
63	801-03290 CONSTRUCTION SIGN, C	1.000	EACH
64	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	4,705.000	LFT
65	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	900.000	LFT
66	801-06640 CONSTRUCTION SIGN, A	92.000	EACH
67	801-06645 CONSTRUCTION SIGN, B	66.000	EACH
68	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
69	801-07119 BARRICADE, III-B	90.000	LFT
70	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN	130.000	LFT
71	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	150.000	LFT
72	801-94295 SIGNAL HEAD, RELOCATE	24.000	EACH
73	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	67.000	LFT
74	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	105.376	SFT
75	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	267.900	SFT
76	802-99045 SIGN REMOUNTING	26.000	EACH
77	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	7.000	EACH
78	805-01579 MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	LUMP	LUMP
79	805-01842 HANDHOLE, SIGNAL	29.000	EACH
80	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	2.000	EACH
81	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
82	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	48.000	EACH
83	805-02262 FLASHER INSTALLATION	LUMP	LUMP
84	805-02373 SIGNAL INTERCONNECT CABLE, FIBER OPTIC	9,200.000	LFT
85	805-02658 CABLE, COAXIAL	5,670.000	LFT
86	805-03978 EMERGENCY VEHICLE PREEMPTION DETECTOR,	1.000	EACH
87	805-03979 EMERGENCY VEHICLE PREEMPTION DETECTOR,	6.000	EACH
88	805-04133 SIGNAL PEDESTAL, 12FT	4.000	EACH
89	805-04782 VIDEO VEHICLE DETECTOR SYSTEM	7.000	EACH
90	805-05870 SIGNAL SUPPORT FOUNDATION	2.000	EACH
91	805-06997 CAMERA	2.000	EACH
92	805-09343 ITS	1.000	EACH
93	805-09773 SIGNAL POLE	2.000	EACH
94	805-11375 SIGNAL CANTILEVER STRUCTURE, SIGNAL	6.000	EACH
95	805-11376 SIGNAL CANTILEVER STRUCTURE, SIGNAL	7.000	EACH
96	805-11377 SIGNAL CANTILEVER STRUCTURE, SIGNAL	7.000	EACH
97	805-11378 SIGNAL CANTILEVER STRUCTURE, SIGNAL	2.000	EACH
98	805-11383 SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT	20.000	EACH

CALL ORDER : 431

CONTRACT ID : T -33244-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
99	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT	2.000 EACH
100	805-11430	SIGNAL CANTILEVER STRUCTURE, POLE SECTION 2,	20.000 EACH
101	805-11431	SIGNAL CANTILEVER STRUCTURE, POLE SECTION 2,	2.000 EACH
102	805-11433	SIGNAL CANTILEVER STRUCTURE, COMBINATION	2.000 EACH
103	805-11434	SIGNAL CANTILEVER STRUCTURE, COMBINATION	8.000 EACH
104	805-11435	SIGNAL CANTILEVER STRUCTURE, COMBINATION	5.000 EACH
105	805-11436	SIGNAL CANTILEVER STRUCTURE, COMBINATION	7.000 EACH
106	805-78010	CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000 EACH
107	805-78106	CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000 EACH
108	805-78109	CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	6.000 EACH
109	805-78205	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	52.000 EACH
110	805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 12"	5.000 EACH
111	805-78370	PEDESTRIAN PUSH BUTTON	48.000 EACH
112	805-78415	SPAN, CATENARY, AND TETHER	2.000 EACH
113	805-78420	DISCONNECT HANGER	2.000 EACH
114	805-78445	SIGNAL SERVICE	6.000 EACH
115	805-78467	SIGNAL CABLE, 3C/8GA	700.000 LFT
116	805-78480	SIGNAL CABLE, 3C/14GA	4,840.000 LFT
117	805-78485	SIGNAL CABLE, 5C/14GA	7,260.000 LFT
118	805-78490	SIGNAL CABLE, 7C/14GA	4,000.000 LFT
119	805-78510	SIGNAL CABLE, 2C/16GA., SHIELDED	745.000 LFT
120	805-78906	SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 12 FT	1.000 EACH
121	805-78925	CONTROLLER CABINET FOUNDATION, P1	6.000 EACH
122	805-81060	SIGNAL STRAIN POLE, STEEL, 36 FT	1.000 EACH
123	805-91615	EMERGENCY PRE-EMPTOR	1.000 EACH
124	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000 EACH
125	807-02191	HANDHOLE, LIGHTING	1.000 EACH
126	807-02426	WIRE, THW, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	20.000 LFT
127	807-02579	MAST ARM, 15FT	2.000 EACH
128	807-02784	LUMINAIRE, MAST ARM, 20 FT	1.000 EACH
129	807-04940	MAST ARM	1.000 EACH
130	807-04940	MAST ARM	3.000 EACH
131	807-04940	MAST ARM	1.000 EACH
132	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN	2,975.000 LFT
133	807-86615	LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	1.000 EACH
134	807-86889	CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	160.000 LFT
135	807-86910	CONNECTOR KIT, UNFUSED	1.000 EACH
136	807-86915	CONNECTOR KIT, FUSED	1.000 EACH
137	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	1.000 EACH
138	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	1.000 EACH
139	807-86930	INSULATION LINK, NON-WATERPROOFED	3.000 EACH
140	807-86935	INSULATION LINK, WATERPROOFED	4.000 EACH
141	807-86950	SIGN UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	1.000 EACH
142	808-02066	TRANSVERSE MARKINGS, THERMOPLASTIC,	205.000 LFT
143	808-06368	TRANSVERSE MARKING, REMOVE	3,100.000 LFT
144	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	624.000 LFT
145	808-06716	LINE, REMOVE	6,000.000 LFT
146	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN	50.000 LFT
147	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,890.000 LFT

CALL ORDER : 431

CONTRACT ID : T -33244-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
148 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	810.000	LFT
149 808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	2,896.000	LFT
150 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	9.000	EACH
151 808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	6.000	EACH
152 808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN	120.000	LFT

CALL ORDER : 441

CONTRACT ID : T -34232-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT MARKINGS		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
7	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	6.000	MOS
8	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
9	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
10	801-06710 FLASHING ARROW SIGN	90.000	DAY
11	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
12	801-92448 CONSTRUCTION SIGNS, MOBILE	120.000	DAY
13	808-75994 PRISMATIC REFLECTOR	19,146.000	EACH
14	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	950.000	EACH
15	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,915.000	EACH

