

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	113-01614 PARTNERING OVERHEAD	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-01261 TESTING FOR ASBESTOS	10.000	EACH
17	202-01261 TESTING FOR ASBESTOS	20.000	EACH
18	202-02240 PAVEMENT REMOVAL	71,968.000	SYS
19	202-02271 HEADWALL, REMOVE	1.000	EACH
20	202-02273 CENTER CURB, CONCRETE, REMOVE	468.000	SYS
21	202-02278 CURB, CONCRETE, REMOVE	303.000	LFT
22	202-02279 CURB AND GUTTER, REMOVE	8,452.000	LFT
23	202-02637 PIPE, ABANDON AND GROUT FILL	2,580.000	LFT
24	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
25	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
26	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
27	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
28	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
29	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
30	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
31	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
32	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
33	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
34	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
35	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
36	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
37	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
38	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
39	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
40	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
41	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
42	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	1,250.000	SFT
43	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	22,496.000	SFT
44	202-03729 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	50.000	LFT
45	202-03729 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	1,722.000	LFT
46	202-05545 REGULATED MATERIALS, DISPOSE, C	100.000	CYS
47	202-05550 REGULATED MATERIALS, REMOVE, C	100.000	CYS
48	202-05555 REGULATED MATERIALS, TRANSPORT, C	100.000	CYS
49	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE,	1.000	EACH

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
50	202-05826 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE,	2.000	EACH
51	202-05858 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	900.000	CFT
52	202-07554 REGULATED MATERIALS, TRANSPORT, Y	10.000	CYS
53	202-07554 REGULATED MATERIALS, TRANSPORT, Y	42.000	CYS
54	202-07555 REGULATED MATERIALS, DISPOSE, TYPE Y	10.000	CYS
55	202-07555 REGULATED MATERIALS, DISPOSE, TYPE Y	42.000	CYS
56	202-09106 TESTING FOR CONTAMINATED MATERIALS, MTBE AND BTEX	8.000	EACH
57	202-51133 RAILING, REMOVE	230.000	LFT
58	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
59	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
60	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
61	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
62	202-51368 SLOPEWALL, REMOVE	91.000	SYS
63	202-52710 SIDEWALK, CONCRETE, REMOVE	170.000	SYS
64	202-74055 OVERHEAD SIGN STRUCTURE, BOX	3.000	EACH
65	202-74080 OVERHEAD SIGN STRUCTURE,	2.000	EACH
66	202-90747 RETAINING WALL, REMOVE	286.000	LFT
67	202-91385 INLET, REMOVE	51.000	EACH
68	202-91840 FENCE, CHAIN LINK, REMOVE	223.000	LFT
69	202-93047 MANHOLE, REMOVE	25.000	EACH
70	202-93615 CONCRETE, REMOVE	2,351.000	SYS
71	202-94810 CURB TURNOUT, REMOVE	1.000	EACH
72	202-96133 PIPE, REMOVE	6,647.000	LFT
73	203-02000 EXCAVATION, COMMON	83,295.000	CYS
74	203-02070 BORROW	55,538.000	CYS
75	203-02100 EXCAVATION, PEAT	36,049.000	CYS
76	203-07042 EMBANKMENT FOUNDATION SOILS TREATMENT	16,753.000	SYS
77	203-08607 LINEAR GRADING	77,212.000	LFT
78	203-51223 EXCAVATION, WATERWAY	745.000	CYS
79	205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE	16.000	EACH
80	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	44.000	EACH
81	205-03371 SEDIMENT, REMOVE	1,183.000	CYS
82	205-06930 SPLASHPAD	6.000	TON
83	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	472.000	TON
84	205-06933 TEMPORARY INLET PROTECTION	59.000	EACH
85	205-06934 TEMPORARY MULCH	67.000	TON
86	205-06936 TEMPORARY SEDIMENT TRAP	1,251.000	TON
87	205-06937 TEMPORARY SILT FENCE	5,827.000	LFT
88	205-06938 TEMPORARY SLOPE DRAIN	305.000	LFT
89	205-09543 NO 2 STONE	100.000	TON
90	205-09543 NO 2 STONE	300.000	TON
91	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	647.000	CYS
92	207-08263 SUBGRADE TREATMENT, TYPE IA	117,685.000	SYS
93	207-08264 SUBGRADE TREATMENT, TYPE II	15,580.000	SYS
94	207-08265 SUBGRADE TREATMENT, TYPE IIA	7,486.000	SYS
95	207-08267 SUBGRADE TREATMENT, TYPE IIIA	14,808.000	SYS
96	211-02050 B BORROW	35,494.000	CYS
97	211-06467 AGGREGATE FOR END BENT BACKFILL	300.000	CYS
98	211-09264 STRUCTURAL BACKFILL, TYPE 1	980.000	CYS

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
99	211-09265 STRUCTURAL BACKFILL, TYPE 2	477.000	CYS
100	211-09266 STRUCTURAL BACKFILL, TYPE 3	1,571.000	CYS
101	211-09268 STRUCTURAL BACKFILL, TYPE 5	162.000	CYS
102	215-07043 CHEMICAL MODIFICATION, SOILS	9,778.000	SYS
103	215-09385 CHEMICAL MODIFIER, SOILS, MODIFYING WET FILL SOIL	100.000	TON
104	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	7,413.000	TON
105	302-07455 DENSE GRADED SUBBASE	276.000	CYS
106	303-01180 COMPACTED AGGREGATE, NO. 53	32,939.000	TON
107	306-08041 MILLING, PCCP	2,178.000	SYS
108	306-08042 MILLING, SCARIFICATION/PROFILE	157,727.000	SYS
109	306-08043 MILLING, TRANSITION	1,712.000	SYS
110	306-08432 MILLING, APPROACH	304.000	SYS
111	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	4,522.000	TON
112	401-07323 QC/QA-HMA, 4, 64, SURFACE, 9.5 mm	8,661.000	TON
113	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	17,365.000	TON
114	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,393.000	TON
115	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2,949.000	TON
116	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	3,149.000	TON
117	401-10258 JOINT ADHESIVE, SURFACE	100.000	LFT
118	402-07432 HMA SURFACE, TYPE A	126.000	TON
119	402-07433 HMA SURFACE, TYPE B	3,327.000	TON
120	402-07435 HMA INTERMEDIATE, TYPE A	198.000	TON
121	402-07438 HMA INTERMEDIATE, TYPE B	5,293.000	TON
122	402-07440 HMA BASE, TYPE A	1,005.000	TON
123	402-07441 HMA BASE, TYPE B	6,221.000	TON
124	402-10087 HMA FOR TEMPORARY PAVEMENT, D	991.000	TON
125	406-05520 ASPHALT FOR TACK COAT	59.000	TON
126	503-05310 TERMINAL JOINT	70.000	LFT
127	601-01522 GUARDRAIL, TRANSITION TYPE TGB	25.000	EACH
128	601-01839 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 6	2.000	EACH
129	601-02241 GUARDRAIL, REMOVE	2,186.000	LFT
130	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	2.000	EACH
131	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	2.000	EACH
132	601-06416 IMPACT ATTENUATOR SPARE PARTS PACKAGE, ED, W1, TL-3	1.000	EACH
133	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
134	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
135	601-08435 GUARDRAIL END TREATMENT, TYPE MS, SPARE PARTS	2.000	EACH
136	601-08436 GUARDRAIL END TREATMENT, TYPE MS, SPARE PARTS	2.000	EACH
137	601-94689 GUARDRAIL END TREATMENT, OS	16.000	EACH
138	601-94690 GUARDRAIL END TREATMENT, MS	4.000	EACH
139	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	3,707.000	LFT
140	601-99108 GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	900.000	LFT
141	602-06729 BARRIER DELINEATOR	56.000	EACH
142	602-08344 REINFORCED CONCRETE MOMENT SLAB	1,515.000	SYS
143	603-06040 FENCE, FARM FIELD, 47 IN	8,491.000	LFT
144	603-06045 FENCE, CHAIN LINK, 48 IN	4,723.000	LFT
145	603-91714 FENCE, RAIL, WOOD	60.000	LFT
146	604-06070 SIDEWALK, CONCRETE	1,683.000	SYS
147	604-07894 CURB RAMP, CONCRETE, A	26.000	SYS

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
148	604-07897 CURB RAMP, CONCRETE, C	61.000	SYS
149	604-07901 CURB RAMP, CONCRETE, G	12.000	SYS
150	604-07902 CURB RAMP, CONCRETE, H	29.000	SYS
151	605-05523 CURB, HMA	794.000	LFT
152	605-06120 CURB, CONCRETE	42.000	LFT
153	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	1,494.000	LFT
154	605-06165 CURB AND GUTTER, C, CONCRETE, MODIFIED	8,613.000	LFT
155	605-06250 CENTER CURB, C, CONCRETE	134.000	SYS
156	605-94811 CURB TURNOUT	2.000	EACH
157	606-07484 MILLED HMA SHOULDER CORRUGATIONS	182,242.000	LFT
158	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	1,641.600	SYS
159	610-07486 HMA FOR APPROACHES, TYPE A	245.000	TON
160	610-07487 HMA FOR APPROACHES, TYPE B	793.000	TON
161	610-08446 PCCP FOR APPROACHES, 6 IN	776.000	SYS
162	610-09108 PCCP FOR APPROACHES, 9 IN	3,366.000	SYS
163	611-06497 MAILBOX ASSEMBLY, SINGLE	21.000	EACH
164	611-06498 MAILBOX ASSEMBLY, DOUBLE	5.000	EACH
165	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	4.000	TON
166	612-60410 DRILLED HOLE FOR UNDERSEAL	72.000	EACH
167	615-06490 RIGHT OF WAY MARKER	156.000	EACH
168	615-06505 MONUMENT, B	88.000	EACH
169	615-06510 MONUMENT, C	36.000	EACH
170	615-06515 MONUMENT, D	18.000	EACH
171	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
172	615-06530 BENCH MARK POST	4.000	EACH
173	616-02320 GEOTEXTILES	5,063.000	SYS
174	616-05688 RIPRAP, CLASS 1	8.000	TON
175	616-06405 RIPRAP, REVETMENT	4,219.000	TON
176	616-51367 SLOPEWALL, CONCRETE, 4 IN	91.000	SYS
177	619-11050 CLEAN STEEL BRIDGE, PARTIAL, QP-2, BR. NO.	LUMP	LUMP
178	619-11050 CLEAN STEEL BRIDGE, PARTIAL, QP-2, BR. NO.	LUMP	LUMP
179	619-51860 PAINT STEEL BRIDGE, PARTIAL, BR. NO.	LUMP	LUMP
180	619-51860 PAINT STEEL BRIDGE, PARTIAL, BR. NO.	LUMP	LUMP
181	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
182	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	129,690.000	SYS
183	621-02770 EROSION CONTROL BLANKET	82,577.000	SYS
184	621-06545 FERTILIZER	16.000	TON
185	621-06553 SEED MIXTURE, R	4,555.000	LBS
186	621-06554 SEED MIXTURE, U	2,111.000	LBS
187	621-06557 SEED MIXTURE, T	1,055.000	LBS
188	621-06565 MULCHING MATERIAL	96.000	TON
189	621-06567 WATER	106.000	KGAL
190	621-06574 SODDING	21,493.000	SYS
191	621-06575 SODDING, NURSERY	7,864.000	SYS
192	621-90853 TAPPING SLEEVE WITH VALVE	3.000	EACH
193	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
194	623-04884 MOWING, CYCLE NO 1	1.000	CYCL
195	627-09327 CABLE BARRIER SYSTEM, TYPE TL-4	21,959.000	LFT
196	627-09329 CABLE BARRIER, TYPE TL-4, SPARE PARTS	1.000	EACH

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
197	627-09331 SAFETY TERMINAL, TYPE TL-4	20.000	EACH
198	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
199	628-09403 FIELD OFFICE, C	30.000	MOS
200	628-09719 ALL TERRAIN VEHICLE	18.000	MOS
201	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	90.000	MOS
202	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
203	701-06011 DYNAMIC PILE LOAD TEST	8.000	EACH
204	701-09557 TEST PILE, DYNAMIC, PRODUCTION	579.000	LFT
205	701-09559 TEST PILE, DYNAMIC, RESTRIKE	8.000	EACH
206	701-09665 PILE, STEEL PIPE, 0.375 IN, 14 IN	3,042.000	LFT
207	701-09679 CONICAL PILE TIP, 14 IN	90.000	EACH
208	701-09826 PILE, STEEL PIPE, 0.5 IN., 14 IN.	1,708.000	LFT
209	702-51005 CONCRETE, A, SUBSTRUCTURE	159.600	CYS
210	702-51015 CONCRETE, B, FOOTINGS	82.400	CYS
211	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	1,288.000	LBS
212	702-51863 FIELD DRILLED HOLE IN CONCRETE	1,334.000	EACH
213	702-76240 CONCRETE	7.700	CYS
214	702-92857 CONCRETE, C, SUBSTRUCTURE	200.400	CYS
215	703-06028 REINFORCING BARS	13,407.000	LBS
216	703-06029 REINFORCING BARS, EPOXY COATED	622,212.000	LBS
217	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	252.000	EACH
218	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,092.700	CYS
219	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	4.000	EACH
220	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	2,232.000	SYS
221	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	53.000	SYS
222	706-09545 COARSE AGGREGATE, NO 8	8.800	CYS
223	706-09959 RAILING, CONCRETE, FT	1,207.000	LFT
224	706-09960 RAILING, CONCRETE, FC	475.000	LFT
225	706-09965 RAILING, CONCRETE, TX	2,786.000	LFT
226	706-11600 RAILING, CONCRETE, FC	50.800	CYS
227	706-11601 RAILING, CONCRETE, FT	127.600	CYS
228	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
229	706-11621 CONCRETE BRIDGE RAILING TRANSITION, TFT	16.000	EACH
230	706-11621 CONCRETE BRIDGE RAILING TRANSITION, TFT	5.000	EACH
231	707-05983 STRUCTURAL MEMBER, CONCRETE I-BEAM, 36 IN X 12 IN	648.000	LFT
232	707-08158 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 42 IN X 49 IN	265.000	LFT
233	707-09634 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 48 IN X 49 IN	1,600.000	LFT
234	709-07110 SEAL COAT, GRAFFITI RESISTANT	51,767.000	SFT
235	709-51821 SURFACE SEAL	LUMP	LUMP
236	709-51821 SURFACE SEAL	LUMP	LUMP
237	709-51821 SURFACE SEAL	LUMP	LUMP
238	709-51821 SURFACE SEAL	LUMP	LUMP
239	709-51821 SURFACE SEAL	LUMP	LUMP
240	709-51821 SURFACE SEAL	LUMP	LUMP
241	709-51821 SURFACE SEAL	LUMP	LUMP
242	709-51821 SURFACE SEAL	LUMP	LUMP
243	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
244	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
245	714-11173 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	580.000	LFT

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
246	714-11190 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	23.000	LFT
247	715-01336 GATE VALVE, 12 IN	4.000	EACH
248	715-04596 WATER SERVICE	1.000	EACH
249	715-04995 LINE STOP	3.000	EACH
250	715-04995 LINE STOP	1.000	EACH
251	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	341.000	LFT
252	715-05032 PIPE, TYPE 2 CIRCULAR 15 IN	171.000	LFT
253	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	26,450.000	LFT
254	715-05049 PIPE, TYPE 4 CIRCULAR 8 IN	265.000	LFT
255	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	265.000	LFT
256	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	3,842.000	LFT
257	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	71.000	LFT
258	715-05125 PIPE, TYPE 1 CIRCULAR 30 IN	156.000	LFT
259	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	3,477.000	LFT
260	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	2,532.000	LFT
261	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	1,409.000	LFT
262	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	543.000	LFT
263	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	158.000	LFT
264	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	582.000	LFT
265	715-05173 PIPE, TYPE 3 CIRCULAR 24 IN	105.000	LFT
266	715-05175 PIPE, TYPE 3 CIRCULAR 30 IN	107.000	LFT
267	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	30,447.000	LFT
268	715-05217 PIPE, TYPE 5 CIRCULAR 12 IN	32.000	LFT
269	715-05218 PIPE, TYPE 5 CIRCULAR 15 IN	331.000	LFT
270	715-05407 PIPE, END BENT DRAIN, 6 IN	305.000	LFT
271	715-05408 PIPE SANITARY SEWER 8 IN	291.000	LFT
272	715-05409 PIPE SANITARY SEWER 10 IN	1,114.000	LFT
273	715-05413 PIPE SANITARY SEWER 18 IN	260.000	LFT
274	715-05711 PIPE SANITARY SEWER 6 IN	50.000	LFT
275	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	16.000	TON
276	715-09064 VIDEO INSPECTION FOR PIPE	8,263.000	LFT
277	715-10238 PIPE ROADWAY DRAIN CASTING EXTENSION	4.000	EACH
278	715-46000 PIPE END SECTION, DIA 12"	7.000	EACH
279	715-46005 PIPE END SECTION, DIA 15"	27.000	EACH
280	715-46010 PIPE END SECTION, DIA 18"	10.000	EACH
281	715-46020 PIPE END SECTION, DIA 24"	6.000	EACH
282	715-46030 PIPE END SECTION, DIA 30"	6.000	EACH
283	715-94530 ADJUST WATER VALVE TO GRADE	6.000	EACH
284	715-95866 GATE VALVE, 6 IN.	5.000	EACH
285	715-96669 WATER MAIN, DUCTILE IRON, 16 IN	590.000	LFT
286	715-96670 WATER MAIN, DUCTILE IRON, 12 IN	870.000	LFT
287	715-96670 WATER MAIN, DUCTILE IRON, 12 IN	115.000	LFT
288	715-98961 FORCE MAIN	225.000	LFT
289	716-07633 PIPE INSTALLATION, TRENCHLESS, 24 IN	210.000	LFT
290	718-06526 HMA FOR UNDERDRAINS	1,248.000	TON
291	718-06528 OUTLET PROTECTOR, 1	113.000	EACH
292	718-06529 OUTLET PROTECTOR, 2	4.000	EACH
293	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	9,500.000	LFT
294	718-52610 AGGREGATE FOR UNDERDRAINS	3,791.000	CYS

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
295	718-99153 GEOTEXTILES FOR UNDERDRAIN	27,346.000	SYS
296	719-05438 PIPE, DRAIN TILE TERMINAL SECTION, 4 IN	60.000	LFT
297	719-05439 PIPE, DRAIN TILE TERMINAL SECTION, 6 IN	40.000	LFT
298	719-05440 PIPE, DRAIN TILE TERMINAL SECTION, 8 IN	30.000	LFT
299	719-05442 PIPE, DRAIN TILE TERMINAL SECTION, 10 IN	30.000	LFT
300	719-05443 PIPE, DRAIN TILE TERMINAL SECTION, 12 IN	30.000	LFT
301	719-93923 DUCTILE IRON FITTINGS	9,171.000	LBS
302	720-02442 PIPE, PLUG EXISTING	1.000	EACH
303	720-09079 INLET, HA5, MODIFIED	4.000	EACH
304	720-44000 CASTING, ADJUST TO GRADE	17.000	EACH
305	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	5.000	EACH
306	720-45030 INLET, E7	10.000	EACH
307	720-45035 INLET, F7	6.000	EACH
308	720-45042 INLET, HA5	3.000	EACH
309	720-45065 INLET, N12	14.000	EACH
310	720-45130 INLET, E7, MODIFIED	3.000	EACH
311	720-45251 CATCH BASIN, K10, MODIFIED	6.000	EACH
312	720-45270 PIPE CATCH BASIN, 18 IN	4.000	EACH
313	720-45275 PIPE CATCH BASIN, 24 IN	2.000	EACH
314	720-45410 MANHOLE, C4	36.000	EACH
315	720-45410 MANHOLE, C4	10.000	EACH
316	720-45425 MANHOLE, F4	1.000	EACH
317	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	28.000	LFT
318	720-90129 MANHOLE, J2	1.000	EACH
319	720-91352 CATCH BASIN, F7	2.000	EACH
320	720-93411 INLET, C15, MODIFIED	1.000	EACH
321	720-94713 CATCH BASIN, C15, MODIFIED	20.000	EACH
322	720-95164 CATCH BASIN, B15, MODIFIED	19.000	EACH
323	720-95422 MANHOLE, J4	7.000	EACH
324	720-97008 FIRE HYDRANT ASSEMBLY, RELOCATE	5.000	EACH
325	720-97009 FIRE HYDRANT ASSEMBLY, REMOVE	3.000	EACH
326	720-98174 INLET, B15	4.000	EACH
327	720-99416 CATCH BASIN, B15	38.000	EACH
328	720-99417 CATCH BASIN, C15	18.000	EACH
329	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	462.000	SFT
330	722-51842 BRIDGE DECK OVERLAY	1,708.000	SYS
331	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	47.800	CYS
332	722-60824 SURFACE MILLING	1,610.000	SYS
333	731-93945 FACE PANELS, CONCRETE	53,207.000	SFT
334	731-93946 WALL ERECTION	53,207.000	SFT
335	731-93947 LEVELING PAD, CONCRETE	3,770.000	LFT
336	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	22.000	EACH
337	801-03290 CONSTRUCTION SIGN, C	20.000	EACH
338	801-04308 ROAD CLOSURE SIGN ASSEMBLY	19.000	EACH
339	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	15,736.000	LFT
340	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	127,299.000	LFT
341	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	5.000	EACH
342	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	5.000	EACH
343	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24"	251.000	LFT

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
344	801-06625 DETOUR ROUTE MARKER ASSEMBLY	48.000	EACH
345	801-06640 CONSTRUCTION SIGN, A	104.000	EACH
346	801-06710 FLASHING ARROW SIGN	1,860.000	DAY
347	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
348	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	1.000	EACH
349	801-07117 TEMPORARY WORKSITE FLASHING LIGHT SIGN ASSEMBLY	16.000	EACH
350	801-07118 BARRICADE, III-A	288.000	LFT
351	801-07119 BARRICADE, III-B	312.000	LFT
352	801-07606 TEMPORARY CROSSOVER DRAINAGE PIPE	750.000	LFT
353	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	1,653.000	LFT
354	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
355	801-52817 TEMPORARY CROSSOVER, B	3.000	EACH
356	801-94295 SIGNAL HEAD, RELOCATE	35.000	EACH
357	802-03783 SIGN, PANEL, REMOVE	7.000	EACH
358	802-03866 MILE MARKER	21.000	EACH
359	802-03896 BOLLARD	10.000	EACH
360	802-04089 SIGN, SHEET, REMOVE	8.000	EACH
361	802-04314 SIGN	32.000	EACH
362	802-04893 REFERENCE POST	116.000	EACH
363	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	1,546.000	LFT
364	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	1,616.000	LFT
365	802-05706 SIGN POST, SQUARE, TYPE 3, UNREINFORCED ANCHOR BASE	23.000	LFT
366	802-07057 SIGN, PANEL, WITH LEGEND	10,026.000	SFT
367	802-07135 CABLE SPAN SIGN STRUCTURE FOUNDATION, IV	2.000	EACH
368	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	58.000	EACH
369	802-07152 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, X	2.000	EACH
370	802-07153 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	23.000	EACH
371	802-07154 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XII	8.000	EACH
372	802-09576 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE D	1.000	EACH
373	802-09577 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E	2.000	EACH
374	802-09578 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	7.000	EACH
375	802-09581 CANTILEVER SIGN SUPPORT FOUNDATION,	10.000	EACH
376	802-09710 BOX TRUSS SIGN STRUCTURE FOUNDATION 36 IN HEIGHT	2.000	EACH
377	802-09714 OVERHEAD SIGN STRUCTURE, C	1.000	EACH
378	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	853.500	SFT
379	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	64.000	SFT
380	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	1,529.000	SFT
381	802-09841 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.125 IN THICKNESS	35.000	SFT
382	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	109.000	SFT
383	802-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	9.000	EACH
384	802-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	96.000	EACH
385	802-76055 SIGN POST, A	278.000	LFT
386	802-76095 STRUCTURAL STEEL, BREAKAWAY	26,559.000	LBS
387	802-76125 OVERHEAD SIGN STRUCTURE, CABLESPAN	1.000	EACH
388	802-93675 MARKER, HISTORIC, RESET	1.000	EACH
389	804-06740 DELINEATOR WITH POST, D2	20.000	EACH
390	804-06770 DELINEATOR POST	20.000	EACH
391	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	3.000	EACH
392	805-01842 HANDHOLE, SIGNAL	9.000	EACH

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
393	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	1,464.000	LFT
394	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
395	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	8.000	EACH
396	805-02645 SIGNAL PEDESTAL FOUNDATION, A	4.000	EACH
397	805-03979 EMERGENCY VEHICLE PREEMPTION DETECTOR,	4.000	EACH
398	805-03985 DETECTOR CABLE 3C 20GA.	1,028.000	LFT
399	805-05405 SIGNAL PEDESTAL, 4FT	4.000	EACH
400	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
401	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	8.000	EACH
402	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	5.000	EACH
403	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
404	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
405	805-78420 DISCONNECT HANGER	4.000	EACH
406	805-78467 SIGNAL CABLE, 3C/8GA	27.000	LFT
407	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	5,109.000	LFT
408	805-78480 SIGNAL CABLE, 3C/14GA	2,067.000	LFT
409	805-78485 SIGNAL CABLE, 5C/14GA	1,246.000	LFT
410	805-78490 SIGNAL CABLE, 7C/14GA	1,007.000	LFT
411	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	5,336.000	LFT
412	805-78785 SIGNAL DETECTOR HOUSING	15.000	EACH
413	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,766.000	LFT
414	805-78906 SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 12 FT	4.000	EACH
415	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
416	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
417	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	9.000	EACH
418	807-86810 SERVICE POINT, II	1.000	EACH
419	808-02977 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	1.000	EACH
420	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	574.000	LFT
421	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	1,971.000	LFT
422	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN	168.000	LFT
423	808-06716 LINE, REMOVE	20,000.000	LFT
424	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
425	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	280.000	LFT
426	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	213,877.000	LFT
427	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	208,383.000	LFT
428	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	8,582.000	LFT
429	808-10038 TRANSVERSE MARKINGS MULTI-COMPONENT,	740.000	LFT
430	808-10043 LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN	164.000	LFT
431	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	125.000	LFT
432	808-10052 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, (ONLY)	6.000	EACH
433	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	48,121.000	LFT
434	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	4,078.000	LFT
435	808-10059 LINE, MULTI-COMPONENT, SOLID, YELLOW, 12 IN	96.000	LFT
436	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	10.000	EACH
437	808-10119 TRANSVERSE MARKING, MULTI-COMPONENT,	605.000	LFT
438	808-11482 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	54.000	LFT
439	808-11493 LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN.	17.000	LFT
440	808-74815 TRANSVERSE MARKING, THERMOPLASTIC,	1,360.000	LFT
441	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	246.000	LFT

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD AND BRIDGE CONSTRUCTION			
442	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	587.000	LFT
443	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	15.000	EACH
444	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	12.000	EACH
445	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	3,929.000	EACH
SECTION NO. 0002 ROAD CONSTRUCTION			
446	203-02000 EXCAVATION, COMMON	135,747.000	CYS
447	211-02050 B BORROW	8,502.000	CYS
448	211-09264 STRUCTURAL BACKFILL, TYPE 1	3,504.000	CYS
449	211-09266 STRUCTURAL BACKFILL, TYPE 3	23,113.000	CYS
450	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5,868.000	TON
451	303-01180 COMPACTED AGGREGATE, NO. 53	3,331.000	TON
452	306-08034 MILLING, ASPHALT, 1 1/2 IN	2,043.000	SYS
453	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
454	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	672.000	TON
455	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	4,546.000	TON
456	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,132.000	TON
457	401-07399 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	7,581.000	TON
458	401-07422 QC/QA-HMA, 1, 64, BASE, 19.0 mm	2,590.000	TON
459	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	10,017.000	TON
460	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	18,607.000	TON
461	401-10258 JOINT ADHESIVE, SURFACE	34,258.000	LFT
462	401-10259 JOINT ADHESIVE, INTERMEDIATE	32,878.000	LFT
463	406-05520 ASPHALT FOR TACK COAT	73.000	TON
464	412-09355 FOG SEAL	7,614.000	SYS
465	415-11527 BASE SEAL	35.000	TON
466	606-07484 MILLED HMA SHOULDER CORRUGATIONS	8,466.000	LFT
467	616-02320 GEOTEXTILES	6,426.000	SYS
468	706-09545 COARSE AGGREGATE, NO 8	476.000	CYS
469	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	2,534.000	LFT
470	718-99153 GEOTEXTILES FOR UNDERDRAIN	8,648.000	SYS
SECTION NO. 0003 ROAD CONSTRUCTION			
471	203-02000 EXCAVATION, COMMON	140,748.000	CYS
472	211-02050 B BORROW	8,420.000	CYS
473	211-09264 STRUCTURAL BACKFILL, TYPE 1	3,501.000	CYS
474	211-09266 STRUCTURAL BACKFILL, TYPE 3	23,131.000	CYS
475	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5,888.000	TON
476	302-06464 SUBBASE FOR PCCC	18,702.000	CYS
477	303-01180 COMPACTED AGGREGATE, NO. 53	10,309.000	TON
478	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,548.000	SYS
479	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	413.000	TON
480	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,162.000	TON
481	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	1,707.000	TON
482	401-10258 JOINT ADHESIVE, SURFACE	12,378.000	LFT
483	401-10259 JOINT ADHESIVE, INTERMEDIATE	11,398.000	LFT
484	406-05520 ASPHALT FOR TACK COAT	21.000	TON

CALL ORDER : 181

CONTRACT ID : IR-30143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 ROAD CONSTRUCTION			
485	412-09355 FOG SEAL	2,751.000	SYS
486	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
487	501-06321 QC/QA-PCCP, 10 IN	58,174.000	SYS
488	501-06727 CORING, PCCP	LUMP	LUMP
489	503-05240 D-1 CONTRACTION JOINT	35,075.000	LFT
490	503-05310 TERMINAL JOINT	280.000	LFT
491	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	8,466.000	LFT
492	616-02320 GEOTEXTILES	6,386.000	SYS
493	706-09545 COARSE AGGREGATE, NO 8	531.000	CYS
494	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	2,583.000	LFT
495	718-99153 GEOTEXTILES FOR UNDERDRAIN	10,004.000	SYS

