

CALL ORDER : 494

CONTRACT ID : B -35603-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	11.000	SYS
11	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE,	1.000	EACH
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	2,412.000	CYS
14	203-02070 BORROW	4,722.000	CYS
15	203-02132 EXPLORATORY DRILLING	45.000	LFT
16	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	9.000	EACH
17	205-03371 SEDIMENT, REMOVE	7.000	CYS
18	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	5.500	TON
19	205-06934 TEMPORARY MULCH	2.000	TON
20	205-06937 TEMPORARY SILT FENCE	2,023.000	LFT
21	205-09543 NO 2 STONE	50.000	TON
22	207-08263 SUBGRADE TREATMENT, TYPE IA	3,378.000	SYS
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	999.000	SYS
24	211-02050 B BORROW	2,494.000	CYS
25	211-09265 STRUCTURAL BACKFILL, TYPE 2	935.000	CYS
26	211-09266 STRUCTURAL BACKFILL, TYPE 3	511.000	CYS
27	215-11477 CHEMICAL STABILIZATION	578.000	TON
28	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	119.000	TON
29	302-08562 COARSE AGGREGATE, NO 8	100.000	TON
30	303-01180 COMPACTED AGGREGATE, NO. 53	361.000	TON
31	306-08034 MILLING, ASPHALT, 1 1/2 IN	301.000	SYS
32	306-08043 MILLING, TRANSITION	98.000	SYS
33	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	265.900	TON
34	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	389.000	TON
35	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	470.500	TON
36	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	451.000	TON
37	401-10258 JOINT ADHESIVE, SURFACE	2,424.000	LFT
38	401-10259 JOINT ADHESIVE, INTERMEDIATE	2,424.000	LFT
39	402-07432 HMA SURFACE, TYPE A	29.500	TON
40	402-07433 HMA SURFACE, TYPE B	84.000	TON
41	402-07435 HMA INTERMEDIATE, TYPE A	59.000	TON
42	402-07438 HMA INTERMEDIATE, TYPE B	195.000	TON
43	406-05521 ASPHALT FOR TACK COAT	7,249.000	SYS
44	415-11527 BASE SEAL	2.800	TON
45	503-05240 D-1 CONTRACTION JOINT	113.400	LFT
46	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
47	601-06854 GUARDRAIL, W-BEAM, NESTED	1.000	EACH
48	601-06856 MODIFIED POSTS, NESTED GUARDRAIL	4.000	EACH
49	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH

CALL ORDER : 494

CONTRACT ID : B -35603-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	268.750	LFT
51	602-06729 BARRIER DELINEATOR	7.000	EACH
52	604-07902 CURB RAMP, CONCRETE, H	25.000	SYS
53	605-06150 CURB AND GUTTER, C, CONCRETE	646.000	LFT
54	615-06490 RIGHT OF WAY MARKER	23.000	EACH
55	616-02320 GEOTEXTILES	1,519.000	SYS
56	616-05688 RIPRAP, CLASS 1	634.000	TON
57	616-06405 RIPRAP, REVETMENT	363.000	TON
58	616-06451 RIPRAP, UNIFORM	191.000	TON
59	616-11736 DECORATIVE STONE	124.000	TON
60	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
61	621-02770 EROSION CONTROL BLANKET	3,832.000	SYS
62	621-06545 FERTILIZER	0.320	TON
63	621-06554 SEED MIXTURE, U	120.000	LBS
64	621-06557 SEED MIXTURE, T	120.000	LBS
65	621-09398 SEED MIXTURE, SLOPE STABILIZATION	38.000	LBS
66	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
67	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
68	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN OR UNDER	141.000	EACH
69	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	129.000	EACH
70	628-09402 FIELD OFFICE, B	6.000	MOS
71	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
72	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
73	703-06029 REINFORCING BARS, EPOXY COATED	3,695.000	LBS
74	706-06354 CONCRETE BRIDGE RAILING TRANSITION, TPS-2	2.000	EACH
75	706-08502 REINFORCED CONCRETE MOMENT SLAB, 15 IN	272.000	SYS
76	706-09964 RAILING, CONCRETE, PS-2	153.400	LFT
77	706-11419 RAILING, STEEL, PS-2	162.100	LFT
78	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	2.000	EACH
79	709-51821 SURFACE SEAL	LUMP	LUMP
80	715-04987 CONNECTION	2.000	EACH
81	715-04987 CONNECTION	2.000	EACH
82	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	635.000	LFT
83	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	229.000	LFT
84	715-05153 PIPE, TYPE 2 CIRCULAR 21 IN	231.000	LFT
85	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	45.000	LFT
86	715-06379 SEWER	1.000	EACH
87	715-11360 INSERTION VALVE, 12 IN.	1.000	EACH
88	715-46000 PIPE END SECTION, DIA 12"	1.000	EACH
89	715-46020 PIPE END SECTION, DIA 24"	1.000	EACH
90	715-91742 WATER METER, RELOCATE	1.000	EACH
91	715-96670 WATER MAIN, DUCTILE IRON, 12 IN	370.000	LFT
92	715-97419 WATER MAIN, DUCTILE IRON, 24 IN	365.000	LFT
93	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	635.000	LFT
94	718-52610 AGGREGATE FOR UNDERDRAINS	57.100	CYS
95	718-99153 GEOTEXTILES FOR UNDERDRAIN	423.000	SYS
96	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
97	720-44015 CASTING, 2, FURNISH AND ADJUST TO GRADE	2.000	EACH
98	720-44296 INLET, CAP	1.000	EACH

CALL ORDER : 494

CONTRACT ID : B -35603-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
99	720-45235 CATCH BASIN, E7	1.000	EACH
100	720-45410 MANHOLE, C4	5.000	EACH
101	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	3.000	LFT
102	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	1.000	EACH
103	720-96999 FIRE HYDRANT ASSEMBLY	2.000	EACH
104	720-97008 FIRE HYDRANT ASSEMBLY, RELOCATE	2.000	EACH
105	720-97009 FIRE HYDRANT ASSEMBLY, REMOVE	2.000	EACH
106	720-98174 INLET, B15	6.000	EACH
107	723-11203 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	76.600	LFT
108	732-08419 MODULAR BLOCK WALL	8.000	SYS
109	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	191.000	SYS
110	732-08421 MODULAR BLOCK WALL ERECTION	199.000	SYS
111	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
112	801-06625 DETOUR ROUTE MARKER ASSEMBLY	37.000	EACH
113	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
114	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
115	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
116	801-07118 BARRICADE, III-A	48.000	LFT
117	801-07119 BARRICADE, III-B	96.000	LFT
118	802-07060 SIGN, SHEET, RELOCATE	9.000	EACH
119	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	28.000	SFT
120	802-76055 SIGN POST, A	90.000	LFT
121	808-06540 TRANSVERSE MARKING, PREFORMED PLASTIC	180.000	LFT
122	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	910.000	LFT
123	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	1,594.000	LFT
124	808-75067 TRANSVERSE MARKING, PREFORMED PLASTIC,	72.000	LFT
125	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2.000	EACH